

GOEMANS APPLIANCES

167 Chrislea Rd. Unit #1-6, Vaughan ON L4L 8N6
Delivery/Install/Service: (877) 463-6267

| INVOICE # | HB00015217 |
|-----------------------|-----------------------|
| Terms: | 2 WKS PRIOR |
| Purchase Date: | Feb 16, 2017 |
| Delivery/Pickup Date: | Aug 02, 2017 |
| Last Edited: | Feb 16, 2017 01:22 PM |
| Salesperson: | JASON NG |
| (905) 264-1771 | jason.ng@goemans.com |

Bill To: 4164641786

BHATT, CHIRAG & ROSHNI

TBA GIBSON CIRCLE

LOT #227

BRADFORD, ON TBA

TEL# (416) 464-1786 BUS# (416) 835-1920

roshnibhatt26@gmail.com

Directions: 6TH LINE & SIMCOE ROAD

Ship To: 4164641786

BHATT, CHIRAG & ROSHNI

TBA GIBSON CIRCLE

LOT #227

BRADFORD, ON TBA

TEL# (416) 464-1786 BUS# (416) 835-1920

roshnibhatt26@gmail.com

| QTY | MODEL # | DESCRIPTION | PRICE | TOTAL |
|--|-----------|--|------------------|----------|
| 1 | JXW9036WP | 36 JENN-AIR PROSTYLE WALL-MOUNT HOOD,600CFM JENN-AIR, HOOD, WALL MOUNT STAINLESS This special order product requires a 50% deposit & is considered FINAL SALE. x _____ PLEASE ALLOW UP TO 4-12 WEEKS FOR DELIVERY OF THIS PIECE. | 2,339.00 | 2,339.00 |
| 1 | ABC178SS | 24 BEV CENTRE, 178 CANS, SINGLE ZONE AVANTGARDE, REFRIGERATOR, U/C, BEV CENTRE STAINLESS PLEASE NOTE, THIS ITEM IS A LIMITED QUANTITY SPECIAL BUY. DELIVERY MUST TAKE WITHIN 3 MONTHS OF SALE. DOOR SWING - HINGES ARE ON THE RIGHT, HANDLE ON THE LEFT | 750.00 | 750.00 |
| 1 | | P-DELIVERY \$2,500-4,999 | 69.00 | 69.00 |
| -1 | | SALES DELIVERY ALLOWANCE | 69.00 | -69.00 |
| 1 | VHOOD3WM | Wall mounted hood fans up to 36" model Mounting of hood to wall, and vent connection up to 4ft in length. No hole cutting. | 275.00 | 275.00 |
| | Payment | MASTER CARD | 950.00 | 950.00 |
| All orders require a 25% deposit before any product is ordered. Customer to confirm final payment method. Final payment method may not be changed without prior approval of GOEMANS APPLIANCES. | | | SUB TOTAL | 3,364.00 |
| | | | HST | 437.32 |
| | | | TOTAL | 3,801.32 |
| | | | DEPOSIT | 950.00 |
| | | | BALANCE | 2,851.32 |

☐ CASH, DEBIT CARD

☐ CERTIFIED FUNDS

☐ CREDIT CARD

☐ ONLINE BANKING (Acc #: 4164641786)

☐ FINANCING

Note: Must allow a minimum of 5 business days for wire transfers and internet banking. Please check your limit for debit card payments. Cheques made payable to **GOEMANS APPLIANCES**

GOEMANS APPLIANCES

167 Chrislea Rd. Unit #1-6, Vaughan ON L4L 8N6
Delivery/Install/Service: (877) 463-6267

INVOICE #

HB00015217

Terms:

2 WKS PRIOR

Purchase Date:

Feb 16, 2017

Delivery/Pickup Date:

Aug 02, 2017

Last Edited:

Feb 16, 2017 01:22 PM

Salesperson:

JASON NG

(905) 264-1771

jason.ng@goemans.com

Y

N

(Please check below)

☐☐

Extended Warranty options have been presented to customer.

☐☐

Installation options have been presented to customer.

☐☐

Appliance removal: this is at the owner's risk and all appliances must be disconnected prior to delivery. If a return visit is required additional fees will apply.

☐☐

I give permission for Goemans Appliances to send me information concerning upcoming sales and events.

Other Terms and Conditions

- ORDERS MUST BE PAID IN FULL 2 WEEKS PRIOR TO SCHEDULED DELIVERY DATE
- Delivery and/or removal access is the customer's responsibility. The location must be ready and safe for delivery to take place.
- All product is sold with a manufacturer's warranty and customer agrees to accept service in accordance with the terms of this warranty.
- Any and all payments are refundable only at Goemans Appliances' discretion.
- A 25% minimum restocking charge will apply on cancellations and returns.
- Product specifications are for planning purposes only and are subject to change without notice. Refer to installation instructions shipped with the product before cutting cabinets, counters, panels, etc.
- **Goemans Appliances assumes no liability for product specifications.**
- Portions of your personal information may be shared with manufacturers and distributors in order to validate the product warranty and/or ensure the proper maintenance of your products.
- All product remains the property of Goemans Appliances until paid in full.
- Interest of 18% per annum will be charged on overdue accounts.
- This sales invoice is based on delivery within 12 months from date of purchase. After 12 months (or if market conditions adversely change) Goemans reserves the right to review pricing/delivery on this order and offer our customers options to accommodate these changes. Any & all date sensitive supplier promotions are exempt from the 12 month price guarantee and must be taken by the promotional delivery deadline.

Customer Signature

Print Name


JENN-AIR® DETAILED PLANNING DIMENSIONS

1 of 2


48"/36"/30" PRO-STYLE™ WALL-MOUNT HOODS

JXW9048WP – 48" x 19³/₈" x 25"JXW9036WP – 36" x 19³/₈" x 25"JXW9030WP – 30" x 19³/₈" x 25"

PRODUCT DIMENSIONS




FRONT VIEW



SIDE VIEW

(shown with optional duct cover)



TOP VIEW

| MODEL # | | JXW9048WP | | JXW9036WP | | JXW9030WP | |
|----------|-------------------------------|--------------------------------|-------|--------------------------------|------|--------------------------------|------|
| | | in | cm | in | cm | in | cm |
| A | Overall width | 48 | 121.9 | 36 | 91.4 | 30 | 76.2 |
| B | Height without trim | 15 ³ / ₄ | 40.0 | 15 ³ / ₄ | 40.0 | 15 ³ / ₄ | 40.0 |
| C | Height of trim | 2 ¹ / ₄ | 5.7 | 2 ¹ / ₄ | 5.7 | 2 ¹ / ₄ | 5.7 |
| D | Height without controls | 18 | 45.7 | 18 | 45.7 | 18 | 45.7 |
| E | Height with controls | 19 ³ / ₈ | 49.1 | 19 ³ / ₈ | 49.1 | 19 ³ / ₈ | 49.1 |
| F | Height of optional duct cover | 12 | 30.5 | 12 | 30.5 | 12 | 30.5 |
| G | Depth of optional duct cover | 12 | 30.5 | 12 | 30.5 | 12 | 30.5 |
| H | Depth of hood | 25 | 63.5 | 25 | 63.5 | 25 | 63.5 |
| I | Vent collar diameter | 9 ⁷ / ₈ | 25.1 | 9 ⁷ / ₈ | 25.1 | 9 ⁷ / ₈ | 25.1 |

IMPORTANT: Dimensional specifications are provided for planning purposes only.

Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.



8562CdZw815


JENN-AIR® DETAILED PLANNING DIMENSIONS

2 of 2

48"/36"/30" PRO-STYLE™ WALL-MOUNT HOODS

JXW9048WP – 48" x 19³/₈" x 25"JXW9036WP – 36" x 19³/₈" x 25"JXW9030WP – 30" x 19³/₈" x 25"

OPENING/CLEARANCE DIMENSIONS



FRONT VIEW

ELECTRICAL REQUIREMENTS

120 volt, 60 Hz, AC only, 15-amp fused, electrical circuit is required. The knockout into the back of the terminal box is located on the right side.

VENTING REQUIREMENTS

The hood is factory set for venting through the roof or wall. Do not terminate the vent in an attic or other enclosed area.

LOCATION REQUIREMENTS

The minimum height from the floor to the top of the vent hood is 7' (2.1 m). The minimum height from the floor to the top of the optional duct cover is 8' (2.4 m).

| MODEL # | | JXW9048WP | | JXW9036WP | | JXW9030WP | |
|----------|---|-----------|-----------|-----------|-----------|-----------|-----------|
| | | in | cm | in | cm | in | cm |
| A | Width of vent entry location – ceiling option | 12 | 30.5 | 12 | 30.5 | 12 | 30.5 |
| B | Width of vent entry location – wall option | 12 | 30.5 | 12 | 30.5 | 12 | 30.5 |
| C | Width of cabinet opening (min.) | 48 | 121.9 | 36 | 91.4 | 30 | 76.2 |
| D | Height from vent entry location to ceiling – wall option (min.) | 2 | 5.1 | 2 | 5.1 | 2 | 5.1 |
| E | Height from hood to vent entry location – wall option (min.) | 24 | 61.0 | 24 | 61.0 | 24 | 61.0 |
| F | Height from hood to cooking surface (min.-max.) | 30-36 | 76.2-91.4 | 30-36 | 76.2-91.4 | 30-36 | 76.2-91.4 |
| G | Height from upper cabinet to countertop (min.) | 18 | 45.7 | 18 | 45.7 | 18 | 45.7 |
| H | Depth of vent entry location – ceiling option | 12 | 30.5 | 12 | 30.5 | 12 | 30.5 |
| v | Recommended vent entry location | | | | | | |

IMPORTANT: Dimensional specifications are provided for planning purposes only.

Do not make any cutouts based on this information. Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.




8562CdZw815

36" PRO-STYLE® DUAL-FUEL RANGES


JDRP536WP, JDRP436WP – 35 $\frac{7}{8}$ " x 36 $\frac{1}{4}$ " x 29 $\frac{1}{4}$ "

PRODUCT DIMENSIONS



FRONT VIEW

| MODEL # | | JDRP536WP JDRP436WP | |
|---------|--------------------------------------|------------------------|-------|
| | | in | cm |
| A | Overall width | 35 $\frac{7}{8}$ | 91.1 |
| B | Height of bullnose | 2 $\frac{1}{4}$ | 5.5 |
| C | Height of control panel | 5 $\frac{3}{8}$ | 13.5 |
| D | Space between door and control panel | $\frac{7}{8}$ | 2.0 |
| E | Height of door | 20 $\frac{3}{4}$ | 52.5 |
| F | Height to top of handle | 19 $\frac{3}{8}$ | 49.0 |
| G | Space between door and lower panel | 1 | 2.5 |
| H | Height of lower panel | 5 $\frac{1}{2}$ | 14.0 |
| I | Depth with control panel overhang | 27 $\frac{7}{8}$ | 69.5 |
| J | Depth with handle | 29 $\frac{1}{4}$ | 74.2 |
| K | Depth with door fully open | 45 $\frac{3}{4}$ | 116.2 |



TOP VIEW


Lot 227
Chiray Bhatt

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

36" PRO-STYLE® DUAL-FUEL RANGES

JDRP536WP, JDRP436WP – 35 $\frac{3}{8}$ " x 36 $\frac{3}{4}$ " x 29 $\frac{1}{4}$ "

DIMENSIONS AS INSTALLED



SIDE VIEW

MODEL

JDRP536WP
JDRP436WP

| | | in | cm |
|----|---|------------------|-------|
| A* | Height to top of grates (min.) | 36 $\frac{3}{4}$ | 93.3 |
| B* | Height to top of cooking surface (min.) | 35 $\frac{3}{8}$ | 90.8 |
| C* | Height to top of door (min.) | 27 $\frac{7}{8}$ | 69.5 |
| D* | Height to top of handle (min.) | 25 $\frac{7}{8}$ | 65.7 |
| E* | Height to top of lower panel (min.) | 5 $\frac{7}{8}$ | 14.9 |
| F | Depth with door fully open | 45 $\frac{3}{4}$ | 116.2 |
| G | Depth with handle | 29 $\frac{1}{4}$ | 74.2 |
| H | Depth with control panel overhang | 27 $\frac{7}{8}$ | 69.5 |
| I | Depth without control panel | 23 $\frac{1}{2}$ | 59.5 |
| J | Depth between grates and wall | 1 $\frac{3}{4}$ | 4.5 |
| K | Depth without door | 24 $\frac{7}{8}$ | 62.5 |
| L | Depth with door | 26 $\frac{3}{4}$ | 68.0 |

OPTIONAL ACCESSORIES

| | | | |
|----|---|------------------|-------|
| M* | Height to top of 9" stainless steel backsplash (min.) | 44 $\frac{3}{4}$ | 113.7 |
|----|---|------------------|-------|

*Add 1 $\frac{3}{4}$ " (4.4 cm) to the height dimension when leveling legs are fully extended.


IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

8780FdZw0516


72" COUNTER-DEPTH FRENCH DOOR REFRIGERATORS WITH EXTERNAL DISPENSER

JFFCC72EF – 35³/₄" x 71¹/₁₆" x 31¹/₄" (with handles)

PRODUCT DIMENSIONS



FRONT VIEW



TOP VIEW

| MODEL # | | JFFCC72EF | |
|---------|--|----------------------------------|-------|
| | | in | cm |
| A | Width of each door | 17 ¹ / ₁₆ | 45.0 |
| B | Space between doors | ³ / ₈ | 0.9 |
| C | Overall width | 35 ³ / ₄ | 90.5 |
| D | Height of door handles | | |
| | Pro-Style® Stainless | 33 ³ / ₁₆ | 84.3 |
| | Euro-Style Stainless | 37 ³ / ₄ | 95.6 |
| E | Height to top of door handles | | |
| | Pro-Style® Stainless | 38 ¹⁵ / ₁₆ | 99.0 |
| | Euro-Style Stainless | 41 ¹ / ₁₆ | 104.6 |
| F | Height of doors | 46 ¹ / ₂ | 118.2 |
| G | Space between doors and drawer | ¹ / ₂ | 1.2 |
| H | Height to top of drawer handle | | |
| | Pro-Style® Stainless | 21 ³ / ₄ | 55.3 |
| | Euro-Style Stainless | 21 ¹ / ₁₆ | 54.8 |
| I | Height of drawer | 23 | 58.4 |
| J | Height of grille | 1 ¹ / ₂ | 3.9 |
| K | Width from side of refrigerator to handle – door fully open 135° | | |
| | Pro-Style® Stainless | 13 ⁷ / ₈ | 35.2 |
| | Euro-Style Stainless | 13 ¹ / ₂ | 34.3 |
| L | Width from side of refrigerator to handle – door open 90° | | |
| | Pro-Style® Stainless | 3 ¹⁵ / ₁₆ | 10.0 |
| | Euro-Style Stainless | 3 ³ / ₈ | 8.4 |
| M | Depth without doors | 24 ⁵ / ₈ | 62.6 |
| N | Depth with doors | 29 ⁵ / ₁₆ | 74.4 |
| O | Depth with handles | | |
| | Pro-Style® Stainless | 31 ¹⁵ / ₁₆ | 81.1 |
| | Euro-Style Stainless | 31 ¹ / ₄ | 79.4 |
| P | Depth with doors open 90° | 44 | 111.7 |

Lot 227


Chirag Bhatt

IMPORTANT: Dimensional specifications are provided for planning purposes only.
 Do not make any cutouts based on this information. Refer to the Installation Guide before
 selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
 All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

72" COUNTER-DEPTH FRENCH DOOR REFRIGERATORS WITH EXTERNAL DISPENSER

JFFCC72EF – 35³/₄" x 71¹⁵/₁₆" x 31¹/₄" (with handles)

DIMENSIONS AS INSTALLED



SIDE VIEW

| MODEL # | | JFFCC72EF | |
|---------|---|----------------------------------|-------|
| | | in | cm |
| A* | Height to top of drawer (min.) | 24 ¹⁵ / ₁₆ | 63.3 |
| B* | Height to top of drawer handle (min.) | | |
| | Pro-Style® Stainless | 23 ¹¹ / ₁₆ | 60.2 |
| | Euro-Style Stainless | 23 ⁹ / ₁₆ | 59.8 |
| C* | Height of recessed refrigerator (min.) | 70 ¹⁵ / ₁₆ | 180.1 |
| D* | Height to top of hinges (min.) | 71 ¹⁵ / ₁₆ | 182.7 |
| E | Depth with drawer fully open including drawer handle (min.) | | |
| | Pro-Style® Stainless | 46 ⁷ / ₁₆ | 117.9 |
| | Euro-Style Stainless | 45 ¹⁵ / ₁₆ | 116.7 |
| F | Depth with handles (min.) | | |
| | Pro-Style® Stainless | 31 ¹⁵ / ₁₆ | 81.1 |
| | Euro-Style Stainless | 31 ¹ / ₄ | 79.4 |
| G | Depth with doors (min.) | 29 ⁹ / ₁₆ | 74.4 |
| H | Depth without doors (min.) | 24 ⁵ / ₈ | 62.6 |
| I | Depth to back of hinges (min.) | 16 ³ / ₄ | 42.6 |


*Add ³/₄" (1.9 cm) to the height dimension when leveling legs are fully extended.

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.


72" COUNTER-DEPTH FRENCH DOOR REFRIGERATORS WITH EXTERNAL DISPENSER

JFFCC72EF – 35³/₄" x 71¹⁵/₁₆" x 31¹/₄" (with handles)

OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



BACK VIEW

| MODEL # | | JFFCC72EF | |
|---------|--|---------------------------------|-----------|
| | | in | cm |
| A | Width (min.) | 36 ³ / ₄ | 93.3 |
| B | Minimum width from side of refrigerator to fixed wall – door open 90° (full access to remove bins) | 3 ³ / ₄ | 9.5 |
| | Minimum width from side of refrigerator to fixed wall – door open approx. 135° | 12 | 30.5 |
| C | Width of recommended electrical/water installation area | 35 ¹ / ₂ | 90.2 |
| D | Height (min.) | 72 ⁷ / ₁₆ | 184.0 |
| E | Height of recommended electrical installation area (min.-max.) | 24-36 | 61.0-91.4 |
| F | Height of recommended water installation area | 12 | 30.5 |
| G | Depth of recommended water installation area | 1 | 2.5 |
| H | Water line location – distance from side | 2 ¹ / ₂ | 6.4 |
| I | Water line location – distance from bottom | 7 | 17.8 |
| e | Recommended electrical connection location | | |
| w | Recommended water connection location | | |

ELECTRICAL REQUIREMENTS

115 volt, 60 Hz, AC only, 15- or 20-amp fused, grounded circuit is required. A dedicated circuit is recommended. Use an outlet that cannot be turned off by a switch.

Minimum length of power cord is 60" (152.0 cm). Do not use an extension cord.

WATER PRESSURE REQUIREMENTS

A cold water supply with water pressure between 30 and 120 psi (207 and 827 kPa) is required to operate the water dispenser and ice maker. Call a licensed, qualified plumber with any questions about the water pressure.

Reverse Osmosis Water Supply

IMPORTANT: The pressure of the water coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 30 and 120 psi (207 and 827 kPa).

If a reverse osmosis water filtration system is connected to the cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).

IMPORTANT: Dimensional specifications are provided for planning purposes only.

Do not make any cutouts based on this information. Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.