

Miele

Lot 250

36" All Gas Range

HR 1134 G, HR 1134 LP



36" All Gas Range

Model: HR 1134 G / HR 1134 LP



HR 1134 G / HR 1134 LP

Features:

- DirectSelect controls
- M Pro dual stacked burner system with TrueSimmer
- ComfortClean dishwasher-safe grates
- 5 Operating modes including Self Clean
- Twin Convection fans
- Soft Open and Soft Close
- Clean Touch Steel™ front

SPECIFICATIONS

HR 1134 G	Item 25113451USA
HR 1134 LP	Item 25113452USA
Overall Unit Width	35 ⁵ / ₁₆ " (913 mm)
Overall Unit Height to Cooktop	35 ¹ / ₂ " — 37" (901.7 — 939.8 mm)
Overall Unit Depth to Front of Control Panel	26 ¹ / ₂ " (673 mm)
Oven Door Clearance	22 ³ / ₄ " (577 mm)
Niche	
Minimum Cabinet Niche Width	36" (914 mm)
Minimum Cabinet Opening Height	35 ¹ / ₂ " (901.7 mm)
Burners (G/LP)	M Pro Power Plus - Standard Configuration*
Gas Burners:	(1) 12,500 BTU (G/LP); (5) 19,500 BTU (G/LP)
Total BTU Output	110,000 BTU (G/LP)
Oven Burners (G/LP)	
Oven Top Burner:	22,000 BTU (G); 20,150 BTU (LP)
Oven Bottom Burner:	25,500 BTU (G); 27,000 BTU (LP)
Gas	
Gas Line Connection	1/2" NPT
Operational Altitudes	
High Altitude	Miele Natural Gas and LP Ranges and Rangetops will function up to 9,800 ft. in altitude without adjustment; the following exception will function up to 6,500 ft. in altitude without adjustment:
	<ul style="list-style-type: none"> • Griddle in LP: HR 1136 LP, HR 1936 LP, HR 1956 LP, KMR 1136 LP, KMR 1356 LP • Grill in G: HR 1135 G, HR 1935 G, HR 1955 G, KMR 1135 G, KMR 1355 G
If an installation exceeds these elevations, please contact rangejetkit@mieleusa.com.	
Electrical	
Electrical Requirements	120V, 60Hz, 15 Amps
Power Cord	NEMA 5-15 plug, 5' 11" (1.8 m) long
Shipping	
Shipping Weight	438.7 lbs (199 kg)
Shipping Dimensions	43 ⁵ / ₁₆ " (1100 mm) W x 52" (1,294 mm) H x 31 ¹ / ₂ " (800 mm) D
Support	
Call Miele	800.843.7231
Miele Website	www.mieleusa.com
20/20 Link	2020technologies.com

* Please note if a BTU-reducing kit is necessary, an authorized installer is required to modify the product to meet ANSI Z21.

HR 1134

Page 2 of 10

Specification Sheet TRS 05022016

36" All Gas Range

Model: HR 1134 G / HR 1134 LP



Optional Accessories:



12" Backguard
RBGAG1236

12" tall high-quality brushed stainless steel Backguard



20" Backguard
RBGAG2036

20" tall high-quality brushed stainless steel Backguard



40" Backsplash
RBS36

40" tall flat stainless steel Backsplash panel


36" All Gas Range

Model: HR 1134 G / HR 1134 LP




PRODUCT VIEWS

Isometric



(x) = Toe-kick height adjustment 5" - 6 1/2" (127 mm - 165.1 mm)




36" All Gas Range

Model: HR 1134 G / HR 1134 LP



PRODUCT VIEWS

Rear View



E = Electrical connection

G = Gas connection

*Anti-tip device must be fastened securely in place to all studs or floor. Please refer to the Anti-tip device section in the installation manual for further details.


36" All Gas Range

Model: HR 1134 G / HR 1134 LP



PRODUCT VIEWS

Detailed Side View



(x) = Toe-kick height adjustment 5" - 6 1/2" (127 mm - 165.1 mm)


36" All Gas Range

Model: HR 1134 G / HR 1134 LP



PRODUCT VIEWS

Detailed Bullnose and Handle View



36" All Gas Range

Model: HR 1134 G / HR 1134 LP



M Pro Power Plus Configuration


Standard Configuration with Pro Hood*



M Pro Power Plus SPECIFICATIONS

Burners (G/LP)

Gas Burners:	(1) 12,500 BTU (G/LP); (5) 19,500 BTU (G/LP)
Total BTU Output	110,000 BTU (G/LP)



Ⓑ In case of combustible materials, a minimum distance of 6" must be observed on each side in addition to dimension Ⓐ.

Ⓓ, Ⓔ, Ⓕ The shaded area represents the installation area for the connections:
E = Electrical connection, G = Gas connection

Position	Dimensions	Description	
①	13" (330 mm)	Maximum depth of top cabinet	
②	18" (457 mm)	Minimum distance to bottom edge of top cabinet	
③	35 1/2"–37" (901–940 mm)	Distance from the floor to cooktop surface	
④	10" (254 mm)	Minimum distance to combustible surfaces.	
Ⓐ	Min. 36" (914 mm)	Width of cabinet opening	
Ⓑ	6" – Ⓐ + 6" (150 mm + Ⓐ + 150 mm)	If combustible materials are present, an additional minimum distance of 6" (150 mm) (each side) is required. Ensure that the local codes are observed.	
Ⓒ	37" (940 mm)	Minimum distance between the top of the cooking area and the bottom of an unprotected combustible surface.	
	36" (914 mm)	Minimum distance between the top of the cooking area and the bottom of the Miele Range Hood (DAR model with DRxB XL blower).	
	30" (762 mm)	Minimum distance between the top of the cooking area and the bottom of the Miele Range Hood (DAR model with DRxB XXL blower).	
	For all other Hoods please consult the manufacturer's specifications for required distances.		
Ⓓ	Approx. 13 3/4" (350 mm)	Maximum connection width right and left	Position of the wall socket
Ⓔ	Approx. 4 1/2" (115 mm)	Maximum connection height	
Ⓕ	Approx. 2 13/16" (72 mm)	Maximum connection depth	

* Please note if a BTU-reducing kit is necessary, an authorized installer is required to modify the product to meet ANSI Z21.

HR 1134

Page 8 of 10


Specification Sheet TRS 05022016

36" All Gas Range
Model: HR 1134 G / HR 1134 LP



M Pro Power
Configuration

Seamless Configuration with Pro
Hood (Zero Gap)



Ⓒ, Ⓓ, Ⓔ The shaded area represents the installation area for the connections:
E = Electrical connection, G = Gas connection

M Pro Power SPECIFICATIONS	
Burners (G/LP)	
Gas Burners:	(1) 10,000 BTU (G/LP); (5) 14,700 BTU (G/LP)
Total BTU Output	83,500 BTU (G/LP)

**Jets are a standard accessory and
are changed during installation**


Position	Dimensions	Description	
Ⓘ	13" (330 mm)	Maximum depth of top cabinet	
Ⓣ	18" (457 mm)	Minimum distance to bottom edge of top cabinet	
ⓐ	35 1/2"-37" (901-940 mm)	Distance from the floor to cooktop surface	
ⓓ	10" (254 mm)	Minimum distance to combustible surfaces.	
ⓐ	Min. 36" (914 mm)	Width of cabinet opening Please contact Miele Service for more information.	
ⓑ	37" (940 mm)	Minimum distance between the top of the cooking area and the bottom of an unprotected combustible surface.	
	36" (914 mm)	Minimum distance between the top of the cooking area and the bottom of the Miele Range Hood (DAR model with DRxB XL blower).	
	30" (762 mm)	Minimum distance between the top of the cooking area and the bottom of the Miele Range Hood (DAR model with DRxB XXL blower).	
	For all other Hoods please consult the manufacturer's specifications for required distances.		
Ⓒ	Approx. 13 3/4" (350 mm)	Maximum connection width right and left	Position of the wall socket
Ⓓ	Approx. 4 1/2" (115 mm)	Maximum connection height	
Ⓔ	Approx. 2 13/16" (72 mm)	Maximum connection depth	

36" All Gas Range
Model: HR 1134 G / HR 1134 LP



M Pro
Configuration

Seamless Configuration with
Non-Pro (Décor)



⑦, ⑧, ⑨ The shaded area represents the installation area for the connections:
E = Electrical connection, G = Gas connection

M Pro SPECIFICATIONS	
Burners (G/LP)	
Gas Burners:	(1) 10,000 BTU (G/LP); (5) 12,200 BTU (G/LP)
Total BTU Output	71,000 BTU (G/LP)

**Jets are a standard accessory and
are changed during installation**

Position	Dimensions	Description	
①	13" (330 mm)	Maximum depth of top cabinet	
②	18" (457 mm)	Minimum distance to bottom edge of top cabinet	
③	35 1/2"–37" (901–940 mm)	Distance from the floor to cooktop surface	
④	10" (254 mm)	Minimum distance to combustible surfaces.	
⑤	Min. 36" (914 mm)	Width of cabinet opening Please contact Miele Service for more information.	
⑥	Please refer to Miele ventilation hood installation manual, Appliance Dimensions section (Distance between cooktop and hood (S)) For all other Hoods please consult the manufacturer's specifications for required distances.		
⑦	Approx. 13 3/4" (350 mm)	Maximum connection width right and left	Position of the wall socket
⑧	Approx. 1 1/2" (115 mm)	Maximum connection height	
⑨	Approx. 2 13/16" (72 mm)	Maximum connection depth	

LEONE

WALL-MOUNT

ASPIRE SERIES

Dimensions

30"W x 24"D x 12 1/8"H
36"W x 24"D x 12 1/8"H
42"W x 24"D x 12 1/8"H

Models

ELN630SS
ELN136SS
ELN142SS

Leone 30" Stainless
Leone 36" Stainless
Leone 42" Stainless

Special features




HUSH



halogen lamps



metallic rotating knob controls



professional stainless steel baffle filters



Give your professional kitchen a splash of Italian design with Leone's crisp lines, seamless welded corner craftsmanship, beveled rim and gleaming stainless steel, plus Leone comes "unbranded", for easy coordination with other appliances. Most importantly, Leone has the extra depth (24") and power (1200 CFM on 36" & 42" widths) needed to support professional ranges and cooktops. No ear plugs required with Leone's HUSH sound suppression system, which enables you to comfortably talk and entertain, even when cooking up a storm. Available in 30", 36" and 42" widths, Leone features metallic rotating knob controls, which operate the 4-speed blower and halogen lighting. Easy maintenance and a cleaner kitchen are assured with professional stainless steel baffle filters.

Leone is designed for standard ducted ventilation only (for heights 8'2" to 10'2").

 elica

FEATURES


Size (in) & Type Finish	30", 36" or 42" Wide Wall-Mount Chimney Stainless Steel													
Controls	Metallic rotating knob													
Illumination	2, 40 Watt Halogen Lamps, 2 Light Intensities (30", 36" & 42") (bulbs included)													
Installation Type	Ducted Installation Only													
Blower Type	600 CFM, 4-Speed Internal (30") 1200 CFM, 4-Speed Internal Blower (36" & 42")													
Blower Performance	<table> <tr> <td>Speed 1</td><td>(For 30") 205 CFM, 1.4 Sones</td><td>(For 36" & 42") 375 CFM, 1.6 Sones</td></tr> <tr> <td>Speed 2</td><td>(For 30") 350 CFM, 2.6 Sones</td><td>(For 36" & 42") 640 CFM, 3.5 Sones</td></tr> <tr> <td>Speed 3</td><td>(For 30") 510 CFM, 4.5 Sones</td><td>(For 36" & 42") 940 CFM, 6.0 Sones</td></tr> <tr> <td>Speed 4</td><td>(For 30") 600 CFM, 6.0 Sones</td><td>(For 36" & 42") 1200 CFM, 7.7 Sones</td></tr> </table>		Speed 1	(For 30") 205 CFM, 1.4 Sones	(For 36" & 42") 375 CFM, 1.6 Sones	Speed 2	(For 30") 350 CFM, 2.6 Sones	(For 36" & 42") 640 CFM, 3.5 Sones	Speed 3	(For 30") 510 CFM, 4.5 Sones	(For 36" & 42") 940 CFM, 6.0 Sones	Speed 4	(For 30") 600 CFM, 6.0 Sones	(For 36" & 42") 1200 CFM, 7.7 Sones
Speed 1	(For 30") 205 CFM, 1.4 Sones	(For 36" & 42") 375 CFM, 1.6 Sones												
Speed 2	(For 30") 350 CFM, 2.6 Sones	(For 36" & 42") 640 CFM, 3.5 Sones												
Speed 3	(For 30") 510 CFM, 4.5 Sones	(For 36" & 42") 940 CFM, 6.0 Sones												
Speed 4	(For 30") 600 CFM, 6.0 Sones	(For 36" & 42") 1200 CFM, 7.7 Sones												
Filter Type	Dishwasher-Safe, Professional Stainless Steel Baffle (1 w/ 30", 2 w/ 36" & 42")													
Telescopic Chimney Extension	For heights 8'8" - 10'4" (ducted)													
Duct Transition	8" Round with Back Draft Damper (top)													
Electrical	120V-60Hz 550 Watts at 4.6 Amps (600 CFM), 800 Watts at 6.7 Amps (1200 CFM)													
Warranty	2 Year Parts & Labor, In-Home Service													

ACCESSORIES


Optional Long Chimney Extension Kit
 Reaches 9'10" - 13'0" (ducted)

 CODE: KIT02785
 MODEL: EXXCEK07

LINE DRAWING



CONSUMABLE PARTS

Replacement Grease Filter (1)
 CODE: GF09FA (30", 42")
 CODE: GF09EA (36")
Replacement Light Bulb (1)

CODE: 2006EA

Consumable parts are sold in units of one (1). Order accordingly.

SPECIAL FEATURES

**Elica HUSH Silence System:**

An exclusive sound deadening technology that effectively reduces sound levels by over 35%, compared to typical range hoods.

Futura Series

Fully Integrated Dishwashers

CLASSIC PLUS	G 4998 Vi, G 4998 SCVi, G4998 SCVi SF
CRYSTAL	G 6665 SCVi
DIMENSION	G 6785 SCVi
LUMEN	G 6875 SCVi
DIAMOND	G 6987 SCVi K2o



Futura Series

Fully Integrated Dishwashers



SPECIFICATIONS


Overall Unit Width		23 ⁹ / ₁₆ " (598mm)
Overall Unit Height		33 ¹¹ / ₁₆ " - 36 ¹ / ₄ " (855 - 920mm)
Overall Unit Depth		22 ⁷ / ₁₆ " (570mm)
Niche		
Minimum Cabinet Opening Width		23 ⁵ / ₈ " (600mm)
Minimum Cabinet Opening Height		33 ³ / ₄ " (857mm)
Minimum Cabinet Opening Depth		22 ⁷ / ₁₆ " (570mm)
Plumbing		
Water Supply Requirements		May be connected to a cold or hot water supply up to a maximum of 140°F/60°C. Must be connected to a shut-off valve with a male 3/8" compression. The water shut-off valve must be accessible after installation. The water pressure must be between 4.35 psi (0.3 bar) and may not exceed 145 psi (10 bar). If the pressure is higher than 145 psi (10 bar), a pressure reducing valve must be installed.
Water Connection Line		4' 11" (1.5m) flexible water intake hose is supplied with a 3/8 compression connection.
Drain Hose		4' 11" (1.5m) flexible drain hose is supplied.
Electrical		
Electrical Requirements - Volts/Amps		110V / 120V, 60Hz, 15 Amps
Power Cord - Plug and length		NEMA 5-15 plug, 3' 11" (1.2m) (Measured from back of unit, Convertible to Hardwire)
Shipping		
Shipping Weight		118 lbs (53.5kg)
Support		
Call Miele		800.565.6435
Miele Website		www.miele.ca

Futura Series

Fully Integrated Dishwashers



INSTALLATION SPECIFICATIONS



- Drain** - 4 ft 11 in (1.5 m) flexible drain hose.
(Connects from lower center rear)
- Water** - 4 ft 11 in (1.5 m) flexible water intake hose with 3/8" compression fitting.
(Connects from lower center rear)
- Electric** - 4 ft 11 in (1.5 m) 120V 15 A 3 wire molded NEMA 5-15 plug power supply. (Connects via Front End Supply or may be hardwired)


Futura Series

Fully Integrated Dishwashers



Custom Panel Installation

Some Miele dishwashers do not come equipped with a front panel. These dishwashers are designed to accept a custom door panel supplied by a cabinet maker. Miele has a unique panel integration system which allows the dishwasher to align with the surrounding cabinets.



Width: 23 7/16" (595 mm) in all Cases
Thickness: 3/4" (19 mm) in all Cases
Height: Determined using the following calculation:

$$\text{Panel Height} = \text{HTC} - \text{TKH}$$

HTC = Height to the underside of countertop
TKH = Toe kick height

Note: Control panel is along the top edge of the unit. It is not visible when the unit is closed. A handle **MUST** be located on front of panel in order to open unit. (Except K2o models).

Maximum panel height: 31 7/8" (810 mm)

Minimum panel height: 27 1/8" (690 mm)

Maximum panel weight: 21 lbs (9.5 kg)

GFVI Installations

Miele offers pre-fabricated stainless steel panels for all fully integrated units. These panels are designed for various toe-kick heights and offer a choice of handle options. See Miele Product Brochure for more info.


For Knock2open (K2o) models, an additional kit is required for use with stainless steel panel. Please contact Miele for further details.

Futura Series

Fully Integrated Dishwashers



Acceptable Installation Heights



Planning Information


Louvered/Collar Trim Kits (TRIMKITSS1 & TRIMKITSS2)

For replacement installation of models E32AF75FPS, E32AR75FPS or for new-build installation – when installed with All-Freezer models EI32AF65FS, E32AF75FPS and All-Refrigerator models EI32AR65FS, E32AR75FPS

79" Single & Double Louvered Trim Kit or 75" Single & Double Collar Trim Kit for All Freezer and All Refrigerator

Designed for replacement installation of any built-in model(s) having pre-existing opening(s) with same cutout dimensions as stated below; or for new-build installation.

Single & Double Cutout Dimensions



†Minimum depth from face of wall or cabinet side panels and requires recessed electrical outlet(s) and water line.

Installation Notes:

Trim kit attaches directly to cutout opening through louvered grille or optional top collar trim piece to stabilize unit(s). Louvered grille used for 79\" opening height and optional top collar trim piece used for 75\" opening height. Installation into 75\" opening requires side trim pieces be shortened by 4\". Double Trim Kit also includes hardware to secure side-by-side units together. Refer to detailed kit installation instructions packed with kit or on web.

Installation Specifications

- **New-Build Installations** – Louvered/Collar Trim Kits (PN# TRIMKITSS1 & PN# TRIMKITSS2) are designed for built-in installation with All-Freezer models EI32AF65JS, E32AF75JPS and All-Refrigerator models EI32AR65JS, E32AR75JPS. New-build installation can use 79\" opening height with use of louvered grille; or 75\" opening height with use of optional top collar trim piece which also requires side trim pieces to be shortened by 4\".
- **Replacement Installations** – Louvered/Collar Trim Kits (PN# TRIMKITSS1 & PN# TRIMKITSS2) are designed as built-in replacement option for All-Freezer model E32AF75FPS and All-Refrigerator model E32AR75FPS when installed with All-Freezer models EI32AF65JS, E32AF75JPS and All-Refrigerator models EI32AR65JS, E32AR75JPS requiring 79\" opening height and use of louvered grille; or as built-in replacement option for any other built-in model(s) having pre-existing 75\" or 79\" opening height.
- To use Single Louvered/Collar Trim Kit (PN# TRIMKITSS1), an enclosure is required around All Freezer or All Refrigerator having an opening of 75\" or 79\" H x 33\" W with minimum cabinet side panels of 25-1/4\" D x 3/4\" W.

- To use Double Louvered/Collar Trim Kit (PN# TRIMKITSS2), an enclosure is required around All Freezer and All Refrigerator having an opening of 75\" or 79\" H x 66\" W with minimum cabinet side panels of 25-1/4\" D x 3/4\" W. (Double Trim Kit includes hardware to secure side-by-side units together.)
- Trim Kit attaches directly to cutout opening through louvered grille or optional top collar trim piece to stabilize unit(s).
- Minimum 25-1/4\" depth requires recessed electrical outlet(s) and water line.
- Cabinet or soffit above unit must extend out to same depth as side panels.
- Clear, adequate floor space required for Trim Kit assembly.
- For detailed Trim Kit installation, refer to instructions packed with kit or on web.
- For detailed All Freezer and/or All Refrigerator installation, refer to model-specific product page and installation guide on web.

Note: For planning purposes only. Refer to product information on the web at electroluxappliances.com or electroluxicon.com for detailed installation instructions. Specifications subject to change.

BUILT-IN ALL REFRIGERATOR

EI32AR80QS

Featuring IQ-Touch™ Electronic Controls



SIGNATURE FEATURES



PERFECT ORGANIZATION SYSTEM

Our organization system features Luxury-Glide® drawers with removable/adjustable dividers and two mini baskets, Perfect Bins™ door storage that tilts out for easy access and a condiment shelf, so you can keep food organized and easily at hand.



PLATINUM STAR® LIMITED WARRANTY

Our exclusive limited warranty that includes a 3-year coverage on parts and one year on labour without charge.¹



LUXURY-DESIGN® LIGHTING

Our ramp-up designer LED lighting is as beautiful as it is functional, keeping the contents clearly visible.



LUXURY-GLIDE® STORAGE DRAWER

Drawer glides out smoothly and fully extends, giving you easy access to what's inside.

PRODUCT DIMENSIONS

Height (Cabinet Incl. Hinge)	70-5/8"
Width	32"
Depth (Incl. Door)	26-1/2"

MORE EASY-TO-USE FEATURES

ALARM SYSTEM

Notifies you if there's been a power failure, if a door stays open longer than five minutes and if the interior temperature of the refrigerator rises above 56 degrees for more than 60 minutes.

PERFECT BINS™ DOOR STORAGE

Convenient door storage bins tilt-out for easy access and can even be removed for even easier access.

PUREADVANTAGE® AIR FILTER

Keeps clean, filtered air circulated throughout to prevent odour transfer.

LUXURY-QUIET™ DESIGN

Designed for consistently quiet operation.

Available in:



Stainless
(S)

OPTIONAL TRIM KITS

84" LOUVERED TRIM KITS

(ECP8436SS & ECP8472SS)
Designed as a replacement option for the Sub-Zero® brand 650 Series models and for new-build installation.

79" LOUVERED / 75" COLLAR TRIM KITS²

(TRIMKITSS1 & TRIMKITSS2)
Designed as a replacement option for Electrolux ICON® brand models E32AR75FPS and E32AF75FPS and for new-build installation.

72" COLLAR TRIM KITS

(ECP7236SS & ECP7272SS)
Designed as a replacement option for the Sub-Zero® brand 601 Series models and for new-build installation.

¹Eligibility based on product registration with Electrolux North America within 60 days of purchase. Products must have been purchased on or after July 1, 2013. Coverage includes material parts for 3 years and labour for 1 year.

²Kits are designed to fit either 79" or 75" opening height. For 79" cutout opening height, installation requires use of top louvered grille; for 75" cutout opening height, installation requires use of top trim piece and shortening of both side trim pieces.

Sub-Zero® is a registered trademark of Sub-Zero, Inc.

BUILT-IN ALL REFRIGERATOR

EI32AR80QS



19 CU. FT. BUILT-IN ALL REFRIGERATOR

CAPACITIES

Total Capacity	18.6 Cu. Ft.
Total Shelf Area	22.4 Sq. Ft.

EXTERIOR

Hidden Hinge Door Design	Yes
Signature Soft-Arc Handle Design	Yes

FEATURES

iQ-Touch™ Electronic Controls	Yes
Temp Alarm System	Yes
Door Ajar Alarm	Yes
Power Failure Alarm	Yes
PureAdvantage® Air Filtration	Yes
Adjustable Full-Width Glass Shelves (Silver Trim)	2
Luxury-Glide® Full-Extension Deli Drawer/Cool Zone™	1
Luxury-Glide® Full-Extension Crisper/Fresh Zone™	1
3-Position Adjustable Crisper Dividers	2
Removable Basket Trays	2
Adjustable Dairy Door Bin	1
Full-Width Gallon Storage with Tall Bottle Retainer	1
Clear Half-Width 2-Litre Adjustable Door Bins	3
Perfect Bins™ Door Storage	2
Full-Width Condiment Shelf	1
Luxury-Design® LED Lighting	Yes
Door Closer	Yes
Luxury-Quiet™ Design	Yes
Air Filter Indicator	Yes
Electronic Control Lock	Yes

ADDITIONAL FEATURES

Sabbath Mode (Star-K® Certified)	Yes
----------------------------------	-----

ACCESSORIES

84" Louvered Trim Kits:	Single – PN# ECP8436SS	Optional
	Double – PN# ECP8472SS	Optional
72" Collar Trim Kits:	Single – PN# ECP7236SS	Optional
	Double – PN# ECP7272SS	Optional
79" Louvered / 75" Collar Trim Kits¹:		
	Single – PN# TRIMKITSS1	Optional
	Double – PN# TRIMKITSS2	Optional

SPECIFICATIONS


Colour –	
Stainless Steel	S
Power Supply Connection Location	Right Bottom Rear
Voltage Rating	115V/60Hz
Connected Load (kW Rating) @ 115 Volts²	0.55
Minimum Circuit Required (Amps)	20
Shipping Weight (Approx.)	266 Lbs.

¹Kits are designed to fit either 79" or 75" opening height. For 79" cutout opening height, installation requires use of top louvered grille; for 75" cutout opening height, installation requires use of top trim piece and shortening of both side trim pieces.

²An electrical supply with grounded three-prong receptacle is required. The power supply circuit must be installed in accordance with national and local codes & ordinances.

NOTE: Always consult local and national electric and plumbing codes. Refer to Product Installation Guide for detailed installation instructions on the web at electroluxappliances.ca.

Specifications subject to change.



PRODUCT DIMENSIONS

Height (Including Door)	71-3/8"
(Cabinet Including Hinge)	70-5/8"
Width	32"
Depth (Including Door)	26-1/2"
(With Door Open 90°)	57-3/8"

Electrolux Major Appliances, N.A.

CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • electroluxappliances.ca

EI32AR80Q 08/15

© 2015 Electrolux Major Appliances, N.A.



High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.

Printed in Canada

BUILT-IN ALL FREEZER

EI32AF80QS

Featuring IQ-Touch™ Electronic Controls



SIGNATURE FEATURES



SURE-2-FIT® CAPACITY

Our most usable space inside gives you plenty of space to stock up so you'll always have food on hand for even an impromptu gathering.



FULL-WIDTH GLASS SHELVES

25" Full-width glass shelves provide enough space for large platters and are designed to keep spills contained, making them easy to clean.



LUXURY-GLIDE® FULL-WIDTH FREEZER DRAWERS

Drawers glide out smoothly and fully extend, giving you easy access to what's inside.



SOFT FREEZE™ BIN

Perfect storage for things like ice cream or anything you want to keep frozen, but still soft for serving.

PRODUCT DIMENSIONS

Height (Cabinet Incl. Hinge)	70-5/8"
Width	32"
Depth (Incl. Door)	26-1/2"

MORE EASY-TO-USE FEATURES

PLATINUM STAR® LIMITED WARRANTY

Our exclusive limited warranty that includes a 3-year coverage on parts and one year on labour without charge.¹

IQ-TOUCH™ CONTROLS

For those who like to have their options always visible on the IQ-Touch™ control panel.

BUILT-IN TRIM KIT

Optional trim kit(s) are available in stainless steel for built-in refrigerator, built-in freezer or side-by-side configuration.

AUTOMATIC ICE MAKER

Ensures you'll always have extra ice on hand.

ENHANCED LIGHTING

Bright lighting makes finding food easy.

ALARM SYSTEM

Notifies you if there's been a power failure, if a door stays open longer than five minutes and if the interior temperature of the freezer rises above 23 degrees for more than 60 minutes.

PUREADVANTAGE® AIR FILTER

Keeps clean, filtered air circulated throughout to prevent odour transfer.

Available in:



Stainless
(S)

OPTIONAL TRIM KITS

84" LOUVERED TRIM KITS

(ECP8436SS & ECP8472SS)
Designed as a replacement option for the Sub-Zero® brand 650 Series models and for new-build installation.

79" LOUVERED / 75" COLLAR TRIM KITS²

(TRIMKITSS1 & TRIMKITSS2)
Designed as a replacement option for Electrolux ICON® brand models E32AR75FPS and E32AF75FPS and for new-build installation.

72" COLLAR TRIM KITS

(ECP7236SS & ECP7272SS)
Designed as a replacement option for the Sub-Zero® brand 601 Series models and for new-build installation.

¹Eligibility based on product registration with Electrolux North America within 60 days of purchase. Products must have been purchased on or after July 1, 2013. Coverage includes material parts for 3 years and labour for 1 year.

²Kits are designed to fit either 79" or 75" opening height. For 79" cutout opening height, installation requires use of top louvered grille; for 75" cutout opening height, installation requires use of top trim piece and shortening of both side trim pieces.

Sub-Zero® is a registered trademark of Sub-Zero, Inc.

BUILT-IN ALL FREEZER

EI32AF80QS



19 CU. FT. BUILT-IN ALL FREEZER

CAPACITIES

Total Capacity	18.6 Cu. Ft.
Total Shelf Area	19.7 Sq. Ft.

EXTERIOR

Hidden Hinge Door Design	Yes
Signature Soft-Arc Handle Design	Yes

FEATURES

IQ-Touch™ Electronic Controls	Yes
Temp Alarm System	Yes
Door Ajar Alarm	Yes
Power Failure Alarm	Yes
PureAdvantage® Air Filtration	Yes
Adjustable Full-Width Glass Shelves (Silver Trim)	2
Luxury-Glide® Full-Width Bottom Basket	1
Luxury-Glide® Full-Width Mid-Level Baskets	2
Soft Freeze™ Bin with Tall Bottle Retainer	1
Clear Half-Width Adjustable Door Bin	4
Full-Width Door Bin	1
Luxury-Design® LED Lighting	Yes
Automatic Ice Maker	Yes
Door Closer	Yes
Luxury-Quiet™ Design	Yes
Air Filter Indicator	Yes
Electronic Control Lock	Yes

ADDITIONAL FEATURES

Sabbath Mode (Star-K® Certified)	Yes
----------------------------------	-----

ACCESSORIES

84" Louvered Trim Kits:	Single – PN # ECP8436SS	Optional
	Double – PN # ECP8472SS	Optional
72" Collar Trim Kits:	Single – PN # ECP7236SS	Optional
	Double – PN # ECP7272SS	Optional
79" Louvered/75" Collar Trim Kits¹:		
	Single – PN # TRIMKITSS1	Optional
	Double – PN # TRIMKITSS2	Optional


SPECIFICATIONS

Colour –	
Stainless Steel	S
Power Supply Connection Location	Right Bottom Rear
Water Inlet Location	Left Bottom Rear
Voltage Rating	115V/60Hz
Connected Load (kW Rating) @ 115 Volts²	0.55
Minimum Circuit Required (Amps)	20
Shipping Weight (Approx.)	255 Lbs.

¹Kits are designed to fit either 79" or 75" opening height. For 79" cutout opening height, installation requires use of top louvered grille; for 75" cutout opening height, installation requires use of top trim piece and shortening of both side trim pieces.

²An electrical supply with grounded three-prong receptacle is required. The power supply circuit must be installed in accordance with national and local codes & ordinances.

NOTE: Always consult local and national electric and plumbing codes. Refer to Product Installation Guide for detailed installation instructions on the web at electroluxappliances.ca. Specifications subject to change.



PRODUCT DIMENSIONS

Height (Including Door)	71-3/8"
(Cabinet Including Hinge)	70-5/8"
Width	32"
Depth (Including Door)	26-1/2"
(With Door Open 90°)	57-3/8"

Electrolux Major Appliances, N.A.

CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • electroluxappliances.ca

EI32AF80Q 08/15

© 2015 Electrolux Major Appliances, N.A.



High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.

Printed in Canada