

# GOEMANS APPLIANCES

1-877-463-6267

HST # 105167993 WWW.GOEMANS.COM  
Find us on Facebook at www.facebook.com/GoemansAppliances

## PACKING SLIP

# HB00016428-1

Salesperson: JASON NG  
Purchase Date: 7/25/17  
Invoice Finished Date:  
Delivery/Pickup Date: Mar 02, 2018  
Invoice Type: VBL  
Date Printed: Jul 25, 2017  
Page: 1

### ONLINE BANKING ACCOUNT

**BILL TO:** 4167238158

ZHAO, JIANMING & JONUS

TBA

LOT # 123

BRADFORD, ON TBA

TEL# (416) 723-8158 BUS# (647) 286-0555

**SHIP TO:** 4167238158

ZHAO, JIANMING & JONUS

TBA

LOT # 123

BRADFORD, ON TBA

TEL# (416) 723-8158 BUS# (647) 286-0555

Directions: 6TH LINE & SIMCOE ROAD

QTY	LOC	MODEL #	SERIAL #	COLOUR	BRAND - DESCRIPTION
1		JS42PPDUDE		PRO STAIN	JEN, RESB: REFRIGERATOR, SIDE-BY-SIDE, BU 42, ADVANCED INTEGRATED LCD ICE & WATER DISPENSER
		This special order product requires a 50% deposit & is considered FINAL SALE. x _____ PLEASE ALLOW UP TO 4-12 WEEKS FOR DELIVERY OF THIS PIECE.			
-1		P-CJEN-1707-15PER			
1		P-CJEN-1707-750			
1		JGRP436WP		STAINLES	JEN, RAGP: RANGE, GAS, PROFESSIONAL 36, COMM RNG, GAS OVEN, CONV, S/C, 7 LCD CNTRL
-1		P-CJEN-1707-15PER			
1		P-CJEN-1707-600			
1		JXW9036WP		STAINLES	JEN, HOWC: HOOD, WALL MOUNT 36 JENN-AIR PROSTYLE WALL-MOUNT HOOD, 600CFM
		This special order product requires a 50% deposit & is considered FINAL SALE. x _____ PLEASE ALLOW UP TO 4-12 WEEKS FOR DELIVERY OF THIS PIECE.			
-1		P-CJEN-1707-15PER			
1		JDB9200CWP		PROSTYLE	JEN, DISIC: DISHWASHER, INTEGRATED, COLOUR STAINLESS STEEL TUB, FULLY INTEGRATED WITH PROSTYL
-1		P-CJEN-1707-15PER			
1		P-DELIVERY \$5,000-9,999			
1	SITE		UNASSIGNED INSTALLER		Pre-inspect

- All products remain the property of Goemans until paid in full.
- Removal of old appliances at owner's risk and must be disconnected.
- Please refer to delivery/installation brochures for important details.
- All authorized returned products will be subject to a restocking charge.
- Interest of 18% per annum will be charged on overdue accounts.
- Upon delivery customer agrees to accept service in accordance with manufacturer's warranty.
- This sales invoice is based on delivery within 12 months from date of purchase. After 12 months (or if market conditions adversely change) Goemans reserves the right to review pricing/delivery on this order and offer our customers options to accommodate these changes. Any & all date sensitive supplier promotions are exempt from the 12 month price guarantee and must be taken by the promotional delivery deadline.

WHITE CUSTOMER COPY

PINK GOEMANS COPY

# GOEMANS APPLIANCES

1-877-463-6267

HST # 105167993

WWW.GOEMANS.COM

Find us on Facebook at [www.facebook.com/GoemansAppliances](http://www.facebook.com/GoemansAppliances)

## PACKING SLIP

# HB00016428-1

Salesperson:	JASON NG
Purchase Date:	7/25/17
Invoice Finished Date:	
Delivery/Pickup Date:	Mar 02, 2018
Invoice Type:	VBL
Date Printed:	Jul 25, 2017
Page:	2

### ONLINE BANKING ACCOUNT

**BILL TO:** 4167238158

ZHAO, JIANMING & JONUS

TBA

LOT # 123

BRADFORD, ON TBA

TEL# (416) 723-8158 BUS# (647) 286-0555

**SHIP TO:** 4167238158

ZHAO, JIANMING & JONUS

TBA

LOT # 123

BRADFORD, ON TBA

TEL# (416) 723-8158 BUS# (647) 286-0555

Directions: 6TH LINE & SIMCOE ROAD

QTY	LOC	MODEL #	SERIAL #	COLOUR	BRAND - DESCRIPTION
1		Installer to inspect site prior to install. Customer will be reimbursed 50% of site inspection fee upon booking installs. Applies to 3 or more installs purchased.	UNASSIGNED		50% SITE DISCOUNT FOR 3 PIECE PURCHASE
		SITE DISCOUNT	INSTALLER		
1		MAY BE ADDED TO AN ORDER IF 3 OR MORE INSTALLS ARE PURCHASED (Accessories are excluded)	UNASSIGNED		Wall mounted hood fans up to 36" model
		VHOOD3WM	INSTALLER		
1		Mounting of hood to wall, and vent connection up to 4ft in length. No hole cutting.	UNASSIGNED		Built-in fridge install 42" - 48" models
		FBIFRG2	INSTALLER		
1		Includes anti-tip, hook-up to existing waterline and levelling NO PANEL INSTALL OR JOINING (SEE FBIFRGJ)	UNASSIGNED		Gas short connection (pro range) Slide In Cooktops
		GPROR1	INSTALLER		
1		Set up of appliance, 4ft flex hose, and shut off valve. Ranges with total BTU greater than 125000 may require commercial gas flex hose. Not included, subject to extra cost. Use this code for PRO Cooktops as well	UNASSIGNED		5% 2-3 UNITS INSTALL PCKG DISCOUNT
		5 PERCENT 2-3 UNITS	INSTALLER		
		Payment			TRANSFER PAYMENT

- All products remain the property of Goemans until paid in full.
- Removal of old appliances at owner's risk and must be disconnected.
- Please refer to delivery/installation brochures for important details.
- All authorized returned products will be subject to a restocking charge.
- Interest of 18% per annum will be charged on overdue accounts.
- Upon delivery customer agrees to accept service in accordance with manufacturer's warranty.
- This sales invoice is based on delivery within 12 months from date of purchase. After 12 months (or if market conditions adversely change) Goemans reserves the right to review pricing/delivery on this order and offer our customers options to accommodate these changes. Any & all date sensitive supplier promotions are exempt from the 12 month price guarantee and must be taken by the promotional delivery deadline.

WHITE CUSTOMER COPY

PINK GOEMANS COPY

# JENN-AIR® DETAILED PLANNING DIMENSIONS


1 of 3

## 42" SIDE-BY-SIDE REFRIGERATORS WITH DISPENSER


JS42PPDUDE – 42<sup>3</sup>/<sub>8</sub>" x 83<sup>3</sup>/<sub>8</sub>" x 27<sup>3</sup>/<sub>4</sub>" (with handles)

JS42SSDUDE – 42<sup>3</sup>/<sub>8</sub>" x 83<sup>3</sup>/<sub>8</sub>" x 27<sup>1</sup>/<sub>8</sub>" (with handles)

### PRODUCT DIMENSIONS



FRONT VIEW



TOP VIEW

MODEL #		JS42PPDUDE JS42SSDUDE	
		in	cm
A	Width of freezer door (including hinge side offset)	17½	44.4
B	Width of refrigerator door (including hinge side offset)	23½	59.7
C	Space between doors	¾	1.0
D	Overall width (including side trim)	42 <sup>3</sup> / <sub>8</sub>	107.6
E	Height of top grille	8 <sup>3</sup> / <sub>8</sub>	21.7
F	Space between doors and top grille	¾	1.0
G	Height of handles		
	Pro-Style® Stainless	45 <sup>5</sup> / <sub>16</sub>	115.7
	Euro Style Stainless	50	127.1
H	Height to top of handles		
	Pro-Style® Stainless	63 <sup>1</sup> / <sub>16</sub>	163.5
	Euro Style Stainless	65 <sup>3</sup> / <sub>4</sub>	167.0
I	Height of doors	71	180.2
J	Height of bottom grille	3	7.6
K	Width of recessed refrigerator	41	104.1
L	Width from side of refrigerator to freezer handle – door fully open 110°		
	Pro-Style® Stainless	7 <sup>1</sup> / <sub>8</sub>	18.1
	Euro Style Stainless	6 <sup>3</sup> / <sub>4</sub>	17.1
M	Width from side of refrigerator to handle – door open 90°		
	Pro-Style® Stainless	2 <sup>5</sup> / <sub>8</sub>	6.7
	Euro Style Stainless	2	5.1
N	Width from side of refrigerator to refrigerator handle – door fully open 110°		
	Pro-Style® Stainless	9 <sup>5</sup> / <sub>8</sub>	24.4
	Euro Style Stainless	9 <sup>1</sup> / <sub>8</sub>	23.1
O	Depth without doors	22 <sup>1</sup> / <sub>8</sub>	56.2
P	Depth with doors	25 <sup>1</sup> / <sub>8</sub>	63.8
Q	Depth with handles		
	Pro-Style® Stainless	27 <sup>3</sup> / <sub>4</sub>	70.5
	Euro Style Stainless	27 <sup>1</sup> / <sub>8</sub>	68.8
R	Depth with refrigerator door open 90°	47 <sup>1</sup> / <sub>16</sub>	120.1

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.

**Do not make any cutouts based on this information.** Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.




8115AdZw915

## 42" SIDE-BY-SIDE REFRIGERATORS WITH DISPENSER

JS42PPDUDE – 42<sup>3</sup>/<sub>8</sub>" x 83<sup>3</sup>/<sub>8</sub>" x 27<sup>3</sup>/<sub>4</sub>" (with handles)JS42SSDUDE – 42<sup>3</sup>/<sub>8</sub>" x 83<sup>3</sup>/<sub>8</sub>" x 27<sup>1</sup>/<sub>8</sub>" (with handles)

## DIMENSIONS AS INSTALLED



SIDE VIEW

MODEL #	JS42PPDUDE JS42SSDUDE	
	in	cm
A*	Height without compressor (min.)	74 <sup>3</sup> / <sub>8</sub> 188.9
B*	Height of recessed refrigerator (min.)	83 <sup>3</sup> / <sub>8</sub> 211.8
C	Depth with refrigerator door open 90° (min.)	47 <sup>1</sup> / <sub>4</sub> 120.0
D	Depth with handles (min.)	
	Pro-Style® Stainless	27 <sup>3</sup> / <sub>4</sub> 70.5
	Euro Style Stainless	27 <sup>1</sup> / <sub>8</sub> 68.8
E	Depth with doors (min.)	25 <sup>1</sup> / <sub>8</sub> 63.8
F	Depth without doors (min.)	22 <sup>1</sup> / <sub>8</sub> 56.2
G	Depth of compressor (min.)	19 <sup>7</sup> / <sub>8</sub> 50.6

\*Add 1<sup>1</sup>/<sub>4</sub>" (3.2 cm) to the height dimension when leveling legs are fully extended.**IMPORTANT:** Dimensional specifications are provided for planning purposes only.



Do not make any cutouts based on this information. Refer to the Installation or Use &amp; Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

## 42" SIDE-BY-SIDE REFRIGERATORS WITH DISPENSER

JS42PPDUDE – 42 $\frac{3}{8}$ " x 83 $\frac{3}{8}$ " x 27 $\frac{3}{4}$ " (with handles)JS42SSDUDE – 42 $\frac{3}{8}$ " x 83 $\frac{3}{8}$ " x 27 $\frac{1}{8}$ " (with handles)

## OPENING/CLEARANCE DIMENSIONS



MODEL #		JS42PPDUDE JS42SSDUDE	
		in	cm
A	Width (min.)	41 $\frac{1}{2}$	105.4
B	Width of recommended electrical location	7 $\frac{1}{2}$	19.1
C	Distance from side of cabinet to recommended water connection location	6	15.2
D	Height (min.)	84	213.4
E	Height to recommended electrical location	77	195.6
F	Depth of recommended water connection location (max.)	1	2.5
e	Recommended electrical connection location		
w	Recommended water connection location		

## ELECTRICAL REQUIREMENTS

115 volt, 60 Hz, AC only, 15- or 20-amp fused, grounded circuit is required. A dedicated circuit is recommended. Use an outlet that cannot be turned off by a switch.

Minimum length of power cord is 84" (213.4 cm). Do not use an extension cord.

## WATER PRESSURE REQUIREMENTS

A cold water supply with water pressure between 30 and 120 psi (207 and 827 kPa) is required to operate the water dispenser and ice maker. Call a licensed, qualified plumber with any questions about the water pressure.

## Reverse Osmosis Water Supply

**IMPORTANT:** The pressure of the water coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 30 and 120 psi (207 and 827 kPa).

If a reverse osmosis water filtration system is connected to the cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).

## LOCATION REQUIREMENTS

Floor must be able to support refrigerator (more than 600 lb [272 kg]) and contents of the refrigerator and must be at the same level as flooring in the room.

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.

**Do not make any cutouts based on this information.** Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.



8115AdZw915


# JENN-AIR® DETAILED PLANNING DIMENSIONS

1 of 3

## 36" PRO-STYLE® GAS RANGES


JGRP536WP, JLRP536WP, JGRP436WP, JLRP436WP – 35<sup>7</sup>/<sub>8</sub>" x 38<sup>3</sup>/<sub>4</sub>" x 29<sup>1</sup>/<sub>4</sub>"

### PRODUCT DIMENSIONS



FRONT VIEW

MODEL #		JGRP536WP JLRP536WP JGRP436WP JLRP436WP	
		in	cm
A	Overall width	35 <sup>7</sup> / <sub>8</sub>	91.1
B	Height of island trim backsplash	3	7.6
C	Height of bullnose	2 <sup>1</sup> / <sub>4</sub>	5.5
D	Height of control panel	5 <sup>3</sup> / <sub>8</sub>	13.5
E	Space between door and control panel	<sup>7</sup> / <sub>8</sub>	2.0
F	Height of door	20 <sup>3</sup> / <sub>4</sub>	52.5
G	Height to top of handle	19 <sup>3</sup> / <sub>8</sub>	49.0
H	Space between door and lower panel	1	2.5
I	Height of lower panel	5 <sup>1</sup> / <sub>2</sub>	14.0
J	Depth with control panel overhang	27 <sup>7</sup> / <sub>8</sub>	69.5
K	Depth with handle	29 <sup>1</sup> / <sub>4</sub>	74.2
L	Depth with door fully open	45 <sup>3</sup> / <sub>4</sub>	116.2



TOP VIEW

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.  
**Do not make any cutouts based on this information.** Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.  
 All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.




8781FdZw0516

## 36" PRO-STYLE® GAS RANGES

JGRP536WP, JLRP536WP, JGRP436WP, JLRP436WP – 35<sup>7</sup>/<sub>8</sub>" x 38<sup>3</sup>/<sub>4</sub>" x 29<sup>1</sup>/<sub>4</sub>"

## DIMENSIONS AS INSTALLED



MODEL #		JGRP536WP JLRP536WP JGRP436WP JLRP436WP	
		in	cm
A*	Height to top of grates (min.)	36 <sup>3</sup> / <sub>4</sub>	93.3
B*	Height to top of cooking surface (min.)	35 <sup>3</sup> / <sub>4</sub>	90.8
C*	Height to top of door (min.)	27 <sup>7</sup> / <sub>8</sub>	69.5
D*	Height to top of handle (min.)	25 <sup>7</sup> / <sub>8</sub>	65.7
E*	Height to top of lower panel (min.)	5 <sup>7</sup> / <sub>8</sub>	14.9
F	Depth with door fully open	45 <sup>3</sup> / <sub>4</sub>	116.2
G	Depth with handle	29 <sup>1</sup> / <sub>4</sub>	74.2
H	Depth with control panel overhang	27 <sup>7</sup> / <sub>8</sub>	69.5
I	Depth without control panel	23 <sup>1</sup> / <sub>2</sub>	59.5
J	Depth of island trim backsplash	2 <sup>1</sup> / <sub>4</sub>	5.7
K	Depth without door	24 <sup>5</sup> / <sub>8</sub>	62.5
L	Depth with door	26 <sup>3</sup> / <sub>4</sub>	68.0
M*	Height to top of island trim backsplash (min.)	38 <sup>3</sup> / <sub>4</sub>	98.4

\*Add 1<sup>3</sup>/<sub>4</sub>" (4.4 cm) to the height dimension when leveling legs are fully extended.

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.


**Do not make any cutouts based on this information.** Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

## 36" PRO-STYLE® GAS RANGES

JGRP536WP, JLRP536WP, JGRP436WP, JLRP436WP – 35<sup>7</sup>/<sub>8</sub>" x 38<sup>3</sup>/<sub>4</sub>" x 29<sup>1</sup>/<sub>4</sub>"

## OPENING/CLEARANCE DIMENSIONS



FRONT VIEW

## MODEL #


		JGRP536WP JLRP536WP JGRP436WP JLRP436WP	
		in	cm
A	Width of combustable area above cooking surface (min.)	36	91.4
B	Width from range to fixed wall or other combustable material (min.)	6	15.2
C	Width of opening (min.)	36 <sup>1</sup> / <sub>4</sub>	92.1
D	Width of electrical installation area	28	71.1
E	Width of gas installation area	14	35.5
F	Width from side cabinet to gas installation area	6	15.2
G*	Height to bottom of uncovered wood or metal cabinet above cooking surface (min.)	42	106.7
H	Height to bottom of uncovered wood or metal cabinet (min.)	18	45.7
I	Height of electrical installation area	15	38.1
J	Depth of electrical and gas installation area	5	12.7
K	Height of gas installation area	3	7.6
L	Depth of upper cabinet (max.)	13	33.0
M**	Depth to wall (min.)	6	15.2
N	Width to electrical conduit	9 <sup>1</sup> / <sub>8</sub>	23.0
O	Width to gas inlet	14 <sup>3</sup> / <sub>8</sub>	36.5
e	Recommended electrical access location		
g	Recommended gas supply line location		

\*If installing a hood or hood liner above the range, follow the hood or hood liner instructions for dimensional clearances above the cooking surface.


\*\*If back wall is constructed of a combustable material and a backsplash is not installed, a 6" (15.2 cm) minimum clearance is required.

## ELECTRICAL REQUIREMENTS

120 volt, 60 Hz, AC only, 15-amp fused, grounded circuit is required. A dedicated circuit is recommended.



SIDE VIEW



BACK VIEW

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.

**Do not make any cutouts based on this information.** Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.


## 48"/36"/30" PRO-STYLE™ WALL-MOUNT HOODS

JXW9048WP – 48" x 19<sup>3</sup>/<sub>8</sub>" x 25"


JXW9036WP – 36" x 19<sup>3</sup>/<sub>8</sub>" x 25"

JXW9030WP – 30" x 19<sup>3</sup>/<sub>8</sub>" x 25"

### PRODUCT DIMENSIONS




FRONT VIEW



SIDE VIEW

(shown with optional duct cover)



TOP VIEW

### MODEL #

		<del>JXW9048WP</del>		<del>JXW9036WP</del>		<del>JXW9030WP</del>	
		<del>in</del>	<del>cm</del>	<del>in</del>	<del>cm</del>	<del>in</del>	<del>cm</del>
<b>A</b>	Overall width	<del>48</del>	<del>121.9</del>	<del>36</del>	<del>91.4</del>	<del>30</del>	<del>76.2</del>
<b>B</b>	Height without trim	<del>15<sup>3</sup>/<sub>4</sub></del>	<del>40.0</del>	<del>15<sup>3</sup>/<sub>4</sub></del>	<del>40.0</del>	<del>15<sup>3</sup>/<sub>4</sub></del>	<del>40.0</del>
<b>C</b>	Height of trim	<del>2<sup>1</sup>/<sub>4</sub></del>	<del>5.7</del>	<del>2<sup>1</sup>/<sub>4</sub></del>	<del>5.7</del>	<del>2<sup>1</sup>/<sub>4</sub></del>	<del>5.7</del>
<b>D</b>	Height without controls	<del>18</del>	<del>45.7</del>	<del>18</del>	<del>45.7</del>	<del>18</del>	<del>45.7</del>
<b>E</b>	Height with controls	<del>19<sup>3</sup>/<sub>8</sub></del>	<del>49.1</del>	<del>19<sup>3</sup>/<sub>8</sub></del>	<del>49.1</del>	<del>19<sup>3</sup>/<sub>8</sub></del>	<del>49.1</del>
<b>F</b>	Height of optional duct cover	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>
<b>G</b>	Depth of optional duct cover	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>
<b>H</b>	Depth of hood	<del>25</del>	<del>63.5</del>	<del>25</del>	<del>63.5</del>	<del>25</del>	<del>63.5</del>
<b>I</b>	Vent collar diameter	<del>9<sup>7</sup>/<sub>8</sub></del>	<del>25.1</del>	<del>9<sup>7</sup>/<sub>8</sub></del>	<del>25.1</del>	<del>9<sup>7</sup>/<sub>8</sub></del>	<del>25.1</del>

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.


**Do not make any cutouts based on this information.** Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

## 48"/36"/30" PRO-STYLE™ WALL-MOUNT HOODS

JXW9048WP – 48" x 19 $\frac{3}{8}$ " x 25"JXW9036WP – 36" x 19 $\frac{3}{8}$ " x 25"JXW9030WP – 30" x 19 $\frac{3}{8}$ " x 25"

## OPENING/CLEARANCE DIMENSIONS



FRONT VIEW

## ELECTRICAL REQUIREMENTS

120 volt, 60 Hz, AC only, 15-amp fused, electrical circuit is required. The knockout into the back of the terminal box is located on the right side.

## VENTING REQUIREMENTS

The hood is factory set for venting through the roof or wall. Do not terminate the vent in an attic or other enclosed area.

## LOCATION REQUIREMENTS

The minimum height from the floor to the top of the vent hood is 7' (2.1 m). The minimum height from the floor to the top of the optional duct cover is 8' (2.4 m).

MODEL #		<del>JXW9048WP</del>		<del>JXW9036WP</del>		<del>JXW9030WP</del>	
		<del>in</del>	<del>cm</del>	<del>in</del>	<del>cm</del>	<del>in</del>	<del>cm</del>
A	Width of vent entry location – ceiling option	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>
B	Width of vent entry location – wall option	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>
C	Width of cabinet opening (min.)	<del>48</del>	<del>121.9</del>	<del>36</del>	<del>91.4</del>	<del>30</del>	<del>76.2</del>
D	Height from vent entry location to ceiling – wall option (min.)	<del>2</del>	<del>5.1</del>	<del>2</del>	<del>5.1</del>	<del>2</del>	<del>5.1</del>
E	Height from hood to vent entry location – wall option (min.)	<del>24</del>	<del>61.0</del>	<del>24</del>	<del>61.0</del>	<del>24</del>	<del>61.0</del>
F	Height from hood to cooking surface (min.-max.)	<del>30-36</del>	<del>76.2-91.4</del>	<del>30-36</del>	<del>76.2-91.4</del>	<del>30-36</del>	<del>76.2-91.4</del>
G	Height from upper cabinet to countertop (min.)	<del>18</del>	<del>45.7</del>	<del>18</del>	<del>45.7</del>	<del>18</del>	<del>45.7</del>
H	Depth of vent entry location – ceiling option	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>	<del>12</del>	<del>30.5</del>
v	Recommended vent entry location						

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.

**Do not make any cutouts based on this information.** Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.



8562CdZw815


# JENN-AIR® DETAILED PLANNING DIMENSIONS

1 of 3


## DISHWASHERS

JDB9800CW, JDB9200CW, JDB9000CW – 23¾" x 33⅞" x 26⅞" (including handle)


### PRODUCT DIMENSIONS



FRONT VIEW



ADJUSTABLE TOE KICK



TOP VIEW

MODEL #		JDB9800CW JDB9200CW JDB9000CW	
		in	cm
<b>A</b>	Width of door	23½	59.7
<b>B</b>	Width of toe kick	23½	59.7
<b>C</b>	Height to top of handle Pro-Style® Stainless	27⅞	70.8
	Euro-Style (color-coordinating)	27⅞	70.8
	Floating Glass	27⅞	70.8
<b>D</b>	Height of door Pro-Style® Stainless	30	76.3
	Euro-Style (color-coordinating)	30	76.3
	Floating Glass	30	76.3
<b>E</b>	Height of adjustable toe kick (min.-max.)	3½- 4⅞	8.9- 10.5
<b>F</b>	Width of recessed dishwasher	23¾	60.4
<b>G</b>	Depth with tub flange	22⅞	57.4
<b>H</b>	Depth with door Pro-Style® Stainless	24⅞	62.6
	Euro-Style (color-coordinating)	24⅞	62.6
	Floating Glass	25	63.5
<b>I</b>	Depth with handle Pro-Style® Stainless	27⅞	70.8
	Euro-Style (color-coordinating)	26⅞	68.3
	Floating Glass	27⅞	70.8
<b>J</b>	Depth with door fully open	49¾	126.3

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.

**Do not make any cutouts based on this information.** Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.




8768CdZw416

## DISHWASHERS

JDB9800CW, JDB9200CW, JDB9000CW – 23<sup>3</sup>/<sub>4</sub>" x 33<sup>7</sup>/<sub>8</sub>" x 26<sup>7</sup>/<sub>8</sub>" (including handle)

## DIMENSIONS AS INSTALLED



MODEL #		JDB9800CW JDB9200CW JDB9000CW	
		in	cm
A*	Height to top of tub flange (min.)	33 <sup>7</sup> / <sub>8</sub>	86.0
B*	Height to top of door (min.)	33 <sup>3</sup> / <sub>4</sub>	85.7
C*	Height to top of handle (min.)		
	Pro-Style® Stainless	31 <sup>1</sup> / <sub>2</sub>	80.1
	Euro-Style (color-coordinating)	31 <sup>1</sup> / <sub>2</sub>	80.1
	Floating Glass	31 <sup>1</sup> / <sub>2</sub>	80.1
D*	Height to bottom of door	3 <sup>5</sup> / <sub>8</sub>	9.4
E*	Height of recessed dishwasher (min.)	33 <sup>3</sup> / <sub>8</sub>	85.5
F	Depth with door fully open (min.)	49 <sup>3</sup> / <sub>4</sub>	126.3
G	Depth with handle (min.)		
	Pro-Style® Stainless	27 <sup>7</sup> / <sub>8</sub>	70.8
	Euro-Style (color-coordinating)	26 <sup>7</sup> / <sub>8</sub>	68.3
	Floating Glass	27 <sup>7</sup> / <sub>8</sub>	70.8
H	Depth with door (min.)	24 <sup>5</sup> / <sub>8</sub>	62.6
I	Depth with tub flange (min.)	22 <sup>5</sup> / <sub>8</sub>	57.4
J	Depth with toe kick (min.)	20 <sup>7</sup> / <sub>8</sub>	52.9

\*With wheels removed. Add up to <sup>5</sup>/<sub>8</sub>" (1.6 cm) to height with wheels and leg levelers fully extended.

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.

**Do not make any cutouts based on this information.** Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.



8768CdZw416


# JENN-AIR® DETAILED PLANNING DIMENSIONS

3 of 3


## DISHWASHERS

JDB9800CW, JDB9200CW, JDB9000CW – 23¾" x 33⅞" x 26⅞" (including handle)


### OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



SIDE VIEW



BACK VIEW

#### MODEL #

JDB9800CW  
JDB9200CW  
JDB9000CW

		in	cm
<b>A</b>	Width (min.)	24	61.0
<b>B</b>	Width of possible utility installation area (back wall)	6¾	17.2
<b>C</b>	Width of clear area (back wall)	10½	26.7
<b>D*</b>	Height with wheels removed (min.)	33⅞	86.0
<b>E</b>	Height of possible utility installation area (back wall)	2½	6.4
<b>F</b>	Height of possible utility installation area (back/side wall)	6¼	15.9
<b>G</b>	Height of clear area (side wall)	3	7.6
<b>H</b>	Depth (min.)	24	61.0
<b>I</b>	Depth of utility location (side wall)	4	10.2

#### Electrical, water and drain connections may be installed in shaded areas

Recommended drain connection location – closest to sink	1½ dia.	3.8 dia.
Recommended electrical connection location – right-hand side or back wall	1½ dia.	3.8 dia.
Recommended water connection location – left-hand side or back wall	½ dia.	1.3 dia.

\*Measured from the lowest point on the underside of countertop.

#### ELECTRICAL REQUIREMENTS

120 volt, 60 Hz, AC only, 15- or 20-amp fused, grounded circuit is required. A dedicated circuit is recommended. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

#### WATER SUPPLY REQUIREMENTS

120°F (49°C) hot water supply with water pressure between 20 and 120 psi (138 and 862 kPa) is required. If you have questions about your water pressure, call a licensed, qualified plumber.

#### DRAIN REQUIREMENTS

Connect drain hose to waste tee or disposer inlet above drain trap. Maximum drain hose length 12' (3.7 m).

#### LOCATION REQUIREMENTS

Corner locations require a 2" (5.1 cm) minimum clearance between the side of the dishwasher door and the wall or cabinet.

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.

**Do not make any cutouts based on this information.** Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.



8768CdZw416