

S42 - 7C ELEV. "A"
5 BEDRM & 4 BEDRM + MEDIA LOFT

SECOND FLOOR FRAMING

HATCH LEGEND	
[Hatch Pattern]	CERAMIC TILES

PlotID	Products			
	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	12
J2	14-00-00	9 1/2" NI-40x	1	35
J3	12-00-00	9 1/2" NI-40x	1	23
J4	10-00-00	9 1/2" NI-40x	1	2
J5	6-00-00	9 1/2" NI-40x	1	11
J6	4-00-00	9 1/2" NI-40x	1	3
J7	18-00-00	9 1/2" NI-80	1	24
B3	14-00-00	VERSALAM-10 2.0E	2	2
B4	14-00-00	VERSALAM-10 2.0E	2	2
B6	14-00-00	VERSALAM-10 2.0E	2	2
B7 (DRPD)	12-00-00	VERSALAM-10 2.0E	2	2
B2	8-00-00	VERSALAM-10 2.0E	1	1
B5	6-00-00	VERSALAM-10 2.0E	1	1
B8	6-00-00	VERSALAM-10 2.0E	1	1
B10 (DRPD)	6-00-00	VERSALAM-10 2.0E	2	2
B9 (DRPD)	6-00-00	VERSALAM-10 2.0E	2	2
B1	4-00-00	VERSALAM-10 2.0E	1	1
B11	2-00-00	VERSALAM-10 2.0E	2	2

HANGER SCHEDULE.

H1 ----- IUS2.56/9.5 (FM)
H2 ----- IUS3.56/9.5 (FM)
H3 ----- HUS1.81/10 (FM)
H4 ----- HGUS410 (FM)

NOTE :

TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED

RIMBOARD

1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls

Multiple squash blocks are required under concentrated loads.


Ceramic tile application as per O.B.C. 9.30.6

Do not scale - refer to architectural plans for dimensions

97055 - March 9/18 revised

T.1505117 - T.1505144 + T.1803015

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpa Roof Trusses Inc. Salesperson: Mario.
File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 1 of 15 Maple, Ontario Tamarack Lumber



PlotID	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	19
J2	14-00-00	9 1/2" NI-40x	1	23
J3	14-00-00	9 1/2" NI-40x	2	8
J4	12-00-00	9 1/2" NI-40x	1	15
J5	12-00-00	9 1/2" NI-40x	2	8
J6	10-00-00	9 1/2" NI-40x	1	3
J7	8-00-00	9 1/2" NI-40x	1	8
J8	8-00-00	9 1/2" NI-40x	2	2
J9	6-00-00	9 1/2" NI-40x	1	38
J10	4-00-00	9 1/2" NI-40x	1	6
J11	2-00-00	9 1/2" NI-40x	1	1
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (-1R)	10-00-00	VERSALAM-10 2.0E	1	1
B15	8-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE:
H1 IUS2.56/6.6 (FM)
H2 HUS310.2 (FM)
H3 HUS1.81/10 (FM)

NOTE:
ITM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED
RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
Multiple squash blocks are required under concentrated loads.
Ceramic tile application as per O.B.C. 9.30.6

FIRST FLOOR FRAMING

Do not scale - refer to architectural plans for dimensions


S42 - 7C ELEV. " A "

HATCH LEGEND

[Symbol]	CERAMIC TILES
----------	---------------

97055-March 9/18

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpa Roof Trusses Inc. Salesperson: Mario.
File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 2 of 15 Maple, Ontario Tamarack Lumber



PlotID	Length	Products		Plies	Nat City
		Length	Product		
J1	16-00-00	9 1/2"	NI-40x	1	12
J2	14-00-00	9 1/2"	NI-40x	1	23
J3	14-00-00	9 1/2"	NI-40x	2	8
J4	12-00-00	9 1/2"	NI-40x	1	21
J5	12-00-00	9 1/2"	NI-40x	2	10
J6	10-00-00	9 1/2"	NI-40x	1	3
J7	8-00-00	9 1/2"	NI-40x	1	8
J8	8-00-00	9 1/2"	NI-40x	2	2
J9	6-00-00	9 1/2"	NI-40x	1	44
J10	4-00-00	9 1/2"	NI-40x	1	6
J11	2-00-00	9 1/2"	NI-40x	1	1
B23	16-00-00	VERSALAM-10.2.0E		2	2
B13A	14-00-00	VERSALAM-10.2.0E		1	1
B14	10-00-00	VERSALAM-10.2.0E		1	1
B19 (HIGH)	10-00-00	VERSALAM-10.2.0E		1	1
B20 (-1R)	10-00-00	VERSALAM-10.2.0E		1	1
B15	8-00-00	VERSALAM-10.2.0E		1	1
B16	8-00-00	VERSALAM-10.2.0E		1	1
B22 (HIGH/LOW)	8-00-00	VERSALAM-10.2.0E		1	2
B18	6-00-00	VERSALAM-10.2.0E		1	1
B12	4-00-00	VERSALAM-10.2.0E		1	1
B17	4-00-00	VERSALAM-10.2.0E		1	1
B21	4-00-00	VERSALAM-10.2.0E		1	1

HANGER SCHEDULE.
H1 ----- IUS2.56/9.5 (FM)
H2 ----- HUS310-2 (FM)
H3 ----- HUS1.61/10 (FM)

NOTE:
TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED
RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
Multiple squash blocks are required under concentrated loads.
Ceramic tile application as per O.B.C. 9.30.6

FIRST FLOOR FRAMING


Do not scale - refer to architectural plans for dimensions



S42 - 7C ELEV. " A " W/ SUNKEN LAUNDRY (ALL COND.)

97055 - March 9/18

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpa Roof Trusses Inc. Salesperson: Mario Tamarack Lumber
File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 3 of 15 Maple, Ontario



Products				
PlotID	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	19
J2	14-00-00	9 1/2" NI-40x	1	27
J3	14-00-00	9 1/2" NI-40x	2	4
J4	12-00-00	9 1/2" NI-40x	1	15
J5	10-00-00	9 1/2" NI-40x	1	3
J6	8-00-00	9 1/2" NI-40x	1	8
J7	8-00-00	9 1/2" NI-40x	2	2
J8	6-00-00	9 1/2" NI-40x	1	38
J9	4-00-00	9 1/2" NI-40x	1	3
J10	2-00-00	9 1/2" NI-40x	1	1
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (-1R)	10-00-00	VERSALAM-10 2.0E	1	1
B15	8-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE.

- H1 IUS2.56/9.5 (FM)
- H2 HUS10-2 (FM)
- H3 HUS1.81/10 (FM)

NOTE:

- TM - Top Mount Hangers
- FM - Face Mount Hanger
- APP - As Per Plan
- BB0 - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED

RIMBOARD

1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls

Multiple squash blocks are required under concentrated loads.

Ceramic tile application as per O.B.C. 9.30.6

FIRST FLOOR FRAMING


Do not scale - refer to architectural plans for dimensions

S42 - 7C ELEV. " A "
W/ W.O.D. COND.

HATCH LEGEND	
[Hatch Pattern]	CERAMIC TILES

97055 - March 9/18 revised

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpa Roof Trusses Inc. Salesperson: Mario.
 File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 4 of 15 Maple, Ontario Tamarack Lumber



ProdID	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	12
J2	14-00-00	9 1/2" NI-40x	1	27
J3	14-00-00	9 1/2" NI-40x	2	4
J4	12-00-00	9 1/2" NI-40x	1	21
J5	12-00-00	9 1/2" NI-40x	2	2
J6	10-00-00	9 1/2" NI-40x	1	3
J7	8-00-00	9 1/2" NI-40x	1	8
J8	8-00-00	9 1/2" NI-40x	2	2
J9	6-00-00	9 1/2" NI-40x	1	44
J10	4-00-00	9 1/2" NI-40x	1	3
J11	2-00-00	9 1/2" NI-40x	1	1
B23	16-00-00	VERSALAM-10 2.0E	2	2
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (-IR)	10-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B18	8-00-00	VERSALAM-10 2.0E	1	1
B22 (HIGH/LOW)	8-00-00	VERSALAM-10 2.0E	1	2
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE:
 H1 IUS2.56/9.5 (FM)
 H2 HU310-2 (FM)
 H3 HUS1.81/10 (FM)

NOTE:
 TM - Top Mount Hangers
 FM - Face Mount Hanger
 AFP - As Per Plan
 BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED
 RIMBOARD
 1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
 Multiple squash blocks are required under concentrated loads.
 Ceramic tile application as per O.B.C. 9.30.6

FIRST FLOOR FRAMING

Do not scale - refer to architectural plans for dimensions

S42 - 7C ELEV. " A "
 W/ SUNKEN LAUNDRY
 & W.O.D. COND.

97055-March 9/18 revised

JT: 44997/94450

Builder: Bayview Wellington Homes

Location: Bradford

Designer: FC/SG

Alpa Roof Trusses Inc.

Salesperson: Mario

File: 288215(248567)


Project: Green Valley Estates East

Date: Sept. 17, 2017

Sheet: S of 15

Maple, Ontario

Tamarack Lumber



Products				
PlotID	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	20
J2	14-00-00	9 1/2" NI-40x	1	25
J3	12-00-00	9 1/2" NI-40x	1	24
J4	10-00-00	9 1/2" NI-40x	1	3
J5	6-00-00	9 1/2" NI-40x	1	11
J6	4-00-00	9 1/2" NI-40x	1	3
J7	18-00-00	9 1/2" NI-80	1	25
B3	14-00-00	VERSALAM-10 2.0E	2	2
B4	14-00-00	VERSALAM-10 2.0E	2	2
B6	14-00-00	VERSALAM-10 2.0E	2	2
B7 (DRPD.)	12-00-00	VERSALAM-10 2.0E	2	2
B2	8-00-00	VERSALAM-10 2.0E	1	1
B5	6-00-00	VERSALAM-10 2.0E	1	1
B8	6-00-00	VERSALAM-10 2.0E	1	1
B10 (DRPD.)	6-00-00	VERSALAM-10 2.0E	2	2
B9 (DRPD.)	6-00-00	VERSALAM-10 2.0E	2	2
B1	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE.

H1 IUS2.56/6.5 (FM)
H2 IUS3.56/9.5 (FM)
H3 HUS1.81/10 (FM)
H4 HGU5410 (FM)

NOTE :

TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED

RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joist under interior load bearing walls

Multiple squash blocks are required under concentrated loads.

Ceramic tile application as per O.B.C. 9.30.6

Do not scale - refer to architectural plans for dimensions


S42 - 7C ELEV. " B "
5 BEDRM & 4 BEDRM + MEDIA LOFT

SECOND FLOOR FRAMING

HATCH LEGEND
[Symbol] CERAMIC TILES

97055 - March 9/18 revised

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpa Roof Trusses Inc. Salesperson: Mario.
File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 6 of 15 Maple, Ontario Tamarack Lumber



S42 - 7C ELEV. " B "

Products				
PlotID	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	26
J2	14-00-00	9 1/2" NI-40x	1	16
J3	14-00-00	9 1/2" NI-40x	2	8
J4	12-00-00	9 1/2" NI-40x	1	16
J5	12-00-00	9 1/2" NI-40x	2	8
J6	10-00-00	9 1/2" NI-40x	1	3
J7	8-00-00	9 1/2" NI-40x	1	8
J8	8-00-00	9 1/2" NI-40x	2	2
J9	6-00-00	9 1/2" NI-40x	1	38
J10	4-00-00	9 1/2" NI-40x	1	6
J11	2-00-00	9 1/2" NI-40x	1	1
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (LOW)	10-00-00	VERSALAM-10 2.0E	1	1
B15	8-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE:
 H1 IUS2.56/9.5 (FM)
 H2 HUS10.2 (FM)
 H3 HUS1.61/10 (FM)

NOTE:
 TM - Top Mount Hangers
 FM - Face Mount Hanger
 APP - As Per Plan
 BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED
RIMBOARD
 1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
 Multiple squash blocks are required under concentrated loads.
 Ceramic tile application as per O.B.C. 9.30.6

FIRST FLOOR FRAMING


Do not scale - refer to architectural plans for dimensions

HATCH LEGEND

[Symbol]	CERAMIC TILES
----------	---------------

97055 - March 9/18

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpha Roof Trusses Inc. Salesperson: Mario.
 File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 7 of 15. Maple, Ontario Tamarack Lumber



S42 - 7C ELEV. " B "
W/ SUNKEN LAUNDRY
(ALL COND.)

PlotID	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	19
J2	14-00-00	9 1/2" NI-40x	1	16
J3	14-00-00	9 1/2" NI-40x	2	8
J4	12-00-00	9 1/2" NI-40x	1	22
J5	12-00-00	9 1/2" NI-40x	2	10
J6	10-00-00	9 1/2" NI-40x	1	3
J7	8-00-00	9 1/2" NI-40x	1	8
J8	8-00-00	9 1/2" NI-40x	2	2
J9	6-00-00	9 1/2" NI-40x	1	44
J10	4-00-00	9 1/2" NI-40x	1	6
J11	2-00-00	9 1/2" NI-40x	1	1
B23	16-00-00	VERSALAM-10 2.0E	2	2
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (-1R)	10-00-00	VERSALAM-10 2.0E	1	1
B15	8-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B22 (HIGH/LOW)	8-00-00	VERSALAM-10 2.0E	1	2
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE.

H1 IUS2.56/9.5 (FM)
H2 HU310-2 (FM)
H3 HUS1.81/10 (FM)

NOTE :

TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others
SUBFLOOR - 5/8" NAILED & GLUED
RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
Multiple squash blocks are required under concentrated loads.
Ceramic tile application as per O.B.C. 9.30.6


FIRST FLOOR FRAMING

Do not scale - refer to architectural plans for dimensions

HATCH LEGEND

[Symbol]	CERAMIC TILES
----------	---------------

97055- March 9/18



Products				
PioliD	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	26
J2	14-00-00	9 1/2" NI-40x	1	20
J3	14-00-00	9 1/2" NI-40x	2	4
J4	12-00-00	9 1/2" NI-40x	1	16
J5	10-00-00	9 1/2" NI-40x	1	3
J6	8-00-00	9 1/2" NI-40x	1	8
J7	8-00-00	9 1/2" NI-40x	2	2
J8	6-00-00	9 1/2" NI-40x	1	38
J9	4-00-00	9 1/2" NI-40x	1	3
J10	2-00-00	9 1/2" NI-40x	1	1
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (-1R)	10-00-00	VERSALAM-10 2.0E	1	1
B15	8-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE.

H1 IUS2.56/9.5 (FM)
H2 HUS10-2 (FM)
H3 HUS1.81/10 (FM)

NOTE:

TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
SBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED

RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls

Multiple squash blocks are required under concentrated loads.

Ceramic tile application as per O.B.C. 9.30.6


FIRST FLOOR FRAMING

Do not scale - refer to architectural plans for dimensions

HATCH LEGEND	
[Hatched Pattern]	CERAMIC TILES

S42 - 7C ELEV. " B "
W/ W.O.D. COND.

97055 - March 9/18 revised



PilotID	Products		
	Length	Product	Piles Net Qty
J1	16-00-00	9 1/2" NI-40x	1 19
J2	14-00-00	9 1/2" NI-40x	1 20
J3	14-00-00	9 1/2" NI-40x	2 4
J4	12-00-00	9 1/2" NI-40x	1 22
J5	12-00-00	9 1/2" NI-40x	2 2
J6	10-00-00	9 1/2" NI-40x	1 3
J7	8-00-00	9 1/2" NI-40x	1 8
J8	8-00-00	9 1/2" NI-40x	2 2
J9	6-00-00	9 1/2" NI-40x	1 44
J10	4-00-00	9 1/2" NI-40x	1 3
J11	2-00-00	9 1/2" NI-40x	1 1
B23	16-00-00	VERSALAM-10 2.0E	2 2
B13A	14-00-00	VERSALAM-10 2.0E	1 1
B14	10-00-00	VERSALAM-10 2.0E	1 1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1 1
B20 (-1R)	10-00-00	VERSALAM-10 2.0E	1 1
B15	8-00-00	VERSALAM-10 2.0E	1 1
B16	8-00-00	VERSALAM-10 2.0E	1 1
B22 (HIGH/LOW)	8-00-00	VERSALAM-10 2.0E	1 2
B18	6-00-00	VERSALAM-10 2.0E	1 1
B12	4-00-00	VERSALAM-10 2.0E	1 1
B17	4-00-00	VERSALAM-10 2.0E	1 1
B21	4-00-00	VERSALAM-10 2.0E	1 1

HANGER SCHEDULE.

H1 IUS2.56/9.5 (FM)
H2 HU310-2 (FM)
H3 HUS1.81/10 (FM)

NOTE :

TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED

RIMBOARD

1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls

Multiple squash blocks are required under concentrated loads.


Ceramic tile application as per O.B.C. 9.30.6

FIRST FLOOR FRAMING

Do not scale - refer to architectural plans for dimensions

97055 - March 9/18 revised

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpa Roof Trusses Inc. Salesperson: Mario Tamarack Lumber
File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 10 of 12 Maple, Ontario



S42 - 7C ELEV. "C"
5 BEDRM & 4 BEDRM + MEDIA LOFT

SECOND FLOOR FRAMING

HATCH LEGEND	
[Hatched Pattern]	CERAMIC TILES

Products				
PlotID	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	19
J2	14-00-00	9 1/2" NI-40x	1	28
J3	12-00-00	9 1/2" NI-40x	1	23
J4	10-00-00	9 1/2" NI-40x	1	3
J5	6-00-00	9 1/2" NI-40x	1	11
J6	4-00-00	9 1/2" NI-40x	1	3
J7	2-00-00	9 1/2" NI-40x	1	2
J8	18-00-00	9 1/2" NI-80	1	24
B3	14-00-00	VERSALAM-10 2.0E	2	2
B4	14-00-00	VERSALAM-10 2.0E	2	2
B6	14-00-00	VERSALAM-10 2.0E	2	2
B7 (DRPD.)	12-00-00	VERSALAM-10 2.0E	2	2
B2	8-00-00	VERSALAM-10 2.0E	1	1
B5	6-00-00	VERSALAM-10 2.0E	1	1
B8	6-00-00	VERSALAM-10 2.0E	1	1
B10 (DRPD.)	6-00-00	VERSALAM-10 2.0E	2	2
B9 (DRPD.)	6-00-00	VERSALAM-10 2.0E	2	2
B1	4-00-00	VERSALAM-10 2.0E	1	1
B11	2-00-00	VERSALAM-10 2.0E	2	2

HANGER SCHEDULE.

H1 ----- IUS2.56/9.5 (FM)
H2 ----- IUS3.56/9.5 (FM)
H3 ----- IUS1.81/10 (FM)
H4 ----- HGUS410 (FM)

NOTE :

TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others


SUBFLOOR - 5/8" NAILED & GLUED
RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
Multiple squash blocks are required under concentrated loads.
Ceramic tile application as per O.B.C. 9.30.6

Do not scale - refer to architectural plans for dimensions

97055 - March 9/18

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpa Roof Trusses Inc. Salesperson: Mario.
File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 11 of 15 Maple, Ontario Tamarack Lumber



Products				
PlotID	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	22
J2	16-00-00	9 1/2" NI-40x	2	4
J3	14-00-00	9 1/2" NI-40x	1	22
J4	14-00-00	9 1/2" NI-40x	2	8
J5	12-00-00	9 1/2" NI-40x	1	13
J6	12-00-00	9 1/2" NI-40x	2	8
J7	10-00-00	9 1/2" NI-40x	1	4
J8	8-00-00	9 1/2" NI-40x	1	8
J9	8-00-00	9 1/2" NI-40x	2	2
J10	6-00-00	9 1/2" NI-40x	1	38
J11	4-00-00	9 1/2" NI-40x	1	7
J12	2-00-00	9 1/2" NI-40x	1	3
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (-1R)	10-00-00	VERSALAM-10 2.0E	1	1
B15	8-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE:
H1 IUS2.58/9.5 (FM)
H2 HUS310-2 (FM)
H3 HUS1.81/10 (FM)

NOTE:
TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED

RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
Multiple squash blocks are required under concentrated loads.
Ceramic tile application as per O.B.C. 9.30.6


FIRST FLOOR FRAMING

Do not scale - refer to architectural plans for dimensions

S42 - 7C ELEV. " C "

97055-March 9/18

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpa Roof Trusses Inc. Salesperson: Mario.
File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 12 of 15 Maple, Ontario Tamarack Lumber



Products				
PlotID	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	15
J2	16-00-00	9 1/2" NI-40x	2	4
J3	14-00-00	9 1/2" NI-40x	1	22
J4	14-00-00	9 1/2" NI-40x	2	8
J5	12-00-00	9 1/2" NI-40x	1	19
J6	12-00-00	9 1/2" NI-40x	2	10
J7	10-00-00	9 1/2" NI-40x	1	4
J8	8-00-00	9 1/2" NI-40x	1	8
J9	8-00-00	9 1/2" NI-40x	2	2
J10	6-00-00	9 1/2" NI-40x	1	44
J11	4-00-00	9 1/2" NI-40x	1	7
J12	2-00-00	9 1/2" NI-40x	1	3
B23	16-00-00	VERSALAM-10 2.0E	2	2
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (-1R)	10-00-00	VERSALAM-10 2.0E	1	1
B15	8-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B22 (HIGH /LOW)	8-00-00	VERSALAM-10 2.0E	1	2
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE.
H1 IUS2.56/9.5 (FM)
H2 HUS10-2 (FM)
H3 HUS1.81/10 (FM)

NOTE:
TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED
RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
Multiple squash blocks are required under concentrated loads.
Ceramic tile application as per O.B.C. 9.30.6


FIRST FLOOR FRAMING

Do not scale - refer to architectural plans for dimensions

S42 - 7C ELEV. " C "
W/ SUNKEN LAUNDRY
(ALL COND.)

97055 - March 9/18

JT: 44997/94450 Builder: Bayview Wellington Homes Location: Bradford Designer: FC/SG Alpa Roof Trusses Inc. Salesperson: Mario.
File: 288215(248567) Project: Green Valley Estates East Date: Sept. 17, 2017 Sheet: 13 of 15 Maple, Ontario Tamarack Lumber



PlotID	Products			
	Length	Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	22
J2	16-00-00	9 1/2" NI-40x	2	4
J3	14-00-00	9 1/2" NI-40x	1	22
J4	14-00-00	9 1/2" NI-40x	2	8
J5	12-00-00	9 1/2" NI-40x	1	15
J6	10-00-00	9 1/2" NI-40x	1	4
J7	8-00-00	9 1/2" NI-40x	1	8
J8	8-00-00	9 1/2" NI-40x	2	2
J9	6-00-00	9 1/2" NI-40x	1	38
J10	4-00-00	9 1/2" NI-40x	1	5
J11	2-00-00	9 1/2" NI-40x	1	3
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (-1R)	10-00-00	VERSALAM-10 2.0E	1	1
B15	8-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE.
H1 ----- IUS2.56/9.5 (FM)
H2 ----- HU310-2 (FM)
H3 ----- HUS1.81/10 (FM)

NOTE:
TM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED
RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.


1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
Multiple squash blocks are required under concentrated loads.
Ceramic tile application as per O.B.C. 9.30.5

FIRST FLOOR FRAMING

Do not scale - refer to architectural plans for dimensions.

S42 - 7C ELEV. " C "
W/ W.O.D. COND.

97055- March 9/18 revised



PlotID	Length	Products		
		Product	Piles	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	15
J2	16-00-00	9 1/2" NI-40x	2	4
J3	14-00-00	9 1/2" NI-40x	1	22
J4	14-00-00	9 1/2" NI-40x	2	8
J5	12-00-00	9 1/2" NI-40x	1	21
J6	12-00-00	9 1/2" NI-40x	2	2
J7	10-00-00	9 1/2" NI-40x	1	4
J8	8-00-00	9 1/2" NI-40x	1	8
J9	8-00-00	9 1/2" NI-40x	2	2
J10	6-00-00	9 1/2" NI-40x	1	44
J11	4-00-00	9 1/2" NI-40x	1	5
J12	2-00-00	9 1/2" NI-40x	1	3
B23	16-00-00	VERSALAM-10 2.0E	2	2
B13A	14-00-00	VERSALAM-10 2.0E	1	1
B14	10-00-00	VERSALAM-10 2.0E	1	1
B19 (HIGH)	10-00-00	VERSALAM-10 2.0E	1	1
B20 (-1R)	10-00-00	VERSALAM-10 2.0E	1	1
B15	8-00-00	VERSALAM-10 2.0E	1	1
B16	8-00-00	VERSALAM-10 2.0E	1	1
B22 (HIGH /LOW)	8-00-00	VERSALAM-10 2.0E	1	2
B18	6-00-00	VERSALAM-10 2.0E	1	1
B12	4-00-00	VERSALAM-10 2.0E	1	1
B17	4-00-00	VERSALAM-10 2.0E	1	1
B21	4-00-00	VERSALAM-10 2.0E	1	1

HANGER SCHEDULE.
H1 IUS2.56/9.5 (FM)
H2 HUS10.2 (FM)
H3 HUS1.81/10 (FM)

NOTE:
FM - Top Mount Hangers
FM - Face Mount Hanger
APP - As Per Plan
BBO - Beam By Others

SUBFLOOR - 5/8" NAILED & GLUED
RIMBOARD
1 - 1/8" X 9-1/2" O.S.B.

1 - 2X6 SPF#2 squash block req'd on one side of each joists under interior load bearing walls
Multiple squash blocks are required under concentrated loads.
Ceramic tile application as per O.B.C. 9.30.6

FIRST FLOOR FRAMING

Do not scale - refer to architectural plans for dimensions

S42 - 7C ELEV. " C "
W/ SUNKEN LAUNDRY
& W.O.D. COND.

97055-March 9/18 Revised



Build 6080

Filename: S42-7C.bcc

Description: Designs\B13A

Specifier:

Designer: F.C.

Company: Alps Roof Trusses Inc.

Code reports: CCMC 12472-R

38514

GREEN VALLEY ESTATES

City, Province, Postal Code: Bradford, ON

Customer: BAYVIEW WELLINGTON HOMES

Code reports: CCMC 12472-R

File Name: S42-7C.bcc


Description: Designs\B13A

Specifier:

Designer: F.C.

Company: Alps Roof Trusses Inc.

Misc:



12-07-00

Total Horizontal Product Length = 12-07-00

Reaction Summary (Down / Uplift) (lbs)


Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	528 / 0	403 / 0		
B1, 3-1/2"	638 / 0	574 / 0		

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1	Unf. Lin. (lb/ft)	L	00-00-00	12-07-00	27	10			n/a
2	Conc. Pt. (lbs)	L	06-08-00	06-08-00	333	135			n/a
3	Unf. Lin. (lb/ft)	L	00-00-00	06-08-00	20	10			n/a
4	Unf. Lin. (lb/ft)	L	00-00-00	01-00-00	0	60			n/a
5	Unf. Lin. (lb/ft)	L	06-00-00	12-07-00	0	60			n/a
6	Conc. Pt. (lbs)	L	08-02-00	08-02-00	240	90			n/a
7	Unf. Lin. (lb/ft)	L	08-02-00	12-07-00	27	10			n/a

Controls Summary

Pos. Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
5,607 ft-lbs	11,610 ft-lbs	48.3%	1	06-08-00	
1,472 lbs	5,785 lbs	25.4%	1	11-06-00	
L/373 (0.39")	0.606"	64.3%	4	06-06-00	
L/642 (0.227")	0.404"	56.1%	5	06-06-00	
0.39"	1"	39%	4	06-06-00	
15.3	n/a	n/a		00-00-00	
Squash Blocks	Valid				



Bearing Supports

	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0	3-1/2" x 1-3/4"	1,295 lbs	34.4%	17.3%	Spruce Pine Fir
B1	3-1/2" x 1-3/4"	1,674 lbs	44.4%	22.4%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.

Calculations assume member is fully braced.

Factor phi has been applied to all presented results per CSA O86.

ALC analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 4



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Floor Beam\B01

November-28-14


Dry | 1 span | No cantilevers | 0/12 slope (deg)



BC CALC® Design Report

File Name: BC
 Description: Designs\B01
 Specifier:
 Designer: F.C.
 Company: Alps Roof Trusses Inc.
 Misc:

38514
 GREEN VALLEY ESTATES
 City, Province, Postal Code: Bradford, ON
 Customer: BAYVIEW WELLINGTON HOMES
 Code reports: CCMC 12472-R



Total Horizontal Product Length = 04-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind	Live	Dead	Snow	Wind	Trib.
B0, 3-1/2"	533 / 0	210 / 0			1.00	0.65	1.00	1.15	
B1, 3-1/2"	533 / 0	210 / 0			40	15			06-08-00

Load Summary

Tag Description	Load Type	Ref. Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR/STAIRS	Unf. Area (lb/ft²)	L 00-00-00	04-00-00	40	15			06-08-00

Controls Summary

Des. Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
833 ft-lbs	12,704 ft-lbs	0.07	1	02-00-00	
487 lbs	5,785 lbs	0.08	1	01-01-00	
Live Load Defl.	L/999 (0.005")	n/a	4	02-00-00	
Live Load Defl.	L/999 (0.004")	n/a	5	02-00-00	
Max Defl.	0.005"	n/a	4	02-00-00	
Span / Depth	4.5	n/a	4	00-00-00	

Disclosure
 Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.\n\nBC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Bearing Supports


	Dim. (L x W)	Demand	Demand/Resistance Support	Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	1,062 lbs	0.28	0.14	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	1,062 lbs	0.28	0.14	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ O.C., STAGGERED IN TWO ROWS



1505117



BC CALC® Design Report

Dry | 1 span | No cantilevers | 0/12 slope (deg)


November-28-14

Project Id 3272

38514

Name: GREEN VALLEY ESTATES
Address: BAYVIEW WELLINGTON HOMES
City, Province, Postal Code: Bradford, ON
Customer: CCMC 12472-R
Code reports:

File Name: S42-7C
Description: Designs\B02
Specifier:
Designer: F.C.
Company: Alps Roof Trusses Inc.
Misc:



07-06-00

B1

Total Horizontal Product Length = 07-06-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead
B0, 3-1/2"	1,795 / 0	860 / 0
B1, 3-1/2"	1,576 / 0	776 / 0

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft^2)	L	00-00-00	07-06-00	40	20			08-08-00
2 PLB1	Conc. Pt. (lbs)	L	03-03-00	03-03-00	533	210			n/a
FLOOR	Unf. Area (lb/ft^2)	L	00-00-00	03-03-00	40	15			01-10-00

Controls Summary

Pos. Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
6,719 ft-lbs	12,704 ft-lbs	0.53	1	03-03-00	
2,806 lbs	5,785 lbs	0.49	1	01-01-00	
Total Load Defl.	L/525 (0.161")	0.352"	4	03-08-06	
Live Load Defl.	L/999 (0.109")	n/a	5	03-08-06	
Max Defl.	0.161"	1"	4	03-08-06	
Span / Depth	8.9	n/a	n/a	00-00-00	

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. \n\nBC CALC®, BC FRAMER®, AJS™, ALLOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Bearing Supports


	Dim. (L x W)	Demand	Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	3,767 lbs	1	0.5	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	3,334 lbs	0.88	0.45	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum total load deflection criteria.
Calculations assume Member is Fully Braced.
Resistance Factor phi has been applied to all presented results per CSA 086.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4
Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
O.C., STAGGERED IN TWO ROWS



150514



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Floor Beam\B03


November-28-14

Dry | 1 span | No cantilevers | 0/12 slope (deg)

BC CALC® Design Report



Report #: 3272
 File Name: S42-7C
 Address: 38514 GREEN VALLEY ESTATES
 Description: Designs\B03
 City, Province, Postal Code: Bradford, ON
 Designer: F.C.
 Customer: BAYVIEW WELLINGTON HOMES
 Company: Alps Roof Trusses Inc.
 Code reports: CCMC 12472-R
 Misc:



Total Horizontal Product Length = 12-08-00
 Total Horizontal Product Length = 12-08-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind	Trib.
B0, 3-1/2"	2,023 / 0	1,371 / 0			05-07-00
B1, 3-1/2"	1,559 / 0	1,116 / 0			n/a

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	09-00-00	40	20			05-07-00
PL B1	Conc. Pt. (lbs)	L	03-00-00	03-00-00	533	210			n/a
3 FLOOR	Unf. Area (lb/ft ²)	L	09-00-00	12-08-00	40	15			05-07-00
4 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	03-00-00	40	15			01-10-00
5 WALL	Unf. Lin. (lb/ft)	L	00-00-00	12-08-00	60				n/a

Controls Summary

Pos	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Moment	12,191 ft-lbs	25,408 ft-lbs	0.48	1	05-09-12
End Shear	3,984 lbs	11,571 lbs	0.34	1	01-01-00
Total Load Defl.	L/310 (0.473")	0.61"	0.78	4	06-02-04
Live Load Defl.	L/530 (0.276")	0.407"	0.68	5	06-02-04
Max Defl.	0.473"	1"	0.47	4	06-02-04
Span / Depth	15.4	n/a	n/a	4	00-00-00

Bearing Supports


Member	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-1/2" x 3-1/2"	4,749 lbs	0.63	0.32	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 3-1/2"	3,732 lbs	0.5	0.25	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ 12" O.C., STAGGERED IN TWO ROWS



T-150519



Boise Cascade

Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP

Floor Beam\B04

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November-28-14

BC CALC® Design Report



Report # 3272

Name:

Address: 38514 GREEN VALLEY ESTATES
City, Province, Postal Code: Bradford, ON
Customer: BAYVIEW WELLINGTON HOMES
Code reports: CCMC 12472-R


File Name: S42-7C
Description: Designs\B04

Specifier:

Designer: F.C.

Company: Alps Roof Trusses Inc.

Misc:



12-08-00

B1

Total Horizontal Product Length = 12-08-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead
B0, 3-1/2"	862 / 0	563 / 0
B1, 3-1/2"	1,373 / 0	928 / 0

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	12-08-00	40	15			01-04-00
2 PL B3	Conc. Pt. (lbs)	L	08-04-00	08-04-00	1,559	1,116			n/a

Controls Summary

Pos. Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
End Shear	12,119 ft-lbs	25,408 ft-lbs	0.48	1	08-04-00
Total Load Defl.	3,093 lbs	11,571 lbs	0.27	1	11-07-00
Live Load Defl.	L/380 (0.385")	0.61"	0.63	4	06-08-15
Max Defl.	0.385"	1"	0.56	5	06-08-15
Span / Depth	15.4	n/a	0.39	4	06-08-15
			n/a	4	00-00-00

Bearing Supports


B0	Wall/Plate	Dim. (L x W)	Demand	Demand/Resistance Support	Member	Material
B1	Wall/Plate	3-1/2" x 3-1/2"	1,996 lbs	0.26	0.13	Spruce Pine Fir
		3-1/2" x 3-1/2"	3,219 lbs	0.43	0.22	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ 12" O.C., STAGGERED IN TWO ROWS



T-1505120



Dry | 1 span | No cantilevers | 0/12 slope (deg)


November-28-14

BC CALC® Design Report



BC 3272
Name: 38514
Address: GREEN VALLEY ESTATES
City, Province, Postal Code: Bradford, ON
Customer: BAYVIEW WELLINGTON HOMES
Code reports: CCMC 12472-R

File Name: S42-7C
Description: Designs\B05
Specifier:
Designer: F.C.
Company: Alps Roof Trusses Inc.
Misc:



B0 B1
05-02-00
Total Horizontal Product Length = 05-02-00

Reaction Summary (Down / Uplift) (lbs)

Table with columns: Bearing, Live, Dead, Snow, Wind. Rows for B0 and B1.

Load Summary

Table with columns: Tag Description, Load Type, Ref., Start, End, Live, Dead, Snow, Wind, Trib. Rows for FLOOR and PL B2.

Controls Summary

Table with columns: Pos., Moment, End Shear, Total Load Def., Live Load Def., Max Def., Span / Depth, Factored Demand, Factored Resistance, Demand / Resistance, Demand / Resistance Support, Demand / Resistance Member, Demand / Resistance Material, Location. Rows for various load cases.

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Bearing Supports


Table with columns: Dim. (L x W), Demand, Demand / Resistance Support, Demand / Resistance Member, Demand / Resistance Material. Rows for Wall/Plate B0 and B1.

Notes

Design meets Code minimum (L/240) Total load deflection criteria. Design meets Code minimum (L/360) Live load deflection criteria. Design meets User specified (1") Maximum total load deflection criteria. Calculations assume Member is Fully Braced. Resistance Factor phi has been applied to all presented results per CSA O86. BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA O86. Design based on Dry Service Condition. Importance Factor : Normal Part code : Part 4 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS @ O.C., STAGGERED IN TWO ROWS



T-150521



BC CALC® Design Report



Project: 3272

Name: 38514

Address: GREEN VALLEY ESTATES

City, Province, Postal Code: Bradford, ON

Customer: BAYVIEW WELLINGTON HOMES

Code reports: CCMC 12472-R

File Name: S42-7C


Description: Designs\B06

Specifier:

Designer: F.C.

Company: Alps Roof Trusses Inc.

Misc:



12-02-00
Total Horizontal Product Length = 12-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	494 / 0	336 / 0		
B1, 3"	2,178 / 0	1,477 / 0		

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	12-02-00	40	20			01-04-00
2 PLB3	Conc. Pt. (lbs)	L	11-00-00	11-00-00	2,023	1,371			n/a

Controls Summary

Pos.	Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
End Shear	5,112 ft-lbs	25,408 ft-lbs	0.2	1	09-03-09	
Total Load Defl.	4,982 lbs	11,571 lbs	0.43	1	11-01-08	
Live Load Defl.	L/800 (0.176")	0.587"	0.3	4	06-07-15	
Max Defl.	0.176"	1"	0.18	5	06-07-15	
Span / Depth	14.8	n/a	n/a	4	00-00-00	

Bearing Supports


	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0	3-1/2" x 3-1/2"	1,161 lbs	0.15	0.08	Spruce Pine Fir
B1	3" x 3-1/2"	5,113 lbs	0.79	0.4	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ 12" O.C., STAGGERED IN TWO ROWS



T-1505102



BC CALC® Design Report

Dry | 1 span | No cantilevers | 0/12 slope (deg)

Report No: 3272

File Name: S42-7C

Project Name: GREEN VALLEY ESTATES

Address: BAYVIEW WELLINGTON HOMES

City, Province, Postal Code: Bradford, ON

Company: Alps Roof Trusses Inc.


Customer: CCMC 12472-R

Misc:

Description: Designs\B07

Specifier:

Designer: F.C.



11-00-00

B1

Total Horizontal Product Length = 11-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,980 / 0	795 / 0		
B1, 3-1/2"	1,980 / 0	795 / 0		

Load Summary

Tag Description	Load Type	Ref. Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft^2)	L 00-00-00	11-00-00	40	15			06-04-00
2 FLOOR	Unf. Area (lb/ft^2)	L 00-00-00	11-00-00	40	15			02-08-00

Controls Summary

Pos. Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
10,012 ft-lbs	25,408 ft-lbs	0.39	1	05-06-00	
3,183 lbs	11,571 lbs	0.28	1	01-01-00	
Total Load Defl.	L/451 (0.28")	0.527"	4	05-06-00	
Live Load Defl.	L/632 (0.2")	0.351"	5	05-06-00	
Max Defl.	0.28"	1"	4	05-06-00	
Span / Depth	13.3	n/a		00-00-00	

Bearing Supports


B0	Wall/Plate	Dim. (L x W)	Demand	Demand / Resistance Support	Member	Material
		3-1/2" x 3-1/2"	3,964 lbs	0.53	0.27	Spruce Pine Fir
B1	Wall/Plate	3-1/2" x 3-1/2"	3,964 lbs	0.53	0.27	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ (2) O.C., STAGGERED IN TWO ROWS



T-1505223



Dry | 1 span | No cantilevers | 0/12 slope (deg)

BC CALC® Design Report

Project: 3272

Name: 38514

Address: GREEN VALLEY ESTATES

City, Province, Postal Code: Bradford, ON

Customer: BAYVIEW WELLINGTON HOMES

Code reports: CCMC 12472-R

File Name: S42-7C


Description: Designs\B08

Specifier:

Designer: F.C.

Company: Alps Roof Trusses Inc.

Misc:



05-06-00

B1

B0 Total Horizontal Product Length = 05-06-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live		Dead	Snow		Wind		Trib.
	Down	Uplift		Start	End	Start	End	
B0, 3-1/2"	733 / 0	733 / 0	453 / 0					
B1, 3-1/2"	733 / 0	733 / 0	453 / 0					

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	05-06-00	40	15			06-08-00
2 WALL	Unf. Lin. (lb/ft)	L	00-00-00	05-06-00	60	60			n/a

Controls Summary

Pos. Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
End Shear	1,926 ft-lbs	12,704 ft-lbs	0.15	1	02-09-00
Total Load Defl.	1,010 lbs	5,785 lbs	0.17	1	01-01-00
Live Load Defl.	L/999 (0.025")	n/a	n/a	4	02-09-00
Max Defl.	0.025"	n/a	n/a	5	02-09-00
Span / Depth	6.4	n/a	n/a	4	02-09-00
					00-00-00

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	1,667 lbs	0.44	0.22	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	1,667 lbs	0.44	0.22	Spruce Pine Fir

Notes


Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ O.C., STAGGERED IN TWO ROWS

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain installation Guide or ask questions, please call 1-800-964-6999 before installation. InVnBC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



T-150524



Boise Cascade

Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP

Floor Beam\B09

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November-28-14



BC CALC® Design Report

Project: 3272

Name: 38514

Address: GREEN VALLEY ESTATES

City, Province, Postal Code: Bradford, ON

Customer: BAYVIEW WELLINGTON HOMES

Code reports: CCMC 12472-R

File Name: S42-7C


Description: Designs\B09

Specifier:

Designer: F.C.

Company: Alps Roof Trusses Inc.

Misc:



B0
06-00-00
B1

Total Horizontal Product Length = 06-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind	Trib.
B0, 3-1/2"	1,240 / 0	494 / 0			
B1, 3-1/2"	1,240 / 0	494 / 0			

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft²)	L	00-00-00	06-00-00	40	15			07-08-00
2 FLOOR	Unf. Area (lb/ft²)	L	00-00-00	06-00-00	40	15			02-08-00

Controls Summary

Pos.	Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
End Shear	3,170 ft-lbs	25,408 ft-lbs	0.12	1	03-00-00	
Total Load Defl.	1,583 lbs	11,571 lbs	0.14	1	01-01-00	
Live Load Defl.	L/999 (0.025")	n/a	n/a	4	03-00-00	
Max Defl.	L/999 (0.018")	n/a	n/a	5	03-00-00	
Span / Depth	0.025"	n/a	n/a	4	03-00-00	
	7	n/a	n/a	4	00-00-00	

Bearing Supports


B0	Wall/Plate	Dim. (L x W)	Demand	Demand/Resistance Support	Member	Material
B0	Wall/Plate	3-1/2" x 3-1/2"	2,477 lbs	0.33	0.17	Spruce Pine Fir
B1	Wall/Plate	3-1/2" x 3-1/2"	2,477 lbs	0.33	0.17	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ 12" O.C., STAGGERED IN TWO ROWS (TOP LOADED)



T-1805125



Boise Cascade

Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP

Floor Beam\B10

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November-28-14



BC CALC® Design Report

Project: 3272

Name: 38514

Address: GREEN VALLEY ESTATES

City, Province, Postal Code: Bradford, ON

Customer: BAYVIEW WELLINGTON HOMES

Code reports: CCMC 12472-R

File Name: S42-7C


Description: Designs\B10

Specifier:

Designer: F.C.

Company: Alps Roof Trusses Inc.

Misc:



06-00-00

B1

B0

Total Horizontal Product Length = 06-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind	Trib.
B0, 3-1/2"	800 / 0	609 / 0			
B1, 3-1/2"	800 / 0	609 / 0			

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	06-00-00	40	20			06-08-00
2 WALL	Unf. Lin. (lb/ft)	L	00-00-00	06-00-00		60			n/a

Properties Summary

Pos.	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Moment	2,509 ft-lbs	25,408 ft-lbs	0.1	1	03-00-00
End Shear	1,253 lbs	11,571 lbs	0.11	1	01-01-00
Total Load Defl.	L/999 (0.02")	n/a	n/a	4	03-00-00
Live Load Defl.	L/999 (0.011")	n/a	n/a	5	03-00-00
Max Defl.	0.02"	n/a	n/a	4	03-00-00
Span / Depth	7	n/a	n/a		00-00-00

Bearing Supports


	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0 Wall/Plate	3-1/2" x 3-1/2"	1,961 lbs	0.26	0.13	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 3-1/2"	1,961 lbs	0.26	0.13	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ 2' O.C., STAGGERED IN TWO ROWS



T-150526



Boise Cascade

Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP

Floor Beam\B11

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November-28-14



BC CALC® Design Report

Report No: 3272

File Name: S42-7C

Description: Designs\B11

38514 GREEN VALLEY ESTATES

Specifier: F.C.

Address: City, Province, Postal Code: Bradford, ON


Designer: F.C.

Customer: BAYVIEW WELLINGTON HOMES

Company: Alps Roof Trusses Inc.

Code reports: CCMC 12472-R

Misc:



02-00-00
B0
B1

Total Horizontal Product Length = 02-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind	Trib.
B0, 3-1/2"	341 / 0	316 / 0	260 / 0		06-04-00
B1, 3-1/2"	341 / 0	316 / 0	260 / 0		n/a

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	02-00-00	40	20			06-04-00
2 WALL	Unf. Lin. (lb/ft)	L	00-00-00	02-00-00		100			n/a
ROOF	Unf. Area (lb/ft ²)	L	00-00-00	02-00-00	11	10		32	08-00-00

Controls Summary

Pos.	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Moment	308 ft-lbs	25,408 ft-lbs	0.01	1	01-00-00
End Shear	86 lbs	11,571 lbs	0.01	1	01-01-00
Total Load Defl.	L/999 (0")	n/a	n/a	11	01-00-00
Live Load Defl.	L/999 (0")	n/a	n/a	15	01-00-00
Max Defl.	0"	n/a	n/a	11	01-00-00
Span / Depth	1.9	n/a	n/a		00-00-00

Bearing Supports


B0	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
Wall/Plate	3-1/2" x 3-1/2"	1,037 lbs	0.14	0.07	Spruce Pine Fir
Wall/Plate	3-1/2" x 3-1/2"	1,037 lbs	0.14	0.07	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 6" O.C., STAGGERED IN TWO ROWS



T-150512



Dry | 1 span | No cantilevers | 0/12 slope (deg)


November-28-14

BC CALC® Design Report

Project: 3272

Name: 38514 GREEN VALLEY ESTATES
Address: GREEN VALLEY ESTATES
City, Province, Postal Code: Bradford, ON
Customer: BAYVIEW WELLINGTON HOMES
Code reports: CCMC 12472-R

File Name: S42-7C
Description: Designs\B12
Specifier:
Designer: F.C.
Company: Alps Roof Trusses Inc.
Misc:



Total Horizontal Product Length = 04-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	333 / 0	135 / 0		
B1, 3-1/2"	333 / 0	135 / 0		

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR/STAIRS	Unf. Area (lb/ft²)	L	00-00-00	04-00-00	40	15		1.00 1.15	04-02-00

Controls Summary

Param.	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Moment	524 ft-lbs	12,704 ft-lbs	0.04	1	02-00-00
Shear	306 lbs	5,785 lbs	0.05	1	01-01-00
Total Load Defl.	L/999 (0.003")	n/a	n/a	4	02-00-00
Live Load Defl.	L/999 (0.002")	n/a	n/a	5	02-00-00
Max Defl.	0.003"	n/a	n/a	4	02-00-00
Span / Depth	4.5	n/a	n/a		00-00-00

Disclosure
Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In BC CALC®, BC FRAMER®, AJS™, ALLJOIST® BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Bearing Supports


	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	668 lbs	0.18	0.09	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	668 lbs	0.18	0.09	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum total load deflection criteria.
Calculations assume Member is Fully Braced.
Resistance Factor phi has been applied to all presented results per CSA 086.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4
Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS @ O.C., STAGGERED IN TWO ROWS



T-150512f



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP

Floor Beam\B14

November-28-14


Dry | 1 span | No cantilevers | 0/12 slope (deg)



BC CALC® Design Report

Report No: 3272
 Name: GREEN VALLEY ESTATES
 Address: BAYVIEW WELLINGTON HOMES
 City, Province, Postal Code: Bradford, ON
 Customer: CCMC 12472-R
 Code reports:

File Name: S42-7C
 Description: Designs\B14
 Specifier:
 Designer: F.C.
 Company: Alps Roof Trusses Inc.
 Misc:



B0
 06-08-00
 B1
 Total Horizontal Product Length = 08-08-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	303 / 0	137 / 0		
B1, 3-1/2"	492 / 0	213 / 0		

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	08-08-00	40	15			01-04-00
2 PL B12	Conc. Pt. (lbs)	L	06-08-00	06-08-00	333	135		1.00 1.15	n/a

Controls Summary

Pos. Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
1,620 ft-lbs	12,704 ft-lbs	0.13	1	05-07-07	
885 lbs	5,785 lbs	0.15	1	07-07-00	
Total Load Defl.	L/999 (0.055")	n/a	4	04-06-14	
Live Load Defl.	L/999 (0.038")	n/a	5	04-06-14	
Max Defl.	0.055"	n/a	4	04-06-14	
Span / Depth	10.4	n/a		00-00-00	

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In/In BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCi®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Bearing Supports


	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	625 lbs	0.17	0.08	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	1,005 lbs	0.27	0.13	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS @ O.C., STAGGERED IN TWO ROWS



T-1505130




Dry | 1 span | No cantilevers | 0/12 slope (deg)

BC CALC® Design Report

Report #: 3272
 Name: 38514
 Address: GREEN VALLEY ESTATES
 City, Province, Postal Code: Bradford, ON
 Customer: BAYVIEW WELLINGTON HOMES
 Code reports: CCMC 12472-R

File Name: S42-7C
 Description: Designs\B15
 Specifier:
 Designer: F.C.
 Company: Alps Roof Trusses Inc.
 Misc:



B0 07-08-00 B1

Total Horizontal Product Length = 07-08-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	490 / 0	450 / 0		
B1, 3-1/2"	588 / 0	545 / 0		

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	04-06-00	40	15			03-00-00
2 FLOOR	Unf. Area (lb/ft ²)	L	04-06-00	07-08-00	40	22			04-03-00
3 WALL	Unf. Lin. (lb/ft)	L	00-00-00	07-08-00		60			n/a

Controls Summary

Pos.	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Moment	2,363 ft-lbs	12,704 ft-lbs	0.19	1	04-00-14
End Shear	1,074 lbs	5,785 lbs	0.19	1	06-07-00
Total Load Defl.	L/999 (0.064")	n/a	n/a	4	03-10-05
Live Load Defl.	L/999 (0.033")	n/a	n/a	5	03-10-05
Max Defl.	0.064"	n/a	n/a	4	03-10-05
Span / Depth	9.1	n/a	n/a		00-00-00

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	1,297 lbs	0.34	0.17	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	1,564 lbs	0.42	0.21	Spruce Pine Fir

Notes


Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 O.C., STAGGERED IN TWO ROWS

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCi®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



2-150513



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP

Floor Beam\B16

November-28-14

Dry | 1 span | No cantilevers | 0/12 slope (deg)



BC CALC® Design Report

Project: 13272

Name: 38514

Address: GREEN VALLEY ESTATES

City, Province, Postal Code: Bradford, ON

Customer: BAYVIEW WELLINGTON HOMES

Code reports: CCMC 12472-R

File Name: S42-7C


Description: Designs\B16

Specifier:

Designer: F.C.

Company: Alps Roof Trusses Inc.

Misc:



Total Horizontal Product Length = 06-06-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind	Trib.
B0, 3-1/2"	230 / 0	128 / 0			
B1, 3-1/2"	807 / 0	558 / 0			

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft²)	L	00-00-00	06-06-00	40	15			01-04-00
2 PL B15	Conc. Pt. (lbs)	L	05-08-00	05-08-00	490	450			n/a
STAIRS	Unf. Area (lb/ft²)	L	05-08-00	06-06-00	40	15			06-00-00

Controls Summary

Pos.	Moment	Factored Demand	Resistance	Demand / Resistance	Load Case	Location
End Shear	1,240 lbs	12,704 ft-lbs	0.08	1	04-06-07	
Total Load Defl.	L/999 (0.019")	5,785 lbs	0.21	1	05-05-00	
Live Load Defl.	0.019"	n/a	n/a	4	03-05-07	
Max Defl.	0.019"	n/a	n/a	5	03-05-07	
Span / Depth	7.6	n/a	n/a	4	03-05-07	
					00-00-00	

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	505 lbs	0.13	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	1,908 lbs	0.51	Spruce Pine Fir

Notes


Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 O.C., STAGGERED IN TWO ROWS

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. InVnBC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING™, SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.




T-1505132



BC CALC® Design Report

B-17-14 3272
 Name: 38514
 Address: GREEN VALLEY ESTATES
 City, Province, Postal Code: Bradford, ON
 Customer: BAYVIEW WELLINGTON HOMES
 Code reports: CCMC 12472-R

File Name: S42-7C
 Description: Designs\B17
 Specifier:
 Designer: F.C.
 Company: Alps Roof Trusses Inc.
 Misc:



03-00-00
 Total Horizontal Product Length = 03-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind	Trib.
B0, 3-1/2"	120 / 0	142 / 0			
B1, 3-1/2"	120 / 0	142 / 0			

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	03-00-00	40	15			02-00-00
2 WALL	Unf. Lin. (lb/ft)	L	00-00-00	03-00-00	4	60		1.00 1.15	n/a

Controls Summary

Pos.	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
End Moment	193 ft-lbs	12,704 ft-lbs	0.02	1	01-06-00
End Shear	99 lbs	5,785 lbs	0.02	1	01-01-00
Total Load Defl.	L/999 (0.001")	n/a	n/a	4	01-06-00
Live Load Defl.	L/999 (0")	n/a	n/a	5	01-06-00
Max Defl.	0.001"	n/a	n/a	4	01-06-00
Span / Depth	3.2	n/a	n/a		00-00-00

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In/In BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING™, SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Bearing Supports


	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	358 lbs	0.09	0.05	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	358 lbs	0.09	0.05	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ O.C., STAGGERED IN TWO ROWS



T-1505183



Dry | 1 span | No cantilevers | 0/12 slope (deg)


November-28-14

BC CALC® Design Report



38514
 38514 GREEN VALLEY ESTATES
 Address: GREEN VALLEY ESTATES
 City, Province, Postal Code: Bradford, ON
 Customer: BAYVIEW WELLINGTON HOMES
 Code reports: CCMC 12472-R

File Name: S42-7C
 Description: Designs\B18
 Specifier:
 Designer: F.C.
 Company: Alps Roof Trusses Inc.
 Misc:



B0
 05-02-00
 B1

Total Horizontal Product Length = 05-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	642 / 0	297 / 0		
B1, 3-1/2"	358 / 0	200 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Trib.
1	FLOOR/STAIRS	Unf. Area (lb/ft ²)	L	00-00-00	02-10-00	40	15	06-08-00
2	PLB17	Conc. Pt. (lbs)	L	02-10-00	02-10-00	120	142	n/a
3	FLOOR	Unf. Area (lb/ft ²)	L	02-10-00	05-02-00	40	15	01-04-00

Controls Summary

Pos.	Moment	End Shear	Total Load Defl.	Live Load Defl.	Max Defl.	Span / Depth	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
	1,384 ft-lbs	759 lbs	L/999 (0.015")	L/999 (0.015")	0.015"		12,704 ft-lbs	5,785 lbs	0.11	02-06-01	1
									0.13	01-01-00	1
									n/a	02-06-01	4
									n/a	02-06-01	5
									n/a	02-06-01	4
									n/a	00-00-00	4

Bearing Supports

	Dim. (L x W)	Demand	Demand/Resistance Support	Resistance Member	Material
B0	Wall/Plate	3-1/2" x 1-3/4"	1,334 lbs	0.35	Spruce Pine Fir
B1	Wall/Plate	3-1/2" x 1-3/4"	787 lbs	0.21	Spruce Pine Fir

Notes


Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 O.C., STAGGERED IN TWO ROWS

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In/InBC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



1505184



BC CALC® Design Report

Dry | 1 span | No cantilevers | 0/12 slope (deg)

38514

Address:

GREEN VALLEY ESTATES

City, Province, Postal Code: Bradford, ON

Customer: BAYVIEW WELLINGTON HOMES

Code reports: CCMC 12472-R

File Name: S42-7C


Description: Designs\B19

Specifier:

Designer: F.C.

Company: Alps Roof Trusses Inc.

Misc:



B0

09-08-00

B1

Total Horizontal Product Length = 09-08-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead
B0, 3-1/2"	728 / 0	317 / 0
B1, 3-1/2"	712 / 0	312 / 0

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft ²)	L	00-00-00	05-00-00	40	15			03-03-00
2 PL B16	Conc. Pt. (lbs)	L	05-00-00	05-00-00	230	128			n/a
3 FLOOR	Unf. Area (lb/ft ²)	L	05-00-00	09-08-00	40	15			03-00-00

Controls Summary

Pos.	Moment	End Shear	Total Load Defl.	Live Load Defl.	Max Defl.	Span / Depth
	3,833 ft-lbs	1,205 lbs	L/714 (0.155")	L/999 (0.107")	0.155"	11.6
	12,704 ft-lbs	5,785 lbs	0.46"	n/a	1"	n/a
	0.3	0.21	0.34	n/a	0.15	n/a
	1	1	4	5	4	
	05-00-00	05-00-00	04-10-08	04-10-08	00-00-00	
	01-01-00	05-00-00	04-10-08	04-10-08	00-00-00	
	04-10-08	05-00-00	04-10-08	04-10-08	00-00-00	
	04-10-08	05-00-00	04-10-08	04-10-08	00-00-00	
	05-00-00	05-00-00	04-10-08	04-10-08	00-00-00	

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCi®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM® PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Bearing Supports


	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0	Wall/Plate	3-1/2" x 1-3/4"	1,488 lbs	0.4	Spruce Pine Fir
B1	Wall/Plate	3-1/2" x 1-3/4"	1,457 lbs	0.39	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi is based on all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 O.C., STAGGERED IN TWO ROWS



T-150518J



BC CALC® Design Report

Dry | 1 span | No cantilevers | 0/12 slope (deg)

BC 3272

File Name: S42-7C

Address: GREEN VALLEY ESTATES

City, Province, Postal Code: Bradford, ON

Customer: BAYVIEW WELLINGTON HOMES


Code reports: CCMC 12472-R

Description: Designs\B20

Designer: F.C.

Company: Alps Roof Trusses Inc.

Misc:



06-08-00

B1

Total Horizontal Product Length = 08-08-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
B0, 3-1/2"	520 / 0	281 / 0	L	00-00-00	08-08-00	40	20			
B1, 3-1/2"	520 / 0	281 / 0								

Load Summary

Tag Description	Load Type	Unf. Area (lb/ft²)	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area	(lb/ft²)	L	00-00-00	08-08-00	40	20			03-00-00

Controls Summary

Controls	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Moment	2,198 ft-lbs	12,704 ft-lbs	0.17	1	04-04-00
Shear	848 lbs	5,785 lbs	0.15	1	01-01-00
Total Load Defl.	L/999 (0.075")	n/a	n/a	4	04-04-00
Live Load Defl.	L/999 (0.049")	n/a	n/a	5	04-04-00
Max Defl.	0.075"	n/a	n/a	4	04-04-00
Span / Depth	10.4	n/a	n/a	4	00-00-00

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In BC CALCC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCIO®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Bearing Supports


Support	Dim. (L x W)	Demand	Demand / Resistance Support	Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	1,131 lbs	0.3	0.15	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	1,131 lbs	0.3	0.15	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 @ O.C., STAGGERED IN TWO ROWS



T-1505126



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Floor Beam\B21

November-28-14




BC CALC® Design Report

Dry | 1 span | No cantilevers | 0/12 slope (deg)

B-3272
 Name: 38514
 Address: GREEN VALLEY ESTATES
 City, Province, Postal Code: Bradford, ON
 Customer: BAYVIEW WELLINGTON HOMES
 Code reports: CCMC 12472-R

File Name: S42-7C
 Description: Designs\B21
 Specifier:
 Designer: F.C.
 Company: Alps Roof Trusses Inc.
 Misc:



Total Horizontal Product Length = 04-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Ref. Start	End	Live	Dead	Snow	Wind	Trib.
B0, 3-1/2"	533 / 0	210 / 0			1.00	0.65			
B1, 3-1/2"	533 / 0	210 / 0			40	15		1.00 1.15	06-08-00

Load Summary

Tag Description	Load Type	Ref. Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft²)	L 00-00-00	04-00-00	40	15			06-08-00

Controls Summary

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Moment	833 ft-lbs	12,704 ft-lbs	0.07	1	02-00-00
Shear	487 lbs	5,785 lbs	0.08	1	01-01-00
Total Load Defl.	L/999 (0.005")	n/a	n/a	4	02-00-00
Live Load Defl.	L/999 (0.004")	n/a	n/a	5	02-00-00
Max Defl.	0.005"	n/a	n/a	4	02-00-00
Span / Depth	4.5	n/a	n/a	4	00-00-00

Bearing Supports

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	1,062 lbs	0.28	0.14	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	1,062 lbs	0.28	0.14	Spruce Pine Fir


Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS @ O.C., STAGGERED IN TWO ROWS

Disclosure
 Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In/BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING™, SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



T-1505137




Dry | 1 span | No cantilevers | 0/12 slope (deg)

BC CALC® Design Report

Report #: 3272

Name: GREEN VALLEY ESTATES
Address: BAYVIEW WELLINGTON HOMES
City, Province, Postal Code: Bradford, ON
Customer: CC MC 12472-R
Code reports:

File Name: S42-7C
Description: Designs\B22
Specifier:
Designer: F.C.
Company: Alps Roof Trusses Inc.
Misc:



07-00-00

B1

Total Horizontal Product Length = 07-00-00

Reaction Summary (Down / Uplift) (lbs)

Tag	Description	Load Type	Live		Dead	Snow		Wind	Live	Dead	Snow	Wind	Trib.
			Down	Uplift		Start	End						
B0	3-1/2"	Unf. Area (lb/ft²)	1,050 / 0		752 / 0				1.00	0.65	1.00	1.15	07-06-00
B1	3-1/2"	Unf. Lin. (lb/ft)	1,050 / 0		752 / 0				1.00	0.65	1.00	1.15	n/a

Properties Summary

Pos.	Moment	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
End Shear	3,843 ft-lbs	12,704 ft-lbs	0.3	1	03-06-00	
Total Load Defl.	1,736 lbs	5,785 lbs	0.3	1	01-01-00	
Live Load Defl.	L/999 (0.085")	n/a	n/a	4	03-06-00	
Max Defl.	0.085"	n/a	n/a	5	03-06-00	
Span / Depth	8.3	n/a	n/a	4	00-00-00	

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation. In/BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Bearing Supports


	Dim. (L x W)	Demand	Demand/Resistance Support	Resistance Member	Material	
B0	Wall/Plate	3-1/2" x 1-3/4"	2,515 lbs	0.67	0.34	Spruce Pine Fir
B1	Wall/Plate	3-1/2" x 1-3/4"	2,515 lbs	0.67	0.34	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum total load deflection criteria.
Calculations assume Member is Fully Braced.
Resistance Factor phi has been applied to all presented results per CSA 086.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4
Deflections less than 1/8" were ignored in the results.

User Notes

NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS @ O.C., STAGGERED IN TWO ROWS



Handwritten signature: E-150513f




Dry | 1 span | No cantilevers | 0/12 slope (deg)



BC CALC® Design Report

Report #: 3272
 Name: 38514
 Address: GREEN VALLEY ESTATES
 City, Province, Postal Code: Bradford, ON
 Customer: BAYVIEW WELLINGTON HOMES
 Code reports: CCMC 12472-R

File Name: S42-7C
 Description: Designs\B23
 Specifier:
 Designer: F.C.
 Company: Alps Roof Trusses Inc.
 Misc:



B0 Total Horizontal Product Length = 15-02-00 B1

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,048 / 0	980 / 0		
B1, 3-1/2"	608 / 0	861 / 0		

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1 FLOOR	Unf. Area (lb/ft^2)	L	00-00-00	15-02-00	40	20			01-00-00
2 PL B22	Conc. Pt. (lbs)	L	04-06-00	04-06-00	1,050	752			n/a
WALL	Unf. Lin. (lb/ft)	L	04-06-00	15-02-00		60			n/a

Controls Summary

Pos.	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Moment	10,972 ft-lbs	25,408 ft-lbs	0.43	1	04-06-00
End Shear	2,693 lbs	11,571 lbs	0.23	1	01-01-00
Total Load Defl.	L/310 (0.57")	0.735"	0.77	4	07-02-06
Live Load Defl.	L/649 (0.272")	0.49"	0.55	5	07-00-09
Max Defl.	0.57"	1"	0.57	4	07-02-06
Span / Depth	18:6	n/a	n/a		00-00-00

Bearing Supports


	Dim. (L x W)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0 Wall/Plate	3-1/2" x 3-1/2"	2,798 lbs	0.37	0.19	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 3-1/2"	1,988 lbs	0.26	0.13	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum total load deflection criteria.
 Calculations assume Member is Fully Braced.
 Resistance Factor phi has been applied to all presented results per CSA 086.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Deflections less than 1/8" were ignored in the results.

User Notes



NAIL ONE PLY TO ANOTHER WITH 3 1/2" SPIRAL NAILS
 (2) O.C., STAGGERED IN TWO ROWS



T-1505139



Maximum Spans - A5
Limit States Design (CAN)






Maximum Floor Spans

Live Load = 40 psf; Dead Load = 15 psf
Simple Spans, L/360 Deflection Limit.
5/8" OSB G&N Sheathing

Depth	Series	Bare			1/2" Gypsum Ceiling				
		On Centre Spacing	On Centre Spacing	On Centre Spacing	On Centre Spacing	On Centre Spacing	On Centre Spacing		
9-1/2"	NI-20	12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-40X	15'-1"	14'-2"	13'-9"	N/A	15'-7"	14'-8"	14'-2"	N/A
	NI-60	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-70	17'-1"	16'-3"	15'-4"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-80	17'-3"	16'-3"	15'-5"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-90X	16'-11"	16'-0"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
	NI-40X	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-0"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
11-7/8"	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
	NI-90X	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40X	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
	NI-90X	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
14"	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90X	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A
	NI-40X	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
16"	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90X	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A
	NI-40X	16'-10"	15'-5"	14'-6"	N/A	17'-1"	16'-7"	16'-7"	N/A
	NI-40X	17'-11"	16'-11"	16'-4"	N/A	18'-5"	17'-4"	16'-7"	N/A
	NI-60	18'-2"	17'-1"	16'-6"	N/A	18'-7"	17'-6"	16'-10"	N/A
	NI-70	19'-2"	17'-10"	17'-2"	N/A	19'-7"	18'-3"	17'-7"	N/A
11-7/8"	NI-80	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
	NI-20	19'-6"	18'-1"	17'-5"	N/A	20'-2"	18'-8"	17'-6"	N/A
	NI-40X	21'-0"	19'-6"	18'-8"	N/A	21'-7"	20'-2"	19'-3"	N/A
	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-6"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
	NI-90X	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40X	23'-7"	21'-11"	20'-11"	N/A	24'-3"	22'-7"	21'-7"	N/A
14"	NI-60	24'-0"	22'-3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
	NI-90X	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-2"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90X	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

Depth	Series	Mid-Span Blocking			Mid-Span Blocking and 1/2" Gypsum Ceiling				
		On Centre Spacing	On Centre Spacing	On Centre Spacing	On Centre Spacing	On Centre Spacing	On Centre Spacing		
9-1/2"	NI-20	12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-40X	16'-10"	15'-5"	14'-6"	N/A	17'-1"	15'-5"	14'-6"	N/A
	NI-60	17'-11"	16'-11"	16'-4"	N/A	18'-5"	17'-4"	16'-7"	N/A
	NI-70	18'-2"	17'-1"	16'-6"	N/A	18'-7"	17'-6"	16'-10"	N/A
	NI-80	19'-2"	17'-10"	17'-2"	N/A	19'-7"	18'-3"	17'-7"	N/A
	NI-90X	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
	NI-20	19'-6"	18'-1"	17'-5"	N/A	20'-2"	18'-8"	17'-6"	N/A
	NI-40X	21'-0"	19'-6"	18'-8"	N/A	21'-7"	20'-2"	19'-3"	N/A
11-7/8"	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-6"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
	NI-90X	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40X	23'-7"	21'-11"	20'-11"	N/A	24'-3"	22'-7"	21'-7"	N/A
	NI-60	24'-0"	22'-3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
16"	NI-90X	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-2"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90X	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/360 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf
Simple Spans, L/360 Deflection Limit
5/8" OSB G&N Sheathing

Depth	Series	Bare			1/2" Gypsum Ceiling				
		On Centre Spacing	24"	19.2"	On Centre Spacing	16"	19.2"	24"	
9-1/2"	NI-20	15'-1"	14'-2"	13'-9"	N/A	15'-7"	14'-8"	13'-11"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
11-7/8"	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
14"	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A


Depth	Series	Mid-Span Blocking			Mid-Span Blocking and 1/2" Gypsum Ceiling				
		On Centre Spacing	24"	19.2"	On Centre Spacing	16"	19.2"	24"	
9-1/2"	NI-20	16'-4"	14'-10"	13'-11"	N/A	16'-4"	14'-10"	13'-11"	N/A
	NI-40x	17'-11"	16'-10"	15'-7"	N/A	18'-5"	16'-10"	15'-7"	N/A
	NI-60	18'-2"	17'-1"	16'-1"	N/A	18'-7"	17'-2"	16'-1"	N/A
	NI-70	19'-2"	17'-10"	16'-2"	N/A	19'-7"	18'-3"	17'-7"	N/A
	NI-80	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
	NI-20	19'-6"	17'-10"	16'-9"	N/A	19'-8"	17'-10"	16'-9"	N/A
	NI-40x	21'-0"	19'-6"	17'-9"	N/A	21'-7"	19'-6"	17'-9"	N/A
	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-4"	N/A
11-7/8"	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-5"	19'-6"	N/A	24'-3"	21'-5"	19'-6"	N/A
	NI-60	24'-0"	22'-3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
14"	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-1"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/360 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



www.nordicewp.com

Refer to the Installation Guide for Residential Floors for additional information.
ICMC EVALUATION REPORT 13032-R



WEB HOLE SPECIFICATIONS

- 5. The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
6. Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the longest side of the longest rectangular hole or duct chase opening) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
7. A knockout is not considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
8. Holes measuring 1-1/2 inches or smaller are permitted anywhere in a cantilevered section of a joist. Holes of greater size may be permitted subject to verification.

- 9. A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
10. All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.
11. Limit three maximum size holes per span, of which one may be a duct chase opening.
12. A group of round holes of approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

TABLE 1 LOCATION OF CIRCULAR HOLES IN JOIST WEBS Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf


Table with columns: Joist Depth, Joist Series, Round Hole Diameter (in.), and Minimum Distance from Inside Face of Any Support to Centre of Hole (ft. - in.). Rows include joist depths of 9-1/2", 11-7/8", 14", and 16".

TABLE 2 DUCT CHASE OPENING SIZES AND LOCATIONS Simple Span Only

Table with columns: Joist Depth, Joist Series, Duct Chase Length (in.), and Minimum distance from inside face of supports to centre of opening (ft. - in.). Rows include joist depths of 9-1/2", 11-7/8", 14", and 16".

- 1. Above table may be used for I-joist spacing of 24 inches on centre or less.
2. Hole location distance is measured from inside face of supports to centre of hole.
3. Distances in this chart are based on uniformly loaded joists.
4. The above table is based on the I-joists being used at their maximum spans. The minimum distance as given above may be reduced for shorter spans, contact your local distributor.
5. The above table may be used for I-joist spacing of 24 inches on centre or less.

FIGURE 7 FIELD-CUT HOLE LOCATOR



Knockouts are pre-cored holes provided for the contractor's convenience to install electrical or small plumbing lines. They are 1-1/2 inches in diameter, and are spaced 15 inches on centre along the length of the Joist. Where possible, it is preferable to use knockouts instead of field-cut holes.

Never drill, cut or notch the flange, or over-cut the web. Holes in webs should be cut with a sharp saw. For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Starting the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the Joist.

SAFETY AND CONSTRUCTION PRECAUTIONS



Do not walk on I-joists until fully fastened and braced, or serious injuries can result.




Never stack building materials over unfastened I-joists. Once sheathed, do not over-stress joists with concentrated loads from building materials.

- WARNING: I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.
AVOID ACCIDENTS BY FOLLOWING THESE IMPORTANT GUIDELINES:
1. Brace and nail each I-joist as it is installed, using hangers, blocking at joist ends. When I-joists are applied continuously over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rafter or buckling.
3. Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and lateral restraint at the end of each box. Lap ends of adjoining bracing over at least two I-joists.
4. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bracing.
5. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
6. Never install a damaged I-joist.
7. Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.




PRODUCT WARRANTY

Chariters Chibongwana guarantees that, in accordance with our specifications, Nordic products are free from manufacturing defects in material and workmanship. Furthermore, Chariters Chibongwana warrants that our products, when utilized in accordance with our handling and installation instructions, will meet or exceed our specifications for the lifetime of the structure.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
NI Joists	3,300

The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
1-1/8" Rim Board Plus	8,090

The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




Load bearing wall above shall align vertically with the bearing wall. Other conditions, such as other bearing walls, are not covered by this detail.




Pair of Squash Blocks	Maximum Factored Vertical Load per Pair of Squash Blocks (lbs)	
	3-1/2" wide	5,170
2x Lumber	Maximum Factored Vertical Load per Pair of Squash Blocks (lbs)	
	5-1/2" wide	8,500
1-1/8" Rim Board Plus	Maximum Factored Vertical Load per Pair of Squash Blocks (lbs)	4,300
	Maximum Factored Vertical Load per Pair of Squash Blocks (lbs)	6,500


Transfer load from above to bearing below. Install squash blocks per detail 1d. Match bearing area of blocks above to post below.



NOTE: Unless hanger sides laterally support stiffeners shall be used.




For hanger capacity see hanger manufacturer's recommendations. Verify double I-joist capacity to support concentrated loads.




Flange Width	Material Thickness Required*	Minimum Depth**
3-1/2"	1"	5-1/2"
	1-1/2"	7-1/4"


* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid sawn lumber and wood structural panels conforming to CAN/CSA-C3025 or CAN/CSA-C437 Standard.




Multiple I-joist header with full depth filler block shown. Nordic Lam or SCL headers may also be used. Verify double I-joist capacity to support concentrated loads.




For nailing schedules for multiple beams, see the manufacturer's recommendations.




NOTE: Unless hanger sides laterally support the top flange, bearing stiffeners shall be used.




Do not bevel-cut joist beyond inside face of wall.




NOTE: Unless hanger sides laterally support the top flange, bearing stiffeners shall be used.



NOTE: In some local codes, blocking is prescriptively required in the first joist space (or first and second joist space) next to the starter joist. Where required, see local code requirements for spacing of the blocking.



NOTE: Blocking required at bearing for lateral support, not shown for clarity.




NOTE: All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.125" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.

WEB STIFFENERS

RECOMMENDATIONS:

- A bearing stiffener is required in all engineered applications with factored reactions greater than shown in the I-joist properties table found in the I-joist Construction Guide (C101). The gap between the stiffener and the flange is at the top.
- A bearing stiffener is required when the I-joist is supported in a hanger and the sides of the hanger do not extend up to, and support, the top flange. The gap between the stiffener and flange is at the top.
- A lead stiffener is required at locations where a factored concentrated load greater than 2,370 lbs is applied to the top flange between supports, or in the case of a cantilever, anywhere between the cantilever tip and the support. These values are for standard term load duration, and may be adjusted for other load durations as permitted by the code. The gap between the stiffener and the flange is at the bottom.

WEB STIFFENER INSTALLATION DETAILS



Flange width 2-1/2" or 3-1/2"

Approx. 2"


Approx. 2"

1/8" x 1/4" Gap

(4) 2-1/2" nails, 3" nails required for I-joists with 3-1/2" flange width

No Gap

WEB STIFFENER INSTALLATION DETAILS



CONCENTRATED LOAD (bearing stiffener)

Tight joint No Gap


Gap

END BEARING (bearing stiffener)

Gap

Tight joint No Gap

CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET



Method 1 — SHEATHING REINFORCEMENT ONE SIDE


Rim board or wood structural panel closure (3/4" minimum thickness); attach per detail 1b

2-1/2" nails

3-1/2" min. bearing required

Use nailing per Method 1 with possible face nailing offset by 3"


CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET



Method 2 — SHEATHING REINFORCEMENT TWO SIDES

Use same installation as Method 1 but reinforce both sides of I-joist with sheathing.

RIM BOARD INSTALLATION DETAILS



ATTACHMENT DETAILS WHERE RIM BOARDS ABUT

Rim Board Joint Between Floor Joists

(1) 2-1/2" nail top and bottom (typical)

Rim board joint

2-1/2" toe-nails at 6" o.c. (typical)

Rim Board Joint at Corner

Rim board joint

2-1/2" nails at 6" o.c. (typical)

Rim board


Top or sole plate

30°

C/2


CANTILEVER DETAILS FOR BALCONIES (NO WALL LOAD)

3a) I-JOIST CANTILEVER DETAIL FOR BALCONIES (No Wall Load)



CAUTION: Cantilevers formed this way must be carefully detailed to prevent intrusion into the structure and potential decay of unattached I-joist extensions.


3b) LUMBER CANTILEVER DETAIL FOR BALCONIES (No Wall Load)



Note: This detail is applicable to cantilevers supporting a maximum specified uniform live load of 60 psf.

CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)


4a) Method 1 — SHEATHING REINFORCEMENT ONE SIDE



Method 2 — SHEATHING REINFORCEMENT TWO SIDES
 - Use same installation as Method 1 but reinforce both sides of I-joist with sheathing.
 - Use nailing pattern shown for Method 1 with opposite face nailing offset by 3".


Note: Condition without plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Drip should match the full height of the joist. Nail with 2-1/2" nails at 6" o.c. top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

4b) Alternate Method 2 — DOUBLE I-JOIST



Block I-joists together with filler blocks for the full length of the reinforcement. For I-joist flange widths greater than 3 inches place an additional row of 3" nails along the centerline of the reinforcing panel from each side. Clinch when possible.

FIGURE 4 (continued)



For hip roofs with the jack trusses running parallel to the ridge beam, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

CANTILEVER REINFORCEMENT METHODS ALLOWED


JOIST SPAN (ft)	ROOF LOADING (UNIFORM)											
	11	12	13	14	15	16	17	18	19	20	21	22
11	N	N	N	N	N	N	N	N	N	N	N	N
12	N	N	N	N	N	N	N	N	N	N	N	N
13	N	N	N	N	N	N	N	N	N	N	N	N
14	N	N	N	N	N	N	N	N	N	N	N	N
15	N	N	N	N	N	N	N	N	N	N	N	N
16	N	N	N	N	N	N	N	N	N	N	N	N
17	N	N	N	N	N	N	N	N	N	N	N	N
18	N	N	N	N	N	N	N	N	N	N	N	N
19	N	N	N	N	N	N	N	N	N	N	N	N
20	N	N	N	N	N	N	N	N	N	N	N	N
21	N	N	N	N	N	N	N	N	N	N	N	N
22	N	N	N	N	N	N	N	N	N	N	N	N

1. N = No reinforcement required.
 2 = NI reinforced with 3/4" wood structural panel on one side only.
 3 = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
 X = If a deeper joist or closer spacing meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, the wall load will be based on 50 psf maximum with window or door openings.

4. For conventional roof construction using ridge beam, the Roof Truss Span column above is equivalent to the ridge beam. When the roof is framed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a ridge beam were used.
 5. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.


BRICK CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

5a) SHEATHING REINFORCEMENT




Note: Condition without plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c. top and bottom flange. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

5b) SET-BACK DETAIL




Note: Provides full depth blocking between joists over support (not shown for clarity). Attach I-joist to plate at all supports per detail 1b. 3-1/2" minimum I-joist bearing required.

5c) SET-BACK CONNECTION



Note: Verify girder joist capacity if the back span exceeds the joist spacing. Attach double I-joist per detail 1b, if required.

FIGURE 5 (continued)



For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST SPAN (ft)	ROOF LOADING (UNIFORM)											
	11	12	13	14	15	16	17	18	19	20	21	22
11	N	N	N	N	N	N	N	N	N	N	N	N
12	N	N	N	N	N	N	N	N	N	N	N	N
13	N	N	N	N	N	N	N	N	N	N	N	N
14	N	N	N	N	N	N	N	N	N	N	N	N
15	N	N	N	N	N	N	N	N	N	N	N	N
16	N	N	N	N	N	N	N	N	N	N	N	N
17	N	N	N	N	N	N	N	N	N	N	N	N
18	N	N	N	N	N	N	N	N	N	N	N	N
19	N	N	N	N	N	N	N	N	N	N	N	N
20	N	N	N	N	N	N	N	N	N	N	N	N
21	N	N	N	N	N	N	N	N	N	N	N	N
22	N	N	N	N	N	N	N	N	N	N	N	N

1. N = No reinforcement required.
 2 = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
 X = If a deeper joist or closer spacing meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, the wall load will be based on 50 psf maximum with window or door openings.


4. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a ridge beam were used.
 5. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

WEB HOLES

RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

- The distance between the inside edge of the support and the centerline of any duct chase opening shall be in compliance with the requirements of Table 1 or 2, respectively.
- Joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.
- Joist top and bottom flanges should be centered on the middle of the web.
- The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the hole or opening and the adjacent I-joist flange.
- The sides of square holes or longest sides of rectangular holes shall not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
- Where more than one hole is necessary, the distance between adjacent hole centerlines shall be at least 12 inches. The distance between the centerline of the side of the largest square hole or duct chase opening and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
- A knockout is not considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
- Holes measuring 1-1/2 inches or smaller shall be permitted anywhere in a cantilevered section of a joist. Holes of greater size may be permitted subject to verification.
- A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
- All holes and duct chase openings shall be cut in a workmanlike manner in accordance with the restrictions listed above and as illustrated in Figure 7.
- Limit three maximum size holes per span, of which one may be a duct chase opening.
- A group of round holes at approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

FIGURE 7
FIELD-CUT HOLE LOCATOR



A knockout is NOT considered a hole, may be utilized wherever it occurs and may be ignored for purposes of calculating minimum distances between holes.

Knockouts are preformed holes provided for the contractor's convenience to install a joist. They are 1-1/2 inches in diameter, and are spaced 12 inches on center along the length of the I-joist. Where possible, it is preferable to use knockouts instead of field-cut holes.



For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners of rectangular holes by drilling a 1/4-inch diameter hole in each of the four corners and then making the cut between the holes is another good method to minimize damage to the I-joist.

TABLE 1
LOCATION OF CIRCULAR HOLES IN JOIST WEBS

Depth	Minimum Distance from Support (Center of Support to Center of Hole)		Minimum Distance from Support (Center of Support to Edge of Hole)
	15 psf and Live Loads up to 40 psf	40 psf and Live Loads up to 15 psf	
12"	12"	12"	12"
10"	10"	10"	10"
8"	8"	8"	8"
6"	6"	6"	6"
4"	4"	4"	4"
2"	2"	2"	2"

- Above table may be used for joist spacing of 24 inches on center or less.
- Hole location distance 1, measured from inside face of support to center of hole.
- Distance in this chart are based on uniformly loaded joist.

OPTIONAL:

The above table is based on the I-beams used at their maximum span. If the I-beams are placed at less than their full maximum span (see Manufacturer's literature for maximum span), the minimum distance from the centerline of the hole to the face of any support (D) as given above may be reduced as follows:

$$D_{reduced} = D \left(\frac{L_{actual}}{L_{SF}} \right)$$

Where:

- $D_{reduced}$ = Distance from the inside face of any support to center of hole, reduced for less than maximum span applications.
- D = Span Adjustment factor given in the above table.
- L_{actual} = The actual measured span distance between the inside faces of supports (ft).
- L_{SF} = Span Adjustment factor given in the above table.
- F = Load is greater than 1, use 1 in the above calculation for L_{SF} .

TABLE 2
DUCT CHASE OPENING SIZES AND LOCATIONS — Simple Span Only

Depth	Minimum Distance from Support (Center of Support to Center of Opening)		Minimum Distance from Support (Center of Support to Edge of Opening)
	15 psf and Live Loads up to 40 psf	40 psf and Live Loads up to 15 psf	
12"	12"	12"	12"
10"	10"	10"	10"
8"	8"	8"	8"
6"	6"	6"	6"
4"	4"	4"	4"
2"	2"	2"	2"

- Above table may be used for joist spacing of 24 inches on center or less.
- Duct chase opening location distance is measured from inside face of supports to center of opening.
- Distance in this chart are based on uniformly loaded floor joists that meet the span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. For other applications, contact your local distributor.
- Distance from the centerline of the hole to the face of any support (D) as given above may be reduced as follows:

INSTALLING THE GLUED FLOOR SYSTEM

- Wipe any mud, dirt, water, or ice from I-joist flanges before gluing.
- Score a chalk line across the I-joists saw feet in from the wall for panel edge alignment and as a boundary for spreading glue.
- Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from the glue manufacturer.
- Lay the first panel with tongue side to the wall, end to end in places. This protects the tongue of the next panel from damage when tapping the place with a block and sheetrock.
- Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-joist. Apply glue in a winding pattern on wide areas, such as with double I-joists.
- After the first row of panels is in place, spread glue in the groove of one or two panels at a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying a thinner line (1/8 inch) then use an I-joist flange.
- Put the second row of panels into place, using a block to protect groove edges.
- Stagger end joints in each succeeding row of panels. A 1/8-inch space between all end joints and 1/8-inch at all edges, including T&G edges, is recommended. Use a spacer tool or an 2-1/2" common nail to assure accurate and consistent spacing.
- Complete all nailing of each panel before glue sets. Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 2" ring- or screw-shank nails for panels 3/4-inch thick or less, and 2-1/2" ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for atypical construction. The glue block can be walked on right away and will carry construction loads without damage to the glue bond.

FASTENERS FOR SHEATHING AND SUBFLOORING(1)

Minimum Joist Spacing (inches)	Minimum Sheathing Thickness (inches)	Minimum Subflooring Thickness (inches)	Minimum Fastener Spacing (inches)
16"	5/8"	2"	1-3/4"
20"	3/8"	2"	1-3/4"
24"	3/4"	2"	1-3/4"


- Fasteners of sheathing and subflooring shall conform to the above table.
- Staples shall not be less than 1/16-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
- Flooring screws shall not be less than 1/8-inch in diameter.
- Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
- Use only adhesive conforming to CAN/CSG 21.26 Standard, Adhesives for Field-Gluing Plywood to Lumber Framing, for Floor Systems, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues; check with panel manufacturer.

Ref.: NRC-CNRC, National Building Code of Canada 2010, Table 9.23.3.5.


IMPORTANT NOTE:
Floor sheathing must be field glued to the I-joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-joist spans must be verified with your local distributor.

RIM BOARD INSTALLATION DETAILS

(6a) ATTACHMENT DETAILS WHERE RIM BOARDS ABUT




(6b) TOE-NAIL CONNECTION AT RIM BOARD



PRODUCT WARRANTY

Chemical Company warrants that its adhesive will meet or exceed the performance specifications set forth in the product literature. Chemical Company is not responsible for any damage or loss resulting from the use of its adhesive. For more information, contact your local distributor.



Distributed by:




INSTALLING NORDIC I-JOISTS

1. Before laying out floor system components, verify that I-joist flange widths match hanger widths. If not, contact your supplier.
2. Except for cutting to length, I-joist flanges should never be cut, drilled, or notched.
3. Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple joists must be level.
5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings.
6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement.
7. Leave a 1/16-inch gap between the I-joist end and a header.
8. Concentrated loads greater than those that can normally be expected in residential construction should only be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment or tall bookshelves, and other heavy loads that are concentrated loads from the top of the I-joist. Or, attach the load to blocking that has been securely fastened to the I-joist webs.
9. Never install I-joists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or I-joist blocking panels.
11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (cripple members) to transfer gravity loads through the floor system to the wall or foundation below.
12. Due to shrinkage, common framing lumber set on edge may never be used as blocking or rim boards. I-joist blocking panels or other engineered wood products – such as rim board – must be cut to fit between the I-joists, and an I-joist-compatible depth selected.
13. Provide appropriate lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly support the bottom flange of all cantilevered I-joists at the end support next to the confflure station. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used.
14. If square-edge panels are used, edges must be supported between I-joists with 2x4 blocking. Give panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed.
15. Nail blocking. Squash walls installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.



SAFETY AND CONSTRUCTION PRECAUTIONS

- WARNING**
- I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.
- Avoid Accidents by Following these Important Guidelines:**
1. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-briding at joist ends. I-joists are applied continuously until the entire floor system is planned or final location.
 2. When the lifting is completed, the floor sheathing will provide lateral bracing. The temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
 - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.
 - Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
 3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with cleare panels, rim board, or cross-briding.
 4. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
 5. Never install a damaged I-joist.
 - Never stack building materials over untreated I-joists.
 - Once sheathed, do not over-stress I-joist with loads from building materials.
- Improper storage or installation failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole size and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.**



STORAGE AND HANDLING GUIDELINES

1. Bundle wrap can be slippery when wet. Avoid walking on wrapped bundles.
2. Store, stack, and handle I-joists vertically and level only.
3. Always stack and handle I-joists in the upright position only.
4. Do not store I-joists in direct contact with the ground and/or flange.
5. Protect I-joists from weather, and use spacers to separate bundles.
6. Bundled ends should be kept intact until time of installation.
7. When handling I-joists with a crane on the job site, take a few simple precautions to prevent damage to the I-joist and injury to your work crew.
 - Pick I-joists in bundles as shipped by the supplier.
 - Orient the bundles so that the webs of the I-joists are vertical.
 - Pick the bundles at the 5th points, using a spreader bar if necessary.
8. Do not handle I-joists in a horizontal orientation.
9. NEVER USE OR TRY TO REPAIR A DAMAGED I-JOIST.





FIGURE 1 TYPICAL NORDIC I-JOIST FLOOR FRAMING AND CONSTRUCTION DETAILS



Some framing requirements such as erection bracing and blocking panels have been omitted for clarity.

All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122 dia.) common splices may be substituted for 2-1/2" (0.125" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.

1b

Blocking Panel on Rim Joist

Blocking Panel on Rim Joist	Maximum Factored Uniform Vertical Load (plf)
1-1/8" Rim Board Plus	3,300

*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.

1c

Attach rim joist to floor joist with one nail at top and bottom. Nail must provide 1 inch minimum penetration into floor joist. Top-nailing may be used.

Attach rim joist to floor joist	Maximum Factored Uniform Vertical Load (plf)
1-1/8" Rim Board Plus	6,500
1-1/8" Rim Board Plus	4,300
1-1/8" Rim Board Plus	6,600

Provide lateral bracing per detail 1e, 1b, or 1c.

MAXIMUM FLOOR SPANS


- Maximum clear spans applicable to simple-span or multiple-span residential floor construction, with a design live load of 40 psf and a maximum deflection limit shall be based on the factored loads of 1.5D + 1.2L. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of L/480. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- Spans are based on a composite floor with glued-rodled oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a fast spacing of 19.2 inches or 24 inches on center. The sheathing shall be installed in accordance with the manufacturer's instructions. OSB sheathing shall meet the requirements given in CGCS 7.2.2. Standard. No concrete topping or bridging element was assumed. Increased spans may be achieved with the use of gypsum and/or a row of blocking at mid-span.
- Minimum bearing length shall be 1.34 inches for the end bearings, and 3-1/2 inches for the intermediate bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniform loads, an engineering analysis may be required based on the use of the design properties.
- Tables are based on United States Design per CAN/CSA C084-09 Standard, and NBC 2010.
- SI units conversion: 1 inch = 25.4 mm
1 foot = 0.305 m

MAXIMUM FLOOR SPANS FOR NORDIC I-JOISTS SIMPLE AND MULTIPLE SPANS

Span Depth	Joist Depth	Simple Span		Multiple Span	
		Design Depth	On-Center Spacing	Design Depth	On-Center Spacing
10'-0"	NL40	12'-0"	14'-0"	12'-0"	14'-0"
	NL40	14'-0"	16'-0"	14'-0"	16'-0"
11'-0"	NL40	13'-0"	15'-0"	13'-0"	15'-0"
	NL40	15'-0"	17'-0"	15'-0"	17'-0"
12'-0"	NL40	14'-0"	16'-0"	14'-0"	16'-0"
	NL40	16'-0"	18'-0"	16'-0"	18'-0"
13'-0"	NL40	15'-0"	17'-0"	15'-0"	17'-0"
	NL40	17'-0"	19'-0"	17'-0"	19'-0"
14'-0"	NL40	16'-0"	18'-0"	16'-0"	18'-0"
	NL40	18'-0"	20'-0"	18'-0"	20'-0"
15'-0"	NL40	17'-0"	19'-0"	17'-0"	19'-0"
	NL40	19'-0"	21'-0"	19'-0"	21'-0"
16'-0"	NL40	18'-0"	20'-0"	18'-0"	20'-0"
	NL40	20'-0"	22'-0"	20'-0"	22'-0"
17'-0"	NL40	19'-0"	21'-0"	19'-0"	21'-0"
	NL40	21'-0"	23'-0"	21'-0"	23'-0"
18'-0"	NL40	20'-0"	22'-0"	20'-0"	22'-0"
	NL40	22'-0"	24'-0"	22'-0"	24'-0"
19'-0"	NL40	21'-0"	23'-0"	21'-0"	23'-0"
	NL40	23'-0"	25'-0"	23'-0"	25'-0"
20'-0"	NL40	22'-0"	24'-0"	22'-0"	24'-0"
	NL40	24'-0"	26'-0"	24'-0"	26'-0"

I-JOIST HANGERS

- Hangers shown illustrate the three most commonly used metal hangers to support I-joists.
- All nailing must meet the hanger manufacturer's recommendations.
- Hangers should be selected based on the joist depth, flange width and load capacity based on the maximum spans.
- Web stiffeners are required when the sides of the hangers do not laterally brace the top flange of the I-joist.




WEB STIFFENERS


RECOMMENDATIONS:

- A bearing stiffener is required in all engineering applications with factored reactions greater than shown in the I-joist properties table found in the Joist Construction Guide (JC17). The gap between the stiffener and the flange is at the top.
 - A bearing stiffener is required when the I-joist is supported in a hanger and the sides of the hanger do not extend up to, and support, the top flange. The gap between the stiffener and flange is at the top.
 - A lead stiffener is required at locations where a factored concentrated load greater than 2,370 lbs is applied to the top flange from supports, or in the case of a spanner, anywhere between the centerline and the end of the hanger. Lead stiffeners shall extend for the full length of the hanger and the stiffener. The gap between the stiffener and the flange is at the bottom.
- SI units conversion: 1 inch = 25.4 mm

FIGURE 2
WEB STIFFENER INSTALLATION DETAILS



NORDIC I-JOIST SERIES



Charmier Chibougemeu Ltd. harvests its own trees, which enables Nordic products to adhere to strict quality control procedures through the Nordic manufacturing process. Every phase of the operation, from logging to the finished product, reflects our commitment to quality.

Nordic Engineered Wood I-joists use only finger-jointed solid spruce or fir lumber in their flanges, ensuring consistent quality, superior strength and longer span carrying capacity.




CONCRETE/SLAB SUPPORT TABLE


Span Depth	Joist Depth	Design Depth	On-Center Spacing
10'-0"	NL40	12'-0"	14'-0"
	NL40	14'-0"	16'-0"
11'-0"	NL40	13'-0"	15'-0"
	NL40	15'-0"	17'-0"
12'-0"	NL40	14'-0"	16'-0"
	NL40	16'-0"	18'-0"
13'-0"	NL40	15'-0"	17'-0"
	NL40	17'-0"	19'-0"
14'-0"	NL40	16'-0"	18'-0"
	NL40	18'-0"	20'-0"
15'-0"	NL40	17'-0"	19'-0"
	NL40	19'-0"	21'-0"
16'-0"	NL40	18'-0"	20'-0"
	NL40	20'-0"	22'-0"
17'-0"	NL40	19'-0"	21'-0"
	NL40	21'-0"	23'-0"
18'-0"	NL40	20'-0"	22'-0"
	NL40	22'-0"	24'-0"
19'-0"	NL40	21'-0"	23'-0"
	NL40	23'-0"	25'-0"
20'-0"	NL40	22'-0"	24'-0"
	NL40	24'-0"	26'-0"




11




11a




11b




11c




11d




11e




11f




11g




11h




11i



11j



11k



BACKER BLOCKS (Blocks must be long enough to permit required nailing without splitting)

Flange Width	Material Thickness Required*	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid wood lumber and wood structural panels conforming to manufacturer's specifications. ** For face-mount hangers use net joist depth minus 3.1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4".

BACKER BLOCKS (Blocks must be long enough to permit required nailing without splitting)

Flange Width	Material Thickness Required*	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid wood lumber and wood structural panels conforming to manufacturer's specifications. ** For face-mount hangers use net joist depth minus 3.1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4".

FILLER BLOCK REQUIREMENTS FOR DOUBLE I-JOIST CONSTRUCTION

Flange Size	Joist Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2"	2-1/8" x 6"
3-1/2" x 1-1/2"	11-7/8"	2-1/8" x 8"
	14"	2-1/8" x 10"
3-1/2" x 1-1/2"	16"	2-1/8" x 12"
	18"	3" x 6"
3-1/2" x 1-1/2"	20"	3" x 8"
	22"	3" x 10"
3-1/2" x 1-1/2"	24"	3" x 9"
	26"	3" x 11"

Notes:

- Support back of I-joist web during nailing to prevent damage to web/flange connection.
- Leave a 1/8 to 1/4-inch gap between top filler block and bottom of top I-joist flange.
- Filler block is required between joists for full length of spans.
- Nail joists together with two rows of 3" nails at 12 inches o.c. clinched when possible on each side of the double I-joist. Total of four nails per foot required. If nails can be clinched, only two nails per foot are required.
- The maximum factored load that may be applied to one end of a double joist shall be 600 lbs/ft. Verify double I-joist capacity.