It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Town of BRADFORD / WEST GWILLIMBURY.

NOTE W1 PROVIDE 2-15M FULL HEIGHT

VERTICAL REBARS EACH SIDE OF OPENING + 2-15M HORIZ. REBARS BELOW AND

EXTEND 24" BEYOND OPENING PROVIDE 3" CLEAR COVER FROM SOIL SIDE

S. J. BOYD

STAIR/SUNKEN AREAS


(RIGID or SPRAY FOAM). -2"x4" @ 16"o.c. w/ R12 BATT

BEARING.

-2" (R10) CONTINUOUS INSULATION

INSULATION & 1/2" DRYWALL FINISH
-EXTEND EXTERIOR WALL FOOTING TO

SUPPORT 2"x4" WALL WHERE LOAD



BASEMENT FLOOR PLAN 'A'

GROUND FLOOR AREA
SECOND FLOOR AREA
SUBTOTAL
DEDUCT ALL OPENINGS
TOTAL NET AREA

COVERAGE W/O PORCH

1144.1 SF
1616.8 SF
2760.9 SF
0 SF
2761 SF
256.5 m2

COVERAGE W/PORCH

AREA CALCULATIONS

ELEV. A

150.4 m2

1773.0 SF

164.7 m2

NOTE: SPACE ALL FLOOR JOISTS © 12" O.C. UNDER ALL CERAMIC TILE AREAS.

NOTE: FLOOR FRAMING INFO REFER TO SHOP DRAWINGS FOR ALL TRUSS—JOIST INFORMATION AND DETAILS. UNLESS OTHERWISE NOTED.

NOTE: ALL LVL'S SUPPORTING FLOOR LOADS ARE TO BE SPECIFIED BY FLOOR TRUSS MANUFACTURER.

NOTE J1: PROVIDE SOLID BLOCKING 24" O.C. WHERE FLOOR JOISTS ARE PARALLEL TO FOUNDATION WALL (TYP.)


١	9				The undersigned has reviewed and takes responsibility for this design	Г
	8				and has the qualifications and meets the requirements set out in the Ontario Building Code to be a Designer.	İ
	7				qualification information	İ
	6				Wellington Jno-Baptiste / 1/30/123/6 25591	İ
	5				nume signature bon	İ
	4				registration information VA3 Design Inc. 42658	ı
	3	REVISED AS PER ENG'S COMMENTS	JAN 21-21	RC		١.
	2	REVISED AS PER ROOF / FLOOR LAYOUTS	DEC 17-20	RC	Contractor must verify all dimensions on the job and report any discrepancy to the Designer before proceeding with the work. All	2
	1	ISSUED FOR CLINET REVIEW	NOV 06-20	RC	drawings and specifications are instruments of service and the property of the Designer which must be returned at the completion of the work.	t
	nο	description	date	hv	Drawings are not to be scaled	1

	TAG
	\
1	
١	
3	DESIGN
	255 Consumers Rd Suite 120
ı	Toronto ON M2J 1R4
ı	t 416.630.2255 f 416.630.4782

		BAY	S42-18 RIDEAU 18						
	project name GREEN	VALLEY	ESTATES		BRADFORD,	onicipality ON.			project r 1304
120	date OCT. 2020				BASEMENT	PLAN	ELEVATIO	N 'A'	drawing no.
. 4782	drawn by		checked by	scale 3/16" - 1'-0"		1304	5_\$42_18 (1)	file name	1

It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Town of BRADFORD / WEST GWILLIMBURY.




<u>ROOF NOTE R1</u> 2"x8" @ 16" O.C. P.T. W/ 2"x4" @ 12" O.C. DIAGONALLY CUT CROSS PURLINS W/ 5/8" EXTERIOR
GRADE SHEATHING W/ SINGLE PLY ROOF MEMBRANE

<u>NOTE:</u> FLOOR FRAMING INFO REFER TO SHOP DRAWINGS FOR ALL TRUSS-JOIST INFORMATION AND DETAILS. UNLESS OTHERWISE NOTED.

<u>NOTE:</u> SPACE ALL FLOOR JOISTS @ 12" O.C. UNDER ALL CERAMIC TILE AREAS.

NOTE: ALL LVL'S SUPPORTING FLOOR LOADS ARE TO BE SPECIFIED BY FLOOR TRUSS MANUFACTURER.



date t

	_
n he	\ \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
5591	V/ À]
BCIN	<u> </u>
2658	DESIGN
	255 Consumers Rd Suite 120
erty	Toronto ON M2J 1R4
vork.	t 416.630.2255 f 416.630.478


		BAY	VIEW	WEILLING	ΓΟΝ		S42-18 RIDEAU 18				
ı	project name GREEN	VALLEY	ESTATES	BRA	ADFORD,	onicipality ON.			pr 1		
ı	date OCT. 2020			GROUND	FLOOR	PLAN	ELEVATION	'A'	drawing		
	drawn by		checked by RC	3/16" = 1'-0"		1304	file 15-S42-18 (LOT4	name 102B)	2		

S. J. BOYD

project no 13045

It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Town of BRADFORD / WEST GWILLIMBURY.



SECOND FLOOR PLAN 'A'


GRAB BAR NOTE:

STUD WALL REINFORCEMENT FOR FUTURE
GRAB BARS IN MAIN BATHROOM

GRAB BARS IN MAIN BATHROOM.


REINFORCEMENT OF STUD WALLS SHALL BE INSTALLED ADJACENT TO WATER CLOSETS AND SHOWER OR BATHTUB IN MAIN BATHROOM PER OBC. DIV. B-9.5.2.3. REFER TO FOLLOWING SECTIONS FOR THE FIXTURES LISTED. WATER CLOSET: 3.8.3.8.(3)(a) & 3.8.3.8.(3)(c). SHOWER 3.8.3.13.(2)(g). BATHTUB 3.8.3.13.(4)(e). FREE STANDING BATHTUB EXCLUDED. SEE DETAILS PROVIDED.

NOTE: REFER TO ROOF TRUSS MANUF. FOR ROOF TRUSS LAYOUTS & BEAM SIZES.



-	9 8 7 6				The undersigned has reviewed and takes responsibility for this design and has the qualifications and meets the requirements set out in the Ontario Building Code to be a Designer. qualification information Wellington Jno-Baptiste	VAR		BAYVIEW	WEILLINGTON	S42- RIDEAU	
	5				name signaty'e BCIN registration information VA3 Design Inc. 42658	DECLON	greet name	VALLEY ESTATE		on.	project no. 13045
	-		JAN 21-21 DEC 17-20	DO.	Contractor must varify all dimensions on the ich and assert any	255 Consumers Rd Suite 120 Toronto ON M2J 1R4	date OCT. 202) checked by	SECOND FLOOR	PLAN ELEVATION 'A	
n	\rightarrow	ISSUED FOR CLINET REVIEW description	NOV 06-20 date	RC		t 416.630.2255 f 416.630.4782 va3design.com		RC	3/16" = 1'-0" 045.BW\units\42'\13045-S42-18 (lot402B).dwg	13045-S42-18 (LOT402B)	l 3

All drawings specifications, related documents and design are the copyright property of VA3 DESIGN. Reproduction of this property in whole or in part is strictly prohibited without VA3 DESIGN's written permission.





UNINSULATED OPENINGS (PER OBC. SB-12,3.1.1(7)) ENERGY EFFICIENCY - OBC SB12 It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot. S42-18 ELEVATION A WALL AREA S.F. OPENING S.F. PERCENTAGE ELEVATION 1892 S.F. 412.25 S.F. **21.79** % FRONT LEFT SIDE 60.67 S.F. **9.18** % RIGHT SIDE 619 S.F. 130.44 S.F. **21.07** % 1745 S.F. 228.89 S.F. 13.12 % REAR This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Town of BRADFORD / WEST GWILLIMBURY. * OPENINGS OMITTED AS PER SB-12 3.1.1.9(4) MAX 19.9 S.F. REFER TO ELEVATION FOR LOCATION 19.9 S.F. TOTAL SQ. FT. **4917.00** S.F. **812.35** S.F. **16.52** % TOTAL SQ. M. **456.80** S.M. **75.47** S.M. **16.52** % 1'-0" - PREFIN. METAL ROOF W/ RAISED SEAMS (TYP.) 8:12 8:12 MEAN OF ROOF 8:12 ASPHALT SHINGLES (TYP.) — _{*} 8:12 8:12 U/S OF SOFFIT EXTENDED HEEL TRUSSES EXTENDED HEEL TRUSSES PREFIN. ALUM. R.W.L., -U/S OF SOFFIT FASCIA, GUTTER & VENTED SOFFIT (TYP.) TOP OF PLATE 1"x6" ALUM. CLAD 10" PRECAST CONC. HEADER -TOP OF WINDOW FRIEZE BD. (TYP.) W/ 1/2" PROJ. (TYP.) - PREFIN. ALUM. PANEL (TYP.) 4" PRECAST CONC. SILL W/ 1/2" PROJ. (TYP.) 6" PREFIN. MTL. FLASHING, FIN SECOND FLOOR W/ CAULKING TO MATCH BRICK COLOUR (TYP.) PREFIN. METAL ROOF W/ 4:12 RAISED SEAMS (TYP.) TOP OF TRANSOM TOP OF WINDOW 18" HIGH TRANSOM FG FACE BRICK (TYP.) -- CONT. PRECAST CONC. SILL W/ 1/2" PROJ. (TYP.) FIN GROUND FLOOR - STONE VENEER (TYP.) FIN GRADE ⊥−fin. Sünken- FOYER ESTABLISH GRADE 20"x20" MASONRY PIER W/ PRECAST CONC. CAP AT TOP & 10"x10" PREFIN. ALUM. CLAD STRAPPED TO 3-2x6 WOOD-POST ANCHORED TO PORCH SLAB W/ GALV. METAL SHOE SADDLE (TYP.) GLASS GUARD WITH METAL TOP OF BASEMENT SLAB RAILING (TYP.) FRONT ELEVATION 'A' 2-15M HORIZONTAL REBARS 4" BELOW WINDOW AND EXTEND 24" BEYOND OPENING 2-15M VERTICAL REBARS EITHER SIDE OF OPENING 3" CLEAR COVER FROM SOIL SIDE S. J. BOYD S42-18 BAYVIEW WEILLINGTON Wellington Jno-Baptiste WBoffes 2559 RIDEAU 18 GREEN VALLEY ESTATES BRADFORD, ON. DESIGN REVISED AS PER ENG'S COMMENTS Contractor must verify all dimensions on the job and report any discrepancy to the Designer before proceeding with the work. All drawings and specifications are instruments of service and the property of the Designer which must be returned at the completion of the work. Drawings are not to be scaled. FRONT ELEVATION 'A' 255 Consumers Rd Suite 120 Toronto ON M2J 1R4 : 416.630.2255 f 416.630.4782 va3design.com REVISED AS PER ROOF / FLOOR LAYOUTS DEC 17-20 checked by scale

RC 3/16" = 1'-0"

RCHIVE\WORKING\2013\13045.BW\units\42\13045-S42-18 (lot4028) 13045-S42-18 (LOT402B) 2B).dwg - Thu - Jan 21 2021 - 10:28 AM ISSUED FOR CLINET REVIEW date b

All drawings specifications, related documents and design are the copyright property of VA3 DESIGN. Reproduction of this property in whole or in part is strictly prohibited without VA3 DESIGN's written per





CONSTRUCTION NOTES (Unless otherwise noted) ALL CONSTRUCTION TO ADHERE TO THESE PLANS AND SPECIFICATIONS AND TO CONFORM TO THE ONTARIO
BUILDING CODE AND ALL OTHER APPLICABLE CODES AND AUTHORITIES HAVING JURISDICTION THESE REQUIREMENTS ARE TO BE TAKEN AS MINIMUM SPECIFICATIONS. ONT. REG. 332/12-2012 OBC

ROOF CONSTRUCTION NO.210 (10.25kg/m2) ASPHALT SHINGLES, 10mm (3/8") PLYWOOD SHEATHING WITH "H" CLIPS. APPROVED WOOD TRUSSES @ 600mm (24") O.C. MAX. APPROVED EAVES PROTECTION TO EXTEND 900mm (3'-0' FROM EDGE OF ROOF AND MIN. 300mm (12") BEYOND INNER FACE OF EXTERIOR WALL. (EAVES PROTECTION NOT REQ'D FOR ROOF SLOPES 8:12 OR GREATER) 38x89 (2"x4") TRUSS BRACING @ 1830mm (6'-0") O.C. AT BOTTOM CHORD, PREFIN, ALUM, EAVESTROUGH, FASCIA, RWL & VENTED SOFFIT. PROVIDE ICE & WATER SHIELD TO ALL ROOF/WALL SURFACES SUSCEPTIBLE TO ICE DAMMING. ROOF SHEATHING TO BE FASTENED 150 (6") c/c ALONG EDGES & INTERMEDIATE SUPPORTS WHEN TRUSSES SPACED GREATER THAN 406 (16"). ATTIC VENTILATION 1:300 OF INSULATED CEILING AREA WITH MIN. 25% AT EAVES & MIN. 25% AT RIDGE (OBC 9.19.1.2.).

FRAME WALL CONSTRUCTION (2"x6") (SB-12-TABLE 3.1.1.2.A) SIDING AS PER ELEV., 19x38 (1"x2") VERTICAL WOOD FURRING, CONTIN. SHEATHING MEMBRANE, 9.5mm (3/8") EXT. TYPE SHEATHING, 38x140 (2"x6") STUDS @ 400mm (16") O.C., RSI 3.87 (R22) INSULATION AND APPR. VAPOUR BARRIER AND APPR. CONTIN. AIR BARRIER, 13mm (1/2") INT. DRYWALL FINISH. SIDING TO BE MIN. 200mm (8") ABOVE FINISH GRADE. REFER TO OBC SB-12, CHAPTER 3 FOR REQUIRED MINIMUM THERMAL INSULATION REQUIREMENTS.

 $\langle 2A. \rangle$ RESERVED

FRAME WALL CONSTRUCTION (2"x4")— GARAGE WALLS SIDING AS PER ELEV., 19x38 (1"x2") VERTICAL WOOD FURRING, CONTIN. SHEATHING MEMBRANE, 9.5mm (3/8") EXT. TYPE SHEATHING, 38x89 (2"x4") STUDS @ 400mm (16") O.C. (MAX. HEIGHT 3000mm (9'-10"), WITH APPR DIAGONAL WALL BRACING SIDING TO BE MIN 200mm (8")

 $\langle 2C. \rangle$ RESERVED

STUCCO WALL CONSTRUCTION (2"x4") -GARAGE WALLS
STUCCO CLADDING SYSTEM CONFORMING TO O.B.C. 9.27.1.1.(2) & 9.28 THAT FMPLOY A MINIMUM 10mm AIR SPACE BEHIND THE CLADDING WITH POSITIVE DRAINAGE TO THE EXTERIOR AND APPLIED PER MANUFACTURERS SPECIFICATIONS OVER 25mm (1") MIN. EXPANDED OR EXTRUDED RIGID POLYSTYRENE ON APPROVED AIR/MOISTURE BARRIER ON 13mm (1/2") EXT. TYPE SHEATHING ON 38x89 (2"x4") STUDS @ 400 (16") O.C.. STUCCO TO BE MIN. 200 (8") ABOVE FINISH GRADE.

WALLS ADJACENT TO ATTIC SPACE - NO CLADDING
9.5mm (3/8") EXT. TYPE SHEATHING, 38x140 (2"x6") STUDS @ 400mm (16") O.C., RSI 3.87 (R22) INSULATION AND APPR, VAPOUR BARRIER AND APPR. CONTIN. AIR BARRIER, 13mm (1/2") INTERIOR DRYWALL FINISH. MID-HEIGHT BLOCKING REQ'D. IF NO SHEATHING APPLIED. REFER TO OBC SB-12, CHAPTER 3 FOR ADDITIONAL THERMAL

MASONRY VENEER CONSTRUCTION (2"x6")(SB-12-TABLE 3.1.1.2.A) (7/8"x7"x0.03") GALV. METAL TÌEŚ @ 400mm (16") O.C. HORIZONTAL 600mm (24") O.C. VERTICAL. APPROVED SHEATHING PAPER, 9.5mm (3/8") EXT. TYPE SHEATHING, 38x140 (2"x6") STUDS @ 400mm (16") O.C., RSI 3.87 (R22) INSULATION & APPR, VAPOUR BARRIER WITH APPR CONTIN. AIR BARRIER. 13mm (1/2") INTERIOR DRYWALL FINISH. PROVIDE WEEP HOLES @ 800mm (32") O.C. BOTTOM COURSE AND OVER OPENINGS. PROVIDE BASE FLASHING UP MIN. 150mm (6") BEHIND BUILDING PAPER. REFER TO OBC SB-12, CHAPTER 3 FOR ADDITIONAL THERMAL INSULATION REQUIREMENTS. MASONRY TO BE MIN. 150mm (6") ABOVE FINISH GRADE.

(3A.) RESERVED

MASONRY VENEER CONSTRUCTION (2"x4")— GARAGE WALLS (14.) BEARING STUD PARTITION (16") O.C. 38x89 (2"x4") SILL (7/8"x7"x0.03") GALV. METAL TIES @ 400mm (16") O.C. HORIZONTAL 600mm (24") O.C. VERTICAL. APPR. SHEATHING PAPER, 9.5mm (3/8") EXT. TYPE SHEATHING, 38x89 (2"x4") STUDS @ 400mm (16") 0 C (MAX. HEIGHT 3000mm 9'-10") WITH APPR. DIAGONAL WALL BRACING. PROVIDE WEEP HOLES @ 800mm (32") O.C. BOTTOM COURSE AND OVER OPENINGS. PROVIDE BASE FLASHING UP MIN. 150mm (6") BEHIND BUILDING PAPER. MASONRY TO BE MIN. 150mm (6") ABOVE FINISH GRADE

STUCCO WALL CONSTRUCTION (2"x6") (SB-12-TABLE 3.1.1.2.A) THAT EMPLOYS A MINIMUM 10mm AIR SPACE BEHIND THE CLADDING WITH POSITIVE DRAINAGE TO THE EXTERIOR AND APPLIED PER MANUFACTURERS SPECIFICATIONS OVER 25mm (1") MIN. EXTRUDED OR EXPANDED RIGID POLYSTYRENE ON APPR. CONTIN. AIR/MOISTURE BARRIER ON 13mm (1/2") EXT. TYPE SHEATHING ON 38x140 (2"x6") STUDS @ 400mm (16") O.C., RSI 3.87 (R22) INSULATION, APPROVED VAPOUR BARRIER, 13mm (1/2") GYPSUM WALLBOARD INTERIOR FINISH. REFER TO OBC SB-12. CHAPTER 3 FOR ADDITIONAL THERMAL INSULATION REQUIREMENTS. STUCCO TO BE MIN. 200 (8") ABOVE FINISH

4. INTERIOR STUD PARTITIONS
FOR BEARING PARTITIONS 38x89 (2"x4") @ 400mm (16") 0.C. FOR 2 STOREYS AND 300mm (12") O.C. FOR 3 STOREYS, NON-BEARING PARTITIONS 38x89 (2"x4") @ 600mm (24") O.C. PROVIDE 38x89 (2"x4") BOTTOM PLATE AND 2/38x89 (2/2"x4") TOP PLATE. 13mm (1/2") INT. DRYWALL BOTH SIDES OF STUDS, PROVIDE 38x140 (2"x6") STUDS/PLATES WHERE NOTED

FOUNDATION WALL/FOOTINGS: (9.15.3, 9.15.4, 9.13.2, 9.14.2.1.(2)) 250mm (10") POURÉD CONC. FDTN. WALL 20MPa (2900psi) WIT BITUMENOUS DAMPPROOFING AND DRAINAGE LAYER. DRAINAGE LAYER REQ'D. WHEN BASEMENT INSUL. EXTENDS 900 (2'-11") BELOW FIN. GRADE, DRAINAGE LAYER IS NOT REQ'D. WHEN FDTN. WALL IS WATERPROOFED. MAXIMUM POUR HEIGHT 2390 (7'-10") ON 500x155 (20"√6") CONTINUOUS KEYED CONC. FTG. BRACE EDIN. WALL PRIOR O BACKFILLING. ALL FOOTINGS SHALL REST ON NATURAL LINDISTURBED SOIL OR COMPACTED ENGINEERED FILL WITH MIN BEARING CAPACITY OF 150kPg OR GREATER. IF SOIL BEARING DOES NOT MEET MINIMUM CAPACITY, ENGINEERED FOOTINGS ARE REQUIRED.

STOREYS SUPPORTED | W/ MASONRY VENEER | W/ SIDING ONLY

1 18" WIDE x 6" DEEP 18" WIDE x 6" DEEP 22" WIDE x 6" DEEP | 22" WIDE x 6" DEEP

28" WIDE x 9" DEEP | 22" WIDE x 6" DEEP -SEE OBC 9.15.3. -MAXIMUM FLOOR LIVE LOAD OF 2.4kPa. (50psf.) PER FLOOR, AND MAX LENGTH OF SUPPORTED FLOOR JOISTS IS 4 9m (16'-1") -REFER TO SOILS REPORT FOR SOIL CONDITIONS AND BEARING

STRIP FOOTING SUPPORTING EXTERIOR WALLS (FOR W.O.B.) -ASSUMING MASONRY VENEER CONSTRUCTION, MAX. FLOOR LIVE LOAD OF 2 4kPg (50psf) PER FLOOR AND MAX LENGTH OF SUPPORTED FLOOR JOISTS IS 4.9m (16'-1"). THE STRIP FOOTING

2 STOREY WITH WALK-OUT BASEMENT 560×155 (22"x6")

FOUNDATION DRAINAGE OBC. 9.14.2. & 9.14.3.
100mm (4") DIA. FOUNDATION DRAINAGE TILE 150mm (6") CRUSHED STONE OVER AND AROUND DRAINAGE TILES.

BASEMENT SLAB OBC. 9.3.1.6.(1)(b), 9.16.4.5.(1), 9.25.3.3.(15) ′80mm (3")MIN. 25MPa (3600psi) CONC. SLAB ON 100mm (4") COARSE GRANULAR FILL, OR 20MPa. (3000psi) CONC. WITH DAMPPROOFING BELOW SLAB. UNDER SLAB INSULATION PER SB-12. ALL SLAB JOINTS & PENETRATIONS TO BE CAULKED.

EXPOSED FLOOR TO EXTERIOR (SB-12-TABLE 3.1.1.2.A) PROVIDE RSI 5.46 (R31) INSULATION, APPROVED VAPOUR BARRIER AND CONTINUOUS AIR BARRIER, FINISHED SOFFIT.

<u>ATTIC INSULATION</u> (SB-12-TABLE 3.1.1.2.A) (SB-12-3.1.1.8) RSI 10.56 (R60) BLOWN IN ROOF INSULATION AND APPROVED VAPOUR BARRIER, 16mm (5/8") INT. DRYWALL FINISH OR APPROVED EQUAL. RSI 3.52 (R20) MIN. ABOVE INNER SURFACE OF EXTERIOR WALL.

ALL STAIRS/EXTERIOR STAIRS -OBC. 9.8.-UNIFORM RISE -5mm (1/4") MAX BETWEEN ADJACENT TREADS OR LANDINGS 10mm (1/2") MAX BETWEEN TALLEST & SHORTEST

= 200 (7-7/8" MAX. RISF MIN. RUN MIN. TREAD = 235 (9-1/4")MAX. NOSING = 25 (1")MIN. HEADROOM

= 1950 (6'-5")RAIL @ LANDING = 900 (2'-11")= 865 (2'-10") to 965 (3'-2") RAIL @ STAIR MIN. STAIR WIDTH = 860 (2'-10")FOR CURVED STAIRS

MIN. RUN = 150 (6") MIN. AVG. RUN = 200 (8") HANDRAILS -OBC. 9.8.7.-

FINISHED RAILING ON PICKETS SPACED MAXIMUM 100mm (4")
BETWEEN PICKETS. CLEARANCE BETWEEN HANDRAIL AND SURFACE BEHIND IT TO BE 50 (2") MIN. HANDRAILS TO BE CONTINUOUS EXCEPT FOR NEWEL POST AT CHANGES OF DIRECTION

INTERIOR GUARDS -OBC. 9.8.8.-INTERIOR GUARDS: 900mm (2'-11") MIN. HIGH

EXTERIOR GUARDS - OBC. 9.8.8. 900mm (36") HIGH GUARD WHERE DISTANCE FROM PORCH TO FIN. GRADE IS LESS THAN 1800mm (71"). 1070mm (42") HIGH GUARD IS REQUIRED WHERE DISTANCE EXCEEDS 1800mm (71").

SILL PLATE - OBC. 9.23.7.

38x89 (2"x4") SILL PLATE WITH 13mm (1/2") DIA. ANCHOR BOLTS 200mm (8") LONG, EMBEDDED MIN. 100mm (4") INTO CONC. @ (7'-10") O.C., CAULKING OR 25 (1") MIN. MINERAL WOOL BETWEEN PLATE AND TOP OF FDTN. WALL USE NON-SHRINK GROUT TO LEVEL SILL PLATE WHEN REQUIRED.

BASEMENT INSULATION (SB-12-3.1.1.7), 9.25.2.3, 9.13.2.6)
FOUNDATION WALLS ENCLOSING HEATED SPACE SHALL BE INSULATED FROM THE UNDERSIDE OF THE SUBFLOOR TO NOT MORE THAN 200mm (8") ABOVE THE FINISHED FLOOR & NO CLOSER THAN 50mm (2") OF HE BASEMENT SLAB. RSI3.52ci (R20ci) BLANKET INSULATION TO HAVE APPROVED VAPOUR BARRIER, RECOMMEND DAMPPROOF WITH BUILDING PAPER BETWEEN THE FOUNDATION WALL AND INSULATION UP 1 GRADE LEVEL. NOTE: FULL HEIGHT INSULATION AT COLD CELLAR WALLS. BARRIER TO BE SEALED TO FOUNDATION WALL WITH CAULKING. CONTINUOUS INSULATION (ci) IS NOT TO BE INTERRUPTED BY FRAMING.

PLATE ON DAMPPROOFING MATERIAL, 13mm (1/2") DIA. ANCHOR BOLTS 200mm (8") LONG, EMBEDDED MIN, 100mm (4") INTO CONC. @ 2400mm (7'-10") O.C. 100mm (4") HIGH CONC. CURB ON 350x155 (14"x6") CONC. FOOTING. ADD HORIZ. BLOCKING AT MID-HEIGHT IF WALL IS UNFINISHED.

ADJUSTABLE STL. COL. W/ MIN. CAPACITY OF 71.2kN (16,000lbs.) AT A MAX. EXTENSION OF 2318mm (7'-7 1/2") CONFORMING TO CAN/CGSB-7.2-94, AND WITH 150x150x9.5 (6"x6"x3/8") STL. PLATE TOP & BOTTOM. 870x870x410 (34"x34"x16") CONC. FOOTING ON SOIL OR ENGINEERED FILL CAPABLE OF SUSTAINING PRESSURE OF 150 Kpa. MINIMUM AND AS PER SOILS REPORT.

STEEL BASEMENT COLUMN (SEE O.B.C. 9.15.3.3) 89mm(3-1/2") DIA x 4.78mm(.188) FIXED STL. COL. WITH 1070x1070x480 (42"x42"x18"). CONC. FOOTING ON UNDISTURBED SOIL OR ENGINEERED FILL CAPABLE OF SUSTAINING A PRESSURE OF 150 Kpa. MIN. AND AS PER SOILS REPORT.

STEEL COLUMN $\langle 15B \rangle \frac{3722233333}{90 \text{mm}(3-1/2")}$ DIA x 4.78mm(.188) NON-ADJUSTABLE STL. COL. TO BE ON 150x150x9.5 (6"x6"x3/8") STEEL TOP PLATE, & BOTTOM PLATE, BASE PLATE 120x250x12.5 (4 1/2"x10"x1/2") WITH 2-12mm DIA. x 300mm LONG x50mm HOOK ANCHORS (2-1/2"x12"x2") FIELD WELD COL. TO BASE PLATE.

CONCRETE NIB/ POCKET BEAM POCKET OR 300x150 (12"x6") POURED CONC. NIB WALLS. MIN. BEARING 90mm (3-1/2")

17. 19x64 (1"x3") CONTINUOUS WOOD STRAPPING BOTH SIDES OF STEEL BEAM.

GARAGE SLAB 18. GARAGE SLAD 100mm (4") 32MPa (4640psi) CONC. SLAB WITH 5-8% AIR ENTRAINMENT ON OPT. 100 (4") COARSE GRANULAR FILL WITH COMPACTED SUB-BASE OR COMPACTED NATIVE FILL.

GARAGE CEILINGS/INTERIOR WALLS

13mm (1/2") GYPSUM BOARD ON WALL AND CEILING BETWEEN
HOUSE AND GARAGE. TAPE AND SEAL ALL JOINTS AIRTIGHT PER O.B.C. 9.10.9.16. WALLS (R22), CEILINGS (R31), REFER TO SB-12, TABLE 3.1.1.2.A. FOR REQUIRED THERMAL INSULATION.

DOOR AND FRAME GASPROOFED. DOOR EQUIPPED WITH SELF CLOSING DEVICE AND WEATHERSTRIPPING PER OBC 9.10.13.15.

21. EXTERIOR STEP PRECAST CONCRETE STEP OR WOOD STEP WHERE NOT EXPOSED TO WEATHER MAX RISE 200mm (7-7/8") MIN TREAD 250mm (9-1/2"). SEE OBC. 9.8.9.2., 9.8.9.3. & 9.8.10.

DRYER EXHAUST (OBC-6.2.3.8.(7) & 6.2.4.11.)
CAPPED DRYER EXHAUST VENTED TO EXTERIOR. (USE 100mm (4") DIA. SMOOTH WALL VENT PIPE)

INSULATED ATTIC ACCESS (OBC-9.19.2.1. & SB12-3.1.1.8) TTIC ACCESS HATCH WITH MIN. DIMENSION OF 545x610mm (2) 1/2"x24") & A MIN. AREA OF 0.32 SQ.M. (3.44 SQ.FT.) WITH WEATHERSTRIPPING. RSI 3.52 (R20) RIGID INSUL. BACKING.

FIREPLACE CHIMNEYS (OBC. 9.21.) TOP OF FIREPLACE CHIMNEY SHALL BE 915mm (3'-0") ABOVE THE HIGHEST POINT AT WHICH IT COMES IN CONTACT WITH THE ROOF AND 610mm (2'-0") ABOVE THE ROOF SURFACE WITHIN A HORIZ. DISTANCE OF 3050mm (10'-0") FROM THE CHIMNEY.

25.) LINEN CLOSET LINEN CLOSET, 4 SHELVES MIN. 350mm (14") DEEP

MECHANICAL EXHAUST MECHANICAL EXHAUST FAN, VENTED TO EXTERIOR AS REQUIRED BY OBC, 9.32.3.5, & 9.32.3.10,

STEEL BEARING PLATE FOR MASONRY WALLS
280x280x16 (11"x11"x5/8") STL. PLATE FOR STL BEAMS AND 280x280x12 (11"x11"x1/2") STL. PLATE FOR WOOD BEAMS BEARING ON CONC. BLOCK PARTYWALL, ANCHORED WITH 2-19mm (3/4") x 200mm (8") LONG GALV. ANCHORS WITHIN SOLID BLOCK COURSE. LEVEL WITH NON-SHRINK GROUT. OR

SOLID WOOD BEARING FOR WOOD STUD WALLS
SOLID BEARING TO BE AT LEAST AS WIDE AS THE SUPPORTED MEMBER, SOLID WOOD BEARING COMPRISED OF BUILT-UP WOOD STUDS TO BE CONSTRUCTED IN ACCORDANCE WITH OBC 9.17.4.2(2)

28. RESERVED

BEARING WOOD POST (BASEMENT) (OBC 9.17.4.)
3-38x140 (3-2"x6") BUILT-UP-POST ON METAL BASE SHI ANCHORED TO CONC. WITH 12.7 DIA. BOLT, 610x610x300 (24"x24"x12") CONC. FOOTING.

STEPPED FOOTINGS OBC 9.15.3.9. MIN. HORIZ, STEP = 600mm (24"

SLAB ON GRADE MIN. 100mm (4") CONCRETE SLAB ON GRADE ON 100mm (4") COARSE GRANULÁR FILL. REINFORCED WITH 6x6-W2.9xW2.9 MESH PLACED NEAR MID-DEPTH OF SLAB, CONC. STRENGTH 32 MPa (4640 psi) WITH 5-8% AIR ENTRAINMENT ON COMPACTED SUB-GRADE, REFER TO OBC SB-12, TABLE 3.1.1.2.A. FOR REQUIRED MINIMUM THERMAL INSULATION UNDER SLAB.

DIRECT VENTING GAS FURNACE/ H.W.T VENT DIRECT VENT FURNACE TERMINAL MIN. 900mm (36") FROM A NATURAL GAS REGULATOR, MIN. 300mm (12") ABOVÉ FIN. GRADE, FROM ALL OPENINGS, EXHAUST AND INTAKE VENTS. HRV INTAKE TO BE A MIN. OF 1830mm (6'-0") FROM ALL EXHAUST TERMINALS. REFER TO GAS UTILIZATION CODE. ALL AIR INTAKES SHALL BE LOCATED SO THAT THEY ARE SEPARATED FROM KITCHEN EXHAUST BY 3.0M IN COMPLIANCE WITH O.B.C. DIV.-B TABLE 6.2.3.12..

DIRECT VENTING GAS FIREPLACE VENT
DIRECT VENT GAS FIREPLACE. VENT TO BE A MINIMUM 300mm (12") FROM ANY OPENING AND ABOVE FIN. GRADE. REFER TO GAS **UTILIZATION CODE.**

SUBFLOOR, JOIST STRAPPING AND BRIDGING
16mm (5/8") T & G SUBFLOOR ON WOOD FLOOR JOISTS. FOR CERAMIC TILE APPLICATION (* SEE OBC 9.30.6. *) 6mm (1/4") PANEL TYPE UNDERLAY UNDER RESILIENT & PARQUET FLOORING (* SEE OBC 9.30.2.*) FLOOR JOISTS WITH SPANS OVER 2100mm (6'-11") TO BE BRIDGED WITH 38x38 (2"x2") CROSS BRACING OR SOLID BLOCKING @ 2100mm (6'-11") O.C. MAX. AND WHERE SPECIFIED BY JOIST TABLES A-1 OR A-2 STRAPPING SHALL BE 19x64 (1"x3") @ 2100mm (6'-11") O.C. UNLESS A PANEL TYPE CEILING FINISH IS APPLIED. (* SEE OBC 9.23.9.4. *)

EXPOSED BUILDING FACE (OBC. 9.10.15. & SB-2-2.3.5.(2)) . EXTERIOR WALLS TO HAVE A FIRE RESISTANCE RATING OF NOT LESS THAN 45 min. WHERE LIMITING DISTANCE (LD) IS LESS THAN 1.2M (3'-11"). WHERE THE LD IS LESS THAN 600mm (1'-11") THE EXPOSING FACE SHALL BE CLAD IN NON-COMBUSTIBLE MATERIAL. SEE ELEVATIONS FOR ADDITIONAL NOTES. OFFENDING GARAGE WALLS INCLUDED.

COLD CELLAR PORCH SLAB (OBC. 9.39.) FOR MAX. 2500mm (8'-2") PORCH DEPTH (SHORTEST DIM.), 125mm (5") 32MPa (4640psi) CONC. SLAB WITH 5-8% AIR ENTRAINMENT. REINF. WITH 10M BARS @ 200mm (7 7/8") O.C EACH WAY IN BOTTOM THIRD OF SLAB, MIN. 30mm (1 1/4") COVER, 600x600 (23 5/8"x23 5/8") 10M DOWELS @ 600mm (23 5/8") O.C., ANCHORED IN PERIMETER FDTN. WALLS. SLOPE SLAB MIN 1.0% FROM HOUSE WALL SLAB TO HAVE MIN 75mm (3") BEARING ON FDTN. WALLS. PROVIDE (L7) LINTEL OVER CELLAR DOOR WITH 100mm (4") END BEARING. BRICK CHECK

 $\langle 37. \rangle$ THE FDTN. WALL SHALL NOT BE REDUCED TO LESS THAN 90mm (3-1/2") THICK TO A MAX. DEPTH OF 600mm (24") AND SHALL BE TIED TO THE FACING MATERIAL WITH METAL TIES SPACED 200mm (8") O.C. VERTICALLY AND 900mm (36") O.C. HORIZONTALLY. FILL SPACE BETWEEN WALL AND FACING SOLID

CONVENTIONAL ROOF FRAMING (2.0Kpg. SNOW LOAD) $\langle 38. \rangle$ 38x140 (2"x6") RAFTERS @ 400mm (16"0.C.) FOR MAX 11'-SPAN, 38x184 (2"x8") RIDGE BOARD. 38x89 (2"x4") COLLAR TIES AT MIDSPANS, CEILING JOISTS TO BE 38x89 (2"x4") @ 400mm (16") O.C. FOR MAX. 2830mm (9'-3") SPAN & 38x140 (2"x6") @ 400 (16") O.C. FOR MAX. 4450mm (14'-7") SPAN. RAFTERS FOR BUILT-UP ROOF TO BE 38x89 (2"x4") @ 600mm (24") O.C. WITH A 38v89 (2"v4") CENTRE POST TO THE TRUSS BELOW, LATERALLY BRACED @ 1800mm (6'-0") O.C. VERTICALLY.

TWO STOREY VOLUME SPACES
-FOR A MAXIMUM 5490 mm (18'-0") HEIGHT AND MAXIMUM SUPPORTED ROOF TRUSS LENGTH OF 6.0m, PROVIDE 2-38x140 (2-2"x6") SPR.#2 CONTIN. STUDS @ 300mm (12") O.C. (TRIPLE UP AT EVERY THIRD DOUBLE STUD FOR BRICK WALLS) C/W 9.6 (3/8") THICK EXT. PLYWOOD SHEATHING. PROVIDE SOLID WOOD BLOCKING BETWEEN WOOD STUDS @ 1220 mm (4'-0") O.C. VERTICALLY. -FOR WALLS WITH HORIZ. DISTANCES NOT EXCEEDING 2900 mm (9'-6"), PROVIDE 38x140 (2"x6") STUDS @ 400 (16") O.C. WITH CONTINUOUS 2-38x140 (2-2"x6")TOP PLATES + $1-38\times140$ (1-2"x6") BOTTOM PLATE & MINIMUM OF 3-38x184 (3-2"x8") CONT. HEADER AT GRND. CEILING LEVEL TOE-NAILED & GLUED AT TOP, BOTTOM PLATES AND HEADERS.

TYPICAL 1 HOUR RATED PARTYWALL 40. TYPICAL 1 HOUR MAILU FARTIWALL. REFER TO DETAILS FOR TYPE AND SPECIFICATIONS.

(41.) FOUNDATION WALL (W.O.D./W.O.B.) - WHERE GRADE TO T/O BASEMENT SLAB EXCEEDS 1200mm

(3'-11") A 250mm (10") WIDE FOUNDATION WALL IS REQUIRED. 42) EXTERIOR WALLS FOR WALK-OUT CONDITIONS THE EXTERIOR BASEMENT STUD WALL TO BE 38x140 (2"x6")

STUDS @ 400mm (16") o.c. <u>OR</u> 38x89 (2"x4") STUDS @

300mm (12")o.c. DRAIN WATER HEAT RECOVERY UNIT (DWHR) PER SB12-3.1.1.12.. A DRAIN WATER HEAT RECOVERY (DWHR UNIT SHALL BE INSTALLED IN EACH DWELLING UNIT TO RECEIVE DRAIN WATER FROM ALL SHOWERS OR FROM AT LEAST TWO SHOWERS WHERE THERE ARE TWO OR MORE SHOWERS IN THE DWFILING UNIT. DOES NOT APPLY IF THERE ARE NO SHOWERS

OR NO STOREY BENEATH ANY OF THE SHOWERS.

WOOD LINTELS AND BUILT-UP WOOD BEAMS L1 ---- 2/38 x 184 (2/2" x 8") SPR.#2 B1 --- 3/38 x 184 (3/2" x 8") SPR.#2 B2 ---- 4/38 x 184 (4/2" x 8") SPR.#2 B7 ---- 5/38 x 184 (5/2" x 8") SPR.#2 L3 ---- 2/38 x 235 (2/2" x 10") SPR.#2 B3 ---- 3/38 x 235 (3/2" x 10") SPR.#2 B4 ---- 4/38 x 235 (4/2" x 10") SPR.#2 L5 ---- 2/38 x 286 (2/2" x 12") SPR.#2

B5 ---- 3/38 x 286 (3/2" x 12") SPR.#2 B6 ---- 4/38 x 286 (4/2" x 12") SPR.#2 LOOSE STEEL LINTELS $L7 = 89 \times 89 \times 6.4L (3-1/2" \times 3-1/2" \times 1/4"L)$

L8 -- 89 x 89 x 7.9L $(3-1/2" \times 3-1/2" \times 5/16"L)$ L9 -- 102 x 89 x 7.9L (4" x 3-1/2" x 5/16"L) $L10 = -127 \times 89 \times 7.9L (5" \times 3 = 1/2" \times 5/16"L)$ $L11 = -152 \times 89 \times 10.0L (6" \times 3 = 1/2" \times 3/8"L)$ L12 -- 152 x 102 x 11.0L (6"x 4" x 7/16"L) L13 -- 178 x 102 x 13.0L (7"x 4" x 1/2"L)

LAMINATED VENEER LUMBER (LVL) BEAMS LVL1A --- 1-1 3/4"x7 1/4" (1-45x184) LVL1 --- 2-1 3/4"x7 1/4" (2-45x184) LVL2 --- 3-1 3/4"x7 1/4" (3-45x184) LVL3 --- 4-1 3/4"x7 1/4" (4-45x184) LVL4A --- 1-1 3/4"x9 1/2" (1-45x240) LVL4 --- 2-1 3/4"x9 1/2" (2-45x240) LVL5 --- 3-1 3/4"x9 1/2" (3-45x240) LVL5A --- 4-1 3/4"x9 1/2" (4-45x240) LVL6A --- 1-1 3/4"x11 7/8" (1-45x300) LVL6 --- 2-1 3/4"x11 7/8" (2-45x300) LVL7 --- 3-1 3/4"x11 7/8" (3-45x300)

LVL8 --- 4-1 3/4"x11 7/8" (4-45x300)

DOOR SCHEDULE EXTERIOR 815 x 2030 x 45 $(2'-8" \times 6'-8" \times 1-3/4")$ DOOR INSULATED MIN. RSI 0.7 (R4) **EXTERIOR** 865 x 2030 x 45 DOOR $(2'-10" \times 6'-8" \times 1-3/4")$ INSULATED MIN. RSI 0.7 (R4) **EXTERIOR** 915 x 2030 x 45 DOOR $(3'-0" \times 6'-8" \times 1-3/4")$

INSULATED MIN. RSI 0.7 (R4)

FXTFRIOR 915 x 2440 x 45 DOOR $(3'-0" \times 8'-0" \times 1-3/4")$ INSULATED MIN. RSI 0.7 (R4) **EXTERIOR** 815 x 2440 x 45

 $(2'-8" \times 8'-0" \times 1-3/4")$ DOOR INSULATED MIN. RSI 0.7 (R4)

INTERIOR 815 x 2030 x 35 DOOR $(2'-8" \times 6'-8" \times 1-3/8")$ EXTERIOR 815 x 2030 x 45 DOOR $(2'-8" \times 6'-8" \times 1-3/4")$ 20 MIN. RATED DOOR AND FRAME, WITH APPROVED SELF CLOSING DEVICE. INSULATED MIN. RSI 0.7 (R4)

815 x 2030 x 45 EXTERIOR $(2'-8" \times 6'-8" \times 1-3/4")$ DOOR WEATHERSTRIPPING INSTALLED 760 x 2030 x 35 INTERIOR

DOOR

 $(2'-6" \times 6'-8" \times 1-3/8")$ DOOR INTERIOR 710 x 2030 x 35 DOOR $(2'-4" \times 6'-8" \times 1-3/8")$ INTERIOR 610 x 2030 x 35

 $(2'-0" \times 6'-8" \times 1-3/8")$ 660 x 2030 x 35 INTERIOR (4A)DOOR $(2'-2" \times 6'-8" \times 1-3/8")$

INTERIOR 460 x 2030 x 35 $(1'-6" \times 6'-8" \times 1-3/8")$ <u>LEGEND</u>

CLASS 'B' VENT LIGHT FIXTURE - (CEILING MOUNTED) (5) EXHAUST VENT LIGHT FIXTURE DUPLEX OUTLET (PULL CHAIN) (12" HIGH) LIGHT FIXTURE **\rightarrow** DUPLEX OUTLET (WALL MOUNTED) (HEIGHT AS NOTED A.F.F) WEATHERPROOF DUPLEX OUTLET `**⊗** ✓ FLOOR DRAIN HEAVY DUTY OUTLET (220 volt) ─# ♦ HOSE BIB POT LIGHT

SOLID WOOD BEARING (SPRUCE No. 2). SOLID BEARING TO BE AS WIDE AS SUPPORTED MEMBER OR AS DIRECTED BY STRUCTURAL ENGINEER. SOLID BEARING TO BE MINIMUM 2 PIECES.

SOLID WOOD BEARING TO MATCH FROM ABOVE

SMOKE ALARM (REFER TO OBC 9.10.19)

CARBON MONOXIDE ALARM (OBC 9.33.4.)

(9.10.19.3.(3)).

CONNECTING THE FLOOR LEVEL AND ALSO 1 IN

INTERCONNECTED TO ACTIVATE ALL ALARMS IF 1

NCORPORATE VISUAL SIGNALLING COMPONENT

BATTERY BACK-UP REQUIRED SMOKE ALARMS TO

WHERE A FUEL-BURNING APPLIANCE IS INSTALLED IN A DWELLING UNIT, A CARBON MONOXIDE ALARM

CONFORMING TO CAN./CSA-6.19 OR UL2034 SHALL BE

INSTALLED ADJACENT TO EACH SLEEPING AREA. CARBON

MONOXIDE DETECTOR(S) SHALL BE PERMANENTLY WIRED

SO THAT ITS ACTIVATION WILL ACTIVATE ALL CARBON

MONOXIDE DETECTORS AND BE EQUIPPED WITH AN

MANUFACTURER FOR ADDDITIONAL REQUIREMENTS.

SOIL GAS CONTROL (OBC 9.13.4.1 & 9.13.4.2)

INTERVENING DOORS ARE CLOSED, REFER TO

CONNECTED TO AN ELECTRICAL CIRCUIT AND

EACH BEDROOM NEAR HALL DOOR. ALARMS TO BE

MECHANICAL SYMBOLS HEAT PIPE PLUMBING (TOILET) =====**≥**♥ PLUMBING (BATH, SINK,SHOWER) WARM AIR RETURN AIR DUCT

DJ

TJ

LVL

8/

P.T.

G.T.

DOUBLE JOIST

TRIPLE JOIST

LUMBER

LUMBER

F.A. FLAT ARCH

I CURVED ARCH

GIRDER TRUSS

MEDICINE CABINET

SEE NOTE (39.)

CONC. BLOCK WALL

DOUBLE VOLUME WALL

LAMINATED VENEER

PRESSURE TREATED

POINT LOAD FROM ABOVE


BY ROOF TRUSS MANUF.

NOTE: STABILITY OF NARROW (20'-25') & TALL (±30') HOUSES -BUILDER TO PROVIDE SUFFICIENT TEMPORARY BRACING TO RESIST WIND LOADING WHEN UNDER CONSTRUCTION. FURTHER RECOMMENDATIONS:

1) REDUCE THE FOUNDATION WALL SILL PLATE ANCHOR BOLT SPACING FROM 2400mm o/c(7'-10") TO 1220mm o/c (4'-0") FOR STANDARD CONDITIONS.

USE 9.5mm (3/8") THICK PLYWOOD OR WAFERBOARD FOR THE EXTERIOR WALL SHEATHING.

3) TO STIFFEN THE STRUCTURE IN TRANSVERSE DIRECTION USE 9.5mm (3/8") THICK PLYWOOD NAILED TO THE INTERIOR PARTITIONS ON EACH FLOOR FOR A MINIMUM 2 INTERIOR PARTITION WALLS ON BOTH SIDES AND PERPENDICULAR TO THE LONG WALLS.



SOURCES OF CONTAMINATION (EXHAUST VENTS) IN COMPLIANCE WITH O.B.C. DIV.-B 6.2.3.12. AND TABLE 6.2.3.12. 1) ALL LUMBER SHALL BE SPRUCE NO.2 GRADE, UNLESS NOTED OTHERWISE. 2) STUDS SHALL BE STUD GRADE SPRUCE, UNLESS NOTED OTHERWISE.

3) LUMBER EXPOSED TO THE EXTERIOR TO BE SPRUCE No. 2 GRADE PRESSURE TREATED OR CEDAR, UNLESS NOTED OTHERWISE. ALL LAMINATED VENEER LUMBER (L.V.L.) BEAMS, GIRDER TRUSSES, AND METAL IGER CONNECTIONS SUPPORTING ROOF FRAMING TO BE DESIGNED & CERTIFIED

BY TRUSS MANUFACTURER. 5) LVL BEAMS SHALL BE 2.0E -2950Fb MIN.. NAIL EACH PLY OF LVL WITH 89mm (3 1/2") LONG COMMON WIRE NAILS @ 300mm (12") O.C. STAGGERED IN 2 ROWS FOR 184, 240 & 300mm (7 1/4",9 1/2", 11 7/8") DEPTHS AND STAGGERED IN 3 ROWS FOR GREATER DEPTHS AND FOR 4 PLY MEMBERS ADD 13mm (1/2") DIA.

GALVANIZED BOLTS BOLTED AT MID-DEPTH OF BEAM @ 915mm (3'-0' PROVIDE TOP MOUNT BEAM HANGERS TYPE "SCL" MANUFACTURED BY SIMPSON STRONG TIE OR EQUAL FOR ALL LVL BEAM TO BEAM CONNECTIONS UNLESS NOTED

OTHERWISE. JOIST HANGERS: PROVIDE METAL HANGERS FOR ALL JOISTS AND BUILT-UP WOOD MEMBERS INTERSECTING FLUSH BUILT-UP WOOD MEMBERS

WOOD FRAMING NOT TREATED WITH A WOOD PRESERVATIVE, IN CONTACT WITH CONCRETE, SHALL BE SEPARATED FROM THE CONC. BY AT LEAST 2 mil. POLYETHYLENE FILM, No.50 (45lbs.) ROLL ROOFING OR OTHER DAMPPROOFING MATERIAL, EXCEPT WHERE THE WOOD MEMBER IS AT LEAST 150mm (6") ABOVE THE GROUND. 1) STRUCTURAL STEEL SHALL CONFORM TO CAN/CSA-G40-21 GRADE 300W HOLLOW

STRUCTURAL SECTIONS SHALL CONFORM TO CSA-G40.21 GRADE 350W "STRUCTURAL

QUALITY STEEL". OBC. B-9.23.4.3. REINFORCING STEEL SHALL CONFORM TO CSA-G30-18M GRADE 400R. ALL STUCCO WALLS TO HAVE A MINIMUM 10mm AIR SPACE BEHIND THE CLADDING WITH POSITIVE DRAINAGE TO THE EXTERIOR. THE EXTERIOR SHEATHING MUST NOT BE GYPSUM BASED, ALL STUCCO TO BE INSTALLED AS PER MANUFACTURERS STUCCO:

PDATED: FEBRUARY 20, 2020 REVISION:

ONT. REG. 332/12-2012 OBC
Amendment 0. Reg. 88/19
January 01, 2020



REFER TO UNIT DRAWINGS OR PAGE CN-2 FOR SB-12 COMPLIANCE PACKAGE A1 TO BE USED FOR HIS MODEL. The minimum thermal performance of building

nvelope and equipment shall conform to the elected package unless otherwise noted. CONTRACTOR MUST VERIFY ALL DIMENSIONS ON THE JOB AND REPORT ANY DISCREPANCY TO VA3 DESIGN BEFORE CONTRACTOR MUST VERIFY ALL DIMENSIONS ON THE JOB AND REPORT ANY DISCREPANCY TO VA3 DESIGN BEFORE PROCEEDING WITH THE WORK. ALL DRAWINGS AND SPECIFICATIONS ARE INSTRUMENTS OF SERVICE AND THE PROPERTY OF VA3 DESIGN WHICH IF REQUESTED MUST BE RETURNED AT THE COMPLETION OF THE WORK. ALL DRAWINGS TO BE USED FOR CONSTRUCTION ONLY AFTER BUILDING PERMIT HAS BEEN ISSUED.

BAYVIEW WELLINGTON

lification information Propreste ellington Jno–Baptiste 🅢 REVISED AS PER ENG'S COMMENTS REVISED AS PER ROOF / FLOOR LAYOUTS DEC 17-20 ISSUED FOR CLINET REVIEW f the Designer which must be returned at the completion of the wo

LUMBER:

STEEL:



GREEN VALLEY ESTATES ČT. 2020

BRADFORD, ON.


3/16" = 1'-0"

RIDEAU 18 CONSTRUCTION NOTES 13045-S42-18 (LOT402B)

S42-18

1304


va3design.com dwg - Thu - Jan 21 2021 - 10:29 AM Il drawings specifications, related documents and design are the copyright property of VA3 DESIGN. Reproduction of this property in whole or in part is strictly prohibited without VA3 DESIGN's written pe




WALL FRAMING SHALL CONFORM TO OBC 9.23.10.1.(2) FOR A 1/50 YEAR REFERENCE WIND PRESSURE OF 0.6 KPa STUDS GREATER THAN 9'-10" HIGH TO BE No. 2 SPF. STUD SPECIFICATION IS SUITABLE FOR BRICK VENEER OR

** STUD INFORMATION TAKEN FROM OBC TABLE A-30

SIDING.








9	•				The undersigned has reviewed and takes responsibility for this design
8					and has the qualifications and meets the requirements set out in the Ontario Building Code to be a Designer.
7					qualification information
6					Wellington Jno-Baptiste 1 130572376 25591
5					name , signature BCIN
4					registration information VA3 Design Inc. 42658
3	REVISED AS PER ENG'S COMMENTS		21-21		
2	REVISED AS PER ROOF / FLOOR LAYOUTS	DEC	17-20	RC	Contractor must verify all dimensions on the job and report any discrepancy to the Designer before proceeding with the work. All
1		NOV	06-20	RC	drawings and specifications are instruments of service and the property of the Designer which must be returned at the completion of the work.
no.	description	(date	by	Drawings are not to be scaled.

-									
VA?		BAY	VIEW	WELLING	GTON		_	42 — RIDEAU	1 8
DESIGN	project name GREEN	VALLEY	ESTATES	ĺ	BRADFORD,	onicipality ON.			
DESIUN 255 Consumers Rd Suite 120	date OCT. 2020)						DETAIL	
Toronto ON M2J 1R4 416.630.2255 f 416.630.4782	drawn by RC		checked by RC	3/16" = 1'-0"		130	45-S42-18	file name (LOT402B)	(
va3design.com	RICHARD - H	I:\ARCHIVE\WOR	RKING\2013\13045	i.BW\units\42"\13045-S	42-18 (lot402B).dw	g – Thu	- Jan 21 2021	- 10:29 AM	

All drawings specifications, related documents and design are the copyright property of VA3 DESIGN. Reproduction of this property in whole or in part is strictly prohibited without VA3 DESIGN's written permissi









S42-18RIDEAU 18


DETAIL

BRADFORD, ON.

9 . 8 . 7 . 6 .		The undersigned has reviewed and takes responsibility for this design and has the qualifications and meets the requirements set out in the Ontario Building Code to be a Designer. qualification information Wellington Jno-Baptiste	VAR	BAYVIEW WELLINGTON
5 .		name signature BCIN	DECICN	GREEN VALLEY ESTATES BRADFORD,
3 REVISED AS PER ENG'S COMMENTS	JAN 21-21 RC	VÁ3 Design Inc. 42658 Contractor must verify all dimensions on the job and report any	I DECION I	dote OCT. 2020
2 REVISED AS PER ROOF / FLOOR LAYOUTS 1 ISSUED FOR CLINET REVIEW	DEC 17-20 RC NOV 06-20 RC	discrepancy to the Designer before proceeding with the work. All drawings and specifications are instruments of service and the property of the Designer which must be returned at the completion of the work.	Toronto ON M2J 1R4 t 416.630.2255 f 416.630.4782	drawn by checked by scale












_	_	
VA?		VIEW
DECIGN	project name GREEN VALLEY	ESTATES
DESIGN Consumers Rd Suite 120	date OCT. 2020	
Toronto ON M2J 1R4	drawn by	checked by
6.630.2255 f 416.630.4782	RC	RC
va3desian.com	PICHARD - H-\ ARCHIVE\ WOR	PKING\ 2013\ 1304


All drawings specifications, related documents and design are the copyright property of VA3 DESIGN. Reproduction of this property in whole or in part is strictly prohibited without VA3 DESIGN's written permis

		BAY	VIEW	WELLIN			S42 -	18	
	greet name	VALLEY	ESTATES		BRADFORD,	onicipality ON.			roject no. 3045
te 120	date OCT. 2020						DETAIL	drawing	g no.
R4 30.4782	drawn by RC		checked by RC	3/16" = 1'-0"		130	file name 45-S42-18 (LOT402B)	CN	14











NOTE: 1. WHERE BACKFILL HEIGHT < 4'-7", PROVIDE 2x6 @ 16" o/c KNEEWALL ON 10" THICK CONC FNDN WALL 2. WHERE BACKFILL HEIGHT > 4'-7", PROVIDE 6" CONC SHELF FOR BRICK VENEER ON 10" THICK CONC FNDN WALL 3. FOOTING TO BE 22"x6" THICK UNLESS NOTED OTHERWISE ON PLAN.









38 Parkside Drive, UNIT 7 Newmarket, ON L3Y 8J9 T: 905-853-8547 E: quaile.eng@rogers.com

BAYMEW WELLINGTON - GREEN VALLEY PROJECT DETACHED HOMES

BRADFORD, ONTARIO

20-106 CHECKED APPROVE

SJB SJB JAYADAM

STRUCTURAL DETAILS AND NOTES

AS NOTED