

FROM PLAN DATED: NOV. 2015

BUILDER:  
BAYVIEW WELLINGTON

SITE:  
ALCONA

MODEL: S32-1-12

ELEVATION: A,B

LOT:  
CITY: INNISFIL, ON

SALESMAN: MARIO  
DESIGNER: CZ  
REVISION: -

NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.


LOADING:  
DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 05/09/2017

1st FLOOR


STANDARD



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	43
J1DJ	14-00-00	9 1/2" NI-40x	2	6
J2	12-00-00	9 1/2" NI-40x	1	2
J3	10-00-00	9 1/2" NI-40x	1	2
J4	6-00-00	9 1/2" NI-40x	1	7
J5	4-00-00	9 1/2" NI-40x	1	1
J6	2-00-00	9 1/2" NI-40x	1	4
B4	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B5	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B15	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B3	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B1	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B16	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B2	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
9	H1	IUS2.56/9.5
2	H1	IUS2.56/9.5
6	H1	IUS2.56/9.5
4	H3	HUS1.81/10

Town of Innisfil Certified Model  
12/03/2018 9:38:32 AM kgervais



FROM PLAN DATED: NOV. 2015

BUILDER:  
BAYVIEW WELLINGTON

SITE:  
ALCONA

MODEL: S32-1-12

ELEVATION: A,B

LOT:  
CITY: INNISFIL, ON

SALESMAN: MARIO  
DESIGNER: CZ  
REVISION: -

NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.


LOADING:  
DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 05/09/2017

1st FLOOR


SUNKEN



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	39
J1DJ	14-00-00	9 1/2" NI-40x	2	6
J2	12-00-00	9 1/2" NI-40x	1	2
J3	10-00-00	9 1/2" NI-40x	1	2
J4	8-00-00	9 1/2" NI-40x	1	8
J5	6-00-00	9 1/2" NI-40x	1	7
J6	4-00-00	9 1/2" NI-40x	1	1
J7	2-00-00	9 1/2" NI-40x	1	4
B4	14-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B5	14-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B17	14-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	2	2
B15	10-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B3	10-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B18L	6-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B19	6-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B1	4-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B16	4-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B2	4-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
17	H1	IUS2.56/9.5
2	H1	IUS2.56/9.5
6	H1	IUS2.56/9.5
4	H3	HUS1.81/10
1	H3	HUS1.81/10

Town of Innisfil Certified Model  
12/03/2018 9:38:40 AM kgervais



FROM PLAN DATED: NOV. 2015

BUILDER:  
BAYVIEW WELLINGTON

SITE:  
ALCONA

MODEL: S32-1-12

ELEVATION: A,B

LOT:  
CITY: INNISFIL, ON

SALESMAN: MARIO  
DESIGNER: CZ  
REVISION: -

NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.


LOADING:  
DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 05/09/2017

1st FLOOR

WOD



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	45
J1DJ	14-00-00	9 1/2" NI-40x	2	6
J2	12-00-00	9 1/2" NI-40x	1	2
J3	10-00-00	9 1/2" NI-40x	1	2
J4	6-00-00	9 1/2" NI-40x	1	7
J5	4-00-00	9 1/2" NI-40x	1	1
B4	14-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B5	14-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B15	10-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B3	10-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B1	4-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B16	4-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1
B2	4-00-00	1-3/4" x 9-1/2" VERSA-LAM@ 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
9	H1	IUS2.56/9.5
2	H1	IUS2.56/9.5
2	H1	IUS2.56/9.5
4	H3	HUS1.81/10

**Town of Innisfil Certified Model**  
12/03/2018 9:38:44 AM kgervais

FROM PLAN DATED: NOV. 2015

BUILDER:  
BAYVIEW WELLINGTON

SITE:  
ALCONA

MODEL: S32-1-12

ELEVATION: A

LOT:  
CITY: INNISFIL, ON

SALESMAN: MARIO  
DESIGNER: CZ  
REVISION: -


NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.

LOADING:  
DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 05/09/2017

## 2nd FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	56
J2	10-00-00	9 1/2" NI-40x	1	5
J2DJ	10-00-00	9 1/2" NI-40x	2	4
J3	8-00-00	9 1/2" NI-40x	1	5
J4	6-00-00	9 1/2" NI-40x	1	7
B11	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B12	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B13	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B7	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B8	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B14	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B10DR	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B9	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2

Connector Summary		
Qty	Manuf	Product
7	H1	IUS2.56/9.5
16	H1	IUS2.56/9.5
2	H2	HGUS410
1	H3	HUS1.81/10
1	H3	HUS1.81/10
1	H4	LS 90
1	H4	LS 90
2	H5	HU310-2

Town of Innisfil Certified Model  
12/03/2018 9:38:46 AM kgervais

FROM PLAN DATED: NOV. 2015

BUILDER:  
BAYVIEW WELLINGTON

SITE:  
ALCONA

MODEL: S32-1-12

ELEVATION: B

LOT:  
CITY: INNISFIL, ON

SALESMAN: MARIO  
DESIGNER: CZ  
REVISION: -


NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.

LOADING:  
DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 05/09/2017

## 2nd FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	64
J2	6-00-00	9 1/2" NI-40x	1	7
B11	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B12A	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B13	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B14	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B10DR	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B9	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2

Connector Summary		
Qty	Manuf	Product
7	H1	IUS2.56/9.5
7	H1	IUS2.56/9.5
1	H3	HUS1.81/10
1	H3	HUS1.81/10
1	H4	LS 90
1	H4	LS 90

**Town of Innisfil Certified Model**  
12/03/2018 9:38:50 AM kgevais



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B1(i4114)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:53

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: S32-1-12.EL B.mmdl

Description: Designs\Flush Beams\Basement\Flush Beams\B1(i4114)

Specifier:


Designer:

Company:

Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:38:53 AM kgervais



Total Horizontal Product Length = 03-02-00

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	559 / 0	288 / 0		
B1	563 / 0	293 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
						1.00	0.65	1.00	1.15	
0	User Load	Unf. Lin. (lb/ft)	L	00-02-12	00-11-04	240	120			n/a
1	User Load	Unf. Lin. (lb/ft)	L	01-01-12	01-11-04	240	120			n/a
2	User Load	Unf. Lin. (lb/ft)	L	02-01-12	02-11-04	240	120			n/a
3	-	Conc. Pt. (lbs)	L	00-01-08	00-01-08	115	58			n/a
4	-	Conc. Pt. (lbs)	L	01-00-08	01-00-08	160	80			n/a
5	-	Conc. Pt. (lbs)	L	02-00-08	02-00-08	165	82			n/a
6	-	Conc. Pt. (lbs)	L	03-00-08	03-00-08	123	66			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	801 ft-lbs	12,704 ft-lbs	6.3%	1	01-07-01
End Shear	955 lbs	5,785 lbs	16.5%	1	00-11-08
Total Load Defl.	L/999 (0.004")	n/a	n/a	4	01-07-01
Live Load Defl.	L/999 (0.002")	n/a	n/a	5	01-07-01
Max Defl.	0.004"	n/a	n/a	4	01-07-01
Span / Depth	3.7	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 1-3/4"	1,198 lbs	n/a	28.1%	HUS1.81/10
B1 Hanger	2" x 1-3/4"	1,212 lbs	n/a	28.4%	HUS1.81/10

### Notes



pg 12



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B1(i4114)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:53

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl

Description: Designs\Flush Beams\Basement\Flush Beams\B1(i4114)

Specifier:

Designer:

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

**CONFORMS TO OBC 2012**

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 45709-17  
STRUCTURAL  
COMPONENT ONLY

*PKZ*


BC CALC® Design Report



Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
 Description: Designs\Flush Beams\Basement\Flush Beams\B2(i4243)  
 Specifier:  
 Designer:  
 Company:  
 Misc:

**Town of Innisfil Certified Model**  
 12/03/2018 9:38:55 AM kgervais



Total Horizontal Product Length = 03-04-04

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B0	482 / 0	249 / 0		
B1	493 / 0	255 / 0		

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
0	J5(i4146)	Conc. Pt. (lbs)	L	00-08-08	00-08-08	316	158			n/a
1	J5(i4202)	Conc. Pt. (lbs)	L	01-08-08	01-08-08	355	178			n/a
2	J5(i4121)	Conc. Pt. (lbs)	L	02-08-08	02-08-08	304	152			n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	978 ft-lbs	12,704 ft-lbs	7.7%	1	01-08-08
End Shear	816 lbs	5,785 lbs	14.1%	1	00-11-08
Total Load Defl.	L/999 (0.005")	n/a	n/a	4	01-07-15
Live Load Defl.	L/999 (0.003")	n/a	n/a	5	01-07-15
Max Defl.	0.005"	n/a	n/a	4	01-07-15
Span / Depth	4	n/a	n/a		00-00-00

**Bearing Supports**

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	Hanger 2" x 1-3/4"	1,034 lbs	n/a	24.2%	HUS1.81/10
B1	Hanger 2" x 1-3/4"	1,059 lbs	n/a	24.8%	HUS1.81/10

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Hanger Manufacturer: Unassigned  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.







# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B3(i4206)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:54


BC CALC® Design Report



Build 5033  
Job Name:  
Address:  
City, Province, Postal Code:  
Customer:  
Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
Description: Designs\Flush Beams\Basement\Flush Beams\B3(i4206)  
Specifier:  
Designer:  
Company:  
Misc:

**Town of Innisfil Certified Model**  
12/03/2018 9:38:57 AM kgervais



Total Horizontal Product Length = 09-03-08

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	446 / 0	250 / 0		
B1, 5-1/2"	345 / 0	210 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
						1.00	0.65	1.00	1.15	
0	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	03-03-08	19	10			n/a
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	03-03-08	09-03-08	22	11			n/a
2	-	Conc. Pt. (lbs)	L	03-04-06	03-04-06	555	286			n/a
3	9(i3662)	Conc. Pt. (lbs)	L	09-00-12	09-00-12	43	33			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	2,816 ft-lbs	12,704 ft-lbs	22.2%	1	03-04-06
End Shear	931 lbs	5,785 lbs	16.1%	1	01-01-00
Total Load Defl.	L/999 (0.089")	n/a	n/a	4	04-03-10
Live Load Defl.	L/999 (0.058")	n/a	n/a	5	04-03-10
Max Defl.	0.089"	n/a	n/a	4	04-03-10
Span / Depth	10.9	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Post	3-1/2" x 1-3/4"	982 lbs	19.7%	13.1%	Unspecified
B1 Wall/Plate	5-1/2" x 1-3/4"	780 lbs	15.2%	6.6%	Unspecified

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

CONFORMS TO OBC 2012



DWG NO. TAM45711-17  
STRUCTURAL  
COMPONENT ONLY



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B4(i4090)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:54


BC CALC® Design Report



Build 5033  
Job Name:  
Address:  
City, Province, Postal Code:  
Customer:  
Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
Description: Designs\Flush Beams\Basement\Flush Beams\B4(i4090)  
Specifier:  
Designer:  
Company:  
Misc:

**Town of Innisfil Certified Model**  
12/03/2018 9:38:59 AM kgervais



Total Horizontal Product Length = 13-03-06

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B0, 2-3/8"	354 / 0	484 / 0		
B1, 5-1/2"	638 / 0	538 / 0		

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	13-03-06	11	6			n/a
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	07-03-06	3				n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-02-06	07-07-02		52			n/a
3	FC1 Floor Material	Unf. Lin. (lb/ft)	L	07-03-06	13-03-06	16	8			n/a
4	-	Conc. Pt. (lbs)	L	07-04-04	07-04-04	570	293			n/a
5	2(i824)	Conc. Pt. (lbs)	L	13-00-10	13-00-10	160	148			n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	5,561 ft-lbs	12,704 ft-lbs	43.8%	1	07-04-04
End Shear	1,125 lbs	5,785 lbs	19.5%	1	12-00-06
Total Load Defl.	L/374 (0.409")	0.637"	64.2%	4	06-08-05
Live Load Defl.	L/723 (0.212")	0.425"	49.8%	5	06-08-05
Max Defl.	0.409"	n/a	n/a	4	06-08-05
Span / Depth	16.1	n/a	n/a		00-00-00

**Bearing Supports**

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material	
B0	Wall/Plate	2-3/8" x 1-3/4"	1,135 lbs	51.1%	22.4%	Unspecified
B1	Wall/Plate	5-1/2" x 1-3/4"	1,629 lbs	31.7%	13.9%	Unspecified

**Notes**



pg 1/2

DWG NO. TAM 45712-17  
STRUCTURAL  
COMPONENT ONLY



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B4(i4090)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:54

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl

Description: Designs\Flush Beams\Basement\Flush Beams\B4(i409

Specifier:

Designer:

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

**CONFORMS TO OBC 2012**

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



*post*

DWG NO. YAM 45712-17  
STRUCTURAL  
COMPONENT ONLY



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B5(i4219)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:53


BC CALC® Design Report



Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
 Description: Designs\Flush Beams\Basement\Flush Beams\B5(i4219)  
 Specifier:  
 Designer:  
 Company:  
 Misc:

**Town of Innisfil Certified Model**  
 12/03/2018 9:39:01 AM kgervais



Total Horizontal Product Length = 13-04-08

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	473 / 0	865 / 0		
B1, 5-1/2"	535 / 0	516 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	07-04-08	6	3			n/a
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-03-05	07-04-08		60			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	07-04-08	13-04-08	5	3			n/a
3	PBO8(i3625)	Conc. Pt. (lbs)	L	00-02-12	00-02-12	167	365			n/a
4	-	Conc. Pt. (lbs)	L	07-05-07	07-05-07	617	320			n/a
5	9(i3662)	Conc. Pt. (lbs)	L	13-01-12	13-01-12	148	157			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	5,381 ft-lbs	12,704 ft-lbs	42.4%	1	07-05-06
End Shear	1,007 lbs	5,785 lbs	17.4%	1	12-01-08
Total Load Defl.	L/390 (0.392")	0.637"	61.6%	4	06-09-07
Live Load Defl.	L/792 (0.193")	0.425"	45.5%	5	06-09-07
Max Defl.	0.392"	n/a	n/a	4	06-09-07
Span / Depth	16.1	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material	
B0	Wall/Plate	3-1/2" x 1-3/4"	1,211 lbs	56.9%	24.9%	Unspecified
B1	Wall/Plate	5-1/2" x 1-3/4"	1,447 lbs	28.2%	12.3%	Unspecified

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor: Normal Part code: Part 9

CONFORMS TO OBC 2012



*pk*

DWG NO. TAM4571317  
 STRUCTURAL  
 COMPONENT ONLY



BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code,:

Customer:

Code reports:

CCMC 12472-R

File Name: S32-1-12.EL B.mmdl

Description: Designs\Flush Beams\Basement\Flush Beams\B5(i4219)

Specifier:

Designer:

Company:

Misc:

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



*POW*

DWG NO. TAM 45713-17  
STRUCTURAL  
COMPONENT ONLY



# Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B9(i4168)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:54


BC CALC® Design Report



Build 5033  
Job Name:  
Address:  
City, Province, Postal Code:  
Customer:  
Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
Description: Designs\Flush Beams\1st Floor\Flush Beams\B9(i4168)  
Specifier:  
Designer:  
Company:  
Misc:

**Town of Innisfil Certified Model**  
12/03/2018 9:39:03 AM kgervais



Total Horizontal Product Length = 04-05-01

### Reaction Summary (Down / Uplift) ( lbs )

Bearing	Live	Dead	Snow	Wind
B0, 3-13/16"	1,322 / 0	682 / 0		
B1, 5-1/2"	1,043 / 0	544 / 0		

### Load Summary

Tag Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
0 Smoothed Load	Unf. Lin. (lb/ft)	L	00-00-00	03-06-09	570	285	1.00	1.15	n/a
1 J1(i4173)	Conc. Pt. (lbs)	L	04-02-09	04-02-09	343	172			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,798 ft-lbs	25,408 ft-lbs	7.1%	1	01-06-09
End Shear	1,500 lbs	11,571 lbs	13%	1	03-02-01
Total Load Defl.	L/999 (0.007")	n/a	n/a	4	02-01-09
Live Load Defl.	L/999 (0.004")	n/a	n/a	5	02-01-09
Max Defl.	0.007"	n/a	n/a	4	02-01-09
Span / Depth	4.8	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-13/16" x 3-1/2"	2,835 lbs	39.7%	17.4%	Unspecified
B1 Wall/Plate	5-1/2" x 3-1/2"	2,245 lbs	21.8%	9.6%	Unspecified

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012



*PK/E*

DWG NO. TAM 45714-17  
STRUCTURAL  
COMPONENT ONLY

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl


Description: Designs\Flush Beams\1st Floor Flush Beams B9(i4168

Specifier:

Designer:

Company:

Misc:

**Connection Diagram**

a minimum = 2"    c = 2-3/4"  
 b minimum = 3"    d = 6"

Calculated Side Load = 659.8 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d Nails

**3 1/2" ARDOX SPIRAL****Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 45714-17  
 STRUCTURAL  
 COMPONENT ONLY



# Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B7(i5009)

Dry | 2 spans | Right cantilever | 0/12 slope (deg)

September 5, 2017 09:34:34

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: S32-1-12.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B7(i5009)

Specifier:


Designer:

Company:

Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:39:05 AM kgervais



Total Horizontal Product Length = 08-09-14

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	87 / 9	88 / 0	0 / 21	
B1, 5-1/2"	184 / 0	390 / 0	241 / 0	

### Load Summary

Tag Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0 FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	08-09-14	13	6			n/a
1 FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	07-09-00	10	5			n/a
2 User Load	Unf. Lin. (lb/ft)	L	07-03-08	08-09-14	33	130	111		n/a
3 FC2 Floor Material	Unf. Lin. (lb/ft)	L	07-09-00	08-09-14	6				n/a
4 FC2 Floor Material	Conc. Pt. (lbs)	L	00-00-00	00-00-00		34			n/a
5 FC2 Floor Material	Conc. Pt. (lbs)	L	08-09-14	08-09-14	15	61	50		n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	301 ft-lbs	25,408 ft-lbs	1.2%	44	03-03-09
Neg. Moment	-527 ft-lbs	-25,408 ft-lbs	2.1%	64	07-06-04
End Shear	139 lbs	11,571 lbs	1.2%	44	00-11-08
Cont. Shear	264 lbs	11,571 lbs	2.3%	49	08-06-08
Total Load Defl.	L/999 (0.004")	n/a	n/a	107	03-05-10
Live Load Defl.	L/999 (0.003")	n/a	n/a	159	03-09-13
Total Neg. Defl.	L/999 (-0.002")	n/a	n/a	154	05-01-06
Max Defl.	0.004"	n/a	n/a	107	03-05-10
Span / Depth	9.4	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 3-1/2"	241 lbs	n/a	2.8%	HGUS410
B1 Wall/Plate	5-1/2" x 3-1/2"	941 lbs	9.2%	4%	Unspecified

### Notes



DWG NO. TAM-5715-17  
STRUCTURAL  
COMPONENT ONLY



BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: S32-1-12.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B7(i5009

Specifier:

Designer:

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

**CONFORMS TO OBC 2012**

Unbalanced snow loads determined from building geometry were used in selected product's verification.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9


Cantilevers require sheathed bottom flanges, blocking at cantilever support and closure at ends.

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

**Connection Diagram**



a minimum = 1"      c = 7-1/2"  
 b minimum = 3"      d = 6"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Member has no side loads.

Connectors are: 16d Nails

**3 1/2" ARDOX SPIRAL**



DWG NO. TAM 45715-17  
**STRUCTURAL  
 COMPONENT ONLY**



# Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B8(i5095)

Dry | 2 spans | Right cantilever | 0/12 slope (deg)

September 5, 2017 09:34:34



BC CALC® Design Report

Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: S32-1-12.mmd

Description: Designs\Flush Beams\1st Floor\Flush Beams\B8(i5095)

Specifier:


Designer:

Company:

Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:39:07 AM kgervais



Total Horizontal Product Length = 08-09-14

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	130 / 10	96 / 0	0 / 24	
B1, 5-1/2"	241 / 0	443 / 0	257 / 0	

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	07-06-04	34	17			n/a
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	07-06-04	08-09-14	37	75	55		n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	07-09-00	08-09-14	22	68	55		n/a
3	FC2 Floor Material	Conc. Pt. (lbs)	L	00-00-00	00-00-00		26			n/a
4	-	Conc. Pt. (lbs)	L	07-05-14	07-05-14	13	45	38		n/a
5	FC2 Floor Material	Conc. Pt. (lbs)	L	08-09-14	08-09-14	19	84	64		n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	444 ft-lbs	25,408 ft-lbs	1.7%	44	03-04-10
Neg. Moment	-603 ft-lbs	-25,408 ft-lbs	2.4%	49	07-06-04
End Shear	202 lbs	11,571 lbs	1.7%	44	00-11-08
Cont. Shear	320 lbs	11,571 lbs	2.8%	49	08-06-08
Total Load Defl.	L/999 (0.006")	n/a	n/a	107	03-06-11
Live Load Defl.	L/999 (0.005")	n/a	n/a	159	03-09-13
Total Neg. Defl.	L/999 (-0.002")	n/a	n/a	154	05-03-07
Max Defl.	0.006"	n/a	n/a	107	03-06-11
Span / Depth	9.4	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 3-1/2"	315 lbs	n/a	3.7%	HGUS410
B1 Wall/Plate	5-1/2" x 3-1/2"	1,060 lbs	10.3%	4.5%	Unspecified

### Notes



*06/2*

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: S32-1-12.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B8(i5095)

Specifier:

Designer:

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

**CONFORMS TO CBC 2012**

Unbalanced snow loads determined from building geometry were used in selected product's verification.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9


Cantilevers require sheathed bottom flanges, blocking at cantilever support and closure at ends.

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

**Connection Diagram**



a minimum = 1" c = 2-1/2"  
 b minimum = 3" d = 6"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record. Member has no side loads.

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL



DWG NO. TAM 45716-17  
 STRUCTURAL  
 COMPONENT ONLY


BC CALC® Design Report



Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mxd  
 Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B101  
 Specifier:  
 Designer:  
 Company:  
 Misc:

**Town of Innisfil Certified Model**  
 12/03/2018 9:39:10 AM kgervais



Total Horizontal Product Length = 04-02-08

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B0, 4-3/4"	1,235 / 0	637 / 0		
B1, 5-3/4"	1,316 / 0	677 / 0		

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-09-04	04-02-08	585	292			n/a
1	-	Conc. Pt. (lbs)	L	00-01-04	00-01-04	540	270			n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,626 ft-lbs	25,408 ft-lbs	6.4%	1	02-01-04
End Shear	1,448 lbs	11,571 lbs	12.5%	1	02-11-04
Total Load Defl.	L/999 (0.005")	n/a	n/a	4	02-00-12
Live Load Defl.	L/999 (0.003")	n/a	n/a	5	02-00-12
Max Defl.	0.005"	n/a	n/a	4	02-00-12
Span / Depth	4.4	n/a	n/a		00-00-00


**Bearing Supports**

	Dim. (L x W)	Demand	Demand / Support Resistance	Demand / Member Resistance	Material
B0	Wall/Plate 4-3/4" x 3-1/2"	2,650 lbs	19.6%	13.1%	Unspecified
B1	Wall/Plate 5-3/4" x 3-1/2"	2,820 lbs	17.3%	11.5%	Unspecified

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume unbraced length of Top: 00-02-12, Bottom: 00-02-12.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor: Normal Part code: Part 9

**CONFORMS TO OBC 2012**



DWG NO. TAM 45717-17  
 STRUCTURAL  
 COMPONENT ONLY

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: S32-1-12.EL B.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B1


Specifier:

Designer:

Company:

Misc:

**Connection Diagram**



a minimum = 1"    c = 7-1/2"  
 b minimum = 3"    d = 6"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record. Member has no side loads.

Connectors are: 16d Nails

**3 1/2" ARDOX SPIRAL**

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 45717-17  
 STRUCTURAL  
 COMPONENT ONLY



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B11(i4140)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:55

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: S32-1-12.EL B.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B11(i4140)

Specifier:


Designer:

Company:

Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:39:13 AM kgervais



Total Horizontal Product Length = 13-03-06

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 4-3/8"	388 / 0	584 / 0		
B1, 5-1/2"	863 / 0	844 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	13-00-02	4	2			n/a
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	08-11-06	3				n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-04-06	13-00-02		43			n/a
3	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-04-06	08-11-06		13			n/a
4	FC2 Floor Material	Unf. Lin. (lb/ft)	L	08-11-06	13-00-02	24	25			n/a
5	B13(i4187)	Conc. Pt. (lbs)	L	09-00-04	09-00-04	1,079	571			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	8,003 ft-lbs	12,704 ft-lbs	63%	1	09-00-04
End Shear	2,215 lbs	5,785 lbs	38.3%	1	12-00-06
Total Load Defl.	L/270 (0.56")	0.629"	89%	6	07-00-00
Live Load Defl.	L/544 (0.278")	0.419"	66.2%	8	07-02-15
Max Defl.	0.56"	n/a	n/a	6	07-00-00
Span / Depth	15.9	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	Wall/Plate 4-3/8" x 1-3/4"	1,312 lbs	32.1%	14%	Unspecified
B1	Wall/Plate 5-1/2" x 1-3/4"	2,349 lbs	45.7%	20%	Unspecified

### Notes



*PKZ*



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B11(i4140)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:55

BC CALC® Design Report



Build 5033  
Job Name:  
Address:  
City, Province, Postal Code:  
Customer:  
Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
Description: Designs\Flush Beams\1st Floor\Flush Beams\B11(i4140)  
Specifier:  
Designer:  
Company:  
Misc:

Design meets Code minimum (L/240) Total load deflection criteria.  
Design meets Code minimum (L/360) Live load deflection criteria.  
Calculations assume member is fully braced.  
Resistance Factor phi has been applied to all presented results per CSA O86.  
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
Design based on Dry Service Condition.  
Importance Factor : Normal Part code : Part 9

**CONFORMS TO OBC 2012**

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



*PK*

DWG NO. TAM 45718-17  
STRUCTURAL  
COMPONENT ONLY


BC CALC® Design Report



Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.mmd  
 Description: Designs\Flush Beams\1st Floor\Flush Beams\B12(i4999)  
 Specifier:  
 Designer:  
 Company:  
 Misc:

**Town of Innisfil Certified Model**  
 12/03/2018 9:39:15 AM kgervais




Total Horizontal Product Length = 13-04-08

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B0, 5-1/2"	1,223 / 69	937 / 0	0 / 157	
B1, 5-1/2"	1,479 / 56	1,110 / 0	0 / 125	

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC2 Floor Material	Unf. Lin. (lb/ft)	L	07-00-04	09-01-06		33			n/a
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	09-01-06	13-01-04	10	35			n/a
2	J3(i5070)	Conc. Pt. (lbs)	L	00-09-04	00-09-04	125	106			n/a
3	-	Conc. Pt. (lbs)	L	01-11-10	01-11-10	212	193	-23		n/a
4	-	Conc. Pt. (lbs)	L	01-11-10	01-11-10	-9				n/a
5	J3 DJ (i5100)	Conc. Pt. (lbs)	L	02-11-00	02-11-00	142	58	-116		n/a
6	J3 DJ (i5100)	Conc. Pt. (lbs)	L	02-11-00	02-11-00	-39				n/a
7	J2(i5011)	Conc. Pt. (lbs)	L	04-00-04	04-00-04	171	127			n/a
8	J2(i5011)	Conc. Pt. (lbs)	L	04-00-04	04-00-04	-6				n/a
9	J2(i5140)	Conc. Pt. (lbs)	L	05-00-04	05-00-04	162	121			n/a
10	J2(i5140)	Conc. Pt. (lbs)	L	05-00-04	05-00-04	-5				n/a
11	J2(i5094)	Conc. Pt. (lbs)	L	06-00-04	06-00-04	162	121			n/a
12	J2(i5094)	Conc. Pt. (lbs)	L	06-00-04	06-00-04	-5				n/a
13	J2(i5138)	Conc. Pt. (lbs)	L	07-00-04	07-00-04	159	105			n/a
14	J2(i5138)	Conc. Pt. (lbs)	L	07-00-04	07-00-04	-5				n/a
15	-	Conc. Pt. (lbs)	L	07-11-06	07-11-06	205	125			n/a
16	-	Conc. Pt. (lbs)	L	07-11-06	07-11-06	-5				n/a
17	-	Conc. Pt. (lbs)	L	09-01-05	09-01-05	776	378	-121		n/a
18	-	Conc. Pt. (lbs)	L	09-01-05	09-01-05	-41				n/a
19	B8(i5095)	Conc. Pt. (lbs)	L	09-11-12	09-11-12	133	98	-22		n/a
20	B8(i5095)	Conc. Pt. (lbs)	L	09-11-12	09-11-12	-10				n/a
21	J3(i5083)	Conc. Pt. (lbs)	L	10-07-08	10-07-08	152	106			n/a
22	J3(i4951)	Conc. Pt. (lbs)	L	11-11-08	11-11-08	249	173			n/a



*pkll*

DWG NO. TAM 45719-17  
 STRUCTURAL  
 COMPONENT ONLY



BC CALC® Design Report



Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.mmdl  
 Description: Designs\Flush Beams\1st Floor\Flush Beams\B12(i4999)  
 Specifier:  
 Designer:  
 Company:  
 Misc:

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	11,328 ft-lbs	25,408 ft-lbs	44.6%	21	07-09-07
End Shear	3,533 lbs	11,571 lbs	30.5%	21	12-01-08
Total Load Defl.	L/331 (0.456")	0.629"	72.4%	56	06-09-04
Live Load Defl.	L/570 (0.265")	0.419"	63.2%	83	06-09-04
Max Defl.	0.456"	n/a	n/a	56	06-09-04
Span / Depth	15.9	n/a	n/a		00-00-00

**Disclosure**  
 Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.


Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Post	5-1/2" x 3-1/2"	3,006 lbs	29.2%	12.8%	Unspecified
B1 Wall/Plate	5-1/2" x 3-1/2"	3,605 lbs	35.1%	15.4%	Unspecified

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
**CONFORMS TO OBC 2012**  
 Unbalanced snow loads determined from building geometry were used in selected product's verification.  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9

**Connection Diagram**



a minimum = 1"      c = 7-1/2"      6"  
 b minimum = 3"      d = 6"

Calculated Side Load = 306.6 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d Nails  
 3 1/2" ARDOX SPIRAL



10/2/17  
 DWG NO. TAM 45719-17  
 STRUCTURAL  
 COMPONENT ONLY

BC CALC® Design Report




Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
 Description: Designs\Flush Beams\1st Floor\Flush Beams\B12A(i413:  
 Specifier:  
 Designer:  
 Company:  
 Misc:

Town of Innisfil Certified Model

12/03/2018 9:39:18 AM kgervais



Total Horizontal Product Length = 13-04-08

### Reaction Summary (Down / Uplift) ( lbs )

Bearing	Live	Dead	Snow	Wind
B0, 5-1/2"	333 / 0	565 / 0		
B1, 5-1/2"	599 / 0	752 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	07-08-10	17	8			n/a
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-05-08	07-08-10		50			n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	07-08-10	13-01-04	14	37			n/a
3	FC2 Floor Material	Unf. Lin. (lb/ft)	L	07-08-10	09-01-06		33			n/a
4	FC2 Floor Material	Unf. Lin. (lb/ft)	L	09-01-06	13-01-04	10	35			n/a
5	B14(i4181)	Conc. Pt. (lbs)	L	07-09-07	07-09-07	57	41			n/a
6	B13(i4187)	Conc. Pt. (lbs)	L	09-01-06	09-01-06	620	341			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	6,003 ft-lbs	25,408 ft-lbs	23.6%	1	09-01-06
End Shear	1,701 lbs	11,571 lbs	14.7%	1	12-01-08
Total Load Defl.	L/662 (0.228")	0.629"	36.3%	4	07-00-02
Live Load Defl.	L/999 (0.102")	n/a	n/a	5	07-01-06
Max Defl.	0.228"	n/a	n/a	4	07-00-02
Span / Depth	15.9	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Post	5-1/2" x 3-1/2"	792 lbs	11.8%	5.2%	Unspecified
B1 Wall/Plate	5-1/2" x 3-1/2"	1,839 lbs	17.9%	7.8%	Unspecified

### Notes



*PLK*

BC CALC® Design Report



Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
 Description: Designs\Flush Beams\1st Floor\Flush Beams\B12A(i4132)  
 Specifier:  
 Designer:  
 Company:  
 Misc:

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9


**CONFORMS TO OBC 2012**

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

**Connection Diagram**



a minimum = 1"      c = 7-1/2"  
 b minimum = 3"      d = 6"

Calculated Side Load = 111.6 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.  
 Connectors are: 3 1/2" ARDOX SPIRAL Nails

**3 1/2" ARDOX SPIRAL**





# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B13(i4187)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:54

BC CALC® Design Report




Build 5033  
Job Name:  
Address:  
City, Province, Postal Code:  
Customer:  
Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
Description: Designs\Flush Beams\1st Floor\Flush Beams\B13(i4187);  
Specifier:  
Designer:  
Company:  
Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:40:28 AM kgervais



09-06-00

B0

B1

Total Horizontal Product Length = 09-06-00

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	1,084 / 0	574 / 0		
B1	614 / 0	338 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	User Load	Unf. Lin. (lb/ft)	L	00-00-01	03-06-01	240	120			n/a
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	03-01-04	09-06-00	1	1			n/a
2	J2(i4221)	Conc. Pt. (lbs)	L	01-01-08	01-01-08	98	49			n/a
3	J2(i4218)	Conc. Pt. (lbs)	L	02-03-00	02-03-00	102	51			n/a
4	-	Conc. Pt. (lbs)	L	03-08-12	03-08-12	158	95			n/a
5	J2(i4177)	Conc. Pt. (lbs)	L	05-01-08	05-01-08	117	58			n/a
6	J2(i4217)	Conc. Pt. (lbs)	L	06-05-08	06-05-08	108	54			n/a
7	J2(i4226)	Conc. Pt. (lbs)	L	07-09-08	07-09-08	108	54			n/a
8	J2(i4232)	Conc. Pt. (lbs)	L	09-01-08	09-01-08	75	39			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	4,051 ft-lbs	12,704 ft-lbs	31.9%	1	03-07-00
End Shear	1,852 lbs	5,785 lbs	32%	1	00-11-08
Total Load Defl.	L/644 (0.173")	0.465"	37.3%	4	04-07-02
Live Load Defl.	L/999 (0.112")	n/a	n/a	5	04-07-02
Max Defl.	0.173"	n/a	n/a	4	04-07-02
Span / Depth	11.7	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	Hanger 2" x 1-3/4"	2,343 lbs	n/a	54.9%	HUS1.81/10
B1	Hanger 2" x 1-3/4"	1,344 lbs	n/a	31.5%	HUS1.81/10

### Notes



*12/2*



BC CALC® Design Report

Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B13(i4187)

Specifier:

Designer:

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

**CONFORMS TO OBC 2012**

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



*pmh*

DWG NO. TAM 4574-17  
STRUCTURAL  
COMPONENT ONLY



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B14(i4181)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:54

BC CALC® Design Report




Build 5033  
Job Name:  
Address:  
City, Province, Postal Code:  
Customer:  
Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
Description: Designs\Flush Beams\1st Floor\Flush Beams\B14(i4181)  
Specifier:  
Designer:  
Company:  
Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:40:30 AM kgervais



06-02-01

B0

B1

Total Horizontal Product Length = 06-02-01

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	32 / 0	31 / 0		
B1	60 / 0	45 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
0	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	05-10-14	1	1			n/a
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	05-10-14	06-02-01	55	27			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	171 ft-lbs	12,704 ft-lbs	1.3%	1	03-05-01
End Shear	135 lbs	5,785 lbs	2.3%	1	05-02-09
Total Load Defl.	L/999 (0.003")	n/a	n/a	4	03-01-13
Live Load Defl.	L/999 (0.002")	n/a	n/a	5	03-02-10
Max Defl.	0.003"	n/a	n/a	4	03-01-13
Span / Depth	7.5	n/a	n/a		00-00-00

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 1-3/4"	86 lbs	n/a	2%	LS 90
B1 Hanger	2" x 1-3/4"	147 lbs	n/a	3.4%	LS 90

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
Design meets Code minimum (L/360) Live load deflection criteria.  
Calculations assume unbraced length of Top: 00-04-07, Bottom: 00-04-07.  
Hanger Manufacturer: Unassigned  
Resistance Factor phi has been applied to all presented results per CSA O86.  
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
Design based on Dry Service Condition.  
Importance Factor : Normal Part code : Part 9

**CONFORMS TO OBC 2012**

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



1  
BWO NO. TAM 45722-17  
STRUCTURAL  
COMPONENT ONLY



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B15(i4233)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:53

BC CALC® Design Report




Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
 Description: Designs\Flush Beams\Basement\Flush Beams\B15(i4233)  
 Specifier:  
 Designer:  
 Company:  
 Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:40:36 AM kgervais



Total Horizontal Product Length = 09-02-06

Reaction Summary (Down / Uplift) (lbs)		Dead	Snow	Wind
Bearing	Live			
B0, 3-1/2"	445 / 0	250 / 0		
B1, 4-3/8"	320 / 0	186 / 0		

Load Summary		Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
Tag	Description				1.00	0.65	1.00	1.15	
0	FC1 Floor Material	L	00-00-01	03-03-08	14	7			n/a
1	FC1 Floor Material	L	03-03-08	09-02-06	27	13			n/a
2	-	L	03-04-06	03-04-06	563	290			n/a

Controls Summary		Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment		2,873 ft-lbs	12,704 ft-lbs	22.6%	1	03-04-06
End Shear		965 lbs	5,785 lbs	16.7%	1	01-01-00
Total Load Defl.		L/999 (0.092")	n/a	n/a	4	04-03-12
Live Load Defl.		L/999 (0.059")	n/a	n/a	5	04-03-12
Max Defl.		0.092"	n/a	n/a	4	04-03-12
Span / Depth		10.9	n/a	n/a		00-00-00

Bearing Supports		Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	Post	3-1/2" x 1-3/4"	980 lbs	19.7%	13.1%	Unspecified
B1	Wall/Plate	4-3/8" x 1-3/4"	712 lbs	17.4%	7.6%	Unspecified


### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
**CONFORMS TO OBC 2012**  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCK®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.P.C.





# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B16(i4184)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:54

BC CALC® Design Report



Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
 Description: Designs\Flush Beams\Basement\Flush Beams\B16(i4184)  
 Specifier:  
 Designer:  
 Company:  
 Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:40:37 AM kgervais



Total Horizontal Product Length = 02-04-04

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 1-3/4"	177 / 0	94 / 0		
B1, 1-3/4"	148 / 0	79 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
0	J3(i4139)	Conc. Pt. (lbs)	L	00-06-08	00-06-08	150	75			n/a
1	J3(i4186)	Conc. Pt. (lbs)	L	01-06-08	01-06-08	175	87			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	232 ft-lbs	12,704 ft-lbs	1.8%	1	01-06-08
End Shear	258 lbs	5,785 lbs	4.5%	1	01-05-00
Total Load Defl.	L/999 (0.001")	n/a	n/a	4	01-02-02
Live Load Defl.	L/999 (0")	n/a	n/a	5	01-02-02
Max Defl.	0.001"	n/a	n/a	4	01-02-02
Span / Depth	2.8	n/a	n/a		00-00-00

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Post	1-3/4" x 1-3/4"	382 lbs	15.4%	10.2%	Unspecified
B1 Post	1-3/4" x 1-3/4"	322 lbs	12.9%	8.6%	Unspecified

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume unbraced length of Top: 00-00-00, Bottom: 00-00-00.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.





BC CALC® Design Report




Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mxd  
 Description: Designs\Flush Beams\Basement\Flush Beams\B17(i4194  
 Specifier:  
 Designer:  
 Company:  
 Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:40:39 AM kgervais



Total Horizontal Product Length = 12-06-06

**Reaction Summary (Down / Uplift) ( lbs )**

Bearing	Live	Dead	Snow	Wind
B0, 2-1/2"	1,628 / 0	1,286 / 0		
B1, 2-3/8"	253 / 0	552 / 0		

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	12-06-06	16	8			n/a
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	06-02-00	7	4			n/a
2	User Load	Unf. Lin. (lb/ft)	L	00-02-08	12-03-06		60			n/a
3	FC1 Floor Material	Unf. Lin. (lb/ft)	L	06-02-00	12-06-06	6	3			n/a
4	5(i839)	Conc. Pt. (lbs)	L	00-00-04	00-00-04	1,364	726			n/a
5	B19(i4103)	Conc. Pt. (lbs)	L	06-01-02	06-01-02	235	126			n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	2,662 ft-lbs	16,515 ft-lbs	16.1%	0	06-01-02
End Shear	744 lbs	7,521 lbs	9.9%	0	11-06-08
Total Load Defl.	L/965 (0.152")	0.612"	24.9%	4	06-03-00
Live Load Defl.	L/999 (0.054")	n/a	n/a	5	06-03-00
Max Defl.	0.152"	n/a	n/a	4	06-03-00
Span / Depth	15.5	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Beam	2-1/2" x 3-1/2"	4,050 lbs	86.7%	37.9%	Unspecified
B1 Wall/Plate	2-3/8" x 3-1/2"	772 lbs	26.8%	11.7%	Unspecified

**Notes**



*pc 1/2*

BC CALC® Design Report



Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
 Description: Designs\Flush Beams\Basement\Flush Beams\B17(i4194)  
 Specifier:  
 Designer:  
 Company:  
 Misc:

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9


**CONFORMS TO DBC 2012**

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

**Connection Diagram**



a minimum = 1"  
 b minimum = 3"  
 c = 1-1/2"  
 d = 4"

Calculated Side Load = 40.7 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 3 1/2" ARDOX SPIRAL Nails



DWG NO. TAM 45725-17  
 STRUCTURAL  
 COMPONENT ONLY

BC CALC® Design Report




Build 5033  
 Job Name:  
 Address:  
 City, Province, Postal Code:  
 Customer:  
 Code reports: CCMC 12472-R

File Name: S32-1-12.EL B.mmdl  
 Description: Designs\Flush Beams\Basement\Flush Beams\B18L(i403  
 Specifier:  
 Designer:  
 Company:  
 Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:40:41 AM kgervais



Reaction Summary (Down / Uplift) (lbs)				
Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	257 / 0	106 / 0		
B1, 4-3/8"	201 / 0	86 / 0		

Load Summary		Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
Tag	Description					1.00	0.65	1.00	1.15	
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-06-08	03-06-08	119	45			n/a
1	J4(i4034)	Conc. Pt. (lbs)	L	00-01-10	00-01-10	75	28			n/a

Controls Summary		Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment		417 ft-lbs	12,704 ft-lbs	3.3%	1	02-00-08
End Shear		350 lbs	5,785 lbs	6.1%	1	01-01-00
Total Load Defl.		L/999 (0.002")	n/a	n/a	4	01-11-12
Live Load Defl.		L/999 (0.002")	n/a	n/a	5	01-11-12
Max Defl.		0.002"	n/a	n/a	4	01-11-12
Span / Depth		4.4	n/a	n/a		00-00-00

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports		Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	Post	3-1/2" x 1-3/4"	517 lbs	10.4%	6.9%	Unspecified
B1	Wall/Plate	4-3/8" x 1-3/4"	409 lbs	10%	4.4%	Unspecified

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9

**CONFORMS TO OBC 2012**





# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B19(i4103)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 5, 2017 09:33:53

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: S32-1-12.EL B.mmdl

Description: Designs\Flush Beams\Basement\Flush Beams\B19(i4103)

Specifier:


Designer:

Company:

Misc:

**Town of Innisfil Certified Model**

12/03/2018 9:40:43 AM kgervais



Total Horizontal Product Length = 04-00-06

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	236 / 0	127 / 0		
B1, 4-3/8"	206 / 0	114 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC1 Floor Material	Unf. Lin. (lb/ft)	L	03-00-10	04-00-06	12	6			n/a
1	J4(i4104)	Conc. Pt. (lbs)	L	00-02-08	00-02-08	72	36			n/a
2	J4(i4097)	Conc. Pt. (lbs)	L	01-00-04	01-00-04	114	57			n/a
3	J4(i4088)	Conc. Pt. (lbs)	L	02-00-10	02-00-10	126	63			n/a
4	J4(i4078)	Conc. Pt. (lbs)	L	03-00-10	03-00-10	119	60			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	456 ft-lbs	12,704 ft-lbs	3.6%	1	02-00-10
End Shear	379 lbs	5,785 lbs	6.5%	1	02-10-08
Total Load Defl.	L/999 (0.003")	n/a	n/a	4	01-11-01
Live Load Defl.	L/999 (0.002")	n/a	n/a	5	01-11-01
Max Defl.	0.003"	n/a	n/a	4	01-11-01
Span / Depth	4.6	n/a	n/a		00-00-00

### Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 1-3/4"	514 lbs	n/a	12%	HUS1.81/10
B1 Wall/Plate	4-3/8" x 1-3/4"	451 lbs	11%	4.8%	Unspecified

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA

O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

**CONFORMS TO OBC 2012**

**DWONG TAM 4572-17  
STRUCTURAL  
COMPONENT ONLY**

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.







### Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf  
Simple Spans, L/480 Deflection Limit  
5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-2"	13'-9"	N/A	15'-7"	14'-8"	14'-2"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
14"	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-9"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
16"	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-8"	15'-3"	14'-5"	N/A	16'-8"	15'-3"	14'-5"	N/A
	NI-40x	17'-11"	16'-11"	16'-1"	N/A	18'-5"	17'-1"	16'-1"	N/A
	NI-60	18'-2"	17'-1"	16'-4"	N/A	18'-7"	17'-4"	16'-4"	N/A
	NI-70	19'-2"	17'-10"	17'-2"	N/A	19'-7"	18'-3"	17'-7"	N/A
	NI-80	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
11-7/8"	NI-20	19'-6"	18'-1"	17'-3"	N/A	19'-11"	18'-3"	17'-3"	N/A
	NI-40x	21'-0"	19'-6"	18'-8"	N/A	21'-7"	20'-2"	19'-2"	N/A
	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-6"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
14"	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-11"	20'-11"	N/A	24'-3"	22'-7"	21'-7"	N/A
	NI-60	24'-0"	22'-3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
16"	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-2"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



### Maximum Floor Spans




Live Load = 40 psf, Dead Load = 15 psf  
Simple Spans, L/480 Deflection Limit  
3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"
	NI-40x	17'-0"	16'-0"	15'-5"	14'-9"	17'-5"	16'-5"	15'-10"	15'-2"
	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-6"	16'-7"	15'-11"	15'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-7"	18'-5"	17'-3"	16'-7"	15'-11"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
11-7/8"	NI-20	17'-10"	16'-10"	16'-2"	15'-6"	18'-6"	17'-4"	16'-9"	16'-1"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-6"	19'-11"	18'-6"	17'-9"	17'-0"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-11"	22'-1"	20'-6"	19'-7"	18'-7"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking			Mid-Span Blocking and 1/2" Gypsum Ceiling				
		On Centre Spacing			On Centre Spacing				
		12"	16"	19.2"	12"	16"	19.2"	24"	
9-1/2"	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"
	NI-40x	18'-8"	17'-2"	16'-3"	15'-2"	18'-10"	17'-2"	16'-3"	15'-2"
	NI-60	18'-11"	17'-6"	16'-6"	15'-5"	19'-2"	17'-6"	16'-6"	15'-5"
	NI-70	20'-0"	18'-7"	17'-9"	16'-7"	20'-5"	18'-11"	17'-10"	16'-7"
11-7/8"	NI-80	20'-3"	18'-10"	17'-11"	16'-10"	20'-8"	19'-3"	18'-2"	16'-10"
	NI-20	20'-1"	18'-5"	17'-5"	16'-2"	20'-1"	18'-5"	17'-5"	16'-2"
	NI-40x	21'-10"	20'-4"	19'-4"	17'-8"	22'-5"	20'-6"	19'-4"	17'-8"
	NI-60	22'-1"	20'-7"	19'-7"	18'-4"	22'-8"	20'-10"	19'-8"	18'-4"
	NI-70	23'-4"	21'-8"	20'-8"	19'-7"	23'-10"	22'-3"	21'-2"	19'-9"
14"	NI-80	23'-7"	21'-11"	20'-11"	19'-9"	24'-1"	22'-6"	21'-5"	20'-0"
	NI-90x	24'-3"	22'-6"	21'-6"	20'-4"	24'-8"	23'-0"	22'-0"	20'-9"
	NI-40x	24'-5"	22'-9"	21'-8"	19'-5"	25'-1"	23'-2"	22'-9"	19'-5"
	NI-60	24'-10"	23'-1"	22'-0"	20'-10"	25'-6"	23'-8"	22'-4"	20'-10"
	NI-70	26'-1"	24'-3"	23'-2"	21'-10"	26'-8"	24'-11"	23'-9"	22'-4"
16"	NI-80	26'-6"	24'-7"	23'-5"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"
	NI-90x	27'-3"	25'-4"	24'-1"	22'-9"	27'-9"	25'-11"	24'-8"	23'-4"
	NI-60	27'-3"	25'-5"	24'-2"	22'-10"	28'-0"	26'-2"	24'-9"	23'-1"
	NI-70	28'-8"	26'-8"	25'-4"	23'-11"	29'-3"	27'-4"	26'-1"	24'-8"
	NI-80	29'-1"	27'-0"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
NI-90x	29'-11"	27'-10"	26'-6"	25'-0"	30'-6"	28'-5"	27'-2"	25'-8"	

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



### Maximum Floor Spans



Live Load = 40 psf, Dead Load = 30 psf  
Simple Spans, L/480 Deflection Limit  
5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
14"	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
16"	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	17'-9"	16'-1"	15'-1"	N/A	17'-9"	16'-1"	15'-1"	N/A
	NI-60	18'-1"	16'-4"	15'-4"	N/A	18'-1"	16'-4"	15'-4"	N/A
	NI-70	19'-2"	17'-10"	16'-9"	N/A	19'-7"	17'-10"	16'-9"	N/A
	NI-80	19'-5"	18'-0"	17'-1"	N/A	19'-10"	18'-3"	17'-1"	N/A
11-7/8"	NI-20	18'-9"	17'-0"	16'-0"	N/A	18'-9"	17'-0"	16'-0"	N/A
	NI-40x	21'-0"	19'-3"	17'-9"	N/A	21'-3"	19'-3"	17'-9"	N/A
	NI-60	21'-4"	19'-8"	18'-5"	N/A	21'-8"	19'-8"	18'-5"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-4"	20'-0"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-5"	N/A
	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
14"	NI-40x	23'-7"	21'-5"	19'-6"	N/A	24'-1"	21'-5"	19'-6"	N/A
	NI-60	24'-0"	22'-3"	21'-0"	N/A	24'-8"	22'-5"	21'-0"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-9"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
16"	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	24'-10"	23'-4"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



### Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf  
Simple Spans, L/480 Deflection Limit  
3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-0"	16'-0"	15'-1"	13'-11"	17'-5"	16'-1"	15'-1"	13'-11"
	NI-60	17'-2"	16'-2"	15'-5"	14'-3"	17'-6"	16'-5"	15'-5"	14'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-6"	18'-5"	17'-3"	16'-7"	15'-6"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	15'-10"
11-7/8"	NI-20	17'-10"	16'-10"	16'-0"	14'-10"	18'-6"	17'-1"	16'-0"	14'-10"
	NI-40x	19'-4"	17'-11"	17'-3"	15'-10"	19'-11"	18'-6"	17'-9"	15'-10"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-1"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-5"	22'-1"	20'-6"	19'-6"	17'-5"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-9"	16'-1"	15'-1"	13'-11"	17'-9"	16'-1"	15'-1"	13'-11"
	NI-60	18'-1"	16'-5"	15'-5"	14'-3"	18'-1"	16'-5"	15'-5"	14'-3"
	NI-70	19'-10"	17'-11"	16'-9"	15'-6"	19'-10"	17'-11"	16'-9"	15'-6"
	NI-80	20'-2"	18'-3"	17'-1"	15'-10"	20'-2"	18'-3"	17'-1"	15'-10"
11-7/8"	NI-20	18'-10"	17'-1"	16'-0"	14'-10"	18'-10"	17'-1"	16'-0"	14'-10"
	NI-40x	21'-3"	19'-3"	17'-9"	15'-10"	21'-3"	19'-3"	17'-9"	15'-10"
	NI-60	21'-9"	19'-8"	18'-5"	17'-1"	21'-9"	19'-8"	18'-5"	17'-1"
	NI-70	23'-4"	21'-5"	20'-1"	18'-6"	23'-8"	21'-5"	20'-1"	18'-6"
	NI-80	23'-7"	21'-10"	20'-5"	18'-11"	24'-1"	21'-10"	20'-5"	18'-11"
14"	NI-90x	24'-3"	22'-6"	21'-3"	19'-7"	24'-8"	22'-7"	21'-3"	19'-7"
	NI-40x	24'-2"	21'-5"	19'-6"	17'-5"	24'-2"	21'-5"	19'-6"	17'-5"
	NI-60	24'-9"	22'-5"	21'-0"	19'-6"	24'-9"	22'-5"	21'-0"	19'-6"
	NI-70	26'-1"	24'-3"	22'-9"	21'-0"	26'-8"	24'-3"	22'-9"	21'-0"
	NI-80	26'-6"	24'-7"	23'-3"	21'-6"	27'-1"	24'-10"	23'-3"	21'-6"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-4"	27'-9"	25'-10"	24'-3"	22'-4"
	NI-60	27'-3"	24'-11"	23'-5"	21'-7"	27'-6"	24'-11"	23'-5"	21'-7"
	NI-70	28'-8"	26'-8"	25'-3"	23'-4"	29'-3"	26'-11"	25'-3"	23'-4"
	NI-80	29'-1"	27'-0"	25'-9"	23'-10"	29'-8"	27'-6"	25'-10"	23'-10"
NI-90x	29'-11"	27'-10"	26'-6"	24'-10"	30'-6"	28'-5"	26'-11"	24'-10"	


1. Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
2. Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
3. Minimum bearing length shall be 1-3/4 inches for the end bearings.
4. Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
5. This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
6. Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



# INORDIC

ENGINEERED WOOD

## INSTALLATION GUIDE FOR RESIDENTIAL FLOORS



Distributed by:

2015-04-16



N-C301 / November 2014

### SAFETY AND CONSTRUCTION PRECAUTIONS



Do not walk on I-joists until fully fastened and braced, or serious injuries can result.



Never stack building materials over unsheathed I-joists. Once sheathed, do not over-stress I-joist with concentrated loads from building materials.

#### WARNING

I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.


#### Avoid Accidents by Following these Important Guidelines:

1. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-bridging at joist ends. When I-joists are applied continuous over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
  - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on center, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.
  - Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bridging.
4. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
5. Never install a damaged I-joist.

Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.

### STORAGE AND HANDLING GUIDELINES

1. Bundle wrap can be slippery when wet. Avoid walking on wrapped bundles.
2. Store, stack, and handle I-joists vertically and level only.
3. Always stack and handle I-joists in the upright position only.
4. Do not store I-joists in direct contact with the ground and/or flatwise.
5. Protect I-joists from weather, and use spacers to separate bundles.
6. Bundled units should be kept intact until time of installation.
7. When handling I-joists with a crane on the job site, take a few simple precautions to prevent damage to the I-joists and injury to your work crew.
  - Pick I-joists in bundles as shipped by the supplier.
  - Orient the bundles so that the webs of the I-joists are vertical.
  - Pick the bundles at the 5th points, using a spreader bar if necessary.
8. Do not handle I-joists in a horizontal orientation.
9. NEVER USE OR TRY TO REPAIR A DAMAGED I-JOIST.



# MAXIMUM FLOOR SPANS

1. Maximum clear spans applicable to simple-span or multiple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of  $1.50L + 1.25D$ . The serviceability limit states include the consideration for floor vibration and a live load deflection limit of  $L/480$ . For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
2. Spans are based on a composite floor with glued-notched oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less, or 3/4 inch for joist spacing of 24 inches. Adhesive shall meet the requirements given in CGS-71.26 Standard. No concrete topping or bridging element was assumed. Increased spans may be achieved with the use of gypsum and/or a row of blocking at mid-span.
3. Minimum bearing length shall be 1-3/4 inches for the end bearings, and 3-1/2 inches for the intermediate bearings.
4. Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
5. This span chart is based on uniform loads. For applications with other than uniform loads, an engineering analysis may be required based on the use of the design properties.
6. Tables are based on Limit States Design per CAN/CSA O86-09 Standard, and NBC 2010.
7. SI units conversion: 1 inch = 25.4 mm  
1 foot = 0.305 m


## MAXIMUM FLOOR SPANS FOR NORDIC I-JOISTS SIMPLE AND MULTIPLE SPANS

Joist Depth	Joist Series	Simple spans				Multiple spans			
		12'	16'	19.2'	24'	12'	16'	19.2'	24'
12"	NI-20	15.4	14.2	13.9	13.5	6.3	5.4	4.1	3.4
12"	NI-40	16.1	15.2	14.8	14.9	6.3	5.4	4.1	3.4
12"	NI-60	16.9	15.4	14.1	14.1	6.5	5.5	4.0	3.5
12"	NI-70	17.1	15.4	14.1	14.1	6.5	5.5	4.0	3.5
12"	NI-80	17.3	15.4	14.1	14.1	6.5	5.5	4.0	3.5
12"	NI-90	17.3	15.4	14.1	14.1	6.5	5.5	4.0	3.5
12"	NI-90x	17.3	15.4	14.1	14.1	6.5	5.5	4.0	3.5
16"	NI-20	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
16"	NI-40	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
16"	NI-60	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
16"	NI-70	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
16"	NI-80	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
16"	NI-90	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
16"	NI-90x	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
19.2"	NI-20	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
19.2"	NI-40	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
19.2"	NI-60	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
19.2"	NI-70	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
19.2"	NI-80	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
19.2"	NI-90	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
19.2"	NI-90x	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
24"	NI-20	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
24"	NI-40	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
24"	NI-60	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
24"	NI-70	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
24"	NI-80	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
24"	NI-90	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4
24"	NI-90x	18.1	16.7	15.3	15.3	6.3	5.4	4.1	3.4

CGS EVALUATION REPORT 130923-R

# I-JOIST HANGERS

1. Hangers shown illustrate the three most commonly used metal hangers to support I-joists.
2. All nailing must meet the hanger manufacturer's recommendations.
3. Hangers should be selected based on the joist depth, flange width and load capacity based on the maximum spans.
4. Web stiffeners are required when the sides of the hangers do not laterally brace the top flange of the I-joist.




# WEB STIFFENERS

## RECOMMENDATIONS:

- A bearing stiffener is required in all engineered applications with factored reactions greater than shown in the I-joist properties table found in the Construction Guide (C101). The gap between the stiffener and the flange is of the top.
  - A bearing stiffener is required when the I-joist is supported in a hanger and the sides of the hanger do not extend up to, and support, the top flange. The gap between the stiffener and flange is at the top.
  - A load stiffener is required at locations where a factored concentrated load greater than 2,370 lbs is applied to the top flange between supports, or in the case of a cantilever, anywhere between the cantilever tip and the support. These values are for standard term load duration, and may be adjusted for other load durations as permitted by the code. The gap between the stiffener and the flange is at the bottom.
- SI units conversion: 1 inch = 25.4 mm


FIGURE 2  
WEB STIFFENER INSTALLATION DETAILS



## STIFFENER SIZE REQUIREMENTS

Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width

# NORDIC I-JOIST SERIES




Chantiers Chibougamau Ltd. harvests its own trees, which enables Nordic products to adhere to strict quality control procedures throughout the manufacturing process. Every phase of the operation, from forest to the finished product, reflects our commitment to quality.

Nordic Engineered Wood I-joists use only finger-jointed back spruce lumber in their flanges, ensuring consistent quality, superior strength and longer span carrying capacity.

2015-04-16


# INSTALLING NORDIC I-JOISTS

1. Before laying out floor system components, verify that I-joist flange widths match hanger widths. If not, contact your supplier.
2. Except for cutting to length, I-joist flanges should **never** be cut, drilled, or notched.
3. Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple spans must be level.
5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings.
6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement.
7. Leave a 1/16-inch gap between the I-joist end and a header.
8. Concentrated loads greater than those that can normally be expected in residential construction should only be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment and security cameras. Never suspend unusual or heavy loads from the I-joist's bottom flange. Whenever possible, suspend all concentrated loads from the top of the I-joist. Or, attach the load to blocking that has been securely fastened to the I-joist webs.
9. Never install I-joists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or I-joist blocking panels.
11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (cripple members) to transfer gravity loads through the floor system to the wall or foundation below.
12. Due to shrinkage, common framing lumber set on edge **may never** be used as blocking or rim boards. I-joist blocking panels or other engineered wood products – such as rim board – must be cut to fit between the I-joists, and an I-joist-compatible depth selected.
13. Provide permanent lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly, support the bottom flange of all cantilevered I-joists at the end support next to the cantilever extension. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used.
14. If square-edge panels are used, edges must be supported between I-joists with 2x4 blocking. Glue panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed.
15. Nail spacing: Space nails installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.




**FIGURE 1**  
**TYPICAL NORDIC I-JOIST FLOOR FRAMING AND CONSTRUCTION DETAILS**

Some framing requirements such as erection bracing and blocking panels have been omitted for clarity.




All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
Nil joists	3,300

\*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
1-1/8" Rim Board Plus	8,090

\*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
Nil rim joist per detail 1a	Minimum 1-3/4" bearing required

\*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.











Pair of Squash Blocks	Maximum Factored Vertical per Pair of Squash Blocks (lbs)
2x Lumber	5,500
1-1/8" Rim Board Plus	4,300

\*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.



Pair of Squash Blocks	Maximum Factored Vertical per Pair of Squash Blocks (lbs)
2x Lumber	5,500
1-1/8" Rim Board Plus	4,300



\*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.



**BACKER BLOCKS** (Blocks must be long enough to permit required nailing without splitting)



Flange Width	Material Thickness Required*	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

\* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid sawn lumber and wood structural panels conforming to CAN/CSA-Q325 or CAN/CSA-Q437 Standard.  
 \*\* For face-mount hangers use net joist depth minus 3-1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4".



**FILLER BLOCK REQUIREMENTS FOR DOUBLE-I-JOIST CONSTRUCTION**


Flange Size	Joist Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2" x 11-7/8" x 14" x 14"	2-1/8" x 6" x 2-1/8" x 8" x 2-1/8" x 10" x 2-1/8" x 12"
3-1/2" x 1-1/2"	9-1/2" x 11-7/8" x 14" x 14"	3" x 6" x 3" x 8" x 3" x 10" x 3" x 12"
3-1/2" x 2"	11-7/8" x 14" x 14"	3" x 7" x 3" x 9" x 3" x 11"




- Notes:**
1. Support back of I-joist web during nailing to prevent damage to web/flange connection.
  2. Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
  3. Filler block is required between joists for full length of span.
  4. Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails can be clinched, only two nails per foot are required.
  5. The maximum factored load that may be applied to one side of the double I-joist using this detail is 860 lbf/ft. Verify double I-joist capacity.

# CANTILEVER DETAILS FOR BALCONIES (NO WALL LOAD)

## 3(a) I-JOIST CANTILEVER DETAIL FOR BALCONIES (No Wall Load)




## 3(b) LUMBER CANTILEVER DETAIL FOR BALCONIES (No Wall Load)



# CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

## 4(a) Method 1 — SHEATHING REINFORCEMENT ONE SIDE




## Method 2 — SHEATHING REINFORCEMENT TWO SIDES

- Use same installation as Method 1 but reinforce both sides of I-joist with sheathing.
- Use nailing pattern shown for Method 1 with opposite face nailing offset by 3\"/>


Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4\") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2\"/>

## 4(b) Alternate Method 2 — DOUBLE I-JOIST



Block I-joists together with filler blocks for the full length of the reinforcement. For I-joist flange widths greater than 3 inches place an additional row of 3\"/>

FIGURE 4 (continued)



## CANTILEVER REINFORCEMENT METHODS ALLOWED


JOIST DEPTH (in.)	ROOF TRUSS SPAN (ft)	ROOF LOADING (UNFACTORED)		
		U = 30 psf, DL = 15 psf	U = 40 psf, DL = 15 psf	U = 50 psf, DL = 15 psf
2-1/2"	12	X	X	X
	16	X	X	X
3-1/2"	12	X	X	X
	16	X	X	X
4-1/2"	12	X	X	X
	16	X	X	X
5-1/2"	12	X	X	X
	16	X	X	X
6-1/2"	12	X	X	X
	16	X	X	X
7-1/2"	12	X	X	X
	16	X	X	X
8-1/2"	12	X	X	X
	16	X	X	X
9-1/2"	12	X	X	X
	16	X	X	X
10-1/2"	12	X	X	X
	16	X	X	X
11-1/2"	12	X	X	X
	16	X	X	X
12-1/2"	12	X	X	X
	16	X	X	X

1. N = No reinforcement required.
  2. = NI reinforced with 3/4\"/>
- For larger openings, or multiple 3'-0\"/>
4. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam.
  5. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

**RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:**

1. The distance between the inside edge of the support and the centerline of any hole or duct chase opening shall be in compliance with the requirements of Table 1 or 2, respectively.
2. I-joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.
3. Whenever possible, field-cut holes should be centered on the middle of the web.
4. The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the hole or opening and the adjacent I-joist flange.
5. The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
6. Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the longest side of the longest rectangular hole or duct chase opening) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
7. A knockout is **not** considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
8. Holes measuring 1-1/2 inches or smaller shall be permitted anywhere in a cantilevered section of a joist. Holes of greater size may be permitted subject to verification.
9. A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
10. All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.
11. Limit three maximum size holes per span, of which one may be a duct chase opening.
12. A group of round holes at approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

**FIGURE 7  
FIELD-CUT HOLE LOCATOR**



A knockout is **NOT** considered a hole, may be utilized wherever it occurs and may be ignored for purposes of calculating minimum distances between holes.

**TABLE 1  
LOCATION OF CIRCULAR HOLES IN JOIST WEBS  
Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf**


Joist Depth	Joist Series	Minimum distance from inside face of any support to centre of hole (ft-in)												Span adjustment Factor																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
		2	3	4	5	6	6-1/4	7	8	8-5/8	9	10	10-3/4		11	12	12-3/4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
11-7/8	N-20	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9	5.2	5.5	5.8	6.1	6.4	6.7	7.0	7.3	7.6	7.9	8.2	8.5	8.8	9.1	9.4	9.7	10.0	10.3	10.6	10.9	11.2	11.5	11.8	12.1	12.4	12.7	13.0	13.3	13.6	13.9	14.2	14.5	14.8	15.1	15.4	15.7	16.0	16.3	16.6	16.9	17.2	17.5	17.8	18.1	18.4	18.7	19.0	19.3	19.6	19.9	20.2	20.5	20.8	21.1	21.4	21.7	22.0	22.3	22.6	22.9	23.2	23.5	23.8	24.1	24.4	24.7	25.0	25.3	25.6	25.9	26.2	26.5	26.8	27.1	27.4	27.7	28.0	28.3	28.6	28.9	29.2	29.5	29.8	30.1	30.4	30.7	31.0	31.3	31.6	31.9	32.2	32.5	32.8	33.1	33.4	33.7	34.0	34.3	34.6	34.9	35.2	35.5	35.8	36.1	36.4	36.7	37.0	37.3	37.6	37.9	38.2	38.5	38.8	39.1	39.4	39.7	40.0	40.3	40.6	40.9	41.2	41.5	41.8	42.1	42.4	42.7	43.0	43.3	43.6	43.9	44.2	44.5	44.8	45.1	45.4	45.7	46.0	46.3	46.6	46.9	47.2	47.5	47.8	48.1	48.4	48.7	49.0	49.3	49.6	49.9	50.2	50.5	50.8	51.1	51.4	51.7	52.0	52.3	52.6	52.9	53.2	53.5	53.8	54.1	54.4	54.7	55.0	55.3	55.6	55.9	56.2	56.5	56.8	57.1	57.4	57.7	58.0	58.3	58.6	58.9	59.2	59.5	59.8	60.1	60.4	60.7	61.0	61.3	61.6	61.9	62.2	62.5	62.8	63.1	63.4	63.7	64.0	64.3	64.6	64.9	65.2	65.5	65.8	66.1	66.4	66.7	67.0	67.3	67.6	67.9	68.2	68.5	68.8	69.1	69.4	69.7	70.0	70.3	70.6	70.9	71.2	71.5	71.8	72.1	72.4	72.7	73.0	73.3	73.6	73.9	74.2	74.5	74.8	75.1	75.4	75.7	76.0	76.3	76.6	76.9	77.2	77.5	77.8	78.1	78.4	78.7	79.0	79.3	79.6	79.9	80.2	80.5	80.8	81.1	81.4	81.7	82.0	82.3	82.6	82.9	83.2	83.5	83.8	84.1	84.4	84.7	85.0	85.3	85.6	85.9	86.2	86.5	86.8	87.1	87.4	87.7	88.0	88.3	88.6	88.9	89.2	89.5	89.8	90.1	90.4	90.7	91.0	91.3	91.6	91.9	92.2	92.5	92.8	93.1	93.4	93.7	94.0	94.3	94.6	94.9	95.2	95.5	95.8	96.1	96.4	96.7	97.0	97.3	97.6	97.9	98.2	98.5	98.8	99.1	99.4	99.7	100.0	100.3	100.6	100.9	101.2	101.5	101.8	102.1	102.4	102.7	103.0	103.3	103.6	103.9	104.2	104.5	104.8	105.1	105.4	105.7	106.0	106.3	106.6	106.9	107.2	107.5	107.8	108.1	108.4	108.7	109.0	109.3	109.6	109.9	110.2	110.5	110.8	111.1	111.4	111.7	112.0	112.3	112.6	112.9	113.2	113.5	113.8	114.1	114.4	114.7	115.0	115.3	115.6	115.9	116.2	116.5	116.8	117.1	117.4	117.7	118.0	118.3	118.6	118.9	119.2	119.5	119.8	120.1	120.4	120.7	121.0	121.3	121.6	121.9	122.2	122.5	122.8	123.1	123.4	123.7	124.0	124.3	124.6	124.9	125.2	125.5	125.8	126.1	126.4	126.7	127.0	127.3	127.6	127.9	128.2	128.5	128.8	129.1	129.4	129.7	130.0	130.3	130.6	130.9	131.2	131.5	131.8	132.1	132.4	132.7	133.0	133.3	133.6	133.9	134.2	134.5	134.8	135.1	135.4	135.7	136.0	136.3	136.6	136.9	137.2	137.5	137.8	138.1	138.4	138.7	139.0	139.3	139.6	139.9	140.2	140.5	140.8	141.1	141.4	141.7	142.0	142.3	142.6	142.9	143.2	143.5	143.8	144.1	144.4	144.7	145.0	145.3	145.6	145.9	146.2	146.5	146.8	147.1	147.4	147.7	148.0	148.3	148.6	148.9	149.2	149.5	149.8	150.1	150.4	150.7	151.0	151.3	151.6	151.9	152.2	152.5	152.8	153.1	153.4	153.7	154.0	154.3	154.6	154.9	155.2	155.5	155.8	156.1	156.4	156.7	157.0	157.3	157.6	157.9	158.2	158.5	158.8	159.1	159.4	159.7	160.0	160.3	160.6	160.9	161.2	161.5	161.8	162.1	162.4	162.7	163.0	163.3	163.6	163.9	164.2	164.5	164.8	165.1	165.4	165.7	166.0	166.3	166.6	166.9	167.2	167.5	167.8	168.1	168.4	168.7	169.0	169.3	169.6	169.9	170.2	170.5	170.8	171.1	171.4	171.7	172.0	172.3	172.6	172.9	173.2	173.5	173.8	174.1	174.4	174.7	175.0	175.3	175.6	175.9	176.2	176.5	176.8	177.1	177.4	177.7	178.0	178.3	178.6	178.9	179.2	179.5	179.8	180.1	180.4	180.7	181.0	181.3	181.6	181.9	182.2	182.5	182.8	183.1	183.4	183.7	184.0	184.3	184.6	184.9	185.2	185.5	185.8	186.1	186.4	186.7	187.0	187.3	187.6	187.9	188.2	188.5	188.8	189.1	189.4	189.7	190.0	190.3	190.6	190.9	191.2	191.5	191.8	192.1	192.4	192.7	193.0	193.3	193.6	193.9	194.2	194.5	194.8	195.1	195.4	195.7	196.0	196.3	196.6	196.9	197.2	197.5	197.8	198.1	198.4	198.7	199.0	199.3	199.6	199.9	200.2	200.5	200.8	201.1	201.4	201.7	202.0	202.3	202.6	202.9	203.2	203.5	203.8	204.1	204.4	204.7	205.0	205.3	205.6	205.9	206.2	206.5	206.8	207.1	207.4	207.7	208.0	208.3	208.6	208.9	209.2	209.5	209.8	210.1	210.4	210.7	211.0	211.3	211.6	211.9	212.2	212.5	212.8	213.1	213.4	213.7	214.0	214.3	214.6	214.9	215.2	215.5	215.8	216.1	216.4	216.7	217.0	217.3	217.6	217.9	218.2	218.5	218.8	219.1	219.4	219.7	220.0	220.3	220.6	220.9	221.2	221.5	221.8	222.1	222.4	222.7	223.0	223.3	223.6	223.9	224.2	224.5	224.8	225.1	225.4	225.7	226.0	226.3	226.6	226.9	227.2	227.5	227.8	228.1	228.4	228.7	229.0	229.3	229.6	229.9	230.2	230.5	230.8	231.1	231.4	231.7	232.0	232.3	232.6	232.9	233.2	233.5	233.8	234.1	234.4	234.7	235.0	235.3	235.6	235.9	236.2	236.5	236.8	237.1	237.4	237.7	238.0	238.3	238.6	238.9	239.2	239.5	239.8	240.1	240.4	240.7	241.0	241.3	241.6	241.9	242.2	242.5	242.8	243.1	243.4	243.7	244.0	244.3	244.6	244.9	245.2	245.5	245.8	246.1	246.4	246.7	247.0	247.3	247.6	247.9	248.2	248.5	248.8	249.1	249.4	249.7	250.0	250.3	250.6	250.9	251.2	251.5	251.8	252.1	252.4	252.7	253.0	253.3	253.6	253.9	254.2	254.5	254.8	255.1	255.4	255.7	256.0	256.3	256.6	256.9	257.2	257.5	257.8	258.1	258.4	258.7	259.0	259.3	259.6	259.9	260.2	260.5	260.8	261.1	261.4	261.7	262.0	262.3	262.6	262.9	263.2	263.5	263.8	264.1	264.4	264.7	265.0	265.3	265.6	265.9	266.2	266.5	266.8	267.1	267.4	267.7	268.0	268.3	268.6	268.9	269.2	269.5	269.8	270.1	270.4	270.7	271.0	271.3	271.6	271.9	272.2	272.5	272.8	273.1	273.4	273.7	274.0	274.3	274.6	274.9	275.2	275.5	275.8	276.1	276.4	276.7	277.0	277.3	277.6	277.9	278.2	278.5	278.8	279.1	279.4	279.7	280.0	280.3	280.6	280.9	281.2	281.5	281.8	282.1	282.4	282.7	283.0	283.3	283.6	283.9	284.2	284.5	284.8	285.1	285.4	285.7	286.0	286.3	286.6	286.9	287.2	287.5	287.8	288.1	288.4	288.7	289.0	289.3	289.6	289.9	290.2	290.5	290.8	291.1	291.4	291.7	292.0	292.3	292.6	292.9	293.2	293.5	293.8	294.1	294.4	294.7	295.0	295.3	295.6	295.9	296.2	296.5	296.8	297.1	297.4	297.7	298.0	298.3	298.6	298.9	299.2	299.5	299.8	300.1	300.4	300.7	301.0	301.3	301.6	301.9	302.2	302.5	302.8	303.1	303.4	303.7	304.0	304.3	304.6	304.9	305.2	305.5	305.8	306.1	306.4	306.7	307.0	307.3	307.6	307.9	308.2	308.5	308.8	309.1	309.4	309.7	310.0	310.3	310.6	310.9	311.2	311.5	311.8	312.1	312.4	312.7

# BRICK CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

## 5a SHEATHING REINFORCEMENT

Provide full depth blocking between joists over support (not shown)


**Note:** Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.



## 5b SET-BACK DETAIL

Rim board or wood structural panel closure (3/4" minimum thickness), attach per detail 1b.

**Notes:**  
 - Provide full depth blocking between joists over support (not shown for clarity)  
 - Attach I-joist to plate at all supports per detail 1b.  
 - 3-1/2" minimum I-joist bearing required.



## 5c SET-BACK CONNECTION

Vertical solid sawn blocks (2x6 S-P-F No. 2 or better) nailed through joist web and web of girder using 2-1/2" nails.

Alternate for opposite side.

**Notes:**  
 - Verify girder joist capacity if the back span exceeds the joist spacing.  
 - Attach double I-joist per detail 1p, if required.






FIGURE 5 (continued)

See table below for NI reinforcement requirements of cantilever.



For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

## BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in)	ROOF TRUSS SPAN (ft)		ROOF LOADING (UNFACTORED)			ROOF LOADING (UNFACTORED)		
	LL = 30 psf, DL = 15 psf	JOIST SPACING (in)	LL = 40 psf, DL = 15 psf	JOIST SPACING (in)	LL = 50 psf, DL = 15 psf	JOIST SPACING (in)		
9-1/2	26	12	26	12	26	12		
	28	16	28	16	28	16		
	30	19.2	30	19.2	30	19.2		
	32	24	32	24	32	24		
	34		34		34			
	36		36		36			
	38		38		38			
	40		40		40			
	42		42		42			
11-7/8	26	12	26	12	26	12		
	28	16	28	16	28	16		
	30	19.2	30	19.2	30	19.2		
	32	24	32	24	32	24		
	34		34		34			
	36		36		36			
	38		38		38			
	40		40		40			
	42		42		42			
14	26	12	26	12	26	12		
	28	16	28	16	28	16		
	30	19.2	30	19.2	30	19.2		
	32	24	32	24	32	24		
	34		34		34			
	36		36		36			
	38		38		38			
	40		40		40			
	42		42		42			
16	26	12	26	12	26	12		
	28	16	28	16	28	16		
	30	19.2	30	19.2	30	19.2		
	32	24	32	24	32	24		
	34		34		34			
	36		36		36			
	38		38		38			
	40		40		40			
	42		42		42			

1. N = No reinforcement required.  
 1 = NI reinforced with 3/4" wood structural panel on one side only.  
 2 = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.  
 X = Try a deeper joist or closer spacing.  
 2. Maximum design load shall be: 1.5 psf roof dead load, 5.5 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0" maximum width window or door openings.
- For larger openings, or multiple 3'-0" width openings spaced less than 6'-0" o.c., additional joists beneath the opening's cripple studs may be required.
- Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
- For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.
- Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

# INSTALLING THE GLUED FLOOR SYSTEM

1. Wipe any mud, dirt, water, or ice from I-joist flanges before gluing.
2. Snap a chalk line across the I-joists four feet in from the wall for panel edge alignment and as a boundary for spreading glue.
3. Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from the glue manufacturer.
4. Lay the first panel with tongue side to the wall, and nail in place. This protects the tongue of the next panel from damage when topped into place with a block and sledgehammer.
5. Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-joist. Apply glue in a winding pattern on wide areas, such as with double I-joists.
6. Apply two lines of glue on I-joists where panel ends butt to assure proper gluing of each end.
7. After the first row of panels is in place, spread glue in the groove of one or two panels of a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying a thinner line (1/8 inch) than used on I-joist flanges.
8. Top the second row of panels into place, using a block to protect groove edges.
9. Stagger end joints in each succeeding row of panels. A 1/8-inch space between all end joints and 1/8-inch at all edges, including T&G edges, is recommended. (Use a spacer tool or an 2-1/2" common nail to assure accurate and consistent spacing.)
10. Complete all nailing of each panel before glue sets. Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 2" ring- or screw-shank nails for panels 3/4-inch thick or less, and 2-1/2" ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for diaphragm construction. The finished deck can be walked on right away and will carry construction loads without damage to the glue bond.

Maximum I-joist Spacing (in.)	Minimum Panel Thickness (in.)	Common Wires or Spiral Nails	Nail Size and Type	Staples	Maximum Spacing of Fasteners
10	5/8	2"	1-3/4"	2"	6"
20	5/8	2"	1-3/4"	2"	6"
24	3/4	2"	1-3/4"	2"	6"


1. Fasteners of sheathing and subflooring shall conform to the above table.
2. Staples shall not be less than 1/16-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
3. Flooring screws shall not be less than 1/8-inch in diameter.
4. Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
5. Use only adhesives conforming to CAN/CSG-71.26 Standard, Adhesives for Field-Gluing Plywood to Lumber Framing for Floor System, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues; check with panel manufacturer.

Ref: NRC-CNRC, National Building Code of Canada 2010, Table 9.23.3.5.


**IMPORTANT NOTE:** Floor sheathing must be field glued to the I-joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-joist spans must be verified with your local distributor.

## RIM BOARD INSTALLATION DETAILS


### 8a ATTACHMENT DETAILS WHERE RIM BOARDS ABUT



### 8b TOE-NAIL CONNECTION AT RIM BOARD



### 8c 2X LEDGER TO RIM BOARD ATTACHMENT DETAIL




2015-04-16

## PRODUCT WARRANTY


Changma's performance guarantee is in accordance with our specifications. No other products are from manufacturing defects in material and workmanship.

Fasteners, Connectors, Changma's performance guarantee does not apply to products when installed in accordance with our handling and installation instructions. We will meet or exceed our specifications for the lifespan of the membrane.





LVL HEADER AND CONVENTIONAL LUMBER NAILING DETAILS		
DETAIL NUMBER	NUMBER OF ROWS	SPACING (INCHES o/c) "d"
A	2	12
B	2	8
C	2	6
D	2	4
1A	3	12
1B	3	8
1C	3	6
1D	3	4
2A	4	12
2B	4	8
2C	4	6
2D	4	4
3A	5	12
3B	5	8
3C	5	6
3D	5	4
4A	6	12
4B	6	8
4C	6	6
4D	6	4



**NOTES:**

- (1) MINIMUM LUMBER EDGE DISTANCE "a" = 1"
- (2) MINIMUM LUMBER END DISTANCE "b" = 2"
- (3) MINIMUM NAIL ROW SPACING "c" = 2"
- (4) STAGGER NAILS "d/2" BETWEEN PLYS FOR MULTI-PLY MEMBERS (3 PLY OR MORE)
- (5) ALL NAILS ARE 3-1/2" ARDOX SPIRAL NAILS
- (6) DO NOT USE AIR-DRIVEN NAILS



DWG NO TAMN1001.14

STRUCTURAL COMPONENT ONLY

TO BE USED ONLY WITH BEAM CILES BEARING THE STAMP BELOWS

PROVIDE NAILING DETAIL # X SEE DWG #TAMN1001-14