

THGQ3-SDS4.5 (MAX)-(S)
HGUS26-2 -(XX)
LJS26DS -(V)
LUS24 -(0)


DENOTES:

H2 -12" HIGHER PLATE
H -12" RAISED CEILING

DESIGN CONFORMS WITH OBC
2012(2019 AMENDMENT)
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 54.3 psf | Sr = 8.4 psf

DESIGN LOADS:
 TCSL = 38.3 psf
 TC DL = 6.0 psf
 BC LL = 0.0 psf
 BC DL = 7.4 psf

**DENOTES:
CONVENTIONAL
FRAMING**



Timeline diagram showing dates from 1-09-00 to 2-09-00. Key dates marked are 6-00-00, 11-00, and 36-09-00. A break symbol is present between 11-00 and 36-09-00.

**10/12 PITCHES (TYP.)
UNLESS NOTED**


42-10-00

23-06-00


4-04-00

6-07-00

T.O.P 7'-10"-0
U/S OF SOFFIT
@ PLATE LEVEL



All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.



211047

Builder / Location:

BAYVIEW WELLINGTON / INNISFIL

Model / Elevation:

S45-4C HUMMINGBIRD 4 / A

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC. SHALL NOT BE REPRODUCED, PUBLISHED OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Milex ver 06.03.20

Mitek ver 8.6.3.353



ASPHALT SHINGLES
12" FINISH O.H.
R.T.M.C
2X6 EXTERIOR WALLS
2X6 FASCIA BOARD
HARDWARE:



THGQ3-SDS4.5 (MAX) - (S)
HGUS26-2 - (XX)
LJS26DS - (V)
LUS24 - (-0)

DENOTES:
H2 -12" HIGHER PLATE
H -12" RAISED CEILING

DESIGN CONFORMS WITH OBC
2012(2019 AMENDMENT)
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 54.3 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 38.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf


DENOTES:
CONVENTIONAL
FRAMING



All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

M11047

 TAMARACK ROOF TRUSSES INC.		Builder / Location:		Model / Elevation:	
Job Track:	50469	Project:		BAYVIEW WELLINGTON / INNISFIL	
Plan Log:	204710	Sales:		Rick DiCiano	
Layout ID:	418650	Designer:		SV/XT	
Date:	11/14/23	Project:		ALCONA SHORES	
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.					
Mitek ver 8.6.3.353					




HGUS26-2 -(XX)
LJS26DS -(V)
LUS24 -(0)

H2 -12" HIGHER PLATE

DESIGN CONFORMS WITH OBC
2012(2019 AMENDMENT)
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 54.3 psf | Sr = 8.4 psf

DESIGN LOADS:
 TCSL = 38.3 psf
 TC DL = 6.0 psf
 BC LL = 0.0 psf
 BC DL = 7.4 psf

**DENOTES:
CONVENTIONAL
FRAMING**



All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'



Job Track: **50469**
Plan Log: **204710**
Layout ID: **418651**

Builder / Location:

BAYVIEW WELLINGTON / INNISFIL


Model / Elevation:

S45-4C HUMMINGBIRD 4 / B

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC. SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mittek ver 8.6.3.3.3

Mitek ver 8.6.3.353



HARDWARE:
HGUS26-2 -(XX)
LJS26DS -(V)
LUS24 -(0)

HN2 -12" HIGHER PLATE


DESIGN CONFORMS WITH OBC
2012(2019 AMENDMENT)
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 54.3 psf | Sr = 8.4 psf

DESIGN LOADS:
TOSL = 38.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf


**DENOTES:
CONVENTIONAL
FRAMING**



**10/12 PITCHES (TYP.)
UNLESS NOTED**



All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.



M11047

BAYVIEW WELLINGTON / INNISFIL

S45-4C HUMMINGBIRD 4 / B OPT COFF


THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMMACK ROOF TRUSSES INC. SHALL NOT BE REPRODUCED, PUBLISHED OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMMACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMMACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Miletek ver 6.6.3.3

Mitek ver 8.6.3.353





DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: A

Job Track: 50469
 PlanLog: 204710
 Layout ID: 418649
 Ref #
 Page: 1 of 4
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Hip Girder	10 /12	35-11-00	6-06-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	453.91 266.67		
	1	T2 Hip	10 /12	35-11-00	8-02-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	179.61 112.33		
	3	T3 Hip	10 /12	35-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	576.47 361.00		
	1 3-ply	T4 Piggyback Base Girder	10 /12	35-11-00	9-10-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	972.14 581.00		
	1 2-ply	T5 Hip Girder	10 /12	33-03-00	6-06-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	430.61 254.67		
	1	T6 Hip	10 /12	33-03-00	8-02-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	161.06 102.00		
	4	T7A Hip	10 /12	32-10-00	9-10-07	2 x 4	1-03-08	1-07-11 1-11-14	661.64 416.00		
	1	T8AS Piggyback Base	10 /12	32-10-00	9-10-07	2 x 4	1-03-08	1-07-11 4-02-08	199.57 125.17		
	4	T9A Piggyback Base	10 /12	32-10-00	9-10-07	2 x 4	1-03-08	1-07-11 4-02-08	761.34 474.67		
	1 3-ply	T10A Common Girder	10 /12	17-08-08	10-10-08	2 x 6		1-07-11 5-04-04	459.52 278.00		
	2	T11A Roof Special	10 /12	17-08-08	10-10-08	2 x 4	1-03-08	1-07-11 4-04-04	228.51 148.00		
	1	G12 GABLE	10 /12	8-06-00	5-02-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	41.52 27.83		
	1	T13 Hip	10 /12	16-07-00	7-04-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	83.14 52.67		
	1	T14 Common	10 /12	16-07-00	8-06-10	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	81.59 51.33		

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: A

Job Track: 50469
 PlanLog: 204710
 Layout ID: 418649
 Ref #
 Page: 2 of 4
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	T15 Hip Girder	10 /12	13-00-00	6-06-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	130.92 84.00		
	2	T16 Roof Special	10 /12	9-04-00	5-06-06	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	106.14 72.00		
	1	T17 Half Hip	10 /12	9-04-00	4-11-11	2 x 4		3-11-03 4-11-11	50.53 33.00		
	1	T18C Half Hip Girder	10 /12	5-04-00	5-08-07	2 x 6		1-07-11 5-08-07	36.67 23.50		
	1 2-ply	T50 Jack-Closed Girder	10 /12	5-10-08	6-06-07	2 x 4 2 x 6		1-07-11 6-06-07	72.89 46.67		
	1 2-ply	T50Z Jack-Closed Girder	10 /12	5-10-08	6-06-07	2 x 4 2 x 6		1-07-11 6-06-07	72.89 46.67		
	1 2-ply	T51 Half Hip Girder	10 /12	5-10-08	3-08-11	2 x 4 2 x 6		1-07-11 3-08-11	63.18 41.67		
	9	T90 Monopitch	8 /12	2-05-00	3-06-05	2 x 4	1-03-08	1-04-13 3-00-02	159.85 106.50		
	10	T91 Monopitch	10 /12	1-07-00	3-07-04	2 x 4	1-03-08	1-07-11 2-11-08	165.24 128.33		
	1	P1 Piggyback	10 /12	16-02-00	1-08-00	2 x 4			48.62 30.17		
	1	P2 Piggyback	10 /12	16-02-00	3-04-00	2 x 4			52.02 33.50		
	1 3-ply	P3 Piggyback	10 /12	16-02-00	4-03-04	2 x 4			150.15 92.50		
	1	P4 Piggyback	10 /12	13-06-00	1-08-00	2 x 4			40.4 25.83		
	1	P5 Piggyback	10 /12	13-06-00	3-04-00	2 x 4			40.99 26.67		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: A


Job Track: 50469
 PlanLog: 204710
 Layout ID: 418649
 Ref #
 Page: 3 of 4
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	P6 Piggyback	10 /12	13-06-00	5-00-00	2 x 4			44.02 28.17		
	2	P7 Piggyback	10 /12	13-06-00	5-07-08	2 x 4			87.91 54.33		
	1	P8S Piggyback	10 /12	16-02-00	5-07-08	2 x 4			55.86 34.67		
	1	P9S Piggyback	10 /12	16-02-00	5-07-08	2 x 4			59.46 37.67		
	1	P10 Piggyback	10 /12	16-02-00	5-00-13	2 x 4			51.27 31.33		
	20	J1 Jack-Open	10 /12	5-10-08	6-06-07	2 x 4	1-03-08	1-07-11 6-06-07	525.16 340.00		
	1	J2 Jack-Open	10 /12	4-10-08	5-08-07	2 x 4	1-03-08	1-07-11 5-08-07	17.85 11.67		
	1	J3 Jack-Open Girder	10 /12	4-10-08	3-01-09	2 x 4	1-03-08	1-07-11 5-08-07	13.27 9.00		
	1	J4 Jack-Open	10 /12	4-10-08	4-09-09	2 x 4	1-03-08	1-07-11 5-08-07	16.23 10.33		
	7	J5 Jack-Open	10 /12	1-10-08	3-01-09	2 x 4	1-03-08	1-07-11 3-02-07	68.92 49.00		
	7	J6 Jack-Open	10 /12	1-10-08	4-09-09	2 x 4	1-03-08 1-10-15	1-07-11 3-02-07	89.7 58.33		
	5	J7 Jack-Open Girder	10 /12	5-10-08	3-01-09	2 x 4	1-03-08	1-07-11 6-06-07	72.03 48.33		
	6	J8 Jack-Open	10 /12	5-10-08	4-09-09	2 x 4	1-03-08	1-07-11 6-06-07	104.25 66.00		
	1	J9 Jack-Open Girder	10 /12	5-10-08	3-01-09	2 x 4	1-03-08	1-07-11 6-06-07	14.41 9.67		



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
Builder: BAYVIEW WELLINGTON
Project: ALCONA SHORES
Location: INNISFIL
Model: S45-4C HUMMINGBIRD 4
Lot #:
Elevation: A

Job Track: 50469
PlanLog: 204710
Layout ID: 418649
Ref #
Page: 4 of 4
Date: 11/14/2023
Designer:
Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
---------	------------	--------------	-------	------	--------	--------	---------------------------	------------------------------	--------------	---------------------	--------------------

TOTAL # TRUSS= 122 TOTAL BFT OF ALL TRUSSES= 4830.85 BFT. TOTAL WEIGHT OF ALL TRSSES 7701.45 LBS


HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	CP3-6	
3	Hardware	HGUS26-2	
12	Hardware	LJS26DS	
6	Hardware	LUS24	
1	Hardware	THGQ3-SDS4.5MAX	

TOTAL NUMBER OF ITEMS= 24



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: A OPT COFF


Job Track: 50469
 PlanLog: 204710
 Layout ID: 418650
 Ref #
 Page: 1 of 4
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1S Hip Girder	10 /12 12 /12	35-11-00	6-06-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	484.61 292.67		
	1	T2S Hip	10 /12 12 /12	35-11-00	8-02-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	186.72 119.33		
	1	T3 Piggyback Base	10 /12	35-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	192.16 120.33		
	2	T3S Hip	10 /12 12 /12	35-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	404.82 259.33		
	1 3-ply	T4 Piggyback Base Girder	10 /12	35-11-00	9-10-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	972.14 581.00		
	1 2-ply	T5 Hip Girder	10 /12	33-03-00	6-06-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	430.61 254.67		
	1	T6 Hip	10 /12	33-03-00	8-02-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	161.06 102.00		
	4	T7A Hip	10 /12	32-10-00	9-10-07	2 x 4	1-03-08	1-07-11 1-11-14	661.64 416.00		
	1	T8AS Piggyback Base	10 /12	32-10-00	9-10-07	2 x 4	1-03-08	1-07-11 4-02-08	199.57 125.17		
	4	T9A Piggyback Base	10 /12	32-10-00	9-10-07	2 x 4	1-03-08	1-07-11 4-02-08	761.34 474.67		
	1 3-ply	T10A Common Girder	10 /12	17-08-08	10-10-08	2 x 6		1-07-11 5-04-04	459.52 278.00		
	2	T11A Roof Special	10 /12	17-08-08	10-10-08	2 x 4	1-03-08	1-07-11 4-04-04	228.51 148.00		
	1	G12 GABLE	10 /12	8-06-00	5-02-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	41.52 27.83		
	1	T13 Hip	10 /12	16-07-00	7-04-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	83.14 52.67		



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: A OPT COFF


Job Track: 50469
 PlanLog: 204710
 Layout ID: 418650
 Ref #
 Page: 2 of 4
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T14 Common	10 /12	16-07-00	8-06-10	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	81.59 51.33		
	2	T15 Hip Girder	10 /12	13-00-00	6-06-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	130.92 84.00		
	2	T16 Roof Special	10 /12	9-04-00	5-06-06	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	106.14 72.00		
	1	T17 Half Hip	10 /12	9-04-00	4-11-11	2 x 4		3-11-03 4-11-11	50.53 33.00		
	1	T18C Half Hip Girder	10 /12	5-04-00	5-08-07	2 x 6		1-07-11 5-08-07	36.67 23.50		
	1 2-ply	T50 Jack-Closed Girder	10 /12	5-10-08	6-06-07	2 x 4 2 x 6		1-07-11 6-06-07	72.89 46.67		
	1 2-ply	T50Z Jack-Closed Girder	10 /12	5-10-08	6-06-07	2 x 4 2 x 6		1-07-11 6-06-07	72.89 46.67		
	1 2-ply	T51 Half Hip Girder	10 /12	5-10-08	3-08-11	2 x 4 2 x 6		1-07-11 3-08-11	63.18 41.67		
	9	T90 Monopitch	8 /12	2-05-00	3-06-05	2 x 4	1-03-08	1-04-13 3-00-02	159.85 106.50		
	10	T91 Monopitch	10 /12	1-07-00	3-07-04	2 x 4	1-03-08	1-07-11 2-11-08	165.24 128.33		
	1	P1 Piggyback	10 /12	16-02-00	1-08-00	2 x 4			48.62 30.17		
	1	P2 Piggyback	10 /12	16-02-00	3-04-00	2 x 4			52.02 33.50		
	1 3-ply	P3 Piggyback	10 /12	16-02-00	4-03-04	2 x 4			150.15 92.50		
	1	P4 Piggyback	10 /12	13-06-00	1-08-00	2 x 4			40.4 25.83		



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: A OPT COFF


Job Track: 50469
 PlanLog: 204710
 Layout ID: 418650
 Ref #
 Page: 3 of 4
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	P5 Piggyback	10/12	13-06-00	3-04-00	2 x 4			40.99 26.67		
	1	P6 Piggyback	10/12	13-06-00	5-00-00	2 x 4			44.02 28.17		
	2	P7 Piggyback	10/12	13-06-00	5-07-08	2 x 4			87.91 54.33		
	1	P8S Piggyback	10/12	16-02-00	5-07-08	2 x 4			55.86 34.67		
	1	P9S Piggyback	10/12	16-02-00	5-07-08	2 x 4			59.46 37.67		
	1	P10 Piggyback	10/12	16-02-00	5-00-13	2 x 4			51.27 31.33		
	15	J1 Jack-Open	10/12	5-10-08	6-06-07	2 x 4	1-03-08	1-07-11 6-06-07	393.87 255.00		
	8	J1S Jack-Open	10/12 12/12	5-10-08	6-06-07	2 x 4	1-03-08	1-07-11 5-06-07	216.91 152.00		
	1	J2 Jack-Open	10/12	4-10-08	5-08-07	2 x 4	1-03-08	1-07-11 5-08-07	17.85 11.67		
	1	J3 Jack-Open Girder	10/12	4-10-08	3-01-09	2 x 4	1-03-08	1-07-11 5-08-07	13.27 9.00		
	1	J4 Jack-Open	10/12	4-10-08	4-09-09	2 x 4	1-03-08	1-07-11 5-08-07	16.23 10.33		
	6	J5 Jack-Open	10/12	1-10-08	3-01-09	2 x 4	1-03-08	1-07-11 3-02-07	59.07 42.00		
	6	J6 Jack-Open	10/12	1-10-08	4-09-09	2 x 4	1-03-08 1-10-15	1-07-11 3-02-07	76.89 50.00		
	5	J7 Jack-Open Girder	10/12	5-10-08	3-01-09	2 x 4	1-03-08	1-07-11 6-06-07	72.03 48.33		



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
Builder: BAYVIEW WELLINGTON
Project: ALCONA SHORES
Location: INNISFIL
Model: S45-4C HUMMINGBIRD 4
Lot #:
Elevation: A OPT COFF

Job Track: 50469
PlanLog: 204710
Layout ID: 418650
Ref #
Page: 4 of 4
Date: 11/14/2023
Designer:
Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	5	J8 Jack-Open	10 /12	5-10-08	4-09-09	2 x 4	1-03-08	1-07-11 6-06-07	86.88 55.00		

TOTAL # TRUSS= 121 TOTAL BFT OF ALL TRUSSES= 4913.51 BFT. TOTAL WEIGHT OF ALL TRSSES 7790.93 LBS


HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	CP3-6	
3	Hardware	HGUS26-2	
12	Hardware	LJS26DS	
6	Hardware	LUS24	
1	Hardware	THGQ3-SDS4.5MAX	

TOTAL NUMBER OF ITEMS= 24



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: B


Job Track: 50469
 PlanLog: 204710
 Layout ID: 418651
 Ref #
 Page: 1 of 3
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Hip Girder	10 / 12	35-11-00	6-06-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	453.91 266.67		
	1	T2 Hip	10 / 12	35-11-00	8-02-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	179.61 112.33		
	8	T3 Hip	10 / 12	35-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	1537.26 962.67		
	2	T12 Common	10 / 12	8-06-00	5-02-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	79.43 53.67		
	1	G12 GABLE	10 / 12	8-06-00	5-02-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	41.52 27.83		
	1	T18C Half Hip Girder	10 / 12	5-04-00	5-08-07	2 x 6		1-07-11 5-08-07	36.67 23.50		
	1 2-ply	T19 Hip Girder	10 / 12	35-11-00	8-09-01	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	528.86 308.67		
	1 2-ply	T20 Hip Girder	10 / 12	31-11-00	6-06-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	419.06 254.67		
	1	T21 Hip	10 / 12	31-11-00	8-02-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	157.4 100.00		
	4	T22 Hip	10 / 12	31-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	656.58 413.33		
	1	T23 Hip	10 / 12	15-03-00	7-04-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	79.83 50.83		
	1	T24 Common	10 / 12	15-03-00	7-11-15	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	71.11 45.33		
	1 2-ply	T25 Common	10 / 12	13-00-00	7-01-01	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	169.89 104.00		
	1 2-ply	T26 Half Hip Girder	10 / 12	8-06-00	4-09-03	2 x 4 2 x 6		1-07-11 4-09-03	131.78 86.00		



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: B


Job Track: 50469
 PlanLog: 204710
 Layout ID: 418651
 Ref #
 Page: 2 of 3
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T60 Half Hip Girder	10 /12	6-03-08	6-01-00	2 x 4 2 x 6		1-08-15 6-01-00	91.58 63.33		
	1 2-ply	T61 Jack-Open Girder	10 /12	5-10-08	6-06-07	2 x 4 2 x 6		1-07-11 6-06-07	71.58 45.67		
	9	T90 Monopitch	8 /12	2-05-00	3-06-05	2 x 4	1-03-08	1-04-13 3-00-02	159.85 106.50		
	10	T91 Monopitch	10 /12	1-07-00	3-07-04	2 x 4	1-03-08	1-07-11 2-11-08	165.24 128.33		
	1	G93 GABLE	10 /12	7-10-00	4-08-10	2 x 4	1-03-08 1-03-08	4-13 4-13	29.69 19.50		
	2	T93 Common	10 /12	7-10-00	4-08-10	2 x 4	1-03-08 1-03-08	4-13 4-13	56.37 37.67		
	2	T93A Common	10 /12	6-11-00	4-08-10	2 x 4	1-03-08	4-13 1-02-00	56.81 38.00		
	2	P1 Piggyback	10 /12	16-02-00	1-08-00	2 x 4			97.23 60.33		
	2	P2 Piggyback	10 /12	16-02-00	3-04-00	2 x 4			104.04 67.00		
	1	P11 Piggyback	10 /12	12-02-00	1-08-00	2 x 4			36.3 22.83		
	1	P12 Piggyback	10 /12	12-02-00	3-04-00	2 x 4			37.02 24.17		
	1	P13 Piggyback	10 /12	12-02-00	5-00-13	2 x 4			33.94 20.50		
	2	P20 Piggyback	10 /12	16-02-00	5-00-00	2 x 4			102.28 64.00		
	19	J1 Jack-Open	10 /12	5-10-08	6-06-07	2 x 4	1-03-08	1-07-11 6-06-07	498.91 323.00		



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
Builder: BAYVIEW WELLINGTON
Project: ALCONA SHORES
Location: INNISFIL
Model: S45-4C HUMMINGBIRD 4
Lot #:
Elevation: B

Job Track: 50469
PlanLog: 204710
Layout ID: 418651
Ref #
Page: 3 of 3
Date: 11/14/2023
Designer:
Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	J2 Jack-Open	10 /12	4-10-08	5-08-07	2 x 4	1-03-08	1-07-11 5-08-07	17.85 11.67		
	1	J3 Jack-Open Girder	10 /12	4-10-08	3-01-09	2 x 4	1-03-08	1-07-11 5-08-07	13.27 9.00		
	1	J4 Jack-Open	10 /12	4-10-08	4-09-09	2 x 4	1-03-08	1-07-11 5-08-07	16.23 10.33		
	4	J5 Jack-Open	10 /12	1-10-08	3-01-09	2 x 4	1-03-08	1-07-11 3-02-07	39.38 28.00		
	4	J6 Jack-Open	10 /12	1-10-08	4-09-09	2 x 4	1-03-08 1-10-15	1-07-11 3-02-07	51.26 33.33		
	3	J7 Jack-Open Girder	10 /12	5-10-08	3-01-09	2 x 4	1-03-08	1-07-11 6-06-07	43.22 29.00		
	3	J8 Jack-Open	10 /12	5-10-08	4-09-09	2 x 4	1-03-08	1-07-11 6-06-07	52.13 33.00		

TOTAL # TRUSS= 103

TOTAL BFT OF ALL TRUSSES= 3984.66 BFT.

TOTAL WEIGHT OF ALL TRSSES 6317.09 LBS


HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	HGUS26-2	
6	Hardware	LJS26DS	
3	Hardware	LUS24	

TOTAL NUMBER OF ITEMS= 11



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: B OPT COFF


Job Track: 50469
 PlanLog: 204710
 Layout ID: 418652
 Ref #
 Page: 1 of 3
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1S Hip Girder	10 /12 12 /12	35-11-00	6-06-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	484.61 292.67		
	1	T2S Hip	10 /12 12 /12	35-11-00	8-02-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	186.72 119.33		
	6	T3 Piggyback Base	10 /12	35-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	1152.95 722.00		
	2	T3S Hip	10 /12 12 /12	35-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	404.82 259.33		
	2	T12 Common	10 /12	8-06-00	5-02-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	79.43 53.67		
	1	G12 GABLE	10 /12	8-06-00	5-02-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	41.52 27.83		
	1	T18C Half Hip Girder	10 /12	5-04-00	5-08-07	2 x 6		1-07-11 5-08-07	36.67 23.50		
	1 2-ply	T19 Hip Girder	10 /12	35-11-00	8-09-01	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	528.86 308.67		
	1 2-ply	T20 Hip Girder	10 /12	31-11-00	6-06-13	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	419.06 254.67		
	1	T21 Hip	10 /12	31-11-00	8-02-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	157.4 100.00		
	4	T22 Hip	10 /12	31-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	656.58 413.33		
	1	T23 Hip	10 /12	15-03-00	7-04-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	79.83 50.83		
	1	T24 Common	10 /12	15-03-00	7-11-15	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	71.11 45.33		
	1 2-ply	T25 Common	10 /12	13-00-00	7-01-01	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	169.89 104.00		



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: B OPT COFF


Job Track: 50469
 PlanLog: 204710
 Layout ID: 418652
 Ref #
 Page: 2 of 3
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T26 Half Hip Girder	10/12	8-06-00	4-09-03	2 x 4 2 x 6		1-07-11 4-09-03	131.78 86.00		
	1 2-ply	T60 Half Hip Girder	10/12	6-03-08	6-01-00	2 x 4 2 x 6		1-08-15 6-01-00	91.58 63.33		
	1 2-ply	T61 Jack-Open Girder	10/12	5-10-08	6-06-07	2 x 4 2 x 6		1-07-11 6-06-07	71.58 45.67		
	9	T90 Monopitch	8/12	2-05-00	3-06-05	2 x 4	1-03-08	1-04-13 3-00-02	159.85 106.50		
	10	T91 Monopitch	10/12	1-07-00	3-07-04	2 x 4	1-03-08	1-07-11 2-11-08	165.24 128.33		
	1	G93 GABLE	10/12	7-10-00	4-08-10	2 x 4	1-03-08 1-03-08	4-13 4-13	29.69 19.50		
	2	T93 Common	10/12	7-10-00	4-08-10	2 x 4	1-03-08 1-03-08	4-13 4-13	56.37 37.67		
	2	T93A Common	10/12	6-11-00	4-08-10	2 x 4	1-03-08	4-13 1-02-00	56.81 38.00		
	2	P1 Piggyback	10/12	16-02-00	1-08-00	2 x 4			97.23 60.33		
	2	P2 Piggyback	10/12	16-02-00	3-04-00	2 x 4			104.04 67.00		
	1	P11 Piggyback	10/12	12-02-00	1-08-00	2 x 4			36.3 22.83		
	1	P12 Piggyback	10/12	12-02-00	3-04-00	2 x 4			37.02 24.17		
	1	P13 Piggyback	10/12	12-02-00	5-00-13	2 x 4			33.94 20.50		
	2	P20 Piggyback	10/12	16-02-00	5-00-00	2 x 4			102.28 64.00		



DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: BAYVIEW WELLINGTON
 Project: ALCONA SHORES
 Location: INNISFIL
 Model: S45-4C HUMMINGBIRD 4
 Lot #:
 Elevation: B OPT COFF

Job Track: 50469
 PlanLog: 204710
 Layout ID: 418652
 Ref #
 Page: 3 of 3
 Date: 11/14/2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	14	J1 Jack-Open	10 / 12	5-10-08	6-06-07	2 x 4	1-03-08	1-07-11 6-06-07	367.61 238.00		
	8	J1S Jack-Open	10 / 12 12 / 12	5-10-08	6-06-07	2 x 4	1-03-08	1-07-11 5-06-07	216.91 152.00		
	1	J2 Jack-Open	10 / 12	4-10-08	5-08-07	2 x 4	1-03-08	1-07-11 5-08-07	17.85 11.67		
	1	J3 Jack-Open Girder	10 / 12	4-10-08	3-01-09	2 x 4	1-03-08	1-07-11 5-08-07	13.27 9.00		
	1	J4 Jack-Open	10 / 12	4-10-08	4-09-09	2 x 4	1-03-08	1-07-11 5-08-07	16.23 10.33		
	3	J5 Jack-Open	10 / 12	1-10-08	3-01-09	2 x 4	1-03-08	1-07-11 3-02-07	29.54 21.00		
	3	J6 Jack-Open	10 / 12	1-10-08	4-09-09	2 x 4	1-03-08 1-10-15	1-07-11 3-02-07	38.44 25.00		
	2	J7 Jack-Open Girder	10 / 12	5-10-08	3-01-09	2 x 4	1-03-08	1-07-11 6-06-07	28.81 19.33		
	2	J8 Jack-Open	10 / 12	5-10-08	4-09-09	2 x 4	1-03-08	1-07-11 6-06-07	34.75 22.00		

TOTAL # TRUSS= 102

TOTAL BFT OF ALL TRUSSES= 4067.32

BFT.

TOTAL WEIGHT OF ALL TRSSES 6406.57 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	HGUS26-2	
6	Hardware	LJS26DS	
3	Hardware	LUS24	

TOTAL NUMBER OF ITEMS= 11




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T1	1	2	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 Mitek Industries, Inc. Tue Nov 14 11:14:46 2023 Page 1

ID:UaoF4umx8QMx1bo7Q0Zg7Cya5EO-bx9oLdwCPoyshtQT2Dur8BO3Wd6YFJguJzqX6syJlQ7

Scale = 1:61.0





JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418649	T1	1	2	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:46 2023 Page 2

ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-bxh9oLdwCPoyshQT2Dur8BO3Wd6YFJquJzqX6syJIQ7

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	8.0	2.50	3.25
C	TTVWV+m	MT20	6.0	10.0	4.00	1.25
D	TMWW+t	MT20	4.0	6.0		
E	TMW+w	MT20	4.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMWW+t	MT20	4.0	6.0		
H	TTVWV+m	MT20	6.0	10.0	4.00	1.25
I	TMVW-t	MT20	5.0	8.0	2.50	3.25
K	BMV1+p	MT20	4.0	6.0		
L	BMWW-t	MT20	5.0	6.0	2.50	2.50
M	BMWW-t	MT20	5.0	6.0		
N	BS-t	MT20	5.0	6.0		
O	BMWWVW-t	MT20	5.0	8.0		
P	BS-t	MT20	5.0	6.0		
Q	BMWW-t	MT20	5.0	6.0		
R	BMWW-t	MT20	5.0	6.0	2.50	2.50
S	BMV1+p	MT20	4.0	6.0		

NOTES-


1) Lateral braces to be a minimum of 2X4 SPF #2.

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	17-11-8	-10	-10	—	FRONT	VERT	TOTAL	—	C1
F	19-11-12	-10	-10	—	FRONT	VERT	TOTAL	—	C1
G	23-11-12	-10	-10	—	FRONT	VERT	TOTAL	—	C1
H	30-0-8	-404	-404	—	FRONT	VERT	TOTAL	—	C1
L	29-11-12	-193	-193	—	FRONT	VERT	TOTAL	—	C1
M	23-11-12	-193	-193	—	FRONT	VERT	TOTAL	—	C1
N	21-11-12	-193	-193	—	FRONT	VERT	TOTAL	—	C1
O	17-11-8	-193	-193	—	FRONT	VERT	TOTAL	—	C1
P	13-11-4	-193	-193	—	FRONT	VERT	TOTAL	—	C1
Q	11-11-4	-193	-193	—	FRONT	VERT	TOTAL	—	C1
R	5-11-4	-193	-193	—	FRONT	VERT	TOTAL	—	C1
T	7-11-4	-10	-10	—	FRONT	VERT	TOTAL	—	C1
U	9-11-4	-10	-10	—	FRONT	VERT	TOTAL	—	C1
V	13-11-4	-10	-10	—	FRONT	VERT	TOTAL	—	C1
W	15-11-4	-10	-10	—	FRONT	VERT	TOTAL	—	C1
X	21-11-12	-10	-10	—	FRONT	VERT	TOTAL	—	C1
Y	25-11-12	-10	-10	—	FRONT	VERT	TOTAL	—	C1
Z	27-11-12	-10	-10	—	FRONT	VERT	TOTAL	—	C1
AA	1-11-4	-29	-29	—	FRONT	VERT	TOTAL	—	C1
AB	3-11-4	-29	-29	—	FRONT	VERT	TOTAL	—	C1
AC	7-11-4	-193	-193	—	FRONT	VERT	TOTAL	—	C1
AD	9-11-4	-193	-193	—	FRONT	VERT	TOTAL	—	C1
AE	15-11-4	-193	-193	—	FRONT	VERT	TOTAL	—	C1
AF	19-11-12	-193	-193	—	FRONT	VERT	TOTAL	—	C1
AG	25-11-12	-193	-193	—	FRONT	VERT	TOTAL	—	C1
AH	27-11-12	-193	-193	—	FRONT	VERT	TOTAL	—	C1
AI	31-11-12	-29	-29	—	FRONT	VERT	TOTAL	—	C1
AJ	33-11-12	-29	-29	—	FRONT	VERT	TOTAL	—	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




STRUCTURAL COMPONENT ONLY
DWG # TR23111077



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418650	T1S	1	2	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:44:49 2023 Page 1
ID:UaoF4umx8QMX1bo7QOz7Cya5EO-bp7mCsStbNy8qml 9NkdfPZ9NQShCi5Hw 4RtryJHzy



LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - E	2x6	DRY	No.2	SPF
E - H	2x6	DRY	No.2	SPF
H - J	2x6	DRY	No.2	SPF
J - L	2x6	DRY	No.2	SPF
W - B	2x6	DRY	No.2	SPF
M - K	2x6	DRY	No.2	SPF
W - V	2x6	DRY	No.2	SPF
U - R	2x6	DRY	No.2	SPF
Q - O	2x6	DRY	No.2	SPF
O - M	2x6	DRY	No.2	SPF
ALL WEBS	2x4	DRY	No.2	SPF
EXCEPT				
R - P	2x6	DRY	No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-E	2	12
E-H	2	12
H-J	2	12
J-L	2	12
W-B	2	12
M-K	2	12
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
W-V	2	12
V-U	2	12
U-R	2	12
Q-O	2	12
O-M	2	12
G-Q	1	12
WEBS : (0.122"x3") SPIRAL NAILS		
T-E	1	6
2x4	1	6
2x6	2	6

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT.	VERT. HORZ	DOWN HORZ UPLIFT	IN-SX	IN-SX
W	8206 0	6206 0	5-8	4-9
M	5500 0	5500 0	5-8	3-7

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
W	4310	3278 / 0	0 / 0	0 / 0	1032 / 0	0 / 0
M	3827	2864 / 0	0 / 0	0 / 0	963 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) W, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.55 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (IN)	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (IN)
FR-TO					FR-TO			
A-B	0 / 60	-129.7	-129.7	0.05 (1)	10.00	V-C	-5546 / 0	0.34 (1)
B-C	-5138 / 0	-129.7	-129.7	0.18 (1)	4.98	C-U	0 / 4785	0.42 (1)
C-D	-8371 / 0	-129.7	-129.7	0.23 (1)	4.00	U-D	0 / 95	0.01 (4)
D-E	-8019 / 0	-129.7	-129.7	0.15 (1)	4.17	D-T	-513 / 0	0.05 (1)
E-Y	-9030 / 0	-129.7	-129.7	0.35 (1)	3.79	T-E	0 / 833	0.06 (1)
Y-Z	-9030 / 0	-129.7	-129.7	0.35 (1)	3.79	E-S	0 / 3900	0.34 (1)
Z-AA	-9030 / 0	-129.7	-129.7	0.35 (1)	3.79	S-F	-2177 / 0	0.32 (1)
AA-F	-9030 / 0	-129.7	-129.7	0.35 (1)	3.79	F-R	0 / 1480	0.13 (1)
F-AB	-10104 / 0	-129.7	-129.7	0.39 (1)	3.57	R-P	0 / 7765	0.50 (1)
AB-AC	-10104 / 0	-129.7	-129.7	0.39 (1)	3.57	P-I	0 / 2799	0.25 (1)
AC-G	-10104 / 0	-129.7	-129.7	0.39 (1)	3.57	I-L	-2719 / 0	0.61 (1)
G-AD	-10070 / 0	-129.7	-129.7	0.43 (1)	3.55	L-J	0 / 4118	0.36 (1)
AD-H	-10070 / 0	-129.7	-129.7	0.43 (1)	3.55	J-N	-153 / 118	0.03 (1)
H-AE	-10070 / 0	-129.7	-129.7	0.43 (1)	3.55	N-V	0 / 4483	0.40 (1)
AE-I	-10070 / 0	-129.7	-129.7	0.43 (1)	3.55	V-K	0 / 4848	0.43 (1)
I-AF	-7805 / 0	-129.7	-129.7	0.35 (1)	4.05			
AF-AG	-7805 / 0	-129.7	-129.7	0.35 (1)	4.05			
AG-AH	-7805 / 0	-129.7	-129.7	0.35 (1)	4.05			
AH-J	-7805 / 0	-129.7	-129.7	0.35 (1)	4.05			
J-K	-6224 / 0	-129.7	-129.7	0.30 (1)	4.51			
K-L	0 / 60	-129.7	-129.7	0.05 (1)	10.00			
W-B	-6191 / 0	0.0	0.0	0.22 (1)	5.95			
M-K	-5450 / 0	0.0	0.0	0.20 (1)	6.28			
W-V	0 / 0	-18.5	-18.5	0.00 (4)	10.00			
V-U	0 / 4852	-18.5	-18.5	0.32 (1)	10.00			
U-AI	0 / 6545	-18.5	-18.5	0.49 (1)	10.00			
AI-T	0 / 6545	-18.5	-18.5	0.49 (1)	10.00			
T-AJ	0 / 6156	-18.5	-18.5	0.46 (1)	10.00			
AJ-AK	0 / 6156	-18.5	-18.5	0.46 (1)	10.00			
AK-AL	0 / 6156	-18.5	-18.5	0.46 (1)	10.00			
AL-S	0 / 6156	-18.5	-18.5	0.46 (1)	10.00			
S-AM	0 / 6030	-18.5	-18.5	0.67 (1)	10.00			
AM-AN	0 / 6030	-18.5	-18.5	0.67 (1)	10.00			
AN-R	0 / 6030	-18.5	-18.5	0.67 (1)	10.00			
Q-R	0 / 384	0.0	0.0	0.16 (1)	10.00			
R-G	-936 / 0	0.0	0.0	0.21 (1)	7.81			
Q-AO	0 / 174	-18.5	-18.5	0.27 (1)	10.00			
AO-AP	0 / 174	-18.5	-18.5	0.27 (1)	10.00			
AP-AQ	0 / 174	-18.5	-18.5	0.27 (1)	10.00			
AQ-P	0 / 174	-18.5	-18.5	0.27 (1)	10.00			
P-AR	0 / 4764	-18.5	-18.5	0.57 (1)	10.00			

TOTAL WEIGHT = 2 X 242 = 485 lb

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

*** NON STANDARD GIRDER ***

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(5% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.22")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.38")

CSI: TC=0.43/1.00 (G-I), BC=0.67/1.00 (R-S), I, WB=0.61/1.00 (I-P), SSI=0.22/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23111100



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418650	T1S	1	2	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:44:49 2023 Page 2
ID:UaoF4umx8QMX1bo7QZg7Cya5EO-bp7mCsSibNy8gml 9NkfPZ9NQShCi5Hw 4RtryJHzy

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	5.0	6.0	2.00 2.00
C	TMVW+t	MT20	5.0	8.0	4.00 1.25
D	TMVW-t	MT20	5.0	6.0	2.50 2.75
E	TTWV+m	MT20	8.0	9.0	Edge 2.75
F	TMVW+t	MT20	4.0	6.0	
G	TMV+p	MT20	4.0	6.0	
H	TS-t	MT20	5.0	6.0	
I	TMVW+t	MT20	4.0	6.0	
J	TTWV+m	MT20	6.0	10.0	4.00 1.25
K	TMVW-t	MT20	5.0	8.0	2.50 3.25
M	BMV1+p	MT20	4.0	6.0	
N	BMVW-t	MT20	5.0	6.0	2.50 2.50
O	BS-t	MT20	5.0	6.0	
P	BMVWV-t	MT20	6.0	10.0	3.00 4.00
Q					
R	BVW+m	MT20	6.0	7.0	3.50 4.00
S	BMVWVW-t	MT20	10.0	12.0	5.50 4.00
T	BMVW-t	MT20	5.0	6.0	
U	BMVW+m	MT20	4.0	6.0	
V	BMVW+m	MT20	6.0	10.0	
W	BMV1+p	MT20	6.0	10.0	3.50 1.50
X	NP-w	MT20	4.0	6.0	
			3.0	4.0	2.00 1.25

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.

LOADING
TOTAL LOAD CASES: (4)


CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MAX. UNBRAC	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO		FROM TO		LENGTH	FR-TO		
AR-AS	0 / 4764	-18.5	-18.5	0.57 (1)	10.00		
AS-O	0 / 4764	-18.5	-18.5	0.57 (1)	10.00		
O-AT	0 / 4764	-18.5	-18.5	0.57 (1)	10.00		
AT-N	0 / 4764	-18.5	-18.5	0.57 (1)	10.00		
N-AU	0 / 0	-18.5	-18.5	0.09 (1)	10.00		
AU-AV	0 / 0	-18.5	-18.5	0.09 (1)	10.00		
AV-M	0 / 0	-18.5	-18.5	0.09 (1)	10.00		

SPECIFIED CONCENTRATED LOADS (LBS)									
JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	5-10-8	-84	-84	---	FRONT	VERT	DEAD	---	C1
E	5-10-8	-889	-889	---	FRONT	VERT	SNOW	---	C1
G	16-5-12	-94	-94	---	FRONT	VERT	TOTAL	---	C1
H	19-11-12	-10	-10	---	FRONT	VERT	TOTAL	---	C1
J	30-0-8	-404	-404	---	FRONT	VERT	TOTAL	---	C1
N	29-11-12	-193	-193	---	FRONT	VERT	TOTAL	---	C1
R	16-8-12	-97	-97	---	TOP	VERT	TOTAL	---	C1
U	2-8-0	-99	-99	---	TOP	VERT	TOTAL	---	C1
V	1-8-0	-200	-200	---	FRONT	VERT	TOTAL	---	C1
Y	6-5-12	-111	-111	---	FRONT	VERT	TOTAL	---	C1
Z	8-5-12	-94	-94	---	FRONT	VERT	TOTAL	---	C1
AA	10-5-12	-94	-94	---	FRONT	VERT	TOTAL	---	C1
AB	12-5-12	-94	-94	---	FRONT	VERT	TOTAL	---	C1
AC	14-5-12	-94	-94	---	FRONT	VERT	TOTAL	---	C1
AD	17-11-8	-10	-10	---	FRONT	VERT	TOTAL	---	C1
AE	21-11-12	-10	-10	---	FRONT	VERT	TOTAL	---	C1
AF	23-11-12	-10	-10	---	FRONT	VERT	TOTAL	---	C1
AG	25-11-12	-10	-10	---	FRONT	VERT	TOTAL	---	C1
AH	27-11-12	-10	-10	---	FRONT	VERT	TOTAL	---	C1
AI	4-5-12	-92	-92	---	TOP	VERT	TOTAL	---	C1
AJ	6-5-12	-92	-92	---	TOP	VERT	TOTAL	---	C1
AK	8-5-12	-92	-92	---	TOP	VERT	TOTAL	---	C1
AL	10-5-12	-92	-92	---	TOP	VERT	TOTAL	---	C1
AM	12-5-12	-92	-92	---	TOP	VERT	TOTAL	---	C1
AN	14-5-12	-92	-92	---	TOP	VERT	TOTAL	---	C1
AO	17-11-8	-193	-193	---	FRONT	VERT	TOTAL	---	C1
AP	19-11-12	-193	-193	---	FRONT	VERT	TOTAL	---	C1
AQ	21-11-12	-193	-193	---	FRONT	VERT	TOTAL	---	C1
AR	23-11-12	-193	-193	---	FRONT	VERT	TOTAL	---	C1
AS	25-11-12	-193	-193	---	FRONT	VERT	TOTAL	---	C1
AT	27-11-12	-193	-193	---	FRONT	VERT	TOTAL	---	C1
AU	31-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AV	33-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

JSI GRIP= 0.89 (N) (INPUT = 0.90)
JSI METAL= 0.88 (B) (INPUT = 1.00)



STRUCTURAL COMPONENT ONLY
DWG # TR23111100




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418650	T2S	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:44:50 2023 Page 2
ID:UaoF4umx8QMX1bo7Q0Zq7Cva5EO-37h8QCSVMh47lwKAj5FuGd6Bpqgqx8gQ8eq_PlvJH2x

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111101




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418649	T3	3	1	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:48 2023 Page 1

ID:UaoF4umx8QMx1bo7Q0Zq7Cva5EO-qKpVD1fAk02q6 ar9ewJdcTL7RqhiCpBnHJeBkyJIQ5



TOTAL WEIGHT = 3 X 192 = 576 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - H	2x4	DRY	No.2	SPF	
H - K	2x4	DRY	No.2	SPF	
U - B	2x6	DRY	No.2	SPF	
L - J	2x6	DRY	No.2	SPF	
U - R	2x4	DRY	No.2	SPF	
R - O	2x4	DRY	No.2	SPF	
O - L	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
D - Q	2x4	DRY	No.2	SPF	
Q - G	2x4	DRY	No.2	SPF	
P - H	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWV-p	MT20	6.0	7.0	Edge	
C, G, I						
D	TMWV-t	MT20	4.0	6.0		
E	TTWV-t	MT20	6.0	7.0	Edge	
F	TMW-w	MT20	2.0	4.0		
G	TS-t	MT20	3.0	8.0		
H	TTWV-t	MT20	6.0	7.0	Edge	
J	TMWV-p	MT20	6.0	7.0	Edge	
L	BMV1-p	MT20	4.0	6.0		
M	BMWV-t	MT20	5.0	6.0	2.50	2.00
N, P, S						
N	BMWV-t	MT20	4.0	6.0		
O	BS-t	MT20	3.0	8.0		
Q	BMWVW-t	MT20	4.0	10.0		
R	BS-t	MT20	3.0	8.0		
T	BMWVW-t	MT20	5.0	6.0	2.50	2.00
U	BMV1-p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQRD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
U	2841	0	2841	0
L	2841	0	2841	0

UNFACTORED REACTIONS

	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
U	1977	1479 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0
L	1977	1479 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.66 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, G-Q, G-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX LC1 (LC)
FR-TO					FR-TO		
A-B	0 / 58	-129.7	-129.7 0.18 (1)	10.00	T-C	-466 / 0	0.24 (1)
B-C	-2775 / 0	-129.7	-129.7 0.55 (1)	3.66	C-S	-259 / 0	0.28 (1)
C-D	-2654 / 0	-129.7	-129.7 0.53 (1)	3.75	S-D	0 / 292	0.07 (1)
D-E	-2481 / 0	-129.7	-129.7 0.52 (1)	3.84	D-Q	0 / 977	0.16 (1)
E-F	-2481 / 0	-129.7	-129.7 0.48 (1)	3.89	Q-E	-751 / 0	0.49 (1)
F-G	-2481 / 0	-129.7	-129.7 0.48 (1)	3.89	Q-G	-4 / 0	0.00 (1)
G-H	-2483 / 0	-129.7	-129.7 0.52 (1)	3.84	P-G	-753 / 0	0.49 (1)
H-I	-2654 / 0	-129.7	-129.7 0.53 (1)	3.75	P-H	0 / 982	0.16 (1)
I-J	-2775 / 0	-129.7	-129.7 0.55 (1)	3.66	N-H	0 / 289	0.07 (1)
J-K	0 / 58	-129.7	-129.7 0.18 (1)	10.00	N-I	-259 / 0	0.28 (1)
U-B	-2800 / 0	0.0	0.0 0.19 (1)	6.26	M-I	-465 / 0	0.24 (1)
L-J	-2800 / 0	0.0	0.0 0.19 (1)	6.26	B-T	0 / 2240	0.50 (1)
					M-J	0 / 2240	0.50 (1)
U-T	0 / 0	-18.5	-18.5 0.10 (4)	10.00			
T-S	0 / 2169	-18.5	-18.5 0.40 (1)	10.00			
S-R	0 / 1999	-18.5	-18.5 0.38 (1)	10.00			
R-Q	0 / 1999	-18.5	-18.5 0.38 (1)	10.00			
Q-P	0 / 2483	-18.5	-18.5 0.46 (1)	10.00			
P-O	0 / 1999	-18.5	-18.5 0.38 (1)	10.00			
O-N	0 / 1999	-18.5	-18.5 0.38 (1)	10.00			
N-M	0 / 2169	-18.5	-18.5 0.40 (1)	10.00			
M-L	0 / 0	-18.5	-18.5 0.10 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 38.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 51.6	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.21")

CSI: TC=0.55/1.00 (I-J:1), BC=0.46/1.00 (P-Q:1), WB=0.50/1.00 (J-M:1), SS=0.33/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (M) (INPUT = 0.90)
JSI METAL= 0.60 (R) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111079

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418650	T3S	2	1	BAYVIEW WELLINGTON TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:44:51 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-XCFWdYT77 Crw3vNHom7oqeOIEBqYlaNIZYkyJHwz



TOTAL WEIGHT = 2 X 202 = 405 lb

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - J	2x4	DRY	No.2
J - M	2x4	DRY	No.2
Y - B	2x6	DRY	No.2
N - L	2x6	DRY	No.2
Y - X	2x4	DRY	No.2
X - W	2x4	DRY	No.2
W - T	2x4	DRY	No.2
S - G	2x4	DRY	No.2
S - Q	2x4	DRY	No.2
Q - N	2x4	DRY	No.2

ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
F - T	2x4	DRY	No.2	SPF
T - R	2x4	DRY	No.2	SPF
R - J	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMWW+p	MT20	5.0	6.0	2.00 2.25
C	CTMWW-t	MT20	5.0	6.0	2.75 1.25
D, E, I, K					
D	TMWW-t	MT20	4.0	6.0	
F	TTWW+m	MT20	6.0	7.0	Edge
G	TMV+p	MT20	3.0	4.0	
H	TS-t	MT20	3.0	8.0	
J	TTWW+m	MT20	6.0	7.0	Edge
L	TMVW-p	MT20	6.0	7.0	Edge
N	BMV1+p	MT20	4.0	6.0	
O	BMWW-t	MT20	4.0	6.0	2.00 1.75
P, U, V					
P	BMWW-t	MT20	4.0	6.0	
Q	BS-t	MT20	3.0	8.0	
R	BMWWWW-t	MT20	5.0	8.0	2.25 3.25
S	BBV+h	MT20	4.0	6.0	Edge
T	BMVWWWW-I	MT20	6.0	10.0	3.00 3.50
W	BBWW+m	MT20	6.0	7.0	3.25 3.00
X	BBWW+m	MT20	6.0	7.0	Edge 2.25
Y	BMV1+p	MT20	4.0	6.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION			MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
Y	2845	0	2845	0	0	5-8	3-12
N	2838	0	2838	0	0	5-8	3-12

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
Y	1980	1481/0	0/0	0/0	0/0	498/0	0/0
N	1975	1477/0	0/0	0/0	0/0	498/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Y, N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.93 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-T, I-R.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 CSI (LBS)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 CSI (LBS)	
FR-TO		FROM	TO		FR-TO				
A-B	0/58	-129.7	-129.7	0.18 (1)	10.00	X-C	-2547/0	0.44 (1)	
B-C	-2053/0	-129.7	-129.7	0.17 (1)	4.58	C-W	0/2076	0.47 (1)	
C-D	-3315/0	-129.7	-129.7	0.19 (1)	3.72	W-D	-222/0	0.04 (1)	
D-E	-3237/0	-129.7	-129.7	0.31 (1)	3.66	U-F	0/551	0.12 (1)	
E-F	-2929/0	-129.7	-129.7	0.30 (1)	3.85	F-T	0/960	0.15 (1)	
F-G	-2827/0	-129.7	-129.7	0.89 (1)	2.93	T-R	0/2444	0.39 (1)	
G-H	-2822/0	-129.7	-129.7	0.66 (1)	3.34	T-I	0/824	0.19 (1)	
H-I	-2822/0	-129.7	-129.7	0.66 (1)	3.34	R-I	-1295/0	0.85 (1)	
I-J	-2422/0	-129.7	-129.7	0.42 (1)	4.00	R-J	0/980	0.16 (1)	
J-K	-2648/0	-129.7	-129.7	0.53 (1)	3.75	P-J	0/279	0.06 (1)	
K-L	-2771/0	-129.7	-129.7	0.55 (1)	3.66	P-K	-262/0	0.08 (1)	
L-M	0/58	-129.7	-129.7	0.18 (1)	10.00	O-K	-462/0	0.24 (1)	
Y-B	-2829/0	0.0	0.0	0.20 (1)	6.23	B-X	0/1907	0.43 (1)	
N-L	-2797/0	0.0	0.0	0.19 (1)	6.26	O-L	0/2237	0.50 (1)	
						E-U	-506/0	0.41 (1)	
						V-E	0/102	0.03 (4)	
						D-V	-137/0	0.04 (1)	
Y-X	0/0	-18.5	-18.5	0.02 (4)	10.00				
X-W	0/1996	-18.5	-18.5	0.32 (1)	10.00				
W-V	0/2612	-18.5	-18.5	0.47 (1)	10.00				
V-U	0/2502	-18.5	-18.5	0.51 (1)	10.00				
U-T	0/2227	-18.5	-18.5	0.46 (1)	10.00				
S-T	0/38	0.0	0.0	0.06 (1)	10.00				
T-G	-880/0	0.0	0.0	0.18 (1)	6.25				
S-R	0/44	-18.5	-18.5	0.10 (4)	10.00				
R-Q	0/1994	-18.5	-18.5	0.38 (1)	10.00				
Q-P	0/1994	-18.5	-18.5	0.38 (1)	10.00				
P-O	0/2166	-18.5	-18.5	0.39 (1)	10.00				
O-N	0/0	-18.5	-18.5	0.11 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	38.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.16")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.30")

CSI: TC=0.89/1.00 (F-G:1) , BC=0.51/1.00 (U-V:1) ,
WB=0.85/1.00 (I-R:1) , SSI=0.41/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES						
PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (R) (INPUT = 0.90)
JSI METAL= 0.59 (Q) (INPUT = 1.00)



STRUCTURAL COMPONENT ONLY
DWG # TR23111102

CONTINUED ON PAGE 2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418650	T3S	2	1	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:44:52 2023 Page 2
ID:UaoF4umx8QMX1bo7Q0Zg7Cva5EO-7OpvquUmulKiXDUZrVHML2BZVeX P??icyJ5UAyJHzv


PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
Z	NP+p	MT20	2.0	4.0	2.00	2.00


Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES-

- 1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111102



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - E	2x6	DRY	No.2 SPF
E - H	2x6	DRY	No.2 SPF
H - J	2x6	DRY	No.2 SPF
J - N	2x6	DRY	No.2 SPF
AA - B	2x6	DRY	No.2 SPF
O - M	2x6	DRY	No.2 SPF
AA - W	2x6	DRY	2100F 1.8E SPF
W - S	2x6	DRY	2100F 1.8E SPF
S - O	2x6	DRY	2100F 1.8E SPF
ALL WEBS EXCEPT			
Z - C	2x12	DRY	No.2 SPF
D - X	2x6	DRY	No.2 SPF
R - K	2x6	DRY	No.2 SPF
P - L	2x12	DRY	No.2 SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 3 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-E	2	12
E-H	2	12
H-J	2	12
J-N	2	12
AA-B	2	12
O-M	2	12
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
AA-W	3	4
W-S	2	12
S-O	3	4
WEBS : (0.122"x3") SPIRAL NAILS		
2x4	1	6
2x6	2	6
L-P	6	4
2x12	6	4

STAGGER NAILS BY HALF THE SURFACE SPACING IN ADJACENT PLIES.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS			
FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION	
JT	VERT	DOWN	UP
AA	3947	0	0
O	15952	0	0

UNFACTORED REACTIONS			
1ST LCASE	MAX/MIN	COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE
AA	2751	2034	0
O	11170	7959	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) AA, O
BEARING SIZE FACTOR = 1.15 AT JNT(S) O (BASED ON SUPPORT DEPTH = 1-8)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.69 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

2x6 DRY SPF No.2 T-BRACE AT F-V, G-U, I-U, J-T

FASTEN T AND I-BRACES TO NARROW EDGE OF WEB WITH ONE ROW PER PLY OF 3" COMMON WIRE NAILS @ 8" O.C. WITH 3" MINIMUM END DISTANCE. BRACE MUST COVER 90% OF WEB LENGTH.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS			
MEMB.	FORCE (LBS)	FACTORED (PLF)	MAX. FACTORED (LBS)
FR-TO			
A-B	0/60	-129.7	-129.7
B-C	-3768/0	-129.7	-129.7
C-D	-4257/0	-129.7	-129.7
D-E	-4201/0	-129.7	-129.7
E-F	-4073/0	-129.7	-129.7
F-G	-4634/0	-129.7	-129.7
G-H	-4634/0	-129.7	-129.7
H-I	-4634/0	-129.7	-129.7
I-J	-5011/0	-129.7	-129.7
J-K	-6603/0	-129.7	-129.7
K-L	-9299/0	-129.7	-129.7
L-M	-15802/0	-129.7	-129.7
M-N	0/60	-129.7	-129.7
AA-B	-3890/0	0.0	0.0
O-M	-15211/0	0.0	0.0
WEBS			
MEMB.	FORCE (LBS)	MAX. FACTORED (LBS)	MAX. FACTORED (LBS)
Z-C	-1107/0	0.02	0.02
C-Y	0/530	0.03	0.03
Y-D	-314/0	0.05	0.05
D-X	-177/0	0.03	0.03
X-E	0/246	0.01	0.01
E-V	0/2182	0.12	0.12
V-F	-1880/0	0.20	0.20
F-U	0/1444	0.08	0.08
U-G	-467/0	0.05	0.05
G-U	-969/0	0.12	0.12
T-I	0/330	0.02	0.02
I-T	-176/0	0.02	0.02
R-J	0/3968	0.21	0.21
J-R	-4485/0	0.70	0.70
K-Q	0/5017	0.27	0.27
Q-L	-6892/0	0.61	0.61
P-L	0/8825	0.22	0.22
B-Z	0/3114	0.17	0.17
P-M	0/12935	0.69	0.69

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014.

(55% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")

CSI: TC=0.33/1.00 (M-O:1), BC=0.24/1.00 (P-Q:1), WB=0.70/1.00 (K-R:1), SS=0.26/1.00 (O-P:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.84 (Z) (INPUT = 0.90)
JSI METAL= 0.85 (M) (INPUT = 1.00)





JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T4	1	3	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:49 2023 Page 2

ID:UaoF4umx8QMX1bo7Q0Zg7Cva5EO-IWNlQNfoVKAXk892ILRYmq0ZDrDJSa4L?x2BjAyJlQ4

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	8.0	9.0	2.75	4.25
C	TMVW-t	MT20	6.0	12.0	3.00	3.50
D	TMVW-t	MT20	5.0	6.0	2.50	2.25
E	TTWW+m	MT20	6.0	7.0	3.25	1.50
F	TMVW-t	MT20	4.0	6.0		
G	TMVW-t	MT20	4.0	6.0		
H	TS-t	MT20	5.0	6.0		
I	TMVW-t	MT20	4.0	6.0		
J	TTWW+m	MT20	6.0	7.0	3.25	1.50
K	TMVW-t	MT20	5.0	6.0	2.50	2.25
L	TMVW-t	MT20	6.0	12.0	3.00	3.50
M	TMVW-t	MT20	8.0	9.0	2.75	4.25
O	BMV1-t	MT20	6.0	10.0	Edge	0.50
P	BMVW-t	MT20	8.0	12.0	4.25	6.00
Q, R, X, Y						
Q	BMVW-t	MT20	5.0	6.0		
S	BS-t	MT20	5.0	6.0		
T	BMVW-t	MT20	4.0	6.0		
U	BMVW-t	MT20	5.0	8.0		
V	BMVW-t	MT20	4.0	6.0		
W	BS-t	MT20	5.0	6.0		
Z	BMVW-t	MT20	8.0	12.0	4.25	6.00
AA	BMV1-t	MT20	6.0	10.0	5.50	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-


- 1) Lateral braces to be a minimum of 2X4 SPF #2.

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
P	33-0-4	-8492	-8492	—	BACK	VERT	TOTAL	—	C1
AB	33-10-4	-1465	-1465	—	BACK	VERT	TOTAL	—	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY
DWG # TR23111080




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418649	T5	1	2	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:50 2023 Page 1

ID:UaoF4umx8QMX1bo7Q0z7Cya5EO-mjwgeigQGdLOLjEH3ynJ1YIDEQbB2AUEbolFdyJlQ3



TOTAL WEIGHT = 2 X 215 = 431 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x8 DRY	No.2	SPF		
C - F	2x6 DRY	No.2	SPF		
F - H	2x6 DRY	No.2	SPF		
H - J	2x6 DRY	No.2	SPF		
S - B	2x6 DRY	No.2	SPF		
K - I	2x6 DRY	No.2	SPF		
S - P	2x6 DRY	No.2	SPF		
P - N	2x6 DRY	No.2	SPF		
N - K	2x6 DRY	No.2	SPF		

ALL WEBS	2x4 DRY	No.2	SPF
EXCEPT			

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	2 12	SIDE(122.0)
C - F	2 12	SIDE(61.0)
F - H	2 12	TOP
H - J	2 12	TOP
S - B	2 12	TOP
K - I	2 12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
S - P	2 12	SIDE(0.0)
P - N	2 12	SIDE(183.1)
N - K	2 12	TOP
WEBS : (0.122"x3") SPIRAL NAILS		
2x4	1 6	SIDE(383.3)
E - O	1 6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	DOWN	UPLIFT	IN-SX
S	6942	0	0	5-8
K	4644	0	0	5-8

UNFACTORED REACTIONS	1ST LCASE	MAX/MIN. COMPONENT REACTIONS
JT	COMBINED	SNOW
S	4812	3709 / 0
K	3225	2450 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.91 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	W E B S	MAX. FACTORED
MEMB.	FORCE	VERT. LOAD	MEMB.	FORCE
FR-TO	(LBS)	LC1	FR-TO	(LBS)
A-B	0 / 60	-129.7	R-C	0 / 103
B-C	-6913 / 0	-129.7	C-Q	0 / 4067
C-D	-8020 / 0	-129.7	Q-D	-1751 / 0
D-T	-8890 / 0	-129.7	D-O	0 / 1323
T-U	-8890 / 0	-129.7	O-E	-632 / 0
U-E	-8890 / 0	-129.7	O-G	0 / 3202
E-F	-8890 / 0	-129.7	M-G	-3166 / 0
F-G	-8890 / 0	-129.7	M-H	0 / 4271
G-H	-6784 / 0	-129.7	L-H	-583 / 0
H-I	-5142 / 0	-129.7	B-R	0 / 5385
I-J	0 / 60	-129.7	L-I	0 / 4006
S-B	-5990 / 0	0.0		
K-I	-4601 / 0	0.0		
S-V	0 / 0	-18.5		
V-W	0 / 0	-18.5		
W-R	0 / 0	-18.5		
R-Q	0 / 5297	-18.5		
Q-P	0 / 8020	-18.5		
P-X	0 / 8020	-18.5		
X-Y	0 / 8020	-18.5		
Y-O	0 / 8020	-18.5		
O-N	0 / 6785	-18.5		
N-M	0 / 6785	-18.5		
M-L	0 / 3925	-18.5		
L-K	0 / 0	-18.5		

SPECIFIED CONCENTRATED LOADS (LBS)	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
JT	5-10-8	-58	-58	-	BACK	VERT	DEAD	-	C1
C	5-10-8	-368	-368	-	BACK	VERT	SNOW	-	C1
O	16-6-8	-1505	-1505	-	BACK	VERT	TOTAL	-	C1
P	12-2-8	-819	-819	-	BACK	VERT	TOTAL	-	C1
T	13-1-12	-10	-10	-	BACK	VERT	TOTAL	-	C1
U	15-1-12	-10	-10	-	BACK	VERT	TOTAL	-	C1
V	1-2-4	-193	-193	-	BACK	VERT	TOTAL	-	C1
W	2-7-8	-1000	-1000	-	BACK	VERT	TOTAL	-	C1
X	13-1-12	-193	-193	-	BACK	VERT	TOTAL	-	C1
Y	15-1-12	-193	-193	-	BACK	VERT	TOTAL	-	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL =	38.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

*** NON STANDARD GIRDER ***

ADDT'L USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.11")
CALCULATED VERT. DEFL.(LL) = L/999 (0.17")
ALLOWABLE DEFL.(TL) = L/360 (1.11")
CALCULATED VERT. DEFL.(TL) = L/999 (0.29")

CSI: TC=0.32/1.00 (B-C:1), BC=0.81/1.00 (O-Q:1), WB=0.71/1.00 (G-M:1), SSI=0.44/1.00 (O-Q:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (G) (INPUT = 0.90)
JSI METAL= 0.98 (P) (INPUT = 1.00)

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23111081



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T5	1	2	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:51 2023 Page 2
ID:UaoF4umx8QMX1bc7Q0Zg7Cva5EO-EvU2r3h31xQFzSIQgmT0rF5wzemqWVQdTFXIn3vJIQ2

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWW-t	MT20	5.0	8.0	2.50	3.25
C	TTWW+m	MT20	6.0	10.0	4.00	1.25
D	TMWW+t	MT20	4.0	6.0		
E	TMWW-w	MT20	4.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMWW+t	MT20	4.0	6.0		
H	TTWW+m	MT20	6.0	10.0	4.00	1.25
I	TMWW-t	MT20	5.0	8.0	2.50	3.25
K	BMV1+t	MT20	6.0	10.0	Edge	0.50
L	BMWW-t	MT20	5.0	6.0	2.50	2.00
M	BMWW+t	MT20	5.0	6.0		
N	BS-t	MT20	5.0	8.0		
O	BMWWW-t	MT20	6.0	10.0	3.50	5.00
P	BS-t	MT20	5.0	8.0		
Q	BMWW+t	MT20	5.0	6.0		
R	BMWW-t	MT20	5.0	6.0	2.50	2.00
S	BMV1+t	MT20	6.0	10.0	5.50	


Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY
DWG # TR23111081




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T6	1	1	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:51 2023 Page 1

ID:UaoF4umx8QMx1bo7Q0Zq7Cya5EO-EvU2r3h31xQFzSIQmT0rF5o8er4wZLdTFXIn3yJlQ2



TOTAL WEIGHT = 161 lb

N. L. G. A. RULES				BUILDING DESIGNER							DESIGN CRITERIA		
CHORDS		SIZE	LUMBER	DESCR.	BEARINGS							SPECIFIED LOADS:	
A - D	2x4	DRY	No.2	SPF	FACTORED		MAXIMUM FACTORED		INPUT	REQRD			
D - F	2x4	DRY	No.2	SPF	GROSS REACTION		GROSS REACTION		BRG	BRG			
F - H	2x4	DRY	No.2	SPF	JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX		
H - K	2x4	DRY	No.2	SPF	U	2644	0	2644	0	5-8	3-2		
U - B	2x6	DRY	No.2	SPF	L	2644	0	2644	0	5-8	3-2		
L - J	2x6	DRY	No.2	SPF									
U - R	2x4	DRY	No.2	SPF									
R - O	2x4	DRY	No.2	SPF									
O - L	2x4	DRY	No.2	SPF									
UNFACTORED REACTIONS													
					1ST LCASE MAX./MIN. COMPONENT REACTIONS								
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL						
U	1839	1377 / 0	0 / 0	0 / 0	0 / 0	462 / 0	0 / 0						
LOADING IN FLAT SECTION BASED ON A SLOPE													

DRY: SEASONED LUMBER.

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.33 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, E-P, G-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

M	BMV1+p	MT20	4.0	6.0																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
---	--------	------	-----	-----	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

NOTES:

1) Lateral braces to be a minimum of 2X4 SPF #2.

STRUCTURAL COMPONENT ONLY

DWG # TR23111082

11/14/23

C. M. HEYENS

100505065

PROVINCE OF ONTARIO




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418649	T7A	4	1	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:53 2023 Page 1

ID:UafF4umx8QMx1bo7Q0Zq7Cya5EO-AlcoGIIJYgzCISpyBWUwgA72SY OPTwwZ0PsvyJlQO



TOTAL WEIGHT = 4 X 165 = 662 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - H	2x4	DRY	No.2	SPF	
Q - B	2x6	DRY	No.2	SPF	
I - H	2x6	DRY	No.2	SPF	
Q - N	2x4	DRY	No.2	SPF	
N - L	2x4	DRY	No.2	SPF	
L - I	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
D - M	2x4	DRY	No.2	SPF	
M - F	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWW-p	MT20	5.0	8.0	Edge	
C	TMWW-t	MT20	4.0	8.0		
D	TTWW-m	MT20	5.0	8.0	2.00	2.25
E	TMWW-w	MT20	2.0	4.0		
F	TTWW-m	MT20	5.0	8.0	2.00	2.00
G	TMWW-t	MT20	4.0	8.0		
H	TMWW-p	MT20	5.0	8.0	Edge	
I	BMV1-p	MT20	4.0	8.0		
J	BMWW-t	MT20	4.0	8.0	2.00	2.50
K	BMWW-t	MT20	4.0	8.0		
L	BS-t	MT20	3.0	8.0		
M	BMWW-t	MT20	4.0	10.0		
N	BS-t	MT20	3.0	8.0		
O	BMWW-t	MT20	4.0	8.0		
P	BMWW-t	MT20	4.0	8.0	2.00	2.25
Q	BMV1-p	MT20	4.0	8.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	2813	0	0	5-8
Q	2433	0	0	3-0
I				MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 2-10.

UNFACTORED REACTIONS

1ST LC CASE MAX/MIN COMPONENT REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
Q	1818	1361/0	0/0	0/0	0/0	457/0	0/0
I	1695	1255/0	0/0	0/0	0/0	440/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.28 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-M.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)	
FR-TO				FR-TO			
A-B	0/58	-129.7	-129.7 0.18 (1)	10.00	P-C	-415/0	0.22 (1)
B-C	-2502/0	-129.7	-129.7 0.53 (1)	3.85	C-O	-298/0	0.32 (1)
C-D	-2347/0	-129.7	-129.7 0.50 (1)	3.98	O-D	0/332	0.07 (1)
D-E	-2167/0	-129.7	-129.7 0.86 (1)	3.28	D-M	0/699	0.11 (1)
E-F	-2167/0	-129.7	-129.7 0.86 (1)	3.28	M-E	-1075/0	0.71 (1)
F-G	-2288/0	-129.7	-129.7 0.46 (1)	4.08	M-F	0/774	0.12 (1)
G-H	-2325/0	-129.7	-129.7 0.46 (1)	4.05	K-F	0/228	0.05 (1)
Q-B	-2571/0	0.0	0.0 0.18 (1)	6.47	K-G	-158/0	0.17 (1)
I-H	-2396/0	0.0	0.0 0.18 (1)	6.65	J-G	-564/0	0.30 (1)
					B-P	0/2024	0.46 (1)
Q-P	0/0	-18.5	-18.5 0.09 (4)	10.00	J-H	0/1936	0.44 (1)
P-O	0/1959	-18.5	-18.5 0.39 (1)	10.00			
O-N	0/1764	-18.5	-18.5 0.38 (1)	10.00			
N-M	0/1764	-18.5	-18.5 0.38 (1)	10.00			
M-L	0/1721	-18.5	-18.5 0.37 (1)	10.00			
L-K	0/1721	-18.5	-18.5 0.37 (1)	10.00			
K-J	0/1823	-18.5	-18.5 0.36 (1)	10.00			
J-I	0/0	-18.5	-18.5 0.08 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.09")
CALCULATED VERT. DEFL.(LL) = L/999 (0.09")
ALLOWABLE DEFL.(TL) = L/360 (1.09")
CALCULATED VERT. DEFL.(TL) = L/999 (0.17")

CSI: TC=0.86/1.00 (D-E:1), BC=0.39/1.00 (O-P:1), WB=0.71/1.00 (E-M:1), SS=0.43/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.90 (P) (INPUT = 0.90)
JSI METAL= 0.58 (L) (INPUT = 1.00)





JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T8AS	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington					

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:54 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zq7Cya5EO-eUABT4ixKspqqv1?Wu1ITtjlosu47rt49DmyOOyJlQ?



TOTAL WEIGHT = 200 lb [M/F]

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - G	2x4	DRY	No.2	SPF	
G - H	2x4	DRY	No.2	SPF	
H - J	2x4	DRY	No.2	SPF	
U - B	2x6	DRY	No.2	SPF	
K - J	2x6	DRY	No.2	SPF	
U - R	2x4	DRY	No.2	SPF	
R - P	2x4	DRY	No.2	SPF	
P - K	2x4	DRY	No.2	SPF	

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
D - Q	2x4	DRY	No.2	SPF	
Q - F	2x4	DRY	No.2	SPF	
L - I	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	Edge	
C	TMVW-t	MT20	4.0	6.0		
D	TTVW-m	MT20	5.0	6.0	2.00	2.25
E	TMVW-w	MT20	2.0	4.0		
F	TTVW-m	MT20	5.0	6.0	2.00	2.00
G	TTVW-m	MT20	5.0	6.0		
H	TTVW-m	MT20	5.0	8.0	2.25	1.50
I	TMVW-t	MT20	4.0	6.0	2.00	2.75
J	TMVW-p	MT20	5.0	6.0	2.00	2.25
K	BMV1+p	MT20	4.0	6.0		
L	BMVW-t	MT20	5.0	6.0		
M, O, S						
M	BMVW-t	MT20	4.0	6.0		
N	BMVW-t	MT20	5.0	6.0		
P	BS-t	MT20	3.0	8.0		
Q	BMVW-t	MT20	4.0	10.0		
R	BS-t	MT20	3.0	8.0		
T	BMVW-t	MT20	5.0	6.0	2.50	2.50
U	BMV1+p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
U	2613	2613	5-8	3-0
K	2433	2433	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT K. MINIMUM BEARING LENGTH AT JOINT K = 2-10.

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
U	COMBINED	1818	1361 / 0	0 / 0	457 / 0	0 / 0
K		1695	1255 / 0	0 / 0	440 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.28 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, G-O, G-N, H-M.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC2)	MAX. FACTORED VERT. LOAD (LC3)	MAX. FACTORED VERT. LOAD (LC4)	MAX. FACTORED VERT. LOAD (LC5)	MAX. FACTORED VERT. LOAD (LC6)	MAX. FACTORED VERT. LOAD (LC7)	MAX. FACTORED VERT. LOAD (LC8)	MAX. FACTORED VERT. LOAD (LC9)	MAX. FACTORED VERT. LOAD (LC10)
FR-TO	A-B	0 / 58	-129.7	-129.7	0.18 (1)	10.00							
	B-C	-2503 / 0	-129.7	-129.7	0.53 (1)	3.85							
	C-D	-2347 / 0	-129.7	-129.7	0.50 (1)	3.98							
	D-E	-2168 / 0	-129.7	-129.7	0.86 (1)	3.28							
	E-F	-2168 / 0	-129.7	-129.7	0.86 (1)	3.28							
	F-G	-2239 / 0	-129.7	-129.7	0.06 (1)	4.53							
	G-H	-1734 / 0	-129.7	-129.7	0.15 (1)	4.93							
	H-I	-1788 / 0	-129.7	-129.7	0.18 (1)	4.85							
	I-J	-1365 / 0	-129.7	-129.7	0.16 (1)	5.40							
	U-B	-2572 / 0	0.0	0.0	0.18 (1)	6.47							
	K-J	-2409 / 0	0.0	0.0	0.49 (1)	6.64							
	U-T	0 / 0	-18.5	-18.5	0.10 (4)	10.00							
	T-S	0 / 1960	-18.5	-18.5	0.38 (1)	10.00							
	S-R	0 / 1764	-18.5	-18.5	0.39 (1)	10.00							
	R-Q	0 / 1764	-18.5	-18.5	0.39 (1)	10.00							
	Q-P	0 / 1716	-18.5	-18.5	0.39 (1)	10.00							
	P-O	0 / 1716	-18.5	-18.5	0.39 (1)	10.00							
	O-N	0 / 1750	-18.5	-18.5	0.31 (1)	10.00							
	N-M	0 / 1339	-18.5	-18.5	0.26 (1)	10.00							
	M-L	0 / 1071	-18.5	-18.5	0.21 (1)	10.00							
	L-K	0 / 0	-18.5	-18.5	0.04 (4)	10.00							

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.8	PSF

SPACING = 24.0 IN. C/C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.09")
CALCULATED VERT. DEFL.(LL)= L/999 (0.11")
ALLOWABLE DEFL.(TL)= L/360 (1.09")
CALCULATED VERT. DEFL.(TL)= L/999 (0.21")

CSI: TC=0.86/1.00 (D-E-1), BC=0.39/1.00 (Q-S-1), WB=0.72/0.90 (G-N-1), SS=0.43/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (D) (INPUT = 0.90)
JSI METAL= 0.64 (P) (INPUT = 1.00)

NOTES-

1) Lateral braces to be a minimum of 2x4 SPF #2.


STRUCTURAL COMPONENT ONLY
DWG # TR23111084



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T9A	4	1	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MITek Industries, Inc. Tue Nov 14 11:14:55 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-6gkZhQkZ5AxhS3cB3Cy05GYgFEYsHODotVWwqyJlQ



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - H	2x4	DRY	No.2	SPF	
H - J	2x4	DRY	No.2	SPF	
T - B	2x6	DRY	No.2	SPF	
K - J	2x6	DRY	No.2	SPF	
T - Q	2x4	DRY	No.2	SPF	
Q - N	2x4	DRY	No.2	SPF	
N - K	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	
D - P	2x4	DRY	No.2	SPF	
P - H	2x4	DRY	No.2	SPF	
O - I	2x4	DRY	No.2	SPF	
L - K	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-p	MT20	5.0	8.0	Edge	
C TMWW-t	MT20	4.0	6.0		
D TTWW-m	MT20	5.0	6.0	2.00	2.00
E TMW+w	MT20	2.0	4.0		
F TS-t	MT20	3.0	8.0		
G TMWW-t	MT20	4.0	6.0		
H TTWW+m	MT20	5.0	6.0	2.25	1.50
I TMWW-t	MT20	4.0	6.0	2.00	2.75
J TMVW-p	MT20	5.0	6.0	2.00	2.25
K BMV1+p	MT20	4.0	6.0		
L BMWW+t	MT20	5.0	6.0		
M BMWW-t	MT20	4.0	6.0		
N BS-t	MT20	3.0	8.0		
O BMWW+t	MT20	4.0	6.0		
P BMWW-t	MT20	4.0	10.0		
Q BS-t	MT20	3.0	8.0		
R BMWW-t	MT20	4.0	6.0		
S BMWW-t	MT20	5.0	6.0	2.50	2.50
T BMV1+p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
T	2613	0	2613	0
K	2433	0	2433	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT K. MINIMUM BEARING LENGTH AT JOINT K = 2-10.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX / MIN	COMPONENT REACTIONS	LIVE	PERM. LIVE	WIND	DEAD	SOIL
T	1818	1361 / 0	0 / 0	0 / 0	0 / 0	0 / 0	457 / 0	0 / 0
K	1695	1255 / 0	0 / 0	0 / 0	0 / 0	0 / 0	440 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.85 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-P, G-O, H-M.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX	CS1 (LC)	UNBRACED LENGTH	FR-TO	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX	CS1 (LC)
A-B	0 / 58	-129.7	-129.7	0.18 (1)	10.00	S-C	-411 / 0	0.22 (1)	C-R	-300 / 0	0.32 (1)		
B-C	-2503 / 0	-129.7	-129.7	0.53 (1)	3.98	R-D	0 / 322	0.07 (1)	D-P	0 / 716	0.12 (1)		
C-D	-2346 / 0	-129.7	-129.7	0.49 (1)	4.14	P-E	-753 / 0	0.50 (1)	E-F	-129.7	-129.7	0.46 (1)	4.19
D-E	-2116 / 0	-129.7	-129.7	0.46 (1)	4.19	F-G	-129.7	-129.7	0.46 (1)	4.19	G-H	-1991 / 0	-129.7
E-F	-2116 / 0	-129.7	-129.7	0.46 (1)	4.19	H-I	-1637 / 0	-129.7	-129.7	0.23 (1)	4.74	O-H	0 / 1249
F-G	-2116 / 0	-129.7	-129.7	0.46 (1)	4.19	I-J	-1463 / 0	-129.7	-129.7	0.22 (1)	5.19	M-H	-378 / 0
G-H	-1991 / 0	-129.7	-129.7	0.46 (1)	4.19	J-K	-2572 / 0	0.0	0.0	0.18 (1)	6.47	B-S	0 / 2024
H-I	-1637 / 0	-129.7	-129.7	0.46 (1)	4.19	K-L	-2405 / 0	0.0	0.0	0.49 (1)	6.65	M-I	0 / 514
I-J	-1463 / 0	-129.7	-129.7	0.46 (1)	4.19	L-K	0 / 0	-18.5	-18.5	0.10 (4)	10.00	L-J	0 / 1715
J-K	-2572 / 0	0.0	0.0	0.18 (1)	6.47			-18.5	-18.5	0.37 (1)	10.00		
K-L	-2405 / 0	0.0	0.0	0.49 (1)	6.65			-18.5	-18.5	0.34 (1)	10.00		
								-18.5	-18.5	0.34 (1)	10.00		
								-18.5	-18.5	0.38 (1)	10.00		
								-18.5	-18.5	0.28 (1)	10.00		
								-18.5	-18.5	0.28 (1)	10.00		
								-18.5	-18.5	0.23 (1)	10.00		
								-18.5	-18.5	0.05 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.09")
CALCULATED VERT. DEFL.(LL) = L/999 (0.10")
ALLOWABLE DEFL.(TL) = L/360 (1.09")
CALCULATED VERT. DEFL.(TL) = L/999 (0.16")

CSI: TC=0.53/1.00 (B-C:1), BC=0.38/1.00 (O-P:1), WB=0.77/1.00 (L-L:1), SSI=0.33/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (H) (INPUT = 0.90)
JSI METAL= 0.53 (Q) (INPUT = 1.00)



STRUCTURAL COMPONENT ONLY
DWG # TR23111085

NOTES

1) Lateral braces to be a minimum of 2X4 SPF #2.



JOB NAME 418649	TRUSS NAME T10A	QUANTITY 1	PLY 3	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington		Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:56 2023 Page 2			

ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-btlxumlBsT3Y3DBOdJ3BYlomOfa4bp?NcXF3SGyJIPz

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	6.0	7.0	1.75	3.50
B	TMWW-t	MT20	5.0	6.0	2.50	2.75
C	TMWW-t	MT20	5.0	6.0	2.50	2.00
D	TTW+p	MT20	5.0	8.0		
E	TMWW-t	MT20	5.0	6.0	2.50	2.75
F	TMVW+p	MT20	5.0	6.0	1.50	2.75
G	BMV1+t	MT20	5.0	14.0	Edge	0.50
H	BMWW+t	MT20	4.0	10.0		
I	BMWW-t	MT20	8.0	9.0		
J	BMWW+t	MT20	5.0	6.0		
K	BS-t	MT20	5.0	6.0		
L	BMWW+t	MT20	6.0	10.0		
M	BMV1+p	MT20	6.0	10.0	Edge	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-


- 1) Lateral braces to be a minimum of 2X4 SPF #2.

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
Q	9-0-4	-1681	-1681	—	FRONT	VERT	TOTAL	—	C1
R	13-0-4	-1681	-1681	—	FRONT	VERT	TOTAL	—	C1
S	15-0-4	-1681	-1681	—	FRONT	VERT	TOTAL	—	C1
T	16-0-4	-1681	-1681	—	FRONT	VERT	TOTAL	—	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY
DWG # TR23111086




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T11A	2	1	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MITek Industries, Inc. Tue Nov 14 11:14:57 2023 Page 1

ID:UaoF4umx8QMX1bo7QOZq7Cya5EO-33rj66mpcnBPhNmaB1aQ5WLwm3u6KEjWrA d jvJlPy



Scale = 1:62.8

TOTAL WEIGHT = 2 X 114 = 229 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - H	2x4	DRY	No.2	SPF	
O - B	2x6	DRY	No.2	SPF	
P - H	2x6	DRY	No.2	SPF	
O - L	2x4	DRY	No.2	SPF	
K - I	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
L - F	2x4	DRY	No.2	SPF	
M - K	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW-p	MT20	5.0	8.0	Edge	
C, E, G						
C	TMW-t	MT20	4.0	6.0		
D	TS-t	MT20	3.0	8.0		
F	TTW+p	MT20	4.0	6.0	Edge	
H	TMW+p	MT20	5.0	6.0	2.00	2.25
I	BVM-i	MT20	8.0	9.0		3.50
J	BMW-w	MT20	4.0	6.0		
K	BMW-w	MT20	8.0	9.0	3.50	2.75
L	BMW-w	MT20	2.0	4.0		
M	BMW-w	MT20	5.0	6.0	2.25	1.50
N	BMW-w	MT20	4.0	6.0		
O	BMV1+p	MT20	4.0	6.0		
P	EBSP-t	MT20	5.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	DOWN	IN-SX	IN-SX
O	1851	0	5-8	2-0
P	2018	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT P. MINIMUM BEARING LENGTH AT JOINT P = 3-8.

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
O	1324	783 / 0	0 / 0	0 / 0	0 / 0	541 / 0	0 / 0	0 / 0
P	1479	677 / 0	0 / 0	0 / 0	0 / 0	802 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.87 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

MAX. UNBRACED INTERIOR CHORD LENGTH = 10.00 FT

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	CS1 (LC)	UNBRAC LENGTH	FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	CS1 (LC)
A-B	0 / 58	-129.7	-129.7	0.20	(1)	10.00	M-E	0 / 216	0.08	(4)
B-C	-1565 / 0	-129.7	-129.7	0.33	(1)	4.87	L-K	0 / 227	0.07	(4)
C-D	-1478 / 0	-129.7	-129.7	0.32	(1)	4.99	K-F	0 / 1119	0.22	(4)
D-E	-1478 / 0	-129.7	-129.7	0.32	(1)	4.99	M-K	0 / 1161	0.21	(1)
E-F	-1167 / 0	-129.7	-129.7	0.26	(1)	5.55	E-K	-528 / 0	0.59	(1)
F-G	-1175 / 0	-129.7	-129.7	0.27	(1)	5.52	K-G	-6 / 15	0.01	(4)
G-H	-1105 / 0	-129.7	-129.7	0.27	(1)	5.66	J-G	-545 / 0	0.52	(1)
O-B	-1817 / 0	0.0	0.0	0.14	(1)	7.37	J-H	0 / 1324	0.33	(1)
P-I	-2018 / 0	0.0	0.0	0.15	(1)	7.08	C-M	-153 / 33	0.09	(1)
I-H	-1906 / 0	0.0	0.0	0.42	(1)	7.23	N-C	-340 / 0	0.12	(1)
O-N	0 / 0	-18.5	-18.5	0.07	(4)	10.00	B-N	0 / 1291	0.32	(1)
N-Q	0 / 1225	-18.5	-18.5	0.48	(4)	10.00				
Q-M	0 / 1225	-18.5	-80.8	0.48	(4)	10.00				
M-L	0 / 10	-80.8	-153.1	0.37	(4)	10.00				
K-J	0 / 871	-145.0	-112.0	0.50	(4)	10.00				
J-I	0 / 0	-112.0	-74.7	0.37	(4)	10.00				

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

*** NON STANDARD GIRDER ***

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.59")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.59")
CALCULATED VERT. DEFL.(TL) = L/999 (0.09")

CSI: TC=0.42/1.00 (H-I:1), BC=0.50/1.00 (J-K:4), WB=0.59/1.00 (E-K:1), SSI=0.35/1.00 (J-K:4)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.81 (M) (INPUT = 0.90)
JSI METAL= 0.39 (J) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111087



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T12	2	1	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:18 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-4Q06W9DKe1iPWZJjOb8IBvElbzPuDBV1QgyCyJHd7



Scale = 1:32.5

TOTAL WEIGHT = 2 X 40 = 79 lb

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				DESIGN CRITERIA			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.	BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD	SPECIFIED LOADS:	
A - C	2x4	DRY	No.2	SPF	GROSS REACTION	DOWN	DOWN	BRG	BRG	TOP CH. LL = 38.3 PSF	
C - E	2x4	DRY	No.2	SPF	VERT	0	0	IN-SX	IN-SX	DL = 6.0 PSF	
H - B	2x4	DRY	No.2	SPF	H	810	810	5-8	1-8	BOT CH. LL = 0.0 PSF	
F - D	2x4	DRY	No.2	SPF	F	810	810	MECHANICAL		DL = 7.4 PSF	
H - F	2x4	DRY	No.2	SPF						TOTAL LOAD = 51.6 PSF	
ALL WEBS	2x3	DRY	No.2	SPF	A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.						
EXCEPT											

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
C	TTW+p	MT20	4.0	6.0	Edge	
D	TMVW+p	MT20	4.0	6.0	Edge	
F	BMV1+p	MT20	3.0	4.0		
G	BMVWW-t	MT20	4.0	6.0		
H	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

UNFACTORED REACTIONS

JT	1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	581	431/0	0/0	0/0	0/0	0/0	131/0	0/0
F	581	431/0	0/0	0/0	0/0	0/0	131/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0/58	-129.7 -129.7	0.18 (1)	G-C	-78/61	0.03 (1)	
B-C	-369/0	-129.7 -129.7	0.30 (1)	B-G	0/297	0.07 (1)	
C-D	-369/0	-129.7 -129.7	0.30 (1)	G-D	0/297	0.07 (1)	
D-E	0/58	-129.7 -129.7	0.18 (1)				
H-B	-779/0	0.0 0.0	0.08 (1)				
F-D	-779/0	0.0 0.0	0.08 (1)				
H-G	0/0	-18.5 -18.5	0.09 (4)				
G-F	0/0	-18.5 -18.5	0.09 (4)				

NOTES-


1) Lateral braces to be a minimum of 2X4 SPF #2.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.49 (B) (INPUT = 0.90)
JSI METAL= 0.27 (D) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111108

STRUCTURAL COMPONENT ONLY
DWG # TR23111057



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T13	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:58 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-XFPhJSmSN5JFJXLmk5fdtLTLM3hff4qkAW9yJlP



TOTAL WEIGHT = 83 lb

LUMBER					DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER										DESIGN CRITERIA			[M][F]
N. L. G. A. RULES					BEARINGS										SPECIFIED LOADS:			
CHORDS	SIZE		LUMBER	DESCR.	FACTORED			MAXIMUM FACTORED			INPUT	REQRD	TOP CH.	LL	PSF			
A - D	2x4	DRY	No.2	SPF	GROSS REACTION			GROSS REACTION			BRG	BRG	DL	=	38.3	PSF		
D - E	2x4	DRY	No.2	SPF	JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	DL	=	6.0	PSF		
E - H	2x4	DRY	No.2	SPF	M	1409	0	1409	0	0	MECHANICAL		DL	=	0.0	PSF		
M - B	2x4	DRY	No.2	SPF	I	1409	0	1409	0	0	5-8	1-8	DL	=	7.4	PSF		
I - G	2x4	DRY	No.2	SPF	A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT M. MINIMUM													
M - K	2x4	DRY	No.2	SPF														
K - I	2x4	DRY	No.2	SPF														
ALL WEBS																		
EXCEPT																		

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TTWW-t	MT20	4.0	6.0		
D	TTW+h	MT20	3.0	4.0	2.00	1.00
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMVW-t	MT20	4.0	6.0		
G	TMV+p	MT20	3.0	4.0		
I	BMVW1-t	MT20	4.0	6.0		
J	BMVW-t	MT20	4.0	6.0		
K	BS-t	MT20	3.0	8.0		
L	BMVW-t	MT20	4.0	6.0		
M	BMVW1-t	MT20	4.0	6.0		

NOTES:
1) Lateral braces to be a minimum of 2X4 SPF #2.

UNFACTORED REACTIONS

1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	979	740 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0
M	979	740 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0
I	979	740 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.12 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 58	-129.7 -129.7	0.18 (1)	C-L	-181 / 0	0.09 (1)	
B-C	0 / 33	-129.7 -129.7	0.24 (1)	L-D	0 / 236	0.05 (1)	
C-D	-957 / 0	-129.7 -129.7	0.20 (1)	L-E	0 / 2	0.00 (1)	
D-E	-711 / 0	-129.7 -129.7	0.14 (1)	J-E	0 / 234	0.05 (1)	
E-F	-956 / 0	-129.7 -129.7	0.20 (1)	J-F	-181 / 0	0.09 (1)	
F-G	0 / 33	-129.7 -129.7	0.24 (1)	M-C	-1301 / 0	0.61 (1)	
G-H	0 / 58	-129.7 -129.7	0.18 (1)	F-I	-1300 / 0	0.61 (1)	
M-B	-349 / 0	0.0	0.04 (1)				
I-G	-349 / 0	0.0	0.04 (1)				
M-L	0 / 826	-18.5 -18.5	0.24 (1)				
L-K	0 / 711	-18.5 -18.5	0.22 (4)				
K-J	0 / 711	-18.5 -18.5	0.22 (4)				
J-I	0 / 826	-18.5 -18.5	0.24 (1)				

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.09")

CSI: TC=0.24/1.00 (F-G-1), BC=0.24/1.00 (J-I-1),
WB=0.61/1.00 (C-M-1), SSI=0.16/1.00 (E-F-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.82 (C) (INPUT = 0.90)
JSI METAL= 0.36 (K) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111088



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T14	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:59 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cva5EO-7Rz4Xon48OR6wgwzISduAxQGfTeDo4apJUTi2byJIPw



Scale = 1:49.7

TOTAL WEIGHT = 82 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
L - B	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	5.0	6.0		
D	TTWW+p	MT20	4.0	6.0	Edge	
E	TMWW-t	MT20	5.0	6.0		
F	TMV+p	MT20	3.0	4.0		
H	BMWW-t	MT20	4.0	6.0		
I	BMWW-t	MT20	4.0	6.0		
J	BS-t	MT20	3.0	8.0		
K	BMWW-t	MT20	4.0	6.0		
L	BMWW-t	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS								
	FACTORED		MAXIMUM FACTORED			INPUT	REQRD	
	GROSS REACTION		GROSS REACTION			BRG	BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
L	1409	0	1409	0	0			
H	1409	0	1409	0	0	MECHANICAL	1-8	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT L. MINIMUM BEARING LENGTH AT JOINT L = 1-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	979	740 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0
H	979	740 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.83 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 58	-129.7 -129.7	0.18 (1)	D-I	0 / 446	0.10 (1)	
B-C	0 / 41	-129.7 -129.7	0.36 (1)	I-E	-326 / 0	0.14 (1)	
C-D	-1028 / 0	-129.7 -129.7	0.29 (1)	K-D	0 / 446	0.10 (1)	
D-E	-1028 / 0	-129.7 -129.7	0.29 (1)	C-K	-326 / 0	0.14 (1)	
E-F	0 / 41	-129.7 -129.7	0.36 (1)	L-C	-1303 / 0	0.89 (1)	
F-G	0 / 58	-129.7 -129.7	0.18 (1)	E-H	-1303 / 0	0.89 (1)	
L-B	-382 / 0	0.0 0.0	0.04 (1)				
H-F	-382 / 0	0.0 0.0	0.04 (1)				
L-K	0 / 854	-18.5 -18.5	0.20 (1)				
K-J	0 / 618	-18.5 -18.5	0.17 (4)				
J-I	0 / 618	-18.5 -18.5	0.17 (4)				
I-H	0 / 854	-18.5 -18.5	0.20 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.36/1.00 (B-C-1), BC=0.20/1.00 (K-L-1), WB=0.89/1.00 (C-L-1), SSI=0.20/1.00 (C-D-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.78 (C) (INPUT = 0.90)
JSI METAL= 0.32 (C) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111089

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T15	2	1	BAYVIEW WELLINGTON TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 Mitek Industries, Inc. Tue Nov 14 11:15:00 2023 Page 1
ID:UaoF4umx8QMx1bo7Q0Zq7Cya5EO-TeXSk8oivZzYqU9s987j8zT4GtBXYByX8DHb2yJIPv



Scale = 1:37.2

TOTAL WEIGHT = 2 X 65 = 131 lb

LUMBER

N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
E - H	2x4	DRY	No.2	SPF
K - B	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF

ALL WEBS	2x3	DRY
EXCEPT		

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+ ϕ	MT20	3.0	4.0		
C	TMWW-t	MT20	5.0	6.0	2.50	2.75
D	TTW+ ϕ	MT20	3.0	4.0	2.50	1.25
E	TTW+ ϕ	MT20	3.0	4.0	2.50	1.25
F	TMWW-t	MT20	5.0	6.0	2.50	2.75
G	TMV+ ϕ	MT20	3.0	4.0		
I	BMVW1-t	MT20	5.0	6.0		
J	BMVWWWW*-I	MT20	4.0	10.0		
K	BMVW1-t	MT20	5.0	6.0		

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111090

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
JT	VERT	HQRZ	DOWN	HQRZ	UPLIFT	IN-SX	IN-SX
K	2101	0	2101	0	0	5-8	2-4
I	2100	0	2100	0	0	3-0	2-4

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					SOIL
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	
K	1462	1096 / 0	0 / 0	0 / 0	0 / 0	366 / 0	0 / 0
I	1461	1095 / 0	0 / 0	0 / 0	0 / 0	366 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.69 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
FACTORED		FACTORED			FACTORED		FACTORED		
MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	LOCAL (PLF)	MAX. CSI (LC)	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO		LENGTH	FR-TO			
A-B	0 / 58	-129.7	-129.7	0.20 (1)	10.00	C-J	0 / 101	0.02 (1)	
B-C	0 / 25	-129.7	-129.7	0.18 (1)	10.00	K-F	0 / 100	0.02 (1)	
C-D	-1835 / 0	-129.7	-129.7	0.23 (1)	4.69	K-C	-2148 / 0	0.80 (1)	
D-E	-1420 / 0	-129.7	-129.7	0.06 (1)	5.41	F-I	-2146 / 0	0.80 (1)	
E-F	-1834 / 0	-129.7	-129.7	0.23 (1)	4.69	D-J	0 / 314	0.08 (1)	
F-G	0 / 25	-129.7	-129.7	0.18 (1)	10.00	J-E	0 / 325	0.08 (1)	
G-H	0 / 58	-129.7	-129.7	0.20 (1)	10.00				
K-B	-329 / 0	0.0	0.0	0.04 (1)	7.81				
I-G	-329 / 0	0.0	0.0	0.04 (1)	7.81				
K-L	0 / 1321	-18.5	-18.5	0.67 (1)	10.00				
L-M	0 / 1321	-18.5	-18.5	0.67 (1)	10.00				
M-N	0 / 1321	-18.5	-18.5	0.67 (1)	10.00				
N-J	0 / 1321	-18.5	-18.5	0.67 (1)	10.00				
J-O	0 / 1320	-18.5	-18.5	0.67 (1)	10.00				
O-P	0 / 1320	-18.5	-18.5	0.67 (1)	10.00				
P-Q	0 / 1320	-18.5	-18.5	0.67 (1)	10.00				
Q-I	0 / 1320	-18.5	-18.5	0.67 (1)	10.00				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
D	5-11-12	-421	-421	—	BACK	VERT	TOTAL	—	C1
E	7-0-14	-413	-413	—	BACK	VERT	TOTAL	—	C1
L	1-11-4	-29	-29	—	BACK	VERT	TOTAL	—	C1
M	3-11-4	-29	-29	—	BACK	VERT	TOTAL	—	C1
N	6-11-4	-193	-193	—	BACK	VERT	TOTAL	—	C1
O	7-0-12	-193	-193	—	BACK	VERT	TOTAL	—	C1
P	9-0-12	-29	-29	—	BACK	VERT	TOTAL	—	C1
Q	11-0-12	-29	-29	—	BACK	VERT	TOTAL	—	C1

CONNECTION REQUIREMENTS

1) **C1:** A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL =	38.3	PSF
		DL =	6.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015.

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.43")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.43")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.11")

CSI: TC=0.23/1.00 (C-D:1), BC=0.67/1.00 (J-K:1),
WB=0.80/1.00 (C-K:1), SS=0.34/1.00 (I-J:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES						
PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.87 (C) (INPUT = 0.90)
JSI METAL= 0.48 (C) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T16	2	1	BAYVIEW WELLINGTON TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:15:01 2023 Page 1
607Q0Zg7Cya5EO-xq5qxUpKg0hqA 3LQsfMFMVe4qMEGA66moyq7UyJIPu

Scale = 1:34.9



TOTAL WEIGHT = 2 X 53 = 106 lb

LUMBER

N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
N - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
N - M	2x4	DRY	No.2	SPF
M - C	2x4	DRY	No.2	SPF
L - J	2x6	DRY	No.2	SPF
I - E	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x4	DRY	No.2	SPF
K - D	2x3	DRY	No.2	SPF
K - E	2x3	DRY	No.2	SPF
C - K	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.


PLATES (table is in inches)

J	T	PLATES	W	L	E	X
B	TMVW+p	MT20	4.0	6.0	Edge	
C	TMVW+p	MT20	4.0	6.0	Edge	2.00
D	TTW+p	MT20	4.0	6.0	Edge	
E	TMVW+p	MT20	4.0	6.0	Edge	2.00
F	TMVW+p	MT20	4.0	6.0	Edge	
H	BMVW1-t	MT20	4.0	6.0		
I	BMV+p	MT20	3.0	4.0		
J	BVMVW1-t	MT20	5.0	8.0	2.75	6.00
K	BMVWVW1-t	MT20	5.0	6.0		
L	BVMVW1-t	MT20	5.0	8.0	1.50	6.00
M	BMV+p	MT20	3.0	4.0		
N	BMVW1-t	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111091

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
N	871	0	871	0	0	MECHANICAL	
H	871	0	871	0	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT N, H. MINIMUM BEARING LENGTH AT JOINT N = 1-8, JOINT H = 1-8.

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
N	604	463 / 0	0 / 0	0 / 0	0 / 0	142 / 0	0 / 0
H	604	463 / 0	0 / 0	0 / 0	0 / 0	142 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED				
MEMB.	FORCE (LBS)	VERT. LOAD	LC1	MAX. (PLF)	MAX. CSI (LC)	UNBRAC	MEMB.	FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO			LENGTH	FR-TO		
A-B	0/58	-129.7	-129.7	0.18 (1)	10.00	K-D	0/208	0.05 (1)	
B-C	-748/0	-129.7	-129.7	0.17 (1)	6.25	K-E	-411/0	0.11 (1)	
C-D	-508/0	-129.7	-129.7	0.21 (1)	6.25	K-K	-260/0	0.07 (1)	
D-E	-502/0	-129.7	-129.7	0.21 (1)	6.25	B-L	0/604	0.10 (1)	
E-F	-919/0	-129.7	-129.7	0.17 (1)	6.25	N-L	-39/0	0.00 (1)	
F-G	0/568	-129.7	-129.7	0.18 (1)	10.00	J-F	0/716	0.12 (1)	
N-B	-833/0	0.0	0.0	0.09 (1)	7.81	J-H	-50/0	0.01 (1)	
H-F	-822/0	0.0	0.0	0.09 (1)	7.81				
N-M	0/26	-18.5	-18.5	0.01 (1)	10.00				
M-L	0/10	0.0	0.0	0.04 (1)	10.00				
L-C	-122/1	0.0	0.0	0.03 (1)	7.81				
L-K	0/618	-18.5	-18.5	0.09 (1)	10.00				
K-J	0/765	-18.5	-18.5	0.11 (1)	10.00				
I-J	0/10	0.0	0.0	0.05 (1)	10.00				
J-E	0/40	0.0	0.0	0.06 (1)	10.00				
I-H	0/29	-18.5	-18.5	0.01 (1)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL =	38.3	PSF
		DL =	6.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL-BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.31")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.31")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.01")

CSI: TC=0.21/1.00 (D-E:1), BC=0.11/1.00 (J-K:1),
WB=0.12/1.00 (F-J:1), SSI=0.17/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.60 (J) (INPUT = 0.90)


JSI METAL= 0.45 (F) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T17	1	1	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MITek Industries, Inc. Tue Nov 14 11:15:02 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zq7Cya5EO-P0fC9qpyRJphn8eX aAboZ2nj4hp?bUF?SiOfwyJIPf



TOTAL WEIGHT = 51 lb

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				DESIGN CRITERIA			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.	BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQRD	SPECIFIED LOADS:	
A - B	2x4	DRY	No.2	SPF	GROSS REACTION	VERT	GROSS REACTION	BRG	BRG	TOP CH. LL = 38.3 PSF	
B - D	2x4	DRY	No.2	SPF	DOWN	HORZ	DOWN	IN-SX	IN-SX	DL = 6.0 PSF	
E - D	2x4	DRY	No.2	SPF	UP	UP	UP	MECHANICAL	MECHANICAL	BOT CH. LL = 0.0 PSF	
H - A	2x4	DRY	No.2	SPF	DOWN	HORZ	DOWN	IN-SX	IN-SX	DL = 7.4 PSF	
H - E	2x4	DRY	No.2	SPF	UP	UP	UP	MECHANICAL	MECHANICAL	DL = 7.4 PSF	
ALL WEBS	2x3	DRY	No.2	SPF	A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E, H. MINIMUM BEARING LENGTH AT JOINT E = 1-8, JOINT H = 1-8.						
EXCEPT										TOTAL LOAD = 51.6 PSF	
DRY: SEASONED LUMBER.										SPACING = 24.0 IN. C/C	

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW+p	MT20	4.0	6.0	Edge
B	TTWW+m	MT20	5.0	6.0	2.25 1.50
C	TMVW+w	MT20	2.0	4.0	
D	TMVW-t	MT20	4.0	6.0	
E	BMV1+p	MT20	3.0	4.0	
F	BMVWW-t	MT20	4.0	6.0	
G	BMVWW-t	MT20	4.0	6.0	
H	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.

UNFACTORED REACTIONS									
JT	1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
E	482	357 / 0	0 / 0	0 / 0	0 / 0	0 / 0	125 / 0	0 / 0	
H	482	357 / 0	0 / 0	0 / 0	0 / 0	0 / 0	125 / 0	0 / 0	

BRACING									
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.									
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.									
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.									

LOADING									
TOTAL LOAD CASES: (4)									
CHORDS					WEBS				
MEMB.	MAX. FACTORED	FORCE	FACTORED		MEMB.	MAX. FACTORED	FORCE	MAX	
FR-TO	(LBS)		VERT. LOAD LC1	MAX. UNBRAC	FR-TO	(LBS)		CS	(LC)
A-B	-228 / 0		-129.7 -129.7	0.04 (1)	6.25	G-B	-404 / 0	0.15 (1)	
B-C	-397 / 0		-129.7 -129.7	0.35 (1)	6.25	A-G	0 / 492	0.11 (1)	
C-D	-397 / 0		-129.7 -129.7	0.35 (1)	6.25	B-F	0 / 357	0.08 (1)	
E-D	-659 / 0		0.0 0.0	0.27 (1)	7.81	F-C	-846 / 0	0.24 (1)	
H-A	-689 / 0		0.0 0.0	0.18 (1)	7.81	F-D	0 / 604	0.14 (1)	
H-G	0 / 0		-18.5 -18.5	0.03 (4)	10.00				
G-F	0 / 164		-18.5 -18.5	0.08 (4)	10.00				
F-E	0 / 0		-18.5 -18.5	0.07 (4)	10.00				

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(5% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.31")
CALCULATED VERT. DEFL.(LL)= L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.31")
CALCULATED VERT. DEFL.(TL)= L/999 (0.02")

CSI: TC=0.35/1.00 (C-D:1), BC=0.08/1.00 (F-G:4), WB=0.24/1.00 (C-F:1), SSI=0.25/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.72 (F) (INPUT = 0.90)
JSI METAL= 0.18 (F) (INPUT = 1.00)



STRUCTURAL COMPONENT ONLY
DWG # TR23111092




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T18C	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Tamarack Roof Truss, Burlington

ID:UaoF4umx8QMX1bo7Q0Zq7Cya5EO-tDDaM9qaCdxYPIDkXHqKnwU02k5PPD6RxBMMyJIPs

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:15:03 2023 Page 1



Scale = 1:34.0

TOTAL WEIGHT = 37 lb

LUMBER		N. L. G. A. RULES		LUMBER	DESCR.
CHORDS	SIZE	SIZE			
A - B	2x6	DRY	No.2	SPF	
C - B	2x6	DRY	No.2	SPF	
D - A	2x6	DRY	No.2	SPF	
D - C	2x6	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMW+p	MT20	5.0	6.0	2.00	2.25
B	TMV+p	MT20	4.0	6.0		
C	BMW1+t	MT20	5.0	6.0		
D	BMV1+p	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ.	UPLIFT	IN-SX	IN-SX
C	1164	0	1164	0	0	MECHANICAL	
D	488	0	488	0	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C, D. MINIMUM BEARING LENGTH AT JOINT C = 1-8, JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
C	807	622 / 0	0 / 0	0 / 0	0 / 0	184 / 0	0 / 0
D	342	243 / 0	0 / 0	0 / 0	0 / 0	99 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED		WEBS		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX (PLF)	MEMB.	FORCE (LBS)	MAX. (LC)	
FR-TO		FROM	TO	FR-TO			
A-E	0 / 206	-129.7	-129.7	0.49 (1)	6.25	A-C	0 / 0
E-B	0 / 206	-129.7	-129.7	0.49 (1)	6.25		
C-B	-1056 / 0	0.0	0.0	0.39 (1)	7.81		
D-A	-413 / 0	0.0	0.0	0.03 (1)	7.81		
D-F	0 / 0	-18.5	-18.5	0.15 (4)	10.00		
F-G	0 / 0	-18.5	-18.5	0.15 (4)	10.00		
G-H	0 / 0	-18.5	-18.5	0.15 (4)	10.00		
H-C	0 / 0	-18.5	-18.5	0.15 (4)	10.00		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	4-10-8	-376	-376	---	BACK	VERT	TOTAL	---	C1
E	4-11-4	-154	-154	---	BACK	VERT	TOTAL	---	C1
F	1-11-4	-21	-21	---	BACK	VERT	TOTAL	---	C1
G	3-11-4	-21	-21	---	BACK	VERT	TOTAL	---	C1
H	4-11-4	-26	-26	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/999 (0.02")

CSI: TC=0.49/1.00 (A-B:1), BC=0.15/1.00 (C-D:4),
WB=0.00/1.00 (A-C:1), SSI=0.54/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747
			788
			1987
			1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.26 (C) (INPUT = 0.90)

JSI METAL= 0.28 (B) (INPUT = 1.00)

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111093



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T19	1	2	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:20 2023 Page 2
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-0pWsxrFaALHQfqiigpdcrc ZTOc9MxooALyn75yJHcz

V-B 1 6
N-K 1 6

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	6.0	10.0	3.00	4.75
C	TMWW-t	MT20	5.0	6.0	2.50	2.00
D	TTWW+m	MT20	6.0	7.0	3.25	1.50
E	TMWW+t	MT20	4.0	6.0		
F	TMW+w	MT20	4.0	6.0		
G	TS-t	MT20	5.0	6.0		
H	TMWW+t	MT20	4.0	6.0		
I	TTWW+m	MT20	6.0	7.0	3.25	1.50
J	TMWW-t	MT20	5.0	6.0	2.50	2.00
K	TMVW-t	MT20	6.0	10.0	3.00	4.75
M	BMV1+t	MT20	6.0	10.0	Edge	0.50
N	BMWW+t	MT20	6.0	10.0	Edge	2.50
O	BMWW-t	MT20	5.0	6.0		
P	BS-t	MT20	5.0	6.0		
Q	BMWW+t	MT20	4.0	6.0		
R	BMWWW-t	MT20	5.0	8.0		
S	BMWW+t	MT20	4.0	6.0		
T	BS-t	MT20	5.0	6.0		
U	BMWW-t	MT20	5.0	6.0		
V	BMWW+t	MT20	6.0	10.0	Edge	2.50
W	BMV1+t	MT20	6.0	10.0	5.50	


Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




STRUCTURAL COMPONENT ONLY
DWG # TR23111109

JOB NAME 418651	TRUSS NAME T20	QUANTITY 1	PLY 2	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:21 2023 Page 1

ID:UaoF4umx8QMX1bo7Q0Zq7Cya5EO-U74E8BGDxePHG HuOX8rNqXkzorZ5RxyP7iKYXyJHcy



TOTAL WEIGHT = 2 X 210 = 419 lb

LUMBER	SIZE	DESCR.
N. L. G. A. RULES		
CHORDS		
A - C	2x6 DRY No.2	SPF
C - F	2x6 DRY No.2	SPF
F - H	2x6 DRY No.2	SPF
H - J	2x6 DRY No.2	SPF
S - B	2x6 DRY No.2	SPF
K - I	2x6 DRY No.2	SPF
S - P	2x6 DRY No.2	SPF
P - N	2x6 DRY No.2	SPF
N - K	2x6 DRY No.2	SPF
ALL WEBS EXCEPT	2x4 DRY No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	2 12	SIDE(122.0)
C - F	2 12	SIDE(183.1)
F - H	2 12	TOP
H - J	2 12	TOP
S - B	2 12	TOP
K - I	2 12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
S - P	2 12	SIDE(183.1)
P - N	2 12	SIDE(183.1)
N - K	2 12	TOP
WEBS : (0.122"x3") SPIRAL NAILS		
2x4 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT HORZ	DOWN HORZ	UPLIFT IN-SX	IN-SX
S	5627 0	5627 0	0 0	3-10
K	4405 0	4405 0	0 0	2-6

UNFACTORED REACTIONS

1ST LOASE	MAX./MIN. COMPONENT REACTIONS
JT	COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL
S	3906 2982 / 0 0 / 0 0 / 0 923 / 0 0 / 0
K	3059 2321 / 0 0 / 0 0 / 0 738 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.16 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED MEMB. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	WEBS	MAX. FACTORED MEMB. FORCE (LBS)	MAX. FACTORED VERT. LOAD (PLF)
FR-TO						FR-TO		
A-B	0 / 60	-129.7 -129.7	0.05 (1)	10.00		R-C	-243 / 109	0.05 (1)
B-C	-6371 / 0	-129.7 -129.7	0.30 (1)	4.46		C-Q	0 / 3301	0.29 (1)
C-T	-7006 / 0	-129.7 -129.7	0.20 (1)	4.39		Q-D	-1793 / 0	0.40 (1)
T-U	-7006 / 0	-129.7 -129.7	0.20 (1)	4.39		D-O	0 / 1363	0.12 (1)
U-D	-7006 / 0	-129.7 -129.7	0.20 (1)	4.39		O-E	-597 / 0	0.13 (1)
D-V	-7870 / 0	-129.7 -129.7	0.22 (1)	4.16		E-G	0 / 2591	0.23 (1)
V-W	-7870 / 0	-129.7 -129.7	0.22 (1)	4.16		G-M	-2709 / 0	0.60 (1)
W-E	-7870 / 0	-129.7 -129.7	0.22 (1)	4.16		M-H	0 / 3946	0.35 (1)
E-F	-7870 / 0	-129.7 -129.7	0.21 (1)	4.17		H-R	-609 / 0	0.14 (1)
F-G	-7870 / 0	-129.7 -129.7	0.21 (1)	4.17		R-L	0 / 4963	0.44 (1)
G-H	-6229 / 0	-129.7 -129.7	0.18 (1)	4.63		L-I	0 / 3758	0.33 (1)
H-I	-4824 / 0	-129.7 -129.7	0.26 (1)	5.03				
I-J	0 / 60	-129.7 -129.7	0.05 (1)	10.00				
S-B	-5565 / 0	0.0 0.0	0.20 (1)	6.23				
K-I	-4352 / 0	0.0 0.0	0.16 (1)	6.87				

S-X	0 / 0	-18.5 -18.5	0.08 (4)	10.00
X-Y	0 / 0	-18.5 -18.5	0.08 (4)	10.00
Y-R	0 / 0	-18.5 -18.5	0.08 (4)	10.00
R-Z	0 / 4874	-18.5 -18.5	0.42 (1)	10.00
Z-AA	0 / 4874	-18.5 -18.5	0.42 (1)	10.00
AA-Q	0 / 4874	-18.5 -18.5	0.42 (1)	10.00
Q-P	0 / 7007	-18.5 -18.5	0.62 (1)	10.00
P-AB	0 / 7007	-18.5 -18.5	0.62 (1)	10.00
AB-O	0 / 7007	-18.5 -18.5	0.62 (1)	10.00
O-AC	0 / 6230	-18.5 -18.5	0.64 (1)	10.00
AC-N	0 / 6230	-18.5 -18.5	0.64 (1)	10.00
N-M	0 / 6230	-18.5 -18.5	0.64 (1)	10.00
M-L	0 / 3681	-18.5 -18.5	0.30 (1)	10.00
L-K	0 / 0	-18.5 -18.5	0.04 (4)	10.00

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LOC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-26	-26	---	FRONT	VERT	DEAD	---	C1
C	5-10-8	-404	-404	---	BACK	VERT	TOTAL	---	C1
C	5-10-8	-321	-321	---	FRONT	VERT	SNOW	---	C1
E	15-11-4	-10	-10	---	BACK	VERT	TOTAL	---	C1
O	15-11-4	-193	-193	---	BACK	VERT	TOTAL	---	C1
P	11-11-4	-193	-193	---	BACK	VERT	TOTAL	---	C1
R	5-11-4	-193	-193	---	BACK	VERT	TOTAL	---	C1
T	7-11-4	-10	-10	---	BACK	VERT	TOTAL	---	C1
U	9-11-4	-10	-10	---	BACK	VERT	TOTAL	---	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

*** NON STANDARD GIRDER ***

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.06")
CALCULATED VERT. DEFL.(LL) = L/999 (0.13")
ALLOWABLE DEFL.(TL) = L/360 (1.06")
CALCULATED VERT. DEFL.(TL) = L/999 (0.22")

CSI: TC=0.30/1.00 (B-C:1), BC=0.64/1.00 (M-O:1), WB=0.60/1.00 (G-M:1), SS=0.62/1.00 (M-O:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (Q) (INPUT = 0.90)
JSI METAL= 0.62 (P) (INPUT = 1.00)

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23111110



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T20	1	2	BAYVIEW WELLINGTON TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:22 2023 Page 2
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-yBedMXGryX8u7s4yEf4w13vjCBoqun5dfOu4zyJHcx

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWW-t	MT20	5.0	8.0	2.50	3.25
C	TTWW+m	MT20	6.0	10.0	4.00	1.25
D	TMWW+t	MT20	4.0	6.0		
E	TMWW+w	MT20	4.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMWW+t	MT20	4.0	6.0		
H	TTWW+m	MT20	6.0	10.0	4.00	1.25
I	TMWW-t	MT20	5.0	8.0	2.50	3.25
K	BMV1+p	MT20	4.0	6.0		
L	BMWW-t	MT20	5.0	6.0	2.50	2.25
M	BMWW-t	MT20	5.0	6.0		
N	BS-t	MT20	5.0	6.0		
O	BMWWWW-t	MT20	6.0	10.0		
P	BS-t	MT20	5.0	6.0		
Q	BMWW-t	MT20	5.0	6.0		
R	BMWW-t	MT20	5.0	6.0	2.50	2.25
S	BMV1+p	MT20	4.0	6.0		

SPECIFIED CONCENTRATED LOADS (LBS)


JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
V	11-11-4	-10	-10	—	BACK	VERT	TOTAL	—	C1
W	13-11-4	-10	-10	—	BACK	VERT	TOTAL	—	C1
X	1-11-4	-29	-29	—	BACK	VERT	TOTAL	—	C1
Y	3-11-4	-29	-29	—	BACK	VERT	TOTAL	—	C1
Z	7-11-4	-193	-193	—	BACK	VERT	TOTAL	—	C1
AA	9-11-4	-193	-193	—	BACK	VERT	TOTAL	—	C1
AB	13-11-4	-193	-193	—	BACK	VERT	TOTAL	—	C1
AC	16-6-8	-1398	-1398	—	BACK	VERT	TOTAL	—	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

NOTES-

- 1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111110

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T21	1	1	BAYVIEW WELLINGTON TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MITek Industries, Inc. Tue Nov 14 12:09:23 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-ROC7ZiHTTGg WHRHWxJSFc rcbEZF1Esl8RcPyJHcw



TOTAL WEIGHT = 157 lb

LUMBER

N. L. G. A. RULES	
CHORDS	SIZE

A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
H - K	2x4	DRY	No.2	SPF
T - B	2x6	DRY	No.2	SPF
L - J	2x6	DRY	No.2	SPF
T - P	2x4	DRY	No.2	SPF
P - L	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY
EXCEPT
DRY: SEASONED LUMBER.

PLATES (table is in inches)

J	T	PLATES	W	L	Y	X
B	TMWV-p	MT20	5.0	8.0	Edge	
C, E, I						
C	TMWV-t	MT20	4.0	6.0		
D	TTWV+m	MT20	6.0	7.0	2.00	2.25
F	TS-t	MT20	3.0	8.0		
G	TMWV+w	MT20	2.0	4.0		
H	TTWV+m	MT20	6.0	7.0	2.00	2.25
J	TMWV-p	MT20	5.0	8.0	Edge	
L	BMV1+p	MT20	4.0	6.0		
M	BMWV-t	MT20	4.0	6.0	2.00	2.50
N	BMWV-t	MT20	4.0	6.0		
O	BMWVWV-t	MT20	5.0	6.0	2.50	1.50
P	BS-t	MT20	3.0	8.0		
Q	BMWVW+t	MT20	4.0	6.0		
R	BMWV-t	MT20	4.0	6.0		
S	BMWV-t	MT20	4.0	6.0	2.00	2.50
T	BMV1+p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
T	2545	0	2545	0	0	5-8	2-12
L	2545	0	2545	0	0	5-8	2-12

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
T	1771	1326 / 0	0 / 0	0 / 0	0 / 0	444 / 0	0 / 0
L	1771	1326 / 0	0 / 0	0 / 0	0 / 0	444 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.69 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-O.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED				
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	LC1 (C/L)	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX. FACTORED	MAX. CSI (C/L)
FR-TO		FROM TO			LENGTH	FR-TO			
A-B	0/58	-129.7	-129.7	0.18 (1)	10.00	R-D	0/160	0.04 (4)	
B-C	-2358/0	-129.7	-129.7	0.44 (1)	4.03	D-Q	0/1038	0.23 (1)	
C-D	-2365/0	-129.7	-129.7	0.44 (1)	4.02	Q-E	-753/0	0.99 (1)	
D-E	-2370/0	-129.7	-129.7	0.66 (1)	3.69	E-O	-4/0	0.00 (1)	
E-F	-2368/0	-129.7	-129.7	0.66 (1)	3.69	O-G	-752/0	0.99 (1)	
F-G	-2368/0	-129.7	-129.7	0.66 (1)	3.69	O-H	0/1032	0.23 (1)	
G-H	-2368/0	-129.7	-129.7	0.65 (1)	3.71	N-H	0/162	0.04 (4)	
H-I	-2365/0	-129.7	-129.7	0.44 (1)	4.02	N-I	-88/0	0.06 (1)	
I-J	-2356/0	-129.7	-129.7	0.44 (1)	4.03	M-I	-525/0	0.19 (1)	
J-K	0/58	-129.7	-129.7	0.18 (1)	10.00	M-J	0/1932	0.43 (1)	
T-B	-2510/0	0.0	0.0	0.17 (1)	6.53	C-R	-89/0	0.06 (1)	
L-J	-2510/0	0.0	0.0	0.17 (1)	6.54	S-C	-524/0	0.19 (1)	
						B-S	0/1932	0.43 (1)	
T-S	0/0	-18.5	-18.5	0.06 (4)	10.00				
S-R	0/1839	-18.5	-18.5	0.35 (1)	10.00				
R-Q	0/1784	-18.5	-18.5	0.34 (1)	10.00				
Q-P	0/2371	-18.5	-18.5	0.44 (1)	10.00				
P-O	0/2371	-18.5	-18.5	0.44 (1)	10.00				
O-N	0/1784	-18.5	-18.5	0.34 (1)	10.00				
N-M	0/1839	-18.5	-18.5	0.35 (1)	10.00				
M-L	0/0	-18.5	-18.5	0.06 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	38.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.06")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.11")
ALLOWABLE DEFL.(TL)= L/360 (1.06")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.18")

CSI: TC=0.66/1.00 (D-E:1), BC=0.44/1.00 (O-Q:1),
WB=0.99/1.00 (E-Q:1), SSI=0.33/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (S) (INPUT = 0.90)
JSI METAL= 0.74 (P) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111111



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T22	4	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:24 2023 Page 1
ID:UaoF4umx8QMx1bo7Q0Zg7Cya5EO-valNnDISEZor7R0T3fhY?S99EOyalonO5yt 9syJHcv



TOTAL WEIGHT = 4 X 164 = 657 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - I	2x4	DRY	No.2	SPF	
R - B	2x6	DRY	No.2	SPF	
J - H	2x6	DRY	No.2	SPF	
R - O	2x4	DRY	No.2	SPF	
O - M	2x4	DRY	No.2	SPF	
M - J	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
D - N	2x4	DRY	No.2	SPF	
N - F	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	3.0	Edge	
C	TMVW-t	MT20	4.0	6.0		
D	TTVW-m	MT20	5.0	6.0	2.00	2.25
E	TMVW-w	MT20	2.0	4.0		
F	TTVW-m	MT20	5.0	6.0	2.00	2.25
G	TMVW-t	MT20	4.0	6.0		
H	TMVW-p	MT20	5.0	3.0	Edge	
J	BMV1+p	MT20	4.0	6.0		
K	BMVW-t	MT20	5.0	6.0	2.50	2.50
L	BMVW-t	MT20	4.0	6.0		
M	BS-t	MT20	3.0	3.0		
N	BMVWW-t	MT20	4.0	10.0		
O	BS-t	MT20	3.0	3.0		
P	BMVW-t	MT20	4.0	6.0		
Q	BMVW-t	MT20	5.0	6.0	2.50	2.50
R	BMV1+p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
R	2545	0	2545	0	5-8	2-12		
J	2545	0	2545	0	0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT J. MINIMUM BEARING LENGTH AT JOINT J = 2-12.

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM.	LIVE			
R	1771	1326 / 0	0 / 0	0 / 0	0 / 0	444 / 0	0 / 0
J	1771	1326 / 0	0 / 0	0 / 0	0 / 0	444 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.85 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		MAX.		WEBS		MAX.	
	MAX.	FACTORED	VERT.	LOAD	LC1	MAX	MAX.	MEMB.	FORCE	MAX
		(LBS)	(PLF)	CSI (LC)	UNBRAC	LENGTH	FR-TO			CSI (LC)
FR-TO										
A-B	0 / 58		-129.7	-129.7	0.18 (1)	10.00	Q-C	-396 / 0	0.21 (1)	
B-C	-2422 / 0		-129.7	-129.7	0.52 (1)	3.91	C-P	-312 / 0	0.34 (1)	
C-D	-2255 / 0		-129.7	-129.7	0.49 (1)	4.06	P-D	0 / 335	0.08 (1)	
D-E	-2037 / 0		-129.7	-129.7	0.68 (1)	3.85	D-N	0 / 640	0.10 (1)	
E-F	-2037 / 0		-129.7	-129.7	0.68 (1)	3.85	N-E	-966 / 0	0.64 (1)	
F-G	-2255 / 0		-129.7	-129.7	0.49 (1)	4.06	N-F	0 / 640	0.10 (1)	
G-H	-2422 / 0		-129.7	-129.7	0.52 (1)	3.91	L-F	0 / 335	0.08 (1)	
H-I	0 / 58		-129.7	-129.7	0.18 (1)	10.00	L-G	-312 / 0	0.34 (1)	
R-B	-2504 / 0		0.0	0.0	0.17 (1)	6.55	K-G	-396 / 0	0.21 (1)	
J-H	-2504 / 0		0.0	0.0	0.17 (1)	6.55	B-Q	0 / 1960	0.44 (1)	
							K-H	0 / 1960	0.44 (1)	
R-Q	0 / 0		-18.5	-18.5	0.10 (4)	10.00				
Q-P	0 / 1898		-18.5	-18.5	0.36 (1)	10.00				
P-O	0 / 1693		-18.5	-18.5	0.35 (1)	10.00				
O-N	0 / 1693		-18.5	-18.5	0.35 (1)	10.00				
N-M	0 / 1693		-18.5	-18.5	0.35 (1)	10.00				
M-L	0 / 1693		-18.5	-18.5	0.35 (1)	10.00				
L-K	0 / 1898		-18.5	-18.5	0.36 (1)	10.00				
K-J	0 / 0		-18.5	-18.5	0.10 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 38.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 51.6	PSF	

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC 2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.06")
CALCULATED VERT. DEFL.(LL)= L/999 (0.09")
ALLOWABLE DEFL.(TL)= L/360 (1.06")
CALCULATED VERT. DEFL.(TL)= L/999 (0.16")

CSI: TC=0.68/1.00 (D-E:1), BC=0.36/1.00 (P-Q:1),
WB=0.64/1.00 (E-N:1), SSI=0.38/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (O) (INPUT = 0.90)
JSI METAL= 0.54 (O) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111112

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T23	1	1	BAYVIEW WELLINGTON TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:26 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-rzt7CuJLmB2ZNIAsB4k04tEcbpfrmjahYGM5DkyJHct



Scale = 1:41.7

TOTAL WEIGHT = 80 lb

LUMBER				
N. L. G. A. RULES				
CHORDS		SIZE	LUMBER	DESCR
A - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
E - H	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF
L - I	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF


DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	4.0	6.0		
D	TTW+h	MT20	3.0	4.0	2.00	1.25
E	TTWW+m	MT20	5.0	8.0	2.25	1.50
F	TMWW-t	MT20	4.0	6.0		
G	TMV+p	MT20	3.0	4.0		
I	BMVV1-t	MT20	4.0	6.0		
J	BMWW-t	MT20	4.0	6.0		
K	BMWWW-t	MT20	4.0	6.0		
L	BMVV1-t	MT20	4.0	6.0		

NOTES

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111113

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
L	1310	0	1310	0	0	5-8	1-8
I	1310	0	1310	0	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 1-8.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	910	689/0	0/0	0/0	0/0	221/0	0/0
I	910	689/0	0/0	0/0	0/0	221/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO	FR-TO			
A-B	0/58	-129.7	-129.7	0.18 (1)	10.00	C-K	-205 / 0
B-C	0/33	-129.7	-129.7	0.25 (1)	10.00	K-D	0/244
C-D	-834 / 0	-129.7	-129.7	0.19 (1)	6.25	K-E	0/8
D-E	-617 / 0	-129.7	-129.7	0.04 (1)	6.25	J-E	0/235
E-F	-832 / 0	-129.7	-129.7	0.19 (1)	6.25	J-F	-205 / 0
F-G	0/33	-129.7	-129.7	0.25 (1)	10.00	L-C	-1176 / 0
G-H	0/58	-129.7	-129.7	0.18 (1)	10.00	F-I	-1174 / 0
L-B	-349 / 0	0.0	0.0	0.04 (1)	7.81		0.55 (1)
I-G	-349 / 0	0.0	0.0	0.04 (1)	7.81		0.55 (1)
L-K	0/747	-18.5	-18.5	0.25 (4)	10.00		
K-J	0/616	-18.5	-18.5	0.25 (4)	10.00		
J-I	0/746	-18.5	-18.5	0.24 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	38.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.51")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.51")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.08")

CSI: TC=0.25/1.00 (F-G:1), BC=0.25/1.00 (K-L:4),
WB=0.55/1.00 (C-L:1), SSI=0.16/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.74 (C) (INPUT = 0.90)
JSI METAL= 0.26 (C) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T24	1	1	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:27 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-J9RWPEKzXUAQ vi2lnFFd5nmPDzUV80qnw6fiByJHcs



TOTAL WEIGHT = 71 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.	SPF
N. L. G. A. RULES	A - D	2x4	DRY	No.2	SPF
	D - G	2x4	DRY	No.2	SPF
	J - B	2x4	DRY	No.2	SPF
	H - F	2x4	DRY	No.2	SPF
	J - H	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	4.0	6.0		
D	TTW+p	MT20	4.0	6.0	Edge	
E	TMWW-t	MT20	4.0	6.0		
F	TMV+p	MT20	3.0	4.0		
H	BMVW-t	MT20	4.0	6.0		
I	BMWW-t	MT20	4.0	6.0		
J	BMVW-t	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	DOWN	HORZ	UPLIFT
J 1310	0	1310	0
H 1310	0	1310	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 1-8.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	910	689 / 0	0 / 0	0 / 0	0 / 0	221 / 0	0 / 0
H	910	689 / 0	0 / 0	0 / 0	0 / 0	221 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC2)	MAX. FACTORED VERT. LOAD (LC3)	MAX. FACTORED VERT. LOAD (LC4)	MAX. FACTORED VERT. LOAD (LC5)	MAX. FACTORED VERT. LOAD (LC6)	MAX. FACTORED VERT. LOAD (LC7)	MAX. FACTORED VERT. LOAD (LC8)	MAX. FACTORED VERT. LOAD (LC9)	MAX. FACTORED VERT. LOAD (LC10)
FR-TO													
A-B	0 / 58	-129.7	-129.7	0.18 (1)	10.00	I-D	0 / 581	0.13 (1)					
B-C	0 / 37	-129.7	-129.7	0.30 (1)	10.00	I-E	-269 / 0	0.16 (1)					
C-D	-790 / 0	-129.7	-129.7	0.24 (1)	6.25	C-I	-269 / 0	0.16 (1)					
D-E	-790 / 0	-129.7	-129.7	0.24 (1)	6.25	J-C	-1165 / 0	0.67 (1)					
E-F	0 / 37	-129.7	-129.7	0.30 (1)	10.00	E-H	-1165 / 0	0.67 (1)					
F-G	0 / 58	-129.7	-129.7	0.18 (1)	10.00								
J-B	-367 / 0	0.0	0.0	0.04 (1)	7.81								
H-F	-367 / 0	0.0	0.0	0.04 (1)	7.81								
J-I	0 / 754	-18.5	-18.5	0.35 (4)	10.00								
I-H	0 / 754	-18.5	-18.5	0.35 (4)	10.00								

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.51")
CALCULATED VERT. DEFL.(LL)= L/999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.51")
CALCULATED VERT. DEFL.(TL)= L/999 (0.09")

CSI: TC=0.30/1.00 (B-C:1), BC=0.35/1.00 (H-I:4), WB=0.67/1.00 (C-J:1), SSI=0.18/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.71 (E) (INPUT = 0.90)
JSI METAL= 0.26 (C) (INPUT = 1.00)

NOTES-

- 1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111114



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418651	T25	1	2	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:29 2023 Page 1
ID:UaoF4umx8QMx1bo7Q0Zg7Cya5EO-FYZGqwME36Q8ECvQsCHjIWsyM1IWz8X7EEblq3yJHcc



TOTAL WEIGHT = 2 X 85 = 170 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x6 DRY	No.2	SPF		
C - E	2x6 DRY	No.2	SPF		
H - B	2x6 DRY	No.2	SPF		
F - D	2x6 DRY	No.2	SPF		
H - F	2x6 DRY	No.2	SPF		
ALL WEBS	2x4 DRY	No.2	SPF		

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C 2	12	SIDE(82.6)
C - E 2	12	SIDE(56.1)
H - B 2	12	TOP
F - D 2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
H - F 2	12	SIDE(11.7)
WEBS : (0.122"x3") SPIRAL NAILS		
G - C 1	6	SIDE(346.4)
2x4 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED		MAXIMUM FACTORED			INPUT	REQD
	GROSS REACTION		GROSS REACTION			BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
H	4878	0	4878	0	0	5-8	2-10
F	4878	0	4878	0	0	5-7	2-10

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS
JT	COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL
H	3373 2646 / 0 0 / 0 0 / 0 727 / 0 0 / 0
F	3373 2646 / 0 0 / 0 0 / 0 727 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.82 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED			
MEMB.	FORCE	VERT. LOAD	MAX	MAX.	MEMB.	FORCE	MAX
	(LBS)	(PLF)	CSI (LC)	UNBRAC		(LBS)	CSI (LC)
FR-TO		FROM TO		LENGTH	FR-TO		
A-B	0 / 60	-129.7 -129.7	0.05 (1)	10.00	G-C	-619 / 318	0.16 (1)
B-C	-4094 / 0	-421.6 -421.6	0.92 (1)	3.82	B-G	0 / 3191	0.28 (1)
C-D	-4094 / 0	-421.6 -421.6	0.92 (1)	3.82	G-D	0 / 3191	0.28 (1)
D-E	0 / 60	-129.7 -129.7	0.05 (1)	10.00			
H-B	-4716 / 0	0.0 0.0	0.17 (1)	6.66			
F-D	-4716 / 0	0.0 0.0	0.17 (1)	6.66			
H-G	0 / 0	-60.1 -60.1	0.19 (4)	10.00			
G-F	0 / 0	-60.1 -60.1	0.19 (4)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	6-6-0	-144	-144	--	FRONT	VERT	DEAD	--	C1
C	6-6-0	-144	-144	--	BACK	VERT	DEAD	--	C1
C	6-6-0	-920	-920	--	FRONT	VERT	SNOW	--	C1
C	6-6-0	-920	-920	--	BACK	VERT	SNOW	--	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL = 38.3 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 51.6 PSF

SPACING = 24.0 IN. C/C

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 0-0
END SETBACK = 6-6-0
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 0-0
END SETBACK = 6-6-0
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO BACK SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.43")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.43")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.92/1.00 (C-D:1), BC=0.19/1.00 (G-H:4), WB=0.28/1.00 (B-G:1), SS=0.35/1.00 (C-D:1)


DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23111115



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T25	1	2	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:29 2023 Page 2

ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-FYZGqWME36Q8ECvQsCHjiWsyM1iWz8X7EEblq3yJHcg

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	8.0	2.50	3.25
C	TTW+p	MT20	5.0	6.0	3.75	2.50
D	TMVW-t	MT20	5.0	8.0	2.50	3.25
F	BMV1+p	MT20	4.0	6.0		
G	BMWWW-t	MT20	6.0	10.0		
H	BMV1+p	MT20	4.0	6.0		

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.60 (D) (INPUT = 0.90)

JSI METAL= 0.45 (D) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111115



JOB NAME 418651	TRUSS NAME T26	QUANTITY 1	PLY 2	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:30 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-ik7e1GNspPY?rMTdQvovFIPEXQzTIY6GTuKJMVyJHcp



TOTAL WEIGHT = 2 X 66 = 132 lb

LUMBER				N. L. G. A. RULES	
CHORDS	SIZE	LUMBER	DESCR.	SPF	SPF
A - C	2x4	DRY	No.2	SPF	SPF
C - E	2x6	DRY	No.2	SPF	SPF
F - E	2x6	DRY	No.2	SPF	SPF
J - A	2x6	DRY	No.2	SPF	SPF

ALL WEBS 2x4 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C 1 12	TOP	
C-E 2 12	TOP	
E-F 2 12	TOP	
J-A 2 12	TOP	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
J-F 2 12	SIDE (0.0)	
WEBS : (0.122"x3") SPIRAL NAILS		
2x4 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	5.0	6.0	2.00 2.25

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQRD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	5410	5410	0	0
F	VERT	5955	5955	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 3-5.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS
JT COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
JT	3761 2835 / 0 0 / 0 0 / 0 927 / 0 0 / 0
J	4140 3121 / 0 0 / 0 0 / 0 1019 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.49 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	-4354 / 0	H-C	0 / 2082
B-C	-3804 / 0	H-D	0 / 1059
C-D	-3012 / 0	G-D	-1109 / 0
D-E	-2541 / 0	G-E	0 / 5125
F-E	-4694 / 0	I-B	-775 / 0
J-A	-4867 / 0	A-I	0 / 801
J-K	0 / 0		0 / 3865
K-L	0 / 0		
L-L	0 / 3342		
L-H	0 / 3342		
H-M	0 / 2541		
M-G	0 / 2541		
G-N	0 / 0		
N-F	0 / 0		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
K	1-0-4	-1756	-1756	FRONT	VERT	TOTAL	-	C1
L	3-0-4	-1756	-1756	FRONT	VERT	TOTAL	-	C1
M	5-0-4	-1756	-1756	FRONT	VERT	TOTAL	-	C1
N	7-0-4	-1756	-1756	FRONT	VERT	TOTAL	-	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 38.3	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.28")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.28")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.48/1.00 (E-F:1), BC=0.46/1.00 (H-I:1), WB=0.45/1.00 (E-G:1), SSI=0.62/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650 371 1747 788 1987 1873	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.76 (I) (INPUT = 0.90)

JSI METAL= 0.60 (I) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T26	1	2	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:30 2023 Page 2

ID:UaoF4umx8QMX1bc7Q0Zg7Cya5EO-jk7e1GNspPY?rMTdQvovFIPEXQzTIY6GTuKJMVyJHcp


PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWW-t	MT20	4.0	6.0	2.00	2.75
C	TTW+h	MT20	4.0	10.0	Edge	1.00
D	TMWW+t	MT20	4.0	6.0		
E	TMWW+p	MT20	6.0	7.0		
F	BMV1+p	MT20	4.0	6.0		
G	BMWW+t	MT20	4.0	10.0		
H	BMWWW-t	MT20	5.0	8.0	2.75	4.00
I	BMWW+t	MT20	5.0	8.0	4.25	2.50
J	BMV1+p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-

- 1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111116

JOB NAME 418649	TRUSS NAME T50	QUANTITY 1	PLY 2	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
---------------------------	--------------------------	----------------------	-----------------	--	----------

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MITek Industries, Inc. Tue Nov 14 11:15:04 2023 Page 1

ID:UaoF4umx8QMX1bo7Q0Zg7Cva5EO-MPnyaVrcz3P1Sow57C3t 7B4tM7TVcYSmBUkpyJlPr



Scale = 1:37.0

TOTAL WEIGHT = 2 X 36 = 73 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - A	2x6 DRY	No.2	SPF		
A - C	2x4 DRY	No.2	SPF		
D - C	2x4 DRY	No.2	SPF		
F - D	2x6 DRY	No.2	SPF		
ALL WEBS	2x3 DRY	No.2	SPF		
DRY: SEASONED LUMBER.					

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F-A 2 5		SIDE(148.3)
A-C 1 12		SIDE(61.0)
C-D 1 12		TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2 12		SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
A	TMWW+p	MT20	5.0	6.0	2.00	2.25
B	TMWW-t	MT20	4.0	6.0		
C	TMWW+p	MT20	3.0	4.0		
D	BMWW1+p	MT20	4.0	6.0		
E	BMWW-t	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	DOWN	UP	IN-SX
F	1999	0	1999	0
D	1200	0	1200	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	1388	1057	0	0	0	330	0
D	834	634	0	0	0	200	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX.	MEMB.	MAX. FACTORED	FORCE	MAX
MEMB.	FORCE	(LBS)	(PLF)	CSI (LC)	UNBRAC	LENGTH	FR-TO	(LBS)	CSI (LC)	(LBS)
FR-TO										
F-A	-1821	0	0.0	0.0	0.07	(1)	7.81	A-E	0/756	0.09
A-B	-881	0	-129.7	-129.7	0.10	(1)	6.25	E-B	0/985	0.12
B-C	-28	0	-129.7	-129.7	0.10	(1)	6.25	B-D	-1117	0.20
D-C	-147	0	0.0	0.0	0.06	(1)	7.81			
F-G	0/0	-18.5	-18.5	0.12	(1)	10.00				
G-E	0/0	-18.5	-18.5	0.12	(1)	10.00				
E-H	0/698	-18.5	-18.5	0.16	(1)	10.00				
H-D	0/698	-18.5	-18.5	0.16	(1)	10.00				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
A	0-0	-557	-557	—	FRONT	VERT	TOTAL	—	C1
G	2-0-12	-590	-590	—	FRONT	VERT	TOTAL	—	C1
H	4-0-12	-467	-467	—	FRONT	VERT	TOTAL	—	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.10/1.00 (A-B:1), BC=0.16/1.00 (D-E:1), WB=0.20/1.00 (B-D:1), SSI=0.24/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)		
MAX MIN	MAX MIN	MAX MIN		
MT20	650	371	1747	788
			1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.45 (B) (INPUT = 0.90)
JSI METAL= 0.20 (A) (INPUT = 1.00)



STRUCTURAL COMPONENT ONLY
DWG # TR23111094

CONTINUED ON PAGE 2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T50	1	2	BAYVIEW WELLINGTON	
				TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:15:04 2023 Page 2


ID:UaoF4umx8QMX1bo7QOZg7Cva5EO-MPnyeVrCzx3P1Sow57C3t 7B4tM7TVcYSmBUkpyJlP

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
F	BMV1+p	MT20	4.0	6.0		

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111094



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418649	T50Z	1	2	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:15:05 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-qbKLnrskEBGebN6fjllQCgMqHfVcx6hhQw2GFyJIPq



Scale = 1:37.0

TOTAL WEIGHT = 2 X 36 = 73 lb [M]

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
F - A	2x6	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - D	2x6	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F-A	2	12 TOP
A-C	1	12 TOP
C-D	1	12 TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D	2	12 SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
B-E	1	6 SIDE(179.5)
2x3	1	6

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	5.0	6.0	2.00	2.25
B	TMVW-t	MT20	4.0	6.0		
C	TMV+p	MT20	3.0	4.0		
D	BMVW1+p	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	GROSS REACTION	VERT	HORZ	GROSS REACTION	DOWN	HORZ	UPLIFT	BRG	BRG
F	1935	0	0	1935	0	0	5-8	1-8	
D	2190	0	0	2190	0	0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	1345	1015 / 0	0 / 0	0 / 0	0 / 0	330 / 0	0 / 0
D	1520	1158 / 0	0 / 0	0 / 0	0 / 0	383 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
F-A	-1521 / 0	0.0	0.0 0.06 (1)	A-E	0 / 1190	0.15 (1)	
A-B	-1403 / 0	-129.7	-129.7 0.10 (1)	E-B	0 / 1824	0.23 (1)	
B-C	-27 / 0	-129.7	-129.7 0.09 (1)	B-D	-1758 / 0	0.31 (1)	
D-C	-149 / 0	0.0	0.0 0.06 (1)				
F-G	0 / 0	-18.5	-18.5 0.16 (1)				
G-H	0 / 0	-18.5	-18.5 0.16 (1)				
H-E	0 / 0	-18.5	-18.5 0.16 (1)				
E-I	0 / 1098	-18.5	-18.5 0.38 (1)				
I-D	0 / 1098	-18.5	-18.5 0.38 (1)				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	7-4	-330	-330		BACK	VERT	TOTAL		C1
H	2-7-4	-964	-964		BACK	VERT	TOTAL		C1
I	4-7-4	-964	-964		BACK	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	51.6	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.10/1.00 (A-B:1), BC=0.38/1.00 (D-E:1),
WB=0.31/1.00 (B-D:1), SSI=0.50/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.84 (B) (INPUT = 0.90)
JSI METAL= 0.26 (E) (INPUT = 1.00)



STRUCTURAL COMPONENT ONLY
DWG # TR23111095

CONTINUED ON PAGE 2



JOB NAME 418649	TRUSS NAME T50Z	QUANTITY 1	PLY 2	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
--------------------	--------------------	---------------	----------	---------------------------------	----------


Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:15:05 2023 Page 2
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-qbKLnrskEBGebN6fijlQCgMgHfvCx6hhQw2GFyJIPq

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
E	BMWW+t	MT20	4.0	6.0	3.25	2.00
F	BMV1+p	MT20	4.0	6.0		

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111095



JOB NAME 418649	TRUSS NAME T51	QUANTITY 1	PLY 2	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 Mitek Industries, Inc. Tue Nov 14 11:15:06 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-louj7BtTVYJ7GlyJDQFXYpDWWh2dxQRnw4gbohyJlPp



TOTAL WEIGHT = 2 X 32 = 63 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - B	2x4 DRY No.2	SPF			
B - C	2x4 DRY No.2	SPF			
D - C	2x4 DRY No.2	SPF			
F - A	2x6 DRY No.2	SPF			
F - D	2x6 DRY No.2	SPF			

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-B 1	12	SIDE(61.0)
B-C 1	12	SIDE(61.0)
C-D 1	12	TOP
F-A 2	5	SIDE(148.3)
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
E-B 1	6	SIDE(40.9)
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	UPLIFT	IN-SX
D	1466	0	1466	0
F	2357	0	2357	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
D	1015	791/0	0/0	0/0	0/0	224/0	0/0
F	1632	1269/0	0/0	0/0	0/0	364/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD LC1 (LC)	MAX. FACTORED VERT. LOAD LC1 (LC)	MAX. FACTORED VERT. LOAD LC1 (LC)	MAX. FACTORED VERT. LOAD LC1 (LC)	MAX. FACTORED VERT. LOAD LC1 (LC)	MAX. FACTORED VERT. LOAD LC1 (LC)
FR-TO								
A-B	-1290/0	-129.7	-129.7	0.08 (1)	6.25	E-B	-181/38	0.02 (1)
B-C	-981/0	-129.7	-129.7	0.14 (1)	6.25	E-C	0/1404	0.17 (1)
D-C	-1217/0	0.0	0.0	0.13 (1)	7.81	A-E	0/1090	0.13 (1)
F-A	-2258/0	0.0	0.0	0.08 (1)	7.81			
F-G	0/0	-18.5	-18.5	0.10 (1)	10.00			
G-E	0/0	-18.5	-18.5	0.10 (1)	10.00			
E-H	0/0	-18.5	-18.5	0.16 (1)	10.00			
H-D	0/0	-18.5	-18.5	0.16 (1)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
A	0-0	-557	-557	---	FRONT	VERT	TOTAL	C1
B	2-6-0	-58	-58	---	FRONT	VERT	DEAD	C1
B	2-6-0	-368	-368	---	FRONT	VERT	SNOW	C1
G	2-0-12	-590	-590	---	BACK	VERT	TOTAL	C1
H	4-0-12	-467	-467	---	BACK	VERT	TOTAL	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL = 38.3	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

*** NON STANDARD GIRDER ***

ADD'L USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/999 (0.01")

CSI: TC=0.14/1.00 (B-C:1), BC=0.16/1.00 (D-E:1), WB=0.17/1.00 (C-E:1), SSI=0.27/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.77 (B) (INPUT = 0.90)
JSI METAL= 0.23 (A) (INPUT = 1.00)

CONTINUED ON PAGE 2





JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	T51	1	2	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:15:06 2023 Page 2

ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-Iouj7BtTVYJ7GlyJDQFxyPDWvh2dxQRrw4gbohYJlPp


PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	5.0	6.0	2.00	2.25
B	TTW+h	MT20	3.0	4.0	2.00	1.25
C	TMVW-t	MT20	4.0	6.0		
D	BMV1+p	MT20	4.0	6.0	3.00	Edge
E	BMWW-t	MT20	5.0	6.0		
F	BMV1+p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111096

JOB NAME 418651	TRUSS NAME T60	QUANTITY 1	PLY 2	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:31 2023 Page 1
ID:UaoF4umx8QMx1bo7Q0Zg7Cya5EO-Cwg0FcNUajgsTW2p dJBnxd.VqKUR3aQIY4suvyJHco



Scale = 1:35.6

LUMBER				
CHORDS	SIZE	LUMBER	DESCR.	SPF
A - C	2x4 DRY	No.2	SPF	
C - D	2x4 DRY	No.2	SPF	
E - D	2x4 DRY	No.2	SPF	
H - A	2x6 DRY	No.2	SPF	
H - E	2x6 DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3 DRY	No.2	SPF	

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C 1	8	SIDE(137.0)
C - D 1	6	SIDE(178.3)
D - E 1	12	TOP
H - A 2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
H - E 2	12	SIDE(28.5)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	5.0	6.0	2.00 2.25

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	VERT	GROSS REACTION	HORZ	GROSS REACTION	DOWN	BRG	IN-SX	BRG	IN-SX
E	2625	0	2625	0	0	5-8	1-8	1-8	1-8
H	2018	0	2018	0	0	5-8	1-8	1-8	1-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	1824	1378 / 0	0 / 0	0 / 0	0 / 0	0 / 0	446 / 0	0 / 0
H	1405	1049 / 0	0 / 0	0 / 0	0 / 0	0 / 0	356 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		W E B S		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	-1330 / 0	-486.4 -486.4	0.31 (1)	F-C	-388 / 0	0.11 (1)	
B-C	-560 / 0	-486.4 -486.4	0.30 (1)	F-D	0 / 1999	0.25 (1)	
C-D	-338 / 0	-486.4 -486.4	0.05 (1)	B-F	-1338 / 0	0.22 (1)	
E-D	-2227 / 0	0.0 0.0	0.75 (1)	G-B	0 / 211	0.04 (4)	
H-A	-1967 / 0	0.0 0.0	0.07 (1)	A-G	0 / 1205	0.15 (1)	
H-G	0 / 0	-69.4 -69.4	0.05 (1)				
G-I	0 / 1092	-69.4 -69.4	0.35 (1)				
I-F	0 / 1092	-69.4 -69.4	0.35 (1)				
F-E	0 / 0	-69.4 -69.4	0.13 (1)				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
I	4-9-12	-792	-792		FRONT	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 46 = 92 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	PSF
DL	38.3	PSF
BOT CH.	LL	PSF
DL	0.0	PSF
DL	7.4	PSF
TOTAL LOAD	51.6	PSF

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 0-0
END SETBACK = 13-0-0
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO BACK SIDE
- ADD'L LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.21")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.21")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.75/1.00 (D-E:1), BC=0.35/1.00 (F-G:1), WB=0.25/1.00 (D-F:1), SSI=0.27/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (F) (INPUT = 0.90)
JSI METAL= 0.27 (F) (INPUT = 1.00)

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23111117



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T60	1	2	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:31 2023 Page 2

ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-Cwg0FcNUajgsTW2p dJBnxxLVgKUR3aQiY4suyvJHco


PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWW-t	MT20	4.0	6.0		
C	TTW+h	MT20	3.0	4.0	2.00	1.25
D	TMVW-t	MT20	4.0	6.0		
E	BMV1+p	MT20	4.0	6.0	3.00	Edge
F	BMWWW-t	MT20	5.0	6.0	2.50	1.50
G	BMWW+t	MT20	4.0	6.0		
H	BMV1+p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES-


1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111117

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T61	1	2	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington					

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:32 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zq7Cya5EO-q6EPSyO6L1oj5gd?XKrQK8UqDEfYAVJZxCpPROyJHcn



Scale = 1:37.0

TOTAL WEIGHT = 2 X 36 = 72 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
D - C	2x4	DRY	No.2	SPF	
F - A	2x6	DRY	No.2	SPF	
F - D	2x6	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C 1	12	TOP
D-C 1	12	TOP
F-A 2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2	12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
E-B 1	6	SIDE(153.8)
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMWW+p	MT20	5.0	6.0	2.00	2.25
B	TMWW-l	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD IN-SX
JT	VERT	HORZ	DOWN	HORZ
D	2036	0	2036	0
F	1891	0	1891	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
D	1413	1078 / 0 0 / 0 0 / 0 335 / 0 0 / 0
F	1314	993 / 0 0 / 0 0 / 0 321 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	MAX. CS1 (LC)	UNBRAC LENGTH	FR-TO	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
A-B	-1462 / 0	-129.7	-129.7	0.11 (1)	6.25	E-B	0 / 1582	0.20 (1)			
B-C	-25 / 0	-129.7	-129.7	0.10 (1)	6.25	B-D	-1590 / 0	0.28 (1)			
D-C	-183 / 0	0.0	0.0	0.07 (1)	7.81	A-E	0 / 1284	0.16 (1)			
F-A	-1635 / 0	0.0	0.0	0.06 (1)	7.81						
F-G	0 / 0	-18.5	-18.5	0.11 (1)	10.00						
G-E	0 / 0	-18.5	-18.5	0.11 (1)	10.00						
E-H	0 / 1150	-18.5	-18.5	0.42 (1)	10.00						
H-D	0 / 1150	-18.5	-18.5	0.42 (1)	10.00						

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	2-7-4	-895	-895	---	BACK	VERT	TOTAL	---	C1
G	7-4	-330	-330	---	BACK	VERT	TOTAL	---	C1
H	4-7-4	-895	-895	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.11/1.00 (A-B:1), BC=0.42/1.00 (D-E:1).
WB=0.28/1.00 (B-D:1), SS=0.25/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.72 (B) (INPUT = 0.90)
JSI METAL= 0.26 (E) (INPUT = 1.00)



STRUCTURAL COMPONENT ONLY
DWG # TR23111118

CONTINUED ON PAGE 2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T61	1	2	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:32 2023 Page 2


ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-g6EPSyO6L1oj5gd?XKrQK8UgDEfYAVJZxCpPROyJHcn

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
C	TMV+p	MT20	3.0	4.0		
D	BMVW1+p	MT20	4.0	6.0		
E	BMVW+t	MT20	4.0	6.0	3.25	2.00
F	BMV1+p	MT20	4.0	6.0		

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111118



JOB NAME 418649	TRUSS NAME T90	QUANTITY 9	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:15:07 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-m S5CXI5GsR uvXVm7mmVdlh95QmqvG 8kP8K8yJlPo



Scale = 1:20.6

TOTAL WEIGHT = 9 X 18 = 180 lb [M]

LUMBER		N. L. G. A. RULES		LUMBER		DESCR.	
CHORDS	SIZE						
A - C	2x4	DRY	No.2	SPF			
D - C	2x4	DRY	No.2	SPF			
E - B	2x4	DRY	No.2	SPF			
E - D	2x4	DRY	No.2	SPF			
ALL WEBS	2x3	DRY	No.2	SPF			
DRY: SEASONED LUMBER.							

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	3.0	4.0	
C	TMVWW1-t	MT20	5.0	14.0	
D	BMV+p	MT20	3.0	4.0	
E	BMVW1-t	MT20	4.0	6.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQ'D	
		GROSS REACTION		GROSS REACTION		BRG		BRG	
JT		VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
E		390	0	390	0	0	3-8	1-8	
F		146	0	146	0	0	5-8	0-0	

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	269	214 / 0	0 / 0	0 / 0	0 / 0	55 / 0	0 / 0
F	102	75 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		FACTORED				WEBS			
		MAX. FACTORED		VERT. LOAD LC1		MAX. FACTORED		MAX. FACTORED	
MEMB.	FORCE (LBS)	FROM	TO	PLF	CSI (LC)	MEMB.	FORCE (LBS)	FROM	TO
FR-TO		LENGTH FR-TO							
A-B	0 / 49	-129.7	-129.7	0.17 (1)	10.00	E-C	-44 / 0	0.01 (1)	
B-C	0 / 0	-129.7	-129.7	0.13 (1)	10.00	C-F	-215 / 0	0.00 (1)	
D-G	0 / 25	0.0	0.0	0.09 (1)	10.00	G-F	0 / 157	0.00 (1)	
G-C	0 / 25	0.0	0.0	0.09 (1)	10.00				
E-B	-335 / 0	0.0	0.0	0.03 (1)	7.81				
E-D	0 / 29	-18.5	-18.5	0.03 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.8	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(65% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.17/1.00 (A-B:1), BC=0.03/1.00 (D-E:4), WB=0.01/1.00 (C-E:1), SSI=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (B) (INPUT = 0.90)
JSI METAL= 0.11 (B) (INPUT = 1.00)

NOTES-

- 1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111097


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	BAYVIEW WELLINGTON	DRWG NO.
418649	T91	10	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:15:08 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-EA0TPtuj19ZrV36hKqH71qIsqVlIPMb8NO9itayJlPn



Scale = 1:21.1



TOTAL WEIGHT = 10 X .17 = 165 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
E - B	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVWW1-t	MT20	5.0	14.0	2.50	4.50
D	BMV+p	MT20	3.0	4.0		
E	BMVW1-t	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

ESTIMATING BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	385	0	385	0	0	3-8	1-8
F	29	0	29	0	-44	5-8	0-0

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	285	216 / 0	0 / 0	0 / 0	0 / 0	49 / 0	0 / 0
F	21	11 / -35	0 / 0	0 / 0	0 / 0	10 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED				
MEMB.	FORCE	VERT. LOAD	LC1	MAX	MAX.	MEMB.	FORCE	MAX	
	(LBS)	(PLF)	CSI	(LC)	UNBRAC		(LBS)	CSI	(LC)
FR-TO		FROM TO			LENGTH	FR-TO			
A-B	0/58	-129.7	-129.7	0.18 (1)	10.00	E-C	-12/18	0.00 (5)	
B-C	-50/0	-129.7	-129.7	0.17 (1)	6.25	C-F	-39/60	0.00 (1)	
D-G	0/16	0.0	0.0	0.03 (5)	10.00	G-F	-40/26	0.00 (1)	
G-C	0/16	0.0	0.0	0.03 (5)	10.00				
E-B	-361/0	0.0	0.0	0.04 (1)	7.81				
E-D	-9/6	-18.5	-18.5	0.01 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	38.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	51.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.18/1.00 (A-B:1), BC=0.01/1.00 (D-E:4),
WB=0.00/1.00 (C-E:5), SSI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)	(PLI)	(PSI)	(PLI)	(PSI)	(PLI)
MT20	650	371	1747	788	1987	1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL= 0.13 (B) (INPUT = 1.00)

NOTES-


1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111098

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	G93	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:12 2023 Page 1
ID:BYtLwPIX250w AVAQK18lyZoeT-FG1rF69Z3tHYhb59M8UkWWfEAAvQUW6dK5zMKyYJHd5



Scale = 1:26.1

TOTAL WEIGHT = 30 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
B - F	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				
GABLE STUDS SPACED AT 2-0-0 OC.				

PLATES (table is in inches)					
JT TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0	1.50 2.00
C	TMW+w	MT20	2.0	4.0	
D	TTW+p	MT20	4.0	6.0	Edge
E	TMW+w	MT20	2.0	4.0	
F	TMB1-I	MT20	3.0	4.0	1.50 2.00
H, I, J					
H	BMW1+w	MT20	2.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 56	-129.7 -129.7	0.18 (1)	I-D	-192 / 0	0.04 (1)	
B-L	-304 / 0	-129.7 -129.7	0.17 (1)	J-C	-251 / 0	0.04 (1)	
L-C	-46 / 0	-129.7 -129.7	0.06 (1)	H-E	-251 / 0	0.04 (1)	
C-D	-42 / 0	-129.7 -129.7	0.07 (1)	K-L	0 / 232	0.00 (1)	
D-E	-42 / 0	-129.7 -129.7	0.07 (1)	M-N	0 / 232	0.00 (1)	
E-N	-46 / 0	-129.7 -129.7	0.06 (1)				
N-F	-304 / 0	-129.7 -129.7	0.17 (1)				
F-G	0 / 56	-129.7 -129.7	0.18 (1)				
B-K	0 / 36	-18.5 -18.5	0.07 (1)				
K-J	0 / 36	-18.5 -18.5	0.07 (1)				
J-I	0 / 21	-18.5 -18.5	0.02 (1)				
I-H	0 / 21	-18.5 -18.5	0.02 (1)				
H-M	0 / 36	-18.5 -18.5	0.07 (1)				
M-F	0 / 36	-18.5 -18.5	0.07 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 38.3 PSF
DL = 6.0 PSF

BOT CH. LL = 0.0 PSF
DL = 7.4 PSF

TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.18/1.00 (A-B:1), BC=0.07/1.00 (B-K:1), WB=0.04/1.00 (D-I:1), SSI=0.19/1.00 (B-L:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN
MT20	650	371	1747 788 1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.28 (B) (INPUT = 0.90)
JSI METAL= 0.13 (C) (INPUT = 1.00)

NOTES-


1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111103

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T93	2	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:34 2023 Page 1
ID:BYtLwPIX250w AVAQKI8lyZoeT-cVM9tdQMte2RKznOfIuPZZ A2NNeTPsOWIWHyJHc



TOTAL WEIGHT = 2 X 28 = 56 lb

LUMBER					DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER										DESIGN CRITERIA	
N. L. G. A. RULES		CHORDS	SIZE	LUMBER	DESCR.	BEARINGS										SPECIFIED LOADS: TOP CH. LL = 38.3 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 51.6 PSF
A - C	2x4	DRY	No.2	SPF	FACTORED											
C - E	2x4	DRY	No.2	SPF	GROSS REACTION											
B - D	2x4	DRY	No.2	SPF	MAXIMUM FACTORED											
ALL WEBS	2x3	DRY	No.2	SPF	INPUT											
DRY; SEASONED LUMBER.					JT	VERT	HORZ	GROSS REACTION	DOWN	HORZ	UPLIFT	BRG IN-SX	REQRD BRG IN-SX	HEEL WEDGE		
					B	760	0	760	0	3-8	1-8	2x4 L				
					D	760	0	760	0	3-8	1-8	2x4 R				

PLATES (table is in inches)	W	LEN	Y	X
JT TYPE	PLATES			
B	TMBH1-m	MT20	4.0	6.0
C	TTW+p	MT20	4.0	6.0
D	TMBH1-m	MT20	4.0	6.0
F	BMW+w	MT20	2.0	4.0

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	527	405 / 0	0 / 0	0 / 0	0 / 0	122 / 0	0 / 0
D	527	405 / 0	0 / 0	0 / 0	0 / 0	122 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.


LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 56	-129.7 -129.7	0.18 (1)	10.00	F-C	0 / 221	0.05 (1)
B-H	-435 / 0	-129.7 -129.7	0.07 (1)	6.25	G-H	-349 / 0	0.00 (1)
H-C	-501 / 0	-129.7 -129.7	0.21 (1)	6.25	I-J	-349 / 0	0.00 (1)
C-J	-501 / 0	-129.7 -129.7	0.21 (1)	6.25			
J-D	-435 / 0	-129.7 -129.7	0.07 (1)	6.25			
D-E	0 / 56	-129.7 -129.7	0.18 (1)	10.00			
B-G	0 / 376	-18.5 -18.5	0.27 (1)	10.00			
G-F	0 / 376	-18.5 -18.5	0.27 (1)	10.00			
F-I	0 / 376	-18.5 -18.5	0.27 (1)	10.00			
I-D	0 / 376	-18.5 -18.5	0.27 (1)	10.00			

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111119

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.26 (D) (INPUT = 0.90)
JSI METAL= 0.15 (D) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	T93A	2	1	BAYVIEW WELLINGTON	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:35 2023 Page 1
ID:BYtzLwPIX250w AVAQKIBlyZoeT-4hwX4zQ?eyAHy7MaDTOT7yn69mRfcNv30dA241jyJHck



Scale = 1:26.2

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
B - E	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMBH1-m	MT20	4.0	6.0		
C	TTW+p	MT20	4.0	6.0	Edge	
D	TMVW+p	MT20	4.0	6.0	Edge	
F	BMVW-l	MT20	5.0	14.0	2.50	4.25
G	BMVW-t	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG	HEEL WEDGE
JT	VERT. HORZ.	DOWN HORZ.	IN-SX	IN-SX	
B	748 0	748 0	3-8	1-8	2x4 L
E	472 0	472 0	5-8	1-8	

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	519	399 / 0	0 / 0	0 / 0	0 / 0	120 / 0	0 / 0
E	330	236 / 0	0 / 0	0 / 0	0 / 0	94 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 56	-129.7 -129.7	0.18 (1)	10.00	G-C	0 / 229	0.05 (1)
B-I	-419 / 0	-129.7 -129.7	0.10 (1)	6.25	G-D	0 / 388	0.09 (1)
I-C	-501 / 0	-129.7 -129.7	0.22 (1)	6.25	H-I	-371 / 0	0.00 (1)
C-D	-487 / 0	-129.7 -129.7	0.20 (1)	6.25			
F-D	-610 / 0	0.0 0.0	0.06 (1)	7.81			
B-H	0 / 374	-18.5 -18.5	0.28 (1)	10.00			
H-G	0 / 374	-18.5 -18.5	0.28 (1)	10.00			
G-F	0 / 0	-18.5 -18.5	0.53 (1)	10.00			
F-E	0 / 0	-18.5 -18.5	0.22 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 38.3 PSF
DL = 6.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD = 51.6 PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.26")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.26")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.08")

CSI: TC=0.22/1.00 (C-I:1), BC=0.53/1.00 (F-G:1), WB=0.09/1.00 (D-G:1), SSI=0.25/1.00 (B-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR	SECTION
(PSI)	(PLI) (PLI)
MAX MIN	MAX MIN MAX MIN
MT20	650 371 1747 788 1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.38 (D) (INPUT = 0.90)
JSI METAL= 0.25 (D) (INPUT = 1.00)

NOTES-

- 1) Lateral braces to be a minimum of 2X4 SPF #2.





STRUCTURAL COMPONENT ONLY
DWG # TR23111120



JOB NAME 418649	TRUSS NAME P1	QUANTITY 1	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:35 2023 Page 1

ID:UaoF4umx8QMx1bo7Q0Zg7Cya5EO-iqW?UbV0o1PW2 4LuPBGcIR3CBTZAPHHnfsD yJlQI



TOTAL WEIGHT = 49 lb

LUMBER	DESCR.
N. L. G. A. RULES	
CHORDS	
A - C	2x4 DRY No.2
C - E	2x4 DRY No.2
E - G	2x4 DRY No.2
B - F	2x4 DRY No.2
ALL WEBS	2x3 DRY No.2
DRY: SEASONED LUMBER.	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQ'D	
		GROSS REACTION		GROSS REACTION		BRG		BRG	
JT		VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
B		191	0	191	0	14-10-9	1-8		
F		191	0	191	0	14-10-9	1-8		
J		429	0	429	0	14-10-9	1-8		
I		1108	0	1108	0	14-10-9	1-8		
H		429	0	429	0	14-10-9	1-8		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.82/1.00 (C-D:1), BC=0.14/1.00 (H-I:4), WB=0.14/1.00 (D-I:1), SSI=0.38/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.49 (D) (INPUT = 0.90)
JSI METAL= 0.21 (D) (INPUT = 1.00)

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0	1.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TMW+w	MT20	2.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMB1-I	MT20	3.0	4.0	1.50	2.00
H	BMW1+w	MT20	2.0	4.0		
I	BMWVW1-I	MT20	4.0	6.0		
J	BMW1+w	MT20	2.0	4.0		

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	128	123 / 0	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
F	128	123 / 0	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
J	305	195 / 0	0 / 0	0 / 0	0 / 0	109 / 0	0 / 0
I	769	585 / 0	0 / 0	0 / 0	0 / 0	184 / 0	0 / 0
H	305	195 / 0	0 / 0	0 / 0	0 / 0	109 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, J, I, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.


LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FORCE (LBS)	MAX. (LC)	MAX. (LC)
FR-TO		FROM	TO	FR-TO			
A-B	0 / 21	-129.7	-129.7 0.03 (1)	10.00	J-C	-308 / 0	0.04 (1)
B-L	-39 / 24	-129.7	-129.7 0.03 (4)	6.25	C-I	-18 / 0	0.01 (1)
L-C	-78 / 0	-129.7	-129.7 0.02 (4)	6.25	I-D	-986 / 0	0.14 (1)
C-D	-10 / 0	-129.7	-129.7 0.82 (1)	10.00	I-E	-18 / 0	0.01 (1)
D-E	-10 / 0	-129.7	-129.7 0.82 (1)	10.00	H-E	-308 / 0	0.04 (1)
E-N	-78 / 0	-129.7	-129.7 0.02 (4)	6.25	K-L	-142 / 0	0.00 (1)
N-F	-39 / 24	-129.7	-129.7 0.03 (4)	6.25	M-N	-142 / 0	0.00 (1)
F-G	0 / 21	-129.7	-129.7 0.03 (1)	10.00			
B-K	0 / 54	-18.5	-18.5 0.04 (1)	10.00			
K-J	0 / 54	-18.5	-18.5 0.10 (4)	10.00			
J-I	0 / 27	-18.5	-18.5 0.14 (4)	10.00			
I-H	0 / 27	-18.5	-18.5 0.14 (4)	10.00			
H-M	0 / 54	-18.5	-18.5 0.10 (4)	10.00			
M-F	0 / 54	-18.5	-18.5 0.04 (1)	10.00			

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111067




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	P2	1	1	BAYVIEW WELLINGTON	
				TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:36 2023 Page 1

ID:UaoF4umx8QMx1bo7Q0Zq7Cya5EO-A04NixVeZKXNg8fYS6V4k2L boSvsoQ0PP7IRyJIQH



TOTAL WEIGHT = 52 lb


LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - C 2x4 DRY No.2 SPF C - E 2x4 DRY No.2 SPF E - G 2x4 DRY No.2 SPF B - F 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF DRY: SEASONED LUMBER.					DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS <table><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></</td></tr></table>																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													</
							</																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	P3	1	3	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:37 2023 Page 1


ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-eDelyGWHKefEHIEK0qDkHIWXP79neKLaf38ZltyJlQG



TOTAL WEIGHT = 3 X 50 = 150 lb

LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - C 2x4 DRY No.2 SPF C - D 2x4 DRY No.2 SPF D - F 2x4 DRY No.2 SPF B - E 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF DRY: SEASONED LUMBER. DESIGN CONSISTS OF 3 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS: CHORDS #ROWS SURFACE SPACING (IN) LOAD (PLF) TOP CHORDS : (0.122"x3") SPIRAL NAILS A-C 1 12 TOP C-D 1 12 TOP D-F 1 12 TOP BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS B-E 1 12 TOP WEBS : (0.122"x3") SPIRAL NAILS 2x3 1 6 STAGGER NAILS BY HALF THE SURFACE SPACING IN ADJACENT PLIES. TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS FACTORED GROSS REACTION MAXIMUM FACTORED GROSS REACTION INPUT REQD JT VERT HORZ. DOWN HORZ. UPLIFT IN-SX BRG IN-SX B 597 0 597 0 0 14-10-9 1-8 E 556 0 556 0 0 14-10-9 1-8 H 543 0 543 0 0 14-10-9 1-8 G 652 0 652 0 0 14-10-9 1-8 UNFACTORED REACTIONS 1ST LCASE MAX/MIN. COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL B 412 330 / 0 0 / 0 0 / 0 82 / 0 0 / 0 E 384 305 / 0 0 / 0 0 / 0 79 / 0 0 / 0 H 382 262 / 0 0 / 0 0 / 0 121 / 0 0 / 0 G 456 326 / 0 0 / 0 0 / 0 130 / 0 0 / 0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, E, H, G BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (4) CHORDS MAX. FACTORED FORCE VERT. LOAD LC1 MAX. MAX. MEMB. MAX. FACTORED FORCE MAX. MEMB. FORCE MAX. CS1 (LC) FR-TO FROM TO LENGTH FR-TO A-B 0 / 21 -129.7 -129.7 0.01 (1) 10.00 H-C -390 / 0 0.03 (1) B-J -43 / 5 -129.7 -129.7 0.06 (1) 6.25 C-G -61 / 0 0.02 (1) J-C -340 / 0 -129.7 -129.7 0.11 (1) 6.25 G-D -465 / 0 0.04 (1) C-D -185 / 0 -129.7 -129.7 0.26 (1) 6.25 I-J -757 / 0 0.00 (1) D-L -276 / 0 -129.7 -129.7 0.11 (1) 6.25 K-L -765 / 0 0.00 (1) L-E -34 / 75 -129.7 -129.7 0.06 (1) 6.25 E-F 0 / 21 -129.7 -129.7 0.01 (1) 10.00 B-I 0 / 246 -18.5 -18.5 0.09 (1) 10.00 I-H 0 / 246 -18.5 -18.5 0.09 (1) 10.00 H-G 0 / 235 -18.5 -18.5 0.05 (1) 10.00 G-K 0 / 197 -18.5 -18.5 0.09 (1) 10.00 K-E 0 / 197 -18.5 -18.5 0.09 (1) 10.00				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 38.3 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 51.6 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12 THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC 2018, NBC-2019AE - PART 9 OF CBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED 'ROOF LIVE LOAD' CSI: TC=0.26/1.00 (C-D-1), BC=0.09/1.00 (B-I-1), WB=0.04/1.00 (D-G-1), SSI=0.19/1.00 (E-K-1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10 COMPANION LIVE LOAD FACTOR = 1.00 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT. NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.17 (B) (INPUT = 0.90) JSI METAL= 0.05 (B) (INPUT = 1.00)			
--	--	--	--	--	--	--	--	--	--	--	--

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111069

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	P4	1	1	BAYVIEW WELLINGTON TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:38 2023 Page 1

ID:UaoF4umx8QMX1bo7Q0Zq7Cya5EO-6PC76cXv5yn5vSpwaXkzqV2fRPV7NmWjUju6qJyJlQF



TOTAL WEIGHT = 40 lb

LUMBER

COMBEN N. L. G. A. RULES

CHORDS	SIZE		LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
B - F	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY
 DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X'
B	TMB1-l	MT20	3.0	4.0	1.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TMW+w	MT20	2.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMB1-l	MT20	3.0	4.0	1.50	2.00
H	BMW1+w	MT20	2.0	4.0		
I	BMWWV1-l	MT20	4.0	6.0		
J	BMW1+w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQ'D BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX
JT	199	0	199	0	0	12-2-9
B	199	0	199	0	0	12-2-9
F	343	0	343	0	0	12-2-9
J	868	0	868	0	0	12-2-9
I	343	0	343	0	0	12-2-9

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	135	120 / 0	0 / 0	0 / 0	0 / 0	15 / 0	0 / 0
F	135	120 / 0	0 / 0	0 / 0	0 / 0	15 / 0	0 / 0
J	243	159 / 0	0 / 0	0 / 0	0 / 0	83 / 0	0 / 0
I	603	459 / 0	0 / 0	0 / 0	0 / 0	144 / 0	0 / 0
H	243	159 / 0	0 / 0	0 / 0	0 / 0	83 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, J, I, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.


LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MAX. FACTORED		FACTORED		MAX. FACTORED		FACTORED		
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		LENGTH	FR-TO			
A-B	0/21	-129.7	-129.7	0.03 (1)	10.00	J-C	-249 / 0	0.04 (1)
B-L	-48/7	-129.7	-129.7	0.01 (4)	6.25	C-D	-20 / 0	0.01 (1)
L-C	-70/0	-129.7	-129.7	0.02 (1)	6.25	I-D	-770 / 0	0.11 (1)
C-D	-9/0	-129.7	-129.7	0.50 (1)	10.00	H-E	-20 / 0	0.07 (1)
D-E	-9/0	-129.7	-129.7	0.50 (1)	10.00	H-E	-249 / 0	0.04 (1)
E-N	-70/0	-129.7	-129.7	0.02 (1)	6.25	K-L	-118 / 0	0.00 (1)
N-F	-48/7	-129.7	-129.7	0.01 (4)	6.25	M-N	-118 / 0	0.00 (1)
F-G	0/21	-129.7	-129.7	0.03 (1)	10.00			
B-K	0/50	-18.5	-18.5	0.04 (1)	10.00			
K-J	0/50	-18.5	-18.5	0.06 (4)	10.00			
J-I	0/29	-18.5	-18.5	0.09 (4)	10.00			
I-H	0/29	-18.5	-18.5	0.09 (4)	10.00			
H-M	0/50	-18.5	-18.5	0.06 (4)	10.00			
M-F	0/50	-18.5	-18.5	0.04 (1)	10.00			

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111070

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	38.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.50/1.00 (C-D:1), BC=0.09/1.00 (H-I:4),
WB=0.11/1.00 (D-I:1), SSI=0.30/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.38 (D) (INPUT = 0.90)

JSI METAL= 0.16 (D) (INPUT = 1.00)

JOB NAME 418649	TRUSS NAME P5	QUANTITY 1	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:39 2023 Page 1
ID:UaoF4umx8QMx1bo7Q0Zg7Cya5EO-abmWKyYXsfwyXcO67FGCMibnSpq26DDsiNdqMlyJIQE



TOTAL WEIGHT = 41 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
B - E	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-i	MT20	3.0	4.0	1.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TTW+h	MT20	3.0	4.0	2.00	1.25
E	TMB1-i	MT20	3.0	4.0	1.50	2.00
G	BMWW1-i	MT20	4.0	6.0		
H	BMW1+w	MT20	2.0	4.0		

NOTES-

1) Lateral braces to be a minimum of 2x4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
B	450	0	450	0	12-2-9	1-8
E	419	0	419	0	12-2-9	1-8
H	505	0	505	0	12-2-9	1-8
G	579	0	579	0	12-2-9	1-8

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	310	252/0	0/0	0/0	0/0	58/0	0/0
E	288	233/0	0/0	0/0	0/0	55/0	0/0
H	355	245/0	0/0	0/0	0/0	110/0	0/0
G	405	288/0	0/0	0/0	0/0	117/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, E, H, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0/21	-129.7 -129.7	0.03 (1)	H-C	-377/0	0.07 (1)	
B-J	-58/0	-129.7 -129.7	0.09 (1)	C-G	-44/0	0.03 (1)	
J-C	-232/0	-129.7 -129.7	0.17 (1)	G-D	-429/0	0.08 (1)	
C-D	-116/0	-129.7 -129.7	0.67 (1)	I-J	-453/0	0.00 (1)	
D-L	-184/0	-129.7 -129.7	0.17 (1)	K-L	-459/0	0.00 (1)	
L-E	-16/0	-129.7 -129.7	0.08 (1)				
E-F	0/21	-129.7 -129.7	0.03 (1)				
B-I	0/168	-18.5 -18.5	0.17 (1)				
I-H	0/168	-18.5 -18.5	0.17 (1)				
H-G	0/154	-18.5 -18.5	0.10 (1)				
G-K	0/131	-18.5 -18.5	0.17 (1)				
K-E	0/131	-18.5 -18.5	0.17 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 38.3 PSF
DL = 6.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD = 51.6 PSF	

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC 2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.67/1.00 (C-D:1), BC=0.17/1.00 (B-I:1), WB=0.08/1.00 (D-G:1), SSI=0.35/1.00 (E-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.57 (D) (INPUT = 0.90)
JSI METAL = 0.10 (B) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111071



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	P6	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:40 2023 Page 1

ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-3oKuXIY9dZ2p8mzJhynRww87PC6arhk0x1NDuCyJlQD



Scale = 1:27.8

TOTAL WEIGHT = 44 lb

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				DESIGN CRITERIA			
CHORDS	SIZE	LUMBER	DESCR.	BEARINGS				SPECIFIED LOADS:			
A - C	2x4	DRY	No.2	FACTORED				TOP CH. LL = 38.3 PSF			
C - D	2x4	DRY	No.2	GROSS REACTION				DL = 6.0 PSF			
D - F	2x4	DRY	No.2	MAXIMUM FACTORED				BOT CH. LL = 0.0 PSF			
B - E	2x4	DRY	No.2	DOWN				DL = 7.4 PSF			
ALL WEBS 2x3 DRY SEASONED LUMBER.				INPUT				TOTAL LOAD = 51.6 PSF			
				BRG				SPACING = 24.0 IN./C			
				IN-SX				LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12			

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-J	MT20	3.0	4.0	1.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TTW-m	MT20	4.0	4.0		
E	TMB1-J	MT20	3.0	4.0	1.50	2.00
G	BMWW1-I	MT20	4.0	4.0		
H	BMW1+w	MT20	2.0	4.0		

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	484	361 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0
E	453	351 / 0	0 / 0	0 / 0	0 / 0	102 / 0	0 / 0
H	169	105 / 0	0 / 0	0 / 0	0 / 0	64 / 0	0 / 0
G	273	202 / 0	0 / 0	0 / 0	0 / 0	71 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, E, H, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.


LOADING

TOTAL LOAD CASES: (4)


CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 21	-129.7 -129.7	0.03 (1)	H-C	-97 / 0	0.03 (1)	
B-J	-63 / 203	-129.7 -129.7	0.30 (1)	C-G	-72 / 0	0.03 (1)	
J-C	-375 / 0	-129.7 -129.7	0.47 (1)	G-D	-181 / 0	0.06 (1)	
C-D	-245 / 0	-129.7 -129.7	0.05 (1)	I-J	-1130 / 0	0.00 (1)	
D-L	-350 / 0	-129.7 -129.7	0.47 (1)	K-L	-1134 / 0	0.00 (1)	
L-E	-61 / 231	-129.7 -129.7	0.31 (1)				
E-F	0 / 21	-129.7 -129.7	0.03 (1)				
B-I	0 / 269	-18.5 -18.5	0.41 (1)				
I-H	0 / 269	-18.5 -18.5	0.41 (1)				
H-G	0 / 266	-18.5 -18.5	0.25 (1)				
G-K	0 / 250	-18.5 -18.5	0.41 (1)				
K-E	0 / 250	-18.5 -18.5	0.41 (1)				

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111072



TOTAL WEIGHT = 2 X 44 = 88 lb

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.	SPF	SPF	SPF
A - D	2x4	DRY	No.2	SPF			
D - G	2x4	DRY	No.2	SPF			
B - F	2x4	DRY	No.2	SPF			
ALL WEBS	2x3	DRY	No.2	SPF			
DRY: SEASONED LUMBER.							

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB1-I	MT20	3.0	4.0	1.50 2.00
C	TMW+w	MT20	2.0	4.0	
D	TTW+p	MT20	4.0	6.0	Edge
E	TMW+w	MT20	2.0	4.0	
F	TMB1-I	MT20	3.0	4.0	1.50 2.00
H	BMVWW1-I	MT20	4.0	6.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

UNFACTORED REACTIONS							
JT	1ST LCASE	MAX/MIN	COMPONENT REACTIONS				
B	331	252 / 0	0 / 0	0 / 0	0 / 0	79 / 0	0 / 0
F	331	252 / 0	0 / 0	0 / 0	0 / 0	79 / 0	0 / 0
H	696	513 / 0	0 / 0	0 / 0	0 / 0	183 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, H

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING							
TOTAL LOAD CASES: (4)							
CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED HORIZ. LOAD (PLF)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)
A-B	0 / 21	-129.7	-129.7	0.03 (1)	10.00	H-D	-367 / 0
B-J	-421 / 0	-129.7	-129.7	0.07 (4)	6.25	H-E	-378 / 0
J-C	-289 / 0	-129.7	-129.7	0.20 (1)	6.25	C-H	-378 / 0
C-D	-5 / 19	-129.7	-129.7	0.20 (1)	10.00	I-J	-7 / 149
D-E	-5 / 19	-129.7	-129.7	0.20 (1)	10.00	K-L	-7 / 149
E-L	-289 / 0	-129.7	-129.7	0.20 (1)	6.25		
L-F	-421 / 0	-129.7	-129.7	0.07 (4)	6.25		
F-G	0 / 21	-129.7	-129.7	0.03 (1)	10.00		
B-I	0 / 250	-18.5	-18.5	0.06 (4)	10.00		
I-H	0 / 250	-18.5	-18.5	0.18 (4)	10.00		
H-K	0 / 250	-18.5	-18.5	0.18 (4)	10.00		
K-F	0 / 250	-18.5	-18.5	0.06 (4)	10.00		

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015
THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.20/1.00 (D-E:1), BC=0.18/1.00 (H-I:4), WB=0.16/1.00 (D-H:1), SSI=0.15/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.35 (F) (INPUT = 0.90)
JSI METAL= 0.11 (F) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111073

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418649	P8S	1	1	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:42 2023 Page 1

ID:UaoF4umx8QMx1bo7Q0Zg7Cva5EO-7ARey aP9AIXO36hpNpv LDNY0slJfJOLSkZ4yJQB



Scale = 1:33.8

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				DESIGN CRITERIA			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.	BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG	SPECIFIED LOADS:	
A - D	2x4	DRY	No.2	SPF	JT. VERT	DOWN	DOWN	14-10-9	1-8	TOP CH. LL = 38.3 PSF	
D - E	2x4	DRY	No.2	SPF	B	519	519	14-10-9	1-8	DL = 6.0 PSF	
E - F	2x4	DRY	No.2	SPF	G	318	318	14-10-9	1-8	BOT CH. LL = 0.0 PSF	
F - H	2x4	DRY	No.2	SPF	K	761	761	14-10-9	1-8	DL = 7.4 PSF	
B - G	2x4	DRY	No.2	SPF	J	484	484	14-10-9	1-8	TOTAL LOAD = 51.6 PSF	
ALL WEBS	2x3	DRY	No.2	SPF	I	281	281	14-10-9	1-8	SPACING = 24.0 IN. C/C	
DRY: SEASONED LUMBER.											

PLATES (table is in inches)					
JT TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0	1.50 2.00
C	TMW+W	MT20	2.0	4.0	
D	TTW+p	MT20	4.0	6.0	Edge
E	TTWW+m	MT20	5.0	6.0	
F	TTWW+m	MT20	5.0	6.0	2.25 1.50
G	TMB1-I	MT20	3.0	4.0	1.50 2.00
I	BMW1+W	MT20	2.0	4.0	
J	BMWW1-I	MT20	4.0	6.0	
K	BMWW1-I	MT20	4.0	6.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	360	276 / 0	0 / 0	0 / 0	0 / 0	84 / 0	0 / 0
G	220	175 / 0	0 / 0	0 / 0	0 / 0	44 / 0	0 / 0
K	532	388 / 0	0 / 0	0 / 0	0 / 0	145 / 0	0 / 0
J	322	245 / 0	0 / 0	0 / 0	0 / 0	77 / 0	0 / 0
I	198	137 / 0	0 / 0	0 / 0	0 / 0	61 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, G, K, J, I.

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 20	-129.7 -129.7	0.03 (1)	C-K	-380 / 0	0.11 (1)	
B-M	-509 / 0	-129.7 -129.7	0.08 (4)	K-D	-374 / 0	0.16 (1)	
M-C	-351 / 0	-129.7 -129.7	0.20 (1)	K-E	-48 / 0	0.01 (1)	
C-D	-42 / 0	-129.7 -129.7	0.20 (1)	J-E	-395 / 0	0.06 (1)	
D-E	-12 / 0	-129.7 -129.7	0.30 (1)	J-F	-64 / 0	0.01 (1)	
E-F	-31 / 0	-129.7 -129.7	0.16 (1)	I-F	-188 / 0	0.03 (1)	
F-O	-125 / 0	-129.7 -129.7	0.09 (1)	L-M	0 / 178	0.00 (1)	
O-G	-57 / 0	-129.7 -129.7	0.03 (1)	N-O	-251 / 0	0.00 (1)	
G-H	0 / 20	-129.7 -129.7	0.03 (1)				

B-L	0 / 299	-18.5 -18.5	0.07 (4)	10.00
L-K	0 / 299	-18.5 -18.5	0.14 (4)	10.00
K-J	0 / 51	-18.5 -18.5	0.13 (4)	10.00
J-I	0 / 81	-18.5 -18.5	0.05 (1)	10.00
I-N	0 / 90	-18.5 -18.5	0.09 (1)	10.00
N-G	0 / 90	-18.5 -18.5	0.09 (1)	10.00

CSI: TC=0.30/1.00 (D-E:1), BC=0.14/1.00 (K-L:4), WB=0.16/1.00 (D-K:1), SSI=0.19/1.00 (G-N:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.39 (B) (INPUT = 0.90)
JSI METAL= 0.12 (B) (INPUT = 1.00)

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111074



JOB NAME 418649	TRUSS NAME P9S	QUANTITY 1	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:43 2023 Page 1

ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-TM70AKb1vUQO7DhuM4K8XZmY2Q9J21fSd7btvXyJlQA



Scale = 1:33.8

TOTAL WEIGHT = 59 lb

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY			
N. L. G. A. RULES				BUILDING DESIGNER			
CHORDS	SIZE	LUMBER	DESCR.	BEARINGS			
A - D	2x4	DRY	No.2	FACTORED	MAXIMUM FACTORED	INPUT	REQRD
D - E	2x4	DRY	No.2	GROSS REACTION	GROSS REACTION	BRG	BRG
E - F	2x4	DRY	No.2	JT	DOWN	IN-SX	IN-SX
F - H	2x4	DRY	No.2	B	508	0	14-10-9
B - G	2x4	DRY	No.2	G	503	0	14-10-9
ALL WEBS	2x3	DRY	No.2	K	787	0	14-10-9
DRY: SEASONED LUMBER.				J	200	0	14-10-9
				I	347	0	14-10-9

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	X
B	TMB1-I	MT20	3.0	4.0	1.50 2.00
C	TTW+u	MT20	2.0	4.0	
D	TTW+p	MT20	4.0	6.0	Edge
E	TTWW+m	MT20	5.0	6.0	
F	TTWW+m	MT20	5.0	6.0	2.25 1.50
G	TMB1-I	MT20	3.0	4.0	1.50 2.00
I	BMW1+w	MT20	2.0	4.0	
J	BMWW1-t	MT20	4.0	6.0	
K	BMWW1-t	MT20	4.0	6.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

UNFACTORED REACTIONS							
1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	353	269 / 0	0 / 0	0 / 0	0 / 0	84 / 0	0 / 0
G	348	272 / 0	0 / 0	0 / 0	0 / 0	76 / 0	0 / 0
K	550	397 / 0	0 / 0	0 / 0	0 / 0	153 / 0	0 / 0
J	135	124 / 0	0 / 0	0 / 0	0 / 0	11 / 0	0 / 0
I	246	157 / 0	0 / 0	0 / 0	0 / 0	89 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, G, K, J, I

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 20	-129.7 -129.7	0.03 (1)	10.00	C-K	-379 / 0	0.10 (1)
B-M	-486 / 0	-129.7 -129.7	0.08 (4)	6.25	K-D	-264 / 0	0.12 (1)
M-C	-336 / 0	-129.7 -129.7	0.20 (1)	6.25	K-E	-148 / 0	0.04 (1)
C-D	-27 / 0	-129.7 -129.7	0.20 (1)	6.25	J-E	-144 / 0	0.04 (1)
D-E	-5 / 3	-129.7 -129.7	0.06 (1)	10.00	J-F	-159 / 0	0.05 (1)
E-F	-53 / 0	-129.7 -129.7	0.16 (1)	6.25	I-F	-160 / 0	0.04 (1)
F-O	-211 / 0	-129.7 -129.7	0.31 (1)	6.25	L-M	0 / 173	0.00 (1)
O-G	-32 / 162	-129.7 -129.7	0.20 (1)	6.25	N-O	-793 / 0	0.00 (1)
G-H	0 / 20	-129.7 -129.7	0.03 (1)	10.00			
B-L	0 / 287	-18.5 -18.5	0.07 (4)	10.00			
L-K	0 / 287	-18.5 -18.5	0.14 (4)	10.00			
K-J	0 / 57	-18.5 -18.5	0.13 (4)	10.00			
J-I	0 / 142	-18.5 -18.5	0.16 (1)	10.00			
I-N	0 / 147	-18.5 -18.5	0.28 (1)	10.00			
N-G	0 / 147	-18.5 -18.5	0.28 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT. CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.31/1.00 (F-O-1), BC=0.28/1.00 (I-N-1), WB=0.12/1.00 (D-K-1), SSI=0.60/1.00 (G-N-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.43 (G) (INPUT = 0.90)
JSI METAL= 0.12 (B) (INPUT = 1.00)


NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111075

JOB NAME 418649	TRUSS NAME P10	QUANTITY 1	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:44 2023 Page 1
ID:UaoF4umx8QMx1bo7Q0Zg7Cya5EO-xZZPNgbqgoYFdNG4worN3mlq0qTrnUocsfLR1zyJlQ9



TOTAL WEIGHT = 51 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
B - E	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB1-I	MT20	3.0	4.0	1.50 2.00
C	TTWW+m	MT20	5.0	6.0	2.25 1.50
D	TTWW+h	MT20	3.0	4.0	2.00 1.25
E	TMB1-I	MT20	3.0	4.0	1.50 2.00
G	BMWV1-I	MT20	4.0	6.0	
H	BMW1+w	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
B	717	0	717	0	14-10-9
E	675	0	675	0	14-10-9
H	396	0	396	0	14-10-9
G	560	0	560	0	14-10-9

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	496	388/0	0/0	0/0	0/0	108/0	0/0
E	468	363/0	0/0	0/0	0/0	105/0	0/0
H	279	185/0	0/0	0/0	0/0	94/0	0/0
G	391	285/0	0/0	0/0	0/0	105/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, E, H, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)	
FR-TO		FROM	TO	FR-TO			
A-B	0/21	-129.7	-129.7 0.03 (1)	10.00	H-C	-240/0	0.09 (1)
B-J	-75/141	-129.7	-129.7 0.29 (1)	6.25	C-G	-80/0	0.05 (1)
J-C	-426/0	-129.7	-129.7 0.49 (1)	6.25	G-D	-342/0	0.12 (1)
C-D	-251/0	-129.7	-129.7 0.36 (1)	6.25	I-J	-1119/0	0.00 (1)
D-L	-362/0	-129.7	-129.7 0.49 (1)	6.25	K-L	-1127/0	0.00 (1)
L-E	-68/211	-129.7	-129.7 0.30 (1)	6.25			
E-F	0/21	-129.7	-129.7 0.03 (1)	10.00			
B-I	0/308	-18.5	-18.5 0.41 (1)	10.00			
I-H	0/308	-18.5	-18.5 0.41 (1)	10.00			
H-G	0/302	-18.5	-18.5 0.20 (1)	10.00			
G-K	0/259	-18.5	-18.5 0.41 (1)	10.00			
K-E	0/259	-18.5	-18.5 0.41 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.49/1.00 (C-J:1), BC=0.41/1.00 (B-I:1), WB=0.12/1.00 (D-G:1), SSI=0.86/1.00 (E-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.60 (B) (INPUT = 0.90)
JSI METAL= 0.17 (B) (INPUT = 1.00)

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111076





JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418651	P11	1	1	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:13 2023 Page 1

ID:UaoF4umx8QMX1bo7Q0Zq7Cya5EO-TbDTS9BqBPPJlqMwr7z28BMzaFhDyWmZlVh yJHd4



TOTAL WEIGHT = 36 lb

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				DESIGN CRITERIA			
N. L. G. A. RULES				BEARINGS				SPECIFIED LOADS:			
CHORDS	SIZE	LUMBER	DESCR.	FACTORED GROSS REACTION				TOP CH. LL = 38.3 PSF			
A - C	2x4	DRY	No.2	JT	VERT	HORZ	DOWN	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG	DL = 6.0 PSF
C - E	2x4	DRY	No.2	B	202	0	202	0	10-10-9	1-8	BOT CH. LL = 0.0 PSF
E - G	2x4	DRY	No.2	F	202	0	202	0	10-10-9	1-8	DL = 7.4 PSF
B - F	2x4	DRY	No.2	J	301	0	301	0	10-10-9	1-8	TOTAL LOAD = 51.6 PSF
ALL WEBS 2x3 DRY SEASONED LUMBER.				I	749	0	749	0	10-10-9	1-8	
				H	301	0	301	0	10-10-9	1-8	

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0	1.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TMW+w	MT20	2.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMB1-I	MT20	3.0	4.0	1.50	2.00
H	BMW1+w	MT20	2.0	4.0		
I	BMW1+w	MT20	4.0	6.0		
J	BMW1+w	MT20	2.0	4.0		

UNFACTORED REACTIONS							
1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	138	119/0	0/0	0/0	0/0	19/0	0/0
F	138	119/0	0/0	0/0	0/0	19/0	0/0
J	213	141/0	0/0	0/0	0/0	71/0	0/0
I	520	396/0	0/0	0/0	0/0	124/0	0/0
H	213	141/0	0/0	0/0	0/0	71/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, J, I, H

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0/21	-129.7 -129.7	0.03 (1)	J-C	-219/0	0.03 (1)	
B-L	-51/1	-129.7 -129.7	0.01 (1)	C-I	-22/0	0.01 (1)	
L-C	-66/0	-129.7 -129.7	0.02 (1)	I-D	-661/0	0.09 (1)	
C-D	-8/0	-129.7 -129.7	0.37 (1)	D-E	-22/0	0.01 (1)	
D-E	-8/0	-129.7 -129.7	0.37 (1)	E-N	-219/0	0.03 (1)	
E-N	-66/0	-129.7 -129.7	0.02 (1)	N-F	-109/0	0.00 (1)	
N-F	-51/1	-129.7 -129.7	0.01 (1)	F-G	-109/0	0.00 (1)	
F-G	0/21	-129.7 -129.7	0.03 (1)				
B-K	0/48	-18.5 -18.5	0.04 (1)				
K-J	0/48	-18.5 -18.5	0.05 (4)				
J-I	0/29	-18.5 -18.5	0.06 (4)				
I-H	0/29	-18.5 -18.5	0.06 (4)				
H-M	0/48	-18.5 -18.5	0.05 (4)				
M-F	0/48	-18.5 -18.5	0.04 (1)				

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.

CSI: TC=0.37/1.00 (D-E:1), BC=0.06/1.00 (H-I:4), WB=0.09/1.00 (D-I:1), SS=0.28/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987.1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.33 (D) (INPUT = 0.90)
JSI METAL= 0.14 (D) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	P12	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington					

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:15 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-grizu8BSMof7Y3qk2G1R8ZHhBNwXhsS303C0LtyJHd2



LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
B - E	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB1-I	MT20	3.0	4.0	1.50 2.00
C	TTVVW+m	MT20	5.0	6.0	2.25 1.50
D	TTVW+h	MT20	3.0	4.0	2.00 1.25
E	TMB1-I	MT20	3.0	4.0	1.50 2.00
G	BMWV1-I	MT20	4.0	6.0	
H	BMW1+w	MT20	2.0	4.0	

NOTES:
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	GROSS REACTION	VERT	HORZ	GROSS REACTION	DOWN	UP	IN-SX	BRG	IN-SX
B	449	0	449	0	0	10-10-9	1-8		
E	415	0	415	0	0	10-10-9	1-8		
H	399	0	399	0	0	10-10-9	1-8		
G	491	0	491	0	0	10-10-9	1-8		

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	310	247 / 0	0 / 0	0 / 0	0 / 0	62 / 0	0 / 0
E	287	228 / 0	0 / 0	0 / 0	0 / 0	59 / 0	0 / 0
H	281	193 / 0	0 / 0	0 / 0	0 / 0	88 / 0	0 / 0
G	344	248 / 0	0 / 0	0 / 0	0 / 0	96 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, E, H, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 21	-129.7 -129.7	0.03 (1)	H-C	-287 / 0	0.05 (1)	
B-J	-59 / 0	-129.7 -129.7	0.08 (1)	C-G	-50 / 0	0.02 (1)	
J-C	-225 / 0	-129.7 -129.7	0.18 (1)	G-D	-349 / 0	0.07 (1)	
C-D	-112 / 0	-129.7 -129.7	0.38 (1)	I-J	-442 / 0	0.00 (1)	
D-L	-174 / 0	-129.7 -129.7	0.18 (1)	K-L	-449 / 0	0.00 (1)	
L-E	-29 / 0	-129.7 -129.7	0.08 (1)				
E-F	0 / 21	-129.7 -129.7	0.03 (1)				
B-I	0 / 163	-18.5 -18.5	0.17 (1)				
I-H	0 / 163	-18.5 -18.5	0.17 (1)				
H-G	0 / 153	-18.5 -18.5	0.09 (1)				
G-K	0 / 124	-18.5 -18.5	0.16 (1)				
K-E	0 / 124	-18.5 -18.5	0.16 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.38/1.00 (C-D:1), BC=0.17/1.00 (B-I:1), WB=0.07/1.00 (D-G:1), SSI=0.34/1.00 (E-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.44 (D) (INPUT = 0.90)
JSI METAL= 0.10 (B) (INPUT = 1.00)



STRUCTURAL COMPONENT ONLY
DWG # TR23111105

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418651	P13	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:16 2023 Page 1
ID:UaoF4umx8QMx1bo7Q0Zg7Cya5EO-81GL5TC476n ACPxbzYggmpanCYQK?DFixZtJyJHd1



TOTAL WEIGHT = 34 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
B - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB1-I	MT20	3.0	4.0	1.50 2.00
C	TTW+p	MT20	4.0	6.0	Edge
D	TMB1-I	MT20	3.0	4.0	1.50 2.00
F	BMW1+w	MT20	2.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT	REQD
JT	VERT	JT	HORZ	BRG	BRG
B	664	0	664	0	1-8
D	664	0	664	0	1-8
F	427	0	427	0	1-8

UNFACTORED REACTIONS

1ST LCASE		MAX / MIN. COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
B	459	361 / 0	0 / 0	0 / 0	0 / 0	98 / 0
D	459	361 / 0	0 / 0	0 / 0	0 / 0	98 / 0
F	303	194 / 0	0 / 0	0 / 0	0 / 0	109 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 21	-129.7 -129.7	0.03 (1)	10.00	F-C	-135 / 0	
B-H	-37 / 272	-129.7 -129.7	0.35 (1)	6.25	G-H	-1238 / 0	
H-C	-382 / 0	-129.7 -129.7	0.47 (1)	6.25	I-J	-1238 / 0	
C-J	-382 / 0	-129.7 -129.7	0.47 (1)	6.25			
J-D	-37 / 272	-129.7 -129.7	0.35 (1)	6.25			
D-E	0 / 21	-129.7 -129.7	0.03 (1)	10.00			
B-G	0 / 272	-18.5 -18.5	0.44 (1)	10.00			
G-F	0 / 272	-18.5 -18.5	0.44 (1)	10.00			
F-I	0 / 272	-18.5 -18.5	0.44 (1)	10.00			
I-D	0 / 272	-18.5 -18.5	0.44 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.47/1.00 (C-H:1), BC=0.44/1.00 (B-G:1), WB=0.05/1.00 (C-F:1), SSI=0.93/1.00 (B-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	850	371	1747
		788	1887
		1873	


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.58 (B) (INPUT = 0.90)
JSI METAL= 0.16 (B) (INPUT = 1.00)

NOTES-

- 1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111106

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	BAYVIEW WELLINGTON	DRWG NO.
418651	P20	2	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 12:09:17 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-cEqkJpDitQvroM 79h3vD M0HBYM9m3MUNh7QmyJHd0



TOTAL WEIGHT = 2 X 51 = 102 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE		LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
B - E	2x4	DRY	No.2	SPF


ALL WEBS 2x3 DRY
 DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0		
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TTW+h	MT20	3.0	4.0	2.00	1.25
E	TMB1-I	MT20	3.0	4.0	1.50	2.00
G	BMWV1-t	MT20	4.0	6.0		
H	BMW1+w	MT20	2.0	4.0		

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111107

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
B	707	0	707	0	0	14-10-9	1-8
E	664	0	664	0	0	14-10-9	1-8
H	408	0	408	0	0	14-10-9	1-8
G	568	0	568	0	0	14-10-9	1-8

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	489	383 / 0	0 / 0	0 / 0	0 / 0	106 / 0	0 / 0
E	460	357 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0
H	288	192 / 0	0 / 0	0 / 0	0 / 0	96 / 0	0 / 0
G	397	290 / 0	0 / 0	0 / 0	0 / 0	107 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, E, H, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM TO			FR-TO			
A-B	0/21	-129.7	-129.7	0.03 (1)	10.00	H-C	-253/0	0.09 (1)
B-J	-73/127	-129.7	-129.7	0.28 (1)	6.25	C-G	-79/0	0.05 (1)
J-C	-418/0	-129.7	-129.7	0.47 (1)	6.25	G-D	-354/0	0.12 (1)
C-D	-244/0	-129.7	-129.7	0.39 (1)	6.25	I-J	-1084/0	0.00 (1)
D-L	-353/0	-129.7	-129.7	0.47 (1)	6.25	K-L	-1093/0	0.00 (1)
L-E	-66/198	-129.7	-129.7	0.29 (1)	6.25			
E-F	0/21	-129.7	-129.7	0.03 (1)	10.00			
B-I	0/302	-18.5	-18.5	0.40 (1)	10.00			
I-H	0/302	-18.5	-18.5	0.40 (1)	10.00			
H-G	0/296	-18.5	-18.5	0.20 (1)	10.00			
G-K	0/252	-18.5	-18.5	0.40 (1)	10.00			
K-E	0/252	-18.5	-18.5	0.40 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	38.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	51.6	PSF

SPACING = 24.0 IN. C/C

1

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.47/1.00 (C-J:1), BC=0.40/1.00 (B-I:1),
WB=0.12/1.00 (D-G:1), SSI=0.84/1.00 (E-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.58 (B) (INPUT = 0.90)
JSI METAL= 0.16 (B) (INPUT = 1.00)



JOB NAME 418649	TRUSS NAME J1	QUANTITY 20	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:26 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-T5UbbWONwGHoTcudt0X9KzZhZOpZLSyjs UP0yJlQR



Scale = 1:36.1

TOTAL WEIGHT = 20 X 26 = 525 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4	DRY	No.2	SPF	
A - D	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	4.0	6.0		
E	BMW1+w	MT20	2.0	4.0		Edge
F	BMW1-t	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	GROSS REACTION	VERT	HORZ	GROSS REACTION	DOWN	HORZ	UPLIFT	BRG	BRG
F	608	0	0	608	0	0	5-8	1-8	1-8
D	144	0	0	144	0	0	1-8	1-8	1-8
E	296	0	0	296	0	0	1-8	1-8	1-8

SEE MITTEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) D, E

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN	COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	421	327 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	94 / 0	0 / 0
D	98	85 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0
E	208	143 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	65 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT.	LOAD LC1	MEMB.	FORCE (LBS)	VERT.	LOAD LC1
FR-TO		FROM	TO	FR-TO		FROM	TO
F-B	-325 / 0	0.0	0.0	0.03 (1)	7.81	C-E	-302 / 0
A-B	0 / 58	-129.7	-129.7	0.18 (1)	10.00	F-C	-292 / 0
B-C	0 / 29	-129.7	-129.7	0.19 (1)	10.00		
C-D	-29 / 0	-129.7	-129.7	0.18 (1)	6.25		
F-E	0 / 180	-18.5	-18.5	0.18 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	51.8	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.19/1.00 (B-C:1), BC=0.18/1.00 (E-F:4), WB=0.12/1.00 (C-E:1), SSI=0.14/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.37 (E) (INPUT = 0.90)
JSI METAL= 0.14 (E) (INPUT = 1.00)

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111058



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
418650	J1S	8	1	BAYVIEW WELLINGTON		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:44:47 2023 Page 1
ID:UaoF4umx8QMx1bo7QDZg7Cya5EO-eQ00nAQd3miQRScb2yiBe Uqsdpukt SqbKqzyJl



Scale = 1:35.6

LUMBER					DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER										TOTAL WEIGHT = 8 X 27 = 217 lb			
N. L. G. A. RULES					BEARINGS										DESIGN CRITERIA			
CHORDS		SIZE	LUMBER	DESCR.	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG	SPECIFIED LOADS:							
I - B	2x4	DRY	No.2	SPF	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	TOP CH. LL = 38.3	PSF					
A - D	2x4	DRY	No.2	SPF								DL = 6.0	PSF					
I - H	2x4	DRY	No.2	SPF								BOT CH. LL = 0.0	PSF					
G - E	2x4	DRY	No.2	SPF								DL = 7.4	PSF					
ALL WEBS EXCEPT		2x4	DRY	No.2	SPF							TOTAL LOAD = 51.6	PSF					
B - H	2x3	DRY	No.2	SPF								SPACING = 24.0 IN. C/C						

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
C	TMVW-t	MT20	4.0	6.0	2.00	2.75
F	BMV+w	MT20	2.0	4.0		
G	BWM-t	MT20	3.0	4.0		
H						
H	BBWW-m	MT20	4.0	6.0	1.00	1.75
I	BMV1+p	MT20	3.0	4.0		
J	NP+p	MT20	2.0	4.0	2.00	1.00

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES:
1) Lateral braces to be a minimum of 2X4 SPF #2.

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
I	440	343 / 0	0 / 0	0 / 0	0 / 0	97 / 0	0 / 0
D	182	153 / 0	0 / 0	0 / 0	0 / 0	29 / 0	0 / 0
E	107	59 / 0	0 / 0	0 / 0	0 / 0	48 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

MAX. UNBRACED INTERIOR CHORD LENGTH = 7.81 FT

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS (LC)	
FR-TO		FROM TO		FR-TO			
I-B	-622 / 0	0.0 0.0 0.07 (1)	7.81	H-G	-142 / 0	0.25 (1)	
A-B	0 / 58	-129.7 -129.7 0.18 (1)	10.00	G-C	0 / 75	0.26 (1)	
B-C	-260 / 0	-129.7 -129.7 0.17 (1)	6.25	B-H	0 / 240	0.05 (1)	
C-D	-10 / 3	-129.7 -129.7 0.37 (1)	6.25	C-F	-413 / 0	0.05 (1)	
I-H	0 / 0	-18.5 -18.5 0.01 (4)	10.00				
G-F	0 / 298	-18.5 -18.5 0.50 (1)	10.00				
F-E	0 / 0	-18.5 -18.5 0.45 (1)	10.00				

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/816 (0.09")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/443 (0.16")

CSI: TC=0.37/1.00 (C-D:1), BC=0.50/1.00 (F-G:1), WB=0.26/1.00 (C-G:1), SSI=0.18/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.72 (H) (INPUT = 0.90)
JSI METAL= 0.21 (F) (INPUT = 1.00)




STRUCTURAL COMPONENT ONLY
DWG # TR23111099

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
418649	J2	1	1	BAYVIEW WELLINGTON	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-xH1zpsO7hZPf5mTpQl20tB5lnzkwpV5yWj1xSyJlQQ

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:27 2023 Page 1



Scale = 1:31.3

TOTAL WEIGHT = 18 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4 DRY	No.2	SPF		
A - C	2x4 DRY	No.2	SPF		
F - D	2x4 DRY	No.2	SPF		
ALL WEBS	2x3 DRY	No.2	SPF		
DRY: SEASONED LUMBER.					

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT VERT	JT HORZ	JT DOWN	JT HORZ
F 541	0	541	0
C 316	0	316	0
D 45	0	51	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT COMBINED	JT SNOW	JT LIVE	JT PERM.LIVE	JT WIND	JT DEAD	JT SOIL
F 374	292/0	0/0	0/0	0/0	82/0	0/0
C 216	186/0	0/0	0/0	0/0	29/0	0/0
D 36	0/0	0/0	0/0	0/0	38/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	FR-TO	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
F-B	-496/0	0.0	0.0	0.05 (1)	7.81	B-E	0/0	0.00 (1)
A-B	0/58	-129.7	-129.7	0.18 (1)	10.00			
B-C	0/0	-129.7	-129.7	0.52 (1)	10.00			
F-E	0/0	-18.5	-18.5	0.11 (4)	10.00			
E-D	0/0	-18.5	-18.5	0.13 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.52/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.19/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.31 (B) (INPUT = 0.90)
JSI METAL= 0.13 (B) (INPUT = 1.00)

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111059

JOB NAME 418649	TRUSS NAME J3	QUANTITY 1	PLY 1	JOB DESC. BAYVIEW WELLINGTON	TRUSS DESC.	DRWG NO.
---------------------------	-------------------------	----------------------	-----------------	--	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MITek Industries, Inc. Tue Nov 14 11:14:28 2023 Page 1

ID:UaoF4umx8QMx1bo7Q0Zq7Cya5EO-PubLB0BPdSxWiv2? RZdQOe?eN4y1GkFAATaTuyJQP



Scale = 1:18.3

TOTAL WEIGHT = 13 lb

LUMBER				DESCR.	SPF
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
F - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
F - D	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMV+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
F	410	0	410	0	5-8	1-8
C	46	0	46	0	1-8	1-8
D	45	0	51	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST CASE COMBINED		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM.LIVE	WIND			
F	285	215 / 0	0 / 0	0 / 0	0 / 0	70 / 0	0 / 0
C	32	27 / 0	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		W E B S		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (LBS)	MAX. (PLF)	MAX. (LC)	MEMB.	MAX. FORCE (LBS)	MAX. (LC)	MEMB.
FR-TO			FROM	TO	FR-TO			FR-TO
F-B	-365 / 0	0.0	0.0	0.04 (1)	B-E	0 / 0	0.00 (1)	
A-B	0 / 58	-129.7	-129.7	0.20 (1)				
B-C	-45 / 0	-129.7	-129.7	0.19 (1)				
F-E	0 / 0	-18.5	-18.5	0.12 (4)				
E-G	0 / 0	-18.5	-18.5	0.14 (4)				
G-H	0 / 0	-18.5	-18.5	0.14 (4)				
H-D	0 / 0	-18.5	-18.5	0.14 (4)				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-11-4	1	1	---	FRONT	VERT	TOTAL	---	C1
H	3-11-4	1	1	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/999 (0.03")

CSI: TC=0.20/1.00 (A-B:1), BC=0.14/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.12/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.23 (B) (INPUT = 0.90)
JSI METAL= 0.10 (B) (INPUT = 1.00)

NOTES-
1) Lateral braces to be a minimum of 2x4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111060




JOB NAME 418649	TRUSS NAME J4	QUANTITY 1	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
---------------------------	-------------------------	----------------------	-----------------	--	----------

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 Mitek Industries, Inc. Tue Nov 14 11:14:29 2023 Page 1

ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-tg9kEXQFCBfNK3dBY84sycB9WnQOmI OPqC80LyJlQO



Scale = 1:26.7

TOTAL WEIGHT = 16 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
F - D	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMV+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT.	HORZ	DOWN	HORZ		
F	470	0	470	0	5-8	1-8
C	246	0	246	0	1-8	1-8
D	45	0	51	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST CASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
F	326	251 / 0	0 / 0	0 / 0	0 / 0	75 / 0	0 / 0
C	168	145 / 0	0 / 0	0 / 0	0 / 0	23 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		MAX.	MEMB.	WEBS		MAX.
	MAX.	FACTORED	FORCE	VERT. LOAD	LC1	MAX.	MAX.	FACTORED	FORCE
FR-TO			(LBS)	FROM	TO	CSI (LC)	UNBRAC	LENGTH	FR-TO
F-B	-425 / 0	0.0	0.0	0.05	(1)	7.81	B-E	0 / 0	0.00 (1)
A-B	0 / 58	-129.7	-129.7	0.18	(1)	10.00			
B-C	0 / 0	-129.7	-129.7	0.32	(1)	10.00			
F-E	0 / 0	-18.5	-18.5	0.11	(4)	10.00			
E-D	0 / 0	-18.5	-18.5	0.13	(4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.32/1.00 (B-C:1), BC=0.13/1.00 (D-E:4),
WB=0.00/1.00 (B-E:1), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.27 (B) (INPUT = 0.90)
JSI METAL = 0.11 (B) (INPUT = 1.00)

NOTES:
1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111061

JOB NAME 418649	TRUSS NAME J5	QUANTITY 7	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
---------------------------	-------------------------	----------------------	-----------------	--	----------

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:30 2023 Page 1
ID:UaoF4umx8QMx1bo7Q0Zq7Cya5EO-Lsj6RtRuzUnEvDCO6sb5VpjMQAnKVAEYyUyhYnyJlQN



Scale = 1:18.7

TOTAL WEIGHT = 7 X 10 = 69 lb

LUMBER	CHORDS	SIZE	DRY	LUMBER	DESCR.
N. L. G. A. RULES	F - B	2x4	DRY	No.2	SPF
	A - C	2x4	DRY	No.2	SPF
	F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
B	TMW+p	MT20	4.0	6.0	Edge	
E	BMW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	JT VERT	JT IN-SX	JT IN-SX
F 383	383	0	1-8
C 46	46	-60	1-8
D 17	19	0	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS	WIND	DEAD	SOIL
JT COMBINED	JT COMBINED	JT COMBINED	JT COMBINED	JT COMBINED
F 263	215/0	0/0	48/0	0/0
C 32	27/-41	0/0	4/0	0/0
D 14	0/0	0/0	14/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	LC2 MAX	MAX. UNBRACED LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
FR-TO							FR-TO			
F-B	-365/0	0.0	0.0	0.04 (1)	7.81	10.00	B-E	0/0	0.00 (1)	10.00
A-B	0/58	-129.7	-129.7	0.18 (1)	10.00	6.25				
B-C	-45/0	-129.7	-129.7	0.17 (1)	6.25					
F-E	0/0	-18.5	-18.5	0.02 (4)	10.00					
E-D	0/0	-18.5	-18.5	0.01 (4)	10.00					

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.18/1.00 (A-B:1), BC=0.02/1.00 (E-F:4), WB=0.00/1.00 (B-E:1), SSI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES	PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.23 (B) (INPUT = 0.90)
JSI METAL= 0.10 (B) (INPUT = 1.00)

NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23111062

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	BAYVIEW WELLINGTON	DRWG NO.
418649	J6	7	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:31 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-p3HUeDRWkov5ZNnafZ6K11GV0a7ZEdUht8hF4DyJlQM

Scale = 1:27.3



TOTAL WEIGHT = $7 \times 13 = 90 \text{ lb}$

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR
F - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ UPLIFT	IN-SX	IN-SX
F	443	0	443	0 0	5-8	1-8
C	246	0	246	0 0	1-8	1-8
D	17	0	19	0 0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST CASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	304	251/ 0	0/ 0	0/ 0	0/ 0	53/ 0	0/ 0
C	168	145/ 0	0/ 0	0/ 0	0/ 0	23/ 0	0/ 0
D	14	0/ 0	0/ 0	0/ 0	0/ 0	14/ 0	0/ 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING


TOTAL LOAD CASES: (5)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM	TO			FR-TO			
F-B	-425 / 0	0.0	0.0	0.05 (1)	7.81	B-E	0 / 0	0.00 (1)	
A-B	0 / 58	-129.7	-129.7	0.18 (1)	10.00				
B-C	0 / 0	-129.7	-129.7	0.32 (1)	10.00				
F-E	0 / 0	-18.5	-18.5	0.02 (4)	10.00				
E-D	0 / 0	-18.5	-18.5	0.01 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111063

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL =	38.3	PSF
		DL =	6.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.4	PSF
TOTAL LOAD		=	51.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.32/1.00 (B-C:1), BC=0.02/1.00 (E-F:4),
WB=0.00/1.00 (B-E:1), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)	(PLI)	(PSI)	(PLI)	(PSI)	(PLI)
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.27 (B) (INPUT = 0.90)
JSI METAL= 0.11 (B) (INPUT = 1.00)

JOB NAME 418649	TRUSS NAME J7	QUANTITY 5	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.630 S Aug 30 2023 MITek Industries, Inc. Tue Nov 14 11:14:32 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-IFrssZS8V61yBXLmDHeZaEphe Qtz4kq5oRocfyJQL



TOTAL WEIGHT = 5 X 14 = 72 lb

LUMBER				DESCR.	
N.L.G.A. RULES	CHORDS	SIZE	LUMBER	SPF	SPF
F - B	2x4	DRY	No.2	SPF	SPF
A - C	2x4	DRY	No.2	SPF	SPF
F - D	2x4	DRY	No.2	SPF	SPF
ALL WEBS	2x3	DRY	No.2	SPF	SPF
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW+p	MT20	4.0	6.0	Edge	
E	BMW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	GROSS REACTION	HORZ	GROSS REACTION	HORZ	BRG	IN-SX	BRG	IN-SX
F	420	0	420	0	0	5-8	1-8	1-8	1-8
C	46	0	46	0	0	1-8	1-8	1-8	1-8
D	64	0	61	0	0	1-8	1-8	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	293	215 / 0	0 / 0	0 / 0	0 / 0	77 / 0	0 / 0
C	32	27 / 0	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
D	43	0 / 0	0 / 0	0 / 0	0 / 0	43 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO		FR-TO		
F-B	-365 / 0	0.0	0.0	0.04 (1)	7.81	B-E	0 / 0
A-B	0 / 58	-129.7	-129.7	0.20 (1)	10.00		0.00 (1)
B-C	-45 / 0	-129.7	-129.7	0.19 (1)	6.25		
F-E	0 / 0	-18.5	-18.5	0.16 (4)	10.00		
E-G	0 / 0	-18.5	-18.5	0.21 (4)	10.00		
G-H	0 / 0	-18.5	-18.5	0.21 (4)	10.00		
H-D	0 / 0	-18.5	-18.5	0.21 (4)	10.00		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-11-4	1	1	---	BACK	VERT	TOTAL	---	C1
H	3-11-4	1	1	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	38.3	PSF
DL =	6.0	PSF	
BOT CH.	LL =	0.0	PSF
DL =	7.4	PSF	
TOTAL LOAD =	51.8	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/999 (0.05")

CS1: TC=0.20/1.00 (A-B:1), BC=0.21/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.12/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.23 (B) (INPUT = 0.90)
JSI METAL = 0.10 (B) (INPUT = 1.00)


NOTES-
1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111064

JOB NAME 418649	TRUSS NAME J8	QUANTITY 6	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:33 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-mRPE3vTmGP9ophwn 9o7SLrWOnOIX KSAL96yJlQK



Scale = 1:26.6

TOTAL WEIGHT = 6 X 17 = 104 lb [M]

LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
F - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
F - D	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)					
JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	6.0	Edge	
E BMW+w	MT20	2.0	4.0		
F BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
F	480	0	480	0	5-8	1-8
C	246	0	246	0	1-8	1-8
D	54	0	61	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX/MIN. COMPONENT REACTIONS		WIND DEAD SOIL	DEAD SOIL
	SNOW	LIVE	PERM. LIVE	WIND		
F	334	251/0	0/0	0/0	83/0	0/0
C	168	145/0	0/0	0/0	23/0	0/0
D	43	0/0	0/0	0/0	43/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MEMB. FORCE (LBS)	MAX. CSI (LC)	MAX. FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO		FR-TO			
F-B	-425/0	0.0	0.0	0.05 (1)	7.81	0/0	0.00 (1)	
A-B	0/58	-129.7	-129.7	0.18 (1)	10.00			
B-C	0/0	-129.7	-129.7	0.32 (1)	10.00			
F-E	0/0	-18.5	-18.5	0.14 (4)	10.00			
E-D	0/0	-18.5	-18.5	0.19 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 38.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 51.6 PSF

SPACING = 24.0 IN./C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.32/1.00 (B-C:1), BC=0.19/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.27 (B) (INPUT = 0.90)
JSI METAL= 0.11 (B) (INPUT = 1.00)


NOTES:
1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111065

JOB NAME 418649	TRUSS NAME J9	QUANTITY 1	PLY 1	JOB DESC. BAYVIEW WELLINGTON	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Aug 30 2023 MiTek Industries, Inc. Tue Nov 14 11:14:34 2023 Page 1
ID:UaoF4umx8QMX1bo7Q0Zg7Cya5EO-EezdHFU01JHfQqV9Lhg1ffu18o6LR D7Z5wvhYyJlQJ



Scale = 1:18.2

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	6.0	Edge
E	BMW+w	MT20	2.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
F	420	0	420	0	0	5-8	1-8	1-8	1-8
C	46	0	46	0	0	1-8	1-8	1-8	1-8
D	54	0	61	0	0	1-8	1-8	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE		SNOW		LIVE		PERM. LIVE		WIND		DEAD		SOIL	
JT	COMBINED	215/0	0/0	0/0	0/0	0/0	0/0	0/0	0/0	77/0	0/0	0/0	0/0
F	293	215/0	0/0	0/0	0/0	0/0	0/0	0/0	0/0	4/0	0/0	0/0	0/0
C	32	27/0	0/0	0/0	0/0	0/0	0/0	0/0	0/0	43/0	0/0	0/0	0/0
D	43	0/0	0/0	0/0	0/0	0/0	0/0	0/0	0/0	43/0	0/0	0/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED FORCE		FACTORED VERT. LOAD		MAX. FACTORED LC1		MAX. FACTORED UNBRAC LENGTH		WEBS		MAX. FACTORED FORCE		MAX. FACTORED LC1	
MEMB.	FR-TO	(LBS)	(PLF)	FROM	TO	CS1 (LC)	CS1 (LC)	FR-TO	FR-TO	MEMB.	FR-TO	(LBS)	(PLF)	CS1 (LC)	CS1 (LC)
F-B	-365/0	0.0	0.0	0.0	0.0	0.04 (1)	7.81	B-E	0/0	0/0	0.00 (1)	0/0	0.00 (1)	0/0	0.00 (1)
A-B	0/58	-129.7	-129.7	0.20 (1)	10.00										
B-C	-45/0	-129.7	-129.7	0.19 (1)	6.25										
F-E	0/0	-18.5	-18.5	0.16 (4)	10.00										
E-G	0/0	-18.5	-18.5	0.21 (4)	10.00										
G-H	0/0	-18.5	-18.5	0.21 (4)	10.00										
H-D	0/0	-18.5	-18.5	0.21 (4)	10.00										

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-11-4	1	1	1	FRONT	VERT	TOTAL	—	C1
H	3-11-4	1	1	1	FRONT	VERT	TOTAL	—	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	38.3	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	51.6	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 54.4 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 38.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/999 (0.05")

CS1: TC=0.20/1.00 (A-B:1), BC=0.21/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SS=0.12/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.23 (B) (INPUT = 0.90)

JSI METAL= 0.10 (B) (INPUT = 1.00)

NOTES-

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23111066





Client: BAYVIEW WELLINGTON
Project: ALCONA SHORES
Address: INNISFIL

Date: 11/14/23
Input by:
Job Name: S45-4C
Project #: 418649

Page 1 of 3

B1 S-P-F #2 2.000" X 10.000" 2-Ply - PASSED

Level: Level



Member Information

Type: Girder
Plies: 2
Moisture Condition: Dry
Deflection LL: 360
Deflection TL: 360
Importance: Normal - II

Application: Roof (Residential)
Slope: 0/12
Design Method: LSD
Building Code: NBCC 2015
OBC 2012(2020 Update)
Load Sharing: No
Deck: Not Checked
Vibration: Not Checked

Unfactored Reactions UNPATTERNED lb (Uplift)

Brg	Direction	Live	Dead	Snow	Wind
1	Vertical	0	299	1028	0
2	Vertical	0	186	646	0

Bearings and Factored Reactions


Bearing	Length	Dir.	Cap.	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF	5.500"	Vert	19%	374 / 1543	1917	L	1.25D+1.5S
2 - SPF	5.500"	Vert	12%	233 / 969	1202	L	1.25D+1.5S

Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	1918 ft-lb	2'5 11/16"	6039 ft-lb	0.318 (32%)	1.25D+1.5S	L
Unbraced	1918 ft-lb	2'5 11/16"	5102 ft-lb	0.376 (38%)	1.25D+1.5S	L
Shear	1542 lb	1'2 3/4"	3984 lb	0.387 (39%)	1.25D+1.5S	L
LL Defl inch	0.022 (L/3119)	3' 7/8"	0.188 (L/360)	0.115 (12%)	S	L
TL Defl inch	0.028 (L/2418)	3' 7/8"	0.188 (L/360)	0.149 (15%)	D+S	L

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 3 rows of Pneumatic Gun Nail (.120x3.25") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Concentrated load fastener specification is in addition to hanger fasteners if a hanger is present.
- 5 Girders are designed to be supported on the bottom edge only.
- 6 Top loads must be supported equally by all plies.
- 7 Unsupported length L_u based on points of zero moments.
- 8 Top must be laterally braced at end bearings.
- 9 Bottom must be laterally braced at end bearings.
- 10 Lateral slenderness ratio based on single ply width.



STRUCTURAL COMPONENT ONLY
DWG# TR2311121 PG 1/3

Manufacturer Info

Tamarack Lumber
(905) 335-1115



This design is valid until 6/28/26




Client: BAYVIEW WELLINGTON
Project: ALCONA SHORES
Address: INNISFIL

Date: 11/14/23
Input by:
Job Name: S45-4C
Project #: 418649


Page 2 of 3

B1 S-P-F #2 2.000" X 10.000" 2-Ply - PASSED

Level: Level



ID	Load Type	Location	Trib Width	Side	Dead	Live	Snow	Wind	Comments
1	Uniform			Top	47 PLF	0 PLF	164 PLF	0 PLF	JACKS
2	Point	1-5-12		Far Face	184 lb	0 lb	622 lb	0 lb	T18C



STRUCTURAL COMPONENT ONLY
DWG# TR2311121 PG 2/3

Manufacturer Info

Tamarack Lumber
(905) 335-1115



This design is valid until 6/28/26




Client: BAYVIEW WELLINGTON
Project: ALCONA SHORES
Address: INNISFIL

Date: 11/14/23
Input by:
Job Name: S45-4C
Project #: 418649

Page 3 of 3

B1 S-P-F #2 2.000" X 10.000" 2-Ply - PASSED

Level: Level



Multi-Ply Analysis

Fasten all plies using 3 rows of Pneumatic Gun Nail (.120x3.25") at 12" o.c.. except for regions covered by concentrated load fastening. Maximum end distance not to exceed 6".



Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	340.0 PLF
Yield Limit per Fastener	113.3 lb.
Yield Mode	g
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

Concentrated Load

Fasten at concentrated side load at 1-5-12 with a minimum of (6) – Pneumatic Gun Nail (.120x3.25") in the pattern shown.

Capacity	85.5 %
Load	581.5 lb.
Total Yield Limit	680.1 lb.
Yield Limit per Fastener	113.3 lb.
Yield Mode	g
Load Combination	1.25D+1.5S
Duration Factor	1.00

Min/Max fastener distances for Concentrated Side Loads



STRUCTURAL COMPONENT ONLY
DWG# TR2311121 PG 3/3

Manufacturer Info

Tamarack Lumber
(905) 335-1115



This design is valid until 6/28/26

THGQ/THGQH — Truss Girder Hangers

SIMPSON
Strong-Tie

Material: THGQ—7 gauge, THGQH—3 gauge

Finish: THGQ—G90 Galvanized,
THGQH—Simpson Strong-Tie® gray paint

Design:


- Factored resistances are in accordance with CSA O86-14 and CSA O86:19.
- Uplift resistances have been increased 15% for short-term load duration. No further increase is allowed.
- Designer must ensure that vertical web member supporting a hanger is capable of resisting loads based on net cross section.
- Girder truss must be a minimum of two plies.
- Bearing assumes Q_r/A_b and $Q_r/A'_b = 812$ psi D.Fir-L and 615 psi S-P-F. Truss plates on supported member must be as per 6.5.4 and 7.5.9 TPIC (2014 or 2019 as applicable) to achieve values shown.
- All multiple members must be fastened together to act as a single unit independent of the hanger fasteners.
- Girders must be adequately laterally braced to prevent excessive displacement due to secondary torsional stresses.

Installation:


- Use all specified fasteners.
- Fill all round holes for minimum values and all round and triangle holes for maximum values.
- Strong-Drive® SDS screws driven through truss plates must be approved by the truss designer. Predrilling, using a $\frac{5}{32}$ " bit, is required.
- Connector must be installed, centred on girder vertical web.

Options:


- These hangers may be skewed 45°
- See current catalogue for options




THGQ2-SDS3
(THGQ3-SDS3 similar)




THGQH2-SDS3



THGQH3-SDS4.5
(THGQH4-SDS6 similar)



Typical THGQH3-SDS4.5 Installation



Typical THGQ2-SDS3 Installation

Model No.	Width (in.)	Max. B.C. Depth	Min. Vert. Web Size	Fasteners		Factored Resistance (lb.)			
						D.Fir-L		S-P-F	
				Header	Joist	Uplift ($K_p=1.15$)	Normal ($K_p=1.00$)	Uplift ($K_p=1.15$)	Normal ($K_p=1.00$)
THGQ2-SDS3 (Min.)	$3\frac{5}{16}$	2x6	2x8	(22) SDS $\frac{1}{4}$ " x 3"	(10) SDS $\frac{1}{4}$ " x 3"	5205	11655	3750	8395
THGQ2-SDS3 (Max.)	$3\frac{5}{16}$	2x6	2x10	(28) SDS $\frac{1}{4}$ " x 3"	(14) SDS $\frac{1}{4}$ " x 3"	6555	18055	4720	13000
THGQH2-SDS3 (Min.)	$3\frac{5}{16}$	2x10	2x8	(18) SDS $\frac{1}{4}$ " x 3"	(14) SDS $\frac{1}{4}$ " x 3"	5790	12555	4170	9040
THGQH2-SDS3 (Max.)	$3\frac{5}{16}$	2x10	2x10	(28) SDS $\frac{1}{4}$ " x 3"	(26) SDS $\frac{1}{4}$ " x 3"	14190	18455	10215	15160
THGQ3-SDS4.5 (Min.)	$4\frac{15}{16}$	2x6	2x8	(22) SDS $\frac{1}{4}$ " x $4\frac{1}{2}$ "	(10) SDS $\frac{1}{4}$ " x $4\frac{1}{2}$ "	5205	11655	3750	8395
THGQ3-SDS4.5 (Max.)	$4\frac{15}{16}$	2x6	2x10	(28) SDS $\frac{1}{4}$ " x $4\frac{1}{2}$ "	(14) SDS $\frac{1}{4}$ " x $4\frac{1}{2}$ "	6555	17760	4720	12785
THGQH3-SDS4.5 (Min.)	$4\frac{15}{16}$	2x10	2x10	(32) SDS $\frac{1}{4}$ " x $4\frac{1}{2}$ "	(14) SDS $\frac{1}{4}$ " x $4\frac{1}{2}$ "	5790	17860	4170	12860
THGQH3-SDS4.5 (Max.)	$4\frac{15}{16}$	2x10	2x12	(38) SDS $\frac{1}{4}$ " x $4\frac{1}{2}$ "	(26) SDS $\frac{1}{4}$ " x $4\frac{1}{2}$ "	14190	21055	10215	15160
THGQH4-SDS6 (Min.)	$6\frac{1}{16}$	2x12	2x10	(34) SDS $\frac{1}{4}$ " x 6"	(14) SDS $\frac{1}{4}$ " x 6"	5790	17860	4170	12860
THGQH4-SDS6 (Max.)	$6\frac{1}{16}$	2x12	2x12	(40) SDS $\frac{1}{4}$ " x 6"	(26) SDS $\frac{1}{4}$ " x 6"	14190	24870	10215	17905

1. Factored resistances have been increased 15% for earthquake or wind load with no further increase allowed; reduce where other loads govern.
2. Minimum 2-ply girder required.
3. Connector must be installed centred on girder vertical webs.

4. The thickness of the supporting girder must be equal to or greater than the screw length. For applications where the length of the supplied screws exceeds the thickness of the supporting girder, 3" or $4\frac{1}{2}$ " screws may be substituted for the longer length screws with no load reduction, or a shim block may be used as approved by the designer.



This document is the property of Simpson Strong-Tie Company. It is to be used for the project and location only. It is not to be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Simpson Strong-Tie Company. This information is subject to change without notice and should not be relied upon after December 31, 2024. Contact Simpson Strong-Tie Company for more information and to request a copy of the current catalogue.

©2022 Simpson Strong-Tie Company, Inc. 3700 Deerpark Drive, Dayton, OH 45424-1099 TSPQTHGQ22 7/22 535 10/24

(800) 999-5099
strongtie.com

HGUS — Double-Shear Joist Hangers

SIMPSON
Strong-Tie

All HGUS hangers have double-shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: 12 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14 and CSA O86:19.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia x 3½" long common wire
- Double-shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:


- See current catalogue for options



HGUS28-2




Typical HGUS Installation



Typical HGUS Installation
(Truss designer to provide fastener quantity for connecting multiple members together)


Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d ₀ ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _p =1.15)	Normal (K _p =1.00)	Uplift (K _p =1.15)	Normal (K _p =1.00)
HGUS26	12	1½	5½	5	4½ ₃₂	(20) 16d	(8) 16d	2685	6625	2685	5700
HGUS26-2	12	3½ ₁₆	5½ ₁₆	4	4½	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-3	12	4½ ₁₆	5½	4	4½	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-4	12	6½ ₁₆	5½ ₁₆	4	4½	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS28	12	1½	7½	5	6½	(36) 16d	(12) 16d	3310	7675	3100	6900
HGUS28-2	12	3½ ₁₆	7½ ₁₆	4	6½	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-3	12	4½ ₁₆	7½	4	6½	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-4	12	6½ ₁₆	7½ ₁₆	4	6½	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS210-2	12	3½ ₁₆	9½ ₁₆	4	8½	(46) 16d	(16) 16d	6840	14015	4855	10270
HGUS210-3	12	4½ ₁₆	9½	4	8½	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS210-4	12	6½ ₁₆	9½ ₁₆	4	8½	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS212-4	12	6½ ₁₆	10½	4	10½	(56) 16d	(20) 16d	7640	14995	5425	10645
HGUS214-4	12	6½ ₁₆	12½	4	11½	(66) 16d	(22) 16d	10130	16400	7195	11645

1. d₀ is the distance from the seat of the hanger to the highest joist nail.




Dome double-shear nailing prevents tabs breaking off (available on some models).

US Patent 5,603,580¹



Double-shear nailing side view. Do not bend tab back.



Double-shear nailing top view.



This notice becomes effective on December 31, 2022, and related information available on July 1, 2022.

This information is updated periodically and should not be relied upon after December 31, 2024.

Consult the Simpson Strong-Tie website for current information and technical details at www.simpsonstrongtie.com.

© 2022 Simpson Strong-Tie Company Inc. 11001 E. 15th, Prescott, CA 94364

T-SPEC-HGUS22 7/22 6/11/24

(800) 999-5099
strongtie.com

LUS — Double-Shear Joist Hangers

SIMPSON
Strong-Tie

All LUS hangers have double-shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections.

Material: 18 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14 and CSA O86:19.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia. x 3½" long common wire,
10d = 0.148" x 3" long common wire
- Double-shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:

- These hangers cannot be modified




Typical LUS
Installation




Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _e ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _p =1.15)	Normal (K _p =1.00)	Uplift (K _p =1.15)	Normal (K _p =1.00)
LUS24	18	1⅞	3⅞	1¾	1⅞	(4) 10d	(2) 10d	710	1630	645	1155
LUS24-2	18	3⅞	3⅞	2	1⅞	(4) 16d	(2) 16d	835	2020	590	1435
LUS26	18	1⅞	4¾	1¾	3⅞	(4) 10d	(4) 10d	1420	2170	1290	1630
LUS26-2	18	3⅞	4¾	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920
LUS26-3	18	4¾	4¾	2	3¼	(4) 16d	(4) 16d	1720	2595	1545	2340
LUS28	18	1⅞	6⅞	1¾	3¾	(6) 10d	(6) 10d	1420	2520	1290	1790
LUS28-2	18	3⅞	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575
LUS28-3	18	4¾	6¼	2	3¼	(6) 16d	(4) 16d	1720	3325	1545	2375
LUS210	18	1⅞	7⅞	1¾	3⅞	(8) 10d	(4) 10d	1420	2785	1290	2210
LUS210-2	18	3⅞	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195
LUS210-3	18	4¾	8⅞	2	5¼	(8) 16d	(6) 16d	2580	3345	2320	2375

1. d_e is the distance from the seat of the hanger to the highest joist nail.



Dome double-shear nailing prevents tabs breaking off (available on some models).

US Patent
5,603,580



Double-shear nailing top view.



This document is the property of Simpson Strong-Tie Company. It is to be used for informational purposes only. It is not to be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Simpson Strong-Tie Company. © 2022 Simpson Strong-Tie Company. All rights reserved.

2022 Simpson Strong-Tie Company, Inc. P.O. Box 10709, Vancouver, BC V6T 1A1, Canada TS-EQLUS22 7/22 5/11/22

(800) 999-5099
strongtie.com

HGUS — Double-Shear Joist Hangers

SIMPSON
Strong-Tie

All HGUS hangers have double-shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: 12 gauge

Finish: G90 galvanized

Design:



- Factored resistances are in accordance with CSA O86-14 and CSA O86:19.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia x 3 1/2" long common wire
- Double-shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:

- See current catalogue for options




Typical HGUS Installation




Typical HGUS Installation
(Truss designer to provide fastener quantity for connecting multiple members together)

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _e ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K ₀ =1.15)	(K ₀ =1.00)	(K ₀ =1.15)	(K ₀ =1.00)
HGUS26	12	1 1/8	5 1/8	5	4 5/32	(20) 16d	(8) 16d	2685	6625	2685	5700
HGUS26-2	12	3 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-3	12	4 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-4	12	6 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS28	12	1 1/8	7 1/8	5	6 1/8	(36) 16d	(12) 16d	3310	7675	3100	6900
HGUS28-2	12	3 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-3	12	4 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-4	12	6 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS210-2	12	3 1/8	9 1/8	4	8 1/8	(46) 16d	(16) 16d	6840	14015	4855	10270
HGUS210-3	12	4 1/8	9 1/8	4	8 1/8	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS210-4	12	6 1/8	9 1/8	4	8 1/8	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS212-4	12	6 1/8	10 1/8	4	10 1/8	(56) 16d	(20) 16d	7640	14995	5425	10645
HGUS214-4	12	6 1/8	12 1/8	4	11 1/8	(66) 16d	(22) 16d	10130	16400	7195	11645


1. d_e is the distance from the seat of the hanger to the highest joist nail.



Dome double-shear nailing prevents tabs breaking off (available on some models).
US Patent 5,603,580



Double-shear nailing side view. Do not bend tab back.



Double-shear nailing top view.



This document is copyrighted by Simpson Strong-Tie Company, Inc. and is the property of Simpson Strong-Tie Company, Inc. It is to be used for informational purposes only and should not be used for design or construction purposes. All rights reserved. © 2022 Simpson Strong-Tie Company, Inc. All other trademarks are the property of their respective owners.

© 2022 Simpson Strong-Tie Company, Inc. • PO Box 10750 • Los Angeles, CA 90046 • TSPCHGUS-2 7/22 5x8 1/2" 1/2"

(800) 999-5099
strongtie.com



EWP DESIGN INC.

(905) 832-2250

FAX (905) 832-0286

RESPONSIBILITIES AND SPECIFICATIONS

RESPONSIBILITIES

1. EWP DESIGN INC. is responsible for the design of trusses as individual components.
2. It is the responsibility of others to ascertain that the design loads utilized on each drawing meet or exceed the actual dead load imposed by the structure, the live load imposed by the intended use and the snow load imposed by local building code or authorities with jurisdictions.
3. All dimensions are to be verified by the owner, contractor, architect or other authorities with jurisdictions before truss fabrication.
4. EWP DESIGN INC. bears no responsibility for the erection of trusses. Persons erecting trusses are cautioned to seek professional advice regarding the temporary and permanent bracing for the system. Bracing shown on EWP DESIGN INC. drawing is specified for the truss as a component only and forms an integral part of the truss design.
5. It is the truss manufacturer's responsibility to ensure that trusses are manufactured in conformance with specifications of EWP DESIGN INC. as outlined below.

SPECIFICATIONS

1. Trusses designed by EWP DESIGN INC. conform to the relevant section of the Ontario Building Code of Canada (Part 9 or Part 4) or to the Canadian code for farm buildings, whichever applies to the building type, as indicated on the EWP DESIGN INC. drawings, and conform to the design procedures established by the Truss Plate Institute of Canada. Unit stresses used for truss designs are as per the edition of CSA-O86 shown on EWP DESIGN INC. drawings.
2. Lumber is to be the size, species and grade as specified on EWP DESIGN INC. drawings.
3. Moisture content of lumber shall not exceed 19% in service unless specified otherwise.
4. Metal connector plates shall be applied to both faces of truss at each joint and shall be positioned as specified.
5. Top chords of trusses are assumed to be continuously braced laterally by roof sheathing or by purlins at intervals not exceeding 12.5 times the thickness of top chord member.
6. Bottom chords shall be laterally braced at intervals not exceeding 3M (10') o.c., where rigid ceiling is not applied directly to the underside of chords.


THESE DRAWINGS CONSTITUTE THE PROPERTY OF EWP DESIGN INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY THE ALPA LUMBER GROUP, AND WILL BE RETRACTED BY EWP DESIGN INC. IF UTILIZED FOR ANY OTHER PURPOSE.

February 1, 2019

Symbols

PLATE LOCATION AND ORIENTATION

Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths or mm. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0-1/8" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

*Plate location details available in Mitek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.

Industry Standards:

TPIC: Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths or mm (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

CCMC Reports:

11996-L, 10319-L, 13270-L, 12691-R

© 2007 Mitek® All Rights Reserved

Mitek
POWER TO PERFORM.™

Mitek Engineering Reference Sheet: MII-7473C rev. 10-08

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSJ.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by TPIC.
7. Design assumes trusses will be suitably protected from the environment in accord with TPIC.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with TPIC Quality Criteria.