




Drawing List:

- A0 TITLE SHEET
- A1 BASEMENT FLOOR ELEV 'A'
- A2 GROUND FLOOR ELEV 'A'
- A3 SECOND FLOOR ELEV 'A'
- A4 FRONT ELEVATION 'A'
- ROOF PLAN ELEV 'A'
- A5 RIGHT SIDE ELEVATION 'A'
- A6 REAR ELEVATION 'A'
- A7 LEFT SIDE ELEVATION 'A'
- D1 CONSTRUCTION NOTES
- D2 CONSTRUCTION NOTES
- D3 CONSTRUCTION NOTES

ONE COPY OF THE CERTIFIED
PLAN OR FACSIMILE TO BE MAINTAINED
ON SITE AND READILY AVAILABLE

NOTICE REQUIREMENTS FOR INSPECTIONS

The owner or an authorized agent shall notify the Chief Official at least two (2) business days prior to each stage of construction for which notice in advance is required under the Building Code as amended from time to time.

[Signature]

MUNICIPALITY OF CLARINGTON
CERTIFIED COPY
FORMING PART OF BUILDING
PERMIT DRAWINGS

It is the builder's complete responsibility to ensure that all plans and specifications fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or building codes with respect to any zoning or building code requirements. The Control Architect's office is not responsible for ensuring that a house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Municipality of CLARINGTON.

Areas:

ELEVATION 'A'		
	SF	SM
GROUND FLOOR	982.0	91.2
SECOND FLOOR	1120.6	104.1
SECOND FLOOR OTB	(5.3)	(0.5)
TOTAL AREA	2097.3	194.8
COVERAGE INC PORCH	1303.6	121.1
COVERAGE NOT INC PORCH	1209.5	112.4


Esquire Homes
North Glen Phase 4
Darlington

I, ERIC SCHNEIDER DECLARE THAT I HAVE REVIEWED AND TAKEN DESIGN RESPONSIBILITY FOR THE DESIGN WORK ON BEHALF OF **RN DESIGN LTD** UNDER DIVISION C PART 3 SUBSECTION 3.2.4 OF THE BUILDING CODE. I AM QUALIFIED AND THE FIRM IS REGISTERED IN THE APPROPRIATE CLASSES / CATEGORIES.
QUALIFIED DESIGNER BCIN: 30840
FIRM BCIN: 26975
DATE: 03-APR-2020
[Signature]
SIGNATURE:

client		Esquire Homes	
project		North Glen Phase 4	
#	revisions	date	dwn
1	ISSUED FOR CLIENT REVIEW	30-May-19	ES
2	REVISED PER FLOOR/TRUSS COORD	11-Mar-20	ES
3	REVISED PER ENGINEER COMMENTS & ISSUED FOR PERMIT	03-APR-20	KC

model	33-1	project #	19025
scale	3/16" = 1'0"		
page			

A0



It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable zoning provisions and requirements in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Municipality of CLARINGTON.

JOHN G. WILLIAMS LTD., ARCHITECT
ARCHITECTURAL CONTROL REVIEW
AND APPROVAL
APPROVED BY: [Signature]
DATE: APR 07, 2020
This stamp certifies compliance with the applicable Design Guidelines only and bears no further professional responsibility.

MUNICIPALITY OF CLARINGTON
CERTIFIED COPY
FORMING PART OF BUILDING
PERMIT DRAWINGS

client Esquire Homes
project North Glen Phase 4
location
marketing name ABR Darlington


#	revisions	date	down	chk	#	revisions	date	down	chk
1	ISSUED FOR CLIENT REVIEW	30-MAY-19	ES						
2	REVISED PER FLOOR/TRUSS COORD	11-MAY-20	ES						
3	REVISED PER ENGINEER COMMENTS & ISSUED FOR PERMIT	03-APR-20	AC	ES					

I, ERIC SCHNEIDER DECLARE THAT I HAVE REVIEWED AND TAKEN DESIGN RESPONSIBILITY FOR THE DESIGN WORK ON BEHALF OF **RN DESIGN LTD** UNDER DIVISION C PART 3 SUBSECTION 3.2.4 OF THE BUILDING CODE. I AM QUALIFIED AND THE FIRM IS REGISTERED IN THE APPROPRIATE CLASSES / CATEGORIES.


QUALIFIED DESIGNER BCIN: 30840
FIRM BCIN: 26995
DATE: 03-APR-2020

SIGNATURE:

[Signature]



WWW.RNDESIGN.COM
Tel: 905-738-3177
WWW.THEPLUSGROUP.CA



GROUND FLOOR ELEV 'A'

NOTE: ELECTRICAL, GAS AND VENT LOCATIONS ARE SCHEMATIC ONLY. TO BE COORDINATED WITH ELECTRICAL AND MECHANICAL DRAWINGS BY THE CONTRACTOR

NOTE: REFER TO FLOOR JOIST DRAWINGS FOR APPROVED FLOOR JOIST LAYOUT AND SPACING

NOTE: REFER TO TRUSS DRAWINGS FOR APPROVED TRUSS LAYOUT

NOTE: CONC FRONT PORCH POURED PRIOR TO BRICK

NOTE: STEEL BEAM SUPPORTING FLOOR ABOVE TO BE DROPPED UNLESS NOTED OTHERWISE

It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements of the City of Clarington. The Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Municipality of CLARINGTON.

JOHN G. WILLIAMS LTD., ARCHITECT
ARCHITECTURAL CONTROL REVIEW
AND APPROVAL
APPROVED BY: [Signature]
DATE: APR 07, 2020
This stamp certifies compliance with the applicable Design Guidelines only and bears no further professional responsibility.

MUNICIPALITY OF CLARINGTON
CERTIFIED COPY
FORMING PART OF BUILDING
PERMIT DRAWINGS

PROFESSIONAL ENGINEER
J. G. ALVAREZ
102014508

model 33-1
scale 3/16" = 10"
project # 19025

page

A2

client Esquire Homes

project North Glen Phase 4

location

marketing name Darlington

#	revisions	date	dwn	chk	#	revisions	date	dwn	chk
1	ISSUED FOR CLIENT REVIEW	30-May-19	ES	ES					
2	REVISED PER FLOOR/TRUSS COORD	11-May-20	ES	ES					
3	REVISED PER ENGINEER COMMENTS & ISSUED FOR PERMIT	03-APR-20	KC	ES					


I, ERIC SCHNEIDER DECLARE THAT I HAVE REVIEWED AND TAKEN DESIGN RESPONSIBILITY FOR THE DESIGN WORK ON BEHALF OF RN DESIGN LTD. UNDER DIVISION C.PART-3 SUBSECTION-3.2.4 OF THE BUILDING CODE. I AM QUALIFIED AND THE FIRM IS REGISTERED IN THE APPROPRIATE CLASSES / CATEGORIES.

QUALIFIED DESIGNER BCIN: 30840
FIRM BCIN: 26995
DATE: 03-APR-2020

SIGNATURE:

[Signature]

WWW.RNDESIGN.COM
Tel: 905-738-3177
WWW.THEPLUSGROUP.CA



NOTE: REFER TO TRUSS DRAWINGS
FOR APPROVED TRUSS LAYOUT

SECOND FLOOR ELEV 'A'

It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements in the subdividing jurisdiction. The Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Municipality of CLARINGTON.

JOHN G. WILLIAMS LTD., ARCHITECT
ARCHITECTURAL CONTROL REVIEW
AND APPROVAL

APPROVED BY:
DATE: APR 02, 2020

This stamp certifies compliance with the applicable Design Guidelines only and bears no further professional responsibility.

MUNICIPALITY OF CLARINGTON
CERTIFIED COPY
FORMING PART OF BUILDING
PERMIT DRAWINGS

I, ERIC SCHNEIDER DECLARE THAT I HAVE REVIEWED AND TAKEN DESIGN RESPONSIBILITY FOR THE DESIGN WORK ON BEHALF OF **BN DESIGN LTD.** UNDER DIVISION C, PART-3 SUBSECTION-3.2.4 OF THE BUILDING CODE. I AM QUALIFIED AND THE FIRM IS REGISTERED IN THE APPROPRIATE CLASSES / CATEGORIES.
QUALIFIED DESIGNER BCIN: 30840
FIRM BCIN: 26995
DATE: 03-APR-2020

SIGNATURE:

client
Esquire Homes
project
North Glen Phase 4
location
Darlington

#	revisions	date	dw	chk	#	revisions	date	dw	chk
1	ISSUED FOR CLIENT REVIEW	30-MAY-19	ES	ES					
2	REVISED PER FLOOR/TRUSS COORD	11-MAY-20	ES	ES					
3	ISSUED FOR PERMIT	03-APR-20	KC	ES					


model
33-1
scale
3/16" = 10"
project #
19025

page

A3



WWW.RNDESIGN.COM
TEL: 905-738-3177
WWW.THEPLUSGROUP.CA



ROOF PLAN ELEV 'A'

NOTE: ALL CONVENTIONAL ROOF FRAMING TO CONFORM TO PART 9 OF THE OBC. ROOF RAFTERS THAT MEET OR CROSS OVER TRUSSES ARE TO BE 2"x4" SPF @ 24" OC WITH A 2"x4" SPF VERTICAL POST TO THE TRUSS UNDER, AT EACH CROSS POINT, POSTS LONGER THAN 6' TO BE Laterally Braced so that the distance between end points & between rows of bracing does not exceed 6'.

NOTE: REFER TO TRUSS DRAWINGS FOR APPROVED TRUSS LAYOUT

NOTE: UNLESS OTHERWISE NOTED, ROOF OVERHANGS ARE 12" STANDARD

NOTE: REFER TO STREETSCAPES FOR POSSIBLE MINOR CHANGES DUE TO GRADING CONDITIONS

TOP OF LOUVER

15"x24" DECOR LOUVER
W/ 6" VINYL HEADER
& 4" VINYL SURROUND & SILL

VERTICAL BOARD & BATTEN VINYL SIDING
W/ METAL FLASHING UP BEHIND

PRE-FINISHED ALUMINUM R.W.L.
AND GUTTER ON PRE-FINISHED
FASCIA BOARD AND VENTED SOFFIT

1"x6" ALUM FREIZE BOARD (TYP)

BRICK SOLDIER COURSE HEADER
(TYP)

FACE BRICK (TYP)

PRECAST CONC SILL (TYP)

PREFIN METAL FLASHING
W/ CAULKING TO MATCH (TYP)

U/S OF GARAGE & PORCH SOFFIT

4" PRECAST CONC. BAND

STONE VENEER (TYP)

U/S OF FOOTING

STEPPED FOOTING (TYP)

3

GROSS GLAZING AREA-ELEV A

TOTAL PERIPHERAL WALL AREA	2810.50 SF	261.10 m²
FRONT GLAZING AREA	101.31 SF	9.41 m²
LEFT SIDE GLAZING AREA	42.00 SF	3.90 m²
RIGHT SIDE GLAZING AREA	75.33 SF	7.00 m²
REAR GLAZING AREA	102.33 SF	9.51 m²
TOTAL GLAZING AREA	320.97 SF	29.82 m²
TOTAL GLAZING PERCENTAGE	11.42 %	



FRONT ELEVATION 'A'

PEAK HEIGHT OF ROOF

31'-5"

MID-POINT OF ROOF

24'-8"

ASPHALT SHINGLES W/
FLASHING AT VALLEYS

31

DECOR. OPEN GABLE END DETAIL
(TYP)

CATHEDRAL CEILING BEYOND
(11:12 SLOPE)

TOP OF PLATE

TOP OF WINDOW

30"x26" GOTHIC STYLE TRANSOM
W/ SELF SUPPORTING BRICK
SOLDIER COURSE ARCH

15" WIDE DECOR VINYL
SHUTTERS (TYP)

FIN. SECOND FLOOR

TOP OF DOOR

TOP OF WINDOW @ STAIR

10"x10" VINYL COLUMN
ANCHORED TO PORCH
SLAB (TYP) 49a

TOP OF BAND

FIN. MAIN FLOOR

FIN. GRADE

POURED CONC. PORCH SLAB

POURED CONC. DOOR SILL

POURED CONC. FDTN WALLS
ON CONC. STRIP FOOTING

14 4 1

TOP OF SLAB

It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Municipality of CLARINGTON.

JOHN G. WILLIAMS LTD., ARCHITECT
ARCHITECTURAL CONTROL REVIEW
AND APPROVAL
APPROVED BY:
DATE: APR 07 2020
This stamp certifies compliance with the applicable Design Guidelines only and bears no further professional responsibility.

MUNICIPALITY OF CLARINGTON
CERTIFIED COPY
FORMING PART OF BUILDING
PERMIT DRAWINGS



client

Esquire Homes

location

North Glen Phase 4

marketing name

Darlington

model 33-1
scale 3/16" = 1'0"
project # 19025


page

A4

WWW.RNDESIGN.COM
Tel: 905-738-3177
WWW.THEPLUSGROUP.CA

I, ERIC SCHNEIDER DECLARE THAT I HAVE REVIEWED AND
TAKEN DESIGN RESPONSIBILITY FOR THE DESIGN WORK ON
BEHALF OF RN DESIGN LTD UNDER DIVISION C/PART-3
SUBSECTION-3.2.4 OF THE BUILDING CODE. I AM QUALIFIED
AND THE FIRM IS REGISTERED IN THE APPROPRIATE CLASSES /
CATEGORIES.
QUALIFIED DESIGNER BCIN: 30840
FIRM BCIN: 26995
DATE: 03-APR-2020

SIGNATURE:



MUNICIPALITY OF CLARINGTON
CERTIFIED COPY
FORMING PART OF BUILDING
PERMIT DRAWINGS


It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Municipality of CLARINGTON.

JOHN G. WILLIAMS LTD., ARCHITECT
ARCHITECTURAL CONTROL REVIEW
AND APPROVAL

APPROVED BY: 
DATE: APR 07, 2020

This stamp certifies compliance with the applicable Design Guidelines only and bears no further professional responsibility.



model 33-1
scale 3/16" = 1'0"
project # 19025
page

A6

RN DESIGN
WWW.RNDESIGN.COM
TEL: 905-738-3177
WWW.THEPLUSGROUP.CA

client

Esquire Homes

project

North Glen Phase 4

marketing name

Darlington


location

DATE OF CH

#	revisions	date	dwn	chk	#	revisions	date	dwn	chk
1	ISSUED FOR CLIENT REVIEW	30-MAY-19	ES	ES					
3	ISSUED FOR PERMIT	03-APR-20	KC	ES					

L. ERIC SCHNEIDER DECLARE THAT I HAVE REVIEWED AND TAKEN DESIGN RESPONSIBILITY FOR THE DESIGN WORK ON BEHALF OF RN DESIGN LTD. UNDER DIVISION C, PART-3 SUBSECTION 3.2.4 OF THE BUILDING CODE. I AM QUALIFIED AND THE FIRM IS REGISTERED IN THE APPROPRIATE CLASSES / CATEGORIES.

QUALIFIED DESIGNER BCIN: 30840
FIRM BCIN: 26995
DATE: 03-APR-2020

SIGNATURE: 



LEFT SIDE ELEVATION 'A'

ALLOWABLE UNPROTECTED OPENINGS					
Total Wall Area		678.85	S.F.	63.07	S.M.
Limiting Distance	3.93	FT	1.2	M	7.00
Allowable Openings		47.52	S.F.	4.41	S.M.
Actual Openings		32.23	S.F.	2.99	S.M.

MUNICIPALITY OF CLARINGTON
CERTIFIED COPY
FORMING PART OF BUILDING
PERMIT DRAWINGS

It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the Municipality of CLARINGTON.

JOHN G. WILLIAMS LTD., ARCHITECT
ARCHITECTURAL CONTROL REVIEW
AND APPROVAL
APPROVED BY: [Signature]
DATE: APR 07, 2020
This stamp certifies compliance with the applicable Design Guidelines only and bears no further professional responsibility.

model 33-1
scale 3/16" = 1'0"
project # 19025
page A7

RN DESIGN
WWW.RNDESIGN.COM
TEL: 905-738-3177
WWW.THEPLUSGROUP.CA

client

Esquire Homes

project

North Glen Phase 4

marking name

Darlington

location

#	revisions	date	dwn	chk	#	revisions	date	dwn	chk
1	ISSUED FOR CLIENT REVIEW	30-May-19	ES	ES					
3	ISSUED FOR PERMIT	03-APR-20	KC	ES					

I, ERIC SCHNEIDER DECLARE THAT I HAVE REVIEWED AND TAKEN DESIGN RESPONSIBILITY FOR THE DESIGN WORK ON BEHALF OF RN DESIGN LTD. UNDER DIVISION C, PART-3 SUBSECTION-3.2.4 OF THE BUILDING CODE. I AM QUALIFIED AND THE FIRM IS REGISTERED IN THE APPROPRIATE CLASSES / CATEGORIES.
QUALIFIED DESIGNER BCIN: 30840
FIRM BCIN: 26995
DATE: 03-APR-2020
SIGNATURE: [Signature]

36D EXTERIOR GUARDS @ JULIET BALCONY:

- FOR RAILING SPANNING MAXIMUM OF 6'-0".
- PROVIDE PREFN. METAL RAILING W/ 76mm VERTICAL OPENING TO CONFORM WITH O.B.C. APPENDIX A-9.8.8.5.
- GUARDS TO BE 3'-6" (1070mm)
- FOR DWELLING UNITS GUARDS TO BE 2'-11" (900mm) WHERE FLOOR TO GRADE DIFFERENCE IS LESS THAN 5'-11" (1800mm) AS PER O.B.C. 9.8.8.2. OR
- FOR DWELLING UNITS GUARDS TO BE 3'-6" WHERE FLOOR TO GRADE DIFFERENCE IS 5'-11" (1800mm) OR GREATER AS PER O.B.C. 9.8.8.2.
- VERTICAL END RAILING MIN. ANCHOR BOLTS EQUALLY SPACED WITH 3" MIN. EMBEDMENT TO STUDS
- PROVIDE SAME ANCHOR BOLTS @ 36" O.C. FOR BASE PLATE CONNECTION.
- LINEN CLOSET 4 SHELVES MIN. 1'-2" (350mm) DEEP
- WASHROOMS TO BE MECHANICALLY VENTED TO PROVIDE AT LEAST ONE AIR CHANGE PER HOUR, O.B.C.- 9.32.1.3.(3)
- CAPPED DRYER VENT

40 -1"x2" (19mmX38mm) BOTH SIDES OF STEEL.

- WOOD FRAMING MEMBERS SUPPORTED ON CONCRETE IN CONTACT WITH GROUND OR FILL SHALL BE PRESSURE TREATED OR SEPARATED FROM CONCRETE W/ 6 mil POLYETHYLENE.

42 -PRECAST CONC. STEP

- 2 RISERS MAXIMUM PERMITTED TO BE LAID ON GROUND

44 SMOKE ALARM. O.B.C.- 9.10.19.

- PROVIDE 1 ON EACH FLOOR INCLUDING BASEMENTS
- PROVIDE 1 IN EACH BEDROOM
- PROVIDE 1 IN EACH HALLWAY SERVICING BEDROOMS
- INSTALLED AT OR NEAR CEILING
- ALARMS TO BE CONNECTED IN CIRCUIT AND INTERCONNECTED SO ALL ALARMS WILL BE ACTIVATED IF ANY ONE OF THEM SOUNDS AND HAVE A VISUAL SIGNALLING COMPONENT
- ALARMS MUST BE HARDWIRED AND HAVE AN ALTERNATE POWER SOURCE THAT CAN POWER ALARM FOR 7 DAYS, FOLLOWED BY 4 MINUTES OF ALARM

48 CARBON MONOXIDE ALARM (CMA), O.B.C.- 9.33.4.

- WHERE THERE IS A FUEL BURNING APPLIANCE A CMA SHALL BE PROVIDED ADJACENT TO EACH SLEEPING AREA.
- CMA TO BE WIRED IN CIRCUIT TO SOUND SMOKE ALARMS WHEN ACTIVATED.

46 -MAIN DOOR TO BE OPERABLE FROM INSIDE W/OUT KEY

- PROVIDE A VIEWER WITH A VIEWING ANGLE OF NOT LESS THAN 160 DEG. UNLESS GLAZING IS PROVIDED IN DOOR OR A SIDELIGHT IS PRESENT.
- R4 (RSI 0.70) WHERE A STORM DOOR IS NOT PROVIDED

47 -GARAGE MAIN DOORS TO BE GAS PROOFED WITH SELF CLOSER.

- WEATHERSTRIPPING, THRESHOLD & DEAD BOLT PER O.B.C. 9.10.13.15.
- R4 (RSI 0.70)

49 -TRAVEL FROM A FLOOR LEVEL TO AN EXIT OR EGRESS DOOR SHALL BE LIMITED TO ONE FLOOR EXCEPT:

- 1) WHERE THAT FLOOR LEVEL HAS ACCESS TO A BALCONY OR

- 2) WHERE THAT FLOOR LEVEL HAS A WINDOW PROVIDING AN UNOBSTRUCTED OPENING OF NOT LESS THAN 3'-3" (1000mm) IN HEIGHT AND 21 5/8" (550mm) IN WIDTH; SUCH WINDOW SHALL BE LOCATED SO THAT THE SILL IS NOT MORE THAN 3'-3" (1000mm) ABOVE FLOOR AND 23'-0" (7.0m) ABOVE ADJACENT GROUND LEVEL.

49

EXTERIOR COLUMN W/ MASONRY PIER:

- MIN. 6"x6" (140mm X 140mm) WOOD POST ANCHORED TO PORCH SLAB W/ METAL SADDLE.
- TOP PORTION OF POST CLAD W/ DECOR. SURROUND PER ELEVATION DRAWINGS.
- MASONRY VENEER SURROUND W/ PRECAST CONCRETE CAP. REFER TO ELEVATION DRAWINGS FOR PIER SIZE AND CAP HEIGHT.
- SURROUND TO BE TIED W/ METAL TIES @ 16" (400mm) O.C. VERT. INSTALLED PER O.B.C. 9.20.9.4.
- OR
- MIN. 6"x6" (140mm X 140mm) WOOD POST CLAD W/ DECOR. SURROUND (PER ELEVATION DRAWINGS) ANCHORED TO CONC. CAP W/ METAL SADDLE.
- MASONRY PIER TO BE CONSTRUCTED SOLID W/ PRECAST CONCRETE CAP. REFER TO ELEVATION DRAWINGS FOR PIER SIZE AND CAP HEIGHT.
- NOTE: DECORATIVE STRUCTURAL COLUMNS MAY REPLACE 6" X 6" POST PROVIDED THAT THEY ARE IN CONFORMANCE WITH O.B.C. 9.17.4.

49D

EXTERIOR COLUMN:

- MIN. 6"x6" (140mm X 140mm) WOOD POST CLAD W/ DECOR. SURROUND (PER ELEVATION DRAWINGS) ANCHORED TO PORCH SLAB W/ METAL SADDLE
- NOTE: DECORATIVE STRUCTURAL COLUMNS MAY REPLACE 6" X 6" ABOVE PROVIDED THAT THEY ARE IN ACCORDANCE WITH O.B.C. 9.17.4.

50

COLD CELLARS:

- FOR COLD CELLARS PROVIDE THE FOLLOWING:

- VENTING AREA TO BE EQUIVALENT TO 0.2% OF COLD CELLAR AREA.
- COVER VENT W/ BUG SCREEN
- WALL MOUNTED LIGHT FIXTURE
- 1'-11/2" FOR DOOR OPENING
- 2'-8" X 6'-8" EXTERIOR TYPE DOOR (MIN.R-4 RSI 0.7)
- INSULATE FULL HEIGHT OF INTERIOR BASEMENT WALL W/ R20 (RSI 3.52)
- CONTINUOUS INSULATION (ZONE 1 OBC SB-12.13.1.1.2.A.)
- ALTERNATE INSULATION METHOD: 2" (51mm) R10 (RSI 1.76) RIGID INSULATION W/ 2"x4"(38mm X 89mm) WOOD STUD W/ R12 (RSI2.11) BATT INSULATION

51


STUD WALL REINFORCEMENT:

- O.B.C. 9.5.2.3.
- WALL STUDS ADJACENT TO WATER CLOSETS & SHOWER BATH TUBS IN MAIN BATHROOM ARE TO BE REINFORCED TO PERMIT THE FUTURE INSTALLATION OF GRAB BARS AS PER O.B.C. 3.8.3.8.(3)(c)&(g) & 3.8.3.13.(2)(f) & 3.8.3.13.(4)(c)
- GRAB BARS TO BE INSTALLED AS PER O.B.C. 9.8.7.7.(2)

53

WINDOW GUARDS:

- @ STAIRS, LANDINGS & RAMPS - OBC 9.8.8.1.(8)
- WINDOW SILL AT 3'-0" (900mm) OR GREATER DOES NOT REQUIRE GUARDS
- @ FLOORS - OBC 9.8.8.1.(6)
- WINDOWS LESS THAN 1'-7" (480mm) ABOVE FLOORS WHERE ADJACENT GRADE IS GREATER THAN 5'-11" (1800mm) REQUIRE A GUARD PER OBC 9.8.8.2.
- OR -
- WINDOW TO BE NON-OPERABLE AND DESIGNED TO WITHSTAND LATERAL LOADS PER OBC 9.8.8.1.(8)(b)



TYPICAL CROSS SECTION - 2 STOREY (BRICK)

N.T.S.

CLIENT SPECIFIC REVISIONS

SCHEDULES

DOORS	
A	845x2030x45 (2'10"x6'8"x1'-3/4")
B	815x2030x35 (2'8"x6'8"x1'-3/8")
C	760x2030x35 (2'6"x6'8"x1'-3/8")
D	710x2030x35 (2'4"x6'8"x1'-3/8")
E	460x2030x35 (1'5"x6'8"x1'-3/8")
F	610x2030x35 (2'0"x6'8"x1'-3/8")
G	OVER SIZED EXTERIOR DOOR

STEEL BEAMS	
ST1	W 6 X 15
ST2	W 8 X 20
ST3	W 8 X 18
ST4	W 8 X 21
ST5	W 8 X 24

WOOD BEAMS	
WD10	2/1 3/4" X7 1/4" (2.0E) LVL
WD11	3/1 3/4" X7 1/4" (2.0E) LVL
WD12A	1/1 3/4" X9 1/2" (2.0E) LVL
WD13	2/1 3/4" X9 1/2" (2.0E) LVL
WD14A	1/1 3/4" X11 7/8" (2.0E) LVL
WD14	2/1 3/4" X11 7/8" (2.0E) LVL
WD15	3/1 3/4" X11 7/8" (2.0E) LVL
WD16A	1/1 3/4" X14" (2.0E) LVL
WD16	2/1 3/4" X14" (2.0E) LVL
WD17	3/1 3/4" X14" (2.0E) LVL

LINTELS	
L1	2/1 2" X 8" SPR
L3	2/1 2" X 10" SPR
L5	2/1 2" X 12" SPR
L7	3-1/2" X 3-1/2" X 1/4" L
L8	4-7/8" X 3-1/2" X 1/4" L
L9	4" X 3-1/2" X 1/4" L
L10	4-7/8" X 3-1/2" X 5/16" L
L11	4-7/8" X 3-1/2" X 3/8" L
L12	5-7/8" X 3-1/2" X 5/16" L
L13	5-7/8" X 3-1/2" X 3/8" L
L14	5-7/8" X 3-1/2" X 1/2" L
L15	5-7/8" X 4" X 1/2" L
L16	7-1/8" X 4" X 3/8" L
L17	7-1/8" X 4" X 1/2" L

PLAN/ELEVATION LEGEND

	SMOKE ALARM (CMA)
	WATERPROOF DUPLEX OUTLET
	VENTS AND INTAKES
	HOSE BIB
	EXHAUST FAN
	COLD CELLAR VENT
	STOVE VENT
	FIRE PLACE VENT
	DRYER VENT

	CARBON MONOXIDE ALARM (CMA)
	DOUBLE JOIST
	PRESSURE TREATED LUMBER
	GIRDER TRUSS
	ABOVE FINISHED FLOOR
	BEAM BY FLOOR MANUF
	FLUSH
	DROPPED
	REPEAT SAME JOIST SIZE
	UNDER SIDE
	FIXED GLAZING
	GLASS BLOCK
	BLACK GLASS

	FLOOR DRAIN
	SOLID BEARING (TO BE SAME WITH AS SUPPORTED MEMBER)
	POINT LOAD
	FLAT ARCH
	2 STORY WALL
	EXT. LIGHT FIXTURE (WALL MOUNTED)
	HYDRO METER
	GAS METER

FRAME CONSTRUCTION:

- ALL FRAMING LUMBER TO BE No.1 AND No. 2 SPF UNLESS NOTED OTHERWISE.
- ROOF LOADING IS BASED ON 1.5kPa SPECIFIED COMPOSITE SNOW AND RAIN LOADS.
- JOISTS TO HAVE MIN. 1-1/2" (38mm) END BEARING
- BEAMS TO HAVE MIN. 3-1/2" (89mm) END BEARING
- DOUBLE STUDS @ OPENINGS
- DOUBLE HEADER JOISTS AROUND FLOOR OPENINGS WHEN THEY ARE BETWEEN 3'-11" (1200mm) AND 10'-6" (3200mm)
- DOUBLE TRIMMER JOISTS WHEN HEADER JOIST LENGTH IS BETWEEN 2'-7" (800mm) AND 6'-7" (2000mm)
- DOUBLE JOISTS OR SOLID BLOCKING UNDER NON-LOAD BEARING PARALLEL PARTITIONS
- BEAMS TO BE PLACED UNDER LOADBEARING WALLS WHEN WALLS ARE PARALLEL TO FLOOR JOISTS
- BEAMS MAY BE A MAX. 24" (600mm) FROM LOADBEARING WALLS WHEN WALLS ARE PERPENDICULAR TO FLOOR JOISTS
- APPROVED METAL HANGERS TO BE USED FOR JOISTS AND BEAMS WHEN THEY FRAME INTO SIDES OF BEAMS, TRIMMERS AND HEADERS
- FLOOR JOISTS SUPPORTING ROOF LOADS SHALL NOT BE CANTILEVERED MORE THAN 15 3/4" (400mm) BEYOND SUPPORTS FOR 2" X 8" (38mm X 184mm)
- FLOOR JOISTS SUPPORTING ROOF LOADS SHALL NOT BE CANTILEVERED MORE THAN 23 5/8" (600mm) BEYOND SUPPORTS FOR 2" X 10" (38mm X 235mm) OR LARGER.

WATERPROOF WALLS IN BATHROOMS:

- REQUIRED AS PER OBC 9.29.2.1.

WINDOWS:

- WINDOWS TO BE SEALED TO THE AIR & VAPOR BARRIER
- WINDOWS THAT SEPARATE HEATED SPACE FROM UNHEATED SPACE SHALL HAVE AN OVERALL COEFFICIENT OF HEAT TRANSFER OF 1.6 W/(m2.K) OR
- AN ENERGY RATING OF NOT LESS THAN 25 FOR WINDOWS
- BASEMENT WINDOWS WITH LOAD BEARING STRUCTURAL FRAME SHALL BE DOUBLE GLAZED WITH LOW-E COATING
- SKYLIGHTS SHALL HAVE AN OVERALL COEFFICIENT OF HEAT TRANSFER OF 2.8 W/(m2.K)
- FOR GROSS GLAZED AREAS LESS THAN AND EQUAL TO 17%

DRAIN WATER HEAT RECOVERY:

- DWHR UNITS TO BE INSTALLED AS PER OBC SB-12.3.1.1.1.(22) & 3.1.1.12. SENTENCES (1) TO (6)
- DWHR ARE REQUIRED IN ALL DWELLING UNITS TO RECEIVE DRAIN WATER FROM ALL SHOWERS OR FROM AT LEAST 2 SHOWERS WHERE THERE ARE 2 OR MORE SHOWERS PROVIDED THERE IS A CRAWL SPACE OR STOREY BELOW THE SHOWERS.

MUNICIPALITY OF CLARINGTON
CERTIFIED COPY
-FORMING PART OF BUILDING
PERMIT DRAWING

THESE DRAWINGS ARE NOT TO BE SCALED. ALL DIMENSIONS MUST BE VERIFIED BY CONTRACTOR PRIOR TO COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES MUST BE REPORTED DIRECTLY TO RN DESIGN LTD

client

Esquire Homes

project

North Glen Phase 4

revisions

#	ISSUED FOR CLIENT REVIEW	date	dwn	chk	#	ISSUED FOR PERMIT	date	dwn	chk
1		30-MAY-19	ES	ES					
3		03-APR-20	KC	ES					

location

Darlington

marking name



model

33-1

scale

3/16" = 10"

page

D3

WWW.RNDESIGN.COM
Tel: 905-738-3177
WWW.THEPLUSGROUP.CA

I, ERIC SCHNEIDER DECLARE THAT I HAVE REVIEWED AND TAKEN DESIGN RESPONSIBILITY FOR THE DESIGN WORK ON BEHALF OF RN DESIGN LTD. UNDER DIVISION C-PART-3 SUBSECTION-3.2.4 OF THE BUILDING CODE. I AM QUALIFIED AND THE FIRM IS REGISTERED IN THE APPROPRIATE CLASSES / CATEGORIES.

QUALIFIED DESIGNER BCIN:

30840
26995
03-APR-2020

SIGNATURE: