

**Kleinburg Glen - 76 - 1 - 38-6 Elev.B WYNDHAM**  
**CENTRAL VAC AND WIRING**

Inv.756	1 - BEDROOM 2: ADD RJ6 CABLE. PLEASE SEE FLOORPLAN FOR LOCATION
Line10195	Note:
17Aug16 / 11Nov16	
Inv.756	1 - CONDUIT PIPE - FROM ATTIC TO ELECTRICAL PANEL - PLEASE RUN A STRAIGHT RUN FROM ELECTRICAL PANEL TO ATTIC
Line10196	Note:
17Aug16 / 11Nov16	
Inv.756	1 - GREAT ROOM: CONDUIT PIPE - FOR TELEVISION - APPROX 54" AFF. TERMINATING STRAIGHT DOWN AT STANDARD HEIGHT
Line10202	Note:
17Aug16 / 11Nov16	

**CERAMIC**

Inv.756	1 - MASTER ENSUITE: UPGRADE TO FREE STANDING TUB - UPG1 ONLY
Line13854	Note:
17Aug16 / 11Nov16	
Inv.1,085	1 - MAIN FLOOR TILE UPG 4: Foyer / Powder Room / Kitchen
Line15945	Note:
10Jan17 / 9Mar17	
Inv.1,085	1 - MAIN FLOOR: UPG 4 Tile - Hallway
Line15946	Note: Please see floor plan for location
10Jan17 / 9Mar17	
Inv.1,085	1 - TWIN BATH: UPG 1 Tub Wall Tile
Line15969	Note:
10Jan17 / 9Mar17	
Inv.1,085	1 - ENSUITE 2: UPG 1 Tub Wall Tile
Line15970	Note:
10Jan17 / 9Mar17	
Inv.1,085	1 - MASTER ENSUITE SHOWER WALL TILE: UPG 2
Line15973	Note:
10Jan17 / 9Mar17	

**DRYWALL**

Inv.756	1 - SMOOTH CEILINGS - (2 - Story Design) SECOND FLOOR
Line10194	Note:
17Aug16 / 11Nov16	

**ELECTRICAL**

Inv.756	1 - KITCHEN: 220V WALL RECEPTICAL ON DEDICATED CIRCUIT - FOR 4 WIRE BUILT - IN WALL OVEN - FOR FUTURE WALL OVEN/MICRO COMBO. PLEASE SEE FLOORPLAN FOR LOCATION. LEFT OF COOKTOP
Line10197	Note:
17Aug16 / 11Nov16	
Inv.756	1 - KITCHEN: 110V WALL RECEPTACLE ON DEDICATED CIRCUIT - FOR MICROWAVE - FOR FUTURE WALL OVEN/MICRO COMBO. PLEASE SEE FLOORPLAN FOR LOCATION. LEFT OF COOKTOP
Line10198	Note:
17Aug16 / 11Nov16	

Kleinburg Glen - 76 - 1 - 38-6 Elev.B WYNDHAM

Inv.756	1 - KITCHEN: 110V WALL RECEPTACLE ON DEDICATED CIRCUIT - GAS FIRED APPLIANCE - FOR AUX. EQUIPMENT - NOT A STOVE PLUG. FOR FUTURE GAS LINE
Line10200	Note:
17Aug16 / 11Nov16	

Inv.756	1 - GREAT ROOM: 110V WALL RECEPTACLE ON NORMAL CIRCUIT - APPROX. 54" AFF. PLEASE SEE FLOORPLAN FOR LOCATION
Line10203	Note:
17Aug16 / 11Nov16	

EXTERIOR COLOURS

Inv.756	1 - EXTERIOR COLOUR PACKAGE 1
Line13855	Note:
17Aug16 / 11Nov16	

FRAMING

Inv.756	1 - DEN: DELETE DOOR AND OPEN DEN. PLEASE SEE FLOORPLAN FOR DETAILS
Line10210	Note:
17Aug16 / 11Nov16	

Inv.756	1 - MASTER ENSUITE: UPGRADE TO FREE STANDING TUB - UPG1 ONLY
Line13853	Note:
17Aug16 / 11Nov16	

GLASS AND MIRROR

Inv.756	1 - MASTER ENSUITE: CONVERT FRAMED SHOWER TO 10MM FRAMLESS SHOWER ENCLOSURE WITH DOOR AND 10MM SIDE PANEL
Line10192	Note:
17Aug16 / 11Nov16	

GRANITE MARBLE QUARTZ

Inv.1,085	1 - KITCHEN COUNTERTOP: UPG 3
Line15943	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - KITCHEN COUNTERTOP EDGE: 3CM FE30
Line15944	Note: Price Included above in stone cost
10Jan17 / 9Mar17	

Inv.1,085	1 - MASTER VANITY COUNTER: UPG 2
Line15972	Note: STD FE20 Edge
10Jan17 / 9Mar17	

Inv.1,085	2 - KITCHEN: Add Waterfall Legs to Island - both sides
Line15979	Note:
10Jan17 / 9Mar17	

HARDWOOD

Inv.1,085	1 - MAIN FLOOR HARDWOOD: UPG 3 - Den / Dining / Great Room
Line15947	Note:
10Jan17 / 9Mar17	

HVAC

Kleinburg Glen - 76 - 1 - 38-6 Elev.B WYNDHAM

Inv.756	1 - KITCHEN: GAS LINE ROUGH - FOR FUTURE COOKTOP
Line10201	Note:
17Aug16 / 11Nov16	

INTERIOR TRIM AND DOORS

Inv.756	3 - MAIN FLOOR: EXTENDED HEIGHT ARCHWAY (PRICE PER DOORWAY) - INCLUDE FRAMING NOTE
Line10204	Note: Extra arch at Den entrance
17Aug16 / 11Nov16	

Inv.756	5 - MAIN FLOOR: STANDARD DOOR EXTENDED HEIGHT 96 INCH (PRICE PER DOOR) - GROUND FLOOR 2 STOREY MODELS
Line10205	Note:
17Aug16 / 11Nov16	

KITCHEN AND BATH CABINETRY

Inv.1,085	1 - KITCHEN CABINETRY: UPG 2
Line15941	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - KITHCEN CABINETRY: Perimeter Cabinets Manhattan PVC White Crystal / Island Florentine Maple Slate
Line15942	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - KITCHEN: UPG Add Built-in wall oven & microwave and cooktop
Line15948	Note: Please see kitchen drawing for location
10Jan17 / 9Mar17	

Inv.1,085	1 - KITCHEN: Add Pots & Pans drawers under cooktop (at drop in cooktop cabinet the top drawer is a false front)
Line15949	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - KITCHEN: UPG ADD Approx 4.5ft of 59cm deep Pantry in Lieu of Option Desk area
Line15964	Note: Please see kitchen area of location / detail. 1/2 to be converted to Wall Oven / Micro combo.
10Jan17 / 9Mar17	

Inv.1,085	3 - KITCHEN: UPG ADD Approx 6ft of 30cm deep pantry - In optional Pantry area
Line15965	Note: Please see Kitchen drawing for location/detail
10Jan17 / 9Mar17	

Inv.1,085	1 - KITCHEN: UPG Add Crown Moulding & Furring Panel
Line15966	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - KITCHEN: UPG Add light Valance to upper cabinets
Line15967	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - MASTER ENSUITE: UPG 2 Vanity Cabinet
Line15971	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - KITCHEN: Purchasers request to NOT INSTALL builder's standard hood fan and standard cabinets above stove. DELETE. Do not supply, install, and/or credit. Purchasers are installing their own hood fan after closing. Leave 42" opening for future 36" Hood
Line15981	Note: See attached spec sheet. Finish Sides of Upper Cabinets. Purchasers accept and acknowledge that the exhaust fan duct hole may be off-centered with stove in kitchen due to purchasers installing their own hood fan after closing. The vendor is exempt.
10Jan17 / 9Mar17	

## Kleinburg Glen - 76 - 1 - 38-6 Elev.B WYNDHAM

Inv.1,085	2 - KITCHEN: Add 2 Gables on either side of Deep Pantry & Wall Oven/Micro Combo area
Line16003	Note: Please see Kitchen drawing for location / detail.
10Jan17 / 9Mar17	

## MISC.

Inv.756	1 - Purchaser has attended a Structural appointment at the Decor Centre & has DECLINED any additional upgrades and accepts and acknowledges that there will be no further structural changes/additions/deletions to be made upon signing on August 17, 2016.
Line10212	Note:
17Aug16 / 11Nov16	

Inv.756	1 - Purchasers are aware & accepts that ANY changes made to upgrades after signing this Purchasers Extra Form are subject to a minimum administration fee of \$500. PLUS a 10% holdback fee.
Line10213	Note:
17Aug16 / 11Nov16	

Inv.756	1 - BONUS PACKAGE: \$7,500.00 (INCLUDING TAXES) WORTH OF UPGRADES FROM GOLD PARK HOMES DÉCOR CENTRE IS BEING APPLIED TOWARD THE STRUCTURAL APPOINTMENT. PURCHASER HAS A REMAINING AMOUNT OF \$00 (INCLUDING TAXES) TO BE USED TOWARD THE COLOUR APPOINTMENT.
Line10214	Note:
17Aug16 / 11Nov16	

Inv.756	1 - Purchaser request that all upgrades from this purchaser's extras form to be added to the purchase price. Purchaser is aware that upgrades will be processed only after the builder receives approval letter from the bank.
Line10215	Note:
17Aug16 / 11Nov16	

Inv.756	1 - BALANCE AFTER CREDIT:     \$11,546.15 50% DEPOSIT BY CHEQUE:     \$5,773.08 50% BALANCE ON CLOSING:     \$5,773.08
Line10216	Note:
17Aug16 / 11Nov16	

Inv.1,085	1 - Purchaser has attended a Colour appointment at the Decor Centre & has DECLINED any additional upgrades and accepts and acknowledges that there will be no further structural changes/additions/deletions to be made upon signing.
Line15997	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - Purchasers are aware & accepts that ANY changes made to upgrades after signing this Purchasers Extra Form are subject to a minimum administration fee of \$500. PLUS a 10% holdback fee.
Line15998	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - STAIRCASE - The purchaser was advised and therefore accepts and acknowledges that the stain of the staircase and flooring chosen do not match. This difference might result in an undesirable colour variance.
Line15999	Note: The purchaser agrees that the vendor is to be exempt from any and all claims by the purchaser regarding this colour variance.
10Jan17 / 9Mar17	

Inv.1,085	1 - STAIRCASE - The purchaser was advised and therefore accepts and acknowledges that the wood species of the staircase and flooring chosen do not match. This difference may result in a stain colour variance.
Line16000	Note: The purchaser agrees that the vendor is to be exempt from any and all claims by the purchaser regarding this colour variance.
10Jan17 / 9Mar17	

Inv.1,085	1 - Due to the many variables that can affect the pattern, colour and/or design and "pitting" of natural products, granite installed will not be identical to the samples displayed.
Line16001	Note: Every effort is made to provide granite counter tops as close as possible but the vendor is not responsible for results which differ from the sample displayed. All countertop surfaces may have seems & product pattern & shade can change in areas containing seems.
10Jan17 / 9Mar17	

Kleinburg Glen - 76 - 1 - 38-6 Elev.B WYNDHAM

Inv.1,085	1 - TOTAL: \$60,370.25 50% Deposit: \$30,185.13 50% on Closing
Line16002	Note:
10Jan17 / 9Mar17	

PAINTING

Inv.1,085	1 - STAIRS & RAILINGS: UPG Stain colour to Generation Cobalt
Line15968	Note:
10Jan17 / 9Mar17	

PLUMBING

Inv.756	1 - KITCHEN: ROUGH - IN - WATERLINE FOR FRIDGE
Line10199	Note:
17Aug16 / 11Nov16	

Inv.756	1 - EXTERIOR: REAR OF HOUSE - HOSE BIB - STANDARD TO UPGRADED WITH HOT AND COLD WATER VALVE
Line10206	Note:
17Aug16 / 11Nov16	

Inv.756	1 - MASTER ENSUITE: UPGRADE TO FREE STANDING TUB - UPG1 ONLY
Line10207	Note:
17Aug16 / 11Nov16	

PLUMBING FIXTURES

Inv.1,085	2 - MASTER ENSUITE: Vanity Sinks - Compac Serenade Round Vessel Lavatory 13-0019W
Line15974	Note:
10Jan17 / 9Mar17	

Inv.1,085	2 - MASTER ENSUITE: Vanity Faucet - Delta Addison Vessel Lavatory Chrome 792-DST
Line15975	Note: See spec sheet attached
10Jan17 / 9Mar17	

Inv.1,085	1 - MASTER ENSUITE: Shower Faucet - x1 Delta Addison Tub & Shower, 2.0 GPM Chrome T14492
Line15976	Note:
10Jan17 / 9Mar17	

Inv.1,085	1 - KITCHEN: Add Soap Dispenser - Delta Chrome RP1002
Line15980	Note:
10Jan17 / 9Mar17	

STAIRS AND RAILINGS

Inv.1,085	1 - STAIRS & RAILINGS: UPG Euroline 1 with V-Groove Handrail
Line15978	Note:
10Jan17 / 9Mar17	

TRIM AND DOORS

Inv.1,085	1 - MAIN FLOOR - UPG 2 Trim & Baseboard
Line15977	Note: STD on Second Floor
10Jan17 / 9Mar17	

WINDOWS - BASEMENT

**Kleinburg Glen - 76 - 1 - 38-6 Elev.B WYNDHAM**

Inv.756	1 - BASEMENT WINDOWS - UPGRADE EXISTING BASEMENT WINDOW TO 53 INCH X 16 INCH - MAY REQUIRE INSTALLATION OF WINDOW WELL
Line10190	Note:
17Aug16 / 11Nov16	
Inv.756	3 - BASEMENT WINDOWS - UPGRADE EXISTING BASEMENT WINDOW TO 30 INCH X 16 INCH
Line10191	Note:
17Aug16 / 11Nov16	

Scheduled Closing Date: February-02-17

Purchaser: Lisa Ann Kaz

Property: 76

Telephone Res. / Bus: (647) 831-9398

Project: Burkshire Holdings Inc.

Decor Advisor: Laura Lofaro

Model and Elevation: 38-6 Elev.B WYNDHAM

Layout Changes: ☐ Yes ☐ NoSketch Attached: ☐ Yes ☐ No

Exterior Colour Scheme:

## 1. Cabinetry

	Style and Colour	Counter	Hardware
Kitchen / Breakfast	*2 Tone Kitchen	*Granite Polished Lennon *Edge3cmFE30	CS1-18
Laundry Room	N/A		
Powder Room	N/A		
Master Ensuite Bathroom	*Florentine Maple Slate	*Granite Polished White Spring Edge FE20	CS1-22
Second Ensuite Bathroom (If Applicable)	Varese PVC AntWhite	Wilsonart 4862K-07 Sandy Topaz	CS1-22
Twin Bath	Varese PVC Mystic	Arborite P-345 LM Inukshuk Taupe	CS1-16
Dishwasher Cabinet			

## Comment

\*Kitchen Cabinetry: UPG 2 Perimeter Cabinets - Manhattan PVC White Crystal, UPG 2 Island Cabinets - Florentine Maple Slate

\*Kitchen - Waterfall legs on either side of Island

## 2. Floor Tile

	Selection	Grout	Threshold
Entrance Vestibule	*17.7x17.7 Must Polished Dove Grey		
Main Hall	*17.7x17.7 Must Polished Dove Grey		
Kitchen / Breakfast	*17.7x17.7 Must Polished Dove Grey		
Laundry Room	13x13 Milieu Fog		
Powder Room	*17.7x17.7 Must Polished Dove Grey		
Master Ensuite Bathroom	*17.7x17.7 Must Polished Taupe		
Second Ensuite Bathroom (If Applicable)	13x13 Venus Series Brown		
Lower Landing (If Applicable)			
Twin Bath	13x13 Venus Series Grey		

## Comment

\* Free Standing Tub in Master Ensuite

## 3. Wall Tile

	Selection	Listello/Inserts	Describe
		<input type="radio"/> Yes <input type="radio"/> No	
Master Ensuite Bathroom			
Tub Deck	N/A	<input type="radio"/> Yes <input checked="" type="radio"/> No	
Shower Stall	*Cristallo (See Comment below)	<input type="radio"/> Yes <input checked="" type="radio"/> No	
Bathroom Walls	N/A	<input type="radio"/> Yes <input checked="" type="radio"/> No	
Second Ensuite Bathroom (If Applicable)	*4x16 CDC Dark Taupe Bright	<input type="radio"/> Yes <input checked="" type="radio"/> No	
Twin Bath	*11.9x10.7 Ont.Hex.GlosTender Gre	<input type="radio"/> Yes <input checked="" type="radio"/> No	

Kitchen Backsplash ☐ Yes ☒ No

Backsplash Behind Fridge

## Comment

\*Master Ensuite Shower Wall Tile - Cristallo Glass Mosaic Brick Layered Glossy/Matte Blends Taupe 0.5x1.9 Code: OD.CR.TPE.0,5X1,9.BL

Scheduled Closing Date: February-02-17

Purchaser: Lisa Ann Kaz

Property: 76

Telephone Res. / Bus: (647) 831-9398

Project: Burkshire Holdings Inc.

Decor Advisor: Laura Lofaro

Model and Elevation: 38-6 Elev.B WYNDHAM

#### 4. Plumbing Fixtures

<input type="checkbox"/>	Second Ensuite	<input type="checkbox"/>	Powder Room	<input type="checkbox"/>
Master Ensuite Bathroom	<input type="checkbox"/>	Other Room - Specify	<input type="checkbox"/>	Other Washroom
<input type="checkbox"/>				

##### Comment

Master Ensuite Vanity Sinks - Compac x2 Serenade round cessel lavatory 13-0019-W  
Master Ensuite Vanity Faucet - x2 Delta Addison Vessel Lavatory Chrome 792-DST  
Master Ensuite Shower Faucet - x1 Delta Addison Tub & Shower, 2.0 GPM Chrome T14492  
Kitchen: Add Soap Dispenser - Delta Chrome RP1002

Everywhere else STD

#### 5. Hardwood Flooring

	Type and Stain		Type and Stain
Main Hall	*See Tile	Upper Landing	*Preverco Ash Komodo Nuance
Kitchen / Breakfast	*See Tile	Upper Hall	N/A
Living Room	N/A	Master Bedroom	N/A
Dining Room	*Preverco Ash Komodo Nuance	Bedroom #2	N/A
Family Room	N/A	Bedroom #3	N/A
Den/Library	*Preverco Ash Komodo Nuance	Bedroom #4	N/A
Entrance Vestibule	*See Tile	Bedroom #5	N/A
Lower Landing (If Applicable)	*See Tile	Other Room - Specify	
		GREAT ROOM	*PREVERCO ASH KOMODO NUANCE

##### Comment

\*Preverco Ash Komodo Nuance Brushed 3/4" x 4-1/4"

#### 6. Carpeting

	Upgrade	Description
Main Hall	<input type="checkbox"/>	N/A
Living Room	<input type="checkbox"/>	N/A
Dining Room	<input type="checkbox"/>	N/A
Family Room	<input type="checkbox"/>	N/A
Den/Library	<input type="checkbox"/>	N/A
Upper Hall	<input type="checkbox"/>	T15
Master Bedroom	<input type="checkbox"/>	T15
Bedroom #2	<input type="checkbox"/>	T15
Bedroom #3	<input type="checkbox"/>	T15
Bedroom #4	<input type="checkbox"/>	T15
Bedroom #5	<input type="checkbox"/>	N/A
<input type="checkbox"/>	<input type="checkbox"/>	
Upper Landing (If Applicable)	<input type="checkbox"/>	N/A
Lower Landing (If Applicable)	<input type="checkbox"/>	N/A

Upgrade Underpad	Type N/A	Area
Carpet on Stairs	Capped N/A	Runner - *Upgrade

##### Comment

APB

Scheduled Closing Date: February-02-17

Purchaser: Lisa Ann Kaz

Property: 76

Telephone Res. / Bus: (647) 831-9398

Project: Burkshire Holdings Inc.

Decor Advisor: Laura Lofaro

Model and Elevation: 38-6 Elev.B WYNDHAM

7. Fireplace

	Living Room			Family Room			Other Room - Specify <input type="checkbox"/> Great Room		
	Purchased	As Per Plan	N/A	Purchased	As Per Plan	N/A	Purchased	As Per Plan	N/A
Fireplace Type	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>
Mantle Type							STD Gas		
Colour / Stain							STD Stone		
Surround							STD		
Hearth							STD		
Comment									

8. Trim Carpentry

Interior Doors	STD	Front Door Glass Inserts	STD	Door Handles	STD
Interior Trim	UPG 2 First Floor / STD Second Floor				
Comment					

\*8Ft Doors at Structural

9. Plaster Mouldings and Medallions

Entrance Vestibule	N/A		Kitchen/Breakfast	N/A	
Main Hall	N/A		Den/Library	N/A	
Living Room	N/A		Lower Landing	N/A	
Dining Room	N/A		Other Room - Specify	N/A	
Family Room	N/A				
Comment					

10. Railings and Spindles

Railing Package	*Euroline 1 with V-Groove Handrail		
Railing Colour	*Generation Cobalt	Spindle Colour	Black Wrought Iron
Stringer / Riser	*Generation Cobalt	Treads	*Generation Cobalt
Comment			
	Oak Stairs	<input checked="" type="radio"/> Yes	<input type="radio"/> No

11. Wall Paint

Main & Upper Hall		Master Bedroom	
Living Room		Bedroom #2	
Dining Room		Bedroom #3	
Kitchen / Breakfast		Bedroom #4	
Family Room		Bedroom #5	
Powder Room		Master Ensuite	
Laundry Room			
Den/Library		Second Ensuite	
Trim Paint	White	Thu-Out	Warm Grey
Comment	Smooth Ceilings First Floor		

AR

Scheduled Closing Date: February-02-17

Purchaser: Lisa Ann Kaz  
Telephone Res. / Bus: (647) 831-9398  
Decor Advisor: Laura Lofaro

Property: 76  
Project: Burkshire Holdings Inc.  
Model and Elevation: 38-6 Elev.B WYNDHAM

12. Electrical


Plugs and Switches	<input type="radio"/> White <input type="radio"/> Ivory		Above Kitchen Cabinet Light	<input type="radio"/> Yes <input type="radio"/> No
Hood Fan	<input type="radio"/> White <input type="radio"/> Ivory		Below Kitchen Cabinet Light	<input type="radio"/> Yes <input checked="" type="radio"/> No
Appliances	Built in Cooktop	Built in Oven	Gas Stove	Microwave
	<input checked="" type="radio"/> Yes <input type="radio"/> No	<input checked="" type="radio"/> Yes <input type="radio"/> No	<input checked="" type="radio"/> Yes <input type="radio"/> No	<input checked="" type="radio"/> Yes <input type="radio"/> No
Comment				

13. Heating and Air Conditioning


Air Conditioning		Gas Provisions Stove	
Gas Provisions Dryer		Gas Provisions Barbecue	
Comment			

14. Additional Comments

15. Disclaimers and Notes

- 1) Colours of all materials are as close as possible to builder's selection, but not necessarily identical due to variances in manufacturing.
- 2) Any extras listed above are null and void unless accompanied by a separate invoice/amendment. Said invoice must be paid in full.
- 3) The Purchaser acknowledges that after Interior Colour Selection form is signed and dated, no further changes will be permitted other than re-selection due to unavailability.  Purchaser's Initials
- 4) The Purchaser acknowledges reading and accepting the "Gold Park Homes Decor Centre Disclaimers" form. This document contains other miscellaneous disclaimers.

This Interior Colour Selection is final and approved by:

Signature:  Date: Jan 12, 17



Trade Name: Gold Park Homes

Site location:





Model: 38-6

Address:




Project: Kleinburg Glen

Phase:


This layout has been explained to the purchaser by Cortina Kitchens Inc. and is understood by the purchaser.



### OPT. 5 BED. SECOND FLOOR



### PART SECOND FL. W/SH.




All prices subject to confirmation from head office.  
This quotation is subject to the terms & conditions set out.

ACCEPTED DATE: JAN. 12, 2017

All agreements are contingent upon strikes, accidents, and delays beyond our control.  
Please provide our installer with template for sinkholes or \$150.00 will be charged for callback.

Lot 76




20mm (3/4") Profiles




30mm (1 1/4") Profiles



WATERFALL  
LEGS  
ON EITHER  
SIDE OF ISLAND.



40mm (1 1/2") Profiles



Note: All colours may not be available in 30mm at time ordered. Vendor reserves the right to use 40 mm edges (by lamination process).

\*Mitre edge is available in Upgrade 1 for an overall thickness of 2". All other Mitre edge options will be an Upgrade 2 Edge.


STD. SINK -  
KUTTEN

K6-76

PPA

JAN. 12, 2017

## STANDARD HARDWARE



CSI-6



CSI-10




CSI-14

TWIN BATH




CSI-16


KURZEN




CSI-18



CSI-19




CSI-20




CSI-21

MASTER ENSUITE  
2ND ENSUITE


CSI-22



CSI-23



CSI-24



CSI-25

## \*NOTES:

- IMAGES ARE FOR QUICK REFERENCE PURPOSES ONLY
- ACTUAL SIZES AND FINISHES AS PER HARDWARE SAMPLE BOARD PROVIDED TO DECOR CENTRE

K6-76



JAN. 12. 2017

K6-76



JAN. 12. 2017

MASTER ENSUITE X2

# Seranade

round vessel lavatory

13-0019-W



**Finish**  
Soft white vitreous china  
Nano easy clean glaze




**Overflow**  
Rear



**Template**  
Supplied




**Dimensions**  
24" (W) x 17 1/4" (D) x 5 3/4" (H)



\$180

# Addison™ Collection




Lavatory 4" Centerset

Chrome Finish  
# 2592-MP-DST

Brilliance® Stainless Finish,  
# 2592-SSMPU-DST

Champagne Bronze™ Finish  
# 2592-CZMPU-DST



Lavatory  
Single or three holes with plate

Chrome Finish  
# 592-DST

Brilliance® Stainless Finish  
# 592-SS-DST

Champagne Bronze™ Finish  
# 592-CZ-DST




Vessel Lavatory

Chrome Finish  
# 792-DST

Brilliance® Stainless Finish  
# 792-SS-DST

Champagne Bronze™ Finish  
# 792-CZ-DST


Applies to faucets shown above



Lavatory Widespread with pop up  
# 3592LF

Brilliance® Stainless Finish  
# 3592-SS


Champagne Bronze™ Finish  
# 3592LF-CZ



Roman Tub - 3 Piece  
# T2792 / R2709

Brilliance® Stainless Finish  
# T2792-SS / R2709

Champagne Bronze™ Finish  
# T2792-CZ / # R2709



Roman Tub - 4 Piece  
# T4792 / R4716

Brilliance® Stainless Finish  
# T4792-SS / R4716

Champagne Bronze™ Finish  
# T4792-CZ / R4716

Shown in Chrome



K6-76


Ⓟ

JAN 12, 2017

MASTER ENSUITE X2

# Addison™ Collection

## Pressure Balance




Shower, 2.0 GPM

Chrome Finish  
# T14292

Brilliance® Stainless Finish  
# T14292-SS

Champagne Bronze™ Finish  
# T14292-CZ

## Dual Function Pressure Balance




Shower, 2.0 GPM

Chrome Finish  
# T17292

Brilliance® Stainless Finish  
# T17292-SS

Champagne Bronze™ Finish  
# T17292-CZ




Tub & Shower, 2.0 GPM

Chrome Finish  
# T14492

Brilliance® Stainless Finish  
# T14492-SS

Champagne Bronze™ Finish  
# T14492-CZ



Tub & Shower, 2.0 GPM

Chrome Finish  
# T17492

Brilliance® Stainless Finish  
# T17492-SS

Champagne Bronze™ Finish  
# T17492-CZ

Shown in Chrome



K6-76

(R)

JAN 12, 2017

MASTER ENSUITE


K6-76

~~KA~~

JAN 12, 2017

KITCHEN


## Kitchen – Soap Dispensers



Soap Dispenser

Chrome Finish  
# RP1001

Arctic™ Stainless Finish  
# RP1001AR




Soap Dispenser

Chrome Finish  
# RP1002

Arctic™ Stainless Finish  
# RP1002AR

Champagne Bronze™ Finish  
# RP1002CZ



Soap Dispenser

Chrome Finish  
# RP50813

Arctic™ Stainless Finish  
# RP50813AR


Champagne Bronze™ Finish  
# RP50813CZ

JENN-AIR® DETAILED PLANNING DIMENSIONS


30" COMBINATION MICROWAVE/WALL OVENS

JMW3430D, JMW2430D – 30" x 43 3/4" x 25 5/16"

PRODUCT DIMENSIONS



FRONT VIEW



TOP VIEW

MODEL #		JMW3430D JMW2430D	
		in	cm
A	Overall width		
	Pro-Style® Stainless or Euro-Style Stainless	30	76.2
	Floating Glass	29 15/16	76.1
B	Height of control panel	5 1/2	14
C	Space between control panel and door	1/2	1.2
D	Height to top of microwave oven handle		
	Pro-Style® Stainless	12 3/16	31.0
	Euro-Style (color-coordinating)	12 3/16	31.0
E	Height of microwave oven door	12 1/16	32.3
F	Space between doors	1 1/8	2.9
G	Height to top of oven handle		
	Pro-Style® Stainless	21 3/8	55.0
	Euro-Style (color-coordinating)	21 7/16	54.4
H	Height of oven door	22 1/8	56.2
I	Height of trim	1 11/16	4.3
J	Overall height	43 3/4	111.1
K	Width of recessed oven	28 7/16	72.2
L	Width of conduit channel	4 15/16	12.5
M	Depth of recessed oven	23 1/4	59.0
N	Depth with doors	24 3/8	61.9
O	Depth with handles		
	Pro-Style® Stainless	26 3/8	67.0
	Euro-Style (color-coordinating)	25 1/16	64.3
P	Depth with door fully open	45 3/8	115.3

KG-76

AR

JAN 12, 2017

**IMPORTANT:** Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

JENN-AIR®

8610AdZw915


JENN-AIR® DETAILED PLANNING DIMENSIONS

2 of 4

30" COMBINATION MICROWAVE/WALL OVENS

JMW3430D, JMW2430D – 30" x 43<sup>3</sup>/<sub>4</sub>" x 25<sup>5</sup>/<sub>16</sub>"

DIMENSIONS AS INSTALLED



MODEL #		JMW3430D	
		<del>JMW2430D</del>	
		in	cm
A	Height to top of upper handle Pro-Style® Stainless	36 <sup>1</sup> / <sub>2</sub>	92.7
	Euro-Style (color-coordinating)	36 <sup>1</sup> / <sub>2</sub>	92.7
B	Height to top of lower handle Pro-Style® Stainless	23 <sup>3</sup> / <sub>4</sub>	59.3
	Euro-Style (color-coordinating)	23 <sup>3</sup> / <sub>4</sub>	58.7
C	Height of trim extending below cutout	1 <sup>1</sup> / <sub>16</sub>	4.3
D	Height from top of recessed oven to top of control panel JMW3430D	2 <sup>1</sup> / <sub>2</sub>	6.3
	JMW2430D	2 <sup>15</sup> / <sub>16</sub>	7.4
E	Height from bottom of recessed oven foot to bottom of oven vent	<sup>3</sup> / <sub>16</sub>	0.5
F	Height of recessed oven	41	104.2
G	Height to top of control panel	43 <sup>3</sup> / <sub>4</sub>	111.1
H	Depth with door fully open	45 <sup>3</sup> / <sub>4</sub>	115.3
I	Depth with handles Pro-Style® Stainless	26 <sup>3</sup> / <sub>8</sub>	67.0
	Euro-Style (color-coordinating)	25 <sup>5</sup> / <sub>16</sub>	64.3
J	Depth with doors	24 <sup>3</sup> / <sub>4</sub>	61.9
K	Depth of recessed oven	23 <sup>1</sup> / <sub>4</sub>	59.0

166-76

AR

JAN. 12, 2017

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.  
Do not make any cutouts based on this information. Refer to the Installation Guide before  
selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.  
All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

JENN-AIR®


8610AdZw915

JENN-AIR® DETAILED PLANNING DIMENSIONS

30" COMBINATION MICROWAVE/WALL OVENS


JMW3430D, JMW2430D – 30" x 43<sup>3</sup>/<sub>4</sub>" x 25<sup>5</sup>/<sub>8</sub>"

OPENING/CLEARANCE DIMENSIONS



FRONT VIEW

SIDE VIEW



BACK VIEW

MODEL #

JMW3430D  
~~JMW2430D~~

		in	cm
A	Width of cabinet (min.)	30	76.2
B	Width of cutout	28½	72.4
C*	Height of cutout (recommended)	41⅝	104.9
D	Top of cutout to bottom of upper cabinet door (min.)	2¼	5.7
E	Bottom of cutout to top of lower cabinet door (min.)	1½	3.8
F	Bottom of cutout to floor	4-19¼	10.2-48.9
G	Depth of cutout (min.)	24	61.0
e	Recommended junction box location		

\* Will fit cutout height from 41" (104.1 cm) to 41½" (105.4 cm).

ELECTRICAL REQUIREMENTS

240 volt, 40-amp fused, grounded circuit is required. A dedicated circuit is required.

The length of conduit provided is for serviceability. Do not cut the conduit. The junction box should be located 3" (7.6 cm) maximum below the support surface. Drill a 1" (2.5 cm) minimum diameter hole in the right rear or left rear corner of the support surface for access to the junction box.

KG-76



JAN 12, 2017

**IMPORTANT:** Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.



8610AdZw915


JENN-AIR® DETAILED PLANNING DIMENSIONS

4 of 4


30" COMBINATION MICROWAVE/WALL OVENS – FLUSH INSTALLATION

JMW3430D, JMW2430D – 30" x 43<sup>3</sup>/<sub>8</sub>" x 24<sup>3</sup>/<sub>8</sub>" (depth without handles)


OPENING/CLEARANCE DIMENSIONS




FRONT VIEW



SIDE VIEW



TOP VIEW



BACK VIEW

\* Cleats and spacers must be recessed 1<sup>1</sup>/<sub>2</sub>" (3.5 cm) from the front of the cabinet.

**IMPORTANT:** Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

MODEL #	JMW3430D	
	in	cm
A	Width of flush inset cutout (min.)	30 <sup>3</sup> / <sub>8</sub> 76.8
B	Width of opening (min.)	28 <sup>3</sup> / <sub>8</sub> 73.3
C	Height of flush inset cutout (min.)	44 <sup>3</sup> / <sub>8</sub> 112.5
D	Height of opening (min.)	43 <sup>1</sup> / <sub>8</sub> 110.9
E	Bottom of cutout to floor	4 <sup>5</sup> / <sub>8</sub> - 19 <sup>1</sup> / <sub>4</sub> 11.7-48.9
F	Depth of cutout (min.)	25 63.5
e	Recommended junction box location	

ELECTRICAL REQUIREMENTS

240 volt, 40-amp fused, grounded circuit is required. A dedicated circuit is required.

The length of conduit provided is for serviceability. Do not cut the conduit. The junction box should be located 3" (7.6 cm) maximum below the support surface. Drill a 1" (2.5 cm) minimum diameter hole in the right rear or left rear corner of the support surface for access to the junction box.

FLUSH INSTALLATION REQUIREMENTS

A 25" (63.5 cm) minimum cutout depth is required.

These dimensions will result in a 1/4" (0.6 cm) reveal on the top, a 1/4" (0.6 cm) reveal on the sides and a 1/8" (0.3 cm) reveal on the bottom of the wall oven.

The front face of the cleats and spacers will be visible and should be treated as a finished surface.

KG-76

24

JAN 12, 2017

JENN-AIR®

8610AdZw915


# JENN-AIR® DETAILED PLANNING DIMENSIONS

1 of 4


## 36" GAS COOKTOP

JGC7636B – 36" x 5 1/4" x 21"


### PRODUCT DIMENSIONS



TOP VIEW



FRONT VIEW



SIDE VIEW

MODEL #		JGC7636B	
		in	cm
A	Overall width	36	91.4
B	Depth of cooktop	21	53.3
C	Center of cooktop to center of gas inlet	13 1/4	34.3
D	Width of recessed cooktop	35 1/4	89.5
E	Height of recessed cooktop	3 1/4	8.3
F	Height from gas inlet to countertop	5 1/4	13.3
G	Height with grates	1 1/4	3.2
H	Depth of recessed cooktop	20 1/4	51.4

KG-76

JAN. 12, 2017

Product dimension, cutout and installation specifications are provided for planning purposes only. Before installing any product, be sure to verify cutout dimensions and electrical/gas connections as actual product dimensions may vary.


JENN-AIR®

7673AdZw713


JENN-AIR® DETAILED PLANNING DIMENSIONS

36" GAS COOKTOP  
JGC7636B – 36" x 5¼" x 21"

OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



SIDE VIEW

TOP VIEW – CUTOUT

MODEL #		JGC7636B	
		in	cm
A	Width of combustable area above cooking surface (min.)	36	91.4
B	Width from cooktop to fixed wall or other combustable material (min.)	6	15.2
C	Width to outer edge of outlet (max.)	24	61.0
D*	Height to bottom of uncovered wood or metal cabinet above cooking surface (min.)	30	76.2
E	Height to bottom of uncovered wood or metal cabinet (min.)	18	45.7
F	Height to top edge of outlet (min.)	5½	14.0
G	Depth of upper cabinet (recommended)	13	33.0
H	Depth from cutout to wall (min.)	2⅞	5.9
I	Width of cutout	35⅜	89.9
J	Depth of cutout	20⅞	51.8
K	Depth from cutout to front of countertop	2⅞	5.9
e	Recommended electrical access location		
g	Recommended gas supply line location		

\*Dimension can be reduced by 6" (15.2 cm) when bottom of wood or metal cabinet is covered by not less than ¼" (0.6 cm) flame retardant millboard covered with not less than No. 28 MSG sheet metal, 0.015" (0.4 mm) stainless steel, 0.024" (0.6 mm) aluminum or 0.020" (0.5 mm) copper.  
If installing a hood or microwave hood combination above the cooktop, follow the hood or microwave hood combination instructions for dimensional clearances above the cooking surface.

GAS REQUIREMENTS

Natural Gas

This cooktop is factory-set for use with natural gas.

LP Gas Conversion

Conversion must be done by a qualified service technician. To convert to LP gas, use the LP gas conversion kit provided with the cooktop.

ELECTRICAL REQUIREMENTS

120 volt, 60 Hz, AC only, 15-amp fused, electrical circuit is required. A time-delay fuse or dedicated circuit is recommended.

LOCATION REQUIREMENTS

- To ensure cooktop base clearance, cabinet side walls need to be wider than the cutout.
- If cabinet has a drawer, allow a 4" (10.2 cm) minimum clearance between countertop and top of drawer. Drawer depth may need to be shortened to avoid interfering with the regulator.

KG-76

AP


JAN 12, 2017

JENN-AIR® DETAILED PLANNING DIMENSIONS


DISHWASHERS

JDB9800CW, JDB9200CW, JDB9000CW – 23¾" x 33¾" x 26⅞" (including handle)


PRODUCT DIMENSIONS



FRONT VIEW



ADJUSTABLE TOE KICK



TOP VIEW

MODEL #		JDB9800CW JDB9200CW JDB9000CW	
		in	cm
A	Width of door	23⅞	59.7
B	Width of toe kick	23⅞	59.7
C	Height to top of handle Pro-Style® Stainless	27⅞	70.8
	Euro-Style (color-coordinating)	27⅞	70.8
	Floating Glass	27⅞	70.8
D	Height of door Pro-Style® Stainless	30	76.3
	Euro-Style (color-coordinating)	30	76.3
	Floating Glass	30	76.3
E	Height of adjustable toe kick (min.-max.)	3½- 4⅞	8.9- 10.5
F	Width of recessed dishwasher	23¾	60.4
G	Depth with tub flange	22⅞	57.4
H	Depth with door Pro-Style® Stainless	24⅞	62.6
	Euro-Style (color-coordinating)	24⅞	62.6
	Floating Glass	25	63.5
I	Depth with handle Pro-Style® Stainless	27⅞	70.8
	Euro-Style (color-coordinating)	26⅞	68.3
	Floating Glass	27⅞	70.8
J	Depth with door fully open	49⅞	126.3

K6-76



JAN 12, 2017


**IMPORTANT:** Dimensional specifications are provided for planning purposes only.  
Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

JENN-AIR® DETAILED PLANNING DIMENSIONS

DISHWASHERS

JDB9800CW, JDB9200CW, JDB9000CW – 23¾" x 33⅞" x 26⅞" (including handle)

DIMENSIONS AS INSTALLED



MODEL #		JDB9800CW JDB9200CW JDB9000CW	
		in	cm
A*	Height to top of tub flange (min.)	33⅞	86.0
	Height to top of door (min.)	33⅞	85.7
C*	Height to top of handle (min.) Pro-Style® Stainless	31½	80.1
	Euro-Style (color-coordinating)	31½	80.1
	Floating Glass	31½	80.1
D*	Height to bottom of door	3⅞	9.4
E*	Height of recessed dishwasher (min.)	33⅞	85.5
F	Depth with door fully open (min.)	49⅞	126.3
G	Depth with handle (min.) Pro-Style® Stainless	27⅞	70.8
	Euro-Style (color-coordinating)	26⅞	68.3
	Floating Glass	27⅞	70.8
H	Depth with door (min.)	24⅞	62.6
I	Depth with tub flange (min.)	22⅞	57.4
J	Depth with toe kick (min.)	20⅞	52.9

\*With wheels removed. Add up to ⅞" (1.6 cm) to height with wheels and leg levelers fully extended.

KG 76  
AK  
JAN 12, 2017

**IMPORTANT:** Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.


JENN-AIR® DETAILED PLANNING DIMENSIONS

3 of 3


DISHWASHERS

JDB9800CW, JDB9200CW, JDB9000CW – 23¾" x 33⅞" x 26⅞" (including handle)


OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



SIDE VIEW



BACK VIEW

MODEL #		JDB9800CW JDB9200CW JDB9000CW	
		in	cm
A	Width (min.)	24	61.0
B	Width of possible utility installation area (back wall)	6¾	17.2
C	Width of clear area (back wall)	10½	26.7
D*	Height with wheels removed (min.)	33⅞	86.0
E	Height of possible utility installation area (back wall)	2½	6.4
F	Height of possible utility installation area (back/side wall)	6¼	15.9
G	Height of clear area (side wall)	3	7.6
H	Depth (min.)	24	61.0
I	Depth of utility location (side wall)	4	10.2

Electrical, water and drain connections may be installed in shaded areas

Recommended drain connection location – closest to sink	1½ dia. 3.8 dia.
Recommended electrical connection location – right-hand side or back wall	1½ dia. 3.8 dia.
Recommended water connection location – left-hand side or back wall	½ dia. 1.3 dia.

\*Measured from the lowest point on the underside of countertop.

ELECTRICAL REQUIREMENTS

120 volt, 60 Hz, AC only, 15- or 20-amp fused, grounded circuit is required. A dedicated circuit is recommended. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

WATER SUPPLY REQUIREMENTS

120°F (49°C) hot water supply with water pressure between 20 and 120 psi (138 and 862 kPa) is required. If you have questions about your water pressure, call a licensed, qualified plumber.

DRAIN REQUIREMENTS

Connect drain hose to waste tee or disposer inlet above drain trap. Maximum drain hose length 12' (3.7 m).

LOCATION REQUIREMENTS

Corner locations require a 2" (5.1 cm) minimum clearance between the side of the dishwasher door and the wall or cabinet.

K6-76

JAN 12, 2017

**IMPORTANT:** Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

JENN-AIR®

8768CdZw416

# JENN-AIR® DETAILED PLANNING DIMENSIONS


1 of 2

## 36" / 30" PYRAMID-STYLE WALL-MOUNT CANOPY HOODS


JXW8536DS – 36" x 24<sup>5</sup>/<sub>16</sub>"-42<sup>5</sup>/<sub>16</sub>" x 19<sup>1</sup>/<sub>16</sub>"

JXW8530DS – 30" x 24<sup>5</sup>/<sub>16</sub>"-42<sup>5</sup>/<sub>16</sub>" x 19<sup>1</sup>/<sub>16</sub>"


### PRODUCT DIMENSIONS



FRONT VIEW



SIDE VIEW



TOP VIEW

MODEL #		JXW8536DS		JXW8530DS	
		in	cm	in	cm
A	Width of chimney	13 <sup>3</sup> / <sub>16</sub>	33.5	13 <sup>3</sup> / <sub>16</sub>	33.5
B	Width of canopy	36	91.4	30	76.2
C	Height of trim	2 <sup>3</sup> / <sub>8</sub>	6.1	2 <sup>3</sup> / <sub>8</sub>	6.1
D	Height of canopy	5	12.7	5	12.7
E	Overall height with vented installation (min.-max.)	24 <sup>5</sup> / <sub>16</sub> -38 <sup>3</sup> / <sub>4</sub>	62.5-98.4	24 <sup>5</sup> / <sub>16</sub> -38 <sup>3</sup> / <sub>4</sub>	62.5-98.4
	Overall height with non-vented (recirculating) installation (min.-max.)	28 <sup>5</sup> / <sub>16</sub> -42 <sup>5</sup> / <sub>16</sub>	71.9-108.3	28 <sup>5</sup> / <sub>16</sub> -42 <sup>5</sup> / <sub>16</sub>	71.9-108.3
F	Depth of chimney	10 <sup>3</sup> / <sub>4</sub>	27.3	10 <sup>3</sup> / <sub>4</sub>	27.3
G	Depth of canopy	19 <sup>1</sup> / <sub>16</sub>	50.0	19 <sup>1</sup> / <sub>16</sub>	50.0
H	Width of vent collar	6 <sup>1</sup> / <sub>4</sub>	15.8	6 <sup>1</sup> / <sub>4</sub>	15.8
I	Depth of vent collar	3 <sup>3</sup> / <sub>4</sub>	9.5	3 <sup>3</sup> / <sub>4</sub>	9.5
J	Width from chimney to edge of canopy	11 <sup>1</sup> / <sub>16</sub>	29.0	8 <sup>7</sup> / <sub>16</sub>	21.4

K6-76

JAN 12, 2017

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.

**Do not make any cutouts based on this information.** Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

**JENN-AIR®**

8316AdZw1114

# JENN-AIR® DETAILED PLANNING DIMENSIONS


2 of 2

## 36" ~~W~~ PYRAMID-STYLE WALL-MOUNT CANOPY HOODS

JXW8536DS – 36" x 24<sup>5</sup>/<sub>8</sub>" x 42<sup>5</sup>/<sub>8</sub>" x 19<sup>1</sup>/<sub>16</sub>"

~~JXW8530DS – 30" x 24<sup>5</sup>/<sub>8</sub>" x 42<sup>5</sup>/<sub>8</sub>" x 19<sup>1</sup>/<sub>16</sub>"~~

### OPENING/CLEARANCE DIMENSIONS



FRONT VIEW

MODEL #		JXW8736DS		JXW8530DS	
		in	cm	in	cm
A	Width of entry location for vent and power supply – ceiling option (min.-max.)	10-13	25.4-33.0	10-13	25.4-33.0
B	Width of entry location for vent and power supply – wall option (min.-max.)	10-13	25.4-33.0	10-13	25.4-33.0
C	Width of cabinet opening (min.)	36	91.4	30	76.2
D	Minimum height from entry location to ceiling for vent and power supply – wall option (vented installation)	2	5.1	2	5.1
	Minimum height from entry location to ceiling for vent and power supply – wall option (non-vented installation)	9	22.9	9	22.9
E	Height from hood to entry location for vent and power supply – wall option (min.)	17	43.2	17	43.2
F	Suggested distance from hood to electric cooking surface (min.-max.)	24-36	61.0-91.4	24-36	61.0-91.4
	Suggested distance from hood to gas cooking surface (min.-max.)	27-36	68.6-91.4	27-36	68.6-91.4
G	Height from upper cabinet to countertop (min.)	18	45.7	18	45.7
H	Depth of entry location for vent and power supply – ceiling option	9½	24.1	9½	24.1
v	Recommended vent and power supply entry location				

### ELECTRICAL REQUIREMENTS

120 volt, 60 Hz, AC only, 15-amp fused, electrical circuit is required.

### VENTING REQUIREMENTS

The hood is factory set for venting through the roof or wall. For non-vented (recirculating) installation, refer to recirculation kit instructions for further information.

### LOCATION REQUIREMENTS

Mounting structure must be able to support 60 lb (27.2 kg).

For vented installation, the chimney can be adjusted for ceilings between 7' 1" (2.16 m) and 9' 2" (2.79 m).

For non-vented (recirculating) installation, the chimney can be adjusted for ceilings between 7' 1" (2.16 m) and 9' 6" (2.90 m).

**IMPORTANT:** Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

**JENN-AIR®**


8316AdZw1114

K6-76

JAN 12, 2017

Elevation A • 2,951 sq.ft.

Elevation B • 2,954 sq.ft.



GROUND FLOOR  
ELEVATION A

STRUCTURAL

LOT 76


PR

SEPT. 6. 2016

COLOURS




PR

JAN 12, 2017



Elevation A • 2,951 sq.ft.

Elevation B • 2,954 sq.ft.



STRUCTURAL

LOT 76


AP

AUG. 17, 2016

COLOURS

AP

JAN. 12, 2017



STRUCTURAL  
LOT 76

PK

AUG. 17, 2016

COLOURS

PK

JAN 12, 2017

# GOLDPARK

WORTH MORE™

Attention: Building Department

Re: Lot # 76

This is to acknowledge that as the purchaser of the above noted lot, I have asked Gold Park Homes not to install the standard builder's kitchen exhaust hood, as I will be installing my own unit after closing.



Purchaser



Vendor

Dated this 12<sup>th</sup> day of JANUARY, 20 17.

# CORTINA

KITCHENS INC.

70 Regina Road Woodbridge ON L4L 8L6  
905-264-6464

## INFORMATION - PVC DOORS

Builder: Gold Park Homes Project: KLEVER GLEN Lot #: 76

All cabinets with PVC (Thermofoil) Doors come with melamine gables, panels and kick. The doors, crown moulding and light valance are PVC wrapped. Open shelves incorporated in design will only be available with melamine interiors. There will be variations in colour shades between the PVC parts (doors, crown and Light valance) and the melamine parts (open shelves, Gables, Panels and Kick) due to the difference in material.

Furring Panel with crown moulding to the ceiling is not available on all PVC door styles due to subtle variations in colour shades between the PVC parts (moulding) and the melamine parts (furring panel) due to the difference in material. Grain directions in wood grain pattern melamine, vary between the furring panel, crown moulding (horizontal) and the PVC doors (vertical).

Thank you for your understanding.

---

I am well informed of this information, and agree to the purchase of the above.

Purchaser: Liaison

Date: JAN. 12. 2017