


Schedule 1: Designer Information

Use one form for each individual who reviews and takes responsibility for design activities with respect to the project.

A. Project Information			
Building number, street name		Unit no.	Lot/con.
Municipality VAUGHAN (WOODBIDGE)	Postal code	Plan number/ other description	
B. Individual who reviews and takes responsibility for design activities			
Name MICHAEL O'ROURKE		Firm HVAC DESIGNS LTD.	
Street address 375 FINLEY AVE		Unit no. 202	Lot/con. N/A
Municipality AJAX	Postal code L1S 2E2	Province ONTARIO	E-mail info@hvacdsgns.ca
Telephone number (905) 619-2300	Fax number (905) 619-2375	Cell number ()	
C. Design activities undertaken by individual identified in Section B. [Building Code Table 3.5.2.1 OF Division C]			
☐ House ☐ Small Buildings ☐ Large Buildings ☐ Complex Buildings			
☒ HVAC – House ☐ Building Services ☐ Detection, Lighting and Power ☐ Fire Protection			
☐ Building Structural ☐ Plumbing – House ☐ Plumbing – All Buildings ☐ On-site Sewage Systems			
Description of designer's work HEAT LOSS / GAIN CALCULATIONS DUCT SIZING RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY RESIDENTIAL SYSTEM DESIGN per CSA-F280-12		Model: 5003 - THE OAKGROVE LOT 91 WOB Project: PINE VALLEY & TESTON	
D. Declaration of Designer			
I <u>MICHAEL O'ROURKE</u> (print name)		declare that (choose one as appropriate):	
☐ I review and take responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Division C, of the Building Code. I am qualified, and the firm is registered, in the appropriate classes/categories. Individual BCIN: _____ Firm BCIN: _____			
☒ I review and take responsibility for the design and am qualified in the appropriate category as an "other designer" under subsection 3.2.5. of Division C, of the Building Code. Individual BCIN: <u>19669</u> Basis for exemption from registration and qualification: <u>O.B.C SENTENCE 3.2.4.1 (4)</u>			
☐ The design work is exempt from the registration and qualification requirements of the Building Code. Basis for exemption from registration and qualification: _____			
I certify that:			
1. The information contained in this schedule is true to the best of my knowledge. 2. I have submitted this application with the knowledge and consent of the firm.			
April 30, 2019			
Date		Signature of Designer	

NOTE:

- For the purposes of this form, "individual" means the "person" referred to in Clause 3.2.4.7(1) d) of Division C, Article 3.2.5.1. of Division C, and all other persons who are exempt from qualification under Subsections 3.2.4. and 3.2.5. of Division C.
- Schedule 1 is not required to be completed by a holder of a license, temporary license, or a certificate of authorization, issued by the Ontario Association of Architects. Schedule 1 is also not required to be completed by a holder of a license to practise, a limited license to practise, or a certificate of authorization, issued by the Association of Professional Engineers of Ontario.

SITE NAME: PINE VALLEY & TESTON DATE: Apr-19 WINTER NATURAL AIR CHANGE RATE 0.407 HEAT LOSS AT °F. 76 CSA-F280-12
BUILDER: GOLD PARK HOMES TYPE: 6003 - THE OAKGROVE GFA: 3554 LOT 91 WOB LO# 82131 SUMMER NATURAL AIR CHANGE RATE 0.148 HEAT GAIN AT °F. 16 SB-12 PACKAGE A1

ROOM USE	MBR	ENS	WIC	BED-2	BED-3	DEN	BATH	LOUNGE	LAUN	ENS-2	BED-4
EXP. WALL	38	14	12	11	31	27	13	16	8	8	28
CLG. HT.	10	9	9	9	9	9	9	9	9	9	9
FACTORS											
GRS.WALL AREA	380	126	108	99	279	243	117	144	72	72	252
GLAZING											
NORTH	0	0	0	0	0	0	0	0	0	0	0
EAST	0	0	0	0	0	0	0	0	0	0	0
SOUTH	0	0	0	0	0	0	0	0	0	0	0
WEST	0	0	0	0	0	0	0	0	0	0	0
SKYLT.	44	19	404	805	0	28	596	1187	0	0	0
DOORS	37.2	103.0	0	0	0	0	0	0	0	0	0
NET EXPOSED WALL	4.5	0.9	336	1499	312	107	478	99	108	482	100
NET EXPOSED BSMT WALL ABOVE OR	3.6	0.7	0	0	0	0	0	0	0	0	0
NO ATTIC EXPOSED CLG	1.3	0.6	255	327	163	196	252	125	203	261	130
EXPOSED FLOOR	0	0	0	0	0	0	0	0	0	0	0
BASEMENT/CRAWL HEAT LOSS	0	0	0	0	0	0	0	0	0	0	0
SLAB ON GRADE HEAT LOSS	0	0	0	0	0	0	0	0	0	0	0
SUBTOTAL HT LOSS	2763	1133	1030	1041	2629	1789	1503	1436	923	688	2178
SUB TOTAL HT GAIN	0.20	0.38	0.20	0.38	0.20	0.38	0.20	0.38	0.20	0.38	0.20
LEVEL FACTOR / MULTIPLIER	1044	428	280	393	993	676	483	643	260	260	823
AIR CHANGE HEAT LOSS	205	90	20	46	269	132	135	81	28	28	182
AIR CHANGE HEAT GAIN	0	0	0	0	0	0	0	0	0	0	0
DUCT LOSS	0	0	0	0	0	0	0	0	0	0	0
DUCT GAIN	0	0	0	0	0	0	0	0	0	0	0
HEAT GAIN PEOPLE	2	480	0	1	240	0	0	0	0	0	1
HEAT GAIN APPLIANCES/LIGHTS	609	1561	1023	1434	609	609	609	609	609	609	609
TOTAL HT LOSS BTU/H	3807	1561	1023	1434	3623	2465	1761	1979	948	948	3001
TOTAL HT GAIN x 1.3 BTU/H	4724	1456	325	1847	5439	2917	2183	2097	1240	448	4045

ROOM USE	DIN	LIV	KT/GT	FOY	MUD	WOB	BAS
EXP. WALL	16	31	31	30	31	60	142
CLG. HT.	11	11	11	11	12	10	10
FACTORS							
GRS.WALL AREA	176	341	1034	330	372	600	994
GLAZING							
NORTH	0	0	0	0	0	0	0
EAST	0	0	0	0	0	0	0
SOUTH	0	0	0	0	0	0	0
WEST	0	0	0	0	0	0	0
SKYLT.	25.2	103.0	0	0	0	0	0
DOORS	25.2	5.2	0	0	0	0	0
NET EXPOSED WALL	4.5	0.9	150	505	20	0	0
NET EXPOSED BSMT WALL ABOVE OR	3.6	0.7	0	0	0	0	0
NO ATTIC EXPOSED CLG	1.3	0.6	255	327	163	196	252
EXPOSED FLOOR	0	0	0	0	0	0	0
BASEMENT/CRAWL HEAT LOSS	0	0	0	0	0	0	0
SLAB ON GRADE HEAT LOSS	0	0	0	0	0	0	0
SUBTOTAL HT LOSS	1223	2429	8970	2225	2227	892	5146
SUB TOTAL HT GAIN	0.30	0.54	0.30	0.54	0.30	0.54	0.50
LEVEL FACTOR / MULTIPLIER	664	1320	4872	1208	1210	4516	16467
AIR CHANGE HEAT LOSS	71	193	907	107	50	0	457
AIR CHANGE HEAT GAIN	0	0	0	0	0	0	0
DUCT LOSS	0	0	0	0	0	0	0
DUCT GAIN	0	0	0	0	0	0	0
HEAT GAIN PEOPLE	240	609	609	0	0	0	0
HEAT GAIN APPLIANCES/LIGHTS	1887	3749	13842	3433	3437	6379	20602
TOTAL HT LOSS BTU/H	1935	3911	15430	1728	1605	5871	2292

TOTAL HEAT GAIN BTU/H: 60155 TONS: 5.01 TOTAL COMBINED HEAT LOSS BTU/H: 79061

32131

AFUE = 96 %
INPUT (BTU/H) = 110,000
OUTPUT (BTU/H) = 106,000

adjusted pressure r/a 0.15

[illegible]

	25	26	27	28	29	30	31	32	33	34
RUN #										
ROOM NAME	BAS	BAS	BAS	ENS	BED-3	BED-3	BED-4	LIV	ENS	BAS
RM LOSS MBH	3.37	3.37	3.37	0.78	1.21	1.21	1.50	1.87	0.78	3.37
CFM PER RUN HEAT	87	87	87	20	31	31	39	48	20	87
RM GAIN MBH	1.02	1.02	1.02	0.73	1.81	1.81	2.02	1.96	0.73	1.02
CFM PER RUN COOLING	34	34	34	24	60	60	66	64	24	34
ADJUSTED PRESSURE	0.16	0.16	0.16	0.17	0.17	0.17	0.17	0.17	0.17	0.16
ACTUAL DUCT LGH	21	23	36	38	52	56	43	34	37	27
EQUIVALENT LENGTH	180	100	130	160	145	155	190	100	195	190
TOTAL EFFECTIVE LENGTH	201	123	166	198	197	211	233	134	232	217
ADJUSTED PRESSURE	0.08	0.13	0.1	0.09	0.09	0.08	0.07	0.13	0.07	0.07
ROUND DUCT SIZE	6	5	5	4	6	6	5	4	4	6
HEATING VELOCITY (ft/min)	444	639	639	229	158	158	286	551	229	444
COOLING VELOCITY (ft/min)	173	250	250	275	306	306	485	734	275	173
OUTLET GRILL SIZE	4X10	3X10	3X10	3X10	4X10	4X10	3X10	3X10	3X10	4X10
TRUNK	F	F	D	F	E	E	D	D	F	B

SUPPLY AIR TRUNK SIZE										RETURN AIR TRUNK SIZE												
TRUNK			STATIC PRESS.	ROUND DUCT	RECT DUCT	VELOCITY (ft/min)	TRUNK			STATIC PRESS.	ROUND DUCT	RECT DUCT	VELOCITY (ft/min)	TRUNK			STATIC PRESS.	ROUND DUCT	RECT DUCT	VELOCITY (ft/min)		
CFM							CFM							CFM								
TRUNK A	414	0.07	10.4	12	X	8	TRUNK G	0	0.00	0	0	X	8	0	TRUNK O	0	0.06	0	0	X	8	0
TRUNK B	714	0.07	12.8	20	X	8	TRUNK H	0	0.00	0	0	X	8	0	TRUNK P	0	0.06	0	0	X	8	0
TRUNK C	1154	0.07	15.3	28	X	8	TRUNK I	0	0.00	0	0	X	8	0	TRUNK Q	0	0.06	0	0	X	8	0
TRUNK D	394	0.07	10.2	12	X	8	TRUNK J	0	0.00	0	0	X	8	0	TRUNK R	0	0.06	0	0	X	8	0
TRUNK E	798	0.07	13.3	20	X	8	TRUNK K	0	0.00	0	0	X	8	0	TRUNK S	0	0.06	0	0	X	8	0
TRUNK F	372	0.07	10	12	X	8	TRUNK L	0	0.00	0	0	X	8	0	TRUNK T	0	0.06	0	0	X	8	0

[illegible]

TYPE: 5003 - THE OAKGROVE
SITE NAME: PINE VALLEY & TESTON

LO # 82131
LOT 91 WOB

RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY

COMBUSTION APPLIANCES		9.32.3.1(1)
a)	☒ Direct vent (sealed combustion) only	
b)	☐ Positive venting induced draft (except fireplaces)	
c)	☐ Natural draft, B-vent or induced draft gas fireplace	
d)	☐ Solid Fuel (including fireplaces)	
e)	☐ No Combustion Appliances	

HEATING SYSTEM	
☒ Forced Air	☐ Non Forced Air
☐ Electric Space Heat	

HOUSE TYPE		9.32.1(2)
☒ I	Type a) or b) appliance only, no solid fuel	
☐ II	Type I except with solid fuel (including fireplaces)	
☐ III	Any Type c) appliance	
☐ IV	Type I, or II with electric space heat	
☐	Other: Type I, II or IV no forced air	

SYSTEM DESIGN OPTIONS		O.N.H.W.P.
☐ 1	Exhaust only/Forced Air System	
☐ 2	HRV with Ducting/Forced Air System	
☒ 3	HRV Simplified/connected to forced air system	
☐ 4	HRV with Ducting/non forced air system	
☐	Part 6 Design	

TOTAL VENTILATION CAPACITY		9.32.3.3(1)
Basement + Master Bedroom	<u>2</u> @ 21.2 cfm <u>42.4</u> cfm	
Other Bedrooms	<u>3</u> @ 10.6 cfm <u>31.8</u> cfm	
Kitchen & Bathrooms	<u>5</u> @ 10.6 cfm <u>53</u> cfm	
Other Rooms	<u>8</u> @ 10.6 cfm <u>84.8</u> cfm	
Table 9.32.3.A.	TOTAL <u>212.0</u> cfm	

PRINCIPAL VENTILATION CAPACITY REQUIRED		9.32.3.4.(1)
1 Bedroom	31.8 cfm	
2 Bedroom	47.7 cfm	
3 Bedroom	63.6 cfm	
4 Bedroom	79.5 cfm	
5 Bedroom	95.4 cfm	
TOTAL 79.5 cfm		

SUPPLEMENTAL VENTILATION CAPACITY		9.32.3.5.
Total Ventilation Capacity	<u>212</u> cfm	
Less Principal Ventil. Capacity	<u>155</u> cfm	
Required Supplemental Capacity	<u>57.0</u> cfm	

PRINCIPAL EXHAUST FAN CAPACITY	
Model: VANEE 65H	Location: BSMT
<u>155.0</u> cfm	<u>3.0</u> sones ☒ HVI Approved

PRINCIPAL EXHAUST HEAT LOSS CALCULATION	
CFM	ΔT °F
155.0 CFM X	76 F X
	FACTOR 1.08 X
	% LOSS 0.25

SUPPLEMENTAL FANS		NUTONE	
Location	Model	cfm	HVI
ENS	QTXEN050C	50	☒
BATH	QTXEN050C	50	☒
ENS-2	QTXEN050C	50	☒
PWD	QTXEN050C	50	☒

HEAT RECOVERY VENTILATOR		9.32.3.11.
Model: VANEE 65H		
<u>155</u> cfm high	<u>64</u> cfm low	
<u>75</u> % Sensible Efficiency	☒ HVI Approved	
@ 32 deg F (0 deg C)		

LOCATION OF INSTALLATION	
Lot:	Concession
Township	Plan:
Address	
Roll #	Building Permit #

BUILDER: GOLD PARK HOMES	
Name:	
Address:	
City:	
Telephone #:	Fax #:

INSTALLING CONTRACTOR	
Name:	
Address:	
City:	
Telephone #:	Fax #:

DESIGNER CERTIFICATION	
I hereby certify that this ventilation system has been designed in accordance with the Ontario Building Code.	
Name:	HVAC Designs Ltd.
Signature:	
HRAI #	001820
Date:	April-19

CSA F280-12 Residential Heat Loss and Heat Gain Calculations																																																																																			
Formula Sheet (For Air Leakage / Ventilation Calculation)																																																																																			
LO#: 82131	Model: 5003 - THE OAKGROVE	Builder: GOLD PARK HOMES	Date: 4/30/2019																																																																																
Volume Calculation		Air Change & Delta T Data																																																																																	
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th>House Volume</th> <th>Floor Area (ft²)</th> <th>Floor Height (ft)</th> <th>Volume (ft³)</th> </tr> <tr> <td>Level</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Bsmt</td> <td>1750</td> <td>10</td> <td>17500</td> </tr> <tr> <td>First</td> <td>1750</td> <td>11</td> <td>19250</td> </tr> <tr> <td>Second</td> <td>2125</td> <td>9</td> <td>19125</td> </tr> <tr> <td>Third</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td>Fourth</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td>Total:</td> <td></td> <td></td> <td>55,875.0 ft³</td> </tr> <tr> <td>Total:</td> <td></td> <td></td> <td>1582.2 m³</td> </tr> </table>		House Volume	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)	Level				Bsmt	1750	10	17500	First	1750	11	19250	Second	2125	9	19125	Third	0	9	0	Fourth	0	9	0	Total:			55,875.0 ft³	Total:			1582.2 m³	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th colspan="4">WINTER NATURAL AIR CHANGE RATE</th> </tr> <tr> <td></td> <td></td> <td></td> <td>0.407</td> </tr> <tr> <th colspan="4">SUMMER NATURAL AIR CHANGE RATE</th> </tr> <tr> <td></td> <td></td> <td></td> <td>0.148</td> </tr> </table> <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th colspan="4">Design Temperature Difference</th> </tr> <tr> <th></th> <th>Tin °C</th> <th>Tout °C</th> <th>ΔT °C</th> </tr> <tr> <td>Winter DTDh</td> <td>22</td> <td>-20</td> <td>42</td> </tr> <tr> <td>Summer DTDc</td> <td>22</td> <td>31</td> <td>9</td> </tr> <tr> <td></td> <td></td> <td></td> <td>ΔT °F</td> </tr> <tr> <td></td> <td></td> <td></td> <td>76</td> </tr> <tr> <td></td> <td></td> <td></td> <td>16</td> </tr> </table>		WINTER NATURAL AIR CHANGE RATE							0.407	SUMMER NATURAL AIR CHANGE RATE							0.148	Design Temperature Difference					Tin °C	Tout °C	ΔT °C	Winter DTDh	22	-20	42	Summer DTDc	22	31	9				ΔT °F				76				16
House Volume	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)																																																																																
Level																																																																																			
Bsmt	1750	10	17500																																																																																
First	1750	11	19250																																																																																
Second	2125	9	19125																																																																																
Third	0	9	0																																																																																
Fourth	0	9	0																																																																																
Total:			55,875.0 ft³																																																																																
Total:			1582.2 m³																																																																																
WINTER NATURAL AIR CHANGE RATE																																																																																			
			0.407																																																																																
SUMMER NATURAL AIR CHANGE RATE																																																																																			
			0.148																																																																																
Design Temperature Difference																																																																																			
	Tin °C	Tout °C	ΔT °C																																																																																
Winter DTDh	22	-20	42																																																																																
Summer DTDc	22	31	9																																																																																
			ΔT °F																																																																																
			76																																																																																
			16																																																																																
6.2.6 Sensible Gain due to Air Leakage																																																																																			
$HG_{salb} = LR_{airc} \times \frac{V_b}{3.6} \times DTD_c \times 1.2$																																																																																			
0.407	x	439.50	x																																																																																
		9 °C	x																																																																																
		1.2	=																																																																																
			686 W																																																																																
			=																																																																																
			2340 Btu/h																																																																																
6.2.7 Sensible heat Gain due to Ventilation																																																																																			
$HL_{vaibrb} = PVC \times DTD_h \times 1.08 \times (1 - E)$																																																																																			
155 CFM	x	16 °F	x																																																																																
		1.08	x																																																																																
		0.25	=																																																																																
			661 Btu/h																																																																																
5.2.3.3 Calculation of Air Change Heat Loss for Each Room (Floor Multiplier Section)																																																																																			
$HL_{airrr} = Level Factor \times HL_{airbv} \times \{(HL_{agcr} + HL_{bgcr}) \div (HL_{agclevel} + HL_{bgclevel})\}$																																																																																			
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th>Level</th> <th>Level Factor (LF)</th> <th>HLairbv Air Leakage + Ventilation Heat Loss (Btu/h)</th> <th>Level Conductive Heat Loss: (HL_{clevel})</th> <th>Air Leakage Heat Loss Multiplier (LF x HLairbv / HL_{clevel})</th> </tr> <tr> <td>1</td> <td>0.5</td> <td rowspan="5" style="text-align: center; vertical-align: middle;">30,914</td> <td>10,632</td> <td>1.454</td> </tr> <tr> <td>2</td> <td>0.3</td> <td>17,074</td> <td>0.543</td> </tr> <tr> <td>3</td> <td>0.2</td> <td>16,368</td> <td>0.378</td> </tr> <tr> <td>4</td> <td>0</td> <td>0</td> <td>0.000</td> </tr> <tr> <td>5</td> <td>0</td> <td>0</td> <td>0.000</td> </tr> </table>				Level	Level Factor (LF)	HLairbv Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{clevel})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HL _{clevel})	1	0.5	30,914	10,632	1.454	2	0.3	17,074	0.543	3	0.2	16,368	0.378	4	0	0	0.000	5	0	0	0.000																																																						
Level	Level Factor (LF)	HLairbv Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{clevel})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HL _{clevel})																																																																															
1	0.5	30,914	10,632	1.454																																																																															
2	0.3		17,074	0.543																																																																															
3	0.2		16,368	0.378																																																																															
4	0		0	0.000																																																																															
5	0		0	0.000																																																																															
*HLairbv = Air leakage heat loss + ventilation heat loss *For a balanced or supply only ventilation system HLairve = 0																																																																																			

HEAT LOSS AND GAIN SUMMARY SHEET

MODEL: 5003 - THE OAKGROVE	LOT 91 WOB	BUILDER: GOLD PARK HOMES
SFQT: 3854	LO# 82131	SITE: PINE VALLEY & TESTON

DESIGN ASSUMPTIONS

HEATING	°F	COOLING	°F
OUTDOOR DESIGN TEMP.	-4	OUTDOOR DESIGN TEMP.	88
INDOOR DESIGN TEMP.	72	INDOOR DESIGN TEMP. (MAX 75°F)	72

BUILDING DATA

ATTACHMENT:	DETACHED	# OF STORIES (+BASEMENT):	3
FRONT FACES:	EAST	ASSUMED (Y/N):	Y
AIR CHANGES PER HOUR:	3.57	ASSUMED (Y/N):	Y
AIR TIGHTNESS CATEGORY:	AVERAGE	ASSUMED (Y/N):	Y
WIND EXPOSURE:	SHELTERED	ASSUMED (Y/N):	Y
HOUSE VOLUME (ft³):	55875.0	ASSUMED (Y/N):	Y
INTERNAL SHADING:	BLINDS/CURTAINS	ASSUMED OCCUPANTS:	5
INTERIOR LIGHTING LOAD (Btu/h/ft²):	1.30	DC BRUSHLESS MOTOR (Y/N):	Y
FOUNDATION CONFIGURATION	BCIN_1	DEPTH BELOW GRADE:	7.0 ft
LENGTH: 61.0 ft	WIDTH: 40.0 ft	EXPOSED PERIMETER:	142.0 ft
WOB INSULATION CONFIGURATION	SCB_9	WOB EXPOSED PERIMETER	60.0 ft

2012 OBC - COMPLIANCE PACKAGE	Compliance Package	
	A1	
	Nominal	Min. Eff.
Ceiling with Attic Space Minimum RSI (R)-Value	60	59.22
Ceiling Without Attic Space Minimum RSI (R)-Value	31	27.65
Exposed Floor Minimum RSI (R)-Value	31	29.80
Walls Above Grade Minimum RSI (R)-Value	22	17.03
Basement Walls Minimum RSI (R)-Value	20 ci	21.12
Below Grade Slab Entire surface > 600 mm below grade Minimum RSI (R)-Value	-	-
Edge of Below Grade Slab ≤ 600 mm Below Grade Minimum RSI (R)-Value	10	10
Heated Slab or Slab ≤ 600 mm below grade Minimum RSI (R)-Value	10	11.13
Windows and Sliding Glass Doors Maximum U-Value	0.28	-
Skylights Maximum U-Value	0.49	-
Space Heating Equipment Minimum AFUE	0.96	-
HRV Minimum Efficiency	75%	-
Domestic Hot Water Heater Minimum EF	0.8	-


INDIVIDUAL BCIN: 19669

MICHAEL O'ROURKE



Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280


Weather Station Description		
Province:	Ontario	
Region:	Vaughan (Woodbridge)	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Floor Length (m):	6.1	 Insulation Configuration
Floor Width (m):	12.2	
Exposed Perimeter (m):	43.3	
Wall Height (m):	3.0	
Depth Below Grade (m):	1.87	
Window Area (m ²):	1.1	
Door Area (m ²):	1.9	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Foundation Loads		
Heating Load (Watts):		836

TYPE: 5003 - THE OAKGROVE
LO# 82131

LOT 91 WOB

Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description		
Province:	Ontario	
Region:	Vaughan (Woodbridge)	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Length (m):	3.0	 Insulation Configuration
Width (m):	12.2	
Exposed Perimeter (m):	18.3	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Results		
Heating Load (Watts):		261

TYPE: 5003 - THE OAKGROVE
LO# 82131

LOT 91 WOB


Air Infiltration Residential Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description			
Province:	Ontario		
Region:	Vaughan (Woodbridge)		
Weather Station Location:	Open flat terrain, grass		
Anemometer height (m):	10		
Local Shielding			
Building Site:	Suburban, forest		
Walls:	Heavy		
Flue:	Heavy		
Highest Ceiling Height (m):	9.14		
Building Configuration			
Type:	Detached		
Number of Stories:	Two		
Foundation:	Full		
House Volume (m ³):	1582.2		
Air Leakage/Ventilation			
Air Tightness Type:	Present (1961-) (3.57 ACH)		
Custom BDT Data:	ELA @ 10 Pa.	2109.1 cm ²	
	3.57	ACH @ 50 Pa	
Mechanical Ventilation (L/s):	Total Supply	Total Exhaust	
	73.2	73.2	
Flue Size			
Flue #:	#1	#2	#3 #4
Diameter (mm):	0	0	0 0
Natural Infiltration Rates			
Heating Air Leakage Rate (ACH/H):	0.407		
Cooling Air Leakage Rate (ACH/H):	0.148		

TYPE: 5003 - THE OAKGROVE
LO# 82131

LOT 91 WOB



I MICHAEL O'ROURKE HAVE REVIEW AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C.3.2.5 OF THE BUILDING CODE.


Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

WOB
CSA-F280-12
PACKAGE A1

HVAC LEGEND							3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.	
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS	

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client		HVACDESIGNS LTD. 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.	HEAT LOSS 79061 BTU/H		# OF RUNS S/A R/A FANS			Sheet Title	
GOLD PARK HOMES			UNIT DATA		3RD FLOOR			BASEMENT	
Project Name PINE VALLEY & TESTON VAUGHAN, ONTARIO			MAKE LENNOX		2ND FLOOR 16 5 4			Date	
			MODEL EL296UH110XE60C		1ST FLOOR 10 3 2			Scale	
			INPUT 110 MBTU/H		BASEMENT 1 0			BCIN# 19669	
THE OAKGROVE WOB 5003 LOT 91 3854 sqft		OUTPUT 106 MBTU/H		ALL S/A DIFFUSERS 4 "x10" UNLESS NOTED OTHERWISE ON LAYOUT. ALL S/A RUNS 5"Ø UNLESS NOTED OTHERWISE ON LAYOUT. UNDERCUT DOORS 1" min. FOR R/A			LO# 82131		
		COOLING 5.0 TONS							
		FAN SPEED 1955 cfm @ 0.6" w.c.							



I MICHAEL O'ROURKE HAVE REVIEW AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C.32.3 OF THE BUILDING CODE.

Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

GROUND FLOOR PLAN ELEV. 'C'

WOB
CSA-F280-12
PACKAGE A1

HVAC LEGEND						3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	2.
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	1.
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	No. Description Date
REVISIONS								

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client
GOLD PARK HOMES

Project Name
**PINE VALLEY & TESTON
VAUGHAN, ONTARIO**

THE OAKGROVE WOB
5003 LOT 91 3854 sqft

HVACDESIGNS LTD.

375 Finley Ave. Suite 202 - Ajax, Ontario
L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375
Email: info@hvacdesigns.ca
Web: www.hvacdesigns.ca

Specializing in Residential Mechanical Design Services

Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.


Sheet Title
**FIRST FLOOR
HEATING
LAYOUT**

Date **APRIL/2019**

Scale **3/16" = 1'-0"**

BCIN# 19669

LO# 82131



SECOND FLOOR PLAN ELEV. 'C'

I MICHAEL O'ROURKE HAVE REVIEWED AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C, 32.5 OF THE BUILDING CODE.

Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

WOB
CSA-F280-12
PACKAGE A1

HVAC LEGEND							3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.	
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS	

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client GOLD PARK HOMES		 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services	Sheet Title SECOND FLOOR HEATING LAYOUT	
Project Name PINE VALLEY & TESTON VAUGHAN, ONTARIO			Date APRIL/2019	
THE OAKGROVE WOB 5003 LOT 91 3854 sqft		Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.	Scale 3/16" = 1'-0"	
			BCIN# 19669	
			LO#	82131