



CITY OF BRAMPTON – BUILDING DIVISION


ROOF TRUSSES

APPLICATION NO.:	19-567627 000 00 CM	FOLDER TYP.:	CM
DESCRIPTION OF PROJECT:	PLAN M2039	SUB TYP.:	Semi Detached Dwelling
BUILDERS NAME:	GOLD PARK HOMES		
PLAN NUMBER:		MODEL NAME:	2017/SD-09

CERTIFIED MODEL DOCUMENTS

PAGES:	DESCRIPTION OF DOCUMENTS		
B	ROOF TRUSS LAYOUTS & COMPONENTS:		
	ELEVATION	DESCRIPTION:	COMMENTS
2			
3			
			
			
			
			
ENTERED BY:		DATE:	yyyy/mm/dd

E19072226-E19072230
E19072240
E19072367-E19072368
E19112570-E19112580



All work shall conform to the Ontario Building Code O. Reg. 332/12 as amended
For conventional framing roof / ceilings framing shall conform to OBC.9.23

CITY OF BRAMPTON
BUILDING DIVISION
REVIEWED
DEC 10 2019
BY
MAY FRENETTE

FIRM BCIN 113884
DESIGNER BCIN 25593

ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 O.B.C. LATEST EDITION. ROOF RAFTERS THAT CROSS OVER TRUSSES TO BE 2X4 SPF #2 @ 24" O.C WITH A VERT. POST TO THE TRUSS UNDERNEATH AT EACH CROSS POINT. VERT. POSTS LONGER THAN 6' TO HAVE LATERAL BRACING SO THAT THE DISTANCE BETWEEN END POINTS & BETWEEN ROWS OF BRACING DOES NOT EXCEED 6'

CONVENTIONAL FRAMING BY OTHERS



Job Track: 39002
Layout ID: 313997
Plan Log: 104423

Builder / Location:
GOLD PARK HOMES / BRAMPTON
Project: **MCLAUGHLIN AND MAYFIELD**
Date: 10/23/2019 Designer: AMANDA

Model / Elevation:
SD-09 / A/B

THESE DRAWINGS CONSTITUTE THE PROPERTY OF ALPA ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY ALPA ROOF TRUSSES INC AND WILL BE RETRACTED BY ALPA ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mike V. 8.2.0

EWP DESIGN INC.

(905) 832-2250

FAX (905) 832-0286

RESPONSIBILITIES AND SPECIFICATIONS


RESPONSIBILITIES

1. EWP DESIGN INC. is responsible for the design of trusses as individual components.
2. It is the responsibility of others to ascertain that the design loads utilized on each drawing meet or exceed the actual dead load imposed by the structure, the live load imposed by the intended use and the snow load imposed by local building code or authorities with jurisdictions.
3. All dimensions are to be verified by the owner, contractor, architect or other authorities with jurisdictions before truss fabrication.
4. EWP DESIGN INC. bears no responsibility for the erection of trusses. Persons erecting trusses are cautioned to seek professional advice regarding the temporary and permanent bracing for the system. Bracing shown on EWP DESIGN INC. drawing is specified for the truss as a component only and forms an integral part of the truss design.
5. It is the truss manufacturer's responsibility to ensure that trusses are manufactured in conformance with specifications of EWP DESIGN INC. as outlined below.

SPECIFICATIONS

1. Trusses designed by EWP DESIGN INC. conform to the relevant section of the Ontario Building Code of Canada (Part 9 or Part 4) or to the Canadian code for farm buildings, whichever applies to the building type, as indicated on the EWP DESIGN INC. drawings, and conform to the design procedures established by the Truss Plate Institute of Canada. Unit stresses used for truss designs are as per the edition of CSA-O86 shown on EWP DESIGN INC. drawings.
2. Lumber is to be the size, species and grade as specified on EWP DESIGN INC. drawings.
3. Moisture content of lumber shall not exceed 19% in service unless specified otherwise.
4. Metal connector plates shall be applied to both faces of truss at each joint and shall be positioned as specified.
5. Top chords of trusses are assumed to be continuously braced laterally by roof sheathing or by purlins at intervals not exceeding 12.5 times the thickness of top chord member.
6. Bottom chords shall be laterally braced at intervals not exceeding 3M (10') o.c., where rigid ceiling is not applied directly to the underside of chords.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF EWP DESIGN INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY THE ALPA LUMBER GROUP, AND WILL BE RETRACTED BY EWP DESIGN INC. IF UTILIZED FOR ANY OTHER PURPOSE.



LUMBER N. L. G. A. RULES CHORDS SIZE A - D 2x4 DRY B - E 2x4 DRY DRY: SEASONED LUMBER.				LUMBER No.2 No.2		DESCR. SPF SPF	
PLATES (table is in inches) JT TYPE PLATES W LEN Y X B TMBH1-I MT20 3.0 4.0 1.50 0.50							

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS <table><tr><td></td><td colspan="2">FACTORED GROSS REACTION</td><td colspan="2">MAXIMUM FACTORED GROSS REACTION</td><td>INPUT BRG</td><td>REQRD BRG</td><td>HEEL</td></tr><tr><td>JT</td><td>VERT</td><td>HORZ</td><td>DOWN</td><td>HORZ</td><td>UPLIFT</td><td>IN-SX</td><td>IN-SX</td><td>WEDGE</td></tr><tr><td>B</td><td>222</td><td>0</td><td>222</td><td>0</td><td>0</td><td>4-0</td><td>1-8</td><td>2x4 L</td></tr><tr><td>F</td><td>46</td><td>0</td><td>46</td><td>0</td><td>0</td><td>5-8</td><td>1-8</td><td></td></tr><tr><td>C</td><td>137</td><td>0</td><td>137</td><td>0</td><td>0</td><td>5-8</td><td>5-8</td><td></td></tr></table> BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): C UNFACTORED REACTIONS <table><tr><td></td><td>1ST LCASE</td><td colspan="6">MAX/MIN. COMPONENT REACTIONS</td></tr><tr><td>JT</td><td>COMBINED</td><td>SNOW</td><td>LIVE</td><td>PERM.LIVE</td><td>WIND</td><td>DEAD</td><td>SOIL</td></tr><tr><td>B</td><td>155</td><td>111 / 0</td><td>0 / 0</td><td>0 / 0</td><td>0 / 0</td><td>44 / 0</td><td>0 / 0</td></tr><tr><td>F</td><td>35</td><td>10 / 0</td><td>0 / 0</td><td>0 / 0</td><td>0 / 0</td><td>25 / 0</td><td>0 / 0</td></tr><tr><td>C</td><td>95</td><td>73 / 0</td><td>0 / 0</td><td>0 / 0</td><td>0 / 0</td><td>22 / 0</td><td>0 / 0</td></tr></table> BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, C BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (5) <table><tr><td colspan="4">CHORDS</td><td colspan="4">WEBS</td></tr><tr><td>MEMB.</td><td>MAX. FACTORED FORCE (LBS)</td><td>FACTORED VERT. LOAD (PLF)</td><td>MAX. LC1 (LC)</td><td>MEMB.</td><td>MAX. FACTORED FORCE (LBS)</td><td>MAX. UNBRACED LENGTH FR-TO</td><td>MAX. FACTORED FORCE (LBS)</td></tr><tr><td>FR-TO</td><td></td><td>FROM</td><td>TO</td><td>FR-TO</td><td></td><td></td><td></td></tr><tr><td>A-B</td><td>0 / 16</td><td>-84.9</td><td>-84.9 0.12 (5)</td><td>10.00</td><td>G-H</td><td>-61 / 0</td><td>0.00 (1)</td></tr><tr><td>B-H</td><td>-15 / 0</td><td>-84.9</td><td>-84.9 0.01 (4)</td><td>6.25</td><td></td><td></td><td></td></tr><tr><td>H-C</td><td>0 / 3</td><td>-84.9</td><td>-84.9 0.04 (1)</td><td>10.00</td><td></td><td></td><td></td></tr><tr><td>C-D</td><td>-14 / 0</td><td>-84.9</td><td>-84.9 0.03 (1)</td><td>6.25</td><td></td><td></td><td></td></tr><tr><td>B-G</td><td>0 / 0</td><td>-18.5</td><td>-18.5 0.04 (1)</td><td>10.00</td><td></td><td></td><td></td></tr><tr><td>G-F</td><td>0 / 0</td><td>-18.5</td><td>-18.5 0.04 (1)</td><td>10.00</td><td></td><td></td><td></td></tr><tr><td>F-E</td><td>0 / 0</td><td>-18.5</td><td>-18.5 0.01 (4)</td><td>10.00</td><td></td><td></td><td></td></tr></table>											FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG	HEEL	JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	WEDGE	B	222	0	222	0	0	4-0	1-8	2x4 L	F	46	0	46	0	0	5-8	1-8		C	137	0	137	0	0	5-8	5-8			1ST LCASE	MAX/MIN. COMPONENT REACTIONS						JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	B	155	111 / 0	0 / 0	0 / 0	0 / 0	44 / 0	0 / 0	F	35	10 / 0	0 / 0	0 / 0	0 / 0	25 / 0	0 / 0	C	95	73 / 0	0 / 0	0 / 0	0 / 0	22 / 0	0 / 0	CHORDS				WEBS				MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH FR-TO	MAX. FACTORED FORCE (LBS)	FR-TO		FROM	TO	FR-TO				A-B	0 / 16	-84.9	-84.9 0.12 (5)	10.00	G-H	-61 / 0	0.00 (1)	B-H	-15 / 0	-84.9	-84.9 0.01 (4)	6.25				H-C	0 / 3	-84.9	-84.9 0.04 (1)	10.00				C-D	-14 / 0	-84.9	-84.9 0.03 (1)	6.25				B-G	0 / 0	-18.5	-18.5 0.04 (1)	10.00				G-F	0 / 0	-18.5	-18.5 0.04 (1)	10.00				F-E	0 / 0	-18.5	-18.5 0.01 (4)	10.00			
	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG	HEEL																																																																																																																																																																						
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	WEDGE																																																																																																																																																																					
B	222	0	222	0	0	4-0	1-8	2x4 L																																																																																																																																																																					
F	46	0	46	0	0	5-8	1-8																																																																																																																																																																						
C	137	0	137	0	0	5-8	5-8																																																																																																																																																																						
	1ST LCASE	MAX/MIN. COMPONENT REACTIONS																																																																																																																																																																											
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL																																																																																																																																																																						
B	155	111 / 0	0 / 0	0 / 0	0 / 0	44 / 0	0 / 0																																																																																																																																																																						
F	35	10 / 0	0 / 0	0 / 0	0 / 0	25 / 0	0 / 0																																																																																																																																																																						
C	95	73 / 0	0 / 0	0 / 0	0 / 0	22 / 0	0 / 0																																																																																																																																																																						
CHORDS				WEBS																																																																																																																																																																									
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH FR-TO	MAX. FACTORED FORCE (LBS)																																																																																																																																																																						
FR-TO		FROM	TO	FR-TO																																																																																																																																																																									
A-B	0 / 16	-84.9	-84.9 0.12 (5)	10.00	G-H	-61 / 0	0.00 (1)																																																																																																																																																																						
B-H	-15 / 0	-84.9	-84.9 0.01 (4)	6.25																																																																																																																																																																									
H-C	0 / 3	-84.9	-84.9 0.04 (1)	10.00																																																																																																																																																																									
C-D	-14 / 0	-84.9	-84.9 0.03 (1)	6.25																																																																																																																																																																									
B-G	0 / 0	-18.5	-18.5 0.04 (1)	10.00																																																																																																																																																																									
G-F	0 / 0	-18.5	-18.5 0.04 (1)	10.00																																																																																																																																																																									
F-E	0 / 0	-18.5	-18.5 0.01 (4)	10.00																																																																																																																																																																									

DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 36.7 PSF SPACING = 24.0 IN. C/C THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015 THIS DESIGN COMPLIES WITH: - PART 9 OF BCBC 2018, OBC 2012, ABC 2019 - CSA 086-09, CSA 086-14 - TPIC 2011, TPIC 2014 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (0.19") CALCULATED VERT. DEFL.(LL) = L/999 (0.00") ALLOWABLE DEFL.(TL)= L/360 (0.19") CALCULATED VERT. DEFL.(TL) = L/999 (0.00") CANTILEVER DEFLECTION: ALLOWABLE DEFL.(TL)= L/120 (0.19") CALCULATED VERT. DEFL.(TL) = L/999 (0.00") CSI: TC=0.12/1.00 (A-B:5), BC=0.04/1.00 (B-G:1), WB=0.00/1.00 (G-H:1), SSI=0.06/1.00 (A-B:5) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10 COMPANION LIVE LOAD FACTOR = 1.00 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .			
---	--	--	--

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H1A		2	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MTek Industries, Inc. Mon Nov 11 13:51:05 2019 Page 1

ID:1dJR6DYvLvlXkyExRWgN1yQawr-ITcgeevQ2E6BNyaTaw?z73MfGelG19R3Ni8HMyKFPa

Scale = 1:42.1



LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
O - B	2x4	DRY	No.2	SPF
O - K	2x6	DRY	No.2	SPF
K - I	2x6	DRY	No.2	SPF

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - F	12	SIDE(41.1)
F - H	12	SIDE(41.1)
H - I	12	TOP
O - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
O - K	12	SIDE(174.2)
K - I	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
L - E	6	SIDE(113.6)
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT 2663 0	DOWN 2663 0	1-8	1-8
I	HORZ 0	UP 0	1-8	1-8
O	VERT 2041 0	DOWN 2041 0	5-8	1-8

UNFACTORED REACTIONS	1ST LCASE	MAX/MIN. COMPONENT REACTIONS
JT	COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
I	1890	1200 / 0 0 / 0 0 / 0 690 / 0 0 / 0
O	1447	932 / 0 0 / 0 0 / 0 515 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, O

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.88 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)
FR-TO									
A - B	0 / 42	-84.9	-84.9	0.07 (1)	10.00	N - C	-402 / 0	0.08 (1)	
B - C	-1766 / 0	-84.9	-84.9	0.11 (1)	8.25	B - N	0 / 1342	0.17 (1)	
C - D	-2620 / 0	-84.9	-84.9	0.20 (1)	5.41	C - M	0 / 1910	0.24 (1)	
D - E	-3384 / 0	-84.9	-84.9	0.22 (1)	4.88	M - D	-1218 / 0	0.25 (1)	
E - F	-2386 / 0	-167.1	-167.1	0.40 (1)	5.31	D - L	0 / 1079	0.13 (1)	
F - G	-2386 / 0	-167.1	-167.1	0.40 (1)	5.31	L - E	0 / 447	0.06 (1)	
G - H	-2386 / 0	-167.1	-167.1	0.40 (1)	5.31	E - J	-1438 / 0	0.66 (1)	
H - I	-2574 / 0	0.0	0.0	0.59 (1)	7.07	J - G	-999 / 0	0.20 (1)	
I - H	-2574 / 0	0.0	0.0	0.12 (1)	7.75	J - H	0 / 3247	0.40 (1)	
D - N	0 / 0	-18.5	-18.5	0.02 (4)	10.00				
N - M	0 / 1235	-18.5	-18.5	0.10 (1)	10.00				
M - L	0 / 2620	-18.5	-18.5	0.20 (1)	10.00				
L - K	0 / 3384	-36.4	-36.4	0.27 (1)	10.00				
K - J	0 / 3384	-36.4	-36.4	0.27 (1)	10.00				
J - I	0 / 0	-36.4	-36.4	0.05 (4)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
L	13-5-9	-1103	-1103	---	FRONT	VERT	TOTAL	---	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 3-5-5
RIGHT SETBACK = 0-0
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 10-5-0 OF SPAN MEASURED FROM THE RIGHT.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.10")

CSI: TC=0.59/1.00 (H-I:1), BC=0.27/1.00 (J-L:1), WB=0.66/1.00 (E-J:1), SSI=0.23/1.00 (G-H:1)


DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

CONTINUED ON PAGE 2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H1A		2	JT-39002	E-19112571(2)

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 13:51:05 2019 Page 2

ID:1djR6DYvLvIIXkyExRWgN1yQawr-ITcggeev0Q2E6BNyaTAw?z?3MfGeIG19R3Ni8HMyKFPa

PLATES (table is in inches)							NAIL VALUES					
JT	TYPE	PLATES	W	LEN	Y	X	PLATE	GRIP(DRY)	SHEAR	SECTION		
B	TMVW+p	MT20	4.0	6.0	2.75	2.00		(PSI)	(PLI)	(PLI)		
C	TTWW+m	MT20	5.0	6.0	2.00	1.50						
D	TMVW-t	MT20	4.0	4.0				MAX	MIN	MAX	MIN	MAX
E	TMVW-t	MT20	4.0	4.0				618	354	1667	788	1987
F	TS-t	MT20	3.0	6.0								1656
G	TMW+w	MT20	2.0	4.0				PLATE PLACEMENT TOL. = 0.250 inches				
H	TMVW-t	MT20	4.0	6.0	1.75	2.75		PLATE ROTATION TOL. = 5.0 Deg.				
I	BMV1+p	MT20	2.0	4.0				JSI GRIP= 0.88 (H) (INPUT = 0.80)				
J	BMVWW-t	MT20	5.0	8.0				JSI METAL= 0.45 (K) (INPUT = 1.00)				
K	BS-t	MT20	4.0	6.0								
L	BMVW-t	MT20	4.0	4.0								
M	BMVW-t	MT20	4.0	4.0	2.00	1.75						
N	BMVW-t	MT20	4.0	4.0								
O	BMV1+p	MT20	2.0	4.0								


NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME 313997	TRUSS NAME H9	QUANTITY 2	PLY 2	JOB DESC. JT-39002	DRWG NO. E-19112572
---------------------------	-------------------------	----------------------	-----------------	------------------------------	-------------------------------

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:50:01 2019 Page 1
ID:1dJR6DYvLvlXkyExRWgN1yQawr-d9kTCm7lUOABVY3HJkm_NVPSIT4HAr0LQC123yKfQa



TOTAL WEIGHT = 2 X 117 = 234 lb

LUMBER	SIZE	DRY	LUMBER	DESCR.
N. L. G. A. RULES				
CHORDS				
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
G - H	2x4	DRY	No.2	SPF
O - B	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
O - K	2x6	DRY	No.2	SPF
K - I	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - E	12	TOP
E - G	12	SIDE(41.1)
G - H	12	SIDE(61.0)
O - B	12	TOP
I - H	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
O - K	2	SIDE(10.0)
K - I	2	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
J - G	6	SIDE(9.9)
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT 2061 0	DOWN 2061 0	UPLIFT 0 0	IN-SX 1-8
O	2061 0	2061 0	0 0	1-8
I	2599 0	2599 0	0 0	1-8

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS
JT COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
O	1461 941 / 0 0 / 0 0 / 0 0 519 / 0 0 / 0
I	1846 1165 / 0 0 / 0 0 / 0 0 681 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.55 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)
MEMB.									
FR-TO									
A-B	0 / 42	-84.9	-84.9	0.07 (1)	10.00	N-C	-474 / 0	0.10 (1)	
B-C	-1767 / 0	-84.9	-84.9	0.11 (1)	6.25	J-G	-784 / 0	0.16 (1)	
C-D	-2850 / 0	-84.9	-84.9	0.25 (1)	5.19	B-N	0 / 1343	0.17 (1)	
D-E	-3375 / 0	-84.9	-84.9	0.44 (1)	4.59	J-H	0 / 1755	0.22 (1)	
E-F	-3375 / 0	-167.1	-167.1	0.44 (1)	4.59	C-M	0 / 2113	0.26 (1)	
F-G	-3374 / 0	-167.1	-167.1	0.47 (1)	4.55	M-D	-948 / 0	0.19 (1)	
G-H	-2167 / 0	-84.9	-84.9	0.10 (1)	5.94	D-L	0 / 698	0.09 (1)	
O-B	-2025 / 0	0.0	0.0	0.12 (1)	7.75	L-F	-932 / 0	0.19 (1)	
I-H	-2538 / 0	0.0	0.0	0.16 (1)	7.11	L-G	0 / 2441	0.30 (1)	
O-N	0 / 0	-18.5	-18.5	0.01 (4)	10.00				
N-M	0 / 1234	-18.5	-18.5	0.18 (1)	10.00				
M-P	0 / 2850	-18.5	-18.5	0.50 (1)	10.00				
P-L	0 / 2850	-36.4	-36.4	0.50 (1)	10.00				
L-K	0 / 1508	-36.4	-36.4	0.25 (1)	10.00				
K-J	0 / 1508	-36.4	-36.4	0.25 (1)	10.00				
J-I	0 / 0	-36.4	-36.4	0.03 (4)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	20-8-11	-195	-195	—	FRONT	VERT	TOTAL	—	C1
P	13-5-9	-1103	-1103	—	FRONT	VERT	TOTAL	—	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 3-5-5
RIGHT SETBACK = 3-1-14
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 10-5-0 OF SPAN MEASURED FROM THE RIGHT.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.13")

CSI: TC=0.47/1.00 (F-G:1), BC=0.50/1.00 (L-M:1), WB=0.30/1.00 (G-L:1), SS=0.31/1.00 (L-M:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

CONTINUED ON PAGE 2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H9		2	JT-39002	E-19112572(2)

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MTek Industries, Inc. Mon Nov 11 13:50:01 2019 Page 2
ID:1dJR6DYvLvIIIXkyExRWgN1yQawr-d9kTCm7tUOABVY3Hjkm NVPSiTi4HAr0LQCI23yKFOa

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.75	2.00
C	TTWW+m	MT20	5.0	6.0	2.00	1.25
D	TMWW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMW+w	MT20	2.0	4.0		
G	TTWW+m	MT20	5.0	6.0	1.75	1.25
H	TMVW+p	MT20	4.0	6.0	2.75	2.00
I	BMV1+p	MT20	2.0	4.0		
J	BMWW-t	MT20	4.0	4.0		
K	BS-t	MT20	4.0	6.0		
L	BMWWW-t	MT20	5.0	8.0		
M	BMWW-t	MT20	4.0	4.0	2.00	1.50
N	BMWW-t	MT20	4.0	4.0		
O	BMV1+p	MT20	2.0	4.0		

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (J) (INPUT = 0.90)
JSI METAL= 0.42 (H) (INPUT = 1.00)


NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H11S	1	1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:32:12 2019 Page 1



Scale = 1:58.7

TOTAL WEIGHT = 6 X 64 = 385 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - E	2x4	DRY	2100F 1.8E	SPF	
H - B	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
C	TMWW+t	MT20	3.0	5.0	2.00	1.00
D	TTW+p	MT20	3.0	4.0	Edge	
E	TMVW+p	MT20	4.0	6.0	2.75	2.00
F	BMV1+p	MT20	2.0	4.0		
G	BMWWW+t	MT20	4.0	6.0		
H	BMVW1+t	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQRD
	VERT	HORZ	DOWN	UP
JT	689	0	689	0
F	807	0	807	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	489	310 / 0	0 / 0	0 / 0	0 / 0	179 / 0	0 / 0
H	571	375 / 0	0 / 0	0 / 0	0 / 0	195 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED		FACTORED		
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX CSI (LC)	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM TO			LENGTH	FR-TO			
A-B	0 / 42	-84.9	-84.9	0.12 (1)	10.00	C-G	-140 / 0	0.09 (1)	
B-C	0 / 24	-84.9	-84.9	0.16 (1)	10.00	G-D	0 / 182	0.05 (4)	
C-D	-427 / 0	-84.9	-84.9	0.13 (1)	6.25	H-C	-644 / 0	0.39 (1)	
D-E	-403 / 0	-84.9	-84.9	0.30 (1)	6.25	G-E	0 / 298	0.07 (1)	
H-B	-228 / 0	0.0	0.0	0.03 (1)	7.81				
F-E	-645 / 0	0.0	0.0	0.08 (1)	7.81				
H-G	0 / 366	-18.5	-18.5	0.27 (4)	10.00				
G-F	0 / 0	-18.5	-18.5	0.24 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.44")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.44")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.30/1.00 (D-E:1), BC=0.27/1.00 (G-H:4), WB=0.38/1.00 (C-H:1), SSI=0.15/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	618	354	1667
	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.79 (H) (INPUT = 0.80)
JSI METAL= 0.39 (C) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H11T		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 M/Tek Industries, Inc. Mon Nov 11 13:31:49 2019 Page 1

ID:1dJR6DYvLVIIKXyExRWgN1yQawr-c4f0Nvvfb7VjaP0Av7DAv9G8TQKCHFXhzjMyKFhe



Scale = 1:58.7

TOTAL WEIGHT = 4 X 71 = 282 lb

[M][F]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
L - K	2x4	DRY	No.2	SPF
K - J	2x4	DRY	No.2	SPF
J - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	6.0	2.75	2.00
C TMWW-t	MT20	3.0	4.0	1.50	1.00
D TTW+p	MT20	3.0	5.0		
E TMWW-t	MT20	3.0	4.0	1.50	1.00
F TMVW+p	MT20	4.0	6.0	2.75	2.00
H BMV1+p	MT20	2.0	4.0		
I BBWW-I	MT20	4.0	6.0	2.00	4.00
J BBWWV-p	MT20	5.0	6.0	2.75	3.00
K BBWW-I	MT20	4.0	6.0	2.00	4.00
L BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQRD
	VERT	DOWN	HORIZ	UPLIFT
JT	829	0	0	5-8
L	829	0	0	5-8
H	829	0	0	5-8

UNFACTORED REACTIONS

1ST CASE	MAX/MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
L	586	385 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0	
H	586	385 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 42	-84.9 -84.9	0.12 (1)	J-D	0 / 572	0.13 (1)	
B-C	-536 / 0	-84.9 -84.9	0.14 (1)	J-E	0 / 37	0.01 (1)	
C-D	-625 / 0	-84.9 -84.9	0.16 (1)	I-E	-408 / 0	0.13 (1)	
D-E	-625 / 0	-84.9 -84.9	0.16 (1)	C-J	0 / 37	0.01 (1)	
E-F	-536 / 0	-84.9 -84.9	0.14 (1)	K-C	-408 / 0	0.13 (1)	
F-G	0 / 42	-84.9 -84.9	0.12 (1)	B-K	0 / 453	0.10 (1)	
L-B	-802 / 0	0.0 0.0	0.09 (1)	I-F	0 / 453	0.10 (1)	
H-F	-802 / 0	0.0 0.0	0.09 (1)				
L-K	0 / 0	-18.5 -18.5	0.05 (4)				
K-J	0 / 473	-18.5 -18.5	0.13 (4)				
J-I	0 / 473	-18.5 -18.5	0.13 (4)				
I-H	0 / 0	-18.5 -18.5	0.05 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.46")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.46")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.16/1.00 (C-D:1), BC=0.13/1.00 (J-K:4), WB=0.13/1.00 (E-I:1), SSI=0.11/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.75 (I) (INPUT = 0.90)

JSI METAL= 0.26 (B) (INPUT = 1.00)


NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



Alpha Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:31:53 2019 Page 1

ID:1dJR6DYvLVIIKxyExRWgN1yQawr-Ur?AskypJ55Z_LuA_EFrH3LbkuV?M8ssA8fAs7yKPha



Scale = 1:59.2

TOTAL WEIGHT = 2 X 80 = 160 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - D	2x4	DRY	No.2	SPF
D - B	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
L - K	2x4	DRY	No.2	SPF
K - J	2x4	DRY	No.2	SPF
J - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				
GABLE STUDS SPACED AT 2-0-0 OC.				

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	6.0	2.75	2.00
C TMVW-t	MT20	3.0	4.0	1.50	1.00
D TTW+p	MT20	3.0	4.0	Edge	
E TMVW-t	MT20	3.0	4.0	1.50	1.00
F TMVW+p	MT20	4.0	6.0	2.75	2.00
H BMV1+p	MT20	2.0	4.0		
I BBWW1-I	MT20	4.0	6.0	2.00	4.00
J BBWW1-p	MT20	4.0	6.0		
K BBWW1-I	MT20	4.0	6.0	2.00	4.00
L BMV1+p	MT20	2.0	4.0		
M NP-p	MT20	2.0	4.0	1.00	1.75
M, N, O, P, Q, R, S, T, U, V					
M NP+w	MT20	2.0	4.0		
T NP-p	MT20	2.0	4.0	1.00	1.75

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX
JT	325	0	325	0	13-9-0 (6-10-8)2-1	
L	263	0	263	0	13-9-0 (6-10-8)2-1	
K	482	0	482	0	13-9-0 (6-10-8)2-1	
J	263	0	263	0	13-9-0 (6-10-8)2-1	
I	325	0	325	0	13-9-0 (6-10-8)2-1	
H	325	0	325	0	13-9-0 (6-10-8)2-1	

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): J

UNFACTORED REACTIONS

	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
JT	227	164 / 0	0 / 0	0 / 0	0 / 0	64 / 0	0 / 0
L	188	109 / 0	0 / 0	0 / 0	0 / 0	79 / 0	0 / 0
K	341	225 / 0	0 / 0	0 / 0	0 / 0	116 / 0	0 / 0
J	188	109 / 0	0 / 0	0 / 0	0 / 0	79 / 0	0 / 0
I	227	164 / 0	0 / 0	0 / 0	0 / 0	64 / 0	0 / 0
H							

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, K, J, I, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
FR-TO					FR-TO		
A-B	0 / 42	-84.9	-84.9 0.12 (1)	10.00	J-D	-271 / 0	0.15 (1)
B-C	-67 / 0	-84.9	-84.9 0.19 (1)	6.25	J-E	-67 / 0	0.02 (1)
C-D	-29 / 0	-84.9	-84.9 0.19 (1)	6.25	I-E	-280 / 0	0.09 (1)
D-E	-29 / 0	-84.9	-84.9 0.19 (1)	6.25	C-J	-67 / 0	0.02 (1)
E-F	-67 / 0	-84.9	-84.9 0.19 (1)	6.25	K-C	-280 / 0	0.09 (1)
F-G	0 / 42	-84.9	-84.9 0.12 (1)	10.00	B-K	0 / 81	0.02 (1)
L-B	-298 / 0	0.0	0.0 0.03 (1)	7.81	I-F	0 / 81	0.02 (1)
H-F	-298 / 0	0.0	0.0 0.03 (1)	7.81			
L-K	0 / 0	-18.5	-18.5 0.05 (4)	10.00			
K-J	0 / 79	-18.5	-18.5 0.09 (4)	10.00			
J-I	0 / 79	-18.5	-18.5 0.09 (4)	10.00			
I-H	0 / 0	-18.5	-18.5 0.05 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.19/1.00 (B-C:1), BC=0.09/1.00 (J-K:4), WB=0.15/1.00 (D-J:1), SSI=0.11/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.43 (D) (INPUT = 0.80)
JSI METAL= 0.17 (J) (INPUT = 1.00)





TOTAL WEIGHT = 2 X 229 = 458 lb

LUMBER				N. L. G. A. RULES	
CHORDS	SIZE	LUMBER	DESCR.		
AU - B	2x4	DRY	No.2	SPF	
A - H	2x4	DRY	No.2	SPF	
H - K	2x4	DRY	No.2	SPF	
K - O	2x4	DRY	No.2	SPF	
O - R	2x4	DRY	No.2	SPF	
R - Y	2x4	DRY	No.2	SPF	
Z - X	2x4	DRY	No.2	SPF	
AU - AM	2x4	DRY	No.2	SPF	
AM - AH	2x4	DRY	No.2	SPF	
AH - Z	2x4	DRY	No.2	SPF	

ALL WEBS EXCEPT				LUMBER	
CHORDS	SIZE	LUMBER	DESCR.		
AI - O	2x4	DRY	No.2	SPF	
AJ - N	2x4	DRY	No.2	SPF	
AK - M	2x4	DRY	No.2	SPF	
AL - L	2x4	DRY	No.2	SPF	
AN - J	2x4	DRY	No.2	SPF	
AG - P	2x4	DRY	No.2	SPF	

ALL GABLE WEBS EXCEPT				LUMBER	
CHORDS	SIZE	LUMBER	DESCR.		
ST1	2x4	DRY	No.2	SPF	
ST2	2x4	DRY	No.2	SPF	
ST3	2x4	DRY	No.2	SPF	
ST4	2x4	DRY	No.2	SPF	
ST5	2x4	DRY	No.2	SPF	
ST12	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.
GABLE STUDS SPACED AT 2'-0" OC.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	2.0	4.0	
C, D, E, F, G, I, J, M, N, P, Q, S, T, U, V, W	C	TMW+w	MT20	2.0	4.0
H	TS-t	MT20	3.0	6.0	
K	TTW+m	MT20	4.0	6.0	Edge 1.00

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
FOR SECTION K-O, MAX. PURLIN SPACING = 2.00 FT.
FOR OTHER SECTIONS, TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.
1 LATERAL BRACE(S) AT 1/2 LENGTH OF O-AI, N-AJ, M-AK, L-AL, J-AN, I-AG, P-AG, Q-AF.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)
FR-TO		FROM TO		FR-TO		FROM TO	
AU-B	-210 / 0	0.0	0.0 0.01 (4)	AI-O	-186 / 0	7.81	0.15 (1)
A-B	0 / 32	-84.9	-84.9 0.11 (1)	AJ-N	-186 / 0	10.00	0.15 (1)
B-C	-11 / 0	-84.9	-84.9 0.04 (1)	AK-M	-185 / 0	6.25	0.14 (1)
C-D	-4 / 0	-84.9	-84.9 0.04 (1)	AL-L	-188 / 0	10.00	0.15 (1)
D-E	-3 / 0	-84.9	-84.9 0.04 (1)	AN-J	-176 / 0	10.00	0.11 (1)
E-F	-2 / 4	-84.9	-84.9 0.04 (1)	AO-I	-165 / 0	10.00	0.10 (1)
F-G	-2 / 6	-84.9	-84.9 0.04 (1)	AP-G	-170 / 0	10.00	0.22 (1)
G-H	-1 / 8	-84.9	-84.9 0.04 (1)	AQ-F	-188 / 0	10.00	0.13 (1)
H-I	-1 / 8	-84.9	-84.9 0.04 (1)	AR-E	-168 / 0	10.00	0.08 (1)
I-J	0 / 12	-84.9	-84.9 0.05 (1)	AS-D	-167 / 0	10.00	0.04 (1)
J-K	-2 / 5	-84.9	-84.9 0.04 (1)	AT-C	-167 / 0	10.00	0.03 (1)
K-L	0 / 15	-92.4	-92.4 0.04 (1)	AG-P	-176 / 0	2.00	0.10 (1)
L-M	0 / 10	-92.4	-92.4 0.04 (1)	AF-Q	-165 / 0	2.00	0.09 (1)
M-AV	0 / 10	-92.4	-92.4 0.04 (1)	AE-S	-170 / 0	2.00	0.21 (1)
AV-N	0 / 10	-92.4	-92.4 0.04 (1)	AD-T	-168 / 0	2.00	0.12 (1)
N-O	0 / 10	-92.4	-92.4 0.04 (1)	AC-U	-166 / 0	2.00	0.07 (1)
O-P	0 / 11	-84.9	-84.9 0.04 (1)	AB-V	-177 / 0	10.00	0.04 (1)
P-Q	0 / 12	-84.9	-84.9 0.04 (1)	AA-W	-121 / 0	10.00	0.02 (1)
Q-R	-1 / 8	-84.9	-84.9 0.04 (1)				
R-S	-1 / 8	-84.9	-84.9 0.04 (1)				
S-T	-2 / 6	-84.9	-84.9 0.04 (1)				
T-U	-2 / 4	-84.9	-84.9 0.04 (1)				
U-V	-3 / 0	-84.9	-84.9 0.04 (1)				
V-W	-3 / 0	-84.9	-84.9 0.04 (1)				
W-X	-26 / 0	-84.9	-84.9 0.09 (1)				
X-Y	0 / 32	-84.9	-84.9 0.11 (1)				
Z-X	-227 / 0	0.0	0.0 0.03 (1)				

AU-AT	0 / 9	-18.5	-18.5 0.02 (4)	10.00
AT-AS	0 / 3	-18.5	-18.5 0.02 (4)	10.00
AS-AR	0 / 2	-18.5	-18.5 0.02 (4)	10.00
AR-AQ	-3 / 2	-18.5	-18.5 0.02 (4)	10.00
AQ-AP	-5 / 1	-18.5	-18.5 0.01 (4)	10.00
AP-AO	-7 / 1	-18.5	-18.5 0.01 (4)	10.00
AO-AN	-8 / 0	-18.5	-18.5 0.01 (4)	10.00
AN-AM	-10 / 0	-18.5	-18.5 0.01 (4)	10.00
AM-AL	-10 / 0	-18.5	-18.5 0.01 (4)	10.00
AL-AK	-10 / 0	-18.5	-18.5 0.01 (4)	10.00
AK-AJ	-10 / 0	-18.5	-18.5 0.01 (4)	10.00
AJ-AI	-10 / 0	-18.5	-18.5 0.01 (4)	10.00
AI-AH	-10 / 0	-18.5	-18.5 0.01 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON PIGGYBACK TRUSS WITH SLOPES OF 6.00/12 AND -6.00/12 AND RESPECTIVE WALL HEIGHTS OF 0-0 AND 0-0 AND AN ADDITIONAL DEAD LOAD OF 3.0 P.S.F.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.11/1.00 (X-Y:1), BC=0.03/1.00 (Z-AA:1), WB=0.22/1.00 (G-AP:1), SSI=0.08/1.00 (X-Y:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.56 (K) (INPUT = 0.90)
JSI METAL= 0.12 (X) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H16P		1	TRUSS DESC.	JT-39002 E-19112578

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:28:58 2019 Page 1

ID:1dJR6DYvLvllXkyExRWgN1yQawr-MjYhQZHomcthg4laht7p4zuXHvv9WxjllbJlyKFjN



Scale = 1:16.5

TOTAL WEIGHT = 2 X 15 = 30 lb [M]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
B - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB14	MT20	3.0	4.0		
C	TTW+p	MT20	3.0	4.0	2.25	1.50
D	TMB14	MT20	3.0	4.0		
F	BMW1+w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): F

PROVIDE ANCHORAGE AT BEARING JOINT A FOR 150 LBS. FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT E FOR 150 LBS. FACTORED UPLIFT
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S).

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (CSI (LC))	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (CSI (LC))
FR-TO		FROM TO		FR-TO		FROM TO	
A-B	0 / 27	-103.4 -103.4	0.05 (1)	10.00	F-C	-108 / 0	0.02 (1)
B-H	-71 / 0	-84.9 -84.9	0.05 (1)	6.25	G-H	-66 / 10	0.00 (1)
H-C	-48 / 0	-84.9 -84.9	0.05 (1)	6.25	I-J	-66 / 10	0.00 (1)
C-J	-48 / 0	-84.9 -84.9	0.05 (1)	6.25			
J-D	-71 / 0	-84.9 -84.9	0.05 (1)	6.25			
D-E	0 / 27	-103.4 -103.4	0.06 (1)	10.00			
B-G	0 / 35	-18.5 -18.5	0.03 (1)	10.00			
G-F	0 / 35	-18.5 -18.5	0.04 (1)	10.00			
F-I	0 / 35	-18.5 -18.5	0.04 (1)	10.00			
I-D	0 / 35	-18.5 -18.5	0.03 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.05/1.00 (D-E:1), BC=0.04/1.00 (F-G:1), WB=0.02/1.00 (C-F:1), SSI=0.06/1.00 (C-J:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.19 (B) (INPUT = 0.90)

JSI METAL= 0.04 (B) (INPUT = 1.00)


NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



Scale = 1:22.6

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
310385	H2		1	TRUSS DESC.	JT-39002
Alpa Roof Truss, Maple					E-19072227

Version 8.300 S May 10 2019 MiTek Industries, Inc. Wed Jul 10 10:24:21 2019 Page 1
ID:MF8llriaTok7DlbpT4B71Xys4PG-_8qg8xPHXxCPnIod8hKid9vCSL?JH2LHmbuOBMyzW1e
Scale = 1:42.5



TOTAL WEIGHT = 4 X 107 = 429 lb

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
E - G	2x4	DRY No.2	SPF
H - G	2x4	DRY No.2	SPF
M - B	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.00	1.50
D	TMVW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMVW+w	MT20	2.0	4.0		
G	TMVW-t	MT20	4.0	6.0	1.75	3.00
H	BMV1+p	MT20	2.0	4.0		
I	BMVWW-t	MT20	5.0	8.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-t	MT20	4.0	4.0		
L	BMVW-t	MT20	4.0	4.0	2.00	1.75
M	BMV1+p	MT20	2.0	4.0		

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
H	1230	0	1230	0	0	1-9	1-8		
M	1348	0	1348	0	0	5-8	2-0		

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS		DEAD		SOIL	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
M	955	619 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.14 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		MAX. FACTORED		WEBS		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 (LC)	MAX	UNBRAC	MEMB.	FORCE (LBS)	MAX	CS1 (LC)
FR-TO					LENGTH	FR-TO			
A-B	0 / 42	-84.9	-84.9	0.12 (1)	10.00	L-C	-120 / 41	0.09 (1)	
B-C	-1069 / 0	-84.9	-84.9	0.39 (1)	5.60	C-K	0 / 642	0.14 (1)	
C-D	-1203 / 0	-84.9	-84.9	0.51 (1)	5.14	K-D	-345 / 0	0.25 (1)	
D-E	-977 / 0	-84.9	-84.9	0.52 (1)	5.53	D-I	-323 / 0	0.18 (1)	
E-F	-977 / 0	-84.9	-84.9	0.52 (1)	5.53	I-F	-596 / 0	0.44 (1)	
F-G	-977 / 0	-84.9	-84.9	0.52 (1)	5.53	I-G	0 / 1368	0.31 (1)	
H-G	-1181 / 0	0.0	0.0	0.24 (1)	5.87	B-L	0 / 790	0.18 (1)	
M-B	-1315 / 0	0.0	0.0	0.15 (1)	7.05				

M-L	0 / 0	-18.5	-18.5	0.13 (4)	10.00
L-K	0 / 752	-18.5	-18.5	0.20 (4)	10.00
K-J	0 / 1203	-18.5	-18.5	0.29 (1)	10.00
J-I	0 / 1203	-18.5	-18.5	0.29 (1)	10.00
I-H	0 / 0	-18.5	-18.5	0.18 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.I. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.09")

CSI: TC=0.52/1.00 (F-G:1), BC=0.29/1.00 (I-K:1), WB=0.44/1.00 (F-I:1), SSI=0.28/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667
	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.80 (L) (INPUT = 0.90)
JSI METAL= 0.48 (B) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
310385	H3		1	JT-39002	E-19072228

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MiTek Industries, Inc. Wed Jul 10 10:24:22 2019 Page 1
ID:MF8ilriaTok7DlbpT4B71Xys4PG-TKO2MHQvIFKGPSNplOrxAMRJJQIJ0WZQ?FeyjoyzW1d
Scale = 1:48.7



TOTAL WEIGHT = 4 X 112 = 450 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	2100F 1.8E	SPF
C - E	2x4	DRY	2100F 1.8E	SPF
E - F	2x4	DRY	2100F 1.8E	SPF
G - F	2x4	DRY	No.2	SPF
J - B	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
C - H	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.50	2.00
C	TTWW+m	MT20	4.0	6.0	Edge	1.00
D	TMW+w	MT20	2.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMVW-t	MT20	4.0	4.0	1.50	1.75
G	BMV1+p	MT20	2.0	4.0		
H	BSWWW-t	MT20	5.0	8.0	3.00	4.00
I	BMWW-t	MT20	4.0	4.0	2.00	1.75
J	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT		VERT	HORZ	DOWN	UPLIFT
G		1230	0	1230	0
J		1348	0	1348	0

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	COMBINED	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
J	COMBINED	955	619 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.62 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF F-G, D-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 / 42	I-C	-9 / 126
B-C	-1060 / 0	C-H	0 / 334
C-D	-999 / 0	H-D	-932 / 0
D-E	-999 / 0	H-F	0 / 1317
E-F	-999 / 0	B-I	0 / 770
G-F	-1147 / 0		
J-B	-1312 / 0		
J-I	0 / 0		
I-H	0 / 748		
H-G	0 / 0		

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD	= 36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.I. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/897 (0.32")

CSI: TC=0.83/1.00 (D-F:1), BC=0.43/1.00 (G-H:4), WB=0.37/1.00 (D-H:1), SS=0.37/1.00 (D-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667
	788	1987	1656


PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (I) (INPUT = 0.80)
JSI METAL= 0.49 (B) (INPUT = 1.00)



JSI GRIP= 0.89 (K) (INPUT = 0.90)
JSI METAL= 0.48 (C) (INPUT = 1.00)



TOTAL WEIGHT = 6 X 137 = 823 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
G - F	2x4	DRY	No.2
K - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2

LUMBER			
DESCR.	SPF	No.2	SPF
ALL WEBS EXCEPT	2x4	DRY	No.2
C - J	2x3	DRY	No.2
K - C	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
C	TMW-t	MT20	4.0	4.0	1.75	1.25
D	TTWW+m	MT20	6.0	6.0	2.00	1.25
E	TMW+w	MT20	2.0	4.0		
F	TMVW-t	MT20	4.0	4.0	1.75	1.75
G	BMV1+p	MT20	2.0	4.0		
H	BMVWW-t	MT20	5.0	8.0		
I	BS-t	MT20	3.0	6.0		
J	BMVW-t	MT20	4.0	4.0		
K	BMVW1-t	MT20	4.0	4.0	2.00	1.75

NOTES- (1)

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT		REQRD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	BRG	IN-SX	BRG	IN-SX
G	1230	0	1230	0	0	1-9	1-8		
K	1348	0	1348	0	0	5-8	1-8		

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	873	654 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
K	955	619 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.10 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF F-G, D-H, E-H, C-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 42	-84.9 -84.9	0.12 (1)	10.00	C-J	-162 / 0	0.18 (1)
B-C	0 / 29	-84.9 -84.9	0.27 (1)	10.00	J-D	0 / 306	0.05 (1)
C-D	-984 / 0	-84.9 -84.9	0.30 (1)	5.90	D-H	-21 / 4	0.02 (4)
D-E	-675 / 0	-84.9 -84.9	0.88 (1)	5.10	H-E	-792 / 0	0.45 (1)
E-F	-676 / 0	-84.9 -84.9	0.88 (1)	5.10	H-F	0 / 1151	0.19 (1)
G-F	-1172 / 0	0.0 0.0	0.87 (1)	5.90	K-C	-1257 / 0	0.52 (1)
K-B	-279 / 0	0.0 0.0	0.03 (1)	7.81			
K-J	0 / 759	-18.5 -18.5	0.38 (4)	10.00			
J-I	0 / 673	-18.5 -18.5	0.38 (4)	10.00			
I-H	0 / 673	-18.5 -18.5	0.38 (4)	10.00			
H-G	0 / 0	-18.5 -18.5	0.22 (4)	10.00			

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 23.3 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF BCBC 2018, OBC 2012
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
 ALLOWABLE DEFL.(TL) = L/360 (0.79")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.19")

CSI: TC=0.88/1.00 (E-F:1), BC=0.38/1.00 (J-K:4), WB=0.52/1.00 (C-K:1), SSI=0.31/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (K) (INPUT = 0.90)
 JSI METAL= 0.48 (C) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
310385	J1	1	1	TRUSS DESC.	JT-39002
Alpa Roof Truss, Maple					E-19072240

Version 8.300 S May 10 2019 MiTek Industries, Inc. Wed Jul 10 10:24:38 2019 Page 1
ID:MF8IrlaTok7DlbpT4B71Xys4PG-7PM6JlcxWAL?Kwbuel7hpk67VB04mqNngkWoHtyzW1N
Scale = 1:31.2



TOTAL WEIGHT = 24 X 16 = 384 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	SIZE	
E - B	2x4	DRY	No.2		SPF
A - C	2x4	DRY	No.2		SPF
E - D	2x3	DRY	No.2		SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	2.0	4.0	
E	BMV1+p	MT20	2.0	4.0	

NOTES- (1)

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
E	494	0	494	0	5-8	1-8
C	187	0	187	0	1-8	1-8
D	43	0	48	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
E	348	235 / 0	0 / 0	0 / 0	0 / 0	113 / 0	0 / 0
C	129	103 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0
D	34	0 / 0	0 / 0	0 / 0	0 / 0	34 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX (LC)	MAX. UNBRACED LENGTH	MEMB. FORCE (LBS)	MAX (LC)	CS (LC)
FR-TO		FROM	TO		FR-TO			
E-B	-428 / 0	0.0	0.0	0.16 (4)	7.81			
A-B	0 / 32	-84.9	-84.9	0.11 (1)	10.00			
B-C	-35 / 0	-84.9	-84.9	0.50 (1)	6.25			
E-D	0 / 0	-18.5	-18.5	0.30 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/ 932 (0.08")

CSI: TC=0.50/1.00 (B-C:1), BC=0.30/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SS=0.20/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES		PLATE GRIP(DRY) SHEAR		SECTION	
(PSI)	(PLI)	(PSI)	(PLI)	(PSI)	(PLI)
MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1667	788	1987


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.28 (B) (INPUT = 0.90)
JSI METAL= 0.22 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





TOTAL WEIGHT = 14 X 145 = 2031 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - G	2x4	DRY	No.2
H - G	2x4	DRY	No.2
L - B	2x4	DRY	No.2
L - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2
ALL WEBS	2x4	DRY	No.2
EXCEPT			
C - K	2x3	DRY	No.2
L - C	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	2.0	4.0	
C	TMWW-t	MT20	4.0	4.0	1.75 1.25
D	TS-t	MT20	3.0	6.0	
E	TTWW+m	MT20	5.0	6.0	2.00 1.25
F	TMW+w	MT20	2.0	4.0	
G	TMV-t	MT20	4.0	4.0	1.75 1.75
H	BMV1+p	MT20	2.0	4.0	
I	BMVWW-t	MT20	5.0	8.0	
J	BS-t	MT20	3.0	6.0	
K	BMVW-t	MT20	4.0	4.0	
L	BMVW1-t	MT20	4.0	4.0	2.00 1.75

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
H	1303	0	1303	0	0	1-9	1-8		
L	1378	0	1378	0	0	5-8	1-8		

UNFACTORED REACTIONS		1ST LCASE		MAX/MIN COMPONENT REACTIONS		LIVE		PERM.LIVE		WIND		DEAD		SOIL	
JT	COMBINED	SNOW	WIND	WIND	WIND	WIND	WIND	WIND	WIND	WIND	WIND	WIND	WIND	WIND	WIND
H	932	654 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0
L	978	619 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, L

BRACING
 FOR SECTION E-G, MAX. PURLIN SPACING = 2.00 FT.
 FOR OTHER SECTIONS, TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.98 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, C-K, F-I, G-I, C-L.
 2 LATERAL BRACE(S) AT 1/3 LENGTH OF E-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
 TOTAL LOAD CASES: (4)

CHORD'S		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. (LC)	MAX. (LC)	MEMB.	FORCE (LBS)	MAX. (LC)
FR-TO		FROM	TO	LENGTH	FR-TO		
A-B	0 / 42	-84.9	-84.9	0.12 (1)	10.00	C-K	-213 / 0
B-C	0 / 37	-84.9	-84.9	0.36 (1)	10.00	K-E	0 / 355
C-D	-958 / 0	-84.9	-84.9	0.30 (1)	5.98	E-I	-117 / 0
D-E	-958 / 0	-84.9	-84.9	0.30 (1)	5.98	I-F	-785 / 0
E-F	-595 / 0	-92.4	-92.4	0.56 (1)	2.00	I-G	0 / 1166
F-G	-596 / 0	-92.4	-92.4	0.57 (1)	2.00	L-C	-1286 / 0
H-G	-1247 / 0	0.0	0.0	0.98 (1)	5.78		
L-B	-279 / 0	0.0	0.0	0.03 (1)	7.81		
L-K	0 / 783	-18.5	-18.5	0.47 (4)	10.00		
K-J	0 / 654	-18.5	-18.5	0.47 (4)	10.00		
J-I	0 / 654	-18.5	-18.5	0.47 (4)	10.00		
I-H	0 / 0	-18.5	-18.5	0.19 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 23.3 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON PIGGYBACK TRUSS WITH SLOPES OF 6.00/12 AND -6.00/12 AND RESPECTIVE WALL HEIGHTS OF 0-0 AND 0-0 AND AN ADDITIONAL DEAD LOAD OF 3.0 P.S.F.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018, OBC 2012
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/380 (0.79")
 CALCULATED VERT. DEFL.(LL) = L/989 (0.03")
 ALLOWABLE DEFL.(TL)= L/360 (0.79")
 CALCULATED VERT. DEFL.(TL) = L/889 (0.32")

CSI: TC=0.98/1.00 (G-H:1), BC=0.47/1.00 (K-L:4), WB=0.62/1.00 (F-I:1), SSI=0.31/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES					
PLATE	GRIP(DRY)	SHEAR	SECTION	(PSI)	(PLI)
MT20	618	354	1667	788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (L) (INPUT = 0.90)
 JSI METAL= 0.49 (C) (INPUT = 1.00)





JSI GRIP= 0.34 (D) (INPUT = 0.90)
JSI METAL= 0.14 (D) (INPUT = 1.00)

May 27, 2019

Re: Expiration Date for Technical Bulletins Extended to 12/31/2019

Please be advised that the expiration date of the Technical Bulletins listed below has been extended until December 31, 2019.

T-SPECCP17	T-SPECH17	T-SPECDSHGUS17R
T-SPECHGUS17-R	T-SPECHHUS17-R	T-SPECHUS17
T-SPECLF17	T-SPECLT17	T-SPECLU17
T-SPECCLUL17	T-SPECLUS17	T-SPECSUR17
T-SPECTBE17	T-SPECTC17	T-SPECTHGB17
T-SPECTHGBHV17	T-SPECTHGQ17	T-SPECTHGW17
T-SPECLSULSSU17	T-SPECHTHGQ17	T-SPECSTHGQ17

Should you have any questions or concerns regarding the above, please contact me at your convenience.

Sincerely,



Brent Bunting, P.Eng.
Simpson Strong-Tie Canada, Ltd.



LUS – Double Shear Joist Hangers

All LUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections.

Material: 18 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners.
- Nails: 16d = 0.162" dia. x 3½" long common wire, 10d = 0.148" x 3" long common wire.
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads.
- Not designed for welded or nailer applications.

Options:

- These hangers cannot be modified




Typical LUS Installation




Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _e ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _p =1.15)	Normal (K _p =1.00)	Uplift (K _p =1.15)	Normal (K _p =1.00)
LUS24	18	1⅞	3⅞	1¾	1⅝	(4) 10d	(2) 10d	710	1630	645	1155
LUS24-2	18	3⅞	3⅞	2	1⅝	(4) 16d	(2) 16d	835	2020	590	1435
LUS26	18	1⅞	4¾	1¾	3⅝	(4) 10d	(4) 10d	1420	2170	1290	1630
LUS26-2	18	3⅞	4¾	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920
LUS26-3	18	4⅞	4¾	2	3¼	(4) 16d	(4) 16d	1720	2595	1545	2340
LUS28	18	1⅞	6⅝	1¾	3¾	(6) 10d	(6) 10d	1420	2520	1290	1790
LUS28-2	18	3⅞	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575
LUS28-3	18	4⅞	6¼	2	3¼	(6) 16d	(4) 16d	1720	3325	1545	2375
LUS210	18	1⅞	7⅝	1¾	3⅞	(8) 10d	(4) 10d	1420	2785	1290	2210
LUS210-2	18	3⅞	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195
LUS210-3	18	4⅞	8⅝	2	5¼	(8) 16d	(6) 16d	2580	3345	2320	2375

1. d_e is the distance from the seat of the hanger to the highest joist nail.



Dome Double Shear Nailing prevents tabs breaking off (available on some models).

U.S. Patent 5,603,580



Double Shear Nailing Top View.



LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2019, and reflects information available as of March 1, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2017 Simpson Strong-Tie Company Inc.

T-SPEC/LUS17 3/17 exp. 6/19

(800) 999-5099
strongtie.com

HHUS – Double Shear Joist Hangers

All HHUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: 14 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia. x 3½" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:

- See current catalogue for options







HHUS410



Typical HHUS Installation
(Truss Designer to provide
fastener quantity for connecting
multiple members together)

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _b ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _o =1.15)	Normal (K _o =1.00)	Uplift (K _o =1.15)	Normal (K _o =1.00)
HHUS26-2	14	3 5/16	5 13/16	3	3 15/16	(14) 16d	(6) 16d	2850	7335	2065	5205
HHUS28-2	14	3 5/16	7 7/32	3	6 5/32	(22) 16d	(8) 16d	3765	8940	2675	6345
HHUS210-2	14	3 5/16	9 3/32	3	8	(30) 16d	(10) 16d	4745	9660	4310	7000
HHUS210-3	14	4 11/16	9	3	7 15/16	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS210-4	14	6 1/8	8 29/32	3	7 27/32	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS46	14	3 5/8	5 13/32	3	3 15/16	(14) 16d	(6) 16d	2540	7335	2065	5205
HHUS48	14	3 5/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3765	8945	2267	6345
HHUS410	14	3 5/8	9	3	8	(30) 16d	(10) 16d	4745	9855	4310	7000
HHUS5.50/10	14	5 1/2	9	3	8	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS7.25/10	14	7 1/4	9	3 5/16	7 29/32	(30) 16d	(10) 16d	4745	10770	4310	7650

1. d_b is the distance from the seat of the hanger to the highest joist nail.




**LIMIT
STATES
DESIGN**

This technical bulletin is effective until June 30, 2019, and reflects information available as of March 1, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2017 Simpson Strong-Tie Company Inc.

T-SPECHUS17_3/17 exp. 6/19

(800) 999-5099
strongtie.com



Wood Truss Installation

**A Guide to proper handling, erecting and bracing
metal plate connected wood trusses**

Table of Content

Warning.....	4
1 Unloading & Lifting.....	5
2 Job Site Handling.....	5
3 Hoisting.....	6
4 Beginning the Erection Process.....	7
5 Erection Tolerance.....	8
6 Bracing.....	8
7 Bracing Requirements for 3 Planes of Roof.....	9
8 Stacking Materials.....	10
Caution Notes.....	11

Warning



General

Familiarity with the Construction Design Documents, the Truss Design Drawings, and Truss Placement Plans (if required by the Construction Design Documents) is required to properly erect, brace, and connect the trusses to the building system.

All of the care and quality involved in the design and manufacture of wood trusses can be jeopardized if the trusses are not properly handled, erected, and braced.

The consequences of improper handling, erecting, and bracing may be a collapse of the structure, which at best is a substantial loss of time and materials, and at worst is a loss of life. The majority of truss accidents occur during truss installation and not as a result of improper design or manufacture.

Prior to truss erection, the builder/erector shall meet with the erection crew for a safety and planning meeting, making sure each crew member understands his or her roles and responsibilities during the erection process.

Temporary Erection Bracing

Trusses are not marked in any way to identify the frequency, or location of temporary erection bracing.

All temporary bracing shall comply with the latest edition of *Commentary and Recommendations for Handling, Installing & Bracing Metal Plate Connected Wood Trusses* (HIB), published by the Truss Plate Institute, and/or as specified in the Construction Design Documents prepared by the building designer.

Permanent Truss Bracing

Permanent bracing for the roof or floor trusses is the responsibility of the building designer and should be shown on the Construction Design Documents. Permanent bracing locations for individual compression members of a wood truss are shown on the Truss Design Drawings, and shall be installed by the building or erection contractor. This bracing is needed for the proper performance of individual trusses within the roof or floor system. The design and connection of the bracing to the truss and then to the overall building system is the responsibility of the building designer, and is in addition to the permanent bracing plan, which is also specified by the building designer.

Special Design Requirements

Special design requirements, such as wind bracing, portal bracing, seismic bracing, diaphragms, shear walls, or other load transfer elements and their connections to wood trusses must be considered separately by the building designer, who shall determine size, location, and method of connections for all bracing as needed to resist these forces.

Unloading & Lifting

Never handle trusses flat



Beginning with the unloading process, and throughout all phases of construction, care must be taken to avoid lateral bending of trusses, which can cause damage to the lumber and metal connector plates at the joints.



Avoid lateral bending


- Use special care in windy weather.
- If using a crane within 10 feet of an electric line, contact the local power company.
- If using a crane within 5 miles of an airport, contact the airport 30 days prior to erection to learn about any safety regulations that must be followed.

Job Site Handling




All trusses should be picked up at the top chords in a vertical position only

Proper banding and smooth ground allow for unloading of trusses without damage. This should be done as close to the building site as possible to minimize handling. Do not break banding until installation begins. Hand erection of trusses is allowed, provided excessive lateral bending is prevented.




Do not store unbraced bundles upright

If trusses are stored vertically they shall be braced in a manner that will prevent tipping or topping. Generally cutting of the banding is done just prior to installation.



Do not store on uneven ground

If trusses are stored horizontally, blocking should be used on eight to ten foot centers, or as required, to minimize lateral bending and moisture gain.



Care should be exercised when removing banding to avoid damaging trusses.


During long term storage, trusses shall be protected from the environment in a manner that provides for adequate ventilation of the trusses. If tarpaulins or other material is used, the ends shall be left open for ventilation. Plastic is not recommended, since it can trap moisture.

3 Hoisting


All trusses that are erected one at a time shall be held safely in position by the erection equipment until such time as all necessary bracing has been installed and the ends of the trusses are securely fastened to the building.




Avoid lateral bending




$L \leq 30'$




Truss sling is acceptable where these criteria are met.




$30' < L \leq 60'$



Use spreader bar in all other cases. It should be noted that the lines from the ends of the spreader bar "TOE IN"; if these lines should "TOE OUT" the truss may fold in half.



$L > 60'$



For lifting trusses with spans in excess of 60 feet, it is recommended that a strongback/spreader bar be used as illustrated. The strongback/spreader bar should be attached to the top chord and web members at intervals of approximately 10 feet. Further, the strongback/spreader bar should be at or above the mid-height of the truss to prevent overturning. The strongback/spreader bar can be of any material with sufficient strength to safely carry the weight of the truss and sufficient rigidity to adequately resist bending of the truss.


4

Beginning the Erection Process


It is important for the builder or erection contractor to provide substantial bracing for the first truss erected. The two or more trusses making up the rest of the first set are tied to and rely upon the first truss for stability. Likewise, after this first set of trusses is adequately cross-braced, the remaining trusses installed rely upon this first set for stability. Thus, the performance of the truss bracing system depends to a great extent on how well the first group of trusses is braced.

Ground Brace – Exterior

One satisfactory method ties the first unit of trusses off to a series of braces that are attached to a stake driven into the ground and securely anchored. The ground brace itself should be supported as shown below or it is apt to buckle. Additional ground braces in the opposite direction, inside the building, are also recommended.





Note: Locate ground braces for first truss directly in line with all rows of top chord continuous lateral bracing (either temporary or permanent).



Ground Brace – Interior

Another satisfactory method where height of building or ground conditions prohibit bracing from the exterior is to tie the first truss rigidly in place from the interior at the floor level, provided the floor is substantially completed and capable of supporting the ground bracing forces. Securely fasten the first truss to the middle of the building. Brace the bracing similar to exterior ground bracing shown at left. Set trusses from the middle toward the end of the building. Properly cross-brace the first set of trusses before removing floor braces and setting remaining trusses.




Inadequate size of bracing material or inadequate fastening is a major cause of erection dominoing.


5 Erection Tolerance

Complying with erection tolerances is critical to achieving an acceptable roof or floor line, and to accomplishing effective bracing. Setting trusses within tolerance the first time will prevent the need for the hazardous practice of respacing or adjusting trusses when roof sheathing or roof purlins are installed. Trusses leaning or bowing can cause nails to miss the top chords when sheathing is applied, and create cumulative stresses on the bracing, which is a frequent cause of dominoing.

When sheathing, make sure nails are driven into the top chord of the trusses.



6 Bracing



Do not install trusses on temporarily connected supports



Do not walk on unbraced trusses



Do not walk on trusses or gable ends lying flat




Nails in withdrawal (parallel to force)

All anchors, hangers, tie-downs, seats, bearing ledgers, etc., that are part of the supporting structure shall be accurately and properly placed and permanently attached before truss installation begins. No trusses shall ever be installed on anchors or ties that have temporary connections to the supporting structure.

Nailing scabs to the end of the building to brace the first truss is not recommended.

All nailing of bracing should be done so that nails are driven perpendicular to the direction of force, as shown at right.




Well nailed (perpendicular to force)

7 Bracing Requirements for 3 Planes of Roof

Temporary erection bracing must be applied to three planes of the roof system to ensure stability: Plane 1) Top Chord (sheathing), Plane 2) Bottom Chord (ceiling plane), and Plane 3) Web Member plane or vertical plane perpendicular to trusses.

1) Top Chord Plane

Most important to the builder or erection contractor is bracing in the plane of the top chord. Truss top chords are susceptible to lateral buckling before they are braced or sheathed.




Exact spacing between trusses should be maintained as bracing is installed to avoid the hazardous practice of removing bracing to adjust spacing. This act of "adjusting spacing" can cause trusses to topple if connections are removed at the wrong time.

3) Web Member Plane

"X" bracing, as shown, is critical in preventing trusses from leaning or dominoing. Repeat as shown to create a succession of rigid units.


X-bracing should be installed on vertical web members wherever possible, at or near lateral bracing. Plywood or OSB may be substituted for X-bracing.



Note: Top chords and some web members are not shown, in order to make drawings more readable.

2) Bottom Chord Plane

In order to hold proper spacing on the bottom chord, temporary bracing is recommended on the top of the bottom chord.




* Long spans, heavy loads or other spacing configurations may require closer spacing between lateral bracing and closer intervals between diagonals. Consult the building designer or HIB and DSB (Recommended Design Specification for Temporary Bracing of Metal-Plate Connected Wood Trusses) for details.

Diagonal or cross-bracing is very important!



Do not use short blocks to brace individual trusses without a specific bracing plan detailing their use





Bracing requirements using the same principles apply to parallel chord trusses

8 Stacking Materials

Do not proceed with building completion until all bracing is securely and properly in place


Never stack materials on unbraced or inadequately braced trusses



Platform must be rigidly braced

Proper distribution of construction materials is a must during construction.


Never stack materials near a peak




Acceptable against outside load bearing wall

Acceptable over load bearing wall

Never stack materials on the cantilever of a truss




Always stack materials over two or more trusses.




Single truss

Never overload small groups or single trusses. Position load over as many trusses as possible.



Roofing and mechanical contractors are cautioned to stack materials only along outside supporting members or directly over inside supporting members. Trusses are not designed for dynamic loads (i.e., moving vehicles). Extreme care should be taken when loading and stacking construction materials (rolled roofing, mechanical equipment, etc.) on the roof or floor system.

Never cut any structural member of a truss.



Sleepers

Panel point

Sleepers for mechanical equipment should be located at panel points (joints) or over main supporting members, and only on trusses that have been designed for such loads.

Caution Notes

Errors in building lines and/or dimensions, or errors by others shall be corrected by the contractor or responsible construction trade subcontractor or supplier before erection of trusses begins.

Cutting of nonstructural overhangs is considered a part of normal erection and shall be done by the builder or erection contractor.

Any field modification that involves the cutting, drilling, or relocation of any structural truss member or connector plate shall not be done without the approval of the truss manufacturer or a licensed design professional.

The methods and procedures outlined are intended to ensure that the overall construction techniques employed will put floor and roof trusses safely in place in a completed structure. These recommendations for bracing wood trusses originate from the collective experience of leading technical personnel in the wood truss industry, but must, due to the nature of responsibilities involved, be presented only as a guide for use by a qualified building designer, builder, or erection contractor. Thus, the Wood Truss Council of America expressly disclaims any responsibility for damages arising from the use, application, or reliance on the recommendations and information contained herein.

[Selected text and figures referenced or reproduced from HIB and DSB by permission of the Truss Plate Institute, Madison, WI.]

THE CANADIAN WOOD TRUSS ASSOCIATION



L'ASSOCIATION CANADIENNE DES FABRICANTS DE FERMES DE BOIS

1400 Blair Place, Suite 210, Ottawa, ON K1J 9B8
Tel.: 613-747-5544 Fax: 613-747-6264



**Wood Truss Council
of America**

One WTCA Center
6300 Enterprise Lane, Madison, WI 53719-1140
Tel.: 608-274-4849 Fax: 608-274-3329
wtca@woodtruss.com www.woodtruss.com

THESE DRAWINGS CONSTITUTE THE PROPERTY OF ALPA ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY ALPA ROOF TRUSSES INC AND WILL BE RETRACTED BY ALPA ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

EWP DESIGN INC.

(905) 832-2250

FAX (905) 832-0286

RESPONSIBILITIES AND SPECIFICATIONS

RESPONSIBILITIES

1. EWP DESIGN INC. is responsible for the design of trusses as individual components.
2. It is the responsibility of others to ascertain that the design loads utilized on each drawing meet or exceed the actual dead load imposed by the structure, the live load imposed by the intended use and the snow load imposed by local building code or authorities with jurisdictions.
3. All dimensions are to be verified by the owner, contractor, architect or other authorities with jurisdictions before truss fabrication.
4. EWP DESIGN INC. bears no responsibility for the erection of trusses. Persons erecting trusses are cautioned to seek professional advice regarding the temporary and permanent bracing for the system. Bracing shown on EWP DESIGN INC. drawing is specified for the truss as a component only and forms an integral part of the truss design.
5. It is the truss manufacturer's responsibility to ensure that trusses are manufactured in conformance with specifications of EWP DESIGN INC. as outlined below.


SPECIFICATIONS

1. Trusses designed by EWP DESIGN INC. conform to the relevant section of the Ontario Building Code of Canada (Part 9 or Part 4) or to the Canadian code for farm buildings, whichever applies to the building type, as indicated on the EWP DESIGN INC. drawings, and conform to the design procedures established by the Truss Plate Institute of Canada. Unit stresses used for truss designs are as per the edition of CSA-O86 shown on EWP DESIGN INC. drawings.
2. Lumber is to be the size, species and grade as specified on EWP DESIGN INC. drawings.
3. Moisture content of lumber shall not exceed 19% in service unless specified otherwise.
4. Metal connector plates shall be applied to both faces of truss at each joint and shall be positioned as specified.
5. Top chords of trusses are assumed to be continuously braced laterally by roof sheathing or by purlins at intervals not exceeding 12.5 times the thickness of top chord member.
6. Bottom chords shall be laterally braced at intervals not exceeding 3M (10') o.c., where rigid ceiling is not applied directly to the underside of chords.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF EWP DESIGN INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY THE ALPA LUMBER GROUP, AND WILL BE RETRACTED BY EWP DESIGN INC. IF UTILIZED FOR ANY OTHER PURPOSE.

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:33:03 2019 Page 1
ID:1dJR6DYvLvIXkyExRWgN1yQawr-RJEdYgoKEcvdN5Ed5xVG7qFa96Q7lqYAG1ctJ4yKFGU



Scale = 1:14.0

TOTAL WEIGHT = 6 X 9 = 55 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.	SPF
A - D	2x4	DRY	No.2			
B - E	2x4	DRY	No.2			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMBH1-I	MT20	3.0	4.0	1.50 0.50

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG	HEEL WEDGE
	VERT	HORZ	DOWN	HORZ			
JT	222	0	222	0	4-0	1-8	2x4 L
B	46	0	46	0	5-8	1-8	
F	137	0	137	0	5-8	5-8	

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): C

UNFACTORED REACTIONS

	1ST LCASE	MAX/MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED	111 / 0	0 / 0	0 / 0	0 / 0	44 / 0	0 / 0
B		35	10 / 0	0 / 0	0 / 0	25 / 0	0 / 0
F		95	73 / 0	0 / 0	0 / 0	22 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO				FR-TO			
A-B	0 / 16	-84.9	0.12 (5)	G-H	-61 / 0	0.00 (1)	
B-H	-15 / 0	-84.9	0.01 (4)				
H-C	0 / 3	-84.9	0.04 (1)				
C-D	-14 / 0	-84.9	0.03 (1)				
B-G	0 / 0	-18.5	0.04 (1)				
G-F	0 / 0	-18.5	0.04 (1)				
F-E	0 / 0	-18.5	0.01 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CANTILEVER DEFLECTION:
ALLOWABLE DEFL.(TL)= L/120 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:5), BC=0.04/1.00 (B-G:1), WB=0.00/1.00 (G-H:1), SSI=0.09/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (B) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2


CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H1A		2	TRUSS DESC. JT-39002	E-19112571

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 13:51:05 2019 Page 1
ID:1dJR6DYvLvlXkyExRWgN1yQawr-ITcgeev0Q2E6BNyaTaw7z?3MIGelG19R3N18HMyKFPa



TOTAL WEIGHT = 2 X 120 = 240 lb

LUMBER

N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - C	2x4 DRY	No.2	SPF
C - F	2x4 DRY	No.2	SPF
F - H	2x4 DRY	No.2	SPF
I - H	2x4 DRY	No.2	SPF
O - B	2x4 DRY	No.2	SPF
O - K	2x6 DRY	No.2	SPF
K - I	2x6 DRY	No.2	SPF

ALL WEBS	2x3 DRY	No.2	SPF
EXCEPT			

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - F	12	SIDE(41.1)
F - H	12	SIDE(41.1)
H - I	12	TOP
O - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
O - K	12	SIDE(174.2)
K - I	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
L - E	6	SIDE(113.6)
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	UP/LIFT	IN-SX
JT	2663	0	2663	0
O	2041	0	2041	0

UNFACTORED REACTIONS

	1ST LCASE	MAX/MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	1890	1200 / 0	0 / 0	0 / 0	0 / 0	690 / 0	0 / 0
O	1447	932 / 0	0 / 0	0 / 0	0 / 0	515 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, O

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.88 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRAC. LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)
FR-TO		FROM TO			FR-TO		
A-B	0 / 42	-84.9 -84.9	0.07 (1)	10.00	N-C	-402 / 0	0.08 (1)
B-C	-1766 / 0	-84.9 -84.9	0.11 (1)	6.25	B-N	0 / 1342	0.17 (1)
C-D	-2620 / 0	-84.9 -84.9	0.20 (1)	5.41	C-M	0 / 1910	0.24 (1)
D-E	-3384 / 0	-84.9 -84.9	0.22 (1)	4.88	M-D	-1218 / 0	0.25 (1)
E-F	-2386 / 0	-167.1 -167.1	0.40 (1)	5.31	L-E	0 / 1079	0.13 (1)
F-G	-2386 / 0	-167.1 -167.1	0.40 (1)	5.31	D-L	0 / 447	0.06 (1)
G-H	-2386 / 0	-167.1 -167.1	0.40 (1)	5.31	E-J	-1438 / 0	0.66 (1)
H-I	-2574 / 0	0.0 0.0	0.59 (1)	7.07	J-G	-999 / 0	0.20 (1)
O-B	-2023 / 0	0.0 0.0	0.12 (1)	7.75	J-H	0 / 3247	0.40 (1)
O-N	0 / 0	-18.5 -18.5	0.02 (4)	10.00			
N-M	0 / 1235	-18.5 -18.5	0.10 (1)	10.00			
M-L	0 / 2620	-18.5 -18.5	0.20 (1)	10.00			
L-K	0 / 3384	-36.4 -36.4	0.27 (1)	10.00			
K-J	0 / 3384	-36.4 -36.4	0.27 (1)	10.00			
J-I	0 / 0	-36.4 -36.4	0.05 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
L	13-5-9	-1103	-1103	MAX+	FRONT	VERT	TOTAL	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 3-5-5
RIGHT SETBACK = 0-0
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 10-5-0 OF SPAN MEASURED FROM THE RIGHT.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 088-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.10")

CSI: TC=0.59/1.00 (H-I:1), BC=0.27/1.00 (J-L:1), WB=0.66/1.00 (E-J:1), SI=0.23/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

CONTINUED ON PAGE 2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H1A		2	JT-39002	E-19112571(2)

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:51:05 2019 Page 2
ID:1dJR6DYvLvIXKyExRWgN1yQawr-ITcgeev0Q2E6BNyaTaw?z73MfGelG19R3Ni8HMyKFPa

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.75	2.00
C	TTWW+m	MT20	5.0	6.0	2.00	1.50
D	TMVW-t	MT20	4.0	4.0		
E	TMVW-t	MT20	4.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMV+w	MT20	2.0	4.0		
H	TMVW-t	MT20	4.0	6.0	1.75	2.75
I	BMV1+p	MT20	2.0	4.0		
J	BMVWW-t	MT20	5.0	8.0		
K	BS-t	MT20	4.0	6.0		
L	BMVW-t	MT20	4.0	4.0		
M	BMVW-t	MT20	4.0	4.0	2.00	1.75
N	BMVW-t	MT20	4.0	4.0		
O	BMV1+p	MT20	2.0	4.0		

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	618	354	1667
	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (H) (INPUT = 0.80)

JSI METAL= 0.45 (K) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
G - H	2x4	DRY	No.2	SPF
O - B	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
O - K	2x6	DRY	No.2	SPF
K - I	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - E	12	TOP
E - G	12	SIDE(41.1)
G - H	12	SIDE(61.0)
O - B	12	TOP
I - H	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
O - K	12	SIDE(10.0)
K - I	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
J - G	6	SIDE(9.9)
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT 2061	DOWN 2061	0	5-8
O	HORZ 0	HORZ 0	0	1-8
I	0	0	0	1-8

UNFACTORED REACTIONS

	1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
O	1461	941 / 0	0 / 0	0 / 0	0 / 0	519 / 0	0 / 0	
I	1846	1165 / 0	0 / 0	0 / 0	0 / 0	681 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, I

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.55 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 42	-84.9 -84.9	0.07 (1)	N-C	-474 / 0	0.10 (1)	
B-C	-1767 / 0	-84.9 -84.9	0.11 (1)	J-G	-784 / 0	0.16 (1)	
C-D	-2850 / 0	-84.9 -84.9	0.25 (1)	B-N	0 / 1343	0.17 (1)	
D-E	-3375 / 0	-84.9 -84.9	0.44 (1)	J-H	0 / 1755	0.22 (1)	
E-F	-3375 / 0	-167.1 -167.1	0.44 (1)	C-M	0 / 2113	0.26 (1)	
F-G	-3374 / 0	-167.1 -167.1	0.47 (1)	M-D	-948 / 0	0.19 (1)	
G-H	-2167 / 0	-84.9 -84.9	0.10 (1)	D-L	0 / 698	0.09 (1)	
O-B	-2025 / 0	0.0 0.0	0.12 (1)	L-F	-932 / 0	0.19 (1)	
I-H	-2538 / 0	0.0 0.0	0.16 (1)	L-G	0 / 2441	0.30 (1)	
O-N	0 / 0	-18.5 -18.5	0.01 (4)				
N-M	0 / 1234	-18.5 -18.5	0.18 (1)				
M-P	0 / 2850	-18.5 -18.5	0.60 (1)				
P-L	0 / 2850	-36.4 -36.4	0.60 (1)				
L-K	0 / 1508	-36.4 -36.4	0.25 (1)				
K-J	0 / 1508	-36.4 -36.4	0.25 (1)				
J-I	0 / 0	-36.4 -36.4	0.03 (4)				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	20-8-11	-195	-195	-	FRONT	VERT	TOTAL	-	C1
P	13-5-9	-1103	-1103	-	FRONT	VERT	TOTAL	-	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 3-5-5
RIGHT SETBACK = 3-1-14
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL. LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 10-5-0 OF SPAN MEASURED FROM THE RIGHT.

*** NON STANDARD GIRDER ***
ADDTL. USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/ 899 (0.07")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.13")

CSI: TC=0.47/1.00 (F-G:1), BC=0.50/1.00 (L-M:1), WB=0.30/1.00 (G-L:1), SS=0.31/1.00 (L-M:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H9		2	JT-39002	E-19112572(2)

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2018 MTEK Industries, Inc. Mon Nov 11 13:50:01 2019 Page 2
ID:1dJR6DYvLvlIXkyExRWgN1yQawr-d9kTCm7tUOABVY3Hjkm NVPSITt4HAr0LQCI23yKFOa

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.75	2.00
C	TTWW+m	MT20	5.0	6.0	2.00	1.25
D	TMWW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMW+w	MT20	2.0	4.0		
G	TTWW+m	MT20	5.0	6.0	1.75	1.25
H	TMVW+p	MT20	4.0	6.0	2.75	2.00
I	BMV1+p	MT20	2.0	4.0		
J	BMWW-t	MT20	4.0	4.0		
K	BS-t	MT20	4.0	6.0		
L	BMWWW-t	MT20	5.0	8.0		
M	BMWW-t	MT20	4.0	4.0	2.00	1.50
N	BMWW-t	MT20	4.0	4.0		
O	BMV1+p	MT20	2.0	4.0		

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	618	354	1667
	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (J) (INPUT = 0.90)
JSI METAL= 0.42 (H) (INPUT = 1.00)


NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME 313997	TRUSS NAME H10	QUANTITY 1	PLY 1	JOB DESC. TRUSS DESC.	JT-39002	DRWG NO. E-19112573
---------------------------	--------------------------	----------------------	-----------------	---------------------------------	-----------------	-------------------------------

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MTek Industries, Inc. Mon Nov 11 13:47:50 2019 Page 1
ID:1dJR6DYvLvlIXyExRWgN1yQawr-zyKyjzXIL8gmIPY6YjwGZtUy7f464tSkDXzJx9yKFSd



TOTAL WEIGHT = 103 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - F	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
L - I	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.00	1.50
D	TMVW+w	MT20	2.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.00	1.50
F	TMVW+p	MT20	4.0	6.0	2.75	2.00
G	BMV1+p	MT20	2.0	4.0		
H	BMVW-t	MT20	4.0	4.0		
I	BS-t	MT20	3.0	6.0		
J	BMVWW-t	MT20	5.0	6.0		
K	BMVW-t	MT20	4.0	4.0	2.00	1.75
L	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED		MAXIMUM FACTORED		INPUT	REQRD
	GROSS REACTION	DOWN	GROSS REACTION	UPLIFT		
JT	VERT	HORZ	DOWN	HORZ	BRG	BRG
L	1348	0	1348	0	5-8	2-0
G	1230	0	1230	0	1-9	1-8

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	955	619 / 0	0 / 0	0 / 0	336 / 0	0 / 0
L	873	554 / 0	0 / 0	0 / 0	319 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.14 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		MEMB.	WEBS	
	MAX. FACTORED	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX. (LC)		MAX. FACTORED	FORCE (LBS)
FR-TO			FROM	TO	FR-TO		
A-B	0 / 42	-84.9	-84.9	0.12 (1)	K-C	-111 / 50	0.08 (1)
B-C	-1072 / 0	-84.9	-84.9	0.39 (1)	C-J	0 / 686	0.15 (1)
C-D	-1249 / 0	-84.9	-84.9	0.90 (1)	J-D	-761 / 0	0.56 (1)
D-E	-1249 / 0	-84.9	-84.9	0.90 (1)	J-E	0 / 714	0.16 (1)
E-F	-1011 / 0	-84.9	-84.9	0.32 (1)	H-E	-177 / 23	0.13 (1)
L-B	-1317 / 0	0.0	0.0	0.15 (1)	B-K	0 / 791	0.18 (1)
G-F	-1203 / 0	0.0	0.0	0.15 (1)	H-F	0 / 772	0.17 (1)
L-K	0 / 0	-18.5	-18.5	0.16 (4)			
K-J	0 / 754	-18.5	-18.5	0.27 (4)			
J-I	0 / 709	-18.5	-18.5	0.26 (4)			
I-H	0 / 708	-18.5	-18.5	0.26 (4)			
H-G	0 / 0	-18.5	-18.5	0.15 (4)			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-06, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.79")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.04")
ALLOWABLE DEFL.(TL) = $L/360$ (0.79")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.09")

CSI: TC=0.90/1.00 (D-E:1), BC=0.27/1.00 (J-K:4), WB=0.58/1.00 (D-J:1), SSI=0.30/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1687

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.65 (H) (INPUT = 0.80)
JSI METAL= 0.48 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2




JOB NAME 313997	TRUSS NAME H11S	QUANTITY 1	PLY 1	JOB DESC. TRUSS DESC.	JT-39002	DRWG NO. E-19112574
---------------------------	---------------------------	----------------------	-----------------	---------------------------------	-----------------	-------------------------------

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 13:32:12 2019 Page 1

ID:1dJR6DYvLIIKXyExRWgN1yQawr-QVeLrEBKFxUsmFqqbJ5IY3dpBYyfJgoXclh1XyKFhH



Scale = 1:58.7

TOTAL WEIGHT = 6 X 64 = 385 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - E	2x4	DRY	2100F 1.8E	SPF	
H - B	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
C	TMVW+t	MT20	3.0	5.0	2.00	1.00
D	TTW+p	MT20	3.0	4.0	Edge	
E	TMVW+p	MT20	4.0	6.0	2.75	2.00
F	BMV1+p	MT20	2.0	4.0		
G	BMVWV+t	MT20	4.0	6.0		
H	BMVWV-t	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQRD
	VERT	DOWN	BRG	BRG
JT	689	0	0	0
F	807	0	0	0
H	807	0	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	489	310 / 0	0 / 0	0 / 0	0 / 0	179 / 0	0 / 0
H	571	375 / 0	0 / 0	0 / 0	0 / 0	195 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

C H O R D S				W E B S			
MAX. FACTORED		FACTORED		MAX. FACTORED			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM TO			FR-TO		
A-B	0 / 42	-84.9 -84.9	0.12 (1)	10.00	C-G	-140 / 0	0.09 (1)
B-C	0 / 24	-84.9 -84.9	0.16 (1)	10.00	G-D	0 / 182	0.05 (4)
C-D	-427 / 0	-84.9 -84.9	0.13 (1)	6.25	H-C	-644 / 0	0.39 (1)
D-E	-403 / 0	-84.9 -84.9	0.30 (1)	6.25	G-E	0 / 298	0.07 (1)
H-B	-228 / 0	0.0 0.0	0.03 (1)	7.81			
F-E	-645 / 0	0.0 0.0	0.08 (1)	7.81			
H-G	0 / 366	-18.5 -18.5	0.27 (4)	10.00			
G-F	0 / 0	-18.5 -18.5	0.24 (4)	10.00			

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 36.7	PSF	

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 085-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.I. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.44")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.44")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.05")

CSI: TC=0.30/1.00 (D-E:1), BC=0.27/1.00 (G-H:4), WB=0.39/1.00 (C-H:1), SSI=0.16/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.


JSI GRIP= 0.79 (H) (INPUT = 0.80)
JSI METAL= 0.39 (C) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H11T		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:31:49 2019 Page 1

ID:1dJR6DYvLVlIXyExRWgN1yQawr-c4f0Nvvtb7VjaPIOAv7DAv9G8TQKCHFXhzjMyKFhe



Scale = 1:58.7

TOTAL WEIGHT = 4 X 71 = 282 lb

[M][F]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
L - B	2x4	DRY	No.2
H - F	2x4	DRY	No.2
L - K	2x4	DRY	No.2
K - J	2x4	DRY	No.2
J - I	2x4	DRY	No.2
I - H	2x4	DRY	No.2

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	6.0	2.75	2.00
C TMWW-t	MT20	3.0	4.0	1.50	1.00
D TTW+p	MT20	3.0	5.0		
E TMWW-t	MT20	3.0	4.0	1.50	1.00
F TMVW+p	MT20	4.0	6.0	2.75	2.00
H BMV1+p	MT20	2.0	4.0		
I BBWW-I	MT20	4.0	6.0	2.00	4.00
J BBWWV-p	MT20	5.0	6.0	2.75	3.00
K BBWW-I	MT20	4.0	6.0	2.00	4.00
L BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQRD
	VERT	DOWN	HORZ	UPLIFT
JT	829	0	0	5-8
L	829	0	0	5-8
H	829	0	0	5-8

UNFACTORED REACTIONS

	1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
JT	586	385 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0	
L	586	385 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC)	UNBRACED LENGTH (FT)
FR-TO				FR-TO			
A-B	0 / 42	-84.9	-84.9 0.12 (1)	10.00	J-D	0 / 572	0.13 (1)
B-C	-536 / 0	-84.9	-84.9 0.14 (1)	6.25	J-E	0 / 37	0.01 (1)
C-D	-625 / 0	-84.9	-84.9 0.16 (1)	6.25	I-E	-408 / 0	0.13 (1)
D-E	-625 / 0	-84.9	-84.9 0.16 (1)	6.25	C-J	0 / 37	0.01 (1)
E-F	-536 / 0	-84.9	-84.9 0.14 (1)	6.25	K-C	-408 / 0	0.13 (1)
F-G	0 / 42	-84.9	-84.9 0.12 (1)	10.00	B-K	0 / 453	0.10 (1)
L-B	-802 / 0	0.0	0.0 0.09 (1)	7.81	I-F	0 / 453	0.10 (1)
H-F	-802 / 0	0.0	0.0 0.09 (1)	7.81			
L-K	0 / 0	-18.5	-18.5 0.05 (4)	10.00			
K-J	0 / 473	-18.5	-18.5 0.13 (4)	10.00			
J-I	0 / 473	-18.5	-18.5 0.13 (4)	10.00			
I-H	0 / 0	-18.5	-18.5 0.05 (4)	10.00			

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.46")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.46")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.04")

CSI: TC=0.16/1.00 (C-D:1), BC=0.13/1.00 (J-K:4)
WB=0.13/1.00 (E-I:1), SSI=0.11/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.75 (I) (INPUT = 0.90)
JSI METAL= 0.26 (B) (INPUT = 1.00)



CHORDS				WEBS				
MAX. FACTORED		FACTORED		MAX. FACTORED				
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM TO			FR-TO			
A-B	0 / 42	-84.9	-84.9	0.12 (1)	10.00	J-D	-271 / 0	0.15 (1)
B-C	-67 / 0	-84.9	-84.9	0.19 (1)	6.25	J-E	-67 / 0	0.02 (1)
C-D	-29 / 0	-84.9	-84.9	0.19 (1)	6.25	I-E	-280 / 0	0.09 (1)
D-E	-29 / 0	-84.9	-84.9	0.19 (1)	6.25	C-J	-67 / 0	0.02 (1)
E-F	-67 / 0	-84.9	-84.9	0.19 (1)	6.25	K-C	-280 / 0	0.09 (1)
F-G	0 / 42	-84.9	-84.9	0.12 (1)	10.00	B-K	0 / 81	0.02 (1)
L-B	-298 / 0	0.0	0.0	0.03 (1)	7.81	I-F	0 / 81	0.02 (1)
H-F	-298 / 0	0.0	0.0	0.03 (1)	7.81			
L-K	0 / 0	-18.5	-18.5	0.05 (4)	10.00			
K-J	0 / 79	-18.5	-18.5	0.09 (4)	10.00			
J-I	0 / 79	-18.5	-18.5	0.09 (4)	10.00			
I-H	0 / 0	-18.5	-18.5	0.05 (4)	10.00			

Algo Roof Truss, Maple Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:31:13 2019 Page 1




JSI GRIP= 0.56 (K) (INPUT = 0.90)
JSI METAL= 0.12 (X) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	H16P		1	TRUSS DESC.	JT-39002 E-19112578

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:29:58 2019 Page 1
ID:1dJR6DYvLvIXKyExRWgN1yQawr-MjYhJQZHomcthg4laht7p4zuXhvv9WxjllbJlyKFjN



Scale = 1:16.5

TOTAL WEIGHT = 2 X 15 = 30 lb [M]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
B - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

GABLE STUDS SPACED AT 2'-0" OC.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0		
C	TTW+p	MT20	3.0	4.0	2.25	1.50
D	TMB1-I	MT20	3.0	4.0		
F	BMW1+w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): F

PROVIDE ANCHORAGE AT BEARING JOINT A FOR 150 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT E FOR 150 LBS FACTORED UPLIFT
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (1)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (1)
FR-TO		FROM TO		FR-TO		FROM TO	
A-B	0 / 27	-103.4 -103.4	0.05 (1)	10.00	F-C	-108 / 0	0.02 (1)
B-H	-71 / 0	-84.9 -84.9	0.05 (1)	6.25	G-H	-66 / 10	0.00 (1)
H-C	-48 / 0	-84.9 -84.9	0.05 (1)	6.25	I-J	-66 / 10	0.00 (1)
C-J	-48 / 0	-84.9 -84.9	0.05 (1)	6.25			
J-D	-71 / 0	-84.9 -84.9	0.05 (1)	6.25			
D-E	0 / 27	-103.4 -103.4	0.06 (1)	10.00			
B-G	0 / 35	-18.5 -18.5	0.03 (1)	10.00			
G-F	0 / 35	-18.5 -18.5	0.04 (1)	10.00			
F-I	0 / 35	-18.5 -18.5	0.04 (1)	10.00			
I-D	0 / 35	-18.5 -18.5	0.03 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.05/1.00 (D-E:1), BC=0.04/1.00 (F-G:1), WB=0.02/1.00 (C-F:1), SSI=0.06/1.00 (C-J:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.19 (B) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	P01		1	TRUSS DESC.	JT-39002
Alpa Roof Truss, Maple					E-19112579

Version 8.300 S Aug 9 2018 MiTek Industries, Inc. Mon Nov 11 14:01:17 2018 Page 1
ID:1dJR6DYvLVIXkyExRWgN1yQawr-qCa15vJv5LGcQkCKiuWn2P7szWTfwWobyXnuYKFG0



Scale = 1:22.5

TOTAL WEIGHT = 6 X 18 = 106 lb [M/F]

LUMBER					
N. L. G. A. RULES					
CHORDS	SIZE	LUMBER	DESCR.	SPF	
A - C	2x4	DRY	No.2	SPF	
F - D	2x4	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)					
JT TYPE	PLATES	W	LEN	Y	X
A	TBMH1-m	MT20	4.0	12.0	2.00 5.25

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD		HEEL	
JT	VERT	GROSS REACTION	HORZ	GROSS REACTION	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	WEDGE	
A	424	0	424	0	0	0	5-8	1-8	1-8	2x4 L	
E	102	0	102	0	0	0	5-8	1-8	1-8		
B	276	0	276	0	0	0	5-8	5-8	5-8		

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): B

UNFACTORED REACTIONS

JT	1ST CASE	MAX./MIN.	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
A	301	191 / 0	0 / 0	0 / 0	0 / 0	0 / 0	110 / 0	0 / 0
E	77	24 / 0	0 / 0	0 / 0	0 / 0	0 / 0	53 / 0	0 / 0
B	182	147 / 0	0 / 0	0 / 0	0 / 0	0 / 0	45 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, B

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		W E B S		FACTORED	
MEMB.	FORCE (LBS)	VERT.	LC1	MAX.	MEMB.	FORCE (LBS)	MAX.
FR-TO					FR-TO		
A-H	-20 / 0	-84.9	-84.9	0.07 (4)	G-H	-224 / 5	0.00 (1)
H-B	0 / 4	-84.9	-84.9	0.36 (1)			
B-C	-14 / 0	-84.9	-84.9	0.03 (1)			
F-A	0 / 0	-103.4	-103.4	0.10 (1)			
A-G	0 / 0	-18.5	-18.5	0.29 (1)			
G-E	0 / 0	-18.5	-18.5	0.29 (1)			
E-D	0 / 0	-18.5	-18.5	0.01 (4)			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 0.0 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.07")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/493$ (0.14")

CANTILEVER DEFLECTION:
ALLOWABLE DEFL.(LL) = $L/120$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/120$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.36/1.00 (B-H:1), BC=0.29/1.00 (E-G:1), WB=0.00/1.00 (G-H:1), SSI=0.19/1.00 (A-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.04 (A) (INPUT = 0.80)
JSI METAL= 0.01 (A) (INPUT = 1.00)


NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313997	G01		1	TRUSS DESC. JT-39002	E-19112580

Alpha Roof Truss, Maple

Version 6.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 13:32:59 2019 Page 1
ID:1dJR6DYvLvIXkyExRWgN1yQawr-YY_6JlpANPBuUwss5Rky_4u2U1Yp0ZaLQegAlyKFgY



TOTAL WEIGHT = 6 X 12 = 69 lb

LUMBER

N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
B - E	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMBH1-I	MT20	3.0	4.0	1.50	0.50

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG	HEEL WEDGE
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
B	274	0	274	0	4-0
F	59	0	59	0	5-8
C	175	0	175	0	5-8

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): C

UNFACTORED REACTIONS

1ST CASE	MAX / MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW
B	192	135 / 0
F	45	13 / 0
C	121	94 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MEMB.	FORCE (LBS)
FR-TO		FROM TO	FR-TO	
A-B	0 / 16	-84.9 -84.9 0.13 (5)	G-H	-117 / 2
B-H	-17 / 0	-84.9 -84.9 0.02 (4)		
H-C	0 / 2	-84.9 -84.9 0.10 (1)		
C-D	-14 / 0	-84.9 -84.9 0.03 (1)		
B-G	0 / 0	-18.5 -18.5 0.08 (1)		
G-F	0 / 0	-18.5 -18.5 0.08 (1)		
F-E	0 / 0	-18.5 -18.5 0.01 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 23.3 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CANTILEVER DEFLECTION:
ALLOWABLE DEFL.(TL) = $L/120$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.13/1.00 (A-B-5), BC=0.08/1.00 (F-G-1), WB=0.00/1.00 (G-H-1), SSI=0.10/1.00 (A-B-5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN




JOB NAME 314237	TRUSS NAME H1T	QUANTITY	PLY 2	JOB DESC. TRUSS DESC.	JT-39002	DRWG NO. E-19112581
---------------------------	--------------------------	----------	-----------------	---------------------------------	-----------------	-------------------------------

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 14:28:54 2018 Page 1

ID:1dJR6DYvLvlXkyExRWgN1yQawr-p_CRSVMH3C69v4vguC74RUX7dv0LPEsPqurIRLyKEs7



TOTAL WEIGHT = 4 X 132 = 529 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF		
C - F	2x4	DRY	No.2	SPF		
F - J	2x4	DRY	No.2	SPF		
K - L	2x4	DRY	No.2	SPF		
R - B	2x6	DRY	No.2	SPF		
R - O	2x6	DRY	No.2	SPF		
O - N	2x6	DRY	No.2	SPF		
N - M	2x6	DRY	No.2	SPF		
M - L	2x6	DRY	No.2	SPF		
L - K	2x6	DRY	No.2	SPF		
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF		

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	SIDE(81.0)
C - F	12	SIDE(41.1)
F - J	12	SIDE(41.1)
J - K	12	TOP
R - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
R - O	12	SIDE(10.0)
O - N	12	SIDE(7.1)
N - M	12	SIDE(50.1)
M - L	12	SIDE(7.1)
L - K	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
Q - C	6	SIDE(14.5)
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
K	2444	0	2444	0
R	2464	0	2464	0

UNFACTORED REACTIONS

1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	1734	1103 / 0	0 / 0	0 / 0	0 / 0	631 / 0	0 / 0
K	1748	1115 / 0	0 / 0	0 / 0	0 / 0	634 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, R

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.03 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. FACTORED VERT. LOAD (PLF)	CS1 (LC)	UNBRACED LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (PLF)	CS1 (LC)
FR-TO								FR-TO				
A - B	0 / 42	-84.9	-84.9	0.07 (1)	10.00	Q - C	-445 / 0	0.09 (1)				
B - C	-2163 / 0	-84.9	-84.9	0.12 (1)	5.92	C - P	0 / 1741	0.22 (1)				
C - D	-2630 / 0	-167.1	-167.1	0.27 (1)	5.29	P - D	-1234 / 0	0.25 (1)				
D - E	-3004 / 0	-167.1	-167.1	0.28 (1)	5.01	D - O	0 / 580	0.07 (1)				
E - F	-4964 / 0	-167.1	-167.1	0.19 (1)	4.18	O - E	-3238 / 0	0.66 (1)				
F - G	-4964 / 0	-167.1	-167.1	0.19 (1)	4.18	E - N	0 / 3452	0.43 (1)				
G - H	-4980 / 0	-84.9	-84.9	0.40 (1)	4.03	N - G	-447 / 0	0.04 (1)				
H - I	-2685 / 0	-167.1	-167.1	0.24 (1)	5.28	N - H	0 / 2453	0.30 (1)				
I - J	-735 / 0	-167.1	-167.1	0.10 (1)	6.25	M - H	-1669 / 0	0.17 (1)				
K - J	-2414 / 0	0.0	0.0	0.56 (1)	7.25	M - I	0 / 3419	0.42 (1)				
R - B	-2419 / 0	0.0	0.0	0.09 (1)	7.81	L - I	-2818 / 0	0.57 (1)				
						L - J	0 / 2327	0.29 (1)				
						B - Q	0 / 1643	0.20 (1)				
R - Q	0 / 0	-36.4	-36.4	0.03 (4)	10.00							
Q - P	0 / 1513	-36.4	-36.4	0.12 (1)	10.00							
P - O	0 / 2631	-36.4	-36.4	0.20 (1)	10.00							
O - N	0 / 4151	-36.4	-36.4	0.28 (1)	10.00							
N - M	0 / 2745	-118.6	-118.6	0.41 (1)	10.00							
M - L	0 / 955	-36.4	-36.4	0.07 (1)	10.00							
L - K	0 / 0	-36.4	-36.4	0.01 (4)	10.00							

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	3-5-5	-213	-213	-	FRONT	VERT	TOTAL	-	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 23.3 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 3-6-5
RIGHT SETBACK = 0-0
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL. LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 13-8-0 OF SPAN MEASURED FROM THE LEFT.

GIRDER TYPE: CStdGirder
START DISTANCE = 13-8-0
START SPAN CARRIED = 5-10-8
END DISTANCE = 20-2-0
END SPAN CARRIED = 5-10-8
END WALL WIDTH = 0-0
APPLIED TO FRONT SIDE OF BOTTOM CHORD.
- ADDTL. LOADS BASED ON 55 % OF GSL.

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 3-6-5
RIGHT SETBACK = 0-0
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL. LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 3-8-9 OF SPAN MEASURED FROM THE RIGHT.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.24")

CSI: TC=0.66/1.00 (J-K:1), BC=0.41/1.00 (M-N:1), WB=0.66/1.00 (E-O:1), SS=0.18/1.00 (C-D:1)

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
314237	H1T		2	JT-39002	E-19112581(2)

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 14:28:54 2019 Page 2
ID:1djR6DYvLvllXkyExRWgN1yQawr-p CRsVMH3C68v4vquC74RUX7dv0LPEsPquriRLyKEs7

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	5.0	6.0	1.75	2.75
C	TTWW+m	MT20	5.0	6.0	2.00	1.50
D	TMWW-t	MT20	4.0	4.0		
E	TMWW+H	MT20	4.0	6.0	3.00	1.50
F	TS-t	MT20	3.0	6.0	1.50	3.00
G	TMW+w	MT20	2.0	4.0		
H	TMWW-t	MT20	4.0	6.0		
I	TMWW-t	MT20	4.0	6.0	1.50	2.75
J	TMVW+p	MT20	4.0	6.0		
K	BMV1+p	MT20	2.0	4.0		
L	BBWW-t	MT20	6.0	7.0	2.75	4.25
M	BBWW+p	MT20	8.0	12.0	5.50	5.25
N	BBWWW+p	MT20	8.0	12.0	5.25	5.25
O	BBWW-t	MT20	7.0	8.0	3.25	4.00
P	BMWW-t	MT20	4.0	4.0	2.00	1.75
Q	BMWW-t	MT20	4.0	4.0		
R	BMV1+p	MT20	2.0	4.0		

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN
THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (I) (INPUT = 0.90)
JSI METAL= 0.44 (E) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2




JOB NAME 314237	TRUSS NAME H2T	QUANTITY 1	PLY 1	JOB DESC. JT-39002	DRWG NO. E-19112582
---------------------------	--------------------------	----------------------	-----------------	------------------------------	-------------------------------

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 14:28:55 2019 Page 1

ID:1djr6DYvLvlXkyExRWgN1yQawr-lBmq3rNwqVE0WDUsSveJzh4IFJO58dOZ2YbFznyKEs6



TOTAL WEIGHT = 2 X 121 = 242 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - F	2x4	DRY	No.2	SPF	
F - I	2x4	DRY	No.2	SPF	
J - L	2x4	DRY	No.2	SPF	
P - B	2x4	DRY	No.2	SPF	
P - N	2x4	DRY	No.2	SPF	
N - M	2x4	DRY	No.2	SPF	
M - L	2x4	DRY	No.2	SPF	
L - K	2x4	DRY	No.2	SPF	
K - J	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.00	1.50
D	TMVW-t	MT20	4.0	4.0	1.50	1.75
E	TMVW+w	MT20	2.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMVW-t	MT20	4.0	4.0	2.00	1.75
H	TMVW+t	MT20	4.0	6.0		
I	TMVW+p	MT20	4.0	4.0	1.75	1.75
J	BMV1+p	MT20	2.0	4.0		
K	BBWW-t	MT20	5.0	6.0	2.00	4.50
L	BBWW+p	MT20	7.0	8.0	3.25	3.75
M	BBWWW+p	MT20	7.0	8.0	3.25	4.50
N	BBWW-h	MT20	6.0	7.0	2.00	4.25
O	BMVW-t	MT20	4.0	4.0	2.00	1.75
P	BMV1+p	MT20	2.0	4.0		

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
J	1230	0	1230	0	1-9	1-8
P	1348	0	1348	0	5-8	2-0

UNFACTORED REACTIONS

JT	1ST CASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
J	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
P	955	619 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, P

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.38 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF I-J, D-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC)	
FR-TO				FR-TO			
A-B	0 / 42	-84.9	-84.9 0.12 (1)	O-C	-103 / 64	0.08 (1)	
B-C	-1075 / 0	-84.9	-84.9 0.39 (1)	C-N	0 / 624	0.14 (1)	
C-D	-1216 / 0	-84.9	-84.9 0.57 (1)	N-D	-1540 / 0	0.44 (1)	
D-E	-1688 / 0	-84.9	-84.9 0.52 (1)	D-M	0 / 1137	0.26 (1)	
E-F	-1695 / 0	-84.9	-84.9 0.46 (1)	M-E	-255 / 0	0.08 (1)	
F-G	-1695 / 0	-84.9	-84.9 0.46 (1)	G-M	0 / 895	0.20 (1)	
G-H	-928 / 0	-84.9	-84.9 0.37 (1)	L-G	-1042 / 0	0.33 (1)	
H-I	-280 / 0	-84.9	-84.9 0.13 (1)	L-H	0 / 1533	0.34 (1)	
J-I	-1215 / 0	0.0	0.0 0.25 (1)	K-H	-1312 / 0	0.96 (1)	
P-B	-1320 / 0	0.0	0.0 0.15 (1)	K-I	0 / 1122	0.25 (1)	
				B-O	0 / 794	0.18 (1)	
P-O	0 / 0	-18.5	-18.5 0.20 (4)				
O-N	0 / 756	-18.5	-18.5 0.27 (4)				
N-M	0 / 1685	-18.5	-18.5 0.28 (1)				
M-L	0 / 954	-18.5	-18.5 0.31 (4)				
L-K	0 / 365	-18.5	-18.5 0.07 (1)				
K-J	0 / 0	-18.5	-18.5 0.01 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.09")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.21")

CSI: TC=0.57/1.00 (C-D:1), BC=0.31/1.00 (L-M:4), WS=0.96/1.00 (H-K:1), SSI=0.26/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.89 (H) (INPUT = 0.90)
JSI METAL= 0.48 (B) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
314237	H3T		1	JT-39002	E-19112583

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 14:28:57 2019 Page 1
ID:1dJR6DYvLvlIXkyExRWgN1yQawr-EZuaUWQAM7UkmXeFZKgn269gB73scbsrWs4M1gyKEs4



TOTAL WEIGHT = 2 X 133 = 267 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	2100F 1.8E	SPF	
C - F	2x4	DRY	No.2	SPF	
F - I	2x4	DRY	No.2	SPF	
J - I	2x4	DRY	No.2	SPF	
P - B	2x4	DRY	No.2	SPF	
P - N	2x4	DRY	No.2	SPF	
N - M	2x4	DRY	No.2	SPF	
M - L	2x4	DRY	No.2	SPF	
L - K	2x4	DRY	No.2	SPF	
K - J	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.50	2.00
C	TTWW+m	MT20	4.0	6.0	Edge	1.00
D	TMVW-t	MT20	4.0	4.0	1.50	2.00
E	TMVW+w	MT20	2.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMVW-t	MT20	4.0	4.0		
H	TMVW-t	MT20	4.0	6.0		
I	TMVW-t	MT20	4.0	4.0	1.50	1.75
J	BMV1+p	MT20	2.0	4.0		
K	BBWW-I	MT20	5.0	6.0	2.00	4.50
L	BBWW+p	MT20	7.0	8.0	Edge	4.25
M	BBWWW+p	MT20	7.0	8.0	3.00	4.25
N	BBWW-h	MT20	6.0	7.0	2.25	4.50
O	BMVW-t	MT20	4.0	4.0	2.00	1.75
P	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	UP		
J	1230	0	1230	0	1-9	1-8
P	1348	0	1348	0	5-8	2-0

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
P	955	619 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, P

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.17 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF I-J, D-N, H-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 42	-84.9 -84.9	0.08 (1)	10.00	O-C	-51 / 82	0.06 (1)
B-C	-1050 / 0	-84.9 -84.9	0.41 (1)	6.25	C-N	0 / 417	0.09 (1)
C-D	-985 / 0	-84.9 -84.9	0.33 (1)	5.83	N-D	-1246 / 0	0.50 (1)
D-E	-1294 / 0	-84.9 -84.9	0.30 (1)	5.28	D-M	0 / 936	0.21 (1)
E-F	-1300 / 0	-84.9 -84.9	0.41 (1)	5.17	M-E	-339 / 0	0.19 (1)
F-G	-1300 / 0	-84.9 -84.9	0.41 (1)	5.17	M-G	0 / 766	0.17 (1)
G-H	-708 / 0	-84.9 -84.9	0.35 (1)	6.25	L-G	-1037 / 0	0.58 (1)
H-I	-231 / 0	-84.9 -84.9	0.13 (1)	6.25	L-H	0 / 1418	0.32 (1)
I-J	-1215 / 0	0.0 0.0	0.35 (1)	5.81	K-H	-1267 / 0	0.51 (1)
P-B	-1303 / 0	0.0 0.0	0.15 (1)	7.08	K-I	0 / 1111	0.25 (1)
					B-O	0 / 762	0.17 (1)
P-O	0 / 0	-18.5 -18.5	0.18 (4)	10.00			
O-N	0 / 740	-18.5 -18.5	0.25 (4)	10.00			
N-M	0 / 1369	-18.5 -18.5	0.23 (1)	10.00			
M-L	0 / 727	-18.5 -18.5	0.29 (4)	10.00			
L-K	0 / 303	-18.5 -18.5	0.06 (1)	10.00			
K-J	0 / 0	-18.5 -18.5	0.01 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 23.3 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.79")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.08")
ALLOWABLE DEFL.(TL) = $L/360$ (0.78")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.20")

CSI: TC=0.41/1.00 (E-G:1), BC=0.29/1.00 (L-M:4), WB=0.58/1.00 (G-L:1), SSI=0.22/1.00 (E-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1657
	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (I) (INPUT = 0.90)
JSI METAL= 0.49 (B) (INPUT = 1.00)




JOB NAME 314237	TRUSS NAME H4T	QUANTITY 1	PLY 1	JOB DESC. JT-39002	DRWG NO. E-19112584
---------------------------	--------------------------	----------------------	-----------------	------------------------------	-------------------------------

Alpa Roof Truss, Maple

Version 8.300 S Aug 8 2019 MiTek Industries, Inc. Mon Nov 11 14:28:59 2018 Page 1

ID:1dJR6DYvLvlXkyExRWgN1yQawr-Ay0KvCQQuKkS?rodhlfjF8XE7KwL4P38zAZT6YyKEs2



Scale = 1:82.0

TOTAL WEIGHT = 2 X 150 = 301 lb

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				DESIGN CRITERIA			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG	SPECIFIED LOADS:	TOP CH. LL	DL
A - D	2x4	DRY	No.2	SPF	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
D - G	2x4	DRY	No.2	SPF	JT	1230	0	1230	0	1-10	1-8
G - J	2x4	DRY	No.2	SPF	K	1348	0	1348	0	5-8	1-8
K - J	2x4	DRY	No.2	SPF	Q	1348	0	1348	0	5-8	1-8
Q - B	2x4	DRY	No.2	SPF	UNFACTORED REACTIONS						
Q - O	2x4	DRY	No.2	SPF	1ST LCASE MAX/MIN. COMPONENT REACTIONS						
O - N	2x4	DRY	No.2	SPF	JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
N - M	2x4	DRY	No.2	SPF	K	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0
M - L	2x4	DRY	No.2	SPF	Q	955	619 / 0	0 / 0	0 / 0	0 / 0	336 / 0
L - K	2x4	DRY	No.2	SPF	BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, Q						
ALL WEBS	2x3	DRY	No.2	SPF	BRACING						
EXCEPT					TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.63 FT.						
					MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.						
					ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.						
					1 LATERAL BRACE(S) AT 1/2 LENGTH OF J-K, E-O, I-L.						
					END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW						
					LOADING						
					TOTAL LOAD CASES: (4)						
					CHORDS						
					MEMB. MAX. FACTORED FORCE (LBS)						
					FR-TO						
					A-B						
					B-C						
					C-D						
					D-E						
					E-F						
					F-G						
					G-H						
					H-I						
					I-J						
					J-K						
					Q-B						
					Q-P						
					P-O						
					O-N						
					N-M						
					M-L						
					L-K						

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	2.0	4.0		
C TMWW-t	MT20	4.0	4.0	1.75	1.25
D TTWW+m	MT20	4.0	6.0	Edge	1.00
E TMWW-t	MT20	4.0	4.0	1.50	2.00
F TMW+w	MT20	2.0	4.0		
G TS-t	MT20	3.0	6.0		
H TMWW-t	MT20	4.0	4.0		
I TMWW-t	MT20	4.0	6.0		
J TMVW-t	MT20	4.0	4.0	1.50	1.75
K BMV1+p	MT20	2.0	4.0		
L BBWW-I	MT20	5.0	6.0	2.00	4.50
M BBWW+p	MT20	6.0	7.0	2.75	3.75
N BBWWW+p	MT20	7.0	8.0	3.25	4.25
O BBWW-h	MT20	6.0	7.0	Edge	2.50
P BMWW-I	MT20	4.0	4.0		
Q BMWW-t	MT20	4.0	4.0	2.00	1.75

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2018
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.07")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.20")

CSI: TC=0.50/1.00 (J-K:1), BC=0.29/1.00 (O-P:4), WS=0.98/1.00 (H-M:1), SSI=0.21/1.00 (F-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.89 (Q) (INPUT = 0.90)
JSI METAL= 0.48 (C) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
314237	H5T		1	JT-39002	E-19112585

Alpa Roof Truss, Maple

Version 6.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 14:29:00 2019 Page 1
ID:1dJR6DYvLvlIXkyExRWgN1yQawr-e8aj6YR2f2sJd?NpFSEUgln7_K3zpxkICqj0e?yKEs1



Scale = 1:70.6

TOTAL WEIGHT = 2 X 184 = 368 lb [M]

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - I	2x4	DRY	No.2	SPF	
J - I	2x4	DRY	No.2	SPF	
P - B	2x4	DRY	No.2	SPF	
P - N	2x4	DRY	No.2	SPF	
N - M	2x4	DRY	No.2	SPF	
M - L	2x4	DRY	No.2	SPF	
L - K	2x4	DRY	No.2	SPF	
K - J	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x4	DRY	No.2	SPF	
C - O	2x3	DRY	No.2	SPF	
E - M	2x3	DRY	No.2	SPF	
M - F	2x3	DRY	No.2	SPF	
L - G	2x3	DRY	No.2	SPF	
L - H	2x3	DRY	No.2	SPF	
P - C	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	2.0	4.0		
C TMVW+I	MT20	4.0	4.0	1.75	1.25
D TTVW+m	MT20	5.0	6.0	2.00	1.25
E TMVW-t	MT20	4.0	4.0	1.50	2.00
F TMVW-t	MT20	4.0	4.0		
G TMVW+w	MT20	2.0	4.0		
H TMVW-t	MT20	4.0	4.0		
I TMVW-t	MT20	4.0	4.0	1.50	1.75
J BMV1+p	MT20	2.0	4.0		
K BBVW-I	MT20	4.0	9.0	2.00	7.50
L BBVW+p	MT20	6.0	9.0	3.25	4.25
M BBVW+p	MT20	6.0	9.0	3.25	3.75
N BBVW-m	MT20	5.0	6.0	1.75	1.75
O BMVW-t	MT20	4.0	4.0		
P BMVW-t	MT20	4.0	4.0	2.00	1.75

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT	REQRD
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
J	1230	0	1230	0	0	1-9	1-8
P	1348	0	1348	0	0	5-8	1-8

UNFACTORED REACTIONS

JT	1ST CASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	873	554 / 0	0 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
P	955	619 / 0	0 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, P

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.91 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF I-J, E-N, F-L, G-L, H-K, C-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED				
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 (LC)	MAX. UNBRACED LENGTH	MEMB.	FORCE (LBS)	MAX. CSI (LC)		
FR-TO		FROM	TO		FR-TO				
A-B	0 / 42	-84.9	-84.9	0.12 (1)	10.00	C-O	-142 / 0	0.16 (1)	
B-C	0 / 31	-84.9	-84.9	0.27 (1)	10.00	O-D	0 / 278	0.05 (4)	
C-D	-981 / 0	-84.9	-84.9	0.30 (1)	5.91	D-N	0 / 136	0.02 (1)	
D-E	-711 / 0	-84.9	-84.9	0.11 (1)	6.25	N-E	-828 / 0	0.47 (1)	
E-F	-884 / 0	-84.9	-84.9	0.32 (1)	6.07	E-M	0 / 742	0.17 (1)	
F-G	-485 / 0	-84.9	-84.9	0.32 (1)	6.25	M-F	0 / 97	0.03 (4)	
G-H	-479 / 0	-84.9	-84.9	0.31 (1)	6.25	F-L	-654 / 0	0.38 (1)	
H-I	-173 / 0	-84.9	-84.9	0.11 (1)	6.25	L-G	-499 / 0	0.24 (1)	
I-J	-1215 / 0	0.0	0.0	0.69 (1)	5.81	L-H	0 / 1293	0.29 (1)	
P-B	-258 / 0	0.0	0.0	0.03 (1)	7.81	K-H	-1220 / 0	0.70 (1)	
						K-I	0 / 1111	0.18 (1)	
						P-C	-1272 / 0	0.45 (1)	
P-O	0 / 757	-18.5	-18.5	0.39 (4)	10.00				
O-N	0 / 673	-18.5	-18.5	0.39 (4)	10.00				
N-M	0 / 988	-18.5	-18.5	0.17 (1)	10.00				
M-L	0 / 883	-18.5	-18.5	0.31 (4)	10.00				
L-K	0 / 221	-18.5	-18.5	0.05 (1)	10.00				
K-J	0 / 0	-18.5	-18.5	0.01 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 088-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.20")

CSI: TC=0.69/1.00 (I-J:1), BC=0.39/1.00 (N-O:4), WS=0.70/1.00 (H-K:1), SSI=0.21/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	354	1687
	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.89 (H) (INPUT = 0.90)
JSI METAL= 0.48 (C) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
314233	J01T		1	TRUSS DESC.	E-19112509

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Fri Nov 8 12:09:33 2019 Page 1
ID: VRLqmcDifZCj2mk6F92VyQuye-PedLg6Kg34EyrhyaL6P1sHTzGSwDvwrmGAw174yLGAm



Scale = 1:33.7

TOTAL WEIGHT = 7 X 30 = 209 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
I - B	2x4	DRY	No.2	SPF
A - E	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-1	MT20	3.0	4.0	1.50	1.00
C	TMVW-1	MT20	3.0	4.0	1.50	1.50
D	TMVW-1	MT20	3.0	4.0	1.50	1.50
E	TMV+p	MT20	2.0	4.0		
F	BMVW-1	MT20	3.0	4.0		
G	BBVW-1	MT20	5.0	6.0	3.00	3.00
H	BBVW-1	MT20	4.0	6.0	2.00	4.50
I	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQD
	VERT	HORZ	DOWN	UP
JT	434	0	434	0
I	290	0	290	0
F	290	0	290	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
I	305	208 / 0	0 / 0	0 / 0	0 / 0	97 / 0	0 / 0
F	206	129 / 0	0 / 0	0 / 0	0 / 0	77 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) !

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
I-B	-415 / 0	0.0	0.0 0.04 (1)	B-H	0 / 173	0.04 (1)	
A-B	0 / 32	-84.9	-84.9 0.11 (1)	H-C	-188 / 0	0.03 (1)	
B-C	-204 / 0	-84.9	-84.9 0.11 (1)	C-G	0 / 81	0.02 (1)	
C-D	-264 / 0	-84.9	-84.9 0.05 (1)	G-D	0 / 172	0.04 (1)	
D-E	-11 / 0	-84.9	-84.9 0.05 (1)	D-F	-308 / 0	0.05 (1)	
F-E	-56 / 0	0.0	0.0 0.01 (1)				
I-H	0 / 0	-18.5	-18.5 0.02 (4)				
H-G	0 / 204	-18.5	-18.5 0.05 (1)				
G-F	0 / 215	-18.5	-18.5 0.05 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.11/1.00 (A-B:1), BC=0.05/1.00 (F-G:1), WB=0.06/1.00 (D-F:1), SSI=0.08/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)	
MT20	618	354	1687 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.56 (B) (INPUT = 0.50)
JSI METAL= 0.12 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
310385	H2		1		JT-39002	E-19072227

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MiTek Industries, Inc. Wed Jul 10 10:24:21 2019 Page 1

ID:MF8IriaTok7DlbpT4B71Xys4PG-8qg8xPHXxCPnIod8hKid9vCSL7JH2LHmbuOBMyzW1e

Scale = 1:42.5



TOTAL WEIGHT = 4 X 107 = 429 lb

LUMBER				N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF			
C - E	2x4	DRY	No.2	SPF			
E - G	2x4	DRY	No.2	SPF			
H - G	2x4	DRY	No.2	SPF			
M - B	2x4	DRY	No.2	SPF			
M - J	2x4	DRY	No.2	SPF			
J - H	2x4	DRY	No.2	SPF			
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF			
DRY: SEASONED LUMBER.							

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	6.0	2.60 2.00
C	TTWW+m	MT20	5.0	6.0	2.00 1.50
D	TMVW-t	MT20	4.0	4.0	
E	TS-t	MT20	3.0	6.0	
F	TMVW+w	MT20	2.0	4.0	
G	TMVW-t	MT20	4.0	6.0	1.75 3.00
H	BMV1+p	MT20	2.0	4.0	
I	BMVWW-t	MT20	5.0	8.0	
J	BS-t	MT20	3.0	6.0	
K	BMVW-t	MT20	4.0	4.0	
L	BMVW-t	MT20	4.0	4.0	2.00 1.75
M	BMV1+p	MT20	2.0	4.0	

NOTES: (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
H	1230	0	1230	0	0	1-9	1-8		
M	1348	0	1348	0	0	5-8	2-0		

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
H	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0		
M	955	619 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.14 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LC1 (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-B	0 / 42	-84.9 -84.9	0.12 (1)	10.00	L-C	-120 / 41	0.09 (1)
B-C	-1069 / 0	-84.9 -84.9	0.39 (1)	5.60	C-K	0 / 642	0.14 (1)
C-D	-1203 / 0	-84.9 -84.9	0.51 (1)	5.14	K-D	-345 / 0	0.25 (1)
D-E	-977 / 0	-84.9 -84.9	0.52 (1)	5.53	D-I	-323 / 0	0.18 (1)
E-F	-977 / 0	-84.9 -84.9	0.52 (1)	5.53	I-F	-596 / 0	0.44 (1)
F-G	-977 / 0	-84.9 -84.9	0.52 (1)	5.53	I-G	0 / 1368	0.31 (1)
H-G	-1181 / 0	0.0 0.0	0.24 (1)	5.87	B-L	0 / 790	0.18 (1)
M-B	-1315 / 0	0.0 0.0	0.15 (1)	7.06			
M-L	0 / 0	-18.5 -18.5	0.13 (4)	10.00			
L-K	0 / 752	-18.5 -18.5	0.20 (4)	10.00			
K-J	0 / 1203	-18.5 -18.5	0.29 (1)	10.00			
J-I	0 / 1203	-18.5 -18.5	0.29 (1)	10.00			
I-H	0 / 0	-18.5 -18.5	0.18 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.09")

CSI: TC=0.52/1.00 (F-G:1), BC=0.29/1.00 (I-K:1), WB=0.44/1.00 (F-I:1), SS=0.26/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.80 (L) (INPUT = 0.90)
JSI METAL= 0.48 (B) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
310385	H3	1		JT-39002	E-19072228

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MiTek Industries, Inc. Wed Jul 10 10:24:22 2019 Page 1
ID:MF8iiriaTok7DlbpT4B71Xys4PG-TKO2MHQvIFKGPSNplOrxAMRJIUJ0WZQ?FeyjoyzW1d
Scale = 1:48.7



TOTAL WEIGHT = 4 X 112 = 450 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	2100F 1.8E	SPF
C - E	2x4	DRY	2100F 1.8E	SPF
E - F	2x4	DRY	2100F 1.8E	SPF
G - F	2x4	DRY	No.2	SPF
J - B	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				
C - H	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMVW+p	MT20	4.0	6.0	2.50 2.00
C TTWW+m	MT20	4.0	6.0	Edge 1.00
D TMW+w	MT20	2.0	4.0	
E TS-t	MT20	3.0	6.0	
F TMVW-t	MT20	4.0	4.0	1.50 1.75
G BMV1+p	MT20	2.0	4.0	
H BSWWW-t	MT20	5.0	8.0	3.00 4.00
I BMWW-t	MT20	4.0	4.0	2.00 1.75
J BMV1+p	MT20	2.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
G	1230	0	1230	0
J	1348	0	1348	0

UNFACTORED REACTIONS

	1ST LCASE	MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
J	955	619 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.62 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF F-G, D-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 42	-84.9	-84.9 0.08 (1)	I-C	-9 / 126	0.04 (4)	
B-C	-1060 / 0	-84.9	-84.9 0.41 (1)	C-H	0 / 334	0.05 (1)	
C-D	-999 / 0	-84.9	-84.9 0.82 (1)	H-D	-932 / 0	0.37 (1)	
D-E	-999 / 0	-84.9	-84.9 0.83 (1)	H-F	0 / 1317	0.21 (1)	
E-F	-999 / 0	-84.9	-84.9 0.83 (1)	B-I	0 / 770	0.17 (1)	
G-F	-1147 / 0	0.0	0.0 0.33 (1)				
J-B	-1312 / 0	0.0	0.0 0.15 (1)				
J-I	0 / 0	-18.5	-18.5 0.32 (4)				
I-H	0 / 748	-18.5	-18.5 0.39 (4)				
H-G	0 / 0	-18.5	-18.5 0.43 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.79")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.03")
ALLOWABLE DEFL.(TL) = $L/360$ (0.79")
CALCULATED VERT. DEFL.(TL) = $L/897$ (0.32")

CSI: TC=0.83/1.00 (D-F:1), BC=0.43/1.00 (G-H:4), WB=0.37/1.00 (D-H:1), SSI=0.37/1.00 (D-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (I) (INPUT = 0.90)
JSI METAL= 0.49 (B) (INPUT = 1.00)





TOTAL WEIGHT = 4 X 123 = 491 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	1650F 1.5E	SPF
F - G	2x4	DRY	1650F 1.5E	SPF
H - G	2x4	DRY	No.2	SPF
K - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
D - I	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	2.0	4.0	
C	TMWW-l	MT20	4.0	4.0	1.75 1.25
D	TTWW+m	MT20	4.0	6.0	Edge 1.00
E	TMW+w	MT20	2.0	4.0	
F	TS-l	MT20	3.0	6.0	
G	TMWW-l	MT20	4.0	4.0	1.75 1.75
H	BMV1+p	MT20	2.0	4.0	
I	BSWWW-l	MT20	5.0	8.0	3.00 4.00
J	BMWW-l	MT20	4.0	4.0	
K	BMWW1-l	MT20	4.0	4.0	2.00 1.75

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT		REQD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	IN-SX	BRG
H	1230	0	1230	0	0	1-9	1-8	1-8	1-8
K	1348	0	1348	0	0	5-8	1-8	1-8	1-8

UNFACTORED REACTIONS		1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
H	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0		
K	965	619 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.35 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, E-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED		FACTORED		VERT. LOAD LC1		MAX		W E B S		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT.	PLF	CSI (LC)	UNBRAC	MEMB.	FORCE (LBS)	MAX	CSI (LC)	MEMB.	FORCE (LBS)	MAX	CSI (LC)
FR-TO						FR-TO				FR-TO			
A-B	0 / 42	-84.9	-84.9	0.12 (1)	10.00	C-J	-80 / 21		0.05 (1)				
B-C	0 / 26	-84.9	-84.9	0.19 (1)	10.00	J-D	0 / 228		0.06 (4)				
C-D	-1037 / 0	-84.9	-84.9	0.21 (1)	5.91	D-I	0 / 147		0.02 (1)				
D-E	-813 / 0	-84.9	-84.9	0.88 (1)	5.35	I-E	-862 / 0		0.49 (1)				
E-F	-813 / 0	-84.9	-84.9	0.88 (1)	5.35	I-G	0 / 1203		0.19 (1)				
F-G	-813 / 0	-84.9	-84.9	0.88 (1)	5.35	K-C	-1296 / 0		0.93 (1)				
H-G	-1153 / 0	0.0	0.0	0.47 (1)	5.93								
K-B	-238 / 0	0.0	0.0	0.03 (1)	7.81								

K-J	0 / 748	-18.5	-18.5	0.39 (4)	10.00
J-I	0 / 715	-18.5	-18.5	0.39 (4)	10.00
I-H	0 / 0	-18.5	-18.5	0.37 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.24")

CSI: TC=0.88/1.00 (E-G:1), BC=0.39/1.00 (I-J:4), WB=0.93/1.00 (C-K:1), SS=0.34/1.00 (E-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
618	354	1667	788


PLATE PLACEMENT TOL. = 0.250 Inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (K) (INPUT = 0.90)
JSI METAL= 0.48 (C) (INPUT = 1.00)

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MITek Industries, Inc. Thu Jul 11 09:24:40 2019 Page 1
 ID:MF8ilriaTok7DlbpT4B71Xys4PG-a9ag2dhkX4XM9pdmHff3j?WIOB_JQTkVz5JJUyZBpb
 2x4 II 4x4 = Scale = 1:60.1





DRY: SEASONED LUMBER.

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2




JSI GRIP= 0.28 (B) (INPUT = 0.90)
JSI METAL= 0.22 (B) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
310395	H6		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MITek Industries, Inc. Thu Jul 11 11:22:22 2019 Page 1
ID:kx9I86OLIWqKxByZIGBJHpySKNA-pmIPCN9UQuGLO5V1_oL7xE77bwCQ3NXzto??MDyzA5F
Scale = 1:67.2



TOTAL WEIGHT = 14 X 145 = 2031 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
H - G	2x4	DRY	No.2	SPF	
L - B	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x4	DRY	No.2	SPF	
C - K	2x3	DRY	No.2	SPF	
L - C	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)							
JT	TYPE	PLATES	W	LEN	Y	X	
B	TMV+p	MT20	2.0	4.0			
C	TMVW-t	MT20	4.0	4.0	1.75	1.25	
D	TS-t	MT20	3.0	6.0			
E	TTWw+m	MT20	5.0	6.0	2.00	1.25	
F	TMW+w	MT20	2.0	4.0			
G	TMVW-t	MT20	4.0	4.0	1.75	1.75	
H	BMV1+p	MT20	2.0	4.0			
I	BMVWW-t	MT20	5.0	8.0			
J	BS-t	MT20	3.0	6.0			
K	BMVW-t	MT20	4.0	4.0			
L	BMVW1-t	MT20	4.0	4.0	2.00	1.75	

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BUILDING DESIGNER								
<u>BEARINGS</u>								
FACTORED			MAXIMUM FACTORED			INPUT	REQRD	
GROSS REACTION			GROSS REACTION			BRG	BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
H	1303	0	1303	0	0	1-9	1-8	
L	1378	0	1378	0	0	5-8	1-8	

UNFACTORED REACTIONS							
	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	932	554 / 0	0 / 0	0 / 0	0 / 0	377 / 0	0 / 0
L	978	619 / 0	0 / 0	0 / 0	0 / 0	359 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, L

BRACING
FOR SECTION E-G, MAX. PURLIN SPACING = 2.00 FT.
FOR OTHER SECTIONS, TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.98 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

- 1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, C-K, F-I, G-I, C-L.
- 2 LATERAL BRACE(S) AT 1/3 LENGTH OF E-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING		CHORDS		WEBS	
TOTAL LOAD CASES: (4)		MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO	FROM TO	FR-TO	FROM TO	FR-TO	FROM TO
A-B	0 / 42	A-B	-84.9	C-K	-213 / 0
B-C	0 / 37	B-C	-84.9	K-E	0 / 355
C-D	-958 / 0	C-D	-84.9	E-I	-117 / 0
D-E	-958 / 0	D-E	-84.9	I-F	-785 / 0
E-F	-595 / 0	E-F	-92.4	I-G	0 / 1166
F-G	-596 / 0	F-G	-92.4	L-C	-1286 / 0
H-G	-1247 / 0	H-G	0.0		
L-B	-279 / 0	L-B	0.0		
L-K	0 / 783	L-K	-18.5		
K-J	0 / 654	K-J	-18.5		
J-I	0 / 654	J-I	-18.5		
I-H	0 / 0	I-H	-18.5		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON PIGGYBACK TRUSS WITH SLOPES OF 6.00/12 AND -6.00/12 AND RESPECTIVE WALL HEIGHTS OF 0-0 AND 0-0 AND AN ADDITIONAL DEAD LOAD OF 3.0 P.S.F.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/889 (0.32")

CSI: TC=0.98/1.00 (G-H:1), BC=0.47/1.00 (K-L:4), WB=0.62/1.00 (F-I:1), SSI=0.31/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (L) (INPUT = 0.90)
JSI METAL= 0.49 (C) (INPUT = 1.00)



May 27, 2019

Re: Expiration Date for Technical Bulletins Extended to 12/31/2019

Please be advised that the expiration date of the Technical Bulletins listed below has been extended until December 31, 2019.

T-SPECCP17	T-SPECH17	T-SPECDSHGUS17R
T-SPECHGUS17-R	T-SPECHHUS17-R	T-SPECHUS17
T-SPECLF17	T-SPECLT17	T-SPECLU17
T-SPECCLUL17	T-SPECLUS17	T-SPECSUR17
T-SPECTBE17	T-SPECTC17	T-SPECTHGB17
T-SPECTHGBHV17	T-SPECTHGQ17	T-SPECTHGW17
T-SPECLSULSSU17	T-SPECHTHGQ17	T-SPECSTHGQ17

Should you have any questions or concerns regarding the above, please contact me at your convenience.

Sincerely,



Brent Bunting, P.Eng.
Simpson Strong-Tie Canada, Ltd.



LUS – Double Shear Joist Hangers



All LUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections.

Material: 18 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners.
- Nails: 16d = 0.162" dia. x 3½" long common wire, 10d = 0.148" x 3" long common wire.
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads.
- Not designed for welded or nailer applications.

Options:

- These hangers cannot be modified




Typical LUS Installation




Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _s ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _p =1.15)	Normal (K _p =1.00)	Uplift (K _p =1.15)	Normal (K _p =1.00)
LUS24	18	1⅞	3⅞	1¾	1⅝	(4) 10d	(2) 10d	710	1630	645	1155
LUS24-2	18	3⅞	3⅞	2	1⅝	(4) 16d	(2) 16d	835	2020	590	1435
LUS26	18	1⅞	4¾	1¾	3⅞	(4) 10d	(4) 10d	1420	2170	1290	1630
LUS26-2	18	3⅞	4¾	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920
LUS26-3	18	4⅞	4¾	2	3¼	(4) 16d	(4) 16d	1720	2595	1545	2340
LUS28	18	1⅞	6⅞	1¾	3¾	(6) 10d	(6) 10d	1420	2520	1290	1790
LUS28-2	18	3⅞	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575
LUS28-3	18	4⅞	6¼	2	3¼	(6) 16d	(4) 16d	1720	3325	1545	2375
LUS210	18	1⅞	7⅝	1¾	3⅞	(8) 10d	(4) 10d	1420	2785	1290	2210
LUS210-2	18	3⅞	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195
LUS210-3	18	4⅞	8⅝	2	5¼	(8) 16d	(6) 16d	2580	3345	2320	2375

1. d_s is the distance from the seat of the hanger to the highest joist nail.



Dome Double Shear Nailing prevents tabs breaking off (available on some models).

U.S. Patent 5,603,580



Double Shear Nailing Top View.



LIMIT STATES DESIGN


This technical bulletin is effective until June 30, 2019, and reflects information available as of March 1, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2017 Simpson Strong-Tie Company Inc.

T-SPEC/LUS17 3/17 exp. 6/19

(800) 999-5099
strongtie.com

HHUS – Double Shear Joist Hangers



All HHUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: 14 gauge

Finish: G90 galvanized

Design:



- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:

- Use all specified fasteners
- Nails: 16d = 0.162" dia. x 3 1/2" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications




Options:

- See current catalogue for options



Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _b ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K ₀ =1.15)	Normal (K ₀ =1.00)	Uplift (K ₀ =1.15)	Normal (K ₀ =1.00)
HHUS26-2	14	3 9/16	5 13/16	3	3 15/16	(14) 16d	(6) 16d	2850	7335	2065	5205
HHUS28-2	14	3 9/16	7 7/32	3	6 5/32	(22) 16d	(8) 16d	3765	8940	2675	6345
HHUS210-2	14	3 9/16	9 9/32	3	8	(30) 16d	(10) 16d	4745	9660	4310	7000
HHUS210-3	14	4 11/16	9	3	7 15/16	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS210-4	14	6 1/8	8 29/32	3	7 27/32	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS46	14	3 3/8	5 1/8	3	3 15/16	(14) 16d	(6) 16d	2540	7335	2065	5205
HHUS48	14	3 3/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3765	8945	2267	6345
HHUS410	14	3 3/8	9	3	8	(30) 16d	(10) 16d	4745	9855	4310	7000
HHUS5.50/10	14	5 1/2	9	3	8	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS7.25/10	14	7 1/4	9	3 3/8	7 29/32	(30) 16d	(10) 16d	4745	10770	4310	7650

1. d_b is the distance from the seat of the hanger to the highest joist nail.




LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2019, and reflects information available as of March 1, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2017 Simpson Strong-Tie Company Inc.

T-SPECHHUS17 3/17 exp. 6/19

(800) 999-5099
strongtie.com



Wood Truss Installation

**A Guide to proper handling, erecting and bracing
metal plate connected wood trusses**

Table of Content

Warning.....	4
1 Unloading & Lifting.....	5
2 Job Site Handling.....	5
3 Hoisting.....	6
4 Beginning the Erection Process.....	7
5 Erection Tolerance.....	8
6 Bracing.....	8
7 Bracing Requirements for 3 Planes of Roof.....	9
8 Stacking Materials.....	10
Caution Notes.....	11

Warning



General

Familiarity with the Construction Design Documents, the Truss Design Drawings, and Truss Placement Plans (if required by the Construction Design Documents) is required to properly erect, brace, and connect the trusses to the building system.

All of the care and quality involved in the design and manufacture of wood trusses can be jeopardized if the trusses are not properly handled, erected, and braced.

The consequences of improper handling, erecting, and bracing may be a collapse of the structure, which at best is a substantial loss of time and materials, and at worst is a loss of life. The majority of truss accidents occur during truss installation and not as a result of improper design or manufacture.

Prior to truss erection, the builder/erector shall meet with the erection crew for a safety and planning meeting, making sure each crew member understands his or her roles and responsibilities during the erection process.

Temporary Erection Bracing

Trusses are not marked in any way to identify the frequency, or location of temporary erection bracing.

All temporary bracing shall comply with the latest edition of *Commentary and Recommendations for Handling, Installing & Bracing Metal Plate Connected Wood Trusses* (HIB), published by the Truss Plate Institute, and/or as specified in the Construction Design Documents prepared by the building designer.

Permanent Truss Bracing

Permanent bracing for the roof or floor trusses is the responsibility of the building designer and should be shown on the Construction Design Documents. Permanent bracing locations for individual compression members of a wood truss are shown on the Truss Design Drawings, and shall be installed by the building or erection contractor. This bracing is needed for the proper performance of individual trusses within the roof or floor system. The design and connection of the bracing to the truss and then to the overall building system is the responsibility of the building designer, and is in addition to the permanent bracing plan, which is also specified by the building designer.

Special Design Requirements

Special design requirements, such as wind bracing, portal bracing, seismic bracing, diaphragms, shear walls, or other load transfer elements and their connections to wood trusses must be considered separately by the building designer, who shall determine size, location, and method of connections for all bracing as needed to resist these forces.

Unloading & Lifting

Never handle trusses flat



Beginning with the unloading process, and throughout all phases of construction, care must be taken to avoid lateral bending of trusses, which can cause damage to the lumber and metal connector plates at the joints.



Avoid lateral bending


- Use special care in windy weather.
- If using a crane within 10 feet of an electric line, contact the local power company.
- If using a crane within 5 miles of an airport, contact the airport 30 days prior to erection to learn about any safety regulations that must be followed.

Job Site Handling




All trusses should be picked up at the top chords in a vertical position only

Proper banding and smooth ground allow for unloading of trusses without damage. This should be done as close to the building site as possible to minimize handling. Do not break banding until installation begins. Hand erection of trusses is allowed, provided excessive lateral bending is prevented.




Do not store unbraced bundles upright

If trusses are stored vertically they shall be braced in a manner that will prevent tipping or topping. Generally cutting of the banding is done just prior to installation.



Do not store on uneven ground

If trusses are stored horizontally, blocking should be used on eight to ten foot centers, or as required, to minimize lateral bending and moisture gain.



Care should be exercised when removing banding to avoid damaging trusses.


During long term storage, trusses shall be protected from the environment in a manner that provides for adequate ventilation of the trusses. If tarpaulins or other material is used, the ends shall be left open for ventilation. Plastic is not recommended, since it can trap moisture.

3 Hoisting


All trusses that are erected one at a time shall be held safely in position by the erection equipment until such time as all necessary bracing has been installed and the ends of the trusses are securely fastened to the building.




Avoid lateral bending




$L \leq 30'$




Truss sling is acceptable where these criteria are met.




$30' < L \leq 60'$



Use spreader bar in all other cases. It should be noted that the lines from the ends of the spreader bar "TOE IN"; if these lines should "TOE OUT" the truss may fold in half.



$L > 60'$




For lifting trusses with spans in excess of 60 feet, it is recommended that a strongback/spreader bar be used as illustrated. The strongback/spreader bar should be attached to the top chord and web members at intervals of approximately 10 feet. Further, the strongback/spreader bar should be at or above the mid-height of the truss to prevent overturning. The strongback/spreader bar can be of any material with sufficient strength to safely carry the weight of the truss and sufficient rigidity to adequately resist bending of the truss.

4 Beginning the Erection Process


It is important for the builder or erection contractor to provide substantial bracing for the first truss erected. The two or more trusses making up the rest of the first set are tied to and rely upon the first truss for stability. Likewise, after this first set of trusses is adequately cross-braced, the remaining trusses installed rely upon this first set for stability. Thus, the performance of the truss bracing system depends to a great extent on how well the first group of trusses is braced.

Ground Brace – Exterior

One satisfactory method ties the first unit of trusses off to a series of braces that are attached to a stake driven into the ground and securely anchored. The ground brace itself should be supported as shown below or it is apt to buckle. Additional ground braces in the opposite direction, inside the building, are also recommended.





Note: Locate ground braces for first truss directly in line with all rows of top chord continuous lateral bracing (either temporary or permanent).



Ground Brace – Interior

Another satisfactory method where height of building or ground conditions prohibit bracing from the exterior is to tie the first truss rigidly in place from the interior at the floor level, provided the floor is substantially completed and capable of supporting the ground bracing forces. Securely fasten the first truss to the middle of the building. Brace the bracing similar to exterior ground bracing shown at left. Set trusses from the middle toward the end of the building. Properly cross-brace the first set of trusses before removing floor braces and setting remaining trusses.




Inadequate size of bracing material or inadequate fastening is a major cause of erection dominoing.


5 Erection Tolerance

Complying with erection tolerances is critical to achieving an acceptable roof or floor line, and to accomplishing effective bracing. Setting trusses within tolerance the first time will prevent the need for the hazardous practice of respacing or adjusting trusses when roof sheathing or roof purlins are installed. Trusses leaning or bowing can cause nails to miss the top chords when sheathing is applied, and create cumulative stresses on the bracing, which is a frequent cause of dominoing.

When sheathing, make sure nails are driven into the top chord of the trusses.



6 Bracing




Do not install trusses on temporarily connected supports



Do not walk on unbraced trusses



Do not walk on trusses or gable ends lying flat




Nails in withdrawal (parallel to force)

All anchors, hangers, tie-downs, seats, bearing ledgers, etc., that are part of the supporting structure shall be accurately and properly placed and permanently attached before truss installation begins. No trusses shall ever be installed on anchors or ties that have temporary connections to the supporting structure.

Nailing scabs to the end of the building to brace the first truss is not recommended.

All nailing of bracing should be done so that nails are driven perpendicular to the direction of force, as shown at right.




Well nailed (perpendicular to force)

7 Bracing Requirements for 3 Planes of Roof

Temporary erection bracing must be applied to three planes of the roof system to ensure stability: Plane 1) Top Chord (sheathing), Plane 2) Bottom Chord (ceiling plane), and Plane 3) Web Member plane or vertical plane perpendicular to trusses.

1) Top Chord Plane

Most important to the builder or erection contractor is bracing in the plane of the top chord. Truss top chords are susceptible to lateral buckling before they are braced or sheathed.




Exact spacing between trusses should be maintained as bracing is installed to avoid the hazardous practice of removing bracing to adjust spacing. This act of "adjusting spacing" can cause trusses to topple if connections are removed at the wrong time.

3) Web Member Plane

"X" bracing, as shown, is critical in preventing trusses from leaning or dominoing. Repeat as shown to create a succession of rigid units.


X-bracing should be installed on vertical web members wherever possible, at or near lateral bracing. Plywood or OSB may be substituted for X-bracing.



Note: Top chords and some web members are not shown, in order to make drawings more readable.

2) Bottom Chord Plane

In order to hold proper spacing on the bottom chord, temporary bracing is recommended on the top of the bottom chord.




* Long spans, heavy loads or other spacing configurations may require closer spacing between lateral bracing and closer intervals between diagonals. Consult the building designer or HIB and DSB (Recommended Design Specification for Temporary Bracing of Metal-Plate Connected Wood Trusses) for details.

Diagonal or cross-bracing is very important!



Do not use short blocks to brace individual trusses without a specific bracing plan detailing their use





Bracing requirements using the same principles apply to parallel chord trusses

8 Stacking Materials

Do not proceed with building completion until all bracing is securely and properly in place



Never stack materials on unbraced or inadequately braced trusses




Platform must be rigidly braced

Proper distribution of construction materials is a must during construction.

Never stack materials near a peak



Never stack materials on the cantilever of a truss




Always stack materials over two or more trusses.




Single truss

Never overload small groups or single trusses. Position load over as many trusses as possible.



Roofing and mechanical contractors are cautioned to stack materials only along outside supporting members or directly over inside supporting members. Trusses are not designed for dynamic loads (i.e., moving vehicles). Extreme care should be taken when loading and stacking construction materials (rolled roofing, mechanical equipment, etc.) on the roof or floor system.

Never cut any structural member of a truss.



Sleepers for mechanical equipment should be located at panel points (joints) or over main supporting members, and only on trusses that have been designed for such loads.

Caution Notes

Errors in building lines and/or dimensions, or errors by others shall be corrected by the contractor or responsible construction trade subcontractor or supplier **before** erection of trusses begins.


Cutting of nonstructural overhangs is considered a part of normal erection and shall be done by the builder or erection contractor.

Any field modification that involves the cutting, drilling, or relocation of any structural truss member or connector plate shall not be done without the approval of the truss manufacturer or a licensed design professional.

The methods and procedures outlined are intended to ensure that the overall construction techniques employed will put floor and roof trusses **safely** in place in a completed structure. These recommendations for bracing wood trusses originate from the collective experience of leading technical personnel in the wood truss industry, but must, due to the nature of responsibilities involved, be presented only as a **guide** for use by a qualified building designer, builder, or erection contractor. Thus, the Wood Truss Council of America expressly disclaims any responsibility for damages arising from the use, application, or reliance on the recommendations and information contained herein.

[Selected text and figures referenced or reproduced from HIB and DSB by permission of the Truss Plate Institute, Madison, WI.]

THE CANADIAN WOOD TRUSS ASSOCIATION



L'ASSOCIATION CANADIENNE DES FABRICANTS DE FERMES DE BOIS

1400 Blair Place, Suite 210, Ottawa, ON K1J 9B8

Tel.: 613-747-5544 Fax: 613-747-6264



Wood Truss Council of America

One WTCA Center

6300 Enterprise Lane, Madison, WI 53719-1140

Tel.: 608-274-4849

Fax: 608-274-3329

wtca@woodtruss.com


www.woodtruss.com

E19072240
 E19072246-E19072250
 E19072392-E19072393
 E19112586-E19112599

All work shall conform to the Ontario Building Code O. Reg. 332/12 as amended

For conventional framing roof / ceilings framing shall conform to OBC.9.2.3

CITY OF BRAMPTON
 BUILDING DIVISION
 REVIEWED
 DEC 10 2019
 MARY FENETTE



FIRM BCIN 113884
 DESIGNER BCIN 25593

ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 O.B.C. LATEST EDITION. ROOF RAFTERS THAT CROSS OVER TRUSSES TO BE 2X4 SPF #2 @ 24" O.C WITH A VERT. POST TO THE TRUSS UNDERNEATH AT EACH CROSS POINT. VERT. POSTS LONGER THAN 6' TO HAVE LATERAL BRACING SO THAT THE DISTANCE BETWEEN END POINTS & BETWEEN ROWS OF BRACING DOES NOT EXCEED 6'

Milek V. 8.2.0
 CONVENTIONAL FRAMING BY OTHERS



Job Track: 39002
 Layout ID: 313999
 Plan Log: 104423

Builder / Location:
GOLD PARK HOMES / BRAMPTON
 Project: **MCLAUGHLIN AND MAYFIELD**
 Date: 10/23/2019 Designer: AMANDA

Model / Elevation:
SD-09 / C/D

THESE DRAWINGS CONSTITUTE THE PROPERTY OF ALPA ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY ALPA ROOF TRUSSES INC AND WILL BE RETRACTED BY ALPA ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

ALPA-BARRIE

EWP DESIGN INC.

(905) 832-2250

FAX (905) 832-0286

RESPONSIBILITIES AND SPECIFICATIONS

RESPONSIBILITIES

1. EWP DESIGN INC. is responsible for the design of trusses as individual components.
2. It is the responsibility of others to ascertain that the design loads utilized on each drawing meet or exceed the actual dead load imposed by the structure, the live load imposed by the intended use and the snow load imposed by local building code or authorities with jurisdictions.
3. All dimensions are to be verified by the owner, contractor, architect or other authorities with jurisdictions before truss fabrication.
4. EWP DESIGN INC. bears no responsibility for the erection of trusses. Persons erecting trusses are cautioned to seek professional advice regarding the temporary and permanent bracing for the system. Bracing shown on EWP DESIGN INC. drawing is specified for the truss as a component only and forms an integral part of the truss design.
5. It is the truss manufacturer's responsibility to ensure that trusses are manufactured in conformance with specifications of EWP DESIGN INC. as outlined below.

SPECIFICATIONS


1. Trusses designed by EWP DESIGN INC. conform to the relevant section of the Ontario Building Code of Canada (Part 9 or Part 4) or to the Canadian code for farm buildings, whichever applies to the building type, as indicated on the EWP DESIGN INC. drawings, and conform to the design procedures established by the Truss Plate Institute of Canada. Unit stresses used for truss designs are as per the edition of CSA-O86 shown on EWP DESIGN INC. drawings.
2. Lumber is to be the size, species and grade as specified on EWP DESIGN INC. drawings.
3. Moisture content of lumber shall not exceed 19% in service unless specified otherwise.
4. Metal connector plates shall be applied to both faces of truss at each joint and shall be positioned as specified.
5. Top chords of trusses are assumed to be continuously braced laterally by roof sheathing or by purlins at intervals not exceeding 12.5 times the thickness of top chord member.
6. Bottom chords shall be laterally braced at intervals not exceeding 3M (10') o.c., where rigid ceiling is not applied directly to the underside of chords.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF EWP DESIGN INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY THE ALPA LUMBER GROUP, AND WILL BE RETRACTED BY EWP DESIGN INC. IF UTILIZED FOR ANY OTHER PURPOSE.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	G02		1	TRUSS DESC.	JT-39002 E-19112587

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:47 2019 Page 1
ID:MF8iiraTok7DlbpT4B71Xys4PG-HBoMjhPn1IMgix7SWfzBVCABoVNL77JvLu7V2yKEKU



TOTAL WEIGHT = 6 X 8 = 48 lb

LUMBER	CHORDS	SIZE	DRY	LUMBER	DESCR.
N. L. G. A. RULES	A - C	2x4	DRY	No.2	SPF
	B - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
	B	TMB1-H	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
C	99	0	99	0	0	5-8	5-8
B	256	0	256	0	0	4-0	1-8
D	43	0	43	0	0	5-8 (5-6)	1-8

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): C

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS					SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	
C	69	52 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
B	179	126 / 0	0 / 0	0 / 0	0 / 0	53 / 0	0 / 0
D	32	12 / 0	0 / 0	0 / 0	0 / 0	20 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) C, B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 16	-84.9 -84.9	0.12 (5)	E-F	-85 / 3	0.00 (1)	
B-F	-10 / 0	-84.9 -84.9	0.02 (4)				
F-C	0 / 2	-84.9 -84.9	0.08 (1)				
B-E	0 / 0	-18.5 -18.5	0.07 (1)				
E-D	0 / 0	-18.5 -18.5	0.07 (1)				

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 23.3 PSF
	DL	= 6.0 PSF
BOT CH.	LL	= 0.0 PSF
	DL	= 7.4 PSF
TOTAL LOAD		= 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.I. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.12/1.00 (A-B:5), BC=0.07/1.00 (D-E:1), WB=0.00/1.00 (E-F:1), SSI=0.09/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667
	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)



Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:48 2019 Page 1
ID:MF8ilriaTok7DlbpT4B71Xys4PG-IOMlx1QQo0UXJ5af4amCkjlDPCB84QPS8?dh1VyKEKT



TOTAL WEIGHT = 2 X 121 = 242 lb

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - F	2x4	DRY No.2	SPF
F - G	2x4	DRY No.2	SPF
H - B	2x4	DRY No.2	SPF
N - G	2x4	DRY No.2	SPF
N - J	2x6	DRY No.2	SPF
J - H	2x6	DRY No.2	SPF

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP SIDE(41.1)
C - F	12	TOP SIDE(41.1)
F - G	12	TOP
G - H	12	TOP
N - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
N - J	12	SIDE(10.0)
J - H	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	IN-SX	IN-SX
JT	2664	0	0	1-8
H	2053	0	0	1-8

UNFACTORED REACTIONS

	1ST LCASE	MAX/MIN. COMPONENT REACTIONS
	COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
JT	1891	1200 / 0 0 / 0 0 / 0 691 / 0 0 / 0
H	1455	937 / 0 0 / 0 0 / 0 518 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, N

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.70 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO				FR-TO			
A-B	0 / 48	-84.9 -84.9	0.07 (1)	M-C	-555 / 0	0.11 (1)	
B-C	-1448 / 0	-84.9 -84.9	0.05 (1)	B-M	0 / 1104	0.14 (1)	
C-D	-2424 / 0	-84.9 -84.9	0.21 (1)	C-L	0 / 2115	0.26 (1)	
D-E	-3422 / 0	-84.9 -84.9	0.34 (1)	D-K	-1380 / 0	0.28 (1)	
E-O	-2390 / 0	-84.9 -84.9	0.35 (1)	E-K	0 / 1368	0.17 (1)	
O-F	-2390 / 0	-167.1 -167.1	0.35 (1)	K-E	0 / 254	0.04 (4)	
F-G	-2381 / 0	-167.1 -167.1	0.56 (1)	E-I	-1416 / 0	0.70 (1)	
H-G	-2585 / 0	0.0 0.0	0.60 (1)	I-F	-838 / 0	0.17 (1)	
N-B	-2071 / 0	0.0 0.0	0.14 (1)	I-G	0 / 3185	0.39 (1)	
N-M	0 / 0	-18.5 -18.5	0.03 (1)				
M-L	0 / 848	-18.5 -18.5	0.09 (1)				
L-K	0 / 2425	-18.5 -18.5	0.23 (1)				
K-P	0 / 3422	-18.5 -18.5	0.35 (1)				
P-J	0 / 3422	-36.4 -36.4	0.35 (1)				
J-I	0 / 3422	-36.4 -36.4	0.35 (1)				
I-H	0 / 0	-36.4 -36.4	0.08 (4)				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	FACE	DIR.	TYPE	HEEL	CONN.
P	13-5-9	-1103	-1103	—	FRONT	VERT	—	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:			
TOP CH.	LL	=	23.3 PSF
	DL	=	6.0 PSF
BOT CH.	LL	=	0.0 PSF
	DL	=	7.4 PSF
TOTAL LOAD		=	36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 2-2-12
RIGHT SETBACK = 0-0
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 10-5-0 OF SPAN MEASURED FROM THE RIGHT.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")

CSI: TC=0.80/1.00 (G-H:1), BC=0.35/1.00 (I-K:1), WB=0.70/1.00 (E-I:1), SSI=0.36/1.00 (I-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.



JOB NAME 313999	TRUSS NAME H1A	QUANTITY 2	PLY 2	JOB DESC. JT-39002	DRWG NO. E-19112588(2)
--------------------	-------------------	---------------	----------	-----------------------	---------------------------

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:49 2019 Page 2

ID:MF8iiriaTok7DlbpT4B71Xys4PG-Daw78MR2ZKcOx9reHHRGwHO9cXNptfcMNEZxyKEKS

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTWW+m	MT20	5.0	6.0	1.75	1.00
D	TMWW-l	MT20	4.0	4.0		
E	TMWW-l	MT20	4.0	4.0		
F	TSW+l	MT20	4.0	6.0		
G	TMVW-l	MT20	4.0	6.0	1.75	3.00
H	BMV1+p	MT20	2.0	4.0		
I	BMWW-l	MT20	5.0	8.0		
J	BS-l	MT20	4.0	6.0		
K	BMWW-l	MT20	4.0	4.0		
L	BMWW-l	MT20	4.0	4.0	2.00	1.50
M	BMWW-l	MT20	4.0	4.0		
N	BMV1+p	MT20	2.0	4.0		

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (G) (INPUT = 0.90)


JSI METAL= 0.58 (J) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 16:04:50 2019 Page 1
ID:MF8iiriaTok7DlbpT4B71Xys4PG-hmUVMISgKdkFZPk1B7ogp8qZf0oDYOVbJ6o5NyKEKR



TOTAL WEIGHT = 2 X 119 = 239 lb

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2
C - E	2x4	DRY	No.2
E - G	2x4	DRY	No.2
G - H	2x4	DRY	No.2
N - B	2x4	DRY	No.2
I - H	2x4	DRY	No.2
N - K	2x6	DRY	No.2
K - I	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - E	12	TOP
E - G	12	SIDE(41.1)
G - H	12	SIDE(61.0)
N - B	12	TOP
I - H	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
N - K	12	SIDE(10.0)
K - I	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
N	2056	0	2056	0	5-8
I	2628	0	2628	0	1-9

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
N	1457	939 / 0	0 / 0	0 / 0	0 / 0	519 / 0	0 / 0
I	1866	1181 / 0	0 / 0	0 / 0	0 / 0	686 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.43 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 / 48	M-C	-705 / 0
B-C	-1395 / 0	J-G	-950 / 0
C-D	-2819 / 0	B-M	0 / 1064
D-E	-3230 / 0	J-H	0 / 1592
E-O	-3230 / 0	C-L	0 / 2491
O-F	-3230 / 0	L-D	-870 / 0
F-G	-3229 / 0	D-K	0 / 518
G-H	-1714 / 0	K-F	-1075 / 0
N-B	-2004 / 0	K-G	0 / 2776
I-H	-2886 / 0		
N-M	0 / 0		
M-L	0 / 813		
L-P	0 / 2819		
P-K	0 / 2819		
K-J	0 / 995		
J-I	0 / 0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	21-11-5	-120	-120	—	FRONT	VERT	TOTAL	—	C1
P	13-5-9	-1103	-1103	—	FRONT	VERT	TOTAL	—	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 2-2-12
RIGHT SETBACK = 1-11-5
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 10-5-0 OF SPAN
MEASURED FROM THE RIGHT.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2010, NBC2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.10")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.20")

CSI: TC=0.61/1.00 (F-G:1), BC=0.70/1.00 (K-L:1),
WB=0.34/1.00 (G-K:1), SSI=0.28/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

CONTINUED ON PAGE 2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H9		2	JT-39002	E-19112589(2)

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 15:04:50 2019 Page 2

ID:MF8ilriaTok7DlbpT4B71Xys4PG-hmUVMISgKdkFZPk1B?ogp8qZf0oDYOVibJ8o5NyKEKR

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTWW+m	MT20	5.0	6.0	1.75	1.00
D	TMVW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMW+w	MT20	2.0	4.0		
G	TTWW+m	MT20	6.0	7.0	Edge	1.50
H	TMVW+p	MT20	4.0	6.0	2.00	2.00
I	BMV1+p	MT20	2.0	4.0		
J	BMWW-t	MT20	4.0	4.0		
K	BSWWW-t	MT20	7.0	8.0	4.50	4.00
L	BMWW-t	MT20	4.0	6.0		
M	BMWW-t	MT20	4.0	4.0		
N	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN MAX MIN
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (J) (INPUT = 0.80)

JSI METAL= 0.30 (K) (INPUT = 1.00)


NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H10		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:52 2019 Page 1
ID:MF8IriaTok7DlbpT4B71Xys4PG-e9cFmOTwsF_zokuQJQr8uZvrMpYz0Dr22dbuAGyKEKP



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H11T		1	TRUSS DESC.	JT-39002


Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 M/Tek Industries, Inc. Mon Nov 11 15:04:53 2019 Page 1

ID:MF8iirfaTok7DibpT4B71Xys4PG-6L9e_kUYdY6pQsTct7MNRmS8pDwRlm5BHHLsilyKEKO

-1-3-8 0-0
1-3-8 5-8-4 5-8-4 5-3-2 10-11-6 13-9-0 15-0-8
3x5 ||
12-1-3 9-11-3 2-4-3 16.00 12 4x6 || 3x5 || 3x5 || 4x8 || 2-4-1 3-2-0 7-8
16.50 12 3x6 || 0-0 5-8 12-10-0 5-8-4 5-8-4 5-3-2 10-11-6 13-3-0 13-9-0 2-3-10 6-0

Scale = 1:90.9



TOTAL WEIGHT = 2 X 77 = 154 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - C	2x4 DRY	1650F 1.6E	SPF	
C - D	2x4 DRY	No.2	SPF	
D - G	2x4 DRY	No.2	SPF	
K - B	2x4 DRY	No.2	SPF	
H - F	2x6 DRY	No.2	SPF	
K - I	2x4 DRY	No.2	SPF	
I - H	2x4 DRY	No.2	SPF	
ALL WEBS	2x3 DRY	No.2	SPF	
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	6.0	2.00	2.00
C TTW+p	MT20	3.0	5.0	2.00	Edge
D TS-I	MT20	3.0	5.0		
E TMVW-I	MT20	3.0	5.0	1.50	1.50
F TMVW-I	MT20	4.0	9.0	2.00	3.00
H BVM1-I	MT20	3.0	6.0	Edge	
I BBWW-I	MT20	5.0	6.0	3.00	3.00
J BBWWW-I	MT20	4.0	6.0		
K BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	UP/LIFT	IN-SX
JT	830	0	830	0
K	830	0	830	0
H	830	0	5-8 (5-6)	5-6

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): H

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN	COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
K	587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0
H	587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.71 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 48	-84.9 -84.9	0.10 (1)	J-C	0 / 258	0.06 (4)	
B-C	-425 / 0	-84.9 -84.9	0.30 (1)	J-E	-497 / 0	0.29 (1)	
C-D	-456 / 0	-84.9 -84.9	0.28 (1)	I-E	0 / 388	0.09 (1)	
D-E	-456 / 0	-84.9 -84.9	0.28 (1)	B-J	0 / 270	0.06 (1)	
E-F	-1132 / 0	-84.9 -84.9	0.23 (1)	I-F	0 / 781	0.18 (1)	
F-G	0 / 48	-84.9 -84.9	0.12 (1)				
K-B	-789 / 0	0.0 0.0	0.10 (1)				
H-F	-804 / 0	0.0 0.0	0.08 (1)				

K-J	0 / 0	-18.5 -18.5	0.16 (4)	10.00
J-I	0 / 697	-18.5 -18.5	0.22 (4)	10.00
I-H	0 / 0	-18.5 -18.5	0.04 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCSC 2018, OBC 2012, ABC 2019
- CSA 088-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.46")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.02")
ALLOWABLE DEFL.(TL) = $L/360$ (0.46")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.05")

CSI: TC=0.30/1.00 (B-C:1), BC=0.22/1.00 (I-J:4), WB=0.29/1.00 (E-J:1), SSI=0.12/1.00 (C-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.81 (D) (INPUT= 0.90)
JSI METAL= 0.31 (I) (INPUT= 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H11TG		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 6.300 S Aug 9 2019 Mitek Industries, Inc. Mon Nov 11 15:04:54 2018 Page 1


ID:MF8IriaTok7DlbpT4B71Xys4PG-aXj0B4VAOsEg10toQrtcz_JZdGgUDLLWx4?E8yKEKN

-1-3-8-0-0 1-8-4 3-8-4 5-8-4 7-8-4 9-8-4 10-11-6 11-8-4 13-9-0 15-0-8

1-3-8 1-8-4, 2-0-0, 2-0-0, 2-0-0, 2-0-0, 2-0-0, 1-3-2 8-14 2-0-12 1-3-8

3x5 ||

Scale = 1:90.9



TOTAL WEIGHT = 93 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - C	2x4	DRY	1650F 1.6E	SPF
C - D	2x4	DRY	No.2	SPF
D - B	2x4	DRY	No.2	SPF
K - G	2x4	DRY	No.2	SPF
H - F	2x6	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				
GABLE STUDS SPACED AT 2-0-0 OC.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTW+p	MT20	3.0	5.0	2.00	Edge
D	TS-t	MT20	3.0	5.0		
E	TMVW-t	MT20	3.0	5.0	1.50	1.50
F	TMVW-t	MT20	4.0	9.0	2.00	3.00
H	BVM1+H	MT20	3.0	6.0	Edge	
I	BBVW-t	MT20	5.0	6.0	3.00	3.00
J	BMVWW-t	MT20	4.0	6.0		
K	BMV1+p	MT20	2.0	4.0		
L, M, N, O, P, Q, R, S, T, U, V, W						
L	NP+w	MT20	2.0	4.0		
N	NP-p	MT20	2.0	4.0	1.00	1.75
U	NP-p	MT20	2.0	4.0	0.75	2.00

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
K	830	0	830	0	0	4-11-8	1-1-5		
H	830	0	830	0	0	5-8 (5-7)	5-7		

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): H

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN	COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
K	587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0
H	587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.71 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	FORCE	MEMB.	FORCE
(LBS)	(PLF)	(LBS)	(PLF)
FR-TO	FROM TO	FR-TO	FROM TO
A-B	0 / 48	J-C	0 / 258
B-C	-425 / 0	J-E	-497 / 0
C-D	-456 / 0	I-E	0 / 389
D-E	-456 / 0	B-J	0 / 270
E-F	-1132 / 0	I-F	0 / 781
F-G	0 / 48		
K-B	-789 / 0		
H-F	-804 / 0		

K-J	0 / 0	-18.5	-18.5	0.16 (4)	10.00
J-I	0 / 697	-18.5	-18.5	0.22 (4)	10.00
I-H	0 / 0	-18.5	-18.5	0.04 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2018
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.46")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.46")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.30/1.00 (B-C:1), BC=0.22/1.00 (I-J:4), WB=0.29/1.00 (E-J:1), SS=0.12/1.00 (C-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	618	354	1667
	788	1887	1656

PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.81 (D) (INPUT = 0.90)
JSI METAL= 0.31 (I) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





JSI GRIP= 0.87 (E) (INPUT = 0.90)
JSI METAL= 0.35 (G) (INPUT = 1.00)



TOTAL WEIGHT = 67 lb

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - G	2x4	DRY No.2	SPF
K - B	2x6	DRY No.2	SPF
H - F	2x6	DRY No.2	SPF
K - J	2x4	DRY No.2	SPF
J - I	2x4	DRY No.2	SPF
I - H	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF
ALL GABLE WEBS	2x3	DRY No.2	SPF
DRY: SEASONED LUMBER.			
GABLE STUDS SPACED AT 2'-0" O.C.			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
K	243	0	243	0	8-11-0 (5-7-6 3-4	
J	337	0	337	0	8-11-0 (5-7-6 3-4	
I	337	0	337	0	8-11-0 (5-7-6 3-4	
H	243	0	243	0	8-11-0 (5-7-6 3-4	

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
K	171	119 / 0	0 / 0	0 / 0	0 / 0	51 / 0	0 / 0
J	239	154 / 0	0 / 0	0 / 0	0 / 0	85 / 0	0 / 0
I	239	154 / 0	0 / 0	0 / 0	0 / 0	85 / 0	0 / 0
H	171	119 / 0	0 / 0	0 / 0	0 / 0	51 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, J, I, H

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MEMB.	MAX. FACTORED	FACTORED		MAX. UNBRACED	MEMB.	MAX. FACTORED		MAX
	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)			FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM	TO	LENGTH	FR-TO			
A-B	0 / 48	-84.9	-84.9	0.12 (1)	10.00	D-I	-36 / 0	0.01 (1)
B-C	0 / 15	-84.9	-84.9	0.09 (1)	10.00	I-E	-246 / 0	0.04 (1)
C-D	-30 / 0	-84.9	-84.9	0.08 (1)	6.25	J-D	-36 / 0	0.01 (1)
D-E	-30 / 0	-84.9	-84.9	0.08 (1)	6.25	J-C	-246 / 0	0.04 (1)
E-F	0 / 15	-84.9	-84.9	0.09 (1)	10.00	B-J	0 / 2	0.00 (1)
F-G	0 / 48	-84.9	-84.9	0.12 (1)	10.00	I-F	0 / 2	0.00 (1)
K-B	-217 / 0	0.0	0.0	0.02 (1)	7.81			
H-F	-217 / 0	0.0	0.0	0.02 (1)	7.81			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.12/1.00 (A-B:1), BC=0.06/1.00 (I-J:4), WB=0.04/1.00 (E-I:1), SSI=0.07/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667	788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.22 (E) (INPUT = 0.90)
JSI METAL= 0.12 (C) (INPUT = 1.00)

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWV-I	MT20	4.0	9.0	2.00	3.00
C	TMWV-w	MT20	2.0	4.0		
D	TTWVW+p	MT20	4.0	6.0		
E	NP+I	MT20	3.0	4.0	2.00	0.25
F	TMWV-w	MT20	2.0	4.0		
H	BVM1-I	MT20	4.0	9.0	2.00	3.00
I	BVM1-I	MT20	3.0	6.0	Edge	
J	BBVWVW1-m	MT20	5.0	6.0	2.50	2.00
I, J, L, M, N						
I	NP+w	MT20	2.0	4.0		
K	BBVWVW1-m	MT20	5.0	6.0	2.50	2.00
K	BVM1-I	MT20	3.0	6.0	Edge	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H14S		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:59 2018 Page 1

ID:MF8ilriaTok7DlbpT4871Xys4PG-wVXvEnZJCotz8nwmDOTng1iCOeyB9Ov4fDomwMyKEKl



Scale = 1:75.2

TOTAL WEIGHT = 3 X 84 = 253 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4 DRY	No.2	SPF		
C - F	2x4 DRY	No.2	SPF		
I - A	2x4 DRY	No.2	SPF		
G - E	2x4 DRY	No.2	SPF		
I - G	2x4 DRY	No.2	SPF		
ALL WEBS	2x3 DRY	No.2	SPF		
EXCEPT					
H - C	2x4 DRY	No.2	SPF		

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	2.0	4.0		
B	TMVW-t	MT20	3.0	4.0	1.50	1.50
C	TTW+p	MT20	3.0	5.0	2.00	Edge
D	TMVW+H	MT20	3.0	5.0	2.25	0.75
E	TMV+p	MT20	2.0	4.0		
G	BMVW-1	MT20	3.0	4.0		
H	BMVW-1	MT20	4.0	9.0		
I	BMVW-1	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
I	689	0	689	0
G	809	0	809	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
I	489	310 / 0	0 / 0	0 / 0	0 / 0	0 / 0	179 / 0	0 / 0
G	572	376 / 0	0 / 0	0 / 0	0 / 0	0 / 0	196 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC2)	MAX. FACTORED VERT. LOAD (LC3)	MAX. FACTORED VERT. LOAD (LC4)	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC)
FR-TO								FR-TO			
A-B	0 / 25	-84.9	-84.9	0.14 (1)	10.00			B-H	-96 / 0	0.11 (1)	
B-C	-384 / 0	-84.9	-84.9	0.11 (1)	6.25			H-C	0 / 354	0.06 (1)	
C-D	-385 / 0	-84.9	-84.9	0.13 (1)	6.25			H-D	-131 / 0	0.14 (1)	
D-E	0 / 28	-84.9	-84.9	0.16 (1)	10.00			I-B	-596 / 0	0.65 (1)	
E-F	0 / 48	-84.9	-84.9	0.12 (1)	10.00			D-G	-600 / 0	0.62 (1)	
I-A	-107 / 0	0.0	0.0	0.02 (1)	7.81						
G-E	-228 / 0	0.0	0.0	0.03 (1)	7.81						
I-H	0 / 255	-18.5	-18.5	0.28 (4)	10.00						
H-G	0 / 278	-18.5	-18.5	0.26 (4)	10.00						

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
	DL = 8.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.44")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.44")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.06")

CSI: TC=0.16/1.00 (D-E:1), BC=0.26/1.00 (G-H:4), WB=0.65/1.00 (B-I:1), SSI=0.11/1.00 (G-H:4)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667
	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.79 (D) (INPUT = 0.80)
JSI METAL= 0.38 (D) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H14T		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 15:05:01 2019 Page 1
ID:MF8iiriaTok7DlbpT4B71Xys4PG-Ph5HS7axzi?qlxVyn5_0DFEN72LfuyJDutXJSnyKEKH



Scale = 1:75.6

TOTAL WEIGHT = 2 X 83 = 166 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
L - K	2x4	DRY	No.2	SPF
K - J	2x4	DRY	No.2	SPF
J - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TMWW-I	MT20	3.0	5.0	1.50	1.50
D	TTW+p	MT20	3.0	5.0	2.00	Edge
E	TMWW-I	MT20	3.0	5.0	1.50	1.50
F	TMVW+p	MT20	4.0	6.0	2.00	2.00
H	BMV1+p	MT20	2.0	4.0		
I	BBWW-I	MT20	4.0	6.0	2.00	4.00
J	BBWWW-p	MT20	5.0	6.0	2.75	3.00
K	BBWW-I	MT20	4.0	6.0	2.00	4.00
L	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
JT	830	0	830	0	5-8	1-8
L	830	0	830	0	5-8	1-8

UNFACTORED REACTIONS

	MAX./MIN. COMPONENT REACTIONS						
	1ST LCASE COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0
H	587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 48	-84.9 -84.9	0.12 (1)	10.00	J-D	0 / 490	0.11 (1)
B-C	-472 / 0	-84.9 -84.9	0.14 (1)	6.25	J-E	-13 / 0	0.01 (1)
C-D	-507 / 0	-84.9 -84.9	0.17 (1)	6.25	I-E	-341 / 0	0.19 (1)
D-E	-507 / 0	-84.9 -84.9	0.17 (1)	6.25	C-J	-13 / 0	0.01 (1)
E-F	-472 / 0	-84.9 -84.9	0.14 (1)	6.25	K-C	-341 / 0	0.19 (1)
F-G	0 / 48	-84.9 -84.9	0.12 (1)	10.00	B-K	0 / 367	0.08 (1)
L-B	-803 / 0	0.0 0.0	0.10 (1)	7.81	I-F	0 / 367	0.08 (1)
H-F	-803 / 0	0.0 0.0	0.10 (1)	7.81			
L-K	0 / 0	-18.5 -18.5	0.05 (4)	10.00			
K-J	0 / 360	-18.5 -18.5	0.12 (4)	10.00			
J-I	0 / 360	-18.5 -18.5	0.12 (4)	10.00			
I-H	0 / 0	-18.5 -18.5	0.05 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.46")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.46")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.17/1.00 (D-E:1), BC=0.12/1.00 (I-J:4), WB=0.19/1.00 (E-I:1), SSI=0.10/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 L.S BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618 354 1667 788 1987 1656	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.75 (D) (INPUT = 0.90)
JSI METAL= 0.21 (F) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H14TG		1	TRUSS DESC.	JT-39002


Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:05:02 2019 Page 1

ID:MF8ilriaTok7DlbpT4B71Xys4PG-L4C1tpbCVJFY?FRLuW0UlgKjHr1YMtjWMB0QWhyKEKF

-1-3-8 0-0-10-8 2-11-0 4-10-8 6-10-8 8-10-8 10-10-0 12-10-8 13-9-0 15-0-8
1-3-8 10-8 2-0-8 1-11-8 2-0-0 2-0-0 1-11-8 2-0-8 10-8 1-3-8

Scale = 1:78.9



TOTAL WEIGHT = 98 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
L - K	2x4	DRY	No.2	SPF
K - J	2x4	DRY	No.2	SPF
J - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				
GABLE STUDS SPACED AT	2-0-0	OC.		

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TMVW-t	MT20	3.0	5.0	1.50	1.50
D	TTW+p	MT20	3.0	5.0	2.00	Edge
E	TMVW-t	MT20	3.0	5.0	1.50	1.50
F	TMVW+p	MT20	4.0	6.0	2.00	2.00
H	BMV1+p	MT20	2.0	4.0		
I	BBWW1-I	MT20	4.0	6.0	2.00	4.00
J	BBWW1-p	MT20	4.0	6.0		
K	BBWW1-I	MT20	4.0	6.0	2.00	4.00
L	BMV1+p	MT20	2.0	4.0		
M	NP+w	MT20	2.0	4.0	1.00	1.00
M, N, O, P, Q, R, S, T, U, V, W, X						
M	NP+w	MT20	2.0	4.0		
P	NP+w	MT20	2.0	4.0	1.25	1.00
U	NP+w	MT20	2.0	4.0	1.00	1.00
X	NP+w	MT20	2.0	4.0	1.25	1.00

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
L	379	0	379	0	13-9-0 (6-10-8)5-4	
K	195	0	195	0	13-9-0 (6-10-8)5-4	
J	512	0	512	0	13-9-0 (6-10-8)5-4	
I	195	0	195	0	13-9-0 (6-10-8)5-4	
H	379	0	379	0	13-9-0 (6-10-8)5-4	

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): J

UNFACTORED REACTIONS

1ST CASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	265	193 / 0	0 / 0	0 / 0	0 / 0	71 / 0	0 / 0
K	141	72 / 0	0 / 0	0 / 0	0 / 0	69 / 0	0 / 0
J	361	241 / 0	0 / 0	0 / 0	0 / 0	121 / 0	0 / 0
I	141	72 / 0	0 / 0	0 / 0	0 / 0	69 / 0	0 / 0
H	265	193 / 0	0 / 0	0 / 0	0 / 0	71 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, K, J, I, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF D-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO			FR-TO		
A-B	0 / 48	-84.9	-84.9	0.12 (1)	J-D	-241 / 0	0.12 (1)
B-C	-96 / 0	-84.9	-84.9	0.19 (1)	J-E	-79 / 0	0.03 (1)
C-D	-50 / 0	-84.9	-84.9	0.19 (1)	I-E	-237 / 0	0.14 (1)
D-E	-50 / 0	-84.9	-84.9	0.19 (1)	C-J	-79 / 0	0.03 (1)
E-F	-96 / 0	-84.9	-84.9	0.19 (1)	K-C	-237 / 0	0.14 (1)
F-G	0 / 48	-84.9	-84.9	0.12 (1)	B-K	0 / 98	0.02 (1)
L-B	-352 / 0	0.0	0.0	0.04 (1)	I-F	0 / 98	0.02 (1)
H-F	-352 / 0	0.0	0.0	0.04 (1)			
L-K	0 / 0	-18.5	-18.5	0.05 (4)			
K-J	0 / 93	-18.5	-18.5	0.09 (4)			
J-I	0 / 93	-18.5	-18.5	0.09 (4)			
I-H	0 / 0	-18.5	-18.5	0.05 (4)			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.19/1.00 (B-C:1), BC=0.09/1.00 (I-J:4), WB=0.14/1.00 (E-I:1), SS=0.10/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1666


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.37 (J) (INPUT = 0.90)
JSI METAL= 0.17 (J) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





Scale = 1:80.2

TOTAL WEIGHT = 2 X 220 = 458 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
AU - B	2x4	DRY No.2	SPF	
A - H	2x4	DRY No.2	SPF	
H - K	2x4	DRY No.2	SPF	
K - O	2x4	DRY No.2	SPF	
O - R	2x4	DRY No.2	SPF	
R - Y	2x4	DRY No.2	SPF	
Z - X	2x4	DRY No.2	SPF	
AU - AN	2x4	DRY No.2	SPF	
AN - AG	2x4	DRY No.2	SPF	
AG - Z	2x4	DRY No.2	SPF	
ALL WEBS EXCEPT				
AI - O	2x4	DRY No.2	SPF	
AJ - N	2x4	DRY No.2	SPF	
AK - M	2x4	DRY No.2	SPF	
AL - L	2x4	DRY No.2	SPF	
AM - J	2x4	DRY No.2	SPF	
AH - P	2x4	DRY No.2	SPF	
ALL GABLE WEBS EXCEPT				
ST1	2x4	DRY No.2	SPF	
ST2	2x4	DRY No.2	SPF	
ST3	2x4	DRY No.2	SPF	
ST4	2x4	DRY No.2	SPF	
ST5	2x4	DRY No.2	SPF	
ST12	2x4	DRY No.2	SPF	

DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2'-0" OC.

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMV+p	MT20	2.0	4.0	
C, D, E, F, G, I, J, M, N, P, Q, S, T, U, V, W	MT20	2.0	4.0	
C TMW+w	MT20	2.0	4.0	
H TS-t	MT20	3.0	6.0	
K				
K TTW+m	MT20	4.0	6.0	Edge 1.00

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

FOR SECTION K-O, MAX. PURLIN SPACING = 2.00 FT.

FOR OTHER SECTIONS, TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF O-AI, N-AJ, M-AK, L-AL, J-AM, I-AO, P-AH, Q-AF.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING									
TOTAL LOAD CASES: (4)									
CHORDS				WEBS					
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)		
FR-TO		FROM TO			FR-TO				
AU-B	-210 / 0	0.0	0.0 0.01 (4)	7.81	AI-O	-186 / 0	0.15 (1)		
A-B	0 / 32	-84.9	-84.9 0.11 (1)	10.00	AJ-N	-186 / 0	0.15 (1)		
B-C	-11 / 0	-84.9	-84.9 0.04 (1)	6.25	AK-M	-186 / 0	0.14 (1)		
C-D	-4 / 0	-84.9	-84.9 0.04 (1)	10.00	AL-L	-188 / 0	0.15 (1)		
D-E	-3 / 0	-84.9	-84.9 0.04 (1)	10.00	AM-J	-176 / 0	0.11 (1)		
E-F	-2 / 4	-84.9	-84.9 0.04 (1)	10.00	AO-I	-165 / 0	0.10 (1)		
F-G	-2 / 6	-84.9	-84.9 0.04 (1)	10.00	AP-G	-170 / 0	0.22 (1)		
G-H	-1 / 8	-84.9	-84.9 0.04 (1)	10.00	AQ-F	-168 / 0	0.13 (1)		
H-I	-1 / 8	-84.9	-84.9 0.04 (1)	10.00	AR-E	-168 / 0	0.08 (1)		
I-J	0 / 12	-84.9	-84.9 0.05 (1)	10.00	AS-D	-167 / 0	0.04 (1)		
J-K	-2 / 5	-84.9	-84.9 0.04 (1)	10.00	AT-C	-167 / 0	0.03 (1)		
K-L	0 / 15	-92.4	-92.4 0.04 (1)	2.00	AH-P	-176 / 0	0.10 (1)		
L-M	0 / 10	-92.4	-92.4 0.04 (1)	2.00	AF-Q	-165 / 0	0.09 (1)		
M-AV	0 / 10	-92.4	-92.4 0.04 (1)	2.00	AE-S	-170 / 0	0.21 (1)		
AV-N	0 / 10	-92.4	-92.4 0.04 (1)	2.00	AD-T	-168 / 0	0.12 (1)		
N-O	0 / 10	-92.4	-92.4 0.04 (1)	2.00	AC-U	-166 / 0	0.07 (1)		
O-P	0 / 11	-84.9	-84.9 0.04 (1)	10.00	AB-V	-177 / 0	0.04 (1)		
P-Q	0 / 12	-84.9	-84.9 0.04 (1)	10.00	AA-W	-121 / 0	0.02 (1)		
Q-R	-1 / 8	-84.9	-84.9 0.04 (1)	10.00					
R-S	-1 / 8	-84.9	-84.9 0.04 (1)	10.00					
S-T	-2 / 6	-84.9	-84.9 0.04 (1)	10.00					
T-U	-2 / 4	-84.9	-84.9 0.04 (1)	10.00					
U-V	-3 / 0	-84.9	-84.9 0.04 (1)	10.00					
V-W	-3 / 0	-84.9	-84.9 0.04 (1)	10.00					
W-X	-26 / 0	-84.9	-84.9 0.09 (1)	6.25					
X-Y	0 / 32	-84.9	-84.9 0.11 (1)	10.00					
Z-X	-227 / 0	0.0	0.0 0.03 (1)	7.81					
AU-AT	0 / 9	-18.5	-18.5 0.02 (4)	10.00					
AT-AS	0 / 3	-18.5	-18.5 0.02 (4)	10.00					
AS-AR	0 / 2	-18.5	-18.5 0.02 (4)	10.00					
AR-AQ	-3 / 2	-18.5	-18.5 0.02 (4)	10.00					
AQ-AP	-5 / 1	-18.5	-18.5 0.01 (4)	10.00					
AP-AO	-7 / 1	-18.5	-18.5 0.01 (4)	10.00					
AO-AN	-8 / 0	-18.5	-18.5 0.01 (4)	10.00					
AN-AM	-8 / 0	-18.5	-18.5 0.01 (4)	10.00					
AM-AL	-10 / 0	-18.5	-18.5 0.01 (4)	10.00					
AL-AK	-10 / 0	-18.5	-18.5 0.01 (4)	10.00					
AK-AJ	-10 / 0	-18.5	-18.5 0.01 (4)	10.00					
AJ-AI	-10 / 0	-18.5	-18.5 0.01 (4)	10.00					
AI-AH	-10 / 0	-18.5	-18.5 0.01 (4)	10.00					

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF
DL = 6.0 PSF

BOT CH. LL = 0.0 PSF
DL = 7.4 PSF

TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON PIGGYBACK TRUSS WITH SLOPES OF 6.00/12 AND -6.00/12 AND RESPECTIVE WALL HEIGHTS OF 0-0 AND 0-0 AND AN ADDITIONAL DEAD LOAD OF 3.0 P.S.F.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2015, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD EXCEPT 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.11/1.00 (A-B:1), BC=0.03/1.00 (Z-AA:1), WB=0.22/1.00 (G-AP:1), SS=0.08/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.56 (K) (INPUT = 0.90)


JSI METAL= 1.02 (X) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H16P		1	TRUSS DESC.	JT-39002 E-19112599

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:05:08 2019 Page 1
ID:MF8iiriaTok7DlbpT4B71Xys4PG-DrSYIAeiZYIzUysy67M5QTWUROSPJjib6Gp_efSyKEKB



Scale = 1:16.5

TOTAL WEIGHT = 2 X 15 = 30 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
B - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0		
C	TTW+p	MT20	3.0	4.0	2.25	1.50
D	TMB1-I	MT20	3.0	4.0		
F	BMW1+w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): F

PROVIDE ANCHORAGE AT BEARING JOINT A FOR 150 LBS. FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT E FOR 150 LBS. FACTORED UPLIFT
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S).

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 27	-103.4 -103.4	0.05 (1)	10.00	F-C	-108 / 0	0.02 (1)
B-H	-71 / 0	-84.9 -84.9	0.05 (1)	6.25	G-H	-66 / 10	0.00 (1)
H-C	-48 / 0	-84.9 -84.9	0.05 (1)	6.25	I-J	-66 / 10	0.00 (1)
C-J	-48 / 0	-84.9 -84.9	0.05 (1)	6.25			
J-D	-71 / 0	-84.9 -84.9	0.05 (1)	6.25			
D-E	0 / 27	-103.4 -103.4	0.05 (1)	10.00			
B-G	0 / 35	-18.5 -18.5	0.03 (1)	10.00			
G-F	0 / 35	-18.5 -18.5	0.04 (1)	10.00			
F-I	0 / 35	-18.5 -18.5	0.04 (1)	10.00			
I-D	0 / 35	-18.5 -18.5	0.03 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN./C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.05/1.00 (A-B:1), BC=0.04/1.00 (F-I:1), WB=0.02/1.00 (C-F:1), SSI=0.06/1.00 (C-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.19 (D) (INPUT = 0.80)
JSI METAL= 0.04 (D) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2


NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME 310385	TRUSS NAME J1	QUANTITY 1	PLY 1	JOB DESC. TRUSS DESC.	JT-39002	DRWG NO. E-19072240
--------------------	------------------	---------------	----------	--------------------------	----------	------------------------

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MiTek Industries, Inc. Wed Jul 10 10:24:38 2019 Page 1
ID:MF8IriaTok7DlbpT4B71Xys4PG-?PM6jlcxWAL?Kwbuel7hpk67VBo4mqNngkWoHtyzW1N
Scale = 1:31.2



TOTAL WEIGHT = 24 X 16 = 384 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
E - D	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

NOTES: (1)

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG	
JT		VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E		494	0	494	0	0	5-8	1-8
C		187	0	187	0	0	1-8	1-8
D		43	0	48	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	348	235 / 0	0 / 0	0 / 0	0 / 0	113 / 0	0 / 0	0 / 0
C	129	103 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0	0 / 0
D	34	0 / 0	0 / 0	0 / 0	0 / 0	34 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS			WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MEMB. UNBRAC LENGTH	FACTORED MAX. FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO		FR-TO		
E-B	-428 / 0	0.0	0.0	0.16 (4)	7.81		
A-B	0 / 32	-84.9	-84.9	0.11 (1)	10.00		
B-C	-35 / 0	-84.9	-84.9	0.50 (1)	6.25		
E-D	0 / 0	-18.5	-18.5	0.30 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 23.3	PSF
DL	= 6.0	PSF	
BOT CH.	LL	= 0.0	PSF
DL	= 7.4	PSF	
TOTAL LOAD	= 36.7	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/932 (0.08")

CSI: TC=0.50/1.00 (B-C:1), BC=0.30/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.20/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667
	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.28 (B) (INPUT = 0.90)
JSI METAL = 0.22 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
310386	H1		2	JT-39002	E-19072246(2)

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MiTek Industries, Inc. Wed Jul 10 13:36:38 2019 Page 2
ID:MF8ilraTok7DlbpT4B71Xys4PG-hfR8Wr11YhIROIGxV9pAJ4EnuzXpwrjQI05Nc9yzTDN

PLATES (table is in inches)


JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTWW+m	MT20	6.0	7.0	Edge	1.50
D	TMVW-t	MT20	4.0	4.0		
E	TMVW-t	MT20	4.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMV+w	MT20	2.0	4.0		
H	TMVW-t	MT20	4.0	6.0	1.75	3.00
I	BMV1+p	MT20	2.0	4.0		
J	BMVWW-t	MT20	5.0	8.0		
K	BS-t	MT20	3.0	6.0		
L	BMVW-t	MT20	4.0	4.0		
M	BMVW-t	MT20	4.0	4.0	2.00	1.50
N	BMVW-t	MT20	4.0	4.0		
O	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





TOTAL WEIGHT = 4 X 108 = 434 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
E - G	2x4	DRY No.2	SPF
H - G	2x4	DRY No.2	SPF
M - B	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	6.0	2.00	2.00
C TTWW+m	MT20	6.0	7.0	Edge	1.50
D TMVW-t	MT20	4.0	4.0		
E TS-t	MT20	3.0	6.0		
F TMVW+w	MT20	2.0	4.0		
G TMVW-t	MT20	4.0	6.0	2.00	2.75
H BMV1+p	MT20	2.0	4.0		
I BMVWW-t	MT20	6.0	8.0		
J BS-t	MT20	3.0	6.0		
K BMVW-t	MT20	4.0	4.0		
L BMVW-t	MT20	4.0	4.0		
M BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES (1)

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
H	1230	0	1230	0	1-9	1-8
M	1349	0	1349	0	5-8	2-0

UNFACTORED REACTIONS

JT	COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
M	956	620 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.99 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 48	-84.9 -84.9	0.12 (1)	10.00	L-C	-219 / 0	0.16 (1)
B-C	-935 / 0	-84.9 -84.9	0.17 (1)	6.20	C-K	0 / 871	0.20 (1)
C-D	-1191 / 0	-84.9 -84.9	0.61 (1)	4.99	K-D	-471 / 0	0.34 (1)
D-E	-1031 / 0	-84.9 -84.9	0.62 (1)	5.22	D-I	-219 / 0	0.13 (1)
E-F	-1031 / 0	-84.9 -84.9	0.62 (1)	5.22	I-F	-645 / 0	0.47 (1)
F-G	-1031 / 0	-84.9 -84.9	0.63 (1)	5.22	I-G	0 / 1393	0.31 (1)
H-G	-1177 / 0	0.0 0.0	0.24 (1)	5.88	B-L	0 / 646	0.15 (1)
M-B	-1336 / 0	0.0 0.0	0.17 (1)	7.00			
M-L	0 / 0	-18.5 -18.5	0.13 (4)	10.00			
L-K	0 / 554	-18.5 -18.5	0.21 (4)	10.00			
K-J	0 / 1191	-18.5 -18.5	0.32 (4)	10.00			
J-I	0 / 1191	-18.5 -18.5	0.32 (4)	10.00			
I-H	0 / 0	-18.5 -18.5	0.21 (4)	10.00			

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.63/1.00 (F-G:1), BC=0.32/1.00 (I-K:4), WB=0.47/1.00 (F-I:1), SSI=0.28/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (G) (INPUT = 0.90)
JSI METAL= 0.38 (B) (INPUT = 1.00)



Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MITek Industries, Inc. Wed Jul 10 13:36:41 2019 Page 1
ID:MF8IriaTok7DlbpT4B71Xys4PG-6E7G8s3wrc70FI?WAlMkIsJrBaH79OsO_K1DUyzTDK
2x4 II Scale = 1:51.4



TOTAL WEIGHT = 4 X 116 = 466 lb

LUMBER				N. L. G. A. RULES	
CHORDS	SIZE	LUMBER	DESCR.		
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
H - G	2x4	DRY	No.2	SPF	
M - B	2x4	DRY	No.2	SPF	
M - J	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
DRY: SEASONED LUMBER.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	6.0	2.00 2.00
C	TTWW+m	MT20	6.0	7.0	Edge 1.50
D	TMVW-t	MT20	4.0	4.0	
E	TS-t	MT20	3.0	6.0	
F	TMVW-w	MT20	2.0	4.0	
G	TMVW-t	MT20	4.0	4.0	1.50 1.75
H	BMV1+p	MT20	2.0	4.0	
I	BMVWW-t	MT20	5.0	6.0	2.25 1.50
J	BS-t	MT20	3.0	6.0	
K	BMVW-t	MT20	4.0	4.0	
L	BMVW-t	MT20	4.0	4.0	
M	BMV1+p	MT20	2.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	GROSS REACTION	VERT	HORZ	GROSS REACTION	DOWN	BRG	IN-SX	BRG	IN-SX
H	1230	0	0	1230	0	0	1-9	1-8	
M	1349	0	0	1349	0	0	5-8	2-0	

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
H	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0		
M	956	620 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.48 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 48	-84.9 -84.9	0.12 (1)	L-C	-146 / 28	0.18 (1)	
B-C	-954 / 0	-84.9 -84.9	0.30 (1)	C-K	0 / 660	0.15 (1)	
C-D	-993 / 0	-84.9 -84.9	0.53 (1)	K-D	-389 / 0	0.47 (1)	
D-E	-824 / 0	-84.9 -84.9	0.54 (1)	D-I	-264 / 0	0.19 (1)	
E-F	-824 / 0	-84.9 -84.9	0.54 (1)	I-F	-613 / 0	0.74 (1)	
F-G	-824 / 0	-84.9 -84.9	0.54 (1)	I-G	0 / 1258	0.28 (1)	
H-G	-1180 / 0	0.0 0.0	0.34 (1)	B-L	0 / 625	0.14 (1)	
M-B	-1322 / 0	0.0 0.0	0.17 (1)				
M-L	0 / 0	-18.5 -18.5	0.13 (4)				
L-K	0 / 567	-18.5 -18.5	0.19 (4)				
K-J	0 / 993	-18.5 -18.5	0.28 (4)				
J-I	0 / 993	-18.5 -18.5	0.28 (4)				
I-H	0 / 0	-18.5 -18.5	0.19 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 36.7	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.08")

CSI: TC=0.54/1.00 (F-G:1), BC=0.28/1.00 (I-K:4), WB=0.74/1.00 (F-I:1), SS=0.28/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (I) (INPUT = 0.90)
JSI METAL= 0.37 (B) (INPUT = 1.00)





JSI GRIP= 0.90 (I) (INPUT = 0.90)
JSI METAL= 0.38 (B) (INPUT = 1.00)



TOTAL WEIGHT = 4 X 143 = 574 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - F	2x6	DRY	No.2
F - G	2x6	DRY	No.2
H - G	2x4	DRY	No.2
K - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
I - H	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2
D - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	2.0	4.0
C	TMWW-t	MT20	4.0	4.0 1.50 1.00
D	TTWW+m	MT20	4.0	6.0 3.00 1.00
E	TMW+w	MT20	2.0	4.0
F	TS-t	MT20	4.0	6.0
G	TMW-t	MT20	4.0	6.0
H	BMV1+p	MT20	2.0	4.0
I	BSWWW-t	MT20	5.0	8.0 3.00 4.00
J	BMW-t	MT20	4.0	4.0
K	BMVW-t	MT20	4.0	4.0 2.00 1.75

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	IN-SX	BRG
H	1230	0	1230	0	0	1-9	1-8	1-8	
K	1349	0	1349	0	0	5-8	1-8	1-8	

UNFACTORED REACTIONS		1ST LCASE		MAX/MIN COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND
H	873	554 / 0	0 / 0	0 / 0	0 / 0
K	956	620 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.18 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I, E-I, G-I, C-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. VERT. LOAD LC1 (L.C)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FR-TO)	MAX. VERT. LOAD LC1 (L.C)
A-B	0 / 48	-84.9	-84.9 0.12 (1)	C-J	0 / 41	10.00	0.01 (4)
B-C	0 / 23	-84.9	-84.9 0.13 (1)	J-D	0 / 160	10.00	0.06 (4)
C-D	-962 / 0	-84.9	-84.9 0.14 (1)	D-I	0 / 277	6.18	0.04 (1)
D-E	-743 / 0	-84.9	-84.9 0.55 (1)	I-E	-924 / 0	6.25	0.71 (1)
E-F	-743 / 0	-84.9	-84.9 0.55 (1)	I-G	0 / 1136	6.25	0.18 (1)
F-G	-743 / 0	-84.9	-84.9 0.55 (1)	K-C	-1224 / 0	6.25	0.38 (1)
H-G	-1148 / 0	0.0	0.0 0.63 (1)				
K-B	-219 / 0	0.0	0.0 0.03 (1)			7.81	
K-J	0 / 553	-18.5	-18.5 0.36 (4)			10.00	
J-I	0 / 564	-18.5	-18.5 0.37 (4)			10.00	
I-H	0 / 0	-18.5	-18.5 0.43 (4)			10.00	

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018 , OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/930 (0.31")

CSI: TC=0.63/1.00 (G-H:1), BC=0.43/1.00 (H-I:4), WB=0.71/1.00 (E-I:1), SSI=0.28/1.00 (E-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX MIN	MAX MIN	MAX MIN	
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 Inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (K) (INPUT = 0.90)
JSI METAL= 0.45 (C) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
310397	H6		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MITek Industries, Inc. Thu Jul 11 13:23:41 2019 Page 1
ID:kx9l86OLlWqKxByZIGBJHypysKNA-B7cAvJELCMLX9JT?v0R4SE_2p7Yo2PUNgmigKpyz8JW
Scale = 1:87.2



TOTAL WEIGHT = 13 X 148 = 1918 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	1650F 1.5E	SPF	
F - G	2x4	DRY	1650F 1.5E	SPF	
H - G	2x4	DRY	No.2	SPF	
K - B	2x4	DRY	No.2	SPF	
K - I	2x4	DRY	No.2	SPF	
I - H	2x4	DRY	No.2	SPF	
ALL WEBS	2x4	DRY	No.2	SPF	
EXCEPT					
C - J	2x3	DRY	No.2	SPF	
K - C	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
C	TMVW-t	MT20	4.0	4.0	1.50	1.00
D	TTWW+m	MT20	6.0	7.0	Edge	1.50
E	TMVW+w	MT20	2.0	4.0		
F	TS-t	MT20	3.0	8.0		
G	TMVW-t	MT20	4.0	4.0	1.75	1.75
H	BMV1+p	MT20	2.0	4.0		
I	BSWWV-t	MT20	5.0	8.0	3.00	3.75
J	BMVW-t	MT20	4.0	4.0		
K	BMVW-t	MT20	4.0	4.0	2.00	1.75

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
H	1311	0	1311	0
K	1393	0	1393	0

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	938	554 / 0	0 / 0	0 / 0	0 / 0	384 / 0	0 / 0
K	990	620 / 0	0 / 0	0 / 0	0 / 0	370 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, K

BRACING

FOR SECTION D-G, MAX. PURLIN SPACING = 2.00 FT.
FOR OTHER SECTIONS, TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.13 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I, E-I, G-I, C-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED VERT. LOAD LC1 (LC)	MAX. UNBRACED LENGTH FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED VERT. LOAD LC1 (LC)
FR-TO		FROM	TO		FR-TO		FROM	TO
A-B	0 / 48	-84.9	-84.9	0.12 (1)	10.00	C-J	-39 / 30	0.05 (1)
B-C	0 / 29	-84.9	-84.9	0.18 (1)	10.00	J-D	0 / 211	0.04 (4)
C-D	-981 / 0	-84.9	-84.9	0.15 (1)	6.13	D-I	0 / 179	0.03 (1)
D-E	-673 / 0	-92.4	-92.4	0.71 (1)	2.00	I-E	-950 / 0	0.75 (1)
E-F	-674 / 0	-92.4	-92.4	0.72 (1)	2.00	I-G	0 / 1156	0.19 (1)
F-G	-674 / 0	-92.4	-92.4	0.72 (1)	2.00	K-C	-1254 / 0	0.49 (1)
H-G	-1233 / 0	0.0	0.0	0.97 (1)	5.78			
K-B	-234 / 0	0.0	0.0	0.03 (1)	7.81			
K-J	0 / 588	-18.5	-18.5	0.37 (4)	10.00			
J-I	0 / 571	-18.5	-18.5	0.38 (4)	10.00			
I-H	0 / 0	-18.5	-18.5	0.38 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON PIGGYBACK TRUSS WITH SLOPES OF 6.00/12 AND -6.00/12 AND RESPECTIVE WALL HEIGHTS OF 0-0 AND 0-0 AND AN ADDITIONAL DEAD LOAD OF 3.0 P.S.F.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.25")

CSI: TC=0.97/1.00 (G-H:1), BC=0.38/1.00 (H-I:4), WB=0.75/1.00 (E-I:1), SI=0.38/1.00 (E-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	618	354	1667

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.90 (I) (INPUT = 0.90)
JSI METAL= 0.47 (C) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
310397	H7		1	TRUSS DESC.	JT-39002 E-19072393

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MiTek Industries, Inc. Thu Jul 11 13:23:42 2019 Page 1
ID:kx9l86OLIWqKxBYZlGBJHypysKNA-fJAY6fFzzgTOns1BSkyJ7RWF0Xupn0aXvQUDsGyz8JV
Scale = 1:29.9



TOTAL WEIGHT = 4 X 52 = 207 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	
B - G	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0	1.50	2.75
C	TTWW+m	MT20	4.0	6.0	1.75	1.00
D	TMW+w	MT20	2.0	4.0		
E	TMW-I	MT20	3.0	4.0	1.50	1.75
F	BMV1+p	MT20	2.0	4.0		
G	BSWWW1-I	MT20	5.0	6.0	3.00	3.00
H	BMW1+w	MT20	2.0	4.0		

NOTES- (1)

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
		GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
F	323	0	323	0	0	16-2-2 (16-1-2)9-1			
B	-76	0	0	0	-192	16-2-2 (16-1-2)9-1			
H	494	0	494	0	0	16-2-2 (16-1-2)9-1			
G	953	0	953	0	0	16-2-2 (16-1-2)9-1			

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

PROVIDE ANCHORAGE AT BEARING JOINT B FOR 192 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	231	137 / 0	0 / 0	0 / 0	0 / 0	93 / 0	0 / 0
B	-74	64 / 0	0 / 0	0 / 0	0 / 0	0 / -137	0 / 0
H	373	111 / 0	0 / 0	0 / 0	0 / 0	261 / 0	0 / 0
G	672	454 / 0	0 / 0	0 / 0	0 / 0	218 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, B, H, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 11	-84.9 -84.9	0.01 (1)	10.00	H-C	-205 / 0	0.03 (1)
B-C	-74 / 0	-84.9 -84.9	0.00 (1)	6.25	C-G	-11 / 0	0.01 (1)
C-D	-2 / 0	-84.9 -84.9	0.87 (1)	10.00	G-D	-826 / 0	0.12 (1)
D-E	-3 / 0	-84.9 -84.9	0.87 (1)	10.00	G-E	0 / 3	0.00 (1)
F-E	-250 / 0	0.0 0.0	0.03 (1)	7.81			
B-H	0 / 39	-18.5 -18.5	0.29 (4)	10.00			
H-G	0 / 14	-18.5 -18.5	0.29 (4)	10.00			
G-F	0 / 0	-18.5 -18.5	0.33 (4)	10.00			

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.87/1.00 (D-E:1), BC=0.33/1.00 (F-G:4), WB=0.12/1.00 (D-G:1), SSI=0.32/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.78 (C) (INPUT = 0.90)
JSI METAL= 0.41 (G) (INPUT = 1.00)

May 27, 2019

Re: Expiration Date for Technical Bulletins Extended to 12/31/2019

Please be advised that the expiration date of the Technical Bulletins listed below has been extended until December 31, 2019.

T-SPECCP17	T-SPECH17	T-SPECDSHGUS17R
T-SPECHGUS17-R	T-SPECHHUS17-R	T-SPECHUS17
T-SPECLF17	T-SPECLT17	T-SPECLU17
T-SPECCLUL17	T-SPECLUS17	T-SPECSUR17
T-SPECTBE17	T-SPECTC17	T-SPECTHGB17
T-SPECTHGBHV17	T-SPECTHGQ17	T-SPECTHGW17
T-SPECLSULSSU17	T-SPECHTHGQ17	T-SPECSTHGQ17

Should you have any questions or concerns regarding the above, please contact me at your convenience.

Sincerely,



Brent Bunting, P.Eng.
Simpson Strong-Tie Canada, Ltd.



LUS – Double Shear Joist Hangers

SIMPSON
Strong-Tie

All LUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections.

Material: 18 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners.
- Nails: 16d = 0.162" dia. x 3½" long common wire, 10d = 0.148" x 3" long common wire.
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads.
- Not designed for welded or nailer applications.

Options:

- These hangers cannot be modified




Typical LUS
Installation




Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _s ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _p =1.15)	Normal (K _p =1.00)	Uplift (K _p =1.15)	Normal (K _p =1.00)
LUS24	18	1⅞	3⅞	1¾	1⅝	(4) 10d	(2) 10d	710	1630	645	1155
LUS24-2	18	3⅞	3⅞	2	1⅝	(4) 16d	(2) 16d	835	2020	590	1435
LUS26	18	1⅞	4¾	1¾	3⅝	(4) 10d	(4) 10d	1420	2170	1290	1630
LUS26-2	18	3⅞	4¾	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920
LUS26-3	18	4⅞	4¾	2	3¼	(4) 16d	(4) 16d	1720	2595	1545	2340
LUS28	18	1⅞	6⅞	1¾	3¾	(6) 10d	(6) 10d	1420	2520	1290	1790
LUS28-2	18	3⅞	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575
LUS28-3	18	4⅞	6¼	2	3¼	(6) 16d	(4) 16d	1720	3325	1545	2375
LUS210	18	1⅞	7⅞	1¾	3⅞	(8) 10d	(4) 10d	1420	2785	1290	2210
LUS210-2	18	3⅞	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195
LUS210-3	18	4⅞	8⅞	2	5¼	(8) 16d	(6) 16d	2580	3345	2320	2375

1. d_s is the distance from the seat of the hanger to the highest joist nail.



Dome Double Shear Nailing prevents tabs breaking off (available on some models).

U.S. Patent 5,603,580



Double Shear Nailing Top View.



LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2019, and reflects information available as of March 1, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2017 Simpson Strong-Tie Company Inc.

T-SPECUS17 3/17 exp. 6/19

(800) 999-5099
strongtie.com

HHUS – Double Shear Joist Hangers

All HHUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: 14 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia. x 3½" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:


- See current catalogue for options



HHUS410






Typical HHUS Installation
(Truss Designer to provide
fastener quantity for connecting
multiple members together)



Typical HHUS
Installation

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _b ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K ₀ =1.15)	Normal (K ₀ =1.00)	Uplift (K ₀ =1.15)	Normal (K ₀ =1.00)
HHUS26-2	14	3 9/16	5 13/16	3	3 15/16	(14) 16d	(6) 16d	2850	7335	2065	5205
HHUS28-2	14	3 9/16	7 7/32	3	6 5/32	(22) 16d	(8) 16d	3765	8940	2675	6345
HHUS210-2	14	3 9/16	9 9/32	3	8	(30) 16d	(10) 16d	4745	9660	4310	7000
HHUS210-3	14	4 11/16	9	3	7 15/16	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS210-4	14	6 1/8	8 29/32	3	7 27/32	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS46	14	3 3/8	5 13/32	3	3 15/16	(14) 16d	(6) 16d	2540	7335	2065	5205
HHUS48	14	3 3/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3765	8945	2267	6345
HHUS410	14	3 3/8	9	3	8	(30) 16d	(10) 16d	4745	9855	4310	7000
HHUS5.50/10	14	5 1/2	9	3	8	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS7.25/10	14	7 1/4	9	3 3/8	7 29/32	(30) 16d	(10) 16d	4745	10770	4310	7650

1. d_b is the distance from the seat of the hanger to the highest joist nail.




This technical bulletin is effective until June 30, 2019, and reflects information available as of March 1, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com

© 2017 Simpson Strong-Tie Company Inc.

T-SPECHHUS17 3/17 exp. 6/19

(800) 999-5099
strongtie.com



Wood Truss Installation

**A Guide to proper handling, erecting and bracing
metal plate connected wood trusses**

Table of Content

Warning.....	4
1 Unloading & Lifting.....	5
2 Job Site Handling.....	5
3 Hoisting.....	6
4 Beginning the Erection Process.....	7
5 Erection Tolerance.....	8
6 Bracing.....	8
7 Bracing Requirements for 3 Planes of Roof.....	9
8 Stacking Materials.....	10
Caution Notes.....	11

Warning



General

Familiarity with the Construction Design Documents, the Truss Design Drawings, and Truss Placement Plans (if required by the Construction Design Documents) is required to properly erect, brace, and connect the trusses to the building system.

All of the care and quality involved in the design and manufacture of wood trusses can be jeopardized if the trusses are not properly handled, erected, and braced.

The consequences of improper handling, erecting, and bracing may be a collapse of the structure, which at best is a substantial loss of time and materials, and at worst is a loss of life. The majority of truss accidents occur during truss installation and not as a result of improper design or manufacture.

Prior to truss erection, the builder/erector shall meet with the erection crew for a safety and planning meeting, making sure each crew member understands his or her roles and responsibilities during the erection process.

Temporary Erection Bracing

Trusses are not marked in any way to identify the frequency, or location of temporary erection bracing.

All temporary bracing shall comply with the latest edition of *Commentary and Recommendations for Handling, Installing & Bracing Metal Plate Connected Wood Trusses* (HIB), published by the Truss Plate Institute, and/or as specified in the Construction Design Documents prepared by the building designer.

Permanent Truss Bracing

Permanent bracing for the roof or floor trusses is the responsibility of the building designer and should be shown on the Construction Design Documents. Permanent bracing locations for individual compression members of a wood truss are shown on the Truss Design Drawings, and shall be installed by the building or erection contractor. This bracing is needed for the proper performance of individual trusses within the roof or floor system. The design and connection of the bracing to the truss and then to the overall building system is the responsibility of the building designer, and is in addition to the permanent bracing plan, which is also specified by the building designer.

Special Design Requirements

Special design requirements, such as wind bracing, portal bracing, seismic bracing, diaphragms, shear walls, or other load transfer elements and their connections to wood trusses must be considered separately by the building designer, who shall determine size, location, and method of connections for all bracing as needed to resist these forces.

Unloading & Lifting

Never handle trusses flat



Beginning with the unloading process, and throughout all phases of construction, care must be taken to avoid lateral bending of trusses, which can cause damage to the lumber and metal connector plates at the joints.



Avoid lateral bending

- Use special care in windy weather.
- If using a crane within 10 feet of an electric line, contact the local power company.
- If using a crane within 5 miles of an airport, contact the airport 30 days prior to erection to learn about any safety regulations that must be followed.

Job Site Handling




All trusses should be picked up at the top chords in a vertical position only

Proper banding and smooth ground allow for unloading of trusses without damage. This should be done as close to the building site as possible to minimize handling. Do not break banding until installation begins. Hand erection of trusses is allowed, provided excessive lateral bending is prevented.




Do not store unbraced bundles upright

If trusses are stored vertically they shall be braced in a manner that will prevent tipping or topping. Generally cutting of the banding is done just prior to installation.



Do not store on uneven ground

If trusses are stored horizontally, blocking should be used on eight to ten foot centers, or as required, to minimize lateral bending and moisture gain.



Care should be exercised when removing banding to avoid damaging trusses.


During long term storage, trusses shall be protected from the environment in a manner that provides for adequate ventilation of the trusses. If tarpaulins or other material is used, the ends shall be left open for ventilation. Plastic is not recommended, since it can trap moisture.

3 Hoisting


All trusses that are erected one at a time shall be held safely in position by the erection equipment until such time as all necessary bracing has been installed and the ends of the trusses are securely fastened to the building.




Avoid lateral bending




$L \leq 30'$




Truss sling is acceptable where these criteria are met.




$30' < L \leq 60'$



Use spreader bar in all other cases. It should be noted that the lines from the ends of the spreader bar "TOE IN"; if these lines should "TOE OUT" the truss may fold in half.



$L > 60'$



For lifting trusses with spans in excess of 60 feet, it is recommended that a strongback/spreader bar be used as illustrated. The strongback/spreader bar should be attached to the top chord and web members at intervals of approximately 10 feet. Further, the strongback/spreader bar should be at or above the mid-height of the truss to prevent overturning. The strongback/spreader bar can be of any material with sufficient strength to safely carry the weight of the truss and sufficient rigidity to adequately resist bending of the truss.


4

Beginning the Erection Process


It is important for the builder or erection contractor to provide substantial bracing for the first truss erected. The two or more trusses making up the rest of the first set are tied to and rely upon the first truss for stability. Likewise, after this first set of trusses is adequately cross-braced, the remaining trusses installed rely upon this first set for stability. Thus, the performance of the truss bracing system depends to a great extent on how well the first group of trusses is braced.

Ground Brace – Exterior

One satisfactory method ties the first unit of trusses off to a series of braces that are attached to a stake driven into the ground and securely anchored. The ground brace itself should be supported as shown below or it is apt to buckle. Additional ground braces in the opposite direction, inside the building, are also recommended.





Note: Locate ground braces for first truss directly in line with all rows of top chord continuous lateral bracing (either temporary or permanent).



Ground Brace – Interior

Another satisfactory method where height of building or ground conditions prohibit bracing from the exterior is to tie the first truss rigidly in place from the interior at the floor level, provided the floor is substantially completed and capable of supporting the ground bracing forces. Securely fasten the first truss to the middle of the building. Brace the bracing similar to exterior ground bracing shown at left. Set trusses from the middle toward the end of the building. Properly cross-brace the first set of trusses before removing floor braces and setting remaining trusses.




Inadequate size of bracing material or inadequate fastening is a major cause of erection dominoing.


5 Erection Tolerance

Complying with erection tolerances is critical to achieving an acceptable roof or floor line, and to accomplishing effective bracing. Setting trusses within tolerance the first time will prevent the need for the hazardous practice of respacing or adjusting trusses when roof sheathing or roof purlins are installed. Trusses leaning or bowing can cause nails to miss the top chords when sheathing is applied, and create cumulative stresses on the bracing, which is a frequent cause of dominoing.

When sheathing, make sure nails are driven into the top chord of the trusses.



6 Bracing



Do not install trusses on temporarily connected supports



Do not walk on unbraced trusses



Do not walk on trusses or gable ends lying flat




Nails in withdrawal (parallel to force)

All anchors, hangers, tie-downs, seats, bearing ledgers, etc., that are part of the supporting structure shall be accurately and properly placed and permanently attached before truss installation begins. No trusses shall ever be installed on anchors or ties that have temporary connections to the supporting structure.

Nailing scabs to the end of the building to brace the first truss is not recommended.

All nailing of bracing should be done so that nails are driven perpendicular to the direction of force, as shown at right.




Well nailed (perpendicular to force)

7 Bracing Requirements for 3 Planes of Roof

Temporary erection bracing must be applied to three planes of the roof system to ensure stability: Plane 1) Top Chord (sheathing), Plane 2) Bottom Chord (ceiling plane), and Plane 3) Web Member plane or vertical plane perpendicular to trusses.

1) Top Chord Plane

Most important to the builder or erection contractor is bracing in the plane of the top chord. Truss top chords are susceptible to lateral buckling before they are braced or sheathed.




Exact spacing between trusses should be maintained as bracing is installed to avoid the hazardous practice of removing bracing to adjust spacing. This act of "adjusting spacing" can cause trusses to topple if connections are removed at the wrong time.

3) Web Member Plane

"X" bracing, as shown, is critical in preventing trusses from leaning or dominoing. Repeat as shown to create a succession of rigid units.


X-bracing should be installed on vertical web members wherever possible, at or near lateral bracing. Plywood or OSB may be substituted for X-bracing.



Note: Top chords and some web members are not shown, in order to make drawings more readable.

2) Bottom Chord Plane

In order to hold proper spacing on the bottom chord, temporary bracing is recommended on the top of the bottom chord.




* Long spans, heavy loads or other spacing configurations may require closer spacing between lateral bracing and closer intervals between diagonals. Consult the building designer or HIB and DSB (Recommended Design Specification for Temporary Bracing of Metal-Plate Connected Wood Trusses) for details.

Diagonal or cross-bracing is very important!



Do not use short blocks to brace individual trusses without a specific bracing plan detailing their use





Bracing requirements using the same principles apply to parallel chord trusses

8 Stacking Materials

Do not proceed with building completion until all bracing is securely and properly in place


Never stack materials on unbraced or inadequately braced trusses




Platform must be rigidly braced

Proper distribution of construction materials is a must during construction.

Never stack materials near a peak



Never stack materials on the cantilever of a truss




Always stack materials over two or more trusses.




Single truss

Never overload small groups or single trusses. Position load over as many trusses as possible.



Roofing and mechanical contractors are cautioned to stack materials only along outside supporting members or directly over inside supporting members. Trusses are not designed for dynamic loads (i.e., moving vehicles). Extreme care should be taken when loading and stacking construction materials (rolled roofing, mechanical equipment, etc.) on the roof or floor system.

Never cut any structural member of a truss.



Sleepers for mechanical equipment should be located at panel points (joints) or over main supporting members, and only on trusses that have been designed for such loads.

Caution Notes

Errors in building lines and/or dimensions, or errors by others shall be corrected by the contractor or responsible construction trade subcontractor or supplier before erection of trusses begins.


Cutting of nonstructural overhangs is considered a part of normal erection and shall be done by the builder or erection contractor.

Any field modification that involves the cutting, drilling, or relocation of any structural truss member or connector plate shall not be done without the approval of the truss manufacturer or a licensed design professional.

The methods and procedures outlined are intended to ensure that the overall construction techniques employed will put floor and roof trusses safely in place in a completed structure. These recommendations for bracing wood trusses originate from the collective experience of leading technical personnel in the wood truss industry, but must, due to the nature of responsibilities involved, be presented only as a guide for use by a qualified building designer, builder, or erection contractor. Thus, the Wood Truss Council of America expressly disclaims any responsibility for damages arising from the use, application, or reliance on the recommendations and information contained herein.

[Selected text and figures referenced or reproduced from HIB and DSB by permission of the Truss Plate Institute, Madison, WI.]

THE CANADIAN WOOD TRUSS ASSOCIATION



L'ASSOCIATION CANADIENNE DES FABRICANTS DE FERMES DE BOIS

1400 Blair Place, Suite 210, Ottawa, ON K1J 9B8
Tel.: 613-747-5544 Fax: 613-747-6264



Wood Truss Council of America

One WTCA Center
6300 Enterprise Lane, Madison, WI 53719-1140
Tel.: 608-274-4849 Fax: 608-274-3329
wtca@woodtruss.com www.woodtruss.com

FIRM BCIN 113884
DESIGNER BCIN 25593


All work shall conform to the Ontario
Building Code O. Reg. 332/12 as amended

For conventional framing roof / ceilings
framing shall conform to OBC.9.23

CITY OF BRAMPTON
BUILDING DIVISION
REVIEWED

DEC 10 2019

BY
MARY FRENETTE



ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 O.B.C. LATEST EDITION. ROOF RAFTERS THAT CROSS OVER TRUSSES TO BE 2X4 SPF #2 @ 24" O.C WITH A VERT. POST TO THE TRUSS UNDERNEATH AT EACH CROSS POINT. VERT. POSTS LONGER THAN 6' TO HAVE LATERAL BRACING SO THAT THE DISTANCE BETWEEN END POINTS & BETWEEN ROWS OF BRACING DOES NOT EXCEED 6'

Mitek V. 8.2.0

CONVENTIONAL
FRAMING BY
OTHERS



Job Track: 39002
Layout ID: 314238
Plan Log: 104619

Builder / Location:
GOLD PARK HOMES / BRAMPTON

Project: MCLAUGHLIN AND MAYFIELD/ENCORE 2

Date: 2019-10-31 Designer: AMANDA

Model / Elevation:

SD-09 REV1 / C/D OPT TRAY

THESE DRAWINGS CONSTITUTE THE PROPERTY OF ALPA ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY ALPA ROOF TRUSSES INC AND WILL BE RETRACTED BY ALPA ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

EWP DESIGN INC.

(905) 832-2250

FAX (905) 832-0286

RESPONSIBILITIES AND SPECIFICATIONS

RESPONSIBILITIES

1. EWP DESIGN INC. is responsible for the design of trusses as individual components.
2. It is the responsibility of others to ascertain that the design loads utilized on each drawing meet or exceed the actual dead load imposed by the structure, the live load imposed by the intended use and the snow load imposed by local building code or authorities with jurisdictions.
3. All dimensions are to be verified by the owner, contractor, architect or other authorities with jurisdictions before truss fabrication.
4. EWP DESIGN INC. bears no responsibility for the erection of trusses. Persons erecting trusses are cautioned to seek professional advice regarding the temporary and permanent bracing for the system. Bracing shown on EWP DESIGN INC. drawing is specified for the truss as a component only and forms an integral part of the truss design.
5. It is the truss manufacturer's responsibility to ensure that trusses are manufactured in conformance with specifications of EWP DESIGN INC. as outlined below.

SPECIFICATIONS


1. Trusses designed by EWP DESIGN INC. conform to the relevant section of the Ontario Building Code of Canada (Part 9 or Part 4) or to the Canadian code for farm buildings, whichever applies to the building type, as indicated on the EWP DESIGN INC. drawings, and conform to the design procedures established by the Truss Plate Institute of Canada. Unit stresses used for truss designs are as per the edition of CSA-O86 shown on EWP DESIGN INC. drawings.
2. Lumber is to be the size, species and grade as specified on EWP DESIGN INC. drawings.
3. Moisture content of lumber shall not exceed 19% in service unless specified otherwise.
4. Metal connector plates shall be applied to both faces of truss at each joint and shall be positioned as specified.
5. Top chords of trusses are assumed to be continuously braced laterally by roof sheathing or by purlins at intervals not exceeding 12.5 times the thickness of top chord member.
6. Bottom chords shall be laterally braced at intervals not exceeding 3M (10') o.c., where rigid ceiling is not applied directly to the underside of chords.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF EWP DESIGN INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY THE ALPA LUMBER GROUP, AND WILL BE RETRACTED BY EWP DESIGN INC. IF UTILIZED FOR ANY OTHER PURPOSE.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	G01		1	TRUSS DESC.	JT-39002 E-19112586

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 15:04:45 2019 Page 1
ID:MF8ilriaTok7DlbpT4B71Xys4PG-Lpgcl7OXV56ySer4PSDV647qZ?DjDd0R2P1QAYKEKW



TOTAL WEIGHT = 6 X 10 = 63 lb

LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - D 2x4 DRY

B - E 2x4 DRY

LUMBER

No.2

No.2

DESCR.

SPF

SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMB1-4	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	UPLIFT
JT	272	0	272	0
B	59	0	59	0
F	174	0	174	0

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): C

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
JT	191	134 / 0	0 / 0	0 / 0	67 / 0	0 / 0	
B	44	13 / 0	0 / 0	0 / 0	32 / 0	0 / 0	
F	121	93 / 0	0 / 0	0 / 0	28 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)	
FR-TO		FROM	TO	FR-TO			
A-B	0 / 16	-84.9	-84.9 0.12 (5)	G-H	-99 / 5	0.00 (1)	
B-H	-10 / 0	-84.9	-84.9 0.03 (4)				
H-C	0 / 2	-84.9	-84.9 0.10 (1)				
C-D	-10 / 0	-84.9	-84.9 0.03 (1)				
B-G	0 / 0	-18.5	-18.5 0.08 (1)				
G-F	0 / 0	-18.5	-18.5 0.08 (1)				
F-E	0 / 0	-18.5	-18.5 0.01 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CANTILEVER DEFLECTION:

ALLOWABLE DEFL.(TL) = $L/120$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.12/1.00 (A-B:5), BC=0.08/1.00 (F-G:1), WB=0.00/1.00 (G-H:1), SS=0.10/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.17 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2


CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN



JOB NO.	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	G02		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:47 2019 Page 1
ID:MF8iiriaTok7DlbpT4B71Xys4PG-HBoMjhPn1IMgix7SWfZBVCABovNL77JvLu7V2yKEKU



TOTAL WEIGHT = 6 X 8 = 49 lb

LUMBER	SIZE	DRY	LUMBER	DESCR.
N. L. G. A. RULES			No.2	SPF
CHORDS	2x4	DRY	No.2	SPF
A - C				
B - D				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMB1-4	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
C	99	0	99	0	5-8	5-8
B	256	0	256	0	4-0	1-8
D	43	0	43	0	5-8 (5-6)	1-8

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): C

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX/MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
C	69	52 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
B	179	126 / 0	0 / 0	0 / 0	0 / 0	53 / 0	0 / 0
D	32	12 / 0	0 / 0	0 / 0	0 / 0	20 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) C, B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 16	-84.9 -84.9	0.12 (5)	10.00	E-F	-85 / 3	0.00 (1)
B-F	-10 / 0	-84.9 -84.9	0.02 (4)	10.00			
F-C	0 / 2	-84.9 -84.9	0.08 (1)	10.00			
B-E	0 / 0	-18.5 -18.5	0.07 (1)	10.00			
E-D	0 / 0	-18.5 -18.5	0.07 (1)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
DL = 6.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.12/1.00 (A-B:5), BC=0.07/1.00 (D-E:1), WB=0.00/1.00 (E-F:1), SSI=0.09/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - G	2x4	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
N - B	2x4	DRY	No.2	SPF
N - J	2x6	DRY	No.2	SPF
J - H	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C 1	12	TOP
C - F 1	12	SIDE(41.1)
F - G 1	12	SIDE(41.1)
G - H 1	12	TOP
N - B 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
N - J 2	12	SIDE(10.0)
J - H 2	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	UPLIFT	IN-SX
JT	2664	0	0	1-8
H	2053	0	0	1-8
N	2053	0	0	1-8

UNFACTORED REACTIONS

	1ST LCASE	MAX/MIN. COMPONENT REACTIONS
	COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
JT	1891	1200 / 0 0 / 0 0 / 0 0 / 0 691 / 0 0 / 0
H	1455	937 / 0 0 / 0 0 / 0 0 / 0 518 / 0 0 / 0
N		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, N

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.70 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO				FR-TO			
A-B	0 / 48	-84.9 -84.9 0.07 (1)	10.00	M-C	-555 / 0	0.11 (1)	
B-C	-1448 / 0	-84.9 -84.9 0.05 (1)	6.25	B-M	0 / 1104	0.14 (1)	
C-D	-2424 / 0	-84.9 -84.9 0.21 (1)	5.57	C-L	0 / 2115	0.26 (1)	
D-E	-3422 / 0	-84.9 -84.9 0.34 (1)	4.70	L-D	-1380 / 0	0.28 (1)	
E-O	-2390 / 0	-84.9 -84.9 0.35 (1)	5.38	D-K	0 / 1368	0.17 (1)	
O-F	-2390 / 0	-167.1 -167.1 0.35 (1)	5.38	K-E	0 / 254	0.04 (4)	
F-G	-2381 / 0	-167.1 -167.1 0.56 (1)	5.01	E-I	-1416 / 0	0.70 (1)	
H-G	-2585 / 0	0.0 0.0 0.60 (1)	7.06	I-F	-838 / 0	0.17 (1)	
N-B	-2071 / 0	0.0 0.0 0.14 (1)	7.69	I-G	0 / 3185	0.39 (1)	
N-M	0 / 0	-18.5 -18.5 0.03 (1)	10.00				
M-L	0 / 848	-18.5 -18.5 0.09 (1)	10.00				
L-K	0 / 2425	-18.5 -18.5 0.23 (1)	10.00				
K-P	0 / 3422	-18.5 -18.5 0.35 (1)	10.00				
P-J	0 / 3422	-36.4 -36.4 0.35 (1)	10.00				
J-I	0 / 3422	-36.4 -36.4 0.35 (1)	10.00				
I-H	0 / 0	-36.4 -36.4 0.08 (4)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
P	13-5-9	-1103	-1103	-	FRONT	VERT	TOTAL	-	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL	PSF
LL	23.3	PSF
DL	6.0	PSF
BOT CH.	LL	PSF
LL	0.0	PSF
DL	7.4	PSF
TOTAL LOAD	36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 2-2-12
RIGHT SETBACK = 0-0
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
-ADDTL LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 10-5-0 OF SPAN MEASURED FROM THE RIGHT.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")

CSI: TC=0.60/1.00 (G-H:1), BC=0.35/1.00 (I-K:1), WB=0.70/1.00 (E-I:1), SSI=0.36/1.00 (I-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H1A		2	JT-39002	E-19112588(2)

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:49 2019 Page 2
ID:MF8iiriaTok7DlbpT4B71Xys4PG-Daw78MR2ZKcOxF9reHtHRGwHO9cXNptfcMfNEZxyKEKS

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTWW+m	MT20	5.0	6.0	1.75	1.00
D	TMWW-t	MT20	4.0	4.0		
E	TMWW-t	MT20	4.0	4.0		
F	TSW-t	MT20	4.0	6.0		
G	TMVW-t	MT20	4.0	6.0	1.75	3.00
H	BMV1+p	MT20	2.0	4.0		
I	BMWW-t	MT20	5.0	8.0		
J	BS-t	MT20	4.0	6.0		
K	BMWW-t	MT20	4.0	4.0		
L	BMWW-t	MT20	4.0	4.0	2.00	1.50
M	BMWW-t	MT20	4.0	4.0		
N	BMV1+p	MT20	2.0	4.0		

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667
		788	1987
			1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.88 (G) (INPUT = 0.90)


JSI METAL = 0.58 (J) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:50 2019 Page 1
ID:MF8ilriaTok7DlbpT4B71Xys4PG-hmUVMiSgKdkFZPk1B?ogp8qZf0oDYOVlbJ6o5NyKEKR



TOTAL WEIGHT = 2 X 119 = 239 lb

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
G - H	2x4	DRY	No.2	SPF
N - B	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
N - K	2x6	DRY	No.2	SPF
K - I	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - E	12	TOP
E - G	12	SIDE(41.1)
G - H	12	SIDE(61.0)
N - B	12	TOP
I - H	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
N - K	12	SIDE(10.0)
K - I	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
JT	2056	0	2056	0	5-8	1-8
N	2628	0	2628	0	1-9	1-8

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
JT	1457	939 / 0	0 / 0	0 / 0	0 / 0	519 / 0
N	1866	1181 / 0	0 / 0	0 / 0	0 / 0	686 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.43 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 MAX (PLF)		MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
		FROM	TO				
FR-TO							
A-B	0 / 48	-84.9	-84.9	0.07 (1)	10.00	M-C	-705 / 0
B-C	-1395 / 0	-84.9	-84.9	0.05 (1)	8.25	J-G	-950 / 0
C-D	-2819 / 0	-84.9	-84.9	0.32 (1)	5.13	B-M	0 / 1064
D-E	-3230 / 0	-84.9	-84.9	0.59 (1)	4.44	J-H	0 / 1592
E-O	-3230 / 0	-84.9	-84.9	0.59 (1)	4.44	C-L	0 / 2491
O-F	-3230 / 0	-167.1	-167.1	0.59 (1)	4.44	L-D	-870 / 0
F-G	-3229 / 0	-167.1	-167.1	0.61 (1)	4.43	D-K	0 / 518
G-H	-1714 / 0	-84.9	-84.9	0.04 (1)	8.25	K-F	-1075 / 0
N-B	-2004 / 0	0.0	0.0	0.13 (1)	7.78	K-G	0 / 2776
I-H	-2886 / 0	0.0	0.0	0.21 (1)	6.96		
N-M	0 / 0	-18.5	-18.5	0.03 (1)	10.00		
M-L	0 / 813	-18.5	-18.5	0.24 (1)	10.00		
L-P	0 / 2819	-18.5	-18.5	0.70 (1)	10.00		
P-K	0 / 2819	-36.4	-36.4	0.70 (1)	10.00		
K-J	0 / 995	-36.4	-36.4	0.14 (4)	10.00		
J-I	0 / 0	-36.4	-36.4	0.10 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	21-11-5	-120	-120	—	FRONT	VERT	TOTAL	—	C1
P	13-5-9	-1103	-1103	—	FRONT	VERT	TOTAL	—	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 2-2-12
RIGHT SETBACK = 1-11-5
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 10-5-0 OF SPAN MEASURED FROM THE RIGHT.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.I. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.79")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.10")
ALLOWABLE DEFL.(TL) = $L/360$ (0.79")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.20")

CSI: TC=0.61/1.00 (F-G-1), BC=0.70/1.00 (K-L-1)
WB=0.34/1.00 (G-K-1), SSI=0.28/1.00 (F-G-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H9		2	JT-39002	E-19112589(2)

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 15:04:50 2019 Page 2

ID:MF8ilriaTok7DlbpT4B71Xys4PG-hmUVMISgKdkFZPk1B?ogp8qZf0oDYOVibJ6o5NyKEKR

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTWW+m	MT20	5.0	6.0	1.75	1.00
D	TMWW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMW+w	MT20	2.0	4.0		
G	TTWW+m	MT20	6.0	7.0	Edge	1.50
H	TMVW+p	MT20	4.0	6.0	2.00	2.00
I	BMV1+p	MT20	2.0	4.0		
J	BMWW-t	MT20	4.0	4.0		
K	BSWWW-t	MT20	7.0	8.0	4.50	4.00
L	BMWW-t	MT20	4.0	6.0		
M	BMWW-t	MT20	4.0	4.0		
N	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (J) (INPUT = 0.80)

JSI METAL= 0.30 (K) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





TOTAL WEIGHT = 112 lb

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY 2100F 1.8E	SPF
E - F	2x4	DRY 2100F 1.8E	SPF
F - G	2x4	DRY No.2	SPF
M - B	2x4	DRY No.2	SPF
H - G	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			
C - K	2x4	DRY No.2	SPF
K - F	2x4	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW+p	MT20	4.0	6.0	2.00	2.00
C	TTWW+m	MT20	6.0	7.0	Edge	1.50
D	TMW+w	MT20	2.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TTWW+m	MT20	6.0	7.0	Edge	1.50
G	TMW+p	MT20	4.0	6.0	2.00	2.00
H	BMV1+p	MT20	2.0	4.0		
I	BMWV-t	MT20	4.0	4.0		
J	BS-t	MT20	3.0	6.0		
K	BMWV-t	MT20	6.0	6.0		
L	BMWV-t	MT20	4.0	4.0		
M	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	UPLIFT	IN-SX
M	1349	0	1349	0	5-8
H	1230	0	1230	0	1-9

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN	COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
M	956	620 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0
H	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.09 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 48	-84.9	-84.9 0.12 (1)	10.00	L-C	-196 / 23	0.14 (1)
B-C	-944 / 0	-84.9	-84.9 0.17 (1)	6.18	C-K	0 / 907	0.15 (1)
C-D	-1297 / 0	-84.9	-84.9 0.86 (1)	5.09	K-D	-921 / 0	0.67 (1)
D-E	-1298 / 0	-84.9	-84.9 0.86 (1)	5.09	K-F	0 / 972	0.16 (1)
E-F	-1298 / 0	-84.9	-84.9 0.86 (1)	5.09	I-F	-288 / 0	0.21 (1)
F-G	-857 / 0	-84.9	-84.9 0.13 (1)	6.25	B-L	0 / 652	0.15 (1)
M-B	-1345 / 0	0.0	0.0 0.17 (1)	6.99	I-G	0 / 663	0.15 (1)
H-G	-1233 / 0	0.0	0.0 0.19 (1)	7.23			
M-L	0 / 0	-18.5	-18.5 0.20 (4)	10.00			
L-K	0 / 559	-18.5	-18.5 0.36 (4)	10.00			
K-J	0 / 505	-18.5	-18.5 0.36 (4)	10.00			
J-I	0 / 505	-18.5	-18.5 0.36 (4)	10.00			
I-H	0 / 0	-18.5	-18.5 0.21 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")

CSI: TC=0.86/1.00 (D-F:1), BC=0.36/1.00 (K-L:4), WB=0.67/1.00 (D-K:1), SSI=0.36/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES		PLATE GRIP(DRY) SHEAR (PSI)	SECTION (PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1687 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (K) (INPUT = 0.90)
JSI METAL = 0.37 (J) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





TOTAL WEIGHT = 2 X 77 = 154 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	1650F 1.6E	SPF
C - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
K - B	2x4	DRY	No.2	SPF
H - F	2x6	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTW+p	MT20	3.0	5.0	2.00	Edge
D	TS-t	MT20	3.0	5.0		
E	TMVW-t	MT20	3.0	5.0	1.50	1.50
F	TMVW-t	MT20	4.0	9.0	2.00	3.00
H	BVM1+H	MT20	3.0	6.0	Edge	
I	BBWW-I	MT20	5.0	6.0	3.00	3.00
J	BMVWV-t	MT20	4.0	6.0		
K	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	DOWN	IN-SX	IN-SX
K	830	830	5-8	1-8
H	830	830	5-8 (5-6)	5-8

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): H

UNFACTORED REACTIONS

JT	1ST LCASE	MAX	MIN	COMPONENT REACTIONS
K	COMBINED	SNOW	LIVE	PERM.LIVE WIND DEAD SOIL
K	587	386 / 0	0 / 0	0 / 0 0 / 0 201 / 0 0 / 0
H	587	386 / 0	0 / 0	0 / 0 0 / 0 201 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.71 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX	LC1	
FR-TO		FROM TO	CSI (LC)		FR-TO			CSI (LC)	
A-B	0 / 48	-84.9 -84.9	0.10 (1)	10.00	J-C	0 / 259		0.06 (4)	
B-C	-425 / 0	-84.9 -84.9	0.30 (1)	6.25	J-E	-497 / 0		0.29 (1)	
C-D	-456 / 0	-84.9 -84.9	0.28 (1)	6.25	I-E	0 / 388		0.09 (1)	
D-E	-456 / 0	-84.9 -84.9	0.28 (1)	6.25	B-J	0 / 270		0.06 (1)	
E-F	-1132 / 0	-84.9 -84.9	0.23 (1)	5.71	I-F	0 / 781		0.18 (1)	
F-G	0 / 48	-84.9 -84.9	0.12 (1)	10.00					
K-B	-789 / 0	0.0 0.0	0.10 (1)	7.81					
H-F	-804 / 0	0.0 0.0	0.08 (1)	7.81					
K-J	0 / 0	-18.5 -18.5	0.16 (4)	10.00					
J-I	0 / 697	-18.5 -18.5	0.22 (4)	10.00					
I-H	0 / 0	-18.5 -18.5	0.04 (4)	10.00					

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BC3C 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.46")

CALCULATED VERT. DEFL.(LL) = L/999 (0.02")

ALLOWABLE DEFL.(TL) = L/360 (0.46")

CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.30/1.00 (B-C:1), BC=0.22/1.00 (I-J:4), WB=0.29/1.00 (E-J:1), SSI=0.12/1.00 (C-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	618	354	1667
	788	1987	1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.81 (D) (INPUT = 0.90)

JSI METAL= 0.31 (I) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2




Alpa Roof Truss, Maple

Version 6.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:54 2019 Page 1

ID:MF8ilriaTok7DlbpT4B71Xys4PG-aXj0B4VAOsEg101oQrtcz_JZdGgUDLLWx4?E8yKEKN

-1-3-8-0-0 1-8-4 3-8-4 5-8-4 7-8-4 9-8-4 10-11-6 11-8-4 13-9-0 15-0-8
1-3-8 1-8-4, 2-0-0, 2-0-0, 2-0-0, 2-0-0, 2-0-0 1-3-2 8-14 2-0-12 1-3-8

Scale = 1:90.9



TOTAL WEIGHT = 93 lb

[M]F

LUMBER					
N. L. G. A. RULES					
CHORDS	SIZE	DRY	LUMBER	DESCR.	
A - C	2x4	DRY	1650F 1.6E	SPF	
C - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
K - B	2x4	DRY	No.2	SPF	
H - F	2x6	DRY	No.2	SPF	
K - I	2x4	DRY	No.2	SPF	
I - H	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	
ALL GABLE WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					
GABLE STUDS SPACED AT 2-0-0 OC.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTW+p	MT20	3.0	5.0	2.00	Edge
D	TS-t	MT20	3.0	5.0		
E	TMVW-t	MT20	3.0	5.0	1.50	1.50
F	TMVW-t	MT20	4.0	9.0	2.00	3.00
H	BVM1+H	MT20	3.0	6.0	Edge	
I	BBVW-t	MT20	5.0	6.0	3.00	3.00
J	BMVWVW-t	MT20	4.0	6.0		
K	BMV1+p	MT20	2.0	4.0		
L, M, N, O, P, Q, R, S, T, U, V, W						
L	NP+w	MT20	2.0	4.0		
N	NP-p	MT20	2.0	4.0	1.00	1.75
U	NP-p	MT20	2.0	4.0	0.75	2.00

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS					
		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT		VERT	HORZ	UPLIFT	IN-SX
K		830	0	0	4-11-8
H		830	0	0	5-8 (5-7)

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): H

UNFACTORED REACTIONS

JT	1ST LCASE	MAX / MIN. COMPONENT REACTIONS					
		COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD
K		587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0
H		587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.71 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-B	0 / 48	-84.9 -84.9	0.10 (1)	J-C	0 / 258	0.06 (4)	
B-C	-425 / 0	-84.9 -84.9	0.30 (1)	J-E	-497 / 0	0.29 (1)	
C-D	-456 / 0	-84.9 -84.9	0.28 (1)	I-E	0 / 389	0.09 (1)	
D-E	-456 / 0	-84.9 -84.9	0.28 (1)	B-J	0 / 270	0.06 (1)	
E-F	-1132 / 0	-84.9 -84.9	0.23 (1)	I-F	0 / 781	0.18 (1)	
F-G	0 / 48	-84.9 -84.9	0.12 (1)				
K-B	-789 / 0	0.0 0.0	0.10 (1)				
H-F	-804 / 0	0.0 0.0	0.08 (1)				

K-J	0 / 0	-18.5 -18.5	0.16 (4)	10.00
J-I	0 / 697	-18.5 -18.5	0.22 (4)	10.00
I-H	0 / 0	-18.5 -18.5	0.04 (4)	10.00

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2018
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.46")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.46")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.30/1.00 (B-C:1), BC=0.22/1.00 (I-J:4), WB=0.29/1.00 (E-J:1), SSI=0.12/1.00 (C-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	354	1667

PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.81 (D) (INPUT = 0.90)
JSI METAL= 0.31 (I) (INPUT = 1.00)




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H12		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:56 2019 Page 1

ID:MF8iiriaTok7DlbpT4B71Xys4PG-WwrmcmWRvTVOHKBBYGv43P4f3Qy8y8OezFZ6J1yKEKL



TOTAL WEIGHT = 3 X 66 = 198 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4 DRY	1650F 1.5E	SPF		
C - D	2x4 DRY	2100F 1.8E	SPF		
D - E	2x4 DRY	No.2	SPF		
F - E	2x4 DRY	No.2	SPF		
I - B	2x4 DRY	No.2	SPF		
I - F	2x4 DRY	No.2	SPF		

ALL WEBS 2x3 DRY No.2 SPF EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTW+p	MT20	3.0	5.0	2.00	Edge
D	TTWW+m	MT20	4.0	6.0	2.75	2.00
E	TMVW-4	MT20	4.0	4.0		
F	BMV1+p	MT20	2.0	4.0		
G	BMVW+t	MT20	3.0	5.0	2.00	1.50
H	BMVWW-t	MT20	4.0	6.0		
I	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQ'D
	VERT	HORZ	DOWN	HORZ
JT	689	0	689	0
F	809	0	809	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	489	310 / 0	0 / 0	0 / 0	0 / 0	179 / 0	0 / 0
I	572	376 / 0	0 / 0	0 / 0	0 / 0	196 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 48	-84.9 -84.9	0.10 (1)	H-C	0 / 157	0.05 (4)	
B-C	-405 / 0	-84.9 -84.9	0.30 (1)	H-D	-373 / 0	0.25 (1)	
C-D	-403 / 0	-84.9 -84.9	0.24 (1)	G-D	-549 / 0	0.08 (1)	
D-E	-568 / 0	-84.9 -84.9	0.04 (1)	G-E	0 / 841	0.19 (1)	
F-E	-683 / 0	0.0 0.0	0.08 (1)	B-H	0 / 257	0.06 (1)	
I-B	-768 / 0	0.0 0.0	0.10 (1)				
I-H	0 / 0	-18.5 -18.5	0.16 (4)				
H-G	0 / 599	-18.5 -18.5	0.22 (4)				
G-F	0 / 0	-18.5 -18.5	0.07 (4)				

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN./C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019

- CSA 086-09, CSA 086-14

- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.I. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.44")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.44")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.04")

CSI: TC=0.30/1.00 (B-C:1) , BC=0.22/1.00 (G-H:4) , WB=0.25/1.00 (D-H:1) , SSI=0.12/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)	(PL)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (E) (INPUT = 0.90)
JSI METAL= 0.35 (G) (INPUT = 1.00)


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H13TG		1	TRUSS DESC.	JT-39002

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:04:58 2019 Page 1
ID:MF8ilriaTok7DlbpT4B71Xys4PG-SJzX1RYhR516WdLafgxY8q92IEg3Q5AxRZ2DNvyKEKJ

-1-3-8 0-0 2-5-8 2-9-10 4-5-8 6-1-6 6-5-8 8-11-0 10-2-8
1-3-8 2-5-8 4-2 1-7-14 1-7-14 4-2 2-5-8 1-3-8

Scale: 3/16"=1'



LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
K - B	2x6	DRY	No.2	SPF
H - F	2x6	DRY	No.2	SPF
K - J	2x4	DRY	No.2	SPF
J - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				
GABLE STUDS SPACED AT 2-0-0 OC.				

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMWV-I	MT20	4.0	9.0	2.00 3.00
C TMWV-w	MT20	2.0	4.0	
D TTWV+p	MT20	4.0	6.0	
D NP+I	MT20	3.0	4.0	2.00 0.25
E TMWV-w	MT20	2.0	4.0	
F TMWV-I	MT20	4.0	9.0	2.00 3.00
H BVM1-I	MT20	3.0	6.0	Edge
I BBWVW1-m	MT20	5.0	6.0	2.50 2.00
I, J, L, M, N				
I NP+w	MT20	2.0	4.0	
J BBWVW1-m	MT20	5.0	6.0	2.50 2.00
K BVM1-I	MT20	3.0	6.0	Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
K	243	0	243	0	0
J	337	0	337	0	0
I	337	0	337	0	0
H	243	0	243	0	0

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	WIND	DEAD	SOIL
K	171	119 / 0	0 / 0	51 / 0	0 / 0
J	239	154 / 0	0 / 0	85 / 0	0 / 0
I	239	154 / 0	0 / 0	85 / 0	0 / 0
H	171	119 / 0	0 / 0	51 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, J, I, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 / 48	D-I	-36 / 0
B-C	0 / 15	E-J	-246 / 0
C-D	-30 / 0	J-K	-36 / 0
D-E	-30 / 0	K-L	-246 / 0
E-F	0 / 15	L-M	0 / 2
F-G	0 / 48	M-N	0 / 2
G-H	-217 / 0		
H-I	-217 / 0		
I-J	0 / 0		
J-K	0 / 12		
K-L	0 / 0		

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.12/1.00 (A-B:1), BC=0.06/1.00 (I-J:4), WB=0.04/1.00 (E-I:1), SSI=0.07/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.22 (E) (INPUT = 0.90)
JSI METAL= 0.12 (C) (INPUT = 1.00)




JSI GRIP= 0.79 (D) (INPUT = 0.90)
JSI METAL= 0.38 (D) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
313999	H14T		1	TRUSS DESC.	JT-39002 E-19112596

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 15:05:01 2019 Page 1
ID:MF8ilriaTok7DlbpT4B71Xys4PG-Ph5HS7axzi?qlxVyn5_0DFEN72LfuyJDutXJSnyKEKH



TOTAL WEIGHT = 2 X 83 = 166 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
L - K	2x4	DRY	No.2	SPF
K - J	2x4	DRY	No.2	SPF
J - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TMVW-I	MT20	3.0	5.0	1.50	1.50
D	TTW+p	MT20	3.0	5.0	2.00	Edge
E	TMVW-I	MT20	3.0	5.0	1.50	1.50
F	TMVW+p	MT20	4.0	6.0	2.00	2.00
H	BMV1+p	MT20	2.0	4.0		
I	BBVW-I	MT20	4.0	6.0	2.00	4.00
J	BBVW-I	MT20	5.0	6.0	2.75	3.00
K	BBVW-I	MT20	4.0	6.0	2.00	4.00
L	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG DOWN	REQD BRG IN-SX
JT	VERT	HORZ	DOWN	HORZ
L	830	0	830	0
H	830	0	830	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0
H	587	386 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	UNBRACED LENGTH	FR-TO	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
A-B	0 / 48	-84.9	-84.9	0.12 (1)	10.00	J-D	0 / 490	0.11 (1)		
B-C	-472 / 0	-84.9	-84.9	0.14 (1)	6.25	J-E	-13 / 0	0.01 (1)		
C-D	-507 / 0	-84.9	-84.9	0.17 (1)	6.25	I-E	-341 / 0	0.19 (1)		
D-E	-507 / 0	-84.9	-84.9	0.17 (1)	6.25	C-J	-13 / 0	0.01 (1)		
E-F	-472 / 0	-84.9	-84.9	0.14 (1)	6.25	K-C	-341 / 0	0.18 (1)		
F-G	0 / 48	-84.9	-84.9	0.12 (1)	10.00	B-K	0 / 367	0.08 (1)		
L-B	-803 / 0	0.0	0.0	0.10 (1)	7.81	I-F	0 / 367	0.08 (1)		
H-F	-803 / 0	0.0	0.0	0.10 (1)	7.81					
L-K	0 / 0	-18.5	-18.5	0.05 (4)	10.00					
K-J	0 / 360	-18.5	-18.5	0.12 (4)	10.00					
J-I	0 / 360	-18.5	-18.5	0.12 (4)	10.00					
I-H	0 / 0	-18.5	-18.5	0.05 (4)	10.00					

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.46")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.46")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.03")

CSI: TC=0.17/1.00 (D-E:1), BC=0.12/1.00 (I-J:4), WB=0.19/1.00 (E-I:1), SS=0.10/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 L.S BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.75 (D) (INPUT = 0.90)
JSI METAL= 0.21 (F) (INPUT = 1.00)

Alpa Roof Truss, Maple


Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:05:02 2019 Page 1

ID:MF8ilriaTok7DlbpT4B71Xys4PG-L4C1tpbCVJFY?F8LuW0UlgKHr1YMtjWMB0QWhyKEKF

-1-3-8 0-0-10-8 2-11-0 4-10-8 6-10-8 8-10-8 10-10-0 12-10-8 13-9-0 15-0-8
1-3-8 10-8 2-0-8 1-11-8 2-0-0 2-0-0 1-11-8 2-0-8 10-8 1-3-8

3x5 //

Scale = 1:78.9



TOTAL WEIGHT = 98 lb

LUMBER					
N. L. G. A. RULES					
CHORDS	SIZE		LUMBER		DESCR.
A - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
L - B	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	
L - K	2x4	DRY	No.2	SPF	
K - J	2x4	DRY	No.2	SPF	
J - I	2x4	DRY	No.2	SPF	
I - H	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	
ALL GABLE WEBS	2x3	DRY	No.2	SPF	
GABLE STUDS SPACED AT 2-0-0 OC.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TMVW-t	MT20	3.0	5.0	1.50	1.50
D	TTW+p	MT20	3.0	5.0	2.00	Edge
E	TMVW-t	MT20	3.0	5.0	1.50	1.50
F	TMVW+p	MT20	4.0	6.0	2.00	2.00
H	BMV1+p	MT20	2.0	4.0		
I	BSWW1-i	MT20	4.0	6.0	2.00	4.00
J	BSWW1-p	MT20	4.0	6.0		
K	BSWW1-i	MT20	4.0	6.0	2.00	4.00
L	BMV1+p	MT20	2.0	4.0		
M	NP+w	MT20	2.0	4.0	1.00	1.00
N, O, P, Q, R, S, T, U, V, W, X						
M	NP+w	MT20	2.0	4.0		
P	NP+w	MT20	2.0	4.0	1.25	1.00
U	NP+w	MT20	2.0	4.0	1.00	1.00
X	NP+w	MT20	2.0	4.0	1.25	1.00

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
L	379	0	379	0	13-9-0 (6-10-8)5-4	
K	195	0	195	0	13-9-0 (6-10-8)5-4	
J	512	0	512	0	13-9-0 (6-10-8)5-4	
I	195	0	195	0	13-9-0 (6-10-8)5-4	
H	379	0	379	0	13-9-0 (6-10-8)5-4	

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): J

UNFACTORED REACTIONS

	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	265	193 / 0	0 / 0	0 / 0	0 / 0	71 / 0	0 / 0
K	141	72 / 0	0 / 0	0 / 0	0 / 0	69 / 0	0 / 0
J	361	241 / 0	0 / 0	0 / 0	0 / 0	121 / 0	0 / 0
I	141	72 / 0	0 / 0	0 / 0	0 / 0	69 / 0	0 / 0
H	265	193 / 0	0 / 0	0 / 0	0 / 0	71 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, K, J, I, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF D-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 48	-84.9 -84.9	0.12 (1)	10.00	J-D	-241 / 0	0.12 (1)
B-C	-96 / 0	-84.9 -84.9	0.19 (1)	6.25	J-E	-79 / 0	0.03 (1)
C-D	-50 / 0	-84.9 -84.9	0.19 (1)	6.25	I-E	-237 / 0	0.14 (1)
D-E	-50 / 0	-84.9 -84.9	0.19 (1)	6.25	C-J	-79 / 0	0.03 (1)
E-F	-96 / 0	-84.9 -84.9	0.19 (1)	6.25	K-C	-237 / 0	0.14 (1)
F-G	0 / 48	-84.9 -84.9	0.12 (1)	10.00	B-K	0 / 98	0.02 (1)
L-B	-352 / 0	0.0 0.0	0.04 (1)	7.81	I-F	0 / 98	0.02 (1)
H-F	-352 / 0	0.0 0.0	0.04 (1)	7.81			
L-K	0 / 0	-18.5 -18.5	0.05 (4)	10.00			
K-J	0 / 93	-18.5 -18.5	0.09 (4)	10.00			
J-I	0 / 93	-18.5 -18.5	0.09 (4)	10.00			
I-H	0 / 0	-18.5 -18.5	0.05 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.19/1.00 (B-C:1), BC=0.09/1.00 (I-J:4), WB=0.14/1.00 (E-I:1), SS=0.10/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1666

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.37 (J) (INPUT = 0.90)
JSI METAL = 0.17 (J) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:05:06 2019 Page 1
ID:MF8iiriaTok7DlbpT4B71Xys4PG-lfuAVrd4oEd7siNwafaBwlyFg339ZD9y29F477yKEKC



LUMBER				N. L. G. A. RULES	
CHORDS	SIZE	LUMBER	DESCR.	SPF	BEARINGS
AU - B	2x4	DRY No.2	SPF		
A - H	2x4	DRY No.2	SPF		
H - K	2x4	DRY No.2	SPF		
K - O	2x4	DRY No.2	SPF		
O - R	2x4	DRY No.2	SPF		
R - Y	2x4	DRY No.2	SPF		
Z - X	2x4	DRY No.2	SPF		
AU - AN	2x4	DRY No.2	SPF		
AN - AG	2x4	DRY No.2	SPF		
AG - Z	2x4	DRY No.2	SPF		
ALL WEBS EXCEPT				SPF	
AI - O	2x4	DRY No.2	SPF		
AJ - N	2x4	DRY No.2	SPF		
AK - M	2x4	DRY No.2	SPF		
AL - L	2x4	DRY No.2	SPF		
AM - J	2x4	DRY No.2	SPF		
AH - P	2x4	DRY No.2	SPF		
ALL GABLE WEBS EXCEPT				SPF	
ST1	2x4	DRY No.2	SPF		
ST2	2x4	DRY No.2	SPF		
ST3	2x4	DRY No.2	SPF		
ST4	2x4	DRY No.2	SPF		
ST5	2x4	DRY No.2	SPF		
ST12	2x4	DRY No.2	SPF		

DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	2.0	4.0		
C, D, E, F, G, I, J, M, N, P, Q, S, T, U, V, W	MT20	2.0	4.0		
C TMW+w	MT20	3.0	6.0		
H TS-t	MT20	3.0	6.0		
K					
K TTW+m	MT20	4.0	6.0	Edge	1.00

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
FOR SECTION K-O, MAX. PURLIN SPACING = 2.00 FT.
FOR OTHER SECTIONS, TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF O-AI, N-AJ, M-AK, L-AL, J-AM, I-AO, P-AH, Q-AF.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)	MAX. CSI (LC)	MAX. UNBRACED LENGTH (FT)
FR-TO				FR-TO			
AU-B	-210 / 0	0.0	0.01 (4)	AI-O	-186 / 0	0.15 (1)	
A-B	0 / 32	-84.9	-84.9 0.11 (1)	AJ-N	-186 / 0	0.15 (1)	
B-C	-11 / 0	-84.9	-84.9 0.04 (1)	AK-M	-186 / 0	0.14 (1)	
C-D	-4 / 0	-84.9	-84.9 0.04 (1)	AL-L	-186 / 0	0.15 (1)	
D-E	-3 / 0	-84.9	-84.9 0.04 (1)	AM-J	-176 / 0	0.11 (1)	
E-F	-2 / 4	-84.9	-84.9 0.04 (1)	AO-I	-165 / 0	0.10 (1)	
F-G	-2 / 6	-84.9	-84.9 0.04 (1)	AP-G	-170 / 0	0.22 (1)	
G-H	-1 / 8	-84.9	-84.9 0.04 (1)	AQ-F	-168 / 0	0.13 (1)	
H-I	-1 / 8	-84.9	-84.9 0.04 (1)	AR-E	-168 / 0	0.08 (1)	
I-J	0 / 12	-84.9	-84.9 0.05 (1)	AS-D	-167 / 0	0.04 (1)	
J-K	-2 / 5	-84.9	-84.9 0.04 (1)	AT-C	-167 / 0	0.03 (1)	
K-L	0 / 15	-92.4	-92.4 0.04 (1)	AH-P	-176 / 0	0.10 (1)	
L-M	0 / 10	-92.4	-92.4 0.04 (1)	AF-Q	-165 / 0	0.09 (1)	
M-AV	0 / 10	-92.4	-92.4 0.04 (1)	AE-S	-170 / 0	0.21 (1)	
AV-N	0 / 10	-92.4	-92.4 0.04 (1)	AD-T	-168 / 0	0.12 (1)	
N-O	0 / 10	-92.4	-92.4 0.04 (1)	AC-U	-166 / 0	0.07 (1)	
O-P	0 / 11	-84.9	-84.9 0.04 (1)	AB-V	-177 / 0	0.04 (1)	
P-Q	0 / 12	-84.9	-84.9 0.04 (1)	AA-W	-121 / 0	0.02 (1)	
Q-R	-1 / 8	-84.9	-84.9 0.04 (1)				
R-S	-1 / 8	-84.9	-84.9 0.04 (1)				
S-T	-2 / 6	-84.9	-84.9 0.04 (1)				
T-U	-2 / 4	-84.9	-84.9 0.04 (1)				
U-V	-3 / 0	-84.9	-84.9 0.04 (1)				
V-W	-3 / 0	-84.9	-84.9 0.04 (1)				
W-X	-26 / 0	-84.9	-84.9 0.09 (1)				
X-Y	0 / 32	-84.9	-84.9 0.11 (1)				
Z-X	-227 / 0	0.0	0.0 0.03 (1)				
AU-AT	0 / 9	-18.5	-18.5 0.02 (4)				
AT-AS	0 / 3	-18.5	-18.5 0.02 (4)				
AS-AR	0 / 2	-18.5	-18.5 0.02 (4)				
AR-AQ	-3 / 2	-18.5	-18.5 0.02 (4)				
AQ-AP	-5 / 1	-18.5	-18.5 0.01 (4)				
AP-AO	-7 / 1	-18.5	-18.5 0.01 (4)				
AO-AN	-8 / 0	-18.5	-18.5 0.01 (4)				
AN-AM	-8 / 0	-18.5	-18.5 0.01 (4)				
AM-AL	-10 / 0	-18.5	-18.5 0.01 (4)				
AL-AK	-10 / 0	-18.5	-18.5 0.01 (4)				
AK-AJ	-10 / 0	-18.5	-18.5 0.01 (4)				
AJ-AI	-10 / 0	-18.5	-18.5 0.01 (4)				
AI-AH	-10 / 0	-18.5	-18.5 0.01 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON PIGGYBACK TRUSS WITH SLOPES OF 6.00/12 AND -6.00/12 AND RESPECTIVE WALL HEIGHTS OF 0-0 AND 0-0 AND AN ADDITIONAL DEAD LOAD OF 3.0 P.S.F.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.11/1.00 (A-B:1), BC=0.03/1.00 (Z-AA:1), WB=0.22/1.00 (G-AP:1), SSI=0.08/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.56 (K) (INPUT = 0.90)
JSI METAL= 0.12 (K) (INPUT = 1.00)

JOB NAME 313999	TRUSS NAME H16P	QUANTITY 1	PLY 1	JOB DESC. TRUSS DESC.	JT-39002	DRWG NO. E-19112599
---------------------------	---------------------------	----------------------	-----------------	---------------------------------	-----------------	-------------------------------

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 15:05:08 2019 Page 1
ID:MF8iiriaTok7DlbpT4B71Xys4PG-DrSYIAeiZyUsy67M5QTWUROSPJljb6Gp_efSyKEKB



TOTAL WEIGHT = 2 X 15 = 30 lb

LUMBER					
N. L. G. A. RULES					
CHORDS	SIZE	LUMBER	DESCR.	SPF	
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
B - D	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
ALL GABLE WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					
GABLE STUDS SPACED AT 2-0-0 OC.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB1-I	MT20	3.0	4.0	
C	TTW+p	MT20	3.0	4.0	2.25 1.50
D	TMB1-I	MT20	3.0	4.0	
F	BMW1+w	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): F

PROVIDE ANCHORAGE AT BEARING JOINT A FOR 150 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT E FOR 150 LBS FACTORED UPLIFT
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S).

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 (LC)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LC1 (LC)	MAX. UNBRACED LENGTH (FT)	
FR-TO		FROM TO			FR-TO				
A-B	0 / 27	-103.4 -103.4	0.05 (1)	10.00	F-C	-108 / 0	0.02 (1)		
B-H	-71 / 0	-84.9 -84.9	0.05 (1)	6.25	G-H	-66 / 10	0.00 (1)		
H-C	-48 / 0	-84.9 -84.9	0.05 (1)	6.25	I-J	-66 / 10	0.00 (1)		
C-J	-48 / 0	-84.9 -84.9	0.05 (1)	6.25					
J-D	-71 / 0	-84.9 -84.9	0.05 (1)	6.25					
D-E	0 / 27	-103.4 -103.4	0.05 (1)	10.00					
B-G	0 / 35	-18.5 -18.5	0.03 (1)	10.00					
G-F	0 / 35	-18.5 -18.5	0.04 (1)	10.00					
F-I	0 / 35	-18.5 -18.5	0.04 (1)	10.00					
I-D	0 / 35	-18.5 -18.5	0.03 (1)	10.00					

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019

- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.06/1.00 (A-B:1), BC=0.04/1.00 (F-I:1), WB=0.02/1.00 (C-F:1), SSI=0.06/1.00 (C-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.18 (D) (INPUT = 0.80)
JSI METAL= 0.04 (D) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JOB NAME 314238	TRUSS NAME H1T	QUANTITY 2	PLY 2	JOB DESC. JT-39002	DRWG NO. E-19112600
---------------------------	--------------------------	----------------------	-----------------	------------------------------	-------------------------------

Alpa Roof Truss, Maple Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 16:17:19 2019 Page 1
ID:MF8IriaTok7DlbpT4B71Xys4PG-sRmc6n4e7sgApliTskXaFsn069D1E4ueR6QEoyKDGU



TOTAL WEIGHT = 4 X 134 = 535 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - G	2x4	DRY	No.2	SPF	
G - J	2x4	DRY	No.2	SPF	
K - J	2x4	DRY	No.2	SPF	
R - B	2x6	DRY	No.2	SPF	
R - O	2x6	DRY	No.2	SPF	
O - N	2x6	DRY	No.2	SPF	
N - M	2x6	DRY	No.2	SPF	
M - L	2x6	DRY	No.2	SPF	
L - K	2x6	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	SIDE(61.0)
C - G	12	SIDE(41.1)
G - J	12	SIDE(41.1)
J - K	12	TOP
R - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
R - O	12	SIDE(10.0)
O - N	12	SIDE(7.1)
N - M	12	SIDE(50.1)
M - L	12	SIDE(7.1)
L - K	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
K	2438	0	2438	0	1-8	1-8
R	2496	0	2496	0	5-8	1-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
K	1730	1100 / 0	0 / 0	0 / 0	0 / 0	630 / 0	0 / 0
R	1771	1132 / 0	0 / 0	0 / 0	0 / 0	638 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, R

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.04 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS						WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)		
FR-TO		FROM	TO			FR-TO				
A-B	0 / 48	-84.9	-84.9	0.07 (1)	10.00	Q-C	-663 / 0	0.13 (1)		
B-C	-1780 / 0	-84.9	-84.9	0.05 (1)	6.25	C-P	0 / 2123	0.26 (1)		
C-D	-2516 / 0	-167.1	-167.1	0.35 (1)	5.27	P-D	-1400 / 0	0.28 (1)		
D-E	-3000 / 0	-167.1	-167.1	0.36 (1)	4.90	D-O	0 / 697	0.09 (1)		
E-F	-4942 / 0	-167.1	-167.1	0.19 (1)	4.19	O-E	-3288 / 0	0.87 (1)		
F-G	-4957 / 0	-84.9	-84.9	0.40 (1)	4.04	E-N	0 / 3422	0.42 (1)		
G-H	-4957 / 0	-84.9	-84.9	0.40 (1)	4.04	N-F	-420 / 0	0.04 (1)		
H-I	-2679 / 0	-167.1	-167.1	0.24 (1)	5.29	M-H	0 / 2435	0.30 (1)		
I-J	-733 / 0	-167.1	-167.1	0.10 (1)	6.25	M-H	-1665 / 0	0.17 (1)		
J-K	-2408 / 0	0.0	0.0	0.56 (1)	7.26	M-I	0 / 3411	0.42 (1)		
R-B	-2497 / 0	0.0	0.0	0.11 (1)	7.81	L-I	-2810 / 0	0.57 (1)		
						L-J	0 / 2321	0.29 (1)		
R-Q	0 / 0	-36.4	-36.4	0.04 (1)	10.00	B-Q	0 / 1357	0.17 (1)		
Q-P	0 / 1043	-36.4	-36.4	0.10 (1)	10.00					
P-O	0 / 2517	-36.4	-36.4	0.20 (1)	10.00					
O-N	0 / 4144	-36.4	-36.4	0.28 (1)	10.00					
N-M	0 / 2738	-118.6	-118.6	0.41 (1)	10.00					
M-L	0 / 952	-36.4	-36.4	0.07 (1)	10.00					
L-K	0 / 0	-36.4	-36.4	0.01 (4)	10.00					

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-2-12	-138	-138		FRONT	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 2-2-12
RIGHT SETBACK = 0-0
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL. LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 13-8-0 OF SPAN MEASURED FROM THE LEFT.

GIRDER TYPE: CStdGirder
START DISTANCE = 13-8-0
START SPAN CARRIED = 5-10-8
END DISTANCE = 20-2-0
END SPAN CARRIED = 5-10-8
END WALL WIDTH = 0-0
APPLIED TO FRONT SIDE OF BOTTOM CHORD.
- ADDTL. LOADS BASED ON 55 % OF GSL.

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 2-2-12
RIGHT SETBACK = 0-0
END SETBACK = 5-10-8
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL. LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 3-8-9 OF SPAN MEASURED FROM THE RIGHT.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.24")

CSI: TC=0.56/1.00 (J-K:1), BC=0.41/1.00 (M-N:1), WB=0.67/1.00 (E-O:1), SSI=0.21/1.00 (C-D:1)

JOB NAME 314238	TRUSS NAME H1T	QUANTITY 2	PLY 2	JOB DESC. JT-39002	DRWG NO. E-19112600(2)
Alpa Roof Truss, Maple				Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 16:17:19 2019 Page 2	
ID:MF8iiriaTok7DlbpT4B71Xys4PG-sRmc6n4e7sgAplltTsKXaFSn069D1E4ueR6QEoyKDGU					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	9.0	2.00	3.00
C	TTWW+m	MT20	6.0	7.0	Edge	1.50
D	TMWW-t	MT20	4.0	4.0		
E	TMWW-t	MT20	4.0	6.0	1.50	2.75
F	TMW+w	MT20	2.0	4.0		
G	TS-t	MT20	3.0	6.0		
H	TMWW-t	MT20	4.0	6.0		
I	TMWW-t	MT20	4.0	6.0	1.50	2.75
J	TMVW+p	MT20	4.0	6.0		
K	BMV1+p	MT20	2.0	4.0		
L	BBWW-l	MT20	6.0	7.0	2.75	4.25
M	BBWW+p	MT20	8.0	12.0	Edge	4.25
N	BBWW+p	MT20	8.0	12.0	Edge	5.50
O	BBWW-h	MT20	7.0	8.0	3.25	4.00
P	BMWW-l	MT20	4.0	4.0	2.00	1.50
Q	BMWW-l	MT20	4.0	4.0		
R	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (I) (INPUT = 0.80)

JSI METAL= 0.36 (L) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2






TOTAL WEIGHT = 2 X 125 = 251 lb

JSI GRIP= 0.89 (H) (INPUT = 0.90)
JSI METAL= 0.36 (B) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
314238	H3T		1	JT-39002	E-19112602

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Mon Nov 11 16:22:31 2019 Page 1
ID:MF8iiriaTok7DlbpT4B71Xys4PG-jTdYbTsMfjzveIzrkOwhD2N4Vug18MhpO_hwBjyKDBc



Scale = 1:54.3

TOTAL WEIGHT = 2 X 138 = 276 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - F	2x4	DRY	No.2	SPF	
F - I	2x4	DRY	No.2	SPF	
J - L	2x4	DRY	No.2	SPF	
P - B	2x4	DRY	No.2	SPF	
P - N	2x4	DRY	No.2	SPF	
N - M	2x4	DRY	No.2	SPF	
M - L	2x4	DRY	No.2	SPF	
L - K	2x4	DRY	No.2	SPF	
K - J	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
C - N	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	6.0	2.00	2.00
C TTVW+m	MT20	6.0	7.0	Edge	1.50
D TMVW-t	MT20	4.0	4.0	1.50	2.00
E TMVW-w	MT20	2.0	4.0		
F TS-t	MT20	3.0	6.0		
G TMVW-t	MT20	4.0	4.0		
H TMVW-t	MT20	4.0	6.0		
I TMVW-t	MT20	4.0	4.0	1.50	1.75
J BMV1+p	MT20	2.0	4.0		
K BBWV-t	MT20	5.0	6.0	2.00	4.50
L BBWV+p	MT20	7.0	8.0	Edge	4.50
M BBWVW+p	MT20	7.0	8.0	3.50	5.00
N BBWV-h	MT20	6.0	7.0	2.00	4.25
O BMVW-t	MT20	4.0	4.0		
P BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
J	1230	0	1230	0
P	1349	0	1349	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED						
J	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
P	956	620 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, P

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.67 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF I-J, D-N, H-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED HORIZ. LOAD (PLF)	MAX. FACTORED UNBRACED LENGTH (FT)	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (PLF)
FR-TO							FR-TO			
A-B		0 / 48	-84.9	-84.9	0.12 (1)	10.00	O-C		-121 / 60	0.15 (1)
B-C		-962 / 0	-84.9	-84.9	0.30 (1)	5.96	C-N		0 / 633	0.10 (1)
C-D		-1015 / 0	-84.9	-84.9	0.67 (1)	5.16	N-D		-1373 / 0	0.55 (1)
D-E		-1291 / 0	-84.9	-84.9	0.60 (1)	4.67	D-M		0 / 846	0.19 (1)
E-F		-1295 / 0	-84.9	-84.9	0.43 (1)	5.15	M-E		-219 / 0	0.12 (1)
F-G		-1295 / 0	-84.9	-84.9	0.43 (1)	5.15	M-G		0 / 756	0.17 (1)
G-H		-710 / 0	-84.9	-84.9	0.36 (1)	6.25	L-G		-1043 / 0	0.58 (1)
H-I		-231 / 0	-84.9	-84.9	0.14 (1)	6.25	L-H		0 / 1424	0.32 (1)
I-J		-1215 / 0	0.0	0.0	0.35 (1)	5.81	K-H		-1265 / 0	0.51 (1)
P-B		-1330 / 0	0.0	0.0	0.17 (1)	7.02	K-I		0 / 1109	0.25 (1)
							B-O		0 / 630	0.14 (1)
P-O		0 / 0	-18.5	-18.5	0.22 (4)	10.00				
O-N		0 / 572	-18.5	-18.5	0.27 (4)	10.00				
N-M		0 / 1409	-18.5	-18.5	0.24 (1)	10.00				
M-L		0 / 729	-18.5	-18.5	0.29 (4)	10.00				
L-K		0 / 302	-18.5	-18.5	0.06 (1)	10.00				
K-J		0 / 0	-18.5	-18.5	0.01 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 23.3	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.08")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.20")

CSI: TC=0.67/1.00 (C-D:1), BC=0.29/1.00 (L-M:4), WB=0.58/1.00 (G-L:1), SSI=0.29/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.88 (I) (INPUT = 0.80)
JSI METAL= 0.37 (B) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
314238	H4T	1		JT-39002	E-19112603

Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MiTek Industries, Inc. Mon Nov 11 16:22:21 2019 Page 1
ID:MF8iiriaTok7DlbpT4B71Xys4PG-0Y0mV2k40fK29ow9lLLpxyPlsGtoqHL5QGOqlyKDBm



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - F	2x4	DRY	No.2	SPF	
F - I	2x4	DRY	No.2	SPF	
J - L	2x4	DRY	No.2	SPF	
P - B	2x4	DRY	No.2	SPF	
P - N	2x4	DRY	No.2	SPF	
N - M	2x4	DRY	No.2	SPF	
M - L	2x4	DRY	No.2	SPF	
L - K	2x4	DRY	No.2	SPF	
K - J	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
C - N	2x4	DRY	No.2	SPF	
L - G	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00	
C	TTWW+m	MT20	6.0	7.0	Edge	1.50	
D	TMVW-t	MT20	4.0	4.0	1.75	2.00	
E	TMVW+w	MT20	2.0	4.0			
F	TS-t	MT20	3.0	6.0			
G	TMVW-t	MT20	4.0	4.0			
H	TMVW+t	MT20	4.0	6.0			
I	TMVW-t	MT20	4.0	4.0	1.50	1.75	
J	BMV1+p	MT20	2.0	4.0			
K	BBVW-t	MT20	5.0	6.0	2.00	4.50	
L	BBVW+p	MT20	6.0	7.0	2.75	3.50	
M	BBVW-w	MT20	7.0	8.0	3.25	5.75	
N	BBVW-h	MT20	6.0	7.0	2.25	4.50	
O	BMVW-t	MT20	4.0	4.0			
P	BMV1+p	MT20	2.0	4.0			

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX		
J	1230	0	1230	0	1-9	1-8		
P	1349	0	1349	0	5-8	2-0		

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
J	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
P	956	620 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, P

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.48 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF I-J, C-O, D-N, H-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED	FORCE (LBS)	FACTORED		MAX. UNBRAC	MEMB.	MAX. FACTORED	MAX CSI (LC)	
			VERT. LOAD (PLF)				FORCE (LBS)		
FR-TO			FROM	TO	LENGTH	FR-TO			
A-B	0 / 48		-84.9	-84.9 0.12 (1)	10.00	O-C	-77 / 72	0.04 (1)	
B-C	-953 / 0		-84.9	-84.9 0.49 (1)	5.73	C-N	0 / 483	0.08 (1)	
C-D	-860 / 0		-84.9	-84.9 0.45 (1)	5.95	N-D	-1161 / 0	0.66 (1)	
D-E	-1046 / 0		-84.9	-84.9 0.43 (1)	5.49	D-M	0 / 726	0.16 (1)	
E-F	-1050 / 0		-84.9	-84.9 0.39 (1)	5.62	M-E	-283 / 0	0.27 (1)	
F-G	-1050 / 0		-84.9	-84.9 0.39 (1)	5.62	M-G	0 / 680	0.15 (1)	
G-H	-572 / 0		-84.9	-84.9 0.35 (1)	6.25	L-G	-1038 / 0	0.70 (1)	
H-I	-199 / 0		-84.9	-84.9 0.15 (1)	6.25	L-H	0 / 1355	0.30 (1)	
J-I	-1215 / 0		0.0	0.0 0.50 (1)	5.81	K-H	-1227 / 0	0.70 (1)	
P-B	-1315 / 0		0.0	0.0 0.17 (1)	7.05	K-I	0 / 1087	0.25 (1)	

P-O	0 / 0	-18.5	-18.5 0.18 (4)	10.00
O-N	0 / 568	-18.5	-18.5 0.24 (4)	10.00
N-M	0 / 1183	-18.5	-18.5 0.20 (1)	10.00
M-L	0 / 593	-18.5	-18.5 0.28 (4)	10.00
L-K	0 / 257	-18.5	-18.5 0.05 (1)	10.00
K-J	0 / 0	-18.5	-18.5 0.01 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.19")

CSI: TC=0.50/1.00 (I-J:1), BC=0.28/1.00 (L-M:4), WB=0.70/1.00 (G-L:1), SS=0.25/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (H) (INPUT = 0.90)
JSI METAL= 0.38 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





TOTAL WEIGHT = 2 X 186 = 372 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
G - J	2x4	DRY	No.2
K - L	2x4	DRY	No.2
Q - B	2x4	DRY	No.2
Q - O	2x4	DRY	No.2
O - N	2x4	DRY	No.2
N - M	2x4	DRY	No.2
M - L	2x4	DRY	No.2
L - K	2x4	DRY	No.2
ALL WEBS EXCEPT	2x4	DRY	No.2
E - N	2x3	DRY	No.2
N - F	2x3	DRY	No.2
M - H	2x3	DRY	No.2
M - I	2x3	DRY	No.2
Q - C	2x3	DRY	No.2
C - P	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	2.0	4.0
C	TMWW-t	MT20	4.0	4.0 1.50 1.00
D	TTWW+m	MT20	8.0	7.0 Edge 1.50
E	TMWW-t	MT20	4.0	4.0 1.75 2.00
F	TMWW-w	MT20	2.0	4.0
G	TS-t	MT20	3.0	6.0
H	TMWW-t	MT20	4.0	4.0
I	TMWW+t	MT20	4.0	6.0
J	TMVV-t	MT20	4.0	4.0 1.50 1.75
K	BMV1+p	MT20	2.0	4.0
L	BBWW-l	MT20	4.0	9.0 2.00 7.50
M	BBWW+p	MT20	6.0	7.0 2.75 3.25
N	BBWWW+p	MT20	7.0	8.0 Edge 4.75
O	BBWW-m	MT20	5.0	6.0 1.75 1.75
P	BMWW-l	MT20	4.0	4.0
Q	BMV1-t	MT20	4.0	4.0

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
K	1230	0	1230	0	1-9	1-8
Q	1349	0	1349	0	5-8	1-8

UNFACTORED REACTIONS						
JT	1ST LCASE	MAX/MIN	COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE
K	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0
Q	956	620 / 0	0 / 0	0 / 0	0 / 0	336 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, Q

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.04 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF J-K, E-O, F-N, H-M, I-L, C-Q.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)
FR-TO					FR-TO		
A-B	0 / 48	-84.9	-84.9 0.12 (1)	10.00	P-D	0 / 120	0.03 (4)
B-C	0 / 23	-84.9	-84.9 0.13 (1)	10.00	O-D	0 / 373	0.06 (1)
C-D	-965 / 0	-84.9	-84.9 0.14 (1)	6.19	O-E	-990 / 0	0.57 (1)
D-E	-730 / 0	-84.9	-84.9 0.30 (1)	6.25	E-N	0 / 657	0.15 (1)
E-F	-881 / 0	-84.9	-84.9 0.28 (1)	6.15	N-F	-352 / 0	0.17 (1)
F-G	-885 / 0	-84.9	-84.9 0.36 (1)	6.04	N-H	0 / 645	0.10 (1)
G-H	-885 / 0	-84.9	-84.9 0.36 (1)	6.04	M-H	-1017 / 0	0.49 (1)
H-I	-480 / 0	-84.9	-84.9 0.32 (1)	6.25	M-I	0 / 1293	0.29 (1)
I-J	-174 / 0	-84.9	-84.9 0.10 (1)	6.25	L-I	-1229 / 0	0.70 (1)
K-J	-1215 / 0	0.0	0.0 0.69 (1)	5.81	L-J	0 / 1119	0.18 (1)
Q-B	-221 / 0	0.0	0.0 0.03 (1)	7.81	Q-C	-1212 / 0	0.39 (1)
Q-P	0 / 548	-18.5	-18.5 0.23 (4)	10.00	C-P	0 / 36	0.01 (4)
P-O	0 / 556	-18.5	-18.5 0.24 (4)	10.00			
O-N	0 / 1014	-18.5	-18.5 0.18 (1)	10.00			
N-M	0 / 492	-18.5	-18.5 0.27 (4)	10.00			
M-L	0 / 222	-18.5	-18.5 0.05 (1)	10.00			
L-K	0 / 0	-18.5	-18.5 0.01 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2015, OBC 2012, ABC 2019
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.18")

CSI: TC=0.69/1.00 (J-K:1), BC=0.27/1.00 (M-N:4), WB=0.70/1.00 (I-L:1), SS=0.21/1.00 (F-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (Q) (INPUT = 0.90)
JSI METAL= 0.45 (C) (INPUT = 1.00)



Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MiTek Industries, Inc. Wed Jul 10 10:24:38 2019 Page 1
ID:MF8ilriaTok7DlbpT4B71Xys4PG-?PM6jlcxWAL?Kwbuel7hpk67VBo4mqNngkWoHtyzW1N
Scale = 1:31.2



TOTAL WEIGHT = $24 \times 16 = 384$ lb

DRY: SEASONED LUMBER.

NOTES- (1)

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX
E	494	0	494	0	0	1-8
C	187	0	187	0	0	1-8
D	43	0	48	0	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	348	235 / 0.	0 / 0	0 / 0	0 / 0	113 / 0	0 / 0
C	129	103 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0
D	34	0 / 0	0 / 0	0 / 0	0 / 0	34 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

LOADING

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO		LENGTH	FR-TO		
E - B	-428 / 0	0.0	0.0 0.16 (4)	7.81			
A - B	0 / 32	-84.9	-84.9 0.11 (1)	10.00			
B - C	-35 / 0	-84.9	-84.9 0.50 (1)	6.25			
E - D	0 / 0	-18.5	-18.5 0.30 (4)	10.00			

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DESIGN CRITERIA

SPECIFIED LOADS:				
TOP	CH.	LL	=	23.3 PSF
		DL	=	6.0 PSF
BOT	CH.	LL	=	0.0 PSF
		DL	=	7.4 PSF
TOTAL LOAD			=	36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

DESIGN ASSUMPTIONS
-OVERHANG NOT TO BE ALTERED OR CUT
OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 932 (0.08")

CSI: TC=0.50/1.00 (B-C:1), BC=0.30/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.20/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL.=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1667	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.28 (B) (INPUT = 0.90)
JSI METAL= 0.22 (B) (INPUT = 1.00)



LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - F	2x4	DRY No.2	SPF
F - H	2x4	DRY No.2	SPF
I - H	2x4	DRY No.2	SPF
O - B	2x4	DRY No.2	SPF
O - K	2x4	DRY No.2	SPF
K - I	2x4	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
 EXCEPT
 DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C 1	12	SIDE(61.0)
C - F 1	12	SIDE(41.1)
F - H 1	12	SIDE(41.1)
H - I 1	12	TOP
O - B 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
O - K 1	12	SIDE(10.0)
K - I 1	12	SIDE(10.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.
 GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.
 TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
I	2426	0	2426	0	1-9	1-8
O	2491	0	2491	0	5-8	1-14

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM.LIVE	WIND			
I	1722	1093 / 0	0 / 0	0 / 0	0 / 0	628 / 0	0 / 0
O	1767	1129 / 0	0 / 0	0 / 0	0 / 0	638 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, O

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.84 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
 TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)
FR-TO		FROM TO			FR-TO		
A-B	0 / 48	-84.9 -84.9	0.07 (1)	10.00	N-C	-699 / 0	0.15 (1)
B-C	-1738 / 0	-84.9 -84.9	0.05 (1)	6.25	C-M	0 / 2180	0.27 (1)
C-D	-2612 / 0	-167.1 -167.1	0.43 (1)	5.08	M-D	-1292 / 0	0.28 (1)
D-E	-2932 / 0	-167.1 -167.1	0.44 (1)	4.84	D-L	0 / 439	0.05 (1)
E-F	-2176 / 0	-167.1 -167.1	0.43 (1)	5.43	L-E	-114 / 94	0.02 (1)
F-G	-2176 / 0	-167.1 -167.1	0.43 (1)	5.43	E-J	-1039 / 0	0.55 (1)
G-H	-2176 / 0	-167.1 -167.1	0.43 (1)	5.43	J-G	-1038 / 0	0.23 (1)
H-I	-2342 / 0	0.0 0.0	0.59 (1)	7.34	J-H	0 / 2936	0.36 (1)
O-B	-2480 / 0	0.0 0.0	0.17 (1)	7.17	B-N	0 / 1348	0.17 (1)
O-N	0 / 0	-36.4 -36.4	0.08 (4)	10.00			
N-M	0 / 1017	-36.4 -36.4	0.16 (4)	10.00			
M-L	0 / 2612	-36.4 -36.4	0.29 (1)	10.00			
L-K	0 / 2932	-36.4 -36.4	0.33 (1)	10.00			
K-J	0 / 2932	-36.4 -36.4	0.33 (1)	10.00			
J-I	0 / 0	-36.4 -36.4	0.14 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-2-12	-138	-138	MAX+	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 23.3 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHlp
 LEFT SETBACK = 2-2-12
 RIGHT SETBACK = 0-0
 END SETBACK = 5-10-8
 END WALL WIDTH = 0-0
 CORNER FRAMING TYPE: CONVENTIONAL
 END JACK TYPE: CONVENTIONAL
 APPLIED TO FRONT SIDE
 - ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018, OBC 2012
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
 ALLOWABLE DEFL.(TL) = L/360 (0.79")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.59/1.00 (H-I:1), BC=0.33/1.00 (J-L:1), WB=0.55/1.00 (E-J:1), SI=0.24/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.84 (M) (INPUT = 0.90)
 JSI METAL= 0.47 (K) (INPUT = 1.00)

PLATES (table is in inches)


JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	2.00	2.00
C	TTWW+m	MT20	6.0	7.0	Edge	1.50
D	TMWW-t	MT20	4.0	4.0		
E	TMWW-t	MT20	4.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMW+w	MT20	2.0	4.0		
H	TMVW-t	MT20	4.0	6.0	1.75	3.00
I	BMV1+p	MT20	2.0	4.0		
J	BMWW-t	MT20	5.0	8.0		
K	BS-t	MT20	3.0	6.0		
L	BMWW-t	MT20	4.0	4.0		
M	BMWW-t	MT20	4.0	4.0	2.00	1.50
N	BMWW-t	MT20	4.0	4.0		
O	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2





TOTAL WEIGHT = 4 X 108 = 434 lb

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
M - B	2x4	DRY	No.2	SPF
M - J	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	6.0	2.00	2.00
C TTWW+m	MT20	6.0	7.0	Edge	1.50
D TMWW-t	MT20	4.0	4.0		
E TS-t	MT20	3.0	6.0		
F TMW+w	MT20	2.0	4.0		
G TMVW-t	MT20	4.0	6.0	2.00	2.75
H BMV1+p	MT20	2.0	4.0		
I BMWWW-t	MT20	6.0	8.0		
J BS-t	MT20	3.0	6.0		
K BMWW-t	MT20	4.0	4.0		
L BMWW-t	MT20	4.0	4.0		
M BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
H	1230	0	1230	0	1-9	1-8
M	1349	0	1349	0	5-8	2-0

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX/MIN. COMPONENT REACTIONS		PERM. LIVE	WIND	DEAD	SOIL
	SNOW	LIVE	SNOW	LIVE				
H	873	554 / 0	0 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0
M	956	620 / 0	0 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.99 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	FACTORED VERT. LOAD LC1 MAX		MAX. UNBRACED LENGTH FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH FR-TO
			FROM	TO				
FR-TO								
A-B	0 / 48	-84.9	-84.9	0.12 (1)	10.00	L-C	-219 / 0	0.16 (1)
B-C	-935 / 0	-84.9	-84.9	0.17 (1)	6.20	C-K	0 / 871	0.20 (1)
C-D	-1191 / 0	-84.9	-84.9	0.61 (1)	4.99	K-D	-471 / 0	0.34 (1)
D-E	-1031 / 0	-84.9	-84.9	0.62 (1)	5.22	D-I	-219 / 0	0.13 (1)
E-F	-1031 / 0	-84.9	-84.9	0.62 (1)	5.22	I-F	-645 / 0	0.47 (1)
F-G	-1031 / 0	-84.9	-84.9	0.63 (1)	5.22	I-G	0 / 1393	0.31 (1)
H-G	-1177 / 0	0.0	0.0	0.24 (1)	5.88	B-L	0 / 646	0.15 (1)
M-B	-1338 / 0	0.0	0.0	0.17 (1)	7.00			
M-L	0 / 0	-18.5	-18.5	0.13 (4)	10.00			
L-K	0 / 554	-18.5	-18.5	0.21 (4)	10.00			
K-J	0 / 1191	-18.5	-18.5	0.32 (4)	10.00			
J-I	0 / 1191	-18.5	-18.5	0.32 (4)	10.00			
I-H	0 / 0	-18.5	-18.5	0.21 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. G/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.63/1.00 (F-G:1), BC=0.32/1.00 (H-K:4), WB=0.47/1.00 (F-I:1), SSI=0.28/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1657 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 Inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.89 (G) (INPUT = 0.90)
JSI METAL= 0.36 (B) (INPUT = 1.00)



Version 8.300 S May 10 2019 MITek Industries, Inc. Wed Jul 10 13:36:41 2019 Page 1
ID:MF8ilriaTok7DlbpT4B71Xys4PG-6E7G8s3wrc70FI?WAlmKisJrBaH79OsO_K1DUyzTDK
2x4 || Scale = 1:51.4




NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



JSI GRIP= 0.88 (I) (INPUT = 0.90)
JSI METAL= 0.37 (B) (INPUT = 1.00)

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MiTek Industries, Inc. Wed Jul 10 13:36:42 2019 Page 1
 ID:MF8ilriaTok7DlbpT4B71Xys4PG-aRhLC4YcwFtsvalk?76twOVNbx_si30ce3blwyztDJ
 Scale = 1:52.7



TOTAL WEIGHT = 4 X 135 = 541 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
M - B	2x4	DRY	No.2	SPF
M - J	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF				
EXCEPT				
C - K	2x4	DRY	No.2	SPF
D - I	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMVW+p	MT20	4.0	6.0	2.00 2.00
C TTWW+m	MT20	6.0	7.0	Edge 1.50
D TMVW-t	MT20	4.0	4.0	
E TS-t	MT20	3.0	6.0	
F TMVW+w	MT20	2.0	4.0	
G TMVW-t	MT20	4.0	4.0	1.75 1.75
H BMV1+p	MT20	2.0	4.0	
I BMVWW-t	MT20	5.0	6.0	2.50 1.50
J BS-t	MT20	3.0	6.0	
K BMVW-t	MT20	4.0	4.0	
L BMVW-t	MT20	4.0	4.0	
M BMV1+p	MT20	2.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
		GROSS REACTION		GROSS REACTION		BRG		BRG	
JT		VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
H	1230	0	1230	0	0	1-9	1-8		
M	1349	0	1349	0	0	5-8	2-0		

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
H	873	554 / 0	0 / 0	0 / 0	0 / 0	319 / 0	0 / 0		
M	956	620 / 0	0 / 0	0 / 0	0 / 0	336 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.74 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, C-L, D-K, D-I, F-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		W E B S		FACTORED	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 48	-84.9 -84.9	0.12 (1)	L-C	-91 / 55	0.05 (1)	
B-C	-949 / 0	-84.9 -84.9	0.49 (1)	C-K	0 / 502	0.08 (1)	
C-D	-848 / 0	-84.9 -84.9	0.46 (1)	K-D	-308 / 0	0.18 (1)	
D-E	-677 / 0	-84.9 -84.9	0.47 (1)	D-I	-307 / 0	0.20 (1)	
E-F	-677 / 0	-84.9 -84.9	0.47 (1)	I-F	-582 / 0	0.33 (1)	
F-G	-677 / 0	-84.9 -84.9	0.48 (1)	I-G	0 / 1179	0.19 (1)	
H-G	-1182 / 0	0.0 0.0	0.48 (1)	B-L	0 / 604	0.14 (1)	
M-B	-1311 / 0	0.0 0.0	0.17 (1)				
M-L	0 / 0	-18.5 -18.5	0.14 (4)				
L-K	0 / 566	-18.5 -18.5	0.19 (4)				
K-J	0 / 849	-18.5 -18.5	0.25 (4)				
J-I	0 / 849	-18.5 -18.5	0.25 (4)				
I-H	0 / 0	-18.5 -18.5	0.18 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
 ALLOWABLE DEFL.(TL)= L/360 (0.79")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.06")

CSI: TC=0.49/1.00 (B-C:1), BC=0.25/1.00 (I-K:4), WB=0.33/1.00 (F-I:1), SI=0.25/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
	MAX	MIN	MAX MIN
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (I) (INPUT = 0.90)
 JSI METAL= 0.38 (B) (INPUT = 1.00)



TOTAL WEIGHT = 4 X 143 = 574 lb [M]

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x6	DRY	No.2	SPF
F - G	2x6	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
K - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
D - I	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	2.0	4.0	
C	TMVW-t	MT20	4.0	4.0	1.50 1.00
D	TTWW+m	MT20	4.0	6.0	3.00 1.00
E	TMVW+w	MT20	2.0	4.0	
F	TS-t	MT20	4.0	6.0	
G	TMVW-t	MT20	4.0	6.0	
H	BMV1+p	MT20	2.0	4.0	
I	BSVWW-t	MT20	5.0	8.0	3.00 4.00
J	BSVWW-t	MT20	4.0	4.0	
K	BMVW1-t	MT20	4.0	4.0	2.00 1.75

NOTES- (1)



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
H	1230	0	1230	0	0	1-9	1-8		
K	1349	0	1349	0	0	5-8	1-8		

UNFACTORED REACTIONS		1ST LCASE		MAX/MIN COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND
H	873	564 / 0	0 / 0	0 / 0	0 / 0
K	956	620 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.18 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I, E-I, G-I, C-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING		TOTAL LOAD CASES: (4)	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)

CHORDS		FACTORED		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	UNBRAC LENGTH	MEMB.
FR-TO					FR-TO
A-B	0 / 48	-84.9	-84.9 0.12 (1)	10.00	C-J
B-C	0 / 23	-84.9	-84.9 0.13 (1)	10.00	J-D
C-D	-962 / 0	-84.9	-84.9 0.14 (1)	6.18	D-I
D-E	-743 / 0	-84.9	-84.9 0.55 (1)	6.25	I-E
E-F	-743 / 0	-84.9	-84.9 0.55 (1)	6.25	I-G
F-G	-743 / 0	-84.9	-84.9 0.55 (1)	6.25	K-C
H-G	-1148 / 0	0.0	0.0 0.63 (1)	5.94	
K-B	-219 / 0	0.0	0.0 0.03 (1)	7.81	

K-J	0 / 553	-18.5	-18.5 0.36 (4)	10.00
J-I	0 / 564	-18.5	-18.5 0.37 (4)	10.00
I-H	0 / 0	-18.5	-18.5 0.43 (4)	10.00

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DESIGN CRITERIA

SPECIFIED LOADS:		
TOP CH.	LL	= 23.3 PSF
	DL	= 6.0 PSF
BOT CH.	LL	= 0.0 PSF
	DL	= 7.4 PSF
TOTAL LOAD = 36.7 PSF		

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)=	L/360 (0.79")
CALCULATED VERT. DEFL.(LL)=	L/ 989 (0.03")
ALLOWABLE DEFL.(TL)=	L/360 (0.79")
CALCULATED VERT. DEFL.(TL)=	L/ 930 (0.31")

CSI: TC=0.63/1.00 (G-H:1), BC=0.43/1.00 (H-I:4), WB=0.71/1.00 (E-I:1), SSI=0.28/1.00 (E-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (K) (INPUT = 0.90)
JSI METAL= 0.45 (C) (INPUT = 1.00)

Alpa Roof Truss, Maple

Version 8.300 S May 10 2019 MITek Industries, Inc. Thu Jul 11 13:23:41 2019 Page 1
 ID:KX9I86OLIWqKxYZIGBJHpsKNA-B7cAvJELCMLX9IT?v0R4SE_2p7Yo2PUNgmigKpyz8JW
 Scale = 1:87.2



TOTAL WEIGHT = 13 X 148 = 1918 lb
 (M/F)

LUMBER				N. L. G. A. RULES	
CHORDS	SIZE	LUMBER	DESCR.		
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	1650F 1.5E	SPF	
F - G	2x4	DRY	1650F 1.5E	SPF	
H - G	2x4	DRY	No.2	SPF	
K - B	2x4	DRY	No.2	SPF	
K - I	2x4	DRY	No.2	SPF	
I - H	2x4	DRY	No.2	SPF	
ALL WEBS	2x4	DRY	No.2	SPF	
EXCEPT					
C - J	2x3	DRY	No.2	SPF	
K - C	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
C	TMVW-t	MT20	4.0	4.0	1.50	1.00
D	TTWW+m	MT20	6.0	7.0	Edge	1.50
E	TMVW+w	MT20	2.0	4.0		
F	TS-t	MT20	3.0	8.0		
G	TMVW-t	MT20	4.0	4.0	1.75	1.75
H	BMV1+p	MT20	2.0	4.0		
I	BSVWVW-t	MT20	5.0	8.0	3.00	3.75
J	BMVW-t	MT20	4.0	4.0		
K	BMVW-t	MT20	4.0	4.0	2.00	1.75

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES: (1)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
JT	1311	0	1311	0	0	1-8	1-8	
H	1393	0	1393	0	0	5-8	1-8	

UNFACTORED REACTIONS

	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	938	554 / 0	0 / 0	0 / 0	0 / 0	384 / 0	0 / 0
H	990	620 / 0	0 / 0	0 / 0	0 / 0	370 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, K

BRACING

FOR SECTION D-G, MAX. PURLIN SPACING = 2.00 FT.
 FOR OTHER SECTIONS, TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.13 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I, E-I, G-I, C-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO	CS1 (LC)	FR-TO		FROM TO	CS1 (LC)
A-B	0 / 48	-84.9 -84.9	0.12 (1)	10.00	C-J	-39 / 30	0.05 (1)
B-C	0 / 29	-84.9 -84.9	0.18 (1)	10.00	J-D	0 / 211	0.04 (4)
C-D	-981 / 0	-84.9 -84.9	0.15 (1)	6.13	D-I	0 / 179	0.03 (1)
D-E	-673 / 0	-92.4 -92.4	0.71 (1)	2.00	I-E	-950 / 0	0.75 (1)
E-F	-674 / 0	-92.4 -92.4	0.72 (1)	2.00	I-G	0 / 1156	0.19 (1)
F-G	-674 / 0	-92.4 -92.4	0.72 (1)	2.00	K-C	-1254 / 0	0.49 (1)
H-G	-1233 / 0	0.0 0.0	0.97 (1)	5.78			
K-B	-234 / 0	0.0 0.0	0.03 (1)	7.81			
K-J	0 / 588	-18.5 -18.5	0.37 (4)	10.00			
J-I	0 / 571	-18.5 -18.5	0.38 (4)	10.00			
I-H	0 / 0	-18.5 -18.5	0.38 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 23.3 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON PIGGYBACK TRUSS WITH SLOPES OF 6.00/12 AND -6.00/12 AND RESPECTIVE WALL HEIGHTS OF 0-0 AND 0-0 AND AN ADDITIONAL DEAD LOAD OF 3.0 P.S.F.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF BCBC 2018, OBC 2012
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
 ALLOWABLE DEFL.(TL) = L/360 (0.79")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.25")

CSI: TC=0.97/1.00 (G-H:1), BC=0.38/1.00 (H-I:4), WB=0.75/1.00 (E-I:1), SSI=0.38/1.00 (E-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)	(PLI)	(PSI)	(PLI)	(PSI)	(PLI)
MT20	618	354	1687	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (I) (INPUT = 0.90)
 JSI METAL= 0.47 (C) (INPUT = 1.00)





TOTAL WEIGHT = 4 X 52 = 207 lb

(M)

LUMBER				N. L. G. A. RULES	
CHORDS	SIZE	LUMBER	DESCR.		
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	
B - G	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0	1.50	2.75
C	TTWW+m	MT20	4.0	6.0	1.75	1.00
D	TMW+w	MT20	2.0	4.0		
E	TMW-I	MT20	3.0	4.0	1.50	1.75
F	BMV1+p	MT20	2.0	4.0		
G	BSWWW1-I	MT20	5.0	6.0	3.00	3.00
H	BMW1+w	MT20	2.0	4.0		

NOTES- (1)

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
F	323	0	323	0	16-2-2 (16-1-2)9-1	
B	-76	0	0	0	16-2-2 (16-1-2)9-1	
H	494	0	494	0	16-2-2 (16-1-2)9-1	
G	953	0	953	0	16-2-2 (16-1-2)9-1	

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

PROVIDE ANCHORAGE AT BEARING JOINT B FOR 192 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS			
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
JT	231	137 / 0	0 / 0	0 / 0	0 / 0	93 / 0
B	-74	64 / 0	0 / 0	0 / 0	0 / 0	0 / -137
H	373	111 / 0	0 / 0	0 / 0	0 / 0	261 / 0
G	672	454 / 0	0 / 0	0 / 0	0 / 0	218 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, B, H, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)		MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	
		FROM	TO			FROM	TO
FR-TO							
A-B	0 / 11	-84.9	-84.9	0.01 (1)	10.00	H-C	-205 / 0
B-C	-74 / 0	-84.9	-84.9	0.00 (1)	6.25	C-G	-11 / 0
C-D	-2 / 0	-84.9	-84.9	0.87 (1)	10.00	G-D	-826 / 0
D-E	-3 / 0	-84.9	-84.9	0.87 (1)	10.00	G-E	0 / 3
F-E	-250 / 0	0.0	0.0	0.03 (1)	7.81		
B-H	0 / 39	-18.5	-18.5	0.29 (4)	10.00		
H-G	0 / 14	-18.5	-18.5	0.29 (4)	10.00		
G-F	0 / 0	-18.5	-18.5	0.33 (4)	10.00		

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, OBC 2012
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.87/1.00 (D-E:1), BC=0.33/1.00 (F-G:4), WB=0.12/1.00 (D-G:1), SSI=0.32/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.78 (C) (INPUT = 0.90)
 JSI METAL= 0.41 (G) (INPUT = 1.00)



JOB NAME 314233	TRUSS NAME J01T	QUANTITY 1	PLY 1	JOB DESC. JT-39002	DRWG NO. E-19112509
---------------------------	---------------------------	----------------------	-----------------	------------------------------	-------------------------------


Alpa Roof Truss, Maple

Version 8.300 S Aug 9 2019 MITek Industries, Inc. Fri Nov 8 12:09:33 2019 Page 1

ID:VRLqmcldiffZCj2mk6F92VyQuye-PedLg6Kg34EyrhyaL6P1sHTzGSwDvwrmGAw1?4yLGAm

-1-3-8 0-0 2-0-0 2-0-0 2-0-0 4-0-0 1-10-8 5-10-8

Scale = 1:33.7



TOTAL WEIGHT = 7 X 30 = 209 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
I - B	2x4	DRY	No.2	SPF
A - E	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-1	MT20	3.0	4.0	1.50	1.00
C TMVW-1	MT20	3.0	4.0	1.50	1.50
D TMVW-1	MT20	3.0	4.0	1.50	1.50
E TMV+p	MT20	2.0	4.0		
F BMVW-1	MT20	3.0	4.0		
G BBVW-1	MT20	5.0	6.0	3.00	3.00
H BBVW-1	MT20	4.0	6.0	2.00	4.50
I BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
	VERT	HORZ	DOWN	UP
JT	434	0	434	0
I	290	0	290	0
F	290	0	290	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD
I	305	208 / 0	0 / 0	0 / 0	97 / 0	0 / 0
F	206	129 / 0	0 / 0	0 / 0	77 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED	FACTORED	MAX	MEMB.	MAX. FACTORED	FACTORED	MAX
	FORCE (LBS)	VERT. LOAD LC1	CSI (LC)		FORCE (LBS)	VERT. LOAD LC1	CSI (LC)
FR-TO		FROM	TO	FR-TO		FROM	TO
I-B	-415 / 0	0.0	0.0	0.04 (1)	7.81	B-H	0 / 173
A-B	0 / 32	-84.9	-84.9	0.11 (1)	10.00	H-C	-188 / 0
B-C	-204 / 0	-84.9	-84.9	0.11 (1)	6.25	C-G	0 / 81
C-D	-264 / 0	-84.9	-84.9	0.05 (1)	6.25	G-D	0 / 172
D-E	-11 / 0	-84.9	-84.9	0.05 (1)	6.25	D-F	-308 / 0
F-E	-56 / 0	0.0	0.0	0.01 (1)	7.81		
I-H	0 / 0	-18.5	-18.5	0.02 (4)	10.00		
H-G	0 / 204	-18.5	-18.5	0.05 (1)	10.00		
G-F	0 / 215	-18.5	-18.5	0.05 (1)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD	= 36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.11/1.00 (A-B:1), BC=0.05/1.00 (F-G:1), WB=0.05/1.00 (D-F:1), SS=0.08/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.56 (B) (INPUT = 0.90)
JSI METAL= 0.12 (B) (INPUT = 1.00)

NOTE: Lateral brace(s) shown shall be 2x4 SPF #2



May 27, 2019

Re: Expiration Date for Technical Bulletins Extended to 12/31/2019

Please be advised that the expiration date of the Technical Bulletins listed below has been extended until December 31, 2019.

T-SPECCP17	T-SPECH17	T-SPECDSHGUS17R
T-SPECHGUS17-R	T-SPECHHUS17-R	T-SPECHUS17
T-SPECLF17	T-SPECLT17	T-SPECLU17
T-SPECCLUL17	T-SPECLUS17	T-SPECSUR17
T-SPECTBE17	T-SPECTC17	T-SPECTHGB17
T-SPECTHGBHV17	T-SPECTHGQ17	T-SPECTHGW17
T-SPECLSULSSU17	T-SPECHTHGQ17	T-SPECSTHGQ17

Should you have any questions or concerns regarding the above, please contact me at your convenience.

Sincerely,



Brent Bunting, P.Eng.
Simpson Strong-Tie Canada, Ltd.



LUS – Double Shear Joist Hangers



All LUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections.

Material: 18 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners.
- Nails: 16d = 0.162" dia. x 3 1/2" long common wire, 10d = 0.148" x 3" long common wire.
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads.
- Not designed for welded or nailer applications.

Options:

- These hangers cannot be modified




Typical LUS Installation




Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _s ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _p =1.15)	Normal (K _p =1.00)	Uplift (K _p =1.15)	Normal (K _p =1.00)
LUS24	18	1 9/16	3 3/8	1 3/4	1 15/16	(4) 10d	(2) 10d	710	1630	645	1155
LUS24-2	18	3 1/8	3 3/8	2	1 13/16	(4) 16d	(2) 16d	835	2020	590	1435
LUS26	18	1 9/16	4 3/4	1 3/4	3 3/8	(4) 10d	(4) 10d	1420	2170	1290	1630
LUS26-2	18	3 1/8	4 7/8	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920
LUS26-3	18	4 5/8	4 3/4	2	3 1/4	(4) 16d	(4) 16d	1720	2595	1545	2340
LUS28	18	1 9/16	6 5/8	1 3/4	3 3/4	(6) 10d	(6) 10d	1420	2520	1290	1790
LUS28-2	18	3 1/8	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575
LUS28-3	18	4 5/8	6 1/4	2	3 1/4	(6) 16d	(4) 16d	1720	3325	1545	2375
LUS210	18	1 9/16	7 13/16	1 3/4	3 7/8	(8) 10d	(4) 10d	1420	2785	1290	2210
LUS210-2	18	3 1/8	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195
LUS210-3	18	4 5/8	8 3/8	2	5 1/4	(8) 16d	(6) 16d	2580	3345	2320	2375

1. d_s is the distance from the seat of the hanger to the highest joist nail.



Dome Double Shear Nailing prevents tabs breaking off (available on some models).
U.S. Patent 5,603,580



Double Shear Nailing Top View.



LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2019, and reflects information available as of March 1, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2017 Simpson Strong-Tie Company Inc.

T-SPECLUS17 3/17 exp. 6/19

(800) 999-5099
strongtie.com

HHUS – Double Shear Joist Hangers

All HHUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: 14 gauge

Finish: G90 galvanized

Design:




- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:

- Use all specified fasteners
- Nails: 16d = 0.162" dia. x 3½" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications



Options:

- See current catalogue for options



Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _b ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K ₀ =1.15)	Normal (K ₀ =1.00)	Uplift (K ₀ =1.15)	Normal (K ₀ =1.00)
HHUS26-2	14	3 5/16	5 1/16	3	3 15/16	(14) 16d	(6) 16d	2850	7335	2065	5205
HHUS28-2	14	3 5/16	7 7/32	3	6 5/32	(22) 16d	(8) 16d	3765	8940	2675	6345
HHUS210-2	14	3 5/16	9 3/32	3	8	(30) 16d	(10) 16d	4745	9660	4310	7000
HHUS210-3	14	4 11/16	9	3	7 15/16	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS210-4	14	6 1/8	8 29/32	3	7 27/32	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS46	14	3 5/8	5 1/32	3	3 15/16	(14) 16d	(6) 16d	2540	7335	2065	5205
HHUS48	14	3 5/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3765	8945	2267	6345
HHUS410	14	3 5/8	9	3	8	(30) 16d	(10) 16d	4745	9855	4310	7000
HHUS5.50/10	14	5 1/2	9	3	8	(30) 16d	(10) 16d	4745	10545	4310	7485
HHUS7.25/10	14	7 1/4	9	3 5/16	7 29/32	(30) 16d	(10) 16d	4745	10770	4310	7650

1. d_b is the distance from the seat of the hanger to the highest joist nail.




LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2019, and reflects information available as of March 1, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2017 Simpson Strong-Tie Company Inc.

T-SPECHHUS17 3/17 exp. 6/19

(800) 999-5099
strongtie.com



Wood Truss Installation

**A Guide to proper handling, erecting and bracing
metal plate connected wood trusses**

Table of Content

	Warning.....	4
1	Unloading & Lifting.....	5
2	Job Site Handling.....	5
3	Hoisting.....	6
4	Beginning the Erection Process.....	7
5	Erection Tolerance.....	8
6	Bracing.....	8
7	Bracing Requirements for 3 Planes of Roof.....	9
8	Stacking Materials.....	10
	Caution Notes.....	11

Warning



General

Familiarity with the Construction Design Documents, the Truss Design Drawings, and Truss Placement Plans (if required by the Construction Design Documents) is required to properly erect, brace, and connect the trusses to the building system.

All of the care and quality involved in the design and manufacture of wood trusses can be jeopardized if the trusses are not properly handled, erected, and braced.

The consequences of improper handling, erecting, and bracing may be a collapse of the structure, which at best is a substantial loss of time and materials, and at worst is a loss of life. The majority of truss accidents occur during truss installation and not as a result of improper design or manufacture.

Prior to truss erection, the builder/erector shall meet with the erection crew for a safety and planning meeting, making sure each crew member understands his or her roles and responsibilities during the erection process.

Temporary Erection Bracing

Trusses are not marked in any way to identify the frequency, or location of temporary erection bracing.

All temporary bracing shall comply with the latest edition of *Commentary and Recommendations for Handling, Installing & Bracing Metal Plate Connected Wood Trusses* (HIB), published by the Truss Plate Institute, and/or as specified in the Construction Design Documents prepared by the building designer.

Permanent Truss Bracing

Permanent bracing for the roof or floor trusses is the responsibility of the building designer and should be shown on the Construction Design Documents. Permanent bracing locations for individual compression members of a wood truss are shown on the Truss Design Drawings, and shall be installed by the building or erection contractor. This bracing is needed for the proper performance of individual trusses within the roof or floor system. The design and connection of the bracing to the truss and then to the overall building system is the responsibility of the building designer, and is in addition to the permanent bracing plan, which is also specified by the building designer.

Special Design Requirements

Special design requirements, such as wind bracing, portal bracing, seismic bracing, diaphragms, shear walls, or other load transfer elements and their connections to wood trusses must be considered separately by the building designer, who shall determine size, location, and method of connections for all bracing as needed to resist these forces.

Unloading & Lifting

Never handle trusses flat



Beginning with the unloading process, and throughout all phases of construction, care must be taken to avoid lateral bending of trusses, which can cause damage to the lumber and metal connector plates at the joints.



Avoid lateral bending

- Use special care in windy weather.
- If using a crane within 10 feet of an electric line, contact the local power company.
- If using a crane within 5 miles of an airport, contact the airport 30 days prior to erection to learn about any safety regulations that must be followed.

Job Site Handling




All trusses should be picked up at the top chords in a vertical position only

Proper banding and smooth ground allow for unloading of trusses without damage. This should be done as close to the building site as possible to minimize handling. Do not break banding until installation begins. Hand erection of trusses is allowed, provided excessive lateral bending is prevented.




Do not store unbraced bundles upright

If trusses are stored vertically they shall be braced in a manner that will prevent tipping or topping. Generally cutting of the banding is done just prior to installation.



Do not store on uneven ground

If trusses are stored horizontally, blocking should be used on eight to ten foot centers, or as required, to minimize lateral bending and moisture gain.



Care should be exercised when removing banding to avoid damaging trusses.


During long term storage, trusses shall be protected from the environment in a manner that provides for adequate ventilation of the trusses. If tarpaulins or other material is used, the ends shall be left open for ventilation. Plastic is not recommended, since it can trap moisture.

3 Hoisting


All trusses that are erected one at a time shall be held safely in position by the erection equipment until such time as all necessary bracing has been installed and the ends of the trusses are securely fastened to the building.




Avoid lateral bending




$L \leq 30'$




Truss sling is acceptable where these criteria are met.




$30' < L \leq 60'$



Use spreader bar in all other cases. It should be noted that the lines from the ends of the spreader bar "TOE IN"; if these lines should "TOE OUT" the truss may fold in half.



$L > 60'$




For lifting trusses with spans in excess of 60 feet, it is recommended that a strongback/spreader bar be used as illustrated. The strongback/spreader bar should be attached to the top chord and web members at intervals of approximately 10 feet. Further, the strongback/spreader bar should be at or above the mid-height of the truss to prevent overturning. The strongback/spreader bar can be of any material with sufficient strength to safely carry the weight of the truss and sufficient rigidity to adequately resist bending of the truss.

4 Beginning the Erection Process


It is important for the builder or erection contractor to provide substantial bracing for the first truss erected. The two or more trusses making up the rest of the first set are tied to and rely upon the first truss for stability. Likewise, after this first set of trusses is adequately cross-braced, the remaining trusses installed rely upon this first set for stability. Thus, the performance of the truss bracing system depends to a great extent on how well the first group of trusses is braced.

Ground Brace – Exterior

One satisfactory method ties the first unit of trusses off to a series of braces that are attached to a stake driven into the ground and securely anchored. The ground brace itself should be supported as shown below or it is apt to buckle. Additional ground braces in the opposite direction, inside the building, are also recommended.





Note: Locate ground braces for first truss directly in line with all rows of top chord continuous lateral bracing (either temporary or permanent).



Ground Brace – Interior

Another satisfactory method where height of building or ground conditions prohibit bracing from the exterior is to tie the first truss rigidly in place from the interior at the floor level, provided the floor is substantially completed and capable of supporting the ground bracing forces. Securely fasten the first truss to the middle of the building. Brace the bracing similar to exterior ground bracing shown at left. Set trusses from the middle toward the end of the building. Properly cross-brace the first set of trusses before removing floor braces and setting remaining trusses.




Inadequate size of bracing material or inadequate fastening is a major cause of erection dominoing.


5 Erection Tolerance

Complying with erection tolerances is critical to achieving an acceptable roof or floor line, and to accomplishing effective bracing. Setting trusses within tolerance the first time will prevent the need for the hazardous practice of respacing or adjusting trusses when roof sheathing or roof purlins are installed. Trusses leaning or bowing can cause nails to miss the top chords when sheathing is applied, and create cumulative stresses on the bracing, which is a frequent cause of dominoing.

When sheathing, make sure nails are driven into the top chord of the trusses.



6 Bracing



Do not install trusses on temporarily connected supports



Do not walk on unbraced trusses



Do not walk on trusses or gable ends lying flat




Nails in withdrawal (parallel to force)

All anchors, hangers, tie-downs, seats, bearing ledgers, etc., that are part of the supporting structure shall be accurately and properly placed and permanently attached before truss installation begins. No trusses shall ever be installed on anchors or ties that have temporary connections to the supporting structure.

Nailing scabs to the end of the building to brace the first truss is not recommended.

All nailing of bracing should be done so that nails are driven perpendicular to the direction of force, as shown at right.




Well nailed (perpendicular to force)

7 Bracing Requirements for 3 Planes of Roof

Temporary erection bracing must be applied to three planes of the roof system to ensure stability: Plane 1) Top Chord (sheathing), Plane 2) Bottom Chord (ceiling plane), and Plane 3) Web Member plane or vertical plane perpendicular to trusses.

1) Top Chord Plane

Most important to the builder or erection contractor is bracing in the plane of the top chord. Truss top chords are susceptible to lateral buckling before they are braced or sheathed.




Exact spacing between trusses should be maintained as bracing is installed to avoid the hazardous practice of removing bracing to adjust spacing. This act of "adjusting spacing" can cause trusses to topple if connections are removed at the wrong time.

3) Web Member Plane

"X" bracing, as shown, is critical in preventing trusses from leaning or dominoing. Repeat as shown to create a succession of rigid units.


X-bracing should be installed on vertical web members wherever possible, at or near lateral bracing. Plywood or OSB may be substituted for X-bracing.



Note: Top chords and some web members are not shown, in order to make drawings more readable.

2) Bottom Chord Plane

In order to hold proper spacing on the bottom chord, temporary bracing is recommended on the top of the bottom chord.




* Long spans, heavy loads or other spacing configurations may require closer spacing between lateral bracing and closer intervals between diagonals. Consult the building designer or HIB and DSB (*Recommended Design Specification for Temporary Bracing of Metal-Plate Connected Wood Trusses*) for details.

Diagonal or cross-bracing is very important!



Do not use short blocks to brace individual trusses without a specific bracing plan detailing their use





Bracing requirements using the same principles apply to parallel chord trusses

8 Stacking Materials

Do not proceed with building completion until all bracing is securely and properly in place


Never stack materials on unbraced or inadequately braced trusses



Platform must be rigidly braced

Proper distribution of construction materials is a must during construction.


Never stack materials near a peak



Acceptable against outside load bearing wall

Acceptable over load bearing wall

Never stack materials on the cantilever of a truss




Always stack materials over two or more trusses.





Single truss

Never overload small groups or single trusses. Position load over as many trusses as possible.



Roofing and mechanical contractors are cautioned to stack materials only along outside supporting members or directly over inside supporting members. Trusses are not designed for dynamic loads (i.e., moving vehicles). Extreme care should be taken when loading and stacking construction materials (rolled roofing, mechanical equipment, etc.) on the roof or floor system.

Never cut any structural member of a truss.



Sleepers

Panel point

Sleepers for mechanical equipment should be located at panel points (joints) or over main supporting members, and only on trusses that have been designed for such loads.

Caution Notes

Errors in building lines and/or dimensions, or errors by others shall be corrected by the contractor or responsible construction trade subcontractor or supplier before erection of trusses begins.

Cutting of nonstructural overhangs is considered a part of normal erection and shall be done by the builder or erection contractor.

Any field modification that involves the cutting, drilling, or relocation of any structural truss member or connector plate shall not be done without the approval of the truss manufacturer or a licensed design professional.

The methods and procedures outlined are intended to ensure that the overall construction techniques employed will put floor and roof trusses safely in place in a completed structure. These recommendations for bracing wood trusses originate from the collective experience of leading technical personnel in the wood truss industry, but must, due to the nature of responsibilities involved, be presented only as a guide for use by a qualified building designer, builder, or erection contractor. Thus, the Wood Truss Council of America expressly disclaims any responsibility for damages arising from the use, application, or reliance on the recommendations and information contained herein.

[Selected text and figures referenced or reproduced from HIB and DSB by permission of the Truss Plate Institute, Madison, WI.]

THE CANADIAN WOOD TRUSS ASSOCIATION



L'ASSOCIATION CANADIENNE DES FABRICANTS DE FERMES DE BOIS

1400 Blair Place, Suite 210, Ottawa, ON K1J 9B8
Tel.: 613-747-5544 Fax: 613-747-6264



**Wood Truss Council
of America**

One WTCA Center
6300 Enterprise Lane, Madison, WI 53719-1140
Tel.: 608-274-4849 Fax: 608-274-3329
wtca@woodtruss.com www.woodtruss.com