

Model #

NE58F9500SS
~~NE58F9500SS~~

Electric Range

user manual

Jan 23, 2020

Per-CAL

REZ-CAL

imagine the possibilities

Thank you for purchasing this Samsung product.

SAMSUNG

82-674

To install the range, refer to the following figure.

~~Amgen~~
~~VI-20115~~
~~Purchased~~



Used to fill gap between the range back and wall. Adds a filler strip to the rear of the range. This kit can only be used when the opening in the countertop is 25" deep.

 If the countertop depth is greater than 25", there will be a gap between the filler kit and the back wall.




BE2-67A

Minimum dimensions

★ IMPORTANT

To eliminate the risk of burns or fire caused by reaching over heated surface units, avoid having cabinet storage space located above the surface units. If you have cabinet storage space over the heating elements, you can reduce the risk by installing a range hood that projects horizontally a minimum of 5 inches beyond the bottom of the cabinets.



* 30" minimum clearance between the top of the cooking surface and the bottom of an unprotected wood or metal cabinet; or 24" minimum when the bottom of the wood or metal cabinet is protected by not less than 1/4" of flame retardant millboard covered with not less than no.28 MSG sheet steel, 0.015" stainless steel, 0.024" aluminum, or 0.020" copper.

** 15" minimum between the countertop and the adjacent cabinet bottom.

02 INSTALLING THE OVEN & PREPARING TO INSTALL THE RANGE

Hood Range

VENMAR CHEF

SPECIFICATION SHEET
VCS500 SERIES


SPECIFICATIONS

MODEL	VCS50030	
VOLTS	120 VAC	
Hz	60	
AMPS	4.8	
CFM (LOW SPEED)	260	
CFM (HIGH SPEED)	500*	
SONES (LOW SPEED)	4	
SONES (HIGH SPEED)	11.5	
DUCTING SIZES	VERTICAL: 6" ROUND OR 3 1/4" x 10"	HORIZONTAL: 3 1/4" x 10"
2 SHIELDED HALOGEN BULBS	120 V, 50 W, GU10 BASE	
WARRANTY	5 YEARS	

*OPTIONAL AIR FLOW REDUCERS:

- (LIMITS THE AIRFLOW OF THE HOOD UNDER 300 CFM)
- ARP6 (WITH 6" ROUND DUCTS)
 - ARP310 (WITH 3 1/4" x 10" DUCTS)

AIR FLOW PERFORMANCE



www.venmar.ca

Venmar Ventilation ULC, 550 Lemire Blvd., Drummondville, Québec, Canada J2G 7W9 - Tel: 1-800-567-3855 Fax: 1-800-567-1715

PROJECT _____

LOCATION _____

MODEL No. _____

QTY. _____


SUBMITTED BY _____

DATE _____

PURCHASER notes REMARKS

→ 30 inch hood range
→ please keep 36" gap between cabinets for hood range.

DIMENSIONS



REQUIREMENTS & STANDARDS

- Complies with CSA C22.2 no. 113 Standard
- Complies with UL 507 requirements
- HVI certified

OPTION

- Non-duct kit model HRKMSS



HVI-2100 CERTIFIED RATINGS comply with new testing technologies and procedures prescribed by the Home Ventilating Institute, for off-the-shelf products, as they are available to consumers. Product performance is rated at 0.1 in. (2.54 mm) static pressure, based on tests conducted in a state-of-the-art test laboratory. Sones are a measure of humanly-perceived loudness, based on laboratory measurements.



RANGE HOOD AIRFLOW HAS BEEN TESTED BY AN INDEPENDANT LABORATORY DESIGNATED BY THE HOME VENTILATING INSTITUTE (HVI). THE MAXIMUM AIRFLOW OF THE BLOWER IS 550 CFM.

RF28R6201SR


28 cu. ft. 3-Door French Door Refrigerator™ with CoolSelect Pantry™

Installation Specifications


1. Measure the height, width and depth of the opening, making sure to include baseboards, molding tile, countertop overhang, etc. Check to be sure there is enough room to open the door (consider walls, islands or other obstacles when measuring).
2. Refer to illustration below to determine dimensions.
3. Allow 2.5" of clearance on hinge side of refrigerator when installing next to a wall where handle may make contact.
4. Allow 1" minimum clearance at rear for proper air circulation and water/electrical connections. Allow a 3/8" minimum clearance at sides and top for ease of installation.
5. Ensure each door and entryway in the home is wide enough for the refrigerator to be moved through easily.

For optimal usage and to be able to open refrigerator doors completely, do not install next to a wall.

Please note: The following dimension and cutout information is for planning purposes only. For complete installation details, consult manual packed with product, or download manual online at samsung.com.



Dimensions



Total Capacity: 28 cu. ft.

Refrigerator: 19.1 cu. ft.

- Premium External Filtered Water and Ice Dispenser
 - Crushed or Cubed Ice
- Ice Max
- CoolSelect Pantry™ with Temperature Control – Deli (41°F), Fresh (38°F) and Chilled (32°F) Options
- Pantry Divider
- 2 Humidity-Controlled Crispers
- 5 Tempered Glass Spill-Proof Shelves:
 - 1 Slide-In
 - 1 Slide-Out
 - 1 Foldable Half
 - 2 Fixed
- 6 Clear Door Bins
 - Right Door: 3 Gallon Bins
 - Left Door: 3 Regular Bins
- Adjustable Shelves for Tall Oversized Items
- High Efficiency Top LED Lighting

Freezer: 8.9 cu. ft.

- EZ-Open Handle™
- 2 Drawer Dividers
- High Efficiency LED Lighting

Accessories

Water Filter: HAF-QIN

Warranty

One (1) Year Parts and Labor on Refrigerator
Five (5) Years Parts and Labor on Sealed Refrigeration System Only*
Ten (10) Years Parts and Five (5) Years Labor on Digital Inverter Compressor

*Compressor, evaporator, condenser, drier and connecting tubing.

Product Dimensions & Weight

Dimensions (WxHxD with hinges, handles and doors):

35 3/4" x 70" x 36"

Dimensions (WxHxD without hinges and door):

35 3/4" x 68 7/8" x 28 7/8"

Dimensions (WxHxD with hinge and door, no handle):

35 3/4" x 70" x 33 1/2"

Weight: 311 lbs

Shipping Dimensions & Weight (WxHxD)

Dimensions: 38 5/8" x 76 5/8" x 36 1/8"

Weight: 320 lbs

Color

Fingerprint Resistant Stainless Steel

Fingerprint Resistant Black Stainless Steel

Fingerprint Resistant Tuscan Stainless Steel

White

Model

RF28R6201SR

UPC Code

887276341330

887276341323

887276341316

887276341347

SAMSUNG

5 on 23, 2020
Richter RE2-67L