It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the City of BRAMPTON.

JOHN G. WILLIAMS LTD., ARCHITECT ARCHITECTURAL CONTROL REVIEW AND APPROVAL

APPROVED BY:

DATE: OCT 28, 2019


This stamp certifies compliance with the applica

Design Guidelines only and bears no further professional responsibility.



(PER UNIT) INTERNAL GARAGE WIDTH: INTERNAL GARAGE LENGTH: GARAGE DOOR WIDTH: 5.53 m 6.10 m NOTE: BUILDER TO VERIFY LOCATION OF ALL HYDRANTS, STREET LIGHTS, TRANSFORMERS AND OTHER SERVICES. IF MIN, DIMENSIONS ARE NOT MAINTAINED BUILDER IS TO RELOCATE AT HIS OWN EXPENSE

BUILDING STATISTICS 43M-2039 R1F-9.0-2452 LOT 127 LOT AREA(m)2 BLDG AREA(m)² N/A LOT COVERAGE(%) N/A No. OF STOREYS MEAN HEIGHT(m) PEAK HEIGHT(m) N/A



NO.	DESCRIPTION	DATE	DWN	CHK
1	ISSUED FOR REVIEW	18-OCT-19	DJH	
2	REVISED PER ENG COMM - FINAL	22-OCT-19	DJH	

MPORIANI FOOTING NOTE:

IT IS THE RESPONSIBILITY OF THE BUILDER TO VERIEY FROM THE

RRCHITECTURAL DRAWINGS BEFORE CONSTRUCTION, WHETHER

ADDITIONAL THICKNESS MAY BE REQUIRED.

LOT GRADING PLANS ASSUME A TBS TO USF DISTANCE OF 0.23, BASED

NO FOOTING THICKNESS UP TO USF DISTANCE OF 0.23, BASED

IF ADDITIONAL FOOTING THICKNESS IS REQUIRED THE USF IS TO BE

OWNERED BY THE FOLLOWING AMOUNTS:

- UP TO 9" FOOTING, LOWER USF BY 0.07

- 10" FOOTING, LOWER USF BY 0.10

- 11" FOOTING, LOWER USF BY 0.13

- 12" FOOTING, LOWER USF BY 0.15

- 13" FOOTING, LOWER USF BY 0.19



WWW.RNDESIGN.COM T:905-738-3177 WWW.THEPLUSGROUP.CA

I, DANIEL HANNINEN DECLARE THAT I HAVE REVIEWED AND TAKEN DESIGN RESPONSIBILITY FOR THE DESIGN WORK ON BEHALF OF RN DESIGN LTD. UNDER DIVISION C, PART-3 SUBSECTION-3.2.4 OF THE BULLIONG CODE. I AM QUALIFIED AND THE FIRM IS REGISTERED IN THE APPROPRIATE CLASSES / CATEGORIES.

QUALIFIED DESIGNER BCIN: 201

FIRM BCIN: 26995 DATE: Oct, 29-2019

SIGNATURE:


GOLD PARK HOMES

MCLAUGHLIN AND MAYFIELD-PH2 BRAMPTON, ON

DRAWING

SITE PLAN

DRAWN BY	SCALE 1:250
PROJECT No.	LOT NUMBER
19037 (13098 Ph.2)	LOT 127



URBANTECH NOTES:

- No final utility location information at this time. Urbantech will not be responsible for future changes to design. Builder should notify purchaser' street hardware and above ground utility furniture may be added or rer from their frontages.
- Builder to lower underside of footings where adjacent to RLCB leads. Exact depth to be determined on site during footing excavation.
- 4) Builder to verify location of all hydrants, street lights, transformers and all other services. If min. dimensions are not maintained as per City standards, builder is to relocate at his own expense.
- conflict prior to footing excavation.
- 6) Final fence design have not been provided at this time. Purchaser to be advised that actual fencing details may not be as shown on this plan.

URBANTECH CONSULTING

We certify that the proposed grades at the lot comers are correct, and that the lot grading of the subject lot is in conformity to the approved subdivision grading plans and City standards

reviewed by: <u>m.w.</u> date:<u>Oct 2</u>5/19

