

RIMBOARD
1- 1/8" X 11 7/8" O.S.B.
SUBFLOOR - 3/4" NAILED & GLUED
APP - AS PER PLAN
BBO - BEAM BY OTHERS

Blocking panels are required over all interior supports. Squash blocks are required under concentrated loads.

Ceramic Tile Application as per O.B.C. 9.30.6

Provide I-Joist blocking between cantilevered joists (along bearing) and rimboard closure at ends.

Do not scale - refer to architectural plans for dimensions.


Second Floor Framing

Do not scale - refer to architectural plans for dimensions

REVISION: July 3, 2018
REVISION: Mar. 16, 2020

SE007556 - SE007574

Home Lumber



MODEL: UNIT 4204 - CORNER
EL. A + WOOD COND.
STD. & OPT. 9\"/>

REVISION: Mar. 16, 2020

First Floor Framing

Do not scale - refer to architectural plans for dimensions

11 7/8\"/>

Products					
PlotID	Length	Product	Plies	Net Qty	Fab Type
J1	16-00-00	11 7/8" NI-20	1	22	MFD
J2	16-00-00	11 7/8" NI-20	2	8	MFD
J3	15-00-00	11 7/8" NI-20	1	12	MFD
J4	13-00-00	11 7/8" NI-20	1	9	MFD
J5	12-00-00	11 7/8" NI-20	1	4	MFD
J6	11-00-00	11 7/8" NI-20	1	31	MFD
J7	8-00-00	11 7/8" NI-20	1	17	MFD
J8	5-00-00	11 7/8" NI-20	1	8	MFD
J9	3-00-00	11 7/8" NI-20	1	2	MFD
J10	2-00-00	11 7/8" NI-20	1	2	MFD
B15	16-00-00	VERSALAM-12 2.0E	2	2	MFD
B14	12-00-00	VERSALAM-12 2.0E	1	1	MFD
B13	11-00-00	VERSALAM-12 2.0E	1	1	MFD
B16	5-00-00	VERSALAM-12 2.0E	1	1	MFD

HANGER SCHEDULE

H1-----LT251188 (TM)
H2-----HUS1.81/10(FM)

NOTE:


TM-----TOP MOUNT HANGERS
FM-----FACE MOUNT HANGERS

RIMBOARD

1- 1/8\"/>

SUBFLOOR - 3/4\"/>

APP - AS PER PLAN
BBO - BEAM BY OTHERS



Blocking panels are required over all interior supports.
Squash blocks are required under concentrated loads.

Ceramic Tile Application as per O.B.C. 9.30.6

Provide I-Joist blocking between cantilevered joists (along bearing) and rimboard closure at ends.

Do not scale - refer to architectural plans for dimensions.

JT/PL: 45147/105729

Builder: Gold Park

Location: Vaughan

Designer: NL/SG

Alpa Roof Trusses Inc.

Salesperson: Derek

LI: (290680)318274


Project: Pine Valley

Date: November 23, 2017

Sheet: 2 of 9

Maple, Ontario

Home Lumber



Products					
PlotID	Length	Product	Plies	Net Qty	Fab Type
J1	16-00-00	11 7/8" NI-20	1	25	MFD
J2	15-00-00	11 7/8" NI-20	1	12	MFD
J3	13-00-00	11 7/8" NI-20	1	9	MFD
J4	12-00-00	11 7/8" NI-20	1	4	MFD
J5	11-00-00	11 7/8" NI-20	1	31	MFD
J6	8-00-00	11 7/8" NI-20	1	17	MFD
J7	5-00-00	11 7/8" NI-20	1	8	MFD
J8	2-00-00	11 7/8" NI-20	1	2	MFD
B15	16-00-00	VERSALAM-12 2.0E	2	2	MFD
B14	12-00-00	VERSALAM-12 2.0E	1	1	MFD
B13	11-00-00	VERSALAM-12 2.0E	1	1	MFD
B16	5-00-00	VERSALAM-12 2.0E	1	1	MFD

HANGER SCHEDULE

H1-----LT251188 (TM)
H2-----HUS1.81/10(FM)

NOTE:


TM-----TOP MOUNT HANGERS
FM-----FACE MOUNT HANGERS

RIMBOARD

1- 1/8" X 11 7/8" O.S.B.

SUBFLOOR - 3/4" NAILED & GLUED

APP - AS PER PLAN
BBO - BEAM BY OTHERS



MODEL: UNIT 4204 - CORNER
- EL.A
STD. & OPT. 9' BSMT. PLAN
L.O.D. & W.O.B. COND. ELEV. B SIMILAR

REVISION: Mar. 16, 2020

First Floor Framing

Do not scale - refer to architectural plans for dimensions

11 7/8" BLOCKING
TOTAL LENGTH: 60"

Blocking panels are required over all interior supports.
Squash blocks are required under concentrated loads.

Ceramic Tile Application as per O.B.C. 9.30.6

Provide I-Joist blocking between cantilevered joists (along bearing) and rimboard closure at ends.

Do not scale - refer to architectural plans for dimensions.

JT/PL: 45147/105729

Builder: Gold Park

Location: Vaughan

Designer: NL/SG

Alpa Roof Trusses Inc.

Salesperson: Derek

LI: (290680)318274


Project: Pine Valley

Date: November 23, 2017

Sheet: 3 of 9

Maple, Ontario

Home Lumber



**MODEL: UNIT 4204 - CORNER
- EL.A(W/OPT. 5 BED 2ND FL.)**

REVISION: July 3, 2018
REVISION: Mar. 16, 2020

Second Floor Framing

Do not scale - refer to architectural plans for dimensions

Products					
PlotID	Length	Product	Plies	Net Qty	Fab Type
J1	16'-00"-00	11 7/8" NI-20	1	30	MFD
J2	15'-00"-00	11 7/8" NI-20	1	24	MFD
J3	13'-00"-00	11 7/8" NI-20	1	2	MFD
J4	7'-00"-00	11 7/8" NI-20	1	10	MFD
J5	6'-00"-00	11 7/8" NI-20	1	9	MFD
J6	5'-00"-00	11 7/8" NI-20	1	2	MFD
J7	4'-00"-00	11 7/8" NI-20	1	3	MFD
J8	3'-00"-00	11 7/8" NI-20	1	2	MFD
J9	2'-00"-00	11 7/8" NI-20	1	1	MFD
J10	20'-00"-00	11 7/8" NI-40x	1	11	MFD
J11	19'-00"-00	11 7/8" NI-40x	1	19	MFD
B9	25'-00"-00	VERSALAM-12 2.0E	3	3	MFD
B7	23'-00"-00	VERSALAM-12 2.0E	2	2	MFD
B2	17'-00"-00	VERSALAM-14 2.0E	3	3	MFD
B4	15'-00"-00	VERSALAM-12 2.0E	2	2	MFD
B10	14'-00"-00	VERSALAM-12 2.0E	1	1	MFD
B1	10'-00"-00	VERSALAM-12 2.0E	2	2	MFD
B6	10'-00"-00	VERSALAM-12 2.0E	2	2	MFD
B5	8'-00"-00	VERSALAM-12 2.0E	1	1	MFD
B11	7'-00"-00	VERSALAM-12 2.0E	1	1	MFD
B12	7'-00"-00	VERSALAM-12 2.0E	2	2	MFD
B3	4'-00"-00	VERSALAM-12 2.0E	1	1	MFD
B8	4'-00"-00	VERSALAM-12 2.0E	1	1	MFD

HANGER SCHEDULE


H1-----LT251188 (TM)
H2-----HUS1.81/10(FM)
H3-----HGUS410 (FM)
H4-----HU9X(FM)
H5-----LSSR410Z(FM)
H6-----LSSR2.56Z(FM)

NOTE:

TM -----TOP MOUNT HANGERS
FM-----FACE MOUNT HANGERS

RIMBOARD

1- 1/8" X 11 7/8" O.S.B.
SUBFLOOR - 3/4" NAILED & GLUED
APP - AS PER PLAN
BBO - BEAM BY OTHERS



Blocking panels are required over all interior supports.
Squash blocks are required under concentrated loads.

Ceramic Tile Application as per O.B.C. 9.30.6

Provide I-Joist blocking between cantilevered joists (along bearing) and rimboard closure at ends.

Do not scale - refer to architectural plans for dimensions.

JT/PL: 45147/105729

Builder: Gold Park

Location: Vaughan

Designer: NL/SG

Alpa Roof Trusses Inc.

Salesperson: Derek

LI: (290680)318274


Project: Pine Valley

Date: November 23, 2017

Sheet: 4 of 9

Maple, Ontario

Home Lumber



**MODEL: UNIT 4204 - CORNER
- EL.A(W/SUNKEN)
STD. & OPT. 9' BSMT. PLAN**

REVISION: Mar. 16, 2020 *TWO COND.*

First Floor Framing

Do not scale - refer to architectural plans for dimensions

11 7/8" BLOCKING

TOTAL LENGTH: 56'

Products					
PlotID	Length	Product	Plies	Net Qty	Fab Type
J1A	8-00-00	9 1/2" NI-20	1	15	MFD
J1	16-00-00	11 7/8" NI-20	1	22	MFD
J2	16-00-00	11 7/8" NI-20	2	8	MFD
J3	15-00-00	11 7/8" NI-20	1	12	MFD
J4	13-00-00	11 7/8" NI-20	1	9	MFD
J5	12-00-00	11 7/8" NI-20	1	4	MFD
J6	11-00-00	11 7/8" NI-20	1	31	MFD
J7	8-00-00	11 7/8" NI-20	1	4	MFD
J8	5-00-00	11 7/8" NI-20	1	8	MFD
J9	3-00-00	11 7/8" NI-20	1	2	MFD
J10	2-00-00	11 7/8" NI-20	1	2	MFD
B15	16-00-00	VERSALAM-12 2.0E	2	2	MFD
B19	14-00-00	VERSALAM-10 2.0E	2	2	MFD
B14	12-00-00	VERSALAM-12 2.0E	1	1	MFD
B13	11-00-00	VERSALAM-12 2.0E	1	1	MFD
B16	5-00-00	VERSALAM-12 2.0E	1	1	MFD

HANGER SCHEDULE

H1-----LT251188 (TM)
H2-----HUS1.81/10(FM)
H5-----LT259(TM)

NOTE:


TM-----TOP MOUNT HANGERS
FM-----FACE MOUNT HANGERS

RIMBOARD

1- 1/8" X 9 1/2" O.S.B.
1- 1/8" X 11 7/8" O.S.B.

SUBFLOOR - 3/4" NAILED & GLUED

APP - AS PER PLAN
BBO - BEAM BY OTHERS



Blocking panels are required over all interior supports.
Squash blocks are required under concentrated loads.

Ceramic Tile Application as per O.B.C. 9.30.6

Provide I-Joist blocking between cantilevered joists (along bearing) and rimboard closure at ends.

Do not scale - refer to architectural plans for dimensions.

JT/PL: 45147/105729

Builder: Gold Park

Location: Vaughan

Designer: NL/SG

Alpa Roof Trusses Inc.

Salesperson: Derek

LI: (290680)318274


Project: Pine Valley

Date: November 23, 2017

Sheet: 5 of 9

Maple, Ontario

Home Lumber



MODEL: UNIT 4204 - CORNER
- EL.B

REVISION: July 3, 2018
REVISION: Mar. 16, 2020

Second Floor Framing

Do not scale - refer to architectural plans for dimensions

11 7/8" BLOCKING
TOTAL LENGTH: 15'

Products					
PlotID	Length	Product	Plies	Net Qty	Fab Type
J1	16-00-00	11 7/8" NI-20	1	29	MFD
J2	15-00-00	11 7/8" NI-20	1	22	MFD
J3	13-00-00	11 7/8" NI-20	1	3	MFD
J3A	9-00-00	11 7/8" NI-20	1	6	MFD
J3B	9-00-00	11 7/8" NI-20	2	4	MFD
J4	7-00-00	11 7/8" NI-20	1	3	MFD
J5	6-00-00	11 7/8" NI-20	1	8	MFD
J6	5-00-00	11 7/8" NI-20	1	2	MFD
J7	4-00-00	11 7/8" NI-20	1	4	MFD
J8	3-00-00	11 7/8" NI-20	1	3	MFD
J10	20-00-00	11 7/8" NI-40x	1	11	MFD
J11	19-00-00	11 7/8" NI-40x	1	19	MFD
B9	25-00-00	VERSALAM-12 2.0E	3	3	MFD
B7	23-00-00	VERSALAM-12 2.0E	2	2	MFD
B2	17-00-00	VERSALAM-14 2.0E	3	3	MFD
B17	15-00-00	VERSALAM-12 2.0E	1	1	MFD
B4	15-00-00	VERSALAM-12 2.0E	2	2	MFD
B18	11-00-00	VERSALAM-12 2.0E	2	2	MFD
B1	10-00-00	VERSALAM-12 2.0E	2	2	MFD
B6	10-00-00	VERSALAM-12 2.0E	2	2	MFD
B5	8-00-00	VERSALAM-12 2.0E	1	1	MFD
B11	7-00-00	VERSALAM-12 2.0E	1	1	MFD
B12	7-00-00	VERSALAM-12 2.0E	2	2	MFD
B3	4-00-00	VERSALAM-12 2.0E	1	1	MFD
B8	4-00-00	VERSALAM-12 2.0E	1	1	MFD

HANGER SCHEDULE	
H1	LT251188 (TM)
H2	HUS1.81/10(FM)
H3	HGUS410 (FM)
H4	HU9X(FM)
H5	LSSR410Z(FM)
H6	LSSR2.56Z(FM)
NOTE:	
TM	TOP MOUNT HANGERS
FM	FACE MOUNT HANGERS


RIMBOARD
1- 1/8" X 11 7/8" O.S.B.
SUBFLOOR - 3/4" NAILED & GLUED
APP - AS PER PLAN
BBO - BEAM BY OTHERS

Blocking panels are required over all interior supports.
Squash blocks are required under concentrated loads.

Ceramic Tile Application as per O.B.C. 9.30.6

Provide I-Joist blocking between cantilevered joists (along bearing) and rimboard closure at ends.


Do not scale - refer to architectural plans for dimensions.



Products					
PlotID	Length	Product	Plies	Net Qty	Fab Type
J1	16-00-00	11 7/8" NI-20	1	23	MFD
J2	16-00-00	11 7/8" NI-20	2	8	MFD
J3	15-00-00	11 7/8" NI-20	1	12	MFD
J4A	14-00-00	11 7/8" NI-20	1	8	MFD
J4	13-00-00	11 7/8" NI-20	1	1	MFD
J5	12-00-00	11 7/8" NI-20	1	4	MFD
J6	11-00-00	11 7/8" NI-20	1	31	MFD
J7	8-00-00	11 7/8" NI-20	1	17	MFD
J8	5-00-00	11 7/8" NI-20	1	8	MFD
J9	3-00-00	11 7/8" NI-20	1	2	MFD
B15	16-00-00	VERSALAM-12 2.0E	2	2	MFD
B14	12-00-00	VERSALAM-12 2.0E	1	1	MFD
B13	11-00-00	VERSALAM-12 2.0E	1	1	MFD
B16	5-00-00	VERSALAM-12 2.0E	1	1	MFD

HANGER SCHEDULE	
H1	LT251188 (TM)
H2	HUS1.81/10(FM)
NOTE:	
TM	TOP MOUNT HANGERS
FM	FACE MOUNT HANGERS

RIMBOARD	
1-	1/8" X 11 7/8" O.S.B.
SUBFLOOR - 3/4" NAILED & GLUED	
APP	AS PER PLAN
BBO	BEAM BY OTHERS



Blocking panels are required over all interior supports.
Squash blocks are required under concentrated loads.

Ceramic Tile Application as per O.B.C. 9.30.6

Provide I-Joist blocking between cantilevered joists (along bearing) and rimboard closure at ends.

Do not scale - refer to architectural plans for dimensions.

MODEL: UNIT 4204 - CORNER
- EL.B
STD. & OPT. 9' BSMT. PLAN

First Floor Framing

Do not scale - refer to architectural plans for dimensions

11 7/8" BLOCKING
TOTAL LENGTH: 60'

REVISION: Mar. 16, 2020

+ WOOD COND.

JT/PL: 45147/105729

Builder: Gold Park

Location: Vaughan

Designer: NL/SG

Alpa Roof Trusses Inc.

Salesperson: Derek

LI: (299728)318274


Project: Pine Valley

Date: November 23, 2017

Sheet: 7 of 9

Maple, Ontario

Home Lumber



**MODEL: UNIT 4204 - CORNER
- EL.B(W/OPT. 2ND FL.)**

REVISION: July 3, 2018
REVISION: Mar. 16, 2020

Second Floor Framing

Do not scale - refer to architectural plans for dimensions

11 7/8" BLOCKING
TOTAL LENGTH: 9'

Products					
PlotID	Length	Product	Plies	Net Qty	Fab Type
J1	16-00-00	11 7/8" NI-20	1	29	MFD
J2	15-00-00	11 7/8" NI-20	1	24	MFD
J3	13-00-00	11 7/8" NI-20	1	3	MFD
J3A	9-00-00	11 7/8" NI-20	1	6	MFD
J3B	9-00-00	11 7/8" NI-20	2	4	MFD
J4	7-00-00	11 7/8" NI-20	1	3	MFD
J5	6-00-00	11 7/8" NI-20	1	9	MFD
J6	5-00-00	11 7/8" NI-20	1	2	MFD
J7	4-00-00	11 7/8" NI-20	1	4	MFD
J8	3-00-00	11 7/8" NI-20	1	3	MFD
J10	20-00-00	11 7/8" NI-40x	1	11	MFD
J11	19-00-00	11 7/8" NI-40x	1	19	MFD
B9	25-00-00	VERSALAM-12 2.0E	3	3	MFD
B7	23-00-00	VERSALAM-12 2.0E	2	2	MFD
B2	17-00-00	VERSALAM-14 2.0E	3	3	MFD
B17	15-00-00	VERSALAM-12 2.0E	1	1	MFD
B4	15-00-00	VERSALAM-12 2.0E	2	2	MFD
B18	11-00-00	VERSALAM-12 2.0E	2	2	MFD
B1	10-00-00	VERSALAM-12 2.0E	2	2	MFD
B6	10-00-00	VERSALAM-12 2.0E	2	2	MFD
B5	8-00-00	VERSALAM-12 2.0E	1	1	MFD
B11	7-00-00	VERSALAM-12 2.0E	1	1	MFD
B12	7-00-00	VERSALAM-12 2.0E	2	2	MFD
B3	4-00-00	VERSALAM-12 2.0E	1	1	MFD
B8	4-00-00	VERSALAM-12 2.0E	1	1	MFD

HANGER SCHEDULE

H1-----LT251188 (TM)
H2-----HUS1.81/10(FM)
H3-----HGUS410 (FM)
H4-----HU9X(FM)
H5-----LSSR410Z(FM)
H6-----LSSR2.56Z(FM)

NOTE:
TM-----TOP MOUNT HANGERS
FM-----FACE MOUNT HANGERS

RIMBOARD

1- 1/8" X 11 7/8" O.S.B.

SUBFLOOR - 3/4" NAILED & GLUED

APP - AS PER PLAN
BBO - BEAM BY OTHERS

Ceramic tile application as per O.B.C. 9.30.6

Provide I-Joist Blocking between cantilevered joists (along bearing) and rimboard closure at ends.

1-2X6 SPF#2 Squash Block req'd on one side of each joist under interior load bearing wall. Multiple Squash Blocks are req'd under concentrated loads.

JT/PL: 45147/105729

Builder: Gold Park

Location: Vaughan

Designer: NL/SG

Alpa Roof Trusses Inc.

Salesperson: Derek

LI: (290680)318274


Project: Pine Valley

Date: November 23, 2017

Sheet: 8 of 9

Maple, Ontario

Home Lumber



Products					
PlotID	Length	Product	Plies	Net Qty	Fab Type
J1A	8-00-00	9 1/2" NI-20	1	15	MFD
J1	16-00-00	11 7/8" NI-20	1	23	MFD
J2	16-00-00	11 7/8" NI-20	2	8	MFD
J3	15-00-00	11 7/8" NI-20	1	12	MFD
J4A	14-00-00	11 7/8" NI-20	1	8	MFD
J4	13-00-00	11 7/8" NI-20	1	1	MFD
J5	12-00-00	11 7/8" NI-20	1	4	MFD
J6	11-00-00	11 7/8" NI-20	1	31	MFD
J7	8-00-00	11 7/8" NI-20	1	4	MFD
J8	5-00-00	11 7/8" NI-20	1	8	MFD
J9	3-00-00	11 7/8" NI-20	1	2	MFD
B15	16-00-00	VERSALAM-12 2.0E	2	2	MFD
B19	14-00-00	VERSALAM-10 2.0E	2	2	MFD
B14	12-00-00	VERSALAM-12 2.0E	1	1	MFD
B13	11-00-00	VERSALAM-12 2.0E	1	1	MFD
B16	5-00-00	VERSALAM-12 2.0E	1	1	MFD

HANGER SCHEDULE

H1-----LT251188 (TM)
H2-----HUS1.81/10(FM)
H5-----LT259(TM)

NOTE:
TM-----TOP MOUNT HANGERS
FM-----FACE MOUNT HANGERS

RIMBOARD

1- 1/8" X 9 1/2" O.S.B.
1- 1/8" X 11 7/8" O.S.B.

SUBFLOOR - 3/4" NAILED & GLUED

APP - AS PER PLAN
BBO - BEAM BY OTHERS

Ceramic tile application as per O.B.C. 9.30.6

Provide I-Joist Blocking between cantilevered joists (along bearing) and rimboard closure at ends.

1-2X6 SPF#2 Squash Block req'd on one side of each joist under interior load bearing wall. Multiple Squash Blocks are req'd under concentrated loads.

MODEL: UNIT 4204 - CORNER
- EL.B(W/SUNKEN)
STD. & OPT. 9' BSMT. PLAN

First Floor Framing

Do not scale - refer to architectural plans for dimensions

11 7/8" BLOCKING

TOTAL LENGTH: 60'

REVISION: Mar. 16, 2020 + WOOD COND.

BC CALC® Member Report
Build 7555


B01 (Floor Beam)

Dry | 1 span | No cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Builder: Gold Park
Code reports: CCMC 12472-R

File name: 290680
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses


Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	3093 / 0	1895 / 0		
B1, 3-1/2"	3093 / 0	1895 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	09-08-00	Top		12			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	09-08-00	Top	40	20			16-00-00
2		Unf. Lin. (lb/ft)	L	00-00-00	09-08-00	Top		60			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	15369 ft-lbs	35392 ft-lbs	43.4%	1	04-10-00
End Shear	5151 lbs	14464 lbs	35.6%	1	01-03-06
Total Load Deflection	L/647 (0.171")	n/a	37.1%	4	04-10-00
Live Load Deflection	L/999 (0.106")	n/a	n/a	5	04-10-00
Max Defl.	0.171"	n/a	17.1%	4	04-10-00
Span / Depth	9.3				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 3-1/2"	7009 lbs	93.0%	46.9%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 3-1/2"	7009 lbs	93.0%	46.9%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4

NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 10" O/C,
STAGGERED IN 2 ROWS



BC CALC® Member Report
Build 7555


B02 (Floor Beam)

Dry | 1 span | No cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Builder: Gold Park
Code reports: CCMC 12472-R

File name: 290680
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses



B0

16-02-00

B1

Total Horizontal Product Length = 16-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	5497 / 0	3405 / 0		
B1, 3-1/2"	5497 / 0	3405 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	16-02-00	Top		21			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	16-02-00	Top	40	20			17-00-00
2		Unf. Lin. (lb/ft)	L	00-00-00	16-02-00	Top		60			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	47703 ft-lbs	75349 ft-lbs	63.3%	1	08-01-00
End Shear	10246 lbs	25578 lbs	40.1%	1	01-05-08
Total Load Deflection	L/300 (0.628")	n/a	80.0%	4	08-01-00
Live Load Deflection	L/486 (0.388")	n/a	74.1%	5	08-01-00
Max Defl.	0.628"	n/a	62.8%	4	08-01-00
Span / Depth	13.5				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Column 3-1/2" x 5-1/4"	12502 lbs	39.2%	55.8%	Spruce-Pine-Fir
B1	Column 3-1/2" x 5-1/4"	12502 lbs	39.2%	55.8%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4


NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 6" O/C,
STAGGERED IN 2 ROWS



BC CALC® Member Report
Build 7555
B03 (Floor Beam)
 Dry | 1 span | No cant.

March 16, 2020 14:06:05

 Job name: 45147 (4204)
 Address: Pine Valley
 City, Province, Postal Code: Vaughan, ON
 Builder: Gold Park
 Code reports: CCMC 12472-R

 File name: 290680
 Description: Second Floor Framing
 Specifier:
 Designer: NL
 Company: Alpa Roof Trusses

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	480 / 0	192 / 0		
B1, 3-1/2"	480 / 0	192 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	04-00-00	Top		6			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	04-00-00	Top	40	15			06-00-00

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	753 ft-lbs	17696 ft-lbs	4.3%	1	02-00-00
End Shear	345 lbs	7232 lbs	4.8%	1	01-03-06
Total Load Deflection	L/999 (0.002")	n/a	n/a	4	02-00-00
Live Load Deflection	L/999 (0.002")	n/a	n/a	5	02-00-00
Max Defl.	0.002"	n/a	n/a	4	02-00-00
Span / Depth	3.6				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	960 lbs	25.5%	12.8%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 1-3/4"	960 lbs	25.5%	12.8%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4


Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

SE007558



Boise Cascade

**Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP****PASSED****B04 (Floor Beam)**

Dry | 1 span | No cant.

March 16, 2020 14:06:05

BC CALC® Member Report

Build 7555

Job name: 45147 (4204)

File name: 290680

Address: Pine Valley

Description: Second Floor Framing

City, Province, Postal Code: Vaughan, ON


Specifier:

Builder: Gold Park

Designer: NL

Code reports: CCMC 12472-R

Company: Alpa Roof Trusses



Total Horizontal Product Length = 15'-00"

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	2355 / 0	1708 / 0		
B1, 3-1/2"	2711 / 0	1859 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	15-00-00	Top		12			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	15-00-00	Top	40	20			07-06-00
2		Unf. Lin. (lb/ft)	L	00-00-00	15-00-00	Top		60			n/a
3		Unf. Lin. (lb/ft)	L	11-10-00	15-00-00	Top	27	14			n/a
4		Conc. Pt. (lbs)	L	11-10-00	11-10-00	Top	480	192			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	20794 ft-lbs	35392 ft-lbs	58.8%	1	07-08-09
End Shear	5383 lbs	14464 lbs	37.2%	1	13-08-10
Total Load Deflection	L/298 (0.585")	n/a	80.5%	4	07-06-09
Live Load Deflection	L/509 (0.343")	n/a	70.7%	5	07-06-09
Max Defl.	0.585"	n/a	58.5%	4	07-06-09
Span / Depth	14.7				

**Bearing Supports**

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 3-1/2"	5668 lbs	75.2%	37.9%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 3-1/2"	6389 lbs	84.8%	42.8%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4

NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 16" O/C,
 STAGGERED IN 2 ROWS

SE007559

BC CALC® Member Report
Build 7555


B05 (Floor Beam)

Dry | 1 span | No cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Builder: Gold Park
Code reports: CCMC 12472-R

File name: 290680
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses



B0

08-00-00

B1

Total Horizontal Product Length = 08-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1537 / 0	1031 / 0		
B1, 3-1/2"	1719 / 0	1128 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-00-00	Top		6			00-00-00
1		Unf. Lin. (lb/ft)	L	00-00-00	08-00-00	Top	27	14			n/a
2		Unf. Lin. (lb/ft)	L	00-00-00	04-02-00	Top	27	14			n/a
3		Unf. Area (lb/ft²)	L	04-02-00	08-00-00	Top	40	15			01-05-00
4		Conc. Pt. (lbs)	L	04-02-00	04-02-00	Top	2711	1859			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	13082 ft-lbs	17696 ft-lbs	73.9%	1	04-02-00
End Shear	3762 lbs	7232 lbs	52.0%	1	06-08-10
Total Load Deflection	L/566 (0.16")	n/a	42.4%	4	04-00-15
Live Load Deflection	L/999 (0.096")	n/a	n/a	5	04-00-15
Max Defl.	0.16"	n/a	16.0%	4	04-00-15
Span / Depth	7.6				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	3595 lbs	95.4%	48.1%	Spruce-Pine-Fir
B1	Column 3-1/2" x 1-3/4"	3989 lbs	37.5%	53.4%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4


Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

SE007560


BC CALC® Member Report
Build 7555

B06 (Floor Beam)
Dry | 1 span | No cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Builder: Gold Park
Code reports: CCMC 12472-R

File name: 290680
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpha Roof Trusses



Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	527 / 0	256 / 0		
B1, 3-1/2"	593 / 0	281 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	09-04-00	Top		12			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	09-04-00	Top	40	15			01-00-00
2		Trapezoidal (lb/ft)	L	00-00-00	09-04-00	Top	60	23			n/a
							100	38			

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	2482 ft-lbs	35392 ft-lbs	7.0%	1	04-09-04
End Shear	1062 lbs	14464 lbs	7.3%	1	08-00-10
Total Load Deflection	L/999 (0.025")	n/a	n/a	4	04-08-00
Live Load Deflection	L/999 (0.017")	n/a	n/a	5	04-08-00
Max Defl.	0.025"	n/a	n/a	4	04-08-00
Span / Depth	9.0				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 3-1/2"	1111 lbs	14.7%	7.4%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 3-1/2"	1240 lbs	16.5%	8.3%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4

NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 12" O/C,
STAGGERED IN 2 ROWS





Boise Cascade


**Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP****PASSED**BC CALC® Member Report
Build 7555**B07 (Floor Beam)**

Dry | 2 spans | L cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
 Address: Pine Valley
 City, Province, Postal Code: Vaughan, ON
 Builder: Gold Park
 Code reports: CCMC 12472-R

File name: 290680
 Description: Second Floor Framing
 Specifier:
 Designer: NL
 Company: Alpha Roof Trusses



Total Horizontal Product Length = 22-03-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 3-1/2"	1862 / 0	935 / 0		
B2, 3-1/2"	515 / 183	226 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	22-03-00	Top		12			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	22-03-00	Top	40	15			01-04-00
2		Conc. Pt. (lbs)	L	00-00-00	00-00-00	Top	480	192			n/a
3		Conc. Pt. (lbs)	L	00-00-00	00-00-00	Top	527	256			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	4393 ft-lbs	35392 ft-lbs	12.4%	3	13-05-00
Neg. Moment	-7158 ft-lbs	-35392 ft-lbs	20.2%	1	03-02-00
End Shear	901 lbs	14464 lbs	6.2%	3	20-11-10
Cont. Shear	2314 lbs	14464 lbs	16.0%	1	02-00-06
Total Load Deflection	2xL/486 (0.156")	n/a	49.4%	9	00-00-00
Live Load Deflection	2xL/536 (0.142")	n/a	67.1%	12	00-00-00
Total Neg. Defl.	L/999 (-0.115")	n/a	n/a	9	10-00-06
Max Defl.	0.187"	n/a	18.7%	10	12-10-12
Cant. Max Defl.	0.156"	n/a	15.6%	9	00-00-00
Span / Depth	19.1				



Bearing Supports	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1	Wall/Plate 3-1/2" x 3-1/2"	3962 lbs	52.6%	26.5%	Spruce-Pine-Fir
B2	Wall/Plate 3-1/2" x 3-1/2"	1054 lbs	14.0%	7.1%	Spruce-Pine-Fir

Cautions

Uplift of 72 lbs found at bearing B2.

NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 12" O/C,
 STAGGERED IN 2 ROWS

SE007562

BC CALC® Member Report
Build 7555


B08 (Floor Beam)

Dry | 1 span | No cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Builder: Gold Park
Code reports: CCMC 12472-R

File name: 290680
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses



B0 **B1**
Total Horizontal Product Length = 03-08-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	202 / 0	87 / 0		
B1, 3-1/2"	202 / 0	87 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live	Dead	Snow	Wind	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	03-08-00	Top	1.00	0.65	1.00	1.15	00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	03-08-00	Top	40	15			02-09-00

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	288 ft-lbs	17696 ft-lbs	1.6%	1	01-10-00
End Shear	124 lbs	7232 lbs	1.7%	1	01-03-06
Total Load Deflection	L/999 (0.001")	n/a	n/a	4	01-10-00
Live Load Deflection	L/999 (0.001")	n/a	n/a	5	01-10-00
Max Defl.	0.001"	n/a	n/a	4	01-10-00
Span / Depth	3.2				

Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	411 lbs	10.9%	5.5%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 1-3/4"	411 lbs	10.9%	5.5%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4


Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

SE007563

B09 (Floor Beam)

Dry | 2 spans | L cant.

March 16, 2020 14:06:05

BC CALC® Member Report

Build 7555

Job name: 45147 (4204)

File name: 290680

Address: Pine Valley

Description: Second Floor Framing

City, Province, Postal Code: Vaughan, ON


Specifier:

Builder: Gold Park

Designer: NL

Code reports: CCMC 12472-R

Company: Alpa Roof Trusses



Total Horizontal Product Length = 24-05-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 3-1/2"	1847 / 0	1062 / 0		
B2, 3-1/2"	515 / 265	235 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	24-05-00	Top		18			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	24-05-00	Top	40	15			01-04-00
2		Conc. Pt. (lbs)	L	00-00-00	00-00-00	Top	593	281			n/a
3		Conc. Pt. (lbs)	L	00-00-00	00-00-00	Top	202	87			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	4212 ft-lbs	55212 ft-lbs	7.6%	3	16-01-04
Neg. Moment	-10627 ft-lbs	-55212 ft-lbs	19.2%	2	05-04-00
End Shear	902 lbs	21696 lbs	4.2%	3	23-01-10
Cont. Shear	2188 lbs	21696 lbs	10.1%	2	04-02-06
Total Load Deflection	2xL/413 (0.31")	n/a	58.1%	9	00-00-00
Live Load Deflection	2xL/509 (0.251")	n/a	70.7%	12	00-00-00
Total Neg. Defl.	L/1724 (-0.131")	n/a	13.9%	9	12-05-08
Max Defl.	-0.131"	n/a	13.1%	9	12-05-08
Cant. Max Defl.	0.31"	n/a	31.0%	9	00-00-00
Span / Depth	19.1				


Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1	Wall/Plate 3-1/2" x 5-1/4"	4099 lbs	36.3%	18.3%	Spruce-Pine-Fir
B2	Wall/Plate 3-1/2" x 5-1/4"	1066 lbs	9.4%	4.8%	Spruce-Pine-Fir
B2	Uplift	186 lbs			

Cautions

Uplift of 186 lbs found at bearing B2.

NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 12" O/C,
STAGGERED IN 2 ROWS


BC CALC® Member Report
Build 7555

B10 (Floor Beam)
Dry | 1 span | No cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Builder: Gold Park
Code reports: CCMC 12472-R

File name: 290680
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses



Total Horizontal Product Length = 13-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	296 / 0	580 / 0		
B1, 3-1/2"	415 / 0	640 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	13-02-00	Top		6			00-00-00
1		Unf. Lin. (lb/ft)	L	00-00-00	13-02-00	Top	27	74			n/a
2		Unf. Lin. (lb/ft)	L	07-06-00	13-02-00	Top	27	14			n/a
4		Conc. Pt. (lbs)	L	07-06-00	07-06-00	Top	202	87			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	4549 ft-lbs	17696 ft-lbs	25.7%	1	07-06-00
End Shear	1168 lbs	7232 lbs	16.1%	1	11-10-10
Total Load Deflection	L/802 (0.19")	n/a	29.9%	4	06-08-11
Live Load Deflection	L/999 (0.075")	n/a	n/a	5	06-08-11
Max Defl.	0.19"	n/a	19.0%	4	06-08-11
Span / Depth	12.8				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	812 lbs	33.2%	16.7%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 1-3/4"	1422 lbs	37.7%	19.0%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4



Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

SE007565

B11 (Floor Beam)


BC CALC® Member Report
Build 7555

Dry | 1 span | No cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Builder: Gold Park
Code reports: CCMC 12472-R

File name: 290680
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses



Total Horizontal Product Length = 06-06-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	357 / 0	1027 / 0	788 / 0	
B1, 3-1/2"	357 / 0	785 / 0	410 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	06-06-00	Top		6			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	06-06-00	Top	40	20			02-09-00
2		Unf. Lin. (lb/ft)	L	00-00-00	06-06-00	Top		100			n/a
3		Unf. Area (lb/ft²)	L	00-00-00	06-06-00	Top		13	21		01-06-00
4		Unf. Area (lb/ft²)	L	00-08-00	06-06-00	Top		13	21		04-00-00
5		Conc. Pt. (lbs)	L	00-08-00	00-08-00	Top		322	504		n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	2880 ft-lbs	17696 ft-lbs	16.3%	5	03-01-08
End Shear	1612 lbs	7232 lbs	22.3%	5	01-03-06
Total Load Deflection	L/999 (0.03")	n/a	n/a	11	03-02-04
Live Load Deflection	L/999 (0.015")	n/a	n/a	15	03-02-04
Max Defl.	0.03"	n/a	n/a	11	03-02-04
Span / Depth	6.1				


Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	2824 lbs	74.9%	37.8%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 1-3/4"	1955 lbs	51.9%	26.2%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4

B12 (Floor Beam)


Dry | 1 span | No cant.

March 16, 2020 14:06:05

BC CALC® Member Report

Build 7555

 Job name: 45147 (4204)
 Address: Pine Valley
 City, Province, Postal Code: Vaughan, ON
 Builder: Gold Park
 Code reports: CCMC 12472-R

 File name: 290680
 Description: Second Floor Framing
 Specifier:
 Designer: NL
 Company: Alpa Roof Trusses


Total Horizontal Product Length = 06-03-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	224 / 0	262 / 0	71 / 0	
B1, 3-1/2"	439 / 0	921 / 0	412 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live	Dead	Snow	Wind	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	06-03-00	Top	1.00	0.65	1.00	1.15	00-00-00
1		Unf. Lin. (lb/ft)	L	00-00-00	06-03-00	Top	27	14			n/a
2		Unf. Lin. (lb/ft)	L	00-00-00	05-01-00	Top	27	14			n/a
3		Unf. Lin. (lb/ft)	L	05-01-00	06-03-00	Top		100			n/a
4		Unf. Area (lb/ft²)	L	05-01-00	06-03-00	Top		13	21		03-00-00
5		Conc. Pt. (lbs)	L	05-01-00	05-01-00	Top	357	785	410		n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	1876 ft-lbs	35392 ft-lbs	5.3%	1	05-01-00
End Shear	1835 lbs	14464 lbs	12.7%	1	04-11-10
Total Load Deflection	L/999 (0.008")	n/a	n/a	11	03-04-04
Live Load Deflection	L/999 (0.004")	n/a	n/a	15	03-04-04
Max Defl.	0.008"	n/a	n/a	11	03-04-04
Span / Depth	5.9				


Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0	Wall/Plate 3-1/2" x 3-1/2"	735 lbs	9.7%	4.9%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 3-1/2"	2221 lbs	29.5%	14.9%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4

NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 12" O/C,
 STAGGERED IN 2 ROWS


B13 (Floor Beam)

Dry | 1 span | No cant.

March 16, 2020 14:06:05

 BC CALC® Member Report
 Build 7555

 Job name: 45147 (4204)
 Address: Pine Valley
 City, Province, Postal Code: Vaughan, ON
 Builder: Gold Park
 Code reports: CCMC 12472-R

 File name: 290680
 Description: First Floor Framing
 Specifier:
 Designer: NL
 Company: Alpa Roof Trusses


B0

10-02-00

B1

Total Horizontal Product Length = 10-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1087 / 0	743 / 0		
B1, 3-1/2"	914 / 0	678 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	10-02-00	Top		6			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	10-02-00	Top	40	15			02-02-00
2		Unf. Lin. (lb/ft)	L	00-00-00	10-02-00	Top		60			n/a
3		Conc. Pt. (lbs)	L	04-04-00	04-04-00	Top	1120	420			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	8135 ft-lbs	17696 ft-lbs	46.0%	1	04-04-00
End Shear	2235 lbs	7232 lbs	30.9%	1	01-03-06
Total Load Deflection	L/661 (0.176")	n/a	36.3%	4	04-11-11
Live Load Deflection	L/999 (0.109")	n/a	n/a	5	04-10-13
Max Defl.	0.176"	n/a	17.6%	4	04-11-11
Span / Depth	9.8				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	2560 lbs	67.9%	34.3%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 1-3/4"	2219 lbs	58.9%	29.7%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4


Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

SE007568

B14 (Floor Beam)

Dry | 1 span | No cant.

March 16, 2020 14:06:05

BC CALC® Member Report

Build 7555

Job name: 45147 (4204)

File name: 290680

Address: Pine Valley

Description: First Floor Framing

City, Province, Postal Code: Vaughan, ON


Specifier:

Builder: Gold Park

Designer: NL

Code reports: CCMC 12472-R

Company: Alpa Roof Trusses



Total Horizontal Product Length = 11-10-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1166 / 0	724 / 0		
B1, 3-1/2"	1234 / 0	645 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	11-10-00	Top		6			00-00-00
1		Unf. Lin. (lb/ft)	L	00-00-00	11-10-00	Top	27	14			n/a
2		Unf. Lin. (lb/ft)	L	00-00-00	04-04-00	Top	27	14			n/a
3		Unf. Area (lb/ft²)	L	04-04-00	11-10-00	Top	40	15			03-06-00
4		Conc. Pt. (lbs)	L	04-04-00	04-04-00	Top	914	678			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	9738 ft-lbs	17696 ft-lbs	55.0%	1	04-04-00
End Shear	2496 lbs	7232 lbs	34.5%	1	01-03-06
Total Load Deflection	L/446 (0.306")	n/a	53.8%	4	05-09-08
Live Load Deflection	L/708 (0.193")	n/a	50.8%	5	05-09-08
Max Defl.	0.306"	n/a	30.6%	4	05-09-08
Span / Depth	11.5				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	2655 lbs	70.4%	35.5%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 1-3/4"	2658 lbs	70.5%	35.6%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4



Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

SE007569


BC CALC® Member Report
Build 7555

B15 (Floor Beam)
Dry | 1 span | No cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Builder: Gold Park
Code reports: CCMC 12472-R

File name: 290680
Description: First Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses



Total Horizontal Product Length = 15-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1598 / 0	1234 / 0		
B1, 3-1/2"	2365 / 0	1586 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	15-02-00	Top		12			00-00-00
1		Unf. Lin. (lb/ft)	L	00-00-00	15-02-00	Top	27	74			n/a
2		Unf. Area (lb/ft²)	L	10-02-00	15-02-00	Top	40	15			06-00-00
3		Conc. Pt. (lbs)	L	04-04-00	04-04-00	Top	1120	420			n/a
4		Conc. Pt. (lbs)	L	10-02-00	10-02-00	Top	1234	645			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	18643 ft-lbs	35392 ft-lbs	52.7%	1	10-02-00
End Shear	4735 lbs	14464 lbs	32.7%	1	13-10-10
Total Load Deflection	L/336 (0.526")	n/a	71.5%	4	07-09-09
Live Load Deflection	L/570 (0.31")	n/a	63.2%	5	07-09-09
Max Defl.	0.526"	n/a	52.6%	4	07-09-09
Span / Depth	14.9				



Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 3-1/2"	3940 lbs	52.3%	26.4%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 3-1/2"	5530 lbs	73.4%	37.0%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4

NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 12" O/C,
STAGGERED IN 2 ROWS


BC CALC® Member Report
Build 7555

B16 (Floor Beam)
Dry | 1 span | No cant.

March 16, 2020 14:06:05

Job name: 45147 (4204)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Builder: Gold Park
Code reports: CCMC 12472-R

File name: 290680
Description: First Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses



Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	750 / 0	294 / 0		
B1, 3-1/2"	750 / 0	294 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	04-02-00	Top		6			00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	04-02-00	Top	40	15			09-00-00

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	1231 ft-lbs	17696 ft-lbs	7.0%	1	02-01-00
End Shear	575 lbs	7232 lbs	7.9%	1	01-03-06
Total Load Deflection	L/999 (0.004")	n/a	n/a	4	02-01-00
Live Load Deflection	L/999 (0.003")	n/a	n/a	5	02-01-00
Max Defl.	0.004"	n/a	n/a	4	02-01-00
Span / Depth	3.7				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	1492 lbs	39.6%	20.0%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 1-3/4"	1492 lbs	39.6%	20.0%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4



Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

SE007571

B17 (Floor Beam)

Dry | 1 span | No cant.

March 16, 2020 14:06:05

BC CALC® Member Report

Build 7555

Job name: 45147 (4204)

File name: 290680

Address: Pine Valley

Description: Second Floor Framing

City, Province, Postal Code: Vaughan, ON


Specifier:

Builder: Gold Park

Designer: NL

Code reports: CCMC 12472-R

Company: Alpa Roof Trusses



B0

14-02-00

B1

Total Horizontal Product Length = 14-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	300 / 0	616 / 0		
B1, 3-1/2"	437 / 0	684 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	14-02-00	Top		6			00-00-00
1		Unf. Lin. (lb/ft)	L	00-00-00	14-02-00	Top	27	74			n/a
2		Unf. Lin. (lb/ft)	L	08-06-00	14-02-00	Top	27	14			n/a
4		Conc. Pt. (lbs)	L	08-06-00	08-06-00	Top	202	87			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	5028 ft-lbs	17696 ft-lbs	28.4%	1	08-06-00
End Shear	1256 lbs	7232 lbs	17.4%	1	12-10-10
Total Load Deflection	L/662 (0.248")	n/a	36.2%	4	07-01-12
Live Load Deflection	L/999 (0.095")	n/a	n/a	5	07-04-07
Max Defl.	0.248"	n/a	24.8%	4	07-01-12
Span / Depth	13.9				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	863 lbs	35.2%	17.8%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 1-3/4"	1510 lbs	40.1%	20.2%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4


Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

SE007572

B18 (Floor Beam)


Dry | 1 span | No cant.

March 16, 2020 14:06:05

BC CALC® Member Report

Build 7555

 Job name: 45147 (4204)
 Address: Pine Valley
 City, Province, Postal Code: Vaughan, ON
 Builder: Gold Park
 Code reports: CCMC 12472-R

 File name: 290680
 Description: Second Floor Framing
 Specifier:
 Designer: NL
 Company: Alpa Roof Trusses


Total Horizontal Product Length = 10-04-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	139 / 0	1967 / 0	2063 / 0	
B1, 3-1/2"	139 / 0	2247 / 0	2501 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	10-04-00	Top		12			00-00-00
1		Unf. Lin. (lb/ft)	L	00-00-00	10-04-00	Top	27	114			n/a
2		Unf. Area (lb/ft²)	L	00-00-00	10-04-00	Top		13	21		01-00-00
3		Unf. Area (lb/ft²)	L	00-00-00	03-10-00	Top		13	21		03-00-00
4		Unf. Area (lb/ft²)	L	03-10-00	10-04-00	Top		13	21		19-00-00
5		Conc. Pt. (lbs)	L	03-10-00	03-10-00	Top		965	1512		n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	18018 ft-lbs	35392 ft-lbs	50.9%	5	04-05-13
End Shear	5227 lbs	14464 lbs	36.1%	5	09-00-10
Total Load Deflection	L/548 (0.216")	n/a	43.8%	11	05-01-11
Live Load Deflection	L/999 (0.113")	n/a	n/a	15	05-01-11
Max Defl.	0.216"	n/a	21.6%	11	05-01-11
Span / Depth	10.0				


Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0	Wall/Plate 3-1/2" x 3-1/2"	5693 lbs	75.5%	38.1%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 3-1/2"	6700 lbs	88.9%	44.8%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4

NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 12" O/C,
 STAGGERED IN 2 ROWS

B19 (Floor Beam)


Dry | 1 span | No cant.

March 16, 2020 14:06:05

BC CALC® Member Report

Build 7555

 Job name: 45147 (4204)
 Address: Pine Valley
 City, Province, Postal Code: Vaughan, ON
 Builder: Gold Park
 Code reports: CCMC 12472-R

 File name: 290680
 Description: First Floor Framing
 Specifier:
 Designer: NL
 Company: Alpa Roof Trusses


Total Horizontal Product Length = 13-09-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1100 / 0	1029 / 0		
B1, 3-1/2"	1100 / 0	1029 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live	Dead	Snow	Wind	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	13-09-00	Top	1.00	0.65	1.00	1.15	00-00-00
1		Unf. Area (lb/ft²)	L	00-00-00	13-09-00	Top	40	20			04-00-00
2		Unf. Lin. (lb/ft)	L	00-00-00	13-09-00	Top		60			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	9430 ft-lbs	23220 ft-lbs	40.6%	1	06-10-08
End Shear	2473 lbs	11571 lbs	21.4%	1	01-01-00
Total Load Deflection	L/367 (0.435")	n/a	65.4%	4	06-10-08
Live Load Deflection	L/710 (0.225")	n/a	50.7%	5	06-10-08
Max Defl.	0.435"	n/a	43.5%	4	06-10-08
Span / Depth	16.8				

Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0	Wall/Plate 3-1/2" x 3-1/2"	2936 lbs	39.0%	19.6%	Spruce-Pine-Fir
B1	Wall/Plate 3-1/2" x 3-1/2"	2936 lbs	39.0%	19.6%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4

NAIL ONE PLY TO ANOTHER WITH 3-1/2" SPIRAL NAILS @ 12" O/C,
 STAGGERED IN 2 ROWS



Maximum Floor Spans – M4.1, L/360

Design Criteria

Spans:	Simple span
Loads:	Live load = 40 psf and dead load = 20 psf
Deflection limits:	L/360 under live load and L/240 under total load
Sheathing:	3/4 in. nailed-glued oriented strand board (OSB) sheathing



Maximum Floor Spans

Joist depth	Joist series	Bare On centre spacing				1/2 in. gypsum ceiling On centre spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-11"	15'-0"	14'-6"	13'-5"	16'-5"	15'-5"	14'-6"	13'-5"
	NI-40x	17'-0"	16'-0"	15'-5"	14'-10"	17'-5"	16'-5"	15'-10"	14'-11"
	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-7"	16'-7"	16'-0"	15'-4"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
11-7/8"	NI-20	17'-11"	16'-11"	16'-3"	15'-8"	18'-7"	17'-5"	16'-10"	16'-1"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-7"	19'-11"	18'-6"	17'-9"	17'-0"
	NI-60	19'-7"	18'-2"	17'-6"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
	NI-80	21'-1"	19'-6"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
	NI-90	21'-6"	19'-10"	18'-11"	17'-11"	22'-0"	20'-4"	19'-5"	18'-4"
14"	NI-40x	21'-5"	19'-11"	18'-11"	18'-0"	22'-1"	20'-7"	19'-7"	18'-7"
	NI-60	21'-10"	20'-2"	19'-3"	18'-3"	22'-6"	20'-10"	19'-11"	18'-10"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
	NI-90	23'-10"	22'-1"	21'-0"	19'-10"	24'-5"	22'-7"	21'-6"	20'-4"
16"	NI-60	23'-9"	22'-0"	21'-0"	19'-10"	24'-6"	22'-9"	21'-8"	20'-7"
	NI-80	25'-6"	23'-7"	22'-5"	21'-2"	26'-2"	24'-3"	23'-1"	21'-10"
	NI-90	26'-0"	24'-0"	22'-10"	21'-6"	26'-7"	24'-8"	23'-5"	22'-2"

Joist depth	Joist series	Mid-span blocking with 1x4 inch strap On centre spacing				Mid-span blocking and 1/2 in. gypsum ceiling On centre spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	17'-1"	15'-5"	14'-6"	13'-5"	17'-1"	15'-5"	14'-6"	13'-5"
	NI-40x	18'-8"	17'-6"	16'-7"	14'-11"	19'-2"	17'-8"	16'-7"	14'-11"
	NI-60	18'-11"	17'-8"	16'-10"	15'-7"	19'-5"	18'-0"	16'-10"	15'-7"
	NI-80	20'-3"	18'-10"	17'-11"	17'-2"	20'-8"	19'-3"	18'-4"	17'-5"
11-7/8"	NI-20	20'-3"	18'-8"	17'-6"	16'-1"	20'-7"	18'-8"	17'-6"	16'-1"
	NI-40x	21'-10"	20'-4"	19'-0"	17'-0"	22'-5"	20'-10"	19'-0"	17'-0"
	NI-60	22'-1"	20'-7"	19'-8"	18'-7"	22'-8"	21'-2"	20'-3"	18'-8"
	NI-80	23'-8"	22'-0"	20'-11"	19'-10"	24'-1"	22'-6"	21'-6"	20'-4"
	NI-90	24'-1"	22'-5"	21'-4"	20'-2"	24'-7"	22'-11"	21'-10"	20'-8"
14"	NI-40x	24'-5"	22'-9"	20'-11"	18'-8"	25'-1"	22'-11"	20'-11"	18'-8"
	NI-60	24'-10"	23'-2"	22'-1"	20'-10"	25'-6"	23'-10"	22'-9"	21'-4"
	NI-80	26'-6"	24'-8"	23'-6"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"
	NI-90	27'-0"	25'-1"	23'-11"	22'-7"	27'-6"	25'-8"	24'-6"	23'-2"
16"	NI-60	27'-3"	25'-5"	24'-3"	22'-11"	28'-0"	26'-2"	25'-0"	23'-1"
	NI-80	29'-1"	27'-1"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
	NI-90	29'-7"	27'-6"	26'-2"	24'-9"	30'-2"	28'-2"	26'-10"	25'-5"

Notes:

- The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.

The construction details for residential designs are prone to changes.

Details released after April 2014 supersedes N-C301


Installation must comply with latest documentation on I-Joist and other Nordic products from the <http://nordic.ca/>

This document does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of its component based on the design criteria and loadings shown on the calculation sheets.

(Nordic Request 1810-095)

NORDIC ENGINEERED WOOD

INSTALLATION GUIDE FOR RESIDENTIAL FLOORS



Distributed by:



SAFETY AND CONSTRUCTION PRECAUTIONS



Do not walk on I-joists until fully fastened and braced, or serious injuries can result.



Never stack building materials over unfastened I-joists. Once sheathed, do not over-stress I-joist with concentrated loads from building materials.

WARNING

I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.

Avoid Accidents by Following these Important Guidelines:

1. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-bridging at joist ends. When I-joists are applied continuously over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
 - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.
 - Or, sheathing (temporary or permanent) can be nailed to the top flanges of the first 4 feet of I-joists at the end of the bay.
3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bridging.
4. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
5. Never install a damaged I-joist.

Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.

STORAGE AND HANDLING GUIDELINES

1. Bundle wrap can be slippery when wet. Avoid walking on wrapped bundles.
2. Store, stack, and handle I-joists vertically and level only.
3. Always stack and handle I-joists in the upright position only.
4. Do not store I-joists in direct contact with the ground and/or flammable.
5. Protect I-joists from weather, and use spacers to separate bundles.
6. Bundled units should be kept intact until time of installation.
 - Pick I-joists in bundles as shipped by the supplier.
 - Orient the bundles so that the webs of the I-joists are vertical.
 - Pick the bundles at the 5th points, using a spreader bar if necessary.
8. Do not handle I-joists in a horizontal orientation.
9. NEVER USE OR TRY TO REPAIR A DAMAGED I-JOIST.




INSTALLING NORDIC I-JOISTS


1. Before laying out floor system components, verify that I-joist flange widths match hanger widths. If not, contact your supplier.
2. Except for cutting to length, I-joist flanges should never be cut, drilled, or notched.
3. Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple-span joists must be level.
5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings.
6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement.
7. Leave a 1/16-inch gap between the I-joist end and a header.
8. Concentrated loads greater than those that can normally be expected in residential construction should only be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment and security cameras. Never suspend unbraced or heavy loads from the I-joist's bottom flange. Whenever possible, suspend all concentrated loads from the top of the I-joist. Or, attach the load to blocking that has been securely fastened to the I-joist webs.
9. Never install I-joists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or I-joist blocking panels.
11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (cripple members) to transfer gravity loads through the floor system to the wall or foundation below.
12. Due to shrinkage, common framing lumber set on edge may never be used as blocking or rim boards. I-joist blocking panels or other engineered wood products – such as rim board – must be cut to fit between the I-joists, and an I-joist-compatible depth selected.
13. Provide permanent lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly, support the bottom flange of all cantilevered I-joists at the end support next to the cantilever extension. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used.
14. If square-edge panels are used, edges must be supported between I-joists with 2x4 blocking. Glue panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed.
15. Nail spacing: Space nails installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.

FIGURE 1
TYPICAL NORDIC I-JOIST FLOOR FRAMING AND CONSTRUCTION DETAILS

Some framing requirements such as erection bracing and blocking panels have been omitted for clarity.




All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.125" dia.) common spiral nails may be substituted for 2-1/2" (0.120" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
Ni Joists	3,300

*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
1-1/8" Rim Board Plus	8,090

*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
Ni Joists	3,300

*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.



Pair of Squash Blocks	Maximum Factored Uniform Vertical Load* (plf)
2x Lumber	5,500
1-1/8" Rim Board Plus	4,300

*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.

The construction details for residential designs are prone to changes.

Details released after April 2014 supersede N-C301

Installation must comply with latest documentation on I-Joist and other Nordic products from the <http://nordic.ca/>

This document does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of its component based on the design criteria and loadings shown on the calculation sheets.

MAXIMUM FLOOR SPANS

- Maximum clear spans applicable to single-span or multiple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.35L + 1.25D. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of L/480. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less, or 3/4 inch for joist spacing of 24 inches. Adhesive shall meet the requirements given in C085-71.26 Standard. No concrete topping or bridging element was assumed. Increased spans may be achieved with the use of gypsum and/or a row of blocking at mid-span.
- Minimum bearing length shall be 1-3/4 inches for the end bearings, and 3-1/2 inches for the intermediate bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniform loads, an engineering analysis may be required based on the use of the design properties.
- Tables are based on Unit States Design per CAN/CSA C085-09 Standard, and NBC 2010.
- SI units conversion: 1 inch = 25.4 mm
1 foot = 0.305 m


MAXIMUM FLOOR SPANS FOR NORDIC I-JOISTS SIMPLE AND MULTIPLE SPANS

Joist Depth	Joist Series	Simple spans					Multiple spans				
		On centre spacing					On centre spacing				
		12"	15"	19.2"	24"		12"	15"	19.2"	24"	
9-1/2"	Ni-20	15'-1"	14'-2"	13'-9"	12'-5"	14'-3"	13'-4"	13'-0"	11'-7"	14'-7"	
	Ni-40x	16'-1"	15'-2"	14'-8"	14'-9"	17'-5"	16'-5"	15'-10"	14'-5"	15'-5"	
	Ni-60	16'-3"	15'-4"	14'-10"	14'-11"	17'-7"	16'-7"	16'-0"	14'-6"	16'-6"	
	Ni-80	17'-1"	16'-1"	15'-4"	15'-7"	18'-7"	17'-4"	16'-9"	15'-2"	17'-2"	
11-7/8"	Ni-20	16'-11"	16'-0"	15'-5"	15'-4"	18'-4"	17'-3"	16'-8"	16'-7"	17'-7"	
	Ni-40x	18'-1"	17'-0"	16'-5"	16'-8"	20'-0"	18'-9"	17'-9"	17'-7"	18'-7"	
	Ni-60	18'-4"	17'-3"	16'-7"	16'-9"	20'-3"	19'-0"	18'-0"	18'-0"	19'-0"	
	Ni-80	19'-6"	18'-0"	17'-4"	17'-5"	21'-6"	19'-11"	19'-0"	19'-0"	19'-8"	
14"	Ni-20	19'-9"	18'-3"	17'-4"	17'-7"	21'-9"	20'-2"	19'-3"	19'-11"	20'-2"	
	Ni-40x	20'-2"	18'-7"	17'-10"	17'-11"	22'-3"	20'-7"	19'-8"	19'-8"	19'-9"	
	Ni-60	20'-4"	18'-9"	17'-11"	18'-0"	22'-5"	20'-9"	19'-10"	19'-10"	20'-5"	
	Ni-80	21'-1"	19'-1"	18'-1"	18'-2"	22'-7"	20'-11"	20'-10"	20'-10"	20'-10"	
16"	Ni-20	21'-7"	20'-0"	19'-1"	19'-2"	23'-10"	22'-1"	21'-1"	21'-10"	21'-10"	
	Ni-40x	21'-11"	20'-3"	19'-4"	19'-5"	24'-3"	22'-5"	21'-5"	22'-2"	22'-2"	
	Ni-60	22'-3"	20'-8"	19'-9"	19'-9"	24'-9"	22'-10"	21'-10"	21'-10"	21'-10"	
	Ni-80	22'-7"	20'-11"	19'-11"	20'-0"	25'-0"	23'-1"	22'-0"	22'-0"	22'-0"	
18"	Ni-20	22'-3"	20'-8"	19'-9"	19'-10"	24'-7"	22'-7"	21'-7"	22'-9"	22'-9"	
	Ni-40x	23'-6"	21'-9"	20'-9"	20'-10"	26'-0"	24'-0"	22'-11"	23'-9"	23'-9"	
	Ni-60	23'-11"	22'-1"	21'-1"	21'-2"	26'-5"	24'-5"	23'-3"	24'-1"	24'-1"	
	Ni-80	24'-3"	22'-6"	21'-5"	21'-8"	26'-11"	24'-10"	23'-9"	23'-9"	23'-9"	
20"	Ni-20	24'-3"	22'-9"	21'-9"	21'-10"	27'-3"	25'-2"	24'-0"	24'-10"	24'-10"	
	Ni-80	24'-3"	22'-9"	21'-9"	21'-10"	27'-3"	25'-2"	24'-0"	24'-10"	24'-10"	

CCMC EVALUATION REPORT 13032-R

I-JOIST HANGERS

- Hangers shown illustrate the three most commonly used metal hangers to support I-joists.
- All nailing must meet the hanger manufacturer's recommendations.
- Hangers should be selected based on the joist depth, flange width and load capacity based on the maximum spans.
- Web stiffeners are required when the sides of the hangers do not laterally brace the top flange of the I-joist.




WEB STIFFENERS

RECOMMENDATIONS:

- A bearing stiffener is required in all engineered applications with factored reactions greater than shown in the I-joist properties table found in the I-joist Construction Guide (C101). The gap between the stiffener and the flange is at the top.
- A bearing stiffener is required when the I-joist is supported in a hanger and the sides of the hanger do not extend up to, and support, the top flange. The gap between the stiffener and flange is at the top.
- A load stiffener is required at locations where a factored concentrated load greater than 2,370 lbs is applied to the top flange between supports, or in the case of a cantilever, anywhere between the cantilever tip and the support. These values are for standard term load duration, and may be adjusted for other load durations as permitted by the code. The gap between the stiffener and the flange is at the bottom.

SI units conversion: 1 inch = 25.4 mm

FIGURE 2
WEB STIFFENER INSTALLATION DETAILS



STIFFENER SIZE REQUIREMENTS

Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width

NORDIC I-JOIST SERIES

Series	Depth	Flange Width	Weight	Spacing	Notes
Ni-20	9-1/2"	15"	2.0 lbs/ft	12"	5-PF No.2
Ni-40x	11-7/8"	17"	3.0 lbs/ft	12"	5-PF No.2
Ni-60	14"	19"	4.0 lbs/ft	12"	5-PF No.2
Ni-80	16"	21"	5.0 lbs/ft	12"	5-PF No.2
Ni-90	18"	23"	6.0 lbs/ft	12"	5-PF No.2
Ni-90x	18"	23"	6.0 lbs/ft	12"	5-PF No.2

Chantiers Chibougon Ltd. harvests its own trees, which enables Nordic products to adhere to strict quality control procedures throughout the manufacturing process. Every phase of the operation, from forest to the finished product, reflects our commitment to quality.

Nordic Engineered Wood I-Joists use only finger-jointed black spruce lumber in their flanges, ensuring consistent quality, superior strength, and longer span carrying capacity.

(Nordic Request 1810-095)



1a Transfer load from above to bearing below. Install squish blocks per detail 1d. Match bearing area of blocks below to post above.

1b Use single I-joist for loads up to 3,300 plf, double I-joists for loads up to 6,600 plf (filler block not required). Attach I-joist to top plate using 2-1/2" nails at 6" o.c.

1c Load bearing wall above shall align vertically with the bearing below. Other conditions, such as offset bearing walls, are not covered by this detail.

1d Backer block (use if longer load exceeds 360 lbs) Before installing a backer block to a double I-joist, drive three additional 3" nails through the webs and filler block where the backer block will fit. Clinch. Install backer right to top flange. Use twelve 3" nails, clinched when possible. Maximum factored resistance for hanger for this detail = 1,620 lbs.

1e Double I-joist header

1f Top- or face-mount hanger

1g Filler block per detail 1p

1h Backer block required (both sides for face-mount hangers)

1i For hanger capacity see hanger manufacturer's recommendations. Verify double I-joist capacity to support concentrated loads.

1j BACKER BLOCKS (Blocks must be long enough to permit required nailing without spilling)

Flange Width	Material Thickness Required*	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid sawn lumber and wood structural panels conforming to CAN/CSA-C0325 or CAN/CSA-C0437 Standard.

** For face-mount hangers use not joist depth minus 3-1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use not depth minus 4-1/4".

1k Nordic Lumber or SCL

1l Top- or face-mount hanger installed per manufacturer's recommendations

1m Top-mount hanger installed per manufacturer's recommendations

1n Multiple I-joist header with full depth filler block shown. Nordic Lumber or SCL headers may also be used. Vary double I-joist capacity to support concentrated loads.

1o Do not bowl-cut joist beyond inside face of wall

1p Filler block

1q Filler block

1r Lumber 2x4 min., extend block to face of adjacent web. Two 2-1/2" spigot nails from each web to lumber piece, alternate on opposite side.

1s One 2-1/2" nails at top and bottom flange

1t Two 2-1/2" nails from each web to lumber piece

1u Two 2-1/2" nails from each web to lumber piece

1v One 2-1/2" nails one side only

1w One 2-1/2" nails at 6" o.c.

1x One 2-1/2" nails at 6" o.c.

1y One 2-1/2" nails at 6" o.c.

1z One 2-1/2" nails at 6" o.c.

1aa One 2-1/2" nails at 6" o.c.

1ab One 2-1/2" nails at 6" o.c.

1ac One 2-1/2" nails at 6" o.c.

1ad One 2-1/2" nails at 6" o.c.

1ae One 2-1/2" nails at 6" o.c.

1af One 2-1/2" nails at 6" o.c.

1ag One 2-1/2" nails at 6" o.c.

1ah One 2-1/2" nails at 6" o.c.

1ai One 2-1/2" nails at 6" o.c.

1aj One 2-1/2" nails at 6" o.c.

1ak One 2-1/2" nails at 6" o.c.

1al One 2-1/2" nails at 6" o.c.

1am One 2-1/2" nails at 6" o.c.

1an One 2-1/2" nails at 6" o.c.

1ao One 2-1/2" nails at 6" o.c.

1ap One 2-1/2" nails at 6" o.c.

1aq One 2-1/2" nails at 6" o.c.

1ar One 2-1/2" nails at 6" o.c.

1as One 2-1/2" nails at 6" o.c.

1at One 2-1/2" nails at 6" o.c.

1au One 2-1/2" nails at 6" o.c.

1av One 2-1/2" nails at 6" o.c.

1aw One 2-1/2" nails at 6" o.c.

1ax One 2-1/2" nails at 6" o.c.

1ay One 2-1/2" nails at 6" o.c.

1az One 2-1/2" nails at 6" o.c.

1ba One 2-1/2" nails at 6" o.c.

1bb One 2-1/2" nails at 6" o.c.

1bc One 2-1/2" nails at 6" o.c.

1bd One 2-1/2" nails at 6" o.c.

1be One 2-1/2" nails at 6" o.c.

1bf One 2-1/2" nails at 6" o.c.

1bg One 2-1/2" nails at 6" o.c.

1bh One 2-1/2" nails at 6" o.c.

1bi One 2-1/2" nails at 6" o.c.

1bj One 2-1/2" nails at 6" o.c.

1bk One 2-1/2" nails at 6" o.c.

1bl One 2-1/2" nails at 6" o.c.

1bm One 2-1/2" nails at 6" o.c.

1bn One 2-1/2" nails at 6" o.c.

1bo One 2-1/2" nails at 6" o.c.

1bp One 2-1/2" nails at 6" o.c.

1bq One 2-1/2" nails at 6" o.c.

1br One 2-1/2" nails at 6" o.c.

1bs One 2-1/2" nails at 6" o.c.

1bt One 2-1/2" nails at 6" o.c.

1bu One 2-1/2" nails at 6" o.c.

1bv One 2-1/2" nails at 6" o.c.

1bw One 2-1/2" nails at 6" o.c.

1bx One 2-1/2" nails at 6" o.c.

1by One 2-1/2" nails at 6" o.c.

1bz One 2-1/2" nails at 6" o.c.

1ca One 2-1/2" nails at 6" o.c.

1cb One 2-1/2" nails at 6" o.c.

1cc One 2-1/2" nails at 6" o.c.

1cd One 2-1/2" nails at 6" o.c.

1ce One 2-1/2" nails at 6" o.c.

1cf One 2-1/2" nails at 6" o.c.

1cg One 2-1/2" nails at 6" o.c.

1ch One 2-1/2" nails at 6" o.c.

1ci One 2-1/2" nails at 6" o.c.

1cj One 2-1/2" nails at 6" o.c.

1ck One 2-1/2" nails at 6" o.c.

1cl One 2-1/2" nails at 6" o.c.

1cm One 2-1/2" nails at 6" o.c.

1cn One 2-1/2" nails at 6" o.c.

1co One 2-1/2" nails at 6" o.c.

1cp One 2-1/2" nails at 6" o.c.

1cq One 2-1/2" nails at 6" o.c.

1cr One 2-1/2" nails at 6" o.c.

1cs One 2-1/2" nails at 6" o.c.

1ct One 2-1/2" nails at 6" o.c.

1cu One 2-1/2" nails at 6" o.c.

1cv One 2-1/2" nails at 6" o.c.

1cw One 2-1/2" nails at 6" o.c.

1cx One 2-1/2" nails at 6" o.c.

1cy One 2-1/2" nails at 6" o.c.

1cz One 2-1/2" nails at 6" o.c.

1da One 2-1/2" nails at 6" o.c.

1db One 2-1/2" nails at 6" o.c.

1dc One 2-1/2" nails at 6" o.c.

1dd One 2-1/2" nails at 6" o.c.

1de One 2-1/2" nails at 6" o.c.

1df One 2-1/2" nails at 6" o.c.

1dg One 2-1/2" nails at 6" o.c.

1dh One 2-1/2" nails at 6" o.c.

1di One 2-1/2" nails at 6" o.c.

1dj One 2-1/2" nails at 6" o.c.

1dk One 2-1/2" nails at 6" o.c.

1dl One 2-1/2" nails at 6" o.c.

1dm One 2-1/2" nails at 6" o.c.

1dn One 2-1/2" nails at 6" o.c.

1do One 2-1/2" nails at 6" o.c.

1dp One 2-1/2" nails at 6" o.c.

1dq One 2-1/2" nails at 6" o.c.

1dr One 2-1/2" nails at 6" o.c.

1ds One 2-1/2" nails at 6" o.c.

1dt One 2-1/2" nails at 6" o.c.

1du One 2-1/2" nails at 6" o.c.

1dv One 2-1/2" nails at 6" o.c.

1dw One 2-1/2" nails at 6" o.c.

1dx One 2-1/2" nails at 6" o.c.

1dy One 2-1/2" nails at 6" o.c.

1dz One 2-1/2" nails at 6" o.c.

1ea One 2-1/2" nails at 6" o.c.

1eb One 2-1/2" nails at 6" o.c.

1ec One 2-1/2" nails at 6" o.c.

1ed One 2-1/2" nails at 6" o.c.

1ee One 2-1/2" nails at 6" o.c.

1ef One 2-1/2" nails at 6" o.c.

1eg One 2-1/2" nails at 6" o.c.

1eh One 2-1/2" nails at 6" o.c.

1ei One 2-1/2" nails at 6" o.c.

1ej One 2-1/2" nails at 6" o.c.

1ek One 2-1/2" nails at 6" o.c.

1el One 2-1/2" nails at 6" o.c.

1em One 2-1/2" nails at 6" o.c.

1en One 2-1/2" nails at 6" o.c.

1eo One 2-1/2" nails at 6" o.c.

1ep One 2-1/2" nails at 6" o.c.

1eq One 2-1/2" nails at 6" o.c.

1er One 2-1/2" nails at 6" o.c.

1es One 2-1/2" nails at 6" o.c.

1et One 2-1/2" nails at 6" o.c.

1eu One 2-1/2" nails at 6" o.c.

1ev One 2-1/2" nails at 6" o.c.

1ew One 2-1/2" nails at 6" o.c.

1ex One 2-1/2" nails at 6" o.c.

1ey One 2-1/2" nails at 6" o.c.

1ez One 2-1/2" nails at 6" o.c.

1fa One 2-1/2" nails at 6" o.c.

1fb One 2-1/2" nails at 6" o.c.

1fc One 2-1/2" nails at 6" o.c.

1fd One 2-1/2" nails at 6" o.c.

1fe One 2-1/2" nails at 6" o.c.

1ff One 2-1/2" nails at 6" o.c.

1fg One 2-1/2" nails at 6" o.c.

1fh One 2-1/2" nails at 6" o.c.

1fi One 2-1/2" nails at 6" o.c.

1fj One 2-1/2" nails at 6" o.c.

1fk One 2-1/2" nails at 6" o.c.

1fl One 2-1/2" nails at 6" o.c.

1fm One 2-1/2" nails at 6" o.c.

1fn One 2-1/2" nails at 6" o.c.

1fo One 2-1/2" nails at 6" o.c.

1fp One 2-1/2" nails at 6" o.c.

1fq One 2-1/2" nails at 6" o.c.

1fr One 2-1/2" nails at 6" o.c.

1fs One 2-1/2" nails at 6" o.c.

1ft One 2-1/2" nails at 6" o.c.

1fu One 2-1/2" nails at 6" o.c.

1fv One 2-1/2" nails at 6" o.c.

1fw One 2-1/2" nails at 6" o.c.

1fx One 2-1/2" nails at 6" o.c.

1fy One 2-1/2" nails at 6" o.c.

1fz One 2-1/2" nails at 6" o.c.

1ga One 2-1/2" nails at 6" o.c.

1gb One 2-1/2" nails at 6" o.c.

1gc One 2-1/2" nails at 6" o.c.

1gd One 2-1/2" nails at 6" o.c.

1ge One 2-1/2" nails at 6" o.c.

1gf One 2-1/2" nails at 6" o.c.

1gg One 2-1/2" nails at 6" o.c.

1gh One 2-1/2" nails at 6" o.c.

1gi One 2-1/2" nails at 6" o.c.

1gj One 2-1/2" nails at 6" o.c.

1gk One 2-1/2" nails at 6" o.c.

1gl One 2-1/2" nails at 6" o.c.

1gm One 2-1/2" nails at 6" o.c.

1gn One 2-1/2" nails at 6" o.c.

1go One 2-1/2" nails at 6" o.c.

1gp One 2-1/2" nails at 6" o.c.

1gq One 2-1/2" nails at 6" o.c.

1gr One 2-1/2" nails at 6" o.c.

1gs One 2-1/2" nails at 6" o.c.

1gt One 2-1/2" nails at 6" o.c.

1gu One 2-1/2" nails at 6" o.c.

1gv One 2-1/2" nails at 6" o.c.

1gw One 2-1/2" nails at 6" o.c.

1gx One 2-1/2" nails at 6" o.c.

1gy One 2-1/2" nails at 6" o.c.

1gz One 2-1/2" nails at 6" o.c.

1ha One 2-1/2" nails at 6" o.c.

1hb One 2-1/2" nails at 6" o.c.

1hc One 2-1/2" nails at 6" o.c.

1hd One 2-1/2" nails at 6" o.c.

1he One 2-1/2" nails at 6" o.c.

1hf One 2-1/2" nails at 6" o.c.

1hg One 2-1/2" nails at 6" o.c.

1hh One 2-1/2" nails at 6" o.c.

1hi One 2-1/2" nails at 6" o.c.

1hj One 2-1/2" nails at 6" o.c.

1hk One 2-1/2" nails at 6" o.c.

1hl One 2-1/2" nails at 6" o.c.

1hm One 2-1/2" nails at 6" o.c.

1hn One 2-1/2" nails at 6" o.c.

1ho One 2-1/2" nails at 6" o.c.

1hp One 2-1/2" nails at 6" o.c.

1hq One 2-1/2" nails at 6" o.c.

1hr One 2-1/2" nails at 6" o.c.

1hs One 2-1/2" nails at 6" o.c.

1ht One 2-1/2" nails at 6" o.c.

1hu One 2-1/2" nails at 6" o.c.

1hv One 2-1/2" nails at 6" o.c.

1hw One 2-1/2" nails at 6" o.c.

1hx One 2-1/2" nails at 6" o.c.

1hy</

The construction details for residential designs are prone to changes.

Details released after April 2014 supersedes N-C301


Installation must comply with latest documentation on I-Joist and other Nordic products from the <http://nordic.ca/>

This document does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of its component based on the design criteria and loadings shown on the calculation sheets.


(Nordic Request 1810-095)



CANTILEVER DETAILS FOR BALCONIES (NO WALL LOAD)



3b LUMBER CANTILEVER DETAIL FOR BALCONIES (No Wall Load)



CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)






FIGURE 4 (continued)



CANTILEVER REINFORCEMENT METHODS ALLOWED

Joint Depth (in.)	Roof Truss Span (ft)	ROOF LOADING (UNFACTORED)							
		LL = 30 psf, DL = 15 psf				LL = 40 psf, DL = 15 psf			
		Joint Spacing (in.)				Joint Spacing (in.)			
		12	16	19.2	24	12	16	19.2	24
9-1/2	26	N	N	1	2	N	1	2	X
	28	N	N	1	X	N	1	2	X
	30	N	1	1	X	N	1	2	X
	32	N	1	2	X	N	2	X	X
	34	N	1	2	X	N	2	X	X
11-7/8	26	N	1	2	X	N	1	2	X
	28	N	1	2	X	N	1	2	X
	30	N	1	2	X	N	1	2	X
	32	N	1	2	X	N	1	2	X
	34	N	1	2	X	N	1	2	X
14	26	N	1	2	X	N	1	2	X
	28	N	1	2	X	N	1	2	X
	30	N	1	2	X	N	1	2	X
	32	N	1	2	X	N	1	2	X
	34	N	1	2	X	N	1	2	X
16	26	N	1	2	X	N	1	2	X
	28	N	1	2	X	N	1	2	X
	30	N	1	2	X	N	1	2	X
	32	N	1	2	X	N	1	2	X
	34	N	1	2	X	N	1	2	X

- N = No reinforcement required.
- N1 = NI reinforced with 3/4" wood structural panel on one side only.
- N2 = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
- X = Try a deeper joist or closer spacing.
- Maximum design load shall be 15 psf roof dead load, 55 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0" maximum width window or door openings.
- For larger openings, or multiple 3'-0" wide openings spaced less than 6'-0" o.c., additional joints beneath the opening's cripple studs may be required.
- Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
- For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge beam, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.
- Cantilevered joints supporting glider trusses or roof beams may require additional reinforcing.

BRICK CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)






FIGURE 5 (continued)



BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED

Joint Depth (in.)	Roof Truss Span (ft)	ROOF LOADING (UNFACTORED)							
		LL = 30 psf, DL = 15 psf				LL = 40 psf, DL = 15 psf			
		Joint Spacing (in.)				Joint Spacing (in.)			
		12	16	19.2	24	12	16	19.2	24
9-1/2	26	1	X	X	X	2	X	X	X
	28	1	X	X	X	2	X	X	X
	30	1	X	X	X	2	X	X	X
	32	2	X	X	X	2	X	X	X
	34	2	X	X	X	2	X	X	X
11-7/8	26	1	X	X	X	2	X	X	X
	28	1	X	X	X	2	X	X	X
	30	1	X	X	X	2	X	X	X
	32	1	X	X	X	2	X	X	X
	34	1	X	X	X	2	X	X	X
14	26	1	X	X	X	2	X	X	X
	28	1	X	X	X	2	X	X	X
	30	1	X	X	X	2	X	X	X
	32	1	X	X	X	2	X	X	X
	34	1	X	X	X	2	X	X	X
16	26	1	X	X	X	2	X	X	X
	28	1	X	X	X	2	X	X	X
	30	1	X	X	X	2	X	X	X
	32	1	X	X	X	2	X	X	X
	34	1	X	X	X	2	X	X	X

- N = No reinforcement required.
- N1 = NI reinforced with 3/4" wood structural panel on one side only.
- N2 = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
- X = Try a deeper joist or closer spacing.
- Maximum design load shall be 15 psf roof dead load, 55 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0" maximum width window or door openings.
- For larger openings, or multiple 3'-0" wide openings spaced less than 6'-0" o.c., additional joints beneath the opening's cripple studs may be required.
- Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
- For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge beam, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.
- Cantilevered joints supporting glider trusses or roof beams may require additional reinforcing.

The construction details for residential designs are prone to changes.

Details released after April 2014 supersedes N-C301

Installation must comply with latest documentation on I-Joist and other Nordic products from the <http://nordic.ca/>

This document does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of its component based on the design criteria and loadings shown on the calculation sheets.

WEB HOLES

RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

- The distance between the inside edge of the support and the centreline of any hole or duct chase opening shall be in compliance with the requirements of Table 1 or 2, respectively.
- I-Joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.
- Whenever possible, field-cut holes should be centred on the middle of the web.
- The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-Joist web shall equal the clear distance between the flanges of the I-Joist minus 1/4 inch. A minimum of 1/8 inch shall always be maintained between the top or bottom of the hole or opening and the adjacent I-Joist flange.
- The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
- Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the largest side of the largest rectangular hole or duct chase opening) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
- A knockout is not considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
- Holes measuring 1-1/2 inches or smaller shall be permitted anywhere in a confirmed section of a joist. Holes of greater size may be permitted subject to verification.
- A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
- All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.
- Limit three maximum size holes per span, of which one may be a duct chase opening.
- A group of round holes at approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

TABLE 1
LOCATION OF CIRCULAR HOLES IN JOIST WEBS
Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf

Joist Depth	Joist Series	Minimum distance from inside face of any support to centre of hole (8 in.)												Span adjustment factor
		2	3	4	5	6	7	8	9	10	11	12	13	
9-1/2"	N100	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N140	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N170	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N200	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
11-7/8"	N100	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N140	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N170	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N200	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
14"	N100	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N140	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N170	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N200	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
16"	N100	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N140	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N170	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0
	N200	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2	1.0

1. Above table may be used for I-Joist spacing of 24 inches on centre or less.
2. Hole location distance is measured from inside face of support to centre of hole.
3. Distances in this chart are based on uniformly loaded joists.

OPTIONAL:


The above table is based on the I-Joist used at its maximum span. If the I-Joist is placed at less than its full maximum span (see Maximum Floor Span), the minimum distance from the centreline of the hole to the face of any support (D) as given above may be reduced as follows:

$$\text{Reduced } D = \frac{\text{Actual Span}}{\text{Maximum Span}} \times D$$

Where:

- Reduced = Distance from the inside face of any support to centre of hole, reduced for less than maximum span applications (D).
- Actual = The actual measured span distance between the inside faces of supports (S).
- Span Adjustment Factor given in this table.
- The minimum distance from the inside face of any support to centre of hole from this table.
- If Actual is greater than 1, use 1 in the above calculation for Actual.

FIGURE 7
FIELD-CUT HOLE LOCATOR



A knockout is NOT considered a hole, may be utilized wherever it occurs and may be ignored for purposes of calculating minimum distances between holes.

Knockouts are predrilled holes provided for the contractor's convenience to install electrical or small plumbing lines. They are 1-1/2 inches in diameter, and are spaced 15 inches on centre along the length of the I-joist. Where possible, it is preferable to use knockouts instead of field-cut holes.

Never drill, cut or notch the flange, or over-cut the web.
Holes in webs should be cut with a sharp saw.

For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Starting the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the I-joist.

TABLE 2
DUCT CHASE OPENING SIZES AND LOCATIONS — Simple Span Only

Joist Depth	Joist Series	Minimum distance from inside face of any support to centre of opening (8 in.)											
		2	3	4	5	6	7	8	9	10	11	12	13
9-1/2"	N100	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N140	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N170	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N200	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
11-7/8"	N100	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N140	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N170	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N200	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
14"	N100	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N140	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N170	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N200	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
16"	N100	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N140	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N170	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2
	N200	0.7	1.2	2.0	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2

1. Above table may be used for I-Joist spacing of 24 inches on centre or less.
2. Duct chase opening location distance is measured from inside face of support to centre of opening.
3. The above table is based on simple span joists only. For other applications, consult your local distributor.
4. Distances are based on uniform loaded floor joists that meet the span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/400. For other applications, consult your local distributor.

INSTALLING THE GLUED FLOOR SYSTEM

- Wipe any mud, dirt, water, or ice from I-Joist flanges before gluing.
- Snap a chalk line across the I-joists four feet from the wall for panel edge alignment and as a boundary for spreading glue.
- Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from the glue manufacturer.
- Lay the first panel with tongue side to the wall, and nail in place. This protects the tongue of the next panel from damage when tapped into place with a block and sledgehammer.
- Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-Joist. Apply glue in a wavy pattern on wide areas, such as with double I-joists.
- Apply two lines of glue on I-joists where panel ends butt to assure proper gluing of each end.
- After the first row of panels is in place, spread glue in the groove of one or two panels at a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying a thinner line (1/8 inch) than used on I-Joist flanges.
- Tap the second row of panels into place, using a block to protect groove edges.
- Stagger and joints in each succeeding row of panels. A 1/8-inch space between all end joints and 1/8 inch at all edges, including T&G edges, is recommended. (Use a spacer block or an 1/2" common nail to assure accurate and consistent spacing.)
- Complete all nailing of each panel before glue sets. Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 2" ring- or screw-shank nails for panels 3/4-inch thick or less, and 2-1/2" ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for diaphragm construction. The finished deck can be walked on right away and will carry construction loads without damage to the glue bond.

FASTENERS FOR SHEATHING AND SUBFLOORING⁽¹⁾

Maximum Joist Spacing (in.)	Minimum Panel Thickness (in.)	Nail Size and Type				Maximum Spacing of Fasteners	
		Common Wire or Spiral Nails	Ring Thread Nail or Screw	Staples		Edges	Inform. Supports
16	5/8	2"	1-3/4"	2"		6"	12"
20	5/8	2"	1-3/4"	2"		6"	12"
24	3/4	2"	1-3/4"	2"		6"	12"

- Fasteners of sheathing and subflooring shall conform to the above table.
- Staples shall not be less than 1/16-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
- Flooring screws shall not be less than 1/8-inch in diameter.
- Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
- Use only adhesives conforming to CAN/CSB-71.26 Standard, Adhesives for Field-Gluing Plywood to Lumber Framing for Floor System, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues check with panel manufacturer.


Ref.: NBC-CNBC, National Building Code of Canada 2010, Table 9.23.3.5.

IMPORTANT NOTE:


Floor sheathing must be field glued to the I-Joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-Joist spans must be verified with your local distributor.

RIM BOARD INSTALLATION DETAILS

(a) ATTACHMENT DETAILS WHERE RIM BOARDS ABUT



(b) TOE-NAIL CONNECTION AT RIM BOARD




DIAMANTIER
FLOORING

PRODUCT WARRANTY

Chantier Diamantier warrants that, in accordance with our specifications, Nordic products are free from manufacturing defect in material and workmanship.

Furthermore, Chantier Diamantier warrants that our products, when installed in accordance with our building and installation instructions, will meet or exceed our specifications for the lifetime of the structure.





Refer to the Installation Guide for Residential Floors for additional information.
CCMC EVALUATION REPORT 13032-R

WEB HOLE SPECIFICATIONS

RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

1. The distance between the inside edge of the support and the centreline of any hole or duct chase opening shall be in compliance with the requirements of Table 1 or 2, respectively.
2. I-joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.
3. Whenever possible, field-cut holes should be centred on the middle of the web.
4. The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the hole or opening and the adjacent I-joist flange.

5. The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
6. Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the longest side of the longest rectangular hole) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
7. A knockout is not considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
8. Holes measuring 1-1/2 inches or smaller are permitted anywhere in a cantilevered section of a joist. Holes of greater size may be permitted subject to verification.

9. A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
10. All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.
11. Limit three maximum size holes per span, of which one may be a duct chase opening.
12. A group of round holes of approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.




TABLE 1
LOCATION OF CIRCULAR HOLES IN JOIST WEBS

Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf

Joist Depth	Joist Series	Minimum Distance from Inside Face of Any Support to Centre of Hole (ft - in.)											
		Round Hole Diameter (in.)											
9-1/2"	NI-20	0-7"	1-6"	2-10"	4-3"	5-8"	6-0"	---	---	---	---	---	---
	NI-40x	0-7"	1-6"	3-0"	4-4"	6-0"	6-4"	---	---	---	---	---	---
	NI-60	1-3"	2-6"	4-0"	5-4"	7-0"	7-5"	---	---	---	---	---	---
	NI-70	2-0"	3-4"	5-0"	6-3"	8-0"	8-4"	---	---	---	---	---	---
	NI-80	2-3"	3-6"	5-0"	6-3"	8-0"	8-4"	---	---	---	---	---	---
11-7/8"	NI-20	0-7"	0-8"	1-0"	2-4"	3-8"	4-0"	5-0"	6-6"	7-9"	---	---	---
	NI-40x	0-7"	0-8"	1-3"	2-8"	4-0"	4-4"	5-5"	7-0"	8-4"	---	---	---
	NI-60	0-7"	1-8"	3-0"	4-3"	5-9"	6-0"	7-3"	8-10"	10-0"	---	---	---
	NI-70	1-3"	2-6"	4-0"	5-4"	6-9"	7-2"	8-4"	10-0"	11-2"	---	---	---
	NI-80	1-6"	2-10"	4-2"	5-6"	7-0"	7-5"	8-6"	10-3"	11-4"	---	---	---
14"	NI-40x	0-7"	0-8"	0-8"	1-0"	2-4"	2-9"	3-9"	5-2"	6-0"	6-6"	8-3"	10-2"
	NI-60	0-7"	0-8"	1-8"	3-0"	4-3"	4-8"	5-8"	7-2"	8-0"	8-8"	10-4"	11-9"
	NI-70	0-8"	1-10"	3-0"	4-5"	5-10"	6-2"	7-3"	8-9"	9-9"	10-4"	12-0"	13-5"
	NI-80	0-10"	2-0"	3-4"	4-9"	6-2"	6-5"	7-6"	9-0"	10-0"	10-8"	12-4"	13-9"
	NI-90x	0-7"	0-8"	0-8"	2-0"	3-9"	4-2"	5-5"	7-3"	8-5"	9-2"	---	---
16"	NI-60	0-7"	0-8"	0-8"	1-6"	2-10"	3-2"	4-2"	5-6"	6-4"	7-0"	8-5"	9-8"
	NI-70	0-7"	1-0"	2-3"	3-6"	4-10"	5-3"	6-3"	7-8"	8-6"	9-2"	10-8"	12-0"
	NI-80	0-7"	1-3"	2-6"	3-10"	5-3"	6-6"	6-6"	8-0"	9-0"	9-5"	11-0"	12-3"
	NI-90x	0-7"	0-8"	0-9"	2-0"	3-6"	4-0"	5-0"	6-9"	7-9"	8-4"	10-2"	11-6"
	NI-90x	0-7"	0-8"	0-9"	2-0"	3-6"	4-0"	5-0"	6-9"	7-9"	8-4"	10-2"	11-6"

1. Above table may be used for I-joist spacing of 24 inches on centre or less.
2. Hole location distance is measured from inside face of supports to centre of hole.
3. Distances in this chart are based on uniformly loaded joists.
4. The above table is based on the I-joists being used at their maximum spans. The minimum distance as given above may be reduced for shorter spans; contact your local distributor.



TABLE 2
DUCT CHASE OPENING SIZES AND LOCATIONS

Simple Span Only

Joist Depth	Joist Series	Minimum Distance from Inside Face of Supports to Centre of Opening (ft - in.)											
		Duct Chase Length (in.)											
9-1/2"	NI-20	4-1"	4-5"	4-10"	5-4"	5-8"	6-1"	6-6"	7-1"	7-5"	---	---	---
	NI-40x	5-3"	5-8"	6-0"	6-5"	6-10"	7-3"	7-8"	8-2"	8-6"	---	---	---
	NI-60	5-4"	5-9"	6-2"	6-7"	7-1"	7-5"	8-0"	8-3"	8-9"	---	---	---
	NI-70	5-1"	5-5"	5-10"	6-3"	6-7"	7-1"	7-6"	8-1"	8-4"	---	---	---
	NI-80	5-3"	5-8"	6-0"	6-5"	6-10"	7-3"	7-8"	8-2"	8-6"	---	---	---
11-7/8"	NI-20	5-9"	6-2"	6-6"	7-1"	7-5"	7-9"	8-3"	8-9"	9-4"	---	---	---
	NI-40x	6-8"	7-2"	7-6"	8-1"	8-6"	9-1"	9-6"	10-1"	10-9"	---	---	---
	NI-60	7-3"	7-8"	8-0"	8-6"	9-0"	9-3"	9-9"	10-3"	11-0"	---	---	---
	NI-70	7-1"	7-4"	7-9"	8-3"	8-7"	9-1"	9-6"	10-1"	10-4"	---	---	---
	NI-80	7-2"	7-7"	8-0"	8-5"	8-10"	9-3"	9-8"	10-2"	10-6"	---	---	---
14"	NI-40x	8-1"	8-7"	9-0"	9-6"	10-1"	10-7"	11-2"	12-0"	12-8"	---	---	---
	NI-60	8-9"	9-3"	9-8"	10-1"	10-6"	11-1"	11-6"	13-3"	13-0"	---	---	---
	NI-70	8-7"	9-1"	9-5"	9-10"	10-4"	10-8"	11-2"	11-7"	12-3"	---	---	---
	NI-80	9-0"	9-3"	9-9"	10-1"	10-7"	11-1"	11-6"	12-6"	12-6"	---	---	---
	NI-90x	9-4"	9-9"	10-3"	10-7"	11-1"	11-7"	12-1"	12-7"	13-2"	---	---	---
16"	NI-60	10-3"	10-8"	11-2"	11-6"	12-1"	12-6"	13-2"	14-1"	14-10"	---	---	---
	NI-70	10-1"	10-5"	11-0"	11-4"	11-10"	12-3"	12-8"	13-3"	14-0"	---	---	---
	NI-80	10-4"	10-9"	11-3"	11-9"	12-1"	12-7"	13-1"	13-8"	14-4"	---	---	---
	NI-90x	11-1"	11-10"	12-4"	12-10"	13-2"	13-7"	13-9"	14-4"	15-2"	---	---	---
	NI-90x	11-1"	11-10"	12-4"	12-10"	13-2"	13-7"	13-9"	14-4"	15-2"	---	---	---

1. Above table may be used for I-joist spacing of 24 inches on centre or less.
2. Duct chase opening location distance is measured from inside face of supports to centre of opening.
3. The above table is based on simple-span joists only. For other applications, contact your local distributor.
4. Distances are based on uniformly loaded floor joists that meet the span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480.
5. The above table is based on the I-joists being used at their maximum spans. The minimum distance as given above may be reduced for shorter spans; contact your local distributor.

FIGURE 7
FIELD-CUT HOLE LOCATOR



Knockouts are pre-scored holes provided for the contractor's convenience to install electrical or small plumbing lines. They are 1-1/2 inches in diameter, and are spaced 15 inches on centre along the length of the I-joist. Where possible, it is preferable to use knockouts instead of field-cut holes.

Never drill, cut or notch the flange, or over-cut the web.

Holes in webs should be cut with a sharp saw.

For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Starting the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the I-joist.

SAFETY AND CONSTRUCTION PRECAUTIONS



Do not walk on I-joists until fully fastened and braced, or serious injuries can result.



Never stack building materials over unshoed I-joists. Once sheathed, do not over-stress I-joists with concentrated loads from building materials.

WARNING: I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.

AVOID ACCIDENTS BY FOLLOWING THESE IMPORTANT GUIDELINES:

1. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-briding at joist ends. When I-joists are applied continuous over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
 - * Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.
 - * Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-briding.
4. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
5. Never install a damaged I-joist.

Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.



PRODUCT WARRANTY

Chantiers Chibougamau guarantees that, in accordance with our specifications, Nordic products are free from manufacturing defects in material and workmanship.

Furthermore, Chantiers Chibougamau warrants that our products, when utilized in accordance with our handling and installation instructions, will meet or exceed our specifications for the lifetime of the structure.


The construction details for residential designs are prone to changes.

Details released after September 2013 supersedes N-303

Installation must comply with latest documentation on I-Joist and other Nordic products from the <http://nordic.ca/>

This document does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of its component based on the design criteria and loadings shown on the calculation sheets.


(Nordic Request 1810-095)



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
NI Joists	3,300

*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.

2-1/2" nails at 6" o.c. to top plate (when used for lateral shear transfer, nail to bearing plate with same nailing as required for decking)



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
1-1/8" Rim Board Plus	8,090


*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.

One 2-1/2" wire or spiral nail at top and bottom flange

Attach rim board to top plate using 2-1/2" wire or spiral toe-nails at 6" o.c.

To avoid splitting flange, start nails at least 1-1/2" from end of I-joist. Nails may be driven at an angle to avoid splitting of bearing plate.

Minimum bearing length shall be 1-3/4" for the end bearings, and 3-1/2" for the intermediate bearings when applicable.





Pair of Squash Blocks	Maximum Factored Vertical Load per Pair of Squash Blocks (lbs)
2x Lumber	5,500
1-1/8" Rim Board Plus	8,500

3-1/2" wide
5-1/2" wide

4,300
6,600

Provide lateral bracing per detail 1a or 1b



Load bearing wall above shall align vertically with the bearing below. Other conditions, such as offset bearing walls, are not covered by this detail.

Blocking required over all interior supports under load-bearing walls or when floor joists are not continuous over support

NI blocking panel per detail 1a







1h Backer block (use if hanger load exceeds 340 lbs). Before installing a backer block to a double I-joist, drive three additional 3" nails through the web and filler block where the backer block will fit. Clinch. Install backer tight to top flange. Use twelve 3" nails, clinched when possible. Maximum factored resistance for hanger for this detail = 1,620 lbs.

BACKER BLOCKS (Blocks must be long enough to permit required nailing without splitting)


Flange Width	Material Thickness Required*	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid sawn lumber and wood structural panels conforming to CAN/CSA-O325 or CAN/CSA-O437 Standard.

** For face-mount hangers use net joist depth minus 3-1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4".




1p FILLER BLOCK REQUIREMENTS FOR DOUBLE I-JOIST CONSTRUCTION



- NOTES:
- Support back of I-joist web during nailing to prevent damage to web/flange connection.
 - Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
 - Filler block is required for joists for full length of span.
 - Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails can be clinched, only two nails per foot are required.
 - The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

Flange Size	Net Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2" 11-7/8" 14" 16"	2-1/8" x 6" 2-1/8" x 8" 2-1/8" x 10" 2-1/8" x 12"
3-1/2" x 1-1/2"	9-1/2" 11-7/8" 14" 16"	3" x 6" 3" x 8" 3" x 10" 3" x 12"
3-1/2" x 2"	11-7/8" 14" 16"	3" x 7" 3" x 9" 3" x 11"




All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.125" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.

WEB STIFFENERS

RECOMMENDATIONS:

- A bearing stiffener is required in all engineered applications with factored reactions greater than shown in the I-joist properties table found in the I-joist Construction Guide (C101). The gap between the stiffener and the flange is at the top.
- A bearing stiffener is required when the I-joist is supported in a hanger and the sides of the hanger do not extend up to, and support, the top flange. The gap between the stiffener and flange is at the top.
- A load stiffener is required at locations where a factored concentrated load greater than 2,370 lbs is applied to the top flange between supports, or in the case of a cantilever, anywhere between the cantilever tip and the support. These values are for standard term load duration, and may be adjusted for other load durations as permitted by the code. The gap between the stiffener and the flange is at the bottom.


FIGURE 2 WEB STIFFENER INSTALLATION DETAILS



Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width

CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET

Method 1 — SHEATHING REINFORCEMENT ONE SIDE




Method 2 — SHEATHING REINFORCEMENT TWO SIDES




NOTE: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

RIM BOARD INSTALLATION DETAILS

8a ATTACHMENT DETAILS WHERE RIM BOARDS ABUT



8b TOE-NAIL CONNECTION AT RIM BOARD



The construction details for residential designs are prone to changes.

Details released after September 2013 supersedes N-303

Installation must comply with latest documentation on I-Joist and other Nordic products from the <http://nordic.ca/>

This document does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of its component based on the design criteria and loadings shown on the calculation sheets.

