

PV-153  
July 29, 2020.

## 36" SEALED BURNER RANGETOP - 6 BURNERS

WOLF

SRT366



### FEATURES

Maintain control with six dual-stacked burners that go from 20,000 Btu down to a mere breath of flame

Simmer and melt sauces, soups, and marinades easily with the lower tier of the dual-stacked burner

Match other Sub-Zero, Wolf, and Cove products with heavy-gauge stainless steel and signature red infinite control knobs

Cleanup is a snap as sealed, seamless burner pans contain splashes and spills

Move pots and pans effortlessly across the continuous cast-iron grates

Reignites flame automatically with spark ignition system

### ACCESSORIES

2-Burner Wok Grate

Black Knobs

Filler Trim

Red Knobs

S-Grates


Stainless Steel Knobs

Stainless steel, brass or chrome bezels

High altitude conversion kits available

5" and 10" stainless steel risers, and 20" riser with shelf


Accessories available through an authorized dealer.  
For local dealer information, visit [subzero-wolf.com/locator](http://subzero-wolf.com/locator).



KNOB OPTIONS




### TOP CONFIGURATION




### RANGETOP SPECIFICATIONS

- Stainless-steel island trim (included)
- Stainless-steel bezels
- 1 - 9,200 Btu burner
- 2 - 15,000 Btu burners
- 2 - 18,000 Btu burners
- 1 - 20,000 Btu burner

Specifications are subject to change without notice. This information was generated on July 14, 2020. Verify specifications prior to finalizing your cabinetry/enclosures.


 PV-153  
 July 29, 2020


## 36" SEALED BURNER RANGETOP - 6 BURNERS




### PRODUCT SPECIFICATIONS

Model	SRT366
Dimensions	35 7/8"W x 8 1/2"H x 28 1/2"D
Electrical Supply	120 VAC, 60 Hz
Electrical Service	15 amp dedicated circuit
Gas Supply	3/4" ID line
Gas Inlet	1/2" NPT female
Receptacle	3-prong grounding-type

### ELECTRICAL




### GAS




NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified

### DIMENSIONS



### STANDARD INSTALLATION



\*Without ventilation hood, 36" (914) minimum clearance countertop to combustible materials. 44" (1118) for charcoal.  
 NOTE: Shaded area above countertop indicates minimum clearance to combustible surfaces, combustible materials cannot be located within this area.  
 Electrical and gas supply located through bottom of platform.  
 For island installation, 12" (305) minimum clearance back of range to combustible rear wall above countertop.


**Vent-A-Hood**  
Model Number: BH234PSLD

Special Notes: LED lights. This model is not available with heat lamps.


*Handwritten:* PV-153  
July 29, 2020.

# WALL MOUNTED LINER INSERT SPECIFICATIONS

WIDTH:	34 3/8"
DEPTH:	22 1/2"
HEIGHT:	12"
CFM:	600
SONES:	6.5
AMPS:	4.0
# LIGHTS:	2




## CONNECTION DIAGRAM



600 CFM B200 Dual Blower (Top View)

## REC. MOUNTING HEIGHT\*



\* Exceeding recommended mounting height may compromise performance.

## ELECTRICAL/MECHANICAL SPECIFICATIONS FOR BLOWER UNIT

MODEL	VOLTS	AMPS+	HZ	RPM	CFM SP@0.0"	EQUIV CFM\$	CFM SP@0.1"	CFM SP@0.2"	CFM SP@0.3"	MIN. ROUND DUCT SIZE	SONES#
B200 Dual	115	4.0	60	1550	600	900	531	480	430	8" (50 sq. in.)	6.5

+ This model is equipped with LED lighting: (2 lights: 30" - 41", 3 lights: 42" - 53", 4 lights: 54" - 66").

\$ Because the Magic Lung blower uses centrifugal filtration rather than conventional baffle or mesh filters, the Magic Lung blower can handle cooking equipment with higher cubic feet per minute (CFM) requirements and can deliver equivalent CFM much more efficiently than other filtration systems. When comparing the Magic Lung with other blower units made by other manufacturers, use the "Equivalent CFM".

# Ratings in accordance with the Standard Test Code by the Energy Systems Laboratory of the Texas Engineering Experiment Station.

Specifications Subject To Change Without Notice





# 30" Double Wall Oven

Benchmark® Series – Stainless Steel HBLP651UC

RF 153  
July 29, 2020.



**HBLP651UC**  
Stainless Steel

The Bosch wall oven features a QuietClose™ door that won't slam shut and a high-resolution TFT user interface.

## Features & Benefits

Dampened hinges softly and quietly guide the QuietClose™ door shut.

The color TFT control panel with SteelTouch™ buttons is easy to use.

A full-extension telescopic rack offers safe access to the oven cavity.

The wall oven is designed to be installed flush with cabinetry.

Bosch wall ovens are compatible with most competitors' cutouts.

## General Properties

**Cooking modes – upper cavity** Bake, Variable Broil (hi & low), Roast, Warm, Sabbath, Proof Dough, Convection Bake, Convection Broil, Convection Roast, Pizza, Multi Rack, Genuine European Convection, Convection Conversion, AutoProbe, Fast Preheat, EcoChef, Speed Convection (Frozen Foods)

**Cooking modes – lower cavity** Identical to Upper Cavity (Exception: Lower Cavity Does not Feature Temperature Probe and EcoChef)

**Cleaning type – upper cavity** Self Clean

**Cleaning type – lower cavity** Self Clean

**Telescopic rack** 1

**Illumination type – upper / lower cavity** Halogen

**Interior lights – upper cavity** 2

**Interior lights – lower cavity** 2



## Oven Performance

**Bake / broil element wattages – upper cavity** 2,400 / 3,800 W

**Convection element wattages – upper cavity** 2,000 W

**Bake / broil element wattages – lower cavity** 2,400 / 3,800 W

**Convection element wattages – lower cavity** 2,000 W

## Technical Details

**Watts (W)** 9,125 W

**Circuit breaker (A)** 40 A

**Volts (V)** 240 / 208 V

**Frequency (Hz)** 60 Hz

**Power cord length (in)** 50"

**Plug type** Fixed Connection, No Plug

**Energy source** Electric

## Dimensions & Weight

**Overall appliance dimensions (HxWxD) (in)** 52 1/16" x 29 3/4" x 24 1/2"

**Required cutout size (HxWxD) (in)** 49 3/4" – 51 1/2" x 28 1/2" x 23 1/2"

**Oven cavity size – lower cavity (cu. ft.)** 4.6

**Overall oven interior dimensions (HxWxD) (in)** 17 13/16" x 24 1/8" x 18"

**Usable oven interior dimensions (HxWxD) (in)** 12 5/16" x 23 1/4" x 15 1/4"

**Net weight (lbs)** 261 lbs

## Accessories-Included

Upper Oven: 1 Telescopic and 2 Standard Oven Racks, Temperature Probe, Broiler Pan  
Lower Oven: 3 Standard Oven Racks

## Accessories-Optional



**HEZTR301**  
30" Telescopic Rack

For help and assistance with Bosch accessories please visit: [www.bosch-eshop.com/eshop/bosch/us](http://www.bosch-eshop.com/eshop/bosch/us) or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 6am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties: Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches of stainless steel, paint/porcelain blemishes, chip, dents, or other damage) to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is", or "B" stock appliances.

For more information on our entire line of products, go to [www.bosch-home.com/us](http://www.bosch-home.com/us) or call 1-800-944-2904


© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.

09/15



Benchmark® Series – Stainless Steel HBLP651UC

RV-153  
July 29, 2020.



measurements in inches (mm)



Single wall oven shown.

For help and assistance with Bosch accessories please visit: [www.bosch-eshop.com/eshop/bosch/us](http://www.bosch-eshop.com/eshop/bosch/us) or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 6am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties. Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches of stainless steel, paint/porelamin blemishes, chip, dents, or other damage) to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is," or "B" stock appliances.

For more information on our entire line of products, go to [www.bosch-home.com/us](http://www.bosch-home.com/us) or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.

09/15


# 30" Double Wall Oven

Benchmark® Series – Stainless Steel HBLP651UC

PV-153  
July 29, 2020



## Installation Details



For help and assistance with Bosch accessories please visit: [www.bosch-eshop.com/eshop/bosch/us](http://www.bosch-eshop.com/eshop/bosch/us) or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 6am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties: Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches of stainless steel, paint/porcelain blemishes, chip, dents, or other damage) to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is", or "B" stock appliances.

For more information on our entire line of products, go to [www.bosch-home.com/us](http://www.bosch-home.com/us) or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.

09/15



# 24" Drawer Microwave

800 Series – Stainless Steel HMD8451UC

RV-153  
July 29, 2020



**HMD8451UC**  
Stainless Steel

The 24" drawer microwave opens and closes automatically with the push of a button, and can be installed flush to cabinet.

## Features & Benefits

Convenient automatic sensor programs simplify cooking for perfect results.

White touch control LCD matches Bosch wall ovens.

Able to fit a 20 oz. cup or a 13" x 9" baking oven pan.

Low profile design with touch "open" and "close".

## General Properties

Cavity material	White
Max. microwave power (W)	950 W

## Capacity

Cavity capacity (cu. ft.)	1.2 cu. ft.
---------------------------	-------------

## Technical Details

Watts (W)	1,500 W
Circuit breaker (A)	15 A
Volts (V)	120 V
Frequency (Hz)	60 Hz
Power cord length (in)	48"
Plug type	120V-3 prong

## Dimensions & Weight

Overall appliance dimensions (HxWxD) (in)	16 5/16" X 23 7/8" X 23 3/8"
Required cutout size (HxWxD) (in)	14 13/16" x 22 1/8" x 23 1/2"
Net weight (lbs)	81 lbs



For help and assistance with Bosch accessories please visit: [www.bosch-eshop.com/eshop/bosch/us](http://www.bosch-eshop.com/eshop/bosch/us) or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 8am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. Please refer to installation instructions prior to making cutout. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties: Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches of stainless steel, paint/porcelain blemishes, chip, dents, or other damage to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is", or "B" stock appliances.

For more information on our entire line of products, go to [www.bosch-home.com/us](http://www.bosch-home.com/us) or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.

05/16


# 24" Drawer Microwave

800 Series – Stainless Steel HMD8451UC


RV-153  
July 29, 2020



## Installation Details




### STANDARD INSTALLATION DIMENSIONS & CLEARANCES




- \* Recommended location of electrical outlet
- \*\* Anti-tip block
- \*\*\* Base should support up to 100 lbs

### FLUSH INSTALLATION DIMENSIONS & CLEARANCES



### FRONTVIEW CUT OUT



- \* Suggested location of electrical outlet
- \*\* Anti-Tip Block
- \*\*\* Base should support up to 100 lbs
- \*\*\*\* Sides should be finished and extend back to cleat.  
Cleats should also be finished, as they may be visible after installation.  
(Cleats are not included with unit.)

For help and assistance with Bosch accessories please visit: [www.bosch-eshop.com/eshop/bosch/us](http://www.bosch-eshop.com/eshop/bosch/us) or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 6am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. Please refer to installation instructions prior to making cutout. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties: Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches on stainless steel, paint/porcelain blemishes, chip, dents, or other damage to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is", or "B" stock appliances.

For more information on our entire line of products, go to [www.bosch-home.com/us](http://www.bosch-home.com/us) or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.

06/16




KBFN502EPA

*pv-153*  
*July 29, 2020*

**KitchenAid®**

**24.2 Cu. Ft. 42" Width Built-In Panel Ready French Door Refrigerator with Platinum Interior Design**

<http://www.kitchenaid.com>



**Key Features:**

- Panel Ready
- Preserva® Food Care System
- Professionally-Inspired Design
- Automatic Ice Maker
- Platinum Interior Design
- SatinGlide® System with Soft-Close
- LED Lighting
- Intuitive Controls
- Adjustable Spill-Resistant Glass Shelves

**Product Dimensions:**

Height: 83 3/8

Width: 42 1/4

Depth: 27 3/4

**Electrical Requirements:**

15.

**Additional Information:**

[Use And Care Guide](#)

[Dimension Guide](#)

[Installation Guide](#)

[Energy Guide](#)

[Warranty Certificate](#)

Available in:

 Panel Ready

INVESTED  
IN  
AMERICA



®Registered trademark/TM Trademark of Whirlpool, U.S.A. © 2016 Whirlpool Corporation. All Rights Reserved.  
All other trademarks are owned by their respective companies.  
Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. We also reserve the right to discontinue or transition products without notice.  
Manufacturer's Suggested Retail Price (MSRP) and Minimum Advertised Price (MAP) provided for reference purposes only. Dealer alone determines advertised and retail prices.  
Created On: Friday, March 03, 2017 07:50:31

# KitchenAid®

FOR THE WAY IT'S MADE.™

## Bottom Mount Built-in Refrigerator

*PV-153*  
*July 29, 2020*

### PRODUCT MODEL NUMBERS

KBBL206E	KBBR306E	KBFN502E
KBBL306E	KBFN402E	KBFN506E
KBBR206E	KBFN406E	

**IMPORTANT:** Observe all governing codes and ordinances.

**Electrical:** A 115 Volt, 60 Hz., AC only 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

A grounded 3 prong electrical outlet should be placed within 4" (10.2 cm) of the right side cabinets or end panel.

**Location:** Do not install in a location where the temperature will fall below 55°F (13°C). It is recommended that you do not install the refrigerator near an oven, radiator, or other heat source.

■ Floor must support the refrigerator weight, more than 600 lbs. (272 kg), door panels, and contents of the refrigerator.

■ Ceiling height must allow for side tipping radius. See "Tipping Radius."

■ Location should permit door to open fully. See "Door Swing Dimensions."

■ Location must permit top grille removal. See "Opening Dimensions."

### Water Supply:

A cold water supply with water pressure between 30 and 120 psi (207 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.


### Reverse Osmosis Water Supply

**IMPORTANT:** The pressure of the water supply coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 30 and 120 psi (207 and 827 kPa).

■ All installations must meet local plumbing code requirements.


■ The water shutoff should be located in the base cabinet on either side of the refrigerator or some other easily accessible area. The right-hand side is recommended. The access hole through the cabinet must be within 1/2" (12.7 mm) of the rear wall.

**NOTE:** If the water shutoff valve is in the back wall behind the refrigerator, it must be at an angle so that the tube is not kinked when the refrigerator is pushed into its final location.



### DOOR SWING DIMENSIONS

The location must permit the door to open a minimum of 90°. Allow 4 1/2" (11.4 cm) minimum space between the side of the refrigerator and a corner wall.  
**NOTE:** More clearance may be required if you are using overlay panels or custom handles.




### PRODUCT DIMENSIONS

■ Height dimensions are shown with the leveling legs extended to 1/4" (3 mm) below the rollers.


■ Width dimensions were measured from trim edge to trim edge.

### FRONT VIEW




\* When leveling legs are fully extended to 1 1/4" (3.2 cm) below rollers, add 1 1/4" (2.9 cm) to the height dimensions.

### SIDE VIEW



### TOP VIEW



■ The water line attached to the back of the refrigerator is 5' (1.5 m) long.




## OPENING DIMENSIONS

To avoid tipping during use, the solid soffit must be within 1" (2.5 cm) maximum above the refrigerator. If the solid soffit is higher than 1" (2.5 cm) or one is not available, then the refrigerator must be braced.


If anti-tip boards are needed, they must be installed to the rear wall studs so that the bottom of the anti-tip board is 84" (213.4 cm) from the floor.

**NOTE:** Do not remove the foam gasket on top of the compressor cover unless removal is necessary to fit the unit under a soffit. Removal of the gasket will cause loss in cooling efficiency.



A. Gasket  
B. Compressor cover

**NOTE:** If installing under a solid soffit, after installation raise the leveling legs so that the gasket is pressed snugly against the soffit.



**NOTE:**  
A clearance of 1/2" (1.3 cm) must be maintained above the top grille in order for the top grille to be removed.


**NOTE:**  
Flooring under refrigerator must be at same level as the room.

## TIPPING RADIUS

Be sure there is adequate ceiling height to stand the refrigerator upright when it is moved into place.


- The dolly wheel height must be added to the tipping radius when a dolly is used.
- If needed, the tipping radius can be reduced. See "Reduce Tipping Radius."

### Side Tipping Radius (36" [91.4 cm] Models)



A. Tip this side only.

### Side Tipping Radius (42" [106.7 cm] Models)




A. Tip this side only.

PV-153  
July 29, 2020

## Overlay Series Custom Panels

Custom overlay panels allow you to blend the exterior of your refrigerator into the overall kitchen décor and to use custom handles for additional design flexibility.

The custom panels must have backer panels attached in order to mount them to the refrigerator. It is most common to work with three panels, as shown in the following graphic: a decorative overlay panel, a  $\frac{1}{8}$ " (3.18 mm) spacer panel or spacer strips and a  $\frac{1}{4}$ " (6.35 mm) backer panel.



In some cases, your cabinet manufacturer may choose to work with one panel routed for the different dimensions. Follow these panel dimension and placement instructions to be sure that the custom overlay panels will fit properly.



### IMPORTANT:

- For 36" (91.4 cm) single-door models, the refrigerator door overlay panel cannot exceed 50 lbs (23 kg) and the freezer drawer overlay panel cannot exceed 20 lbs (9.1 kg).
- For 36" (91.4 cm) and 42" (106.7 cm) French-door models, the refrigerator door overlay panel cannot exceed 30 lbs (13.5 kg) and the freezer drawer overlay panel cannot exceed 25 lbs (11.4 kg).
- The weight of the top grille overlay panel cannot exceed 10 lbs (4.5 kg) for both models.

To minimize panel weight, you may use 2" (5.08 cm) spacer strips around the perimeter in place of full-sheet solid spacer panels. The spacer strips must be set in at least 1" (2.54 cm) from the top, bottom and side edges of the backer panel. If you use spacer strips, it is also recommended that you use two 2" (5.08 cm) strips horizontally centered for added support.




PV-153  
July 29, 2020




#### Spacer Panels (all models)

NOTE: Spacer panels must be at least 1" (2.54 cm) from the top, bottom, and side edges of the backer panel.

#### 3-Piece Grille Overlay Panel Configuration



#### 3-Piece Door Overlay Panel Configuration



#### 1-Piece Overlay Panel Configuration

In some cases, your cabinet manufacturer may choose to work with one panel routed for the different dimensions. Follow these panel dimensions and placement instructions to be sure that the custom overlay panels will fit properly.

# Miele

Fully Integrated Dishwasher

*PV-153*  
*July 29, 2020*

SPECIFICATIONS	
Overall Unit Dimensions	23 <sup>9</sup> / <sub>16</sub> " (598mm) W x 33 <sup>1</sup> / <sub>16</sub> " - 36 <sup>1</sup> / <sub>4</sub> " (855 - 920mm) H x 22 <sup>7</sup> / <sub>16</sub> " (570mm) D
Niche	
Minimum Cabinet Opening Dimensions	23 <sup>9</sup> / <sub>16</sub> " (600mm) W x 33 <sup>1</sup> / <sub>16</sub> " (857mm) H x 22 <sup>7</sup> / <sub>16</sub> " (570mm) D
Plumbing	
Water Supply Requirements	May be connected to a cold or hot water supply up to a maximum of 140°F/60°C. Must be connected to a shut-off valve with a male 3/8" compression. The water shut-off valve must be accessible after installation. The water pressure must be between 7.25 psi (0.5 bar) and 145 psi (10 bar). If the pressure is higher than 145 psi (10 bar), a pressure reducing valve must be installed.
Water Connection Line	4' 11" (1.5 m) flexible water intake hose is supplied with a 3/8" compression connection.
Drain Hose	4' 11" (1.5 m) flexible drain hose with a 7/8" (22 mm) internal diameter is supplied. The drain hose length must not be longer than 13' 1 1/2" (4 m) and the delivery head must not exceed 3' 3 3/8" (1 m).
Electrical	
Electrical Requirements	110V / 120V, 60Hz, 15 Amps
Power Cord	NEMA 5-15 plug, 3' 11" (1.2 m) (Measured from back of unit, convertible to hardwire)
Shipping	
Shipping Weight	121 lbs (55 kg)
Shipping Dimensions	27 <sup>1</sup> / <sub>8</sub> " W x 38 <sup>1</sup> / <sub>8</sub> " H x 26 <sup>3</sup> / <sub>8</sub> " D
Support	
Call Miele	(800) 999-1360
Miele Website	<a href="http://www.mieleusa.com">www.mieleusa.com</a>
20/20 Link	<a href="http://2020technologies.com">2020technologies.com</a>

## Custom Panel Ready


Classic Plus 3D

Crystal

Dimension

Lumen

Diamond




G 4998 Vi  
Item 21499861USA  
G 4998 SCVi  
Item 21499862USA



G 6665 SCVi  
Item 21666562USA



G 6785 SCVi  
Item 21678562USA



G 6875 SCVi  
Item 21687562USA  
G 6885 SCVi K2o  
Item 21688562USA



G 6687 SCVi K2o  
Item 21698762USA

## Pre-Finished


Classic Plus

Classic Plus 3D


Crystal

Dimension

Lumen



G 4977 Vi SF  
Item 21497763USA  
G 4977 SCVi SF  
Item 21497764USA



G 4998 Vi SF  
Item 21499863USA  
G 4998 SCVi SF  
Item 21499864USA



G 6665 SCVi SF  
Item 21666563USA



G 6785 SCVi SF  
Item 21678563USA



G 6875 SCVi SF  
Item 21687563USA




# Miele

Fully Integrated Dishwasher

## INSTALLATION SPECIFICATIONS

*Handwritten:* PV-153  
July 29, 2020



- Drain -** 4 ft 11 in (1.5 m) flexible drain hose.  
(Connects from lower center rear)
- Water -** 4 ft 11 in (1.5 m) flexible water intake hose with 3/8" compression fitting.  
(Connects from lower center rear)
- Electric -** 4 ft 11 in (1.5 m) 120V 15 A 3 wire molded NEMA 5-15 plug power supply. (Connects via Front End Supply or may be hardwired)


# Miele

Fully Integrated Dishwasher

*[Handwritten signature]*  
PV-153  
July 29, 2020.

## CUSTOM PANEL DETAILS

Some Miele dishwashers do not come equipped with a front panel. These dishwashers are designed to accept a custom door panel supplied by a cabinet maker. Miele has a unique panel integration system which allows the dishwasher to align with the surrounding cabinets.



**Width:** 23 7/16" (595 mm) in all Cases

**Thickness:** 3/4" (19 mm) in all Cases

**Height:** Determined using the following calculation:

$$\text{Panel Height} = \text{HTC} - \text{TKH}$$

**HTC** = Height to the underside of countertop

**TKH** = Toe kick height

**Note:** Control panel is along the top edge of the unit. It is not visible when the unit is closed. A handle **MUST** be located on front of panel in order to open unit. (Except K2o models).

Maximum panel height: 31 7/8" (810 mm)

Minimum panel height: 27 1/8" (690 mm)

Maximum panel weight: 21 lbs (9.5 kg)

## Miele Stainless Steel GFVi Panels

Miele offers pre-fabricated stainless steel panels for all fully integrated units. These panels are designed for various toe-kick heights and offer a choice of handle options. See Miele Product Brochure for more info.

For Knock2open (K2o) models, an additional kit is required for use with stainless steel panel. Please contact Miele for further details.



# Miele

Fully Integrated Dishwasher

*Handwritten signature*  
 PV-153  
 July 29, 2020

POSSIBLE TOEKICK HEIGHT +  
 CABINET HEIGHT COMBINATION

Height to underside of countertop

	33 3/4	34	34 1/4	34 1/2	34 3/4	35	35 1/4	35 1/2	35 3/4	36
2 1/2										
3										
3 1/2										
4										
4 1/2										
5										
5 1/2										
6										
6 1/2										
7										
7 1/2										
8										
8 1/2										

- Acceptable combinations
- Typical American installation

PV-153  
July 29, 2020




## WM4370\*

### 4.5 cu.ft. Ultra Large Front Load Washer

- 4.5 cu.ft. Ultra Large Capacity
- TurboWash® Technology
- Steam Technology
- Allergiene™ Cycle
- NeveRust™ Stainless Steel Drum
- 14 Wash Programs
- NFC Tag On
- ENERGY STAR® Qualified
- Available in Premium Black Stainless Steel and White

#### LG SideKick™

The LG SideKick™ is the perfect fit for your customers' laundry, whether they prefer Front Load or Top Load. Thanks to the added compatibility with LG front control top load systems, your customers can easily customize their own TwinWash™ system based on their needs or budget!



CAPACITY	
Capacity	4.5 cu. ft.
APPEARANCE	
Design Look	Front Control
Intelligent Electronic Controls with Dual LED Display	Yes
Dial-A-Cycle™	Yes
ENERGY	
ENERGY STAR® Most Efficient 2016	Yes
CEE Tier	2
WASH PROGRAMS	
No. of Programs	14
Wash Programs	Cotton/Normal, Perm. Press, Delicates, Speed Wash, TubClean™, Bulky/Large, Hand Wash/Wool, Sanitary, Allergiene™, Heavy Duty, Bright Whites™, Towels, Drains+Spin, Download
No. of Options	11
Options	Prewash, Delay Wash, Extra Rinse, Drum Light, Rinse+Spin, Child Lock, Cold Wash™, Steam, FreshCare™, TurboWash™, Add Garment
No. of Wash/Rinse Temps	5
	Extra Hot, Hot, Warm, Cold, Tap Cold (All Cold Rinses)
Spin Speeds	Extra High (1,300 max.), High, Medium, Low, No Spin
No. of Water Levels	Automatically adjusts to the size of load
No. of Soil Levels	5
FABRIC CARE FEATURES	
TurboWash®	Yes
Steam Technology	Yes
Allergiene™ Cycle	Yes
Sanitary Cycle	Yes
Cold Wash™ Option	Yes

CONVENIENCE FEATURES	
TrueBalance™ Anti-Vibration System	Yes
4 Tray Dispenser	Prewash, Main Wash (with liquid detergent cup), Bleach, Fabric Softener
LoDecibel™ Quiet Operation	Yes
End of Cycle Signal	Yes
LoadSense	Yes
Child Lock	Yes
Auto Suds Removal	Yes
Forced Drain System	Yes
Easy Loading Tilt™	Yes

SMART THING™ TECHNOLOGY	
SmartDiagnosis™	Yes (v 3.0)
NFC Tag On Technology	Yes
MOTOR AND AGITATOR	
Motor Type	Inverter Direct Drive Motor
Motor Speed	Variable
Max RPM	1,300
Axis	Horizontal

MATERIALS AND FINISHES	
NeveRust™ Stainless Steel Drum	Yes
Cabinet	PCM
Control Panel	Plastic
Top Plate	Painted
Door Rim	Glass/Chrome
Door Cover	Dark Blue Tinted
Available Colors	White (W) Black Stainless Steel (K)

OPTIONS/ACCESSORIES	
Pedestal	WDP4W, WDP4K
Pedestal (Width)	27" x 14 1/8" x 28 2/5"
SideKick™	WD100CW (White), WD100CK (Black Stainless Steel)
Pedestal Washer	27" x 14 1/8" x 30-3/4" (50-1/2 with drawer open)
Stacking Kit	KSTK1

LIMITED WARRANTY	
1 Year Parts and Labor; 10 Years Motor, Lifetime on Drum	

UPC CODES	
WM4370HWA Washer (White)	048231 013260
WM4370HKA Washer (Black Stainless Steel)	048231 018764
DLEX4370K Electric Dryer (Black Stainless Steel)	048231 018791
DLGX4371K Gas Dryer (Black Stainless Steel)	048231 018807
DLEX4370W Electric Dryer (White)	048231 013277
DLGX4371W Gas Dryer (White)	048231 013284
WDP4K Pedestal (Black Stainless Steel)	048231 019194
WDP4W Pedestal (White)	48231 012898
WD100CK SideKick™ Pedestal Washer (Black Stainless Steel)	048231 019200
WD100CW SideKick™ Pedestal Washer (White)	048231 015172
KSTK1 Stacking Kit (Chrome)	048231 011204

© 2016 LG Electronics USA, Inc. All rights reserved. "LG Life's Good" is a registered trademark of LG Corp. All other product and brand names are trademarks or registered trademarks of their respective owners. Design, features and specifications are subject to change without notice. Non-metric weights and measurements are approximate. Some features may require Internet access. Content and services may vary by product and are subject to change without notice. 8/24/16





2V-153  
July 29, 2020.

## WM4370\*

### QUICK INSTALL & CLEARANCES

For full installation directions/clearances please refer to the corresponding User Manual and Installation Guide.

#### DIMENSIONS

A Width	27"
B Height	38-11/16"
C Depth	29-3/4"
D Depth with door open	51"
Carton (WxHxD)	29-1/2" x 43-5/16" x 31-5/16"
Weight (Product/ Carton)	202.8 lbs / 224.8 lbs

#### POWER SOURCE


Ratings	UL Listed
Electrical Requirements	120V, 10 Amps
Type	Electric, 60 Hz



#### CONNECT TO THE POWER SUPPLY

- The washer should be plugged into a 120-VAC, 60-Hz grounded 3-prong outlet. Plug in the washer. Improper connection of the equipment-grounding conductor can result in risk of electric shock. Check with a qualified electrician or service technician if you are in doubt as to whether the appliance is properly grounded. Do not modify the plug provided with the appliance. If it does not fit the outlet, have a proper outlet installed by a qualified electrician. Failure to follow these warnings can cause serious injury, fire, electrical shock, or death.
- The power outlet must be within 60 inches (1.5 m) of either side of the washer.
- The appliance and outlet must be positioned so that the plug is easily accessible.
- Do not overload the outlet with more than one appliance.
- The outlet must be grounded in accordance with current wiring codes and regulations.
- Time-delay fuse or circuit breaker is recommended.
- It is the personal responsibility and obligation of the product owner to have a proper outlet installed by a qualified electrician.

#### DIMENSIONS / CLEARANCES




- Install the washing machine on a solid floor that is strong and rigid enough to support the weight of the washing machine, even when fully loaded, without flexing or bouncing. If the floor has too much flex, you may need to reinforce it to make it more rigid. If the floor is not solid, it may cause severe vibration and noise.

#### CONNECTING THE WATER LINES


LG recommends the use of LG hoses. Any leaking, property damage, or damage to the washing machine caused by an improper installation or by the use of non-LG hoses is not covered under the terms of the LG warranty and is the sole responsibility of the customer and/or an installer.

- Water supply pressure must be between 20 psi and 120 psi (1.38-8.27 kPa). If the water supply pressure is more than 120 psi, a pressure reducing valve must be installed.
- Inspect the threaded fitting on each hose and make sure there is a rubber seal in place in both ends of each hose.
- Connect the water supply hoses to the HOT and COLD water faucets tightly by hand and then tighten another 2/3 turn with pliers.
- Always run a gallon or two of water through each inlet hose to flush dirt, scale and other debris out of the water lines. Doing so will help prevent future problems with clogged filter screens, and will also allow you to verify which water line is hot and which is cold.
- Attach the hot water line to the hot water inlet on the back of the washer. Attach the cold water line to the cold water inlet on the back of the washer. Tighten the fittings securely. Turn ON both faucets all the way and check for leaks at both ends of the hoses.




#### CONNECTING THE DRAIN HOSE

- The drain hose should always be properly secured. Failure to properly secure the drain hose can result in flooding and property damage.
- The drain must be installed in accordance with any applicable local codes and regulations.
- Make sure that the drain hose is not stretched, pinched, crushed, or kinked.
- Normal height of the end of the hose should be approximately 35"-47" (0.9-1.2 m) from the floor.
- Do not install the end of the drain hose lower than 29 in. (73.7 cm) or higher than 96 in. (243.8 cm) above the bottom of the washer or more than 60 in. (152.4 cm) away from the washer.
- Never create an airtight seal between the hose and the drain with tape or other means. If no air gap is present, water can be siphoned out of the tub resulting in poor wash/rinse performance or clothing damage.



#### STANDPIPE Option

Do not insert the end of the drain hose into the standpipe more than 8 inches (20 cm). Doing so can cause siphoning, odors, or improper draining.



#### LAUNDRY TUB Option

Do not use this drain hose with a floor drain. The end of the drain hose must be at least 29 inches above the floor for proper draining to occur.

DV-153  
July 29, 2020



## DLEX4370\* / DLGX4371\*

7.4 cu.ft. Super Capacity  
TurboSteam® Dryer

### FEATURES

- 7.4 cu.ft. Capacity
- TurboSteam® Technology
- 14 Drying Programs
- Available in Black Stainless Steel & White
- Sensor Dry
- LoDecibel™ Quiet Operation
- Smart ThinQ™ Technology
- ENERGY STAR® Qualified

TurboSteam™

smart ThinQ™



CAPACITY	
Capacity	7.4 cu. ft.
APPEARANCE	
Design Look	Front Control Panel
Intelligent Electronic Controls with Dual LED Display	Yes
Dial-A-Cycle™	Yes
DRYER PROGRAMS	
No. of Programs	14
Programs (Sensor Dry)	Cotton/Normal, Perm Press, Bulky/Large, Towels, Delicates, Heavy Duty, SteamFresh™, SteamSanitary™, Anti-Bacterial, Sports Wear, Download Cycle
Programs (Manual Dry)	Freshen Up, Speed Dry, Air Dry
No. of Options	10
Options	More Time, Less Time, Damp Dry Signal, Wrinkle Care, Child Lock, Custom Program, PCM Save, Reduce Static, Drum Light, Energy Saver
Temperature Settings	High, Medium High, Medium Low, Ultra Low
Drying Levels	Very Dry, More Dry, Normal Dry, Less Dry, Damp Dry
Manual Dry Times	60 min, 50 min, 40 min, 30 min, 20 min, More Time/Less Time
FABRIC CARE FEATURES	
TurboSteam® Technology	Yes
Sensor Dry	Yes

CONVENIENCE FEATURES	
LoDecibel™ Quiet Operation	Yes
End of Cycle Signal	Yes
Drum Light	Yes
Reversible Door	Yes
FlowSense™ Duct Clogging Sensor	Yes
Venting Option	Electric: 4 Way Venting Gas: 3 Way Venting
Leveling Legs	4 Adjustable Legs
Remaining Time Display/Status Indicator(s)	Yes
3 Minute Installation Check	Yes
SMART THINQ™ TECHNOLOGY	
SmartDiagnosis™	Yes
NFC Tag On	Yes
MATERIALS AND FINISHES	
NeverRust™ Stainless Steel Drum	Yes
Tub Rear	Painted
Cabinet	Painted Steel
Control Panel	Plastic
Top Plate	White: Powder Coat Black Stainless Steel: Porcelain
Door	Glass/Chrome
Door Cover	Dark Blue Tinted Round Cover
Available Colors	White (W) Black Stainless Steel (K)
ENERGY	
ENERGY STAR® Qualified	Yes

OPTIONS	
Pedestal	WDP4W, WDP4V
Pedestal (W/InD)	27" x 14 1/8" x 28 2/5"
Stacking Kit	KSTK1
LIMITED WARRANTY	
1 Year Parts and Labor	
UPC CODES	
DLEX4370K Electric Dryer (Black Stainless Steel)	048231 018791
DLGX4371K Gas Dryer (Black Stainless Steel)	048231 018907
DLEX4370W Electric Dryer (White)	048231 013277
DLGX4371W Gas Dryer (White)	048231 013284
WM4370HWA Washer (White)	048231 013260
VIM4370HKA Washer (Black Stainless Steel)	048231 018784
WDP4K Pedestal (Black Stainless Steel)	048231 019194
WDP4W Pedestal (White)	048231 012898
WD100CK Sidelock™ Pedestal Washer (Black Stainless Steel)	048231 019200
WD100CW Sidelock™ Pedestal Washer (White)	048231 015172
KSTK1 Stacking Kit (Chrome)	048231 011204

© 2017 LG Electronics USA, Inc. All rights reserved. "LG Life's Good" is a registered trademark of LG Corp. All other product and brand names are trademarks or registered trademarks of their respective owners. Design, features and specifications are subject to change without notice. Non-metric weights and measurements are approximate. Some features may require internet access. Content and services may vary by product and are subject to change without notice. 2/15/17



2V-153  
July 29, 2020



## DLEX4370\* / DLGX4371\* QUICK INSTALL & CLEARANCES

For full installation directions/clearances  
please refer to the corresponding  
User Manual and Installation Guide.


DIMENSIONS	
A Width	27"
B Height	38-11/16"
C Depth	30"
D Depth with door open	51"
Carton (WxHxD)	29-7/10" x 43-1/5" x 31-3/10"
Weight (Product/ Carton)	Electric 146.8 lbs / 160.0 lbs Gas 148.4 lbs / 161.6 lbs

POWER SOURCE	
Ratings	CSA Listed
Electrical Requirements	120V, 15 Amps (Gas) 240V, 30 Amps (Electric)
Type	Gas/Electric
BTU	20,000




### CONNECTING THE GAS SUPPLY

- Installation and service must be performed by a qualified installer, service agency, or the gas supplier.
- Use only a new stainless steel flexible connector and a new AGA-certified connector.
- A gas shutoff valve must be installed within 6 ft. (1.8 m) of the dryer.
- The dryer is configured for natural gas when shipped from the factory. Make sure that the dryer is equipped with the correct burner nozzle for the type of gas being used (natural gas or propane gas).
- If necessary, the correct nozzle (for the LP nozzle kit, order part number 383EEL3002D) should be installed by a qualified technician and the change should be noted on the dryer.
- All connections must be in accordance with local codes and regulations. Gas dryers MUST exhaust to the outdoors.



### DIMENSIONS / CLEARANCES




\* Required spacing

\*\* For side or bottom venting, 2-inch (5.1 cm) of spacing is allowed.

### VENTING / DUCTWORK

NOTE: Follow the guidelines below to maximize drying performance and reduce lint buildup and condensation in the ductwork. Ductwork and fittings are NOT included and must be purchased separately.

- Use 4-inch (10.2 cm) diameter rigid, semi-rigid or flexible metal ductwork.
- The exhaust duct run should be as short as possible.
- Use as few elbow joints as possible.
- The male end of each section of exhaust duct must point away from the dryer.
- Use duct tape on all duct joints.
- Insulate ductwork that runs through unheated areas in order to reduce condensation and lint buildup on duct surfaces.
- Incorrect or inadequate exhaust systems are not covered by the dryer warranty. Dryer failures or service required because of such exhaust systems will not be covered by the dryer warranty.



Wall Cap Type	Number of 90° Elbows	Maximum length of 4-inch diameter rigid metal duct
Recommended	0	55 ft. (16.8 m)
	1	39 ft. (11.9 m)
	2	23 ft. (7.0 m)
	3	7 ft. (2.1 m)
Use only for short run installations	0	55 ft. (16.8 m)
	1	47 ft. (14.3 m)
	2	39 ft. (11.9 m)
	3	31 ft. (9.4 m)

- Ductwork is not provided with the dryer. You should obtain the necessary ductwork locally. The vent hood should have hinged dampers to prevent backdraft when the dryer is not in use.
- The total length of flexible metal duct must not exceed 8 ft. (2.4 m).
- Deduct 6 ft. (1.8 m) for each additional elbow. Do not use more than four 90° elbows.

### CONNECTING ELECTRIC DRYERS

- A 4-wire connection is required for all mobile and manufactured home installations, as well as all new construction after January 1, 1996.
- A 3-wire connection is NOT permitted on new construction after January 1, 1996.
- A UL-listed strain relief is required.
- Use a 30-amp, 240-volt, 4-wire, UL-listed power cord with #10 AWG-minimum copper conductor and closed loop or forked terminals with upturned ends.

