



CONSTRUCTION SUMMARY

Lot: 132
Model: 50.06 B SILVERWOOD
Project/Phase: Pine Valley Forevergreen / 1

APPLIANCES

Invoice	Qty.	Description
2673 29Mar21 NoCat	1	APPLIANCE SPECIFICATIONS ATTACHED - SIGNED COPY

CERAMIC

Invoice	Qty.	Description
2490 37 20Jan21	1	POWDER ROOM: TILE, FLOOR , LEVEL 5 - POWDER ROOM -12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2490 20Jan21 NoCat	1	KITCHEN **SERVERY ONLY** UPGRADE 4 TILE BACKSPLASH - 3X12" LAID IN HORIZONTAL STACKED PATTERN.
2490 32 20Jan21	1	MUD ROOM: TILE, FLOOR , LEVEL 1 - MUD ROOM - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2490 35 20Jan21	1	ENSUITE 2: TILE, FLOOR , LEVEL 3 - ENSUITE #2 - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2490 49 20Jan21	1	ENSUITE 2: TILE, WALL, LEVEL 3 - ENSUITE #2 - 12X24" LAID IN HORIZONTAL STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2490 43 20Jan21	1	ENSUITE 2: TILE, SHOWER FLOOR, LEVEL 2 - ENSUITE #2 - 2" SQUARE
2490 32 20Jan21	1	SHARED ENSUITE: TILE, FLOOR , LEVEL 1 - SHARED BATH - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2490 35 20Jan21	1	MASTER ENSUITE: TILE, FLOOR , LEVEL 3 - MASTER ENSUITE - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2490 50 20Jan21	1	MASTER ENSUITE: TILE, WALL, LEVEL 4 - MASTER ENSUITE - 10X30" LAID VERTICAL STACKED PATTERN
2490 43 20Jan21	1	MASTER ENSUITE: TILE, SHOWER FLOOR, LEVEL 2 - MASTER ENSUITE - 2" SQUARE
2490 37 20Jan21	1	FRONT FOYER: TILE, FLOOR , LEVEL 5 - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION



CONSTRUCTION SUMMARY

Lot: 132
Model: 50.06 B SILVERWOOD
Project/Phase: Pine Valley Forevergreen / 1

CONCRETE AND DRAIN

Invoice	Qty.	Description
2245 06Aug20 NoCat	1	.BACK-FLOW PREVENTER VALVE
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** BUILD ADDITIONAL THIRD CAR GARAGE SPACE WITH TANDEM. PURCHASER ACKNOWLEDGES THAT EXISTING WINDOW IN BEDROOM 2 WILL BE REDUCED IN SIZE AND/OR RELOCATED ALONG THE WALL TO PERMIT TANDEM INCLUDED IN APS
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO EXTEND THREE CAR GARAGE SPACE TO APPROXIMATELY 30 FEET WIDE AND INSTALL GARAGE DOORS THAT ARE APPROXIMATELY ONE FOOT WIDER AND TALLER THAN STANDARD SIZE
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO SUPPLY AND INSTALL OPTIONAL COVERED LOGGIA AS PER PLAN

CROWN MOULDING

Invoice	Qty.	Description
2379 20Jan21 NoCat	1	.FAMILY ROOM - OPT. COFFERED CEILING AS PER PLAN
2379 20Jan21 NoCat	1	.FAMILY ROOM - OPT. WAFFLE CEILING, BEAM DETAIL AS PER PLAN (6 BOXES) OPTION#1 CTR-B07
2490 20Jan21 NoCat	1	**REVISED JANUARY 18 2021** GREAT ROOM - INSTALL 5 BOX WAFFLE (rectangular) IN LIEU OF 6 BOXES, SEE ATTACHED SKETCH FOR DETAIL CTR-B07 DIFFERENCE IN PRICE FROM ORIGINAL SELECTION (PE.2379)



CONSTRUCTION SUMMARY

Lot: 132
Model: 50.06 B SILVERWOOD
Project/Phase: Pine Valley Forevergreen / 1

DRYWALL

Invoice	Qty.	Description
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** BUILD ADDITIONAL THIRD CAR GARAGE SPACE WITH TANDEM. PURCHASER ACKNOWLEDGES THAT EXISTING WINDOW IN BEDROOM 2 WILL BE REDUCED IN SIZE AND/OR RELOCATED ALONG THE WALL TO PERMIT TANDEM
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO EXTEND THREE CAR GARAGE SPACE TO APPROXIMATELY 30 FEET WIDE AND INSTALL GARAGE DOORS THAT ARE APPROXIMATELY ONE FOOT WIDER AND TALLER THAN STANDARD SIZE
2379 20Jan21 NoCat	1	.MASTER BEDROOM: UPGRADE EXTERIOR GARDEN DOOR ASSEMBLY TO 96"
2379 20Jan21 NoCat	1	.GREAT ROOM: UPGRADE EXTERIOR SLIDING DOOR ASSEMBLY TO 96"
2379 20Jan21 NoCat	1	.FAMILY ROOM - OPT. COFFERED CEILING AS PER PLAN
2379 20Jan21 NoCat	1	.FAMILY ROOM - OPT. WAFFLE CEILING, BEAM DETAIL AS PER PLAN (6 BOXES) OPTION#1 CTR-B07

ELECTRICAL

Invoice	Qty.	Description
2379 72,307 20Jan21	1	.KITCHEN: FIXTURE: RELOCATE STANDARD CEILING MOUNT FIXTURE LOCATE ABOVE ISLAND, SEE PLAN FOR LOCATION
2379 72,280 20Jan21	1	.KITCHEN: CEILING OUTLET: ADDITIONAL REINFORCED CEILING OUTLET - LOCATE ABOVE ISLAND, USE SAME SWITCH AS STANDARD LIGHT
2379 72,289 20Jan21	6	.MAIN HALL: 4" E/S LED INTERIOR POT LIGHT - GROUND FLOOR - EACH -SEE PLAN FOR LOCATION IN LIEU OF STANDARD CEILING LIGHTS - USE STANDARD SWITCH INCLUDED IN APS
2379 20Jan21 NoCat	1	.GREAT ROOM: FIREPLACE - ADD HEAT ACTIVATED FAN
2379 20Jan21 NoCat	1	APRILAIRE 600 WHOLE HOUSE STEAM HUMIDIFIER (UP TO 4,000 SQ.FT.) - COMPLETE WITH HI VOLTAGE WIRING, 240V DOUBLE BREAKER 20 AMP, SHUT OFF VALVE



CONSTRUCTION SUMMARY

Lot: 132
Model: 50.06 B SILVERWOOD
Project/Phase: Pine Valley Forevergreen / 1

EXTERIOR COLOURS

Invoice	Qty.	Description
2245	1	EXTERIOR COLOUR PACKAGE # BR.1
06Aug20 NoCat		

FIREPLACE

Invoice	Qty.	Description
2379 72,321 20Jan21	1	.GREAT ROOM: FIREPLACE - ADD HEAT ACTIVATED FAN

FORMING

Invoice	Qty.	Description
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO PROVIDE A SERVICE STAIRCASE TO BASEMENT INCLUDED IN APS
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO SUPPLY AND INSTALL OPTIONAL COVERED LOGGIA AS PER PLAN INCLUDED IN APS
2245 06Aug20 NoCat	3	.BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 10" FRAME (PINEVALLEY 50 FOOT LOTS ONLY)
2245 06Aug20 NoCat	1	.BASEMENT WINDOWS - EGRESS BASEMENT WINDOW 40" X 24" - 10" FRAME (PINEVALLEY 50 FOOT LOTS ONLY)
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** BUILD ADDITIONAL THIRD CAR GARAGE SPACE WITH TANDEM. PURCHASER ACKNOWLEDGES THAT EXISTING WINDOW IN BEDROOM 2 WILL BE REDUCED IN SIZE AND/OR RELOCATED ALONG THE WALL TO PERMIT TANDEM
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO EXTEND THREE CAR GARAGE SPACE TO APPROXIMATELY 30 FEET WIDE AND INSTALL GARAGE DOORS THAT ARE APPROXIMATELY ONE FOOT WIDER AND TALLER THAN STANDARD SIZE
2379 20Jan21 NoCat	1	.GREAT ROOM: UPGRADE EXTERIOR SLIDING DOOR ASSEMBLY TO 96"
2379 20Jan21 NoCat	1	.MASTER BEDROOM: UPGRADE EXTERIOR GARDEN DOOR ASSEMBLY TO 96"
2379 20Jan21 NoCat	1	.KITCHEN - UPGRADE TO 8" DUCT (INTERIOR WALL) IN LIEU OF STANDARD OFFERING



CONSTRUCTION SUMMARY

Lot: 132
Model: 50.06 B SILVERWOOD
Project/Phase: Pine Valley Forevergreen / 1

FRAMING

Invoice	Qty.	Description
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO EXTEND THREE CAR GARAGE SPACE TO APPROXIMATELY 30 FEET WIDE AND INSTALL GARAGE DOORS THAT ARE APPROXIMATELY ONE FOOT WIDER AND TALLER THAN STANDARD SIZE INCLUDED IN APS
2245 06Aug20 NoCat	3	.BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 10" FRAME (PINEVALLEY 50 FOOT LOTS ONLY)
2245 06Aug20 NoCat	1	.BASEMENT WINDOWS - EGRESS BASEMENT WINDOW 40" X 24" - 10" FRAME (PINEVALLEY 50 FOOT LOTS ONLY)
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** BUILD ADDITIONAL THIRD CAR GARAGE SPACE WITH TANDEM. PURCHASER ACKNOWLEDGES THAT EXISTING WINDOW IN BEDROOM 2 WILL BE REDUCED IN SIZE AND/OR RELOCATED ALONG THE WALL TO PERMIT TANDEM
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO PROVIDE A SERVICE STAIRCASE TO BASEMENT
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO SUPPLY AND INSTALL OPTIONAL COVERED LOGGIA AS PER PLAN
2379 20Jan21 NoCat	1	.GREAT ROOM: UPGRADE EXTERIOR SLIDING DOOR ASSEMBLY TO 96"
2379 20Jan21 NoCat	1	.MASTER BEDROOM: UPGRADE EXTERIOR GARDEN DOOR ASSEMBLY TO 96"
2379 72,609 20Jan21	1	.FAMILY ROOM - OPT. COFFERED CEILING AS PER PLAN
2379 72,608 20Jan21	1	.FAMILY ROOM - OPT. WAFFLE CEILING, BEAM DETAIL AS PER PLAN (6 BOXES) OPTION#1 CTR-B07
2379 20Jan21 NoCat	1	.KITCHEN - UPGRADE TO 8" DUCT (INTERIOR WALL) IN LIEU OF STANDARD OFFERING



CONSTRUCTION SUMMARY

Lot: 132
Model: 50.06 B SILVERWOOD
Project/Phase: Pine Valley Forevergreen / 1

GARAGE DOORS

Invoice	Qty.	Description
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** BUILD ADDITIONAL THIRD CAR GARAGE SPACE WITH TANDEM. PURCHASER ACKNOWLEDGES THAT EXISTING WINDOW IN BEDROOM 2 WILL BE REDUCED IN SIZE AND/OR RELOCATED ALONG THE WALL TO PERMIT TANDEM
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO EXTEND THREE CAR GARAGE SPACE TO APPROXIMATELY 30 FEET WIDE AND INSTALL GARAGE DOORS THAT ARE APPROXIMATELY ONE FOOT WIDER AND TALLER THAN STANDARD SIZE

GLASS AND MIRROR

Invoice	Qty.	Description
2490 20Jan21 NoCat	3	MASTER ENSUITE + ENSUITE 2 + SHARED ENSUITE: UPGRADE SHOWER DOOR HANDLE TO MT6X6 CHROME

GRANITE MARBLE QUARTZ

Invoice	Qty.	Description
2490 20Jan21 NoCat	1	POWDER ROOM: UPGRADE 4 QUARTZ COUNTER
2490 20Jan21 NoCat	1	KITCHEN: UPGRADE 4 QUARTZ COUNTER TOP
2490 20Jan21 NoCat	1	KITCHEN: **RANGE WALL ONLY** ADD FULL HEIGHT SLAB BACKSPLAST AT RANGE WALL ONLY - LEVEL 4
2490 20Jan21 NoCat	1	MASTER ENSUITE: UPGRADE 4 QUARTZ COUNTER TOP

HARDWOOD

Invoice	Qty.	Description
2490 9 20Jan21	1	VINTAGE SERIES, 6 1/2" WHITE OAK, NSS ENGINEERED HARDWOOD, 3/4" THK, SCULPTED TEXTURE, UVF FINISH - LOT SPECIFIC 132, KITCHEN/BREAKFAST/SERVERY - LEVEL 6
2490 9 20Jan21	1	THRU OUT - ALL STANDARD AREAS: MAIN HALL/ LIBRARY/ FAMILY/ DINING/ MASTER BEDROOM/ BEDROOM 2/ BEDROOM 3/ BEDROOM 4/ UPPER HALL: VINTAGE SERIES, 6 1/2" WHITE OAK, NSS ENGINEERED HARDWOOD, 3/4" THK, SCULPTED TEXTURE, UVF FINISH - LOT SPECIFIC 132,- LEVEL 6



CONSTRUCTION SUMMARY

Lot: 132
Model: 50.06 B SILVERWOOD
Project/Phase: Pine Valley Forevergreen / 1

HVAC

Invoice	Qty.	Description
2379 72,218 20Jan21	1	.KITCHEN - UPGRADE TO 8" DUCT (INTERIOR WALL) IN LIEU OF STANDARD OFFERING
2379 72,248 20Jan21	1	.APRILAIRE 600 WHOLE HOUSE STEAM HUMIDIFIER (UP TO 4,000 SQ.FT.) - COMPLETE WITH HI VOLTAGE WIRING, 240V DOUBLE BREAKER 20 AMP, SHUT OFF VALVE
2379 72,215 20Jan21	1	.FURNACE - LENNOX 2 STAGE VARIABLE SPEED FURNACE (90,000 TO 110,000 BTU FOOT s) IN LIEU OF STANDARD OFFERING - (PINE VALLEY SITE ONLY - REFERENCE MODEL SPECIFIC FOR FURANCE UPGRADE EXTRA)
2379 20Jan21 NoCat	1	.GREAT ROOM: FIREPLACE - ADD HEAT ACTIVATED FAN
2379 20Jan21 ** NoCat	1	APRILAIRE 600 WHOLE HOUSE STEAM HUMIDIFIER (UP TO 4,000 SQ.FT.) - COMPLETE WITH HI VOLTAGE WIRING, 240V DOUBLE BREAKER 20 AMP, SHUT OFF VALVE

INTERIOR DOORS AND TRIM

Invoice	Qty.	Description
2490 72,645 20Jan21	13	THRU OUT: ADDITIONAL FOR SAFE & SOUND (SOLID CORE) - MAIN FLOOR + 2ND FLOOR (NOT BASEMENT) not including closet doors

INTERIOR TRIM AND DOORS

Invoice	Qty.	Description
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** BUILD ADDITIONAL THIRD CAR GARAGE SPACE WITH TANDEM. PURCHASER ACKNOWLEDGES THAT EXISTING WINDOW IN BEDROOM 2 WILL BE REDUCED IN SIZE AND/OR RELOCATED ALONG THE WALL TO PERMIT TANDEM
2379 20Jan21 NoCat	1	.FAMILY ROOM - OPT. COFFERED CEILING AS PER PLAN
2379 20Jan21 NoCat	1	.FAMILY ROOM - OPT. WAFFLE CEILING, BEAM DETAIL AS PER PLAN (6 BOXES) OPTION#1 CTR-B07
2665 25Mar21 NoCat	1	WINDOW STOOLS AND APRON PRODUCT SELECTION - SIGNED DOCUMENTS ATTACHED



CONSTRUCTION SUMMARY

Lot: 132
Model: 50.06 B SILVERWOOD
Project/Phase: Pine Valley Forevergreen / 1

KITCHEN AND BATH CABINETRY

Invoice	Qty.	Description
2379 20Jan21 NoCat	1	.KITCHEN - UPGRADE TO 8" DUCT (INTERIOR WALL) IN LIEU OF STANDARD OFFERING
2490 20Jan21 NoCat	1	THRU OUT: SEE ATTACHED CABINETRY SCHEDULE
2592 10Mar21 NoCat	1	SEE ATTACHED *REVISED CABINETRY SCHEDULE* TO BE PAID ON FINAL INSTALLMENT - APRIL 19 2021

PAINT

Invoice	Qty.	Description
2379 20Jan21 NoCat	1	.FAMILY ROOM - OPT. COFFERED CEILING AS PER PLAN
2379 20Jan21 NoCat	1	.FAMILY ROOM - OPT. WAFFLE CEILING, BEAM DETAIL AS PER PLAN (6 BOXES) OPTION#1 CTR-B07
2490 20Jan21 NoCat	2	MAIN STAIRS BASEMENT TO 2ND FLOOR: STAIN STAIRS AND LANDINGS
2665 25Mar21 NoCat	1	WINDOW STOOLS AND APRON PRODUCT SELECTION - SIGNED DOCUMENTS ATTACHED

PLUMBING

Invoice	Qty.	Description
2245 06Aug20 NoCat	1	.BACK-FLOW PREVENTER VALVE
2379 20Jan21 ** NoCat	1	APRILAIRE 600 WHOLE HOUSE STEAM HUMIDIFIER (UP TO 4,000 SQ.FT.) - COMPLETE WITH HI VOLTAGE WIRING, 240V DOUBLE BREAKER 20 AMP, SHUT OFF VALVE
2490 20Jan21 NoCat	1	KITCHEN: BLANCO QUATRUS R15 U2 #401519

STAIRS AND RAILINGS

Invoice	Qty.	Description
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** VENDOR TO PROVIDE A SERVICE STAIRCASE TO BASEMENT



CONSTRUCTION SUMMARY

Lot: 132
Model: 50.06 B SILVERWOOD
Project/Phase: Pine Valley Forevergreen / 1

TRIM AND DOORS

Invoice	Qty.	Description
2490 20Jan21 NoCat	1	THRU OUT: UPGRADE TRIM TO WINDOW STOOLS AND APRONS

WINDOWS - BASEMENT

Invoice	Qty.	Description
2245 72,675 06Aug20	3	.BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 10" FRAME (PINEVALLEY 50 FOOT LOTS ONLY)
2245 72,678 06Aug20	1	.BASEMENT WINDOWS - EGRESS BASEMENT WINDOW 40" X 24" - 10" FRAME (PINEVALLEY 50 FOOT LOTS ONLY)

WINDOWS AND DOORS

Invoice	Qty.	Description
2245 06Aug20 NoCat	1	**CUSTOM LAYOUT** BUILD ADDITIONAL THIRD CAR GARAGE SPACE WITH TANDEM. PURCHASER ACKNOWLEDGES THAT EXISTING WINDOW IN BEDROOM 2 WILL BE REDUCED IN SIZE AND/OR RELOCATED ALONG THE WALL TO PERMIT TANDEM
2379 20Jan21 NoCat	1	.GREAT ROOM: UPGRADE EXTERIOR SLIDING DOOR ASSEMBLY TO 96"
2379 20Jan21 NoCat	1	.MASTER BEDROOM: UPGRADE EXTERIOR GARDEN DOOR ASSEMBLY TO 96"

AVG

LOT 32 March 29/21



AVM-368PS

36" Insert hood - MSRP: \$649.00




Model		AVM-368PS
Features		
Control	Mechanical push buttons	
Lighting	2 bulbs, 3W LED (bulbs included)	
Blower type	860 CFM, 3-Speed	
Blower performance	Speed 1, 0.7 sones	
	Speed 3, 4.0 sones	
Filter type	2 aluminium superior micro hole filters and stainless steel baffle filters included	
Duct transition	6" Round (Top)	
Ducting	Ducted	
Exterior Appearance		
Stainless steel grade	201	
Electrical Requirements		
Electrical requirements	120V / 60Hz / 2.7 Amps	
Dimensions		
Dimensions	35 1/2" (W) x 11 3/8" (D) x 13 1/2" (H)	
Warranty		
1-year Warranty	Parts and labour, in-home service	

The information contained herein is based on sources that we believe to be reliable, but is not guaranteed by us, may be incomplete or may change without notice


WA 32 March 29/21

28
Be
AVM-278/368PS

Dimensions



Installation



A	Floor to ceiling height	variable
B	Floor to counter top height (standard)	36"
C	Recommended height between cooking surface and bottom of the hood	26" to 30"
D	Hood height (including transition height (4"))	16"
E	Cabinet height	N/A

Duct transition

Top 6" Round



The information contained herein is based on sources that we believe to be reliable, but is not guaranteed by us, may be incomplete and/or may change without notice.


Need technical support? 1(888) 651-2534

Lot 52 March 4/21



36" Gas Cooktop

Benchmark® Series – Stainless Steel NGMP656UC



NGMP656UC
Stainless Steel

The 36" Benchmark® Series gas cooktop features a dual-stacked burner that delivers both a low simmer and high heat flame.

Features & Benefits

- Dual stacked burner designed for faster boil time (20,000 BTUs) and a low simmer
- OptiSim® Burner – simmer delicate sauces and melt chocolate without scorching
- Electronic re-ignition will automatically re-ignite the burner in case the flame goes out
- Continuous grates make moving heavy pots easier
- Distinctive red LED light indicates burners are on

General Properties	
Knob material	Metal
Sealed burners	Yes
Grate material	Cast iron
Element Performance	
Total BTU load (NG / LP)	59,500 / 47,300
Power of front left burner (NG / LP)	12,000 / 9,100
Power of back left burner (NG / LP)	10,000 / 9,100
Power of center burner (NG / LP)	20,000 / 15,000
Power of back right burner (NG / LP)	5,500 / 5,000
Power of front right burner (NG / LP)	12,000 / 9,100
Technical Details	
Watts	380 W
Circuit breaker	15 A
Volts	120 V
Frequency	60 Hz
Plug type	3 prong
Power cord length	60"
Energy source	Gas
Convertible to LP (kit required)	Yes

Dimensions & Weight	
Overall appliance dimensions (HxWxD)	3 13/16" x 37" x 21 1/4"
Required cutout size (HxWxD)	3 13/16" x 34 15/16" x 19 1/8"
Minimum distance from counter front	1 7/8"
Minimum distance from rear wall	3"
Net weight	35 lbs
Accessories – Included	
Included	LP conversion kit
Accessories – Optional	



HEZ298102
Wok ring



HEZGR301
Griddle



For help and assistance with Bosch accessories please visit: www.bosch-eshop.com/eshop/bosch/us or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 6am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties: Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches of stainless steel, paint/porcelain blemishes, chip, dents, or other damage) to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is", or "B" stock appliances.

For more information on our entire line of products, go to www.bosch-home.com/us or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.




Lot 32 March 29/21

36" Gas Cooktop

Benchmark® Series – Stainless Steel NGMP656UC



Installation Details



For help and assistance with Bosch accessories please visit: www.bosch-eshop.com/eshop/bosch/us or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 6am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties: Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches of stainless steel, paint/porcelain blemishes, chip, dents, or other damage) to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is", or "B" stock appliances.


For more information on our entire line of products, go to www.bosch-home.com/us or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.


Lot 32 Mana 29/24

36" Gas Cooktop

Benchmark® Series – Stainless Steel NGMP656UC



Installation Details



For help and assistance with Bosch accessories please visit: www.bosch-eshop.com/eshop/bosch/us or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 6am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties: Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches of stainless steel, paint/porcelain blemishes, chip, dents, or other damage) to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is", or "B" stock appliances.


For more information on our entire line of products, go to www.bosch-home.com/us or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.

Lot 32 March 29/21

36" Counter-Depth 3-Door Refrigerator

800 Series – Stainless Steel B36CT80SNS



B36CT80SNS
Stainless Steel

Also available in:
Black Stainless Steel
B36CT80SNB

Introducing the revolutionary, new FarmFresh System™, with four freshness technologies designed to work together to keep your food fresher, longer. Enjoy less food waste, new innovative features and more thoughtful design.

Features & Benefits

VitaFreshPro™ provides pre-programmed freshness settings to optimize temperature and humidity to keep meat, fish, and produce fresher, longer.

Interior Water Dispenser is thoughtfully placed inside for refreshing water at the touch of a button or a push of a nozzle.

FlexBar™ utilizes typically unused space in the upper refrigerator cavity.

General Properties	
Full 72" height and true counter depth for built-in appearance	Yes
Easy Clean Stainless Steel	Yes
Lighting	Recessed LED light bars
Number of compressors/evaporators	2 / 2
Defrost process refrigerator section	Frost-free
Number of shelves – refrigerator	5
Adjustable shelves – refrigerator	4 half-width
Shelf material – refrigerator	Tempered glass
Type of shelves – refrigerator	Frameless split shelves with metal trim
Flexible storage bar	FlexBar™
Gallon storage bins	2
Humidity control compartments	2
Full width temp. & humidity controlled drawer	VitaFreshPro™
Ice maker	Yes
Water filter	UltraClarityPro™
Internal water dispenser	Yes
Touch control panel	Yes
AirFresh® filter	Yes
FreshProtect™ ethylene filter	Yes
MultiAirFlow™	Yes
Stainless steel back wall	Yes
Defrost process freezer section	Automatic
Number of drawers – freezer	3
Wi-Fi enabled	Yes, Home Connect™ app

Capacity	
Total capacity (cu. ft.)	20.8
Refrigerator capacity (cu. ft.)	14.8
Freezer capacity (cu. ft.)	6
Technical Details	
Current (A)	15 A
Volts (V)	115 V
Frequency (Hz)	60 Hz
Power cord length (in.)	91
Plug type	120V-3 prong
Dimensions & Weight	
Appliance dimensions with hinges, handles and doors (HxWxD) (in.)	72" x 35 5/8" x 31 1/8"
Appliance dimensions without hinges and doors (HxWxD) (in.)	71 1/2" x 35.5/8" x 24"
Appliance dimensions with hinges and doors, no handles (HxWxD)(in.)	72" x 35 5/8" x 28 3/4"
Required cutout size (HxWxD) (in.)	72" x 36" x 25"
Net weight (lbs)	350 lbs
Efficiency	
Energy consumption (kWh/yr)	570
ENERGY STAR® qualified	Yes
Accessories	
UltraClarityPro™ Water Filter: BORPLFTR50 FlexBar™ Bottle Holder: BOFLEXBOTL FlexBar™ Deep Shelf: BOFLEXLGSH FlexBar™ Shallow Shelf: BOFLEXSMH Ethylene Filter Refill Kit: FPETHRF50	

Home Connect



*When leveling legs are fully extended, add 5/8" to overall height, total 72 5/8".

**The cutout depth of 25" includes the required 1" airflow. The electrical covers on the back of unit do not require additional depth.

Accessories: To purchase Bosch accessories, cleaners & parts please visit www.bosch-home.com/us/store or call 1-800-944-2904 (Mon to Fri 5 am to 6 pm PST, Sat 6 am to 3 pm PST).

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout.

Warranties: Please see Use & Care manual or Bosch website for statement of limited warranty.


For more information on our entire line of products, go to www.bosch-home.com/us or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.



Lot 32 March 29/21

36" Counter-Depth 3-Door Refrigerator

800 Series – Stainless Steel B36CT80SNS



Installation Details



Accessories: To purchase Bosch accessories, cleaners & parts please visit www.bosch-home.com/us/store or call 1-800-944-2904 (Mon to Fri 5 am to 6 pm PST, Sat 6 am to 3 pm PST).

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout.

Warranties: Please see Use & Care manual or Bosch website for statement of limited warranty.


For more information on our entire line of products, go to www.bosch-home.com/us or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.

Lot 32 March 29/21

24" Scoop Handle Dishwasher

300 Series DLX – Stainless Steel SHS863WD5N



SHS863WD5N
Stainless Steel

Also available in:

White SHS863WD2N
Black SHS863WD6N

The 3rd rack provides the perfect space for silverware and large utensils while its V shape leaves room below for taller items.

Features & Benefits

44 dBA: Quietest dishwasher brand in North America.*

A 3rd rack adds versatility and offers 30% more loading area.

FlexSpace™ Tines fold back to fit your larger pots & pans.

RackMatic® offers 3 height levels, for 9 possible rack positions.

Speed60® gets your dishes dirty to dry in about an hour.

General Properties	
Number of wash cycles	5
Number of options	5
dBA	44
Third rack	Standard 3rd Rack
Rack adjustability	Rackmatic®
Tub material	Stainless Steel
Control type	Buttons
Concealed heating element	Yes
Leak protection system	24/7 AquaStop®
Water softener	No
Five-level wash	Yes
ChildLock	No
Special features	Intolight®, Extra Dry Option

Efficiency	
Water usage per cycle	3.5
Energy efficiency class	Tier 1
ENERGY STAR® qualified	Yes
Total annual energy consumption (kWh)	269
Total annual water consumption (g)	623.5

Capacity	
Number of place settings	16

Technical Details	
Watts (W)	1440 W
Current (A)	12 Amps
Volts (V)	120 V
Frequency (Hz)	60 Hz
Power cord length	N/A
Minimum water pressure (lb/sin)	14
Length outlet hose (in)	79"

Dimensions & Weight	
Overall appliance dimensions (HxWxD) (in)	33 7/8" x 23 9/16" x 23 3/4"
Required cutout size (HxWxD) (in)	33 7/8" x 23 5/8" x 24"
Adjustable feet	Yes
Net weight (lbs)	91 lbs

Accessories – Optional	
Drain Hose Extension Kit	SGZ1010UC
Dishwasher Accessory Kit	SMZ5000
Anti-Tarnish Silverware Cassette	SMZ5002UC
Power Cord with Cold Plug	SMZ10002UC



*Based on an average of sound ratings of 24" Full Size Stainless Steel Tub dishwashers contained in major brands US & Canadian websites. Major brands defined as TraQline Top 5 Market Share (US & Canada) December 2016.



For help and assistance with Bosch accessories please visit: www.bosch-eshop.com/eshop/bosch/us or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 6am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties: Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches of stainless steel, paint/porcelain blemishes, chip, dents, or other damage) to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is", or "B" stock appliances.

For more information on our entire line of products, go to www.bosch-home.com/us or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.






lot 32 March 29/21

24" Scoop Handle Dishwasher

300 Series DLX – Stainless Steel SHS863WD5N



Installation Details



For help and assistance with Bosch accessories please visit: www.bosch-eshop.com/eshop/bosch/us or call 1-800-944-2904 Mon-Fri 5am to 6pm PST Sat 6am to 3pm PST

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's Installation Instructions for final dimensional data and other details prior to making cutout. Applicable product warranty can be found in accompanying product literature or you may contact your account manager for further details.

Warranties: Bosch warrants that the Product is free from defects in materials and workmanship for a period of three hundred and sixty-five (365) days from the date of purchase. The foregoing timeline begins to run upon the date of purchase, and shall not be stalled, tolled, extended, or suspended, for any reason whatsoever. This Product is also warranted to be free from cosmetic defects in material and workmanship (such as scratches of stainless steel, paint/porcelain blemishes, chip, dents, or other damage) to the finish of the Product, for a period of thirty (30) days from the date of purchase or closing date for new construction. This cosmetic warranty excludes slight color variations due to inherent differences in painted and porcelain parts, as well as differences caused by kitchen lighting, product location, or other similar factors. This cosmetic warranty specifically excludes any display, floor, "As Is", or "B" stock appliances.

For more information on our entire line of products, go to www.bosch-home.com/us or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.

Lot 32


March 27/21

30" Speed Combination Oven

800 Series – Stainless Steel HBL8753UC



BOSCH
Invented for life



HBL8753UC
Stainless Steel

Also available in:

Black HBL8743UC
Stainless Steel

Bosch speed combination ovens create an all-in-one cooking center with an upper speed oven and a Genuine European Convection oven below.

Features & Benefits

2-in-1 microwave and convection oven with 9 SpeedChef® programs to simplify cooking with fast results.

Lower oven's convection multi-rack mode gives uniform baking results even when using all 3 racks simultaneously.

Oven is equipped with a self-cleaning cycle that easily cleans itself via 2, 3, and 4 hour cycle options.

Download the Home Connect app to remotely monitor and control your Bosch wall oven with your smart phone or tablet.

General Properties

Home Connect™ – lower cavity (WiFi enabled)	Yes
Cooking modes – upper cavity	Speed oven; 12 Auto Programs (including Auto Defrost, Melt Butter, Soften Ice Cream, Pizza), 9 Sensor Cook Programs, 9 SpeedChef® Programs, Hi & Lo Broil, European Convection, Keep Warm, Frozen Foods
Cooking modes – lower cavity	Bake, Variable Broil (hi & low), Roast, Warm, Sabbath, Proof Dough, Convection Bake, Convection Broil, Convection Roast, Pizza, Multi Rack Genuine European Convection, Convection Conversion, Temperature Probe, Fast Preheat
Cleaning type – lower	Self Clean
Telescopic rack	1
Illumination type	LED (Upper) / Incandescent (Lower)
Interior lights	1 Upper / 2 Lower

Oven Performance

Microwave power – upper cavity	1000 W
Bake / broil element wattages – upper cavity	600 / 1,750 W
Convection element wattages – upper cavity	1,700 W
Bake / broil element wattages – lower cavity	2,400 / 3,800 W
Convection element wattages – lower cavity	2,000 W

Technical Details

Watts (W)	9,600 W
Circuit breaker (A)	40 A
Volts (V); Frequency (Hz)	240 / 208 V, 60 Hz
Power cord length (in)	50"
Plug type	Fixed Connection, No Plug
Energy source	Electric

Dimensions & Weight

Overall appliance dimensions (HxWxD)(in)	49" x 29 3/4" x 24 1/2"
Required cutout size – Standard (HxWxD) (in)	48 5/8" x 28 1/2" x 23 1/2"
Required cutout size – Flush (HxWxD) (in)	49 1/8" x 30" x 24 1/2"
Speed oven cavity size – upper	1.6 cu. ft.
Overall upper speed oven interior dimensions (HxWxD) (in.)	9 7/8" x 16 1/2" x 16 1/2"
Metal turntable diameter (in)	14 1/8" dia.
Ceramic tray diameter (in)	13 3/4" dia.
Rack – rectangular cookware max. – upper	15" x 12"
Oven cavity size – lower	4.6 cu. ft.
Overall lower oven interior dimensions (HxWxD) (in)	17 13/16" x 24 1/8" x 18"
Usable lower oven interior dimensions (HxWxD) (in)	12 1/4" x 23 1/4" x 15 1/4"
Net weight (lbs)	259 lbs

Accessories – Included

Upper Oven: Metal Turntable, Square rack, Ceramic Cooking Tray
Lower Oven: 1 Telescopic and 2 Standard Oven Racks, Meat Probe

Accessories – Optional



HEZTR301
30" Telescopic Rack





home
connect

*Lower wall oven only

Accessories: To purchase Bosch accessories, cleaners & parts please visit www.bosch-home.com/us/store or call 1-800-944-2904 (Mon to Fri 5 am to 6 pm PST, Sat 6 am to 3 pm PST).
Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout.
Warranties: Please see Use & Care manual or Bosch website for statement of limited warranty.
For more information on our entire line of products, go to www.bosch-home.com/us or call 1-800-944-2904
© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.



800 Series – Stainless Steel HBL8753UC



© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.


Lot 32 March 29/21

30" Speed Combination Oven

800 Series – Stainless Steel HBL8753UC



Installation Details



Accessories: To purchase Bosch accessories, cleaners & parts please visit www.bosch-home.com/us/store or call 1-800-944-2904 (Mon to Fri 5 am to 6 pm PST, Sat 6 am to 3 pm PST).

Notes: All height, width and depth dimensions are shown in inches. BSH reserves the absolute and unrestricted right to change product materials and specifications, at any time, without notice. Consult the product's installation instructions for final dimensional data and other details prior to making cutout.

Warranties: Please see Use & Care manual or Bosch website for statement of limited warranty.


For more information on our entire line of products, go to www.bosch-home.com/us or call 1-800-944-2904

© BSH Home Appliances Corporation. All rights reserved. Bosch is a registered trademark of Robert Bosch GmbH.




PINE VALLEY
FOREVERGREEN

WINDOW STOOLS & APRONS




802

2 1/4" x 1 1/16"




901

1 1/4" x 1 11/16"



827

2 1/2" x 1 3/4"



927

1 3/8" X 2 1/2"

☐ 802 + 901 PACKAGE

☐ 827 + 927 PACKAGE

Lot#

132

Date:

MAR 18 2021

Room:

THRU OUT



Signature:

Attached

Signature:

GOLDPARK
WORTH MORE

WINDOW STOOLS & APRONS



☒ 802 + 901 PACKAGE

☐ 827 + 927 PACKAGE

Lot# 132	Date: MAR 18 2021	Room: HALL OUT
Signature: <i>[Signature]</i>		
Signature: <i>[Signature]</i>		

GOLDPARK

PV-132 Cabinetry Schedule

Amended March 4th, 2021

ROOM	DESCRIPTION	PRICE	QTY
KITCHEN	ADD: FLIP UP CABINET ABOVE FRIDGE/FREEZER	525.00	1
		CABINETRY TOTAL:	

LOT #: PV-132

DATE: March 4, 2021

SIGNATURE:

attached

SIGNATURE:

GOLDPARK
WORTH MORE

REVISED:
2021-03-04 12:25


REVISED &

March 4, 2021

attached

PV-132

OPTION 2





PV-132 Cabinetry Schedule

Amended March 4th, 2021

ROOM	DESCRIPTION	PRICE	QTY	TOTAL
KITCHEN	ADD: FLIP UP CABINET ABOVE FRIDGE/FREEZER	\$25.00	1	
		CABINETS TOTAL:		


LOT # PV-132	DATE March 4, 2021
SIGNATURE (MO)	
SIGNATURE	

GOLD PARK

REVISED:
2021-03-04 12:27

OPTION 2

* REVISED *
March 4, 2021
PV-139 (10)



Purchaser: Mario DiLeo

Property: 132 of Plan -

Telephone Res. / Bus: /

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Yolande Somerville

Model and Elevation: 50.06 B SILVERWOOD

Layout Changes: ☐ Yes ☒ No

Sketch Attached: ☒ Yes ☐ No

Exterior Colour Scheme:

1. Cabinetry

	Style and Colour	Counter	Hardware
Kitchen / Breakfast	*Medio 6 'Oyster'	*Quartz: 'Frosty Carina'	bh0519
Laundry Room	Bowery 'Ello'	P-Lam 'White'	k00203
Powder Room	*Medio 6 'Glazed Oyster'	*Quartz: Jasmine Pearl	k00203
Master Ensuite Bathroom	*Medio 6 'Oyster'	*Quartz: Cosmopolitan White	k00203
Second Ensuite Bathroom (If Applicable)	Tribeca 'Stello'	Quartz: Nordic Loft	k00203
Shared Bath	Bowery 'Ello'	Quartz: Ice Snow	k00203

Comment

2. Floor Tile

	Selection
Entrance Vestibule	*12x24" Marmorea polished 'Grigio Imperial'
Main Hall	n/a
Kitchen / Breakfast	(hardwood)
Laundry Room	*12x24" Land 'Bianco' (Mud Room)
Powder Room	*12x24" Marmorea polished 'Grigio Imperial'
Shared Bath	*12x24" Land 'Bianco'
Master Ensuite Bathroom	*12x24" Eterna polished 'Medium Grey'
Second Ensuite Bathroom (If Applicable)	*12x24" Eterna polished 'Imperial Grey'
Lower Landing (If Applicable)	13x13" Costa 'White'
Master ensuite shower floor	*2x2" Ontario matte 'Taupe' (square)

Comment

Ensuite 2 Shower Floor: 2" Quebec 'Arctic White' (square) // Shared Bath: std 2x2" white

3. Wall Tile

	Selection	Listello/Inserts	Describe
		☐ Yes ☒ No	
Master Ensuite Bathroom			
Tub Deck	n/a	☐ Yes ☒ No	
Shower Stall	*10x30" Roma filo decor Statuario'	☐ Yes ☒ No	
Bathroom Walls	n/a	☐ Yes ☒ No	
Second Ensuite Bathroom (If Applicable)	*12x24" Eterna pol 'Imperial Grey'	☐ Yes ☒ No	
Shared Bath	8x10" Uniwall 'White'	☐ Yes ☒ No	
Kitchen Backsplash	☒ Yes ☐ No	Backsplash Behind Fridge	
	see below		

Comment

Kitchen Backsplash: SLAB FHBS same as counter **at range wall only** + Servery: 3x12" Oxford 'Silver Metallic' **as servery only**

su attached

Purchaser: Mario DiLeo

Property: 132 of Plan -

Telephone Res. / Bus: /

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Yolande Somerville

Model and Elevation: 50.06 B SILVERWOOD

4. Plumbing Fixtures

Master Ensuite Bathroom Second Ensuite Powder Room
Other Room - Specify Other Washroom

Comment

Standard except kitchen sink

5. Hardwood Flooring

	Type and Stain		Type and Stain
Main Hall		Upper Landing	
Kitchen / Breakfast	*3/4x6-1/2" sculpted 'Athena'	Upper Hall	
Living Room		Master Bedroom	
Dining Room		Bedroom #2	
Family Room		Bedroom #3	
Den/Library		Bedroom #4	
Entrance Vestibule		Bedroom #5	
Lower Landing (If Applicable)		Other Room - Specify	
		Thru out standard areas	*3/4x6-1/2" sculpted 'Athena'

Comment

6. Carpeting

	Upgrade	Description
Ground Floor	☐	
Second Floor	☐	
	☐	

	Type	Area
Upgrade Underpad		
Carpet on Stairs	Capped	Runner - *Upgrade

Comment

7. Fireplace

	Living Room			Family Room			Other Room - Specify		
	Purchased	As Per Plan	N/A	Purchased	As Per Plan	N/A	Purchased	As Per Plan	N/A
Fireplace Type	☐	☐	☒	☐	☒	☐	☐	☐	☒
Mantle Type									
Colour / Stain									
Surround									
Hearth									

Comment

See attached

Purchaser: Mario DiLeo

Property: 132 of Plan -

Telephone Res. / Bus: /

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Yolande Somerville

Model and Elevation: 50.06 B SILVERWOOD

8. Trim Carpentry

Interior Doors Carrara - solid ☐ Front Door Glass Inserts n/a ☐ Door Handles standard ☐
 Interior Trim Standard ☐
 Comment

9. Plaster Mouldings and Medallions

Standard Throughout ☐ Yes ☐ No ☒ N/A

Entrance Vestibule			Kitchen/Breakfast		
Main Hall			Den/Library		
Living Room			Lower Landing		
Dining Room			Other Room - Specify		
Family Room					

Comment

10. Railings and Spindles

Railing Package Standard 2 square oak pickets
 Railing Colour *Hopscotch Spindle Colour *Hopscotch
 Stringer / Riser *Hopscotch Treads *Hopscotch
 Oak Stairs ☒ Yes ☐ No ☐ N/A

Comment

11. Wall Paint / Ceilings

Throughout Finished Areas Warm Grey

Trim Paint White

Smooth Ceilings

Ground Floor ☒

Second Floor ☒

Note

Comment see attached

Purchaser: Mario DiLeo

Property: 132 of Plan -

Telephone Res. / Bus: /

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Yolande Somerville

Model and Elevation: 50.06 B SILVERWOOD

12. Electrical

Hood Fan ☐ White ☐ Stainless ☒ N/A

Above Kitchen Cabinet Light ☐ Yes ☒ No

Below Kitchen Cabinet Light ☐ Yes ☒ No

Standard Appliances ☐

Over The Range Microwave ☐

Chimney Style Fan ☐

Comment

13. Heating and Air Conditioning

Air Conditioning

Gas Provisions Stove

Gas Provisions Dryer

Gas Provisions Barbecue

Comment

14. Additional Comments

15. Disclaimers and Notes

- Colours of all materials are as close as possible to builder's selection, but not necessarily identical due to variances in manufacturing.
- Any extras listed above are null and void unless accompanied by a separate invoice/amendment. Said invoice must be paid in full.
- The Purchaser acknowledges that after Interior Colour Selection form is signed and dated, no further changes will be permitted other than re-selection due to unavailability. _____ Purchaser's Initials
- The Purchaser acknowledges reading and accepting the "Gold Park Homes Decor Centre Disclaimers" form. This document contains other miscellaneous disclaimers.

This Interior Colour Selection is final and approved by:

Signature: see attached Date: Jan 19, 2021

PV-132 Cabinetry Schedule

ROOM	DESCRIPTION	PRICE	QTY	TOTAL
MASTER ENSUITE	UPGRADE FROM SERIES 2 TO SERIES 5 (MEDIO 6 OYSTER)		1	
POWDER ROOM	UPGRADE FROM SERIES 2 TO SERIES 5 (MEDIO 6 OYSTER)		1	
KITCHEN & ISLAND	UPGRADE KITCHEN CABINETS FROM SERIES 2 TO SERIES 5 (MEDIO 6 OYSTER)		1	
	UPGRADE ISLAND CABINETS FROM SERIES 2 TO SERIES 5		1	
	CONVERT STD. CABINETRY TO TALL BUILT-IN OVEN UNIT WITH 3/4" EXTENSION WITH DRAWER BELOW		1	
	APPLIANCE HARDWARE - BAH-053-09		3	
	UPGRADE HARDWARE BH-051-09		1	
	ADD OVERSIZED DUMMY DOORS TO SIDES OF ISLAND - FOR 48"D ISLAND		1	
	CONVERT STD. CABINETRY TO TALL DEEP PANTRY - 102"H		1	
	ADD DECORATIVE HOOD FAN CABINET 36"W - ASPEN RANGE		1	
	RETURN TRIP FOR KICKPLATE ADJUSTMENTS		1	
	DÉCOR PANEL TO ACCOMMODATE DISHWASHER		1	
	DÉCOR PANEL TO ACCOMMODATE BUILT IN FRIDGE		1	
CABINETRY TOTAL:				

LOT #: PV-132

DATE: Jan. 19, 2021

SIGNATURE: see attached

SIGNATURE:


SCHEDULE 'F'



See
attach.
TV-132
JUNE 9 2020

PV-132 see attached
Jan. 19, 2021

Lot 132
50' SERIES
Elevation B • 3,465 sq.ft.



VENDOR

PURCHASER

PURCHASER

GOLDPARK
WORTH MORE™

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 5006


SCHEDULE 'F'



PV-132 *See attached*
June 9 2020
PV-132 *see attached*
Jan. 19, 2021

Lot 132
50' SERIES
Elevation B • 3,465 sq.ft.

Coffin + Waffle
REVISE to
5 Box Waffle
JAN 19 2021



SECOND FLOOR | ELEV. B

VENDOR

PURCHASER

PURCHASER

GOLDPARK
WORTH MORE™


Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 5006

SCHEDULE 'F'



PV-132
 JUNE 9 2020
 PV-132 *see attached*
 Jan. 19, 2021

Lot 132
50' SERIES
 Elevation B • 3,465 sq.ft.




VENDOR
 PURCHASER
 PURCHASER

GOLDPARK
 WORTH MORE™

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 5006

see attached
PL-132
Jan. 19, 2021

* Medio 6 : 6x6x6
BAH 051-09
BAH-053-09



PV - 132 see attached

Jan. 19, 2021

* Medio 6 : 'Glazed Oyster'




K002-03

**GOLDPARK HOMES
PINE VALLEY
VAUGHAN, ONTARIO
MODEL: (5006) SILVERWOOD**


SITE STANDARD: WHITE 3/4" EXTENSION
SOFT-CLOSE DRAWERS & STANDARD SLAM DOOR HINGES
TO VANITIES

ONE TOP DRAWER WHERE POSSIBLE THROUGHOUT EACH
VANITY, ONE BANK OF DRAWERS WHERE POSSIBLE
THROUGHOUT EACH MASTER ENSUITE VANITY


Bowery 'Ello'
K002-03



Tribeca 'Stello'
K002-03



Bowery 'Ello'
K002-03




* Medio 6 : 'Oyster'
K002-03



PINE VALLEY
FOREVERGREEN

STONE COUNTERTOP EDGE PROFILES



2CM EASED EDGE


LOCATION:

THRU OUT




3CM EASED EDGE

LOCATION:



4CM MITRED EDGE

LOCATION:



2CM OGEE EDGE

LOCATION:

LOT #: PV-132

DATE: Jan. 19, 2021

SIGNATURE: *see attached*

SIGNATURE:

GOLDPARK
WORTH MORE

STANDARD HARDWARE / KNOBS



K002-02



K002-03



K002-04

KITCHEN
ISLAND
- Rear.

→ Mud Room / Laundry Room
→ Master Ensuite
→ Shared Ensuite
→ Second Ensuite
→ Powder Room



K002-06



K002-05



K002-14



K024-03

LOT #

pV-132

DATE:

Jan. 19, 2021

SIGNATURE:

see attached

SIGNATURE:

UPGRADE HARDWARE



BH-051-09

Modern Brushed Gold - Subtle Surge Pull



LOCATION:

Kitchen

LOT # PV-132

DATE: Jan. 19, 2021

SIGNATURE: see attached

SIGNATURE:

UPGRADE HARDWARE



BAH-053-09

Appliance Pull - 'Brushed Gold'



LOCATION:

Kitchen

LOT # PV-132

DATE: Jan. 19, 2021

SIGNATURE:

see attached



SIGNATURE:

GOLDPARK
WORTH MORE

UPGRADE KITCHEN SINK



BLANCO - QUATRUS R15 U 2
Stainless Steel - Undermount
32" x 18" x 9"



Stainless Steel

☐ GRID

MODEL 401519 Stainless Steel / 406454 Grid

Lot# PV-132

Room: Kitchen

Signature: see attached

Date: Jan 19, 2021

Signature:




PINE VALLEY
FOREVERGREEN

UPGRADE SHOWER HARDWARE

MT6X6

Shower Door Handle



MT6X6
Shower Door Handle

6" x 6" back-to-back
3/4" dia. tube
Cut and mitred corners with
washers
(Also available single sided)

☒ CHROME
☐ MATTE BLACK


Lot# 132	Date: Jan. 19, 2021	Room: MASTER + ENS 2 + SHARED
Signature: see attached		
Signature:		

GOLDPARK
WORTH MORE

BATHROOM ACCESSORIES



Tissue Holder
Mason - Chrome



Towel Bar
Mason - Chrome

*Please select one of the following below:

☒ INSTALL STANDARD BATHROOM ACCESSORIES THRU OUT
(tissue holder + towel bar) **location as per vendors discretion**

☐ ***DO NOT*** INSTALL STANDARD BATHROOM ACCESSORIES
THRU OUT **tissue holder + towel bar will not be provided**

LOT # PY-132

DATE: Jan. 19, 2021

SIGNATURE:

see attached


SIGNATURE:

UPGRADE KITCHEN EXTRA



ASPEN RANGE HOOD

(Insert fan not included)



LOT #
PV-132

DATE: Jan. 19, 2021

ROOM: Kitchen

SIGNATURE:
see attached

SIGNATURE:



Project: Pine Valley

Lot: 132

Purchaser(s): Mario Dileo

Standard Hood Fan Deletion

We acknowledge that the builder's standard hood fan will not be installed.
Do not supply, install and/or credit. We will install our own hood fan after closing.

Signature: see attached

Signature: _____

Date: January 19, 2021

Purchaser: Mario DiLeo

Property: 132 of Plan -

Telephone Res. / Bus: /

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Yolande Somerville

Model and Elevation: 50.06 B SILVERWOOD

Layout Changes: ☐ Yes ☒ No

Sketch Attached: ☒ Yes ☐ No

Exterior Colour Scheme:

1. Cabinetry

	Style and Colour	Counter	Hardware
Kitchen / Breakfast	*Medio 6 'Oyster'	*Quartz 'Frosty Carina'	bh0519
Laundry Room	Bowery 'Ello'	P-Lam 'White'	k00203
Powder Room	*Medio 6 'Glazed Oyster'	*Quartz 'Jasmine Pearl'	k00203
Master Ensuite Bathroom	*Medio 6 'Oyster'	*Quartz 'Cosmopolitan White'	k00203
Second Ensuite Bathroom (If Applicable)	Tribeca 'Stello'	Quartz 'Nordic Loft'	k00203
Shared Bath	Bowery 'Ello'	Quartz 'Ice Snow'	k00203

Comment

2. Floor Tile

	Selection
Entrance Vestibule	*12x24" Marmorea polished 'Grigio Imperial'
Main Hall	n/a
Kitchen / Breakfast	(hardwood)
Laundry Room	*12x24" Land 'Bianco' (Mud Room)
Powder Room	*12x24" Marmorea polished 'Grigio Imperial'
Shared Bath	*12x24" Land 'Bianco'
Master Ensuite Bathroom	*12x24" Eterna polished 'Medium Grey'
Second Ensuite Bathroom (If Applicable)	*12x24" Eterna polished 'Imperial Grey'
Lower Landing (If Applicable)	13x13" Costa 'White'
Master ensuite shower floor	*2x2" Ontario matla 'Taupe' (square)

Comment

Ensuite 2 Shower Floor: 2" Quebec 'Arctic White' (square) // Shared Bath: std 2x2" white

3. Wall Tile

	Selection	Listello/Inserts	Describe
Master Ensuite Bathroom		☐ Yes ☒ No	
Tub Deck	n/a	☐ Yes ☒ No	
Shower Stall	*10x30" Roma filo decor Statuario	☐ Yes ☒ No	
Bathroom Walls	n/a	☐ Yes ☒ No	
Second Ensuite Bathroom (If Applicable)	*12x24" Eterna pol 'Imperial Grey'	☐ Yes ☒ No	
Shared Bath	8x10" Uniwall 'White'	☐ Yes ☒ No	
Kitchen Backsplash	☒ Yes ☐ No	Backsplash Behind Fridge	

Comment

Kitchen Backsplash: SLAB FH&S same as counter "at range wall only" + Servery. 3x12" Oxford 'Silver Metallic' "as servery only"

Purchaser: Mario DiLeo

Property: 132 of Plan -

Telephone Res. / Bus: /

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Yolande Somerville

Model and Elevation: 50.06 B SILVERWOOD

4. Plumbing Fixtures

Master Ensuite Bathroom ☐ Second Ensuite ☐ Powder Room ☐
Other Room - Specify ☐ Other Washroom ☐
Comment
Standard except kitchen sink

5. Hardwood Flooring

	Type and Stain		Type and Stain
Main Hall		Upper Landing	
Kitchen / Breakfast	*3/4x6-1/2" sculpted 'Athena'	Upper Hall	
Living Room		Master Bedroom	
Dining Room		Bedroom #2	
Family Room		Bedroom #3	
Den/Library		Bedroom #4	
Entrance Vestibule		Bedroom #5	
Lower Landing (If Applicable)		Other Room - Specify	
		Thru out standard areas	*3/4x6-1/2" sculpted 'Athena'

Comment

6. Carpeting

	Upgrade	Description
Ground Floor	☐	
Second Floor	☐	
	☐	

Upgrade Underpad Type ☐ Area ☐
Capped ☐ Runner - *Upgrade ☐
Carpet on Stairs ☐

Comment

7. Fireplace

	Living Room			Family Room			Other Room - Specify		
	Purchased	As Per Plan	N/A	Purchased	As Per Plan	N/A	Purchased	As Per Plan	N/A
Fireplace Type	☐	☐	☒	☐	☒	☐	☐	☐	☒
Mantle Type				Standard Gas					
Colour / Stain				Mediterranean					
Surround				Arctic White					
Hearth				n/a					
				none					

Comment

Scheduled Closing Date: Thursday, February 18, 2021

Purchaser: Mario DiLeo

Property: 132 of Plan -

Telephone Res. / Bus: /

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Yolande Somerville

Model and Elevation: 50.06 B SILVERWOOD

8. Trim Carpentry

Interior Doors Carrara - solid ☐ Front Door Glass Inserts n/a ☐ Door Handles standard ☐
Interior Trim Standard ☐
Comment

9. Plaster Mouldings and Medallions

Standard Throughout ☐ Yes ☐ No ☒ N/A

Entrance Vestibule	☐	☐	Kitchen/Breakfast	☐	☐
Main Hall	☐	☐	Den/Library	☐	☐
Living Room	☐	☐	Lower Landing	☐	☐
Dining Room	☐	☐	Other Room - Specify	☐	☐
Family Room	☐	☐			

Comment

10. Railings and Spindles

Railing Package Standard 2 square oak pickets ☐
Railing Colour Hopscotch ☐ Spindle Colour Hopscotch ☐
Stringer / Riser Hopscotch ☐ Treads Hopscotch ☐
Oak Stairs ☒ Yes ☐ No ☐ N/A
Comment

11. Wall Paint / Ceilings

Throughout Finished Areas Warm Grey ☐
Trim Paint White ☐
Smooth Ceilings
Ground Floor ☒
Second Floor ☒
Note

Comment

Scheduled Closing Date: Thursday, February 18, 2021

Purchaser: Mario DiLeo

Property: 132 of Plan -

Telephone Res. / Bus: /

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Yolande Somerville

Model and Elevation: 50.06 B SILVERWOOD

12. Electrical

Hood Fan ☐ White ☐ Stainless ☒ N/A

Above Kitchen Cabinet Light ☐ Yes ☒ No

Below Kitchen Cabinet Light ☐ Yes ☒ No

Standard Appliances ☐

Over The Range Microwave ☐

Chimney Style Fan ☐

Comment

13. Heating and Air Conditioning

Air Conditioning no ☐

Gas Provisions Stove no ☐

Gas Provisions Dryer no ☐

Gas Provisions Barbecue std ☐


Comment

14. Additional Comments

15. Disclaimers and Notes

- 1) Colours of all materials are as close as possible to builder's selection, but not necessarily identical due to variances in manufacturing.
- 2) Any extras listed above are null and void unless accompanied by a separate invoice/amendment. Said invoice must be paid in full.
- 3) The Purchaser acknowledges that after Interior Colour Selection form is signed and dated, no further changes will be permitted other than re-selection due to unavailability. Purchaser's Initials _____
- 4) The Purchaser acknowledges reading and accepting the "Gold Park Homes Decor Centre Disclaimers" form. This document contains other miscellaneous disclaimers.

This Interior Colour Selection is final and approved by:

Signature: 

Date: Jan 19, 2021

SCHEDULE 'F'




PV-132
June 9 2020

PV-132
Jan. 19, 2021

Lot 132
50' SERIES

Elevation B • 3,465 sq.ft.



VENDOR _____
PURCHASER _____
PURCHASER _____

GOLDPARK
WORTH MORE™

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 2006

SCHEDULE 'F'



PV-132

June 9 2020

PV-132

Jan. 19, 2021

See attached


MDC

Lot 132

50' SERIES

Elevation B • 3,465 sq.ft.

Copper +
Waffle
REVISE to
5 Box waffle
Jan 19 2021



SECOND FLOOR | ELEV B

VENDOR

PURCHASER

PURCHASER

GOLDPARK
WORTH MORE™

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & C.E. 9006

SCHEDULE 'F'




PV-132
JUNE 8 2020

See
attach.

PV-132 MDC
Jan. 19, 2021


Lot 132
50' SERIES
Elevation B • 3,465 sq.ft.



VENDOR
PURCHASER
PURCHASER

GOLDPARK
WORTH MORE™

Prices, figures, illustrations, views, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & C.E. 5006



74-132 (W)C
Jan. 19, 2021






Media 6: 6/2/2021
BH 051-09
VAN-053-09

PV-132 *MOY*
Jan. 19, 2021

* Medio to 'Glass Oyster'

**GOLDPARK HOMES
PINE VALLEY
VAUGHAN, ONTARIO
MODEL: (5006) SILVERWOOD**

SITE STANDARD: WHITE 3/4" EXTENSION
SOFT-CLOSE DRAWERS & STANDARD SLAM DOOR HINGES
TO VANITIES
ONE TOP DRAWER WHERE POSSIBLE THROUGHOUT EACH
VANITY, ONE BANK OF DRAWERS WHERE POSSIBLE
THROUGHOUT EACH MASTER ENSUITE VANITY




Tribecca 'Stella'
K002-03

Bowery 'Ello'
K002-03

* Medio to 'Oyster'
K002-03

PLAN VIEW


STONE COUNTERTOP EDGE PROFILES



2CM EASED EDGE


LOCATION:

THRU OUT




3CM EASED EDGE

LOCATION:



4CM MITRED EDGE

LOCATION:



2CM OGEE EDGE

LOCATION:

LOT #: PV-132

DATE: Jan. 19, 2021

SIGNATURE: *[Signature]*

SIGNATURE:


GOLD PARK

STANDARD HARDWARE / KNOBS



K002-02 K002-02 ISLAND - Rear.	 ☒ K002-02	K002-03 K002-03	 ☐ K002-04
	 ☐ K002-06	 ☐ K002-05	☐ K002-14 → Mud Room / Laundry Room → Master Ensuite → Shared Ensuite → Second Ensuite → Powder Room
	 ☐ K024-03		

LOT # PV-132	DATE Jan. 19, 2021
-----------------	-----------------------

SIGNATURE:	
SIGNATURE:	

GOLDPARK

UPGRADE HARDWARE



BH-051-09

Modern Brushed Gold - Subtle Surge Pull



LOCATION:

Kitchen

LOT # PV-132

DATE: Jan. 19, 2021

SIGNATURE:

[Signature]

SIGNATURE:

GOLDPARK

UPGRADE HARDWARE



BAH-053-09

Appliance Pull - 'Brushed Gold'



LOCATION:

Kitchen

LOT # PV-132

DATE: Jan. 19, 2021

SIGNATURE:

A handwritten signature in black ink, appearing to be "APC", written over a horizontal line.




SIGNATURE:

GOLDPARK

UPGRADE KITCHEN SINK



BLANCO - QUATRUS R15 U 2
Stainless Steel - Undermount
32" x 18" x 9"



Stainless Steel

☐ GRID

MODEL 401519 Stainless Steel / 406454 Grid

Lot# PV-132

Room: Kitchen

Signature:

Date: Jan 19, 2021

Signature:


GOLDPARK

UPGRADE SHOWER HARDWARE



MT6X6

Shower Door Handle



MT6X6
Shower Door Handle

6" x 6" back-to-back
3/4" dia. tube
Cut and mitred corners with
washers
(Also available single sided)

- ☒ CHROME
☐ MATTE BLACK


Lot# 132	Date: Jan. 19, 2021	Room: MASTER ENS 2 + SHARED
Signature: 		
Signature:		

GOLDPARK

BATHROOM ACCESSORIES



Tissue Holder
Mason - Chrome



Towel Bar
Mason - Chrome

*Please select one of the following below:

☒ INSTALL STANDARD BATHROOM ACCESSORIES THRU OUT
(tissue holder + towel bar) **location as per vendors discretion**

☐ ***DO NOT*** INSTALL STANDARD BATHROOM ACCESSORIES
THRU OUT **tissue holder + towel bar will not be provided**

LOT # PY-132

DATE: Jan. 19, 2021

SIGNATURE:

SIGNATURE:


GOLDPARK

UPGRADE KITCHEN EXTRA



ASPEN RANGE HOOD

(Insert fan not included)



LOT # PV-132	DATE: Jan. 19, 2021	ROOM: Kitchen
SIGNATURE: 		
SIGNATURE: 		

GOLDPARK



Project: Pine Valley

Lot: 132

Purchaser(s): Mario Dileo

Standard Hood Fan Deletion

We acknowledge that the builder's standard hood fan will not be installed.
Do not supply, install and/or credit. We will install our own hood fan after closing.

Signature: [Signature]

Signature: [Signature]

Date: January 19, 2021

DIMENSIONS


PV-132 see attached
Feb. 5, 2021

1 of 30

COMMERCIAL-STYLE RANGES

PRODUCT DIMENSIONS

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J	
	in	cm	in	cm
Overall Width (A)	29 ⁷ / ₈	75.9	35 ⁷ / ₈	91.1
Bullnose Height (B)	2 ³ / ₁₆	5.6	2 ³ / ₁₆	5.6
Control Panel Height (C)	5 ⁵ / ₁₆	13.5	5 ⁵ / ₁₆	13.5
Door Height (D)	20 ¹¹ / ₁₆	52.6	20 ¹¹ / ₁₆	52.6
Door Bottom to Handle Top (E)	20	50.8	20	50.8
Toe-Kick Height (F)	5 ¹ / ₂	14	5 ¹ / ₂	14



FRONT VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.

Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

W11255637A

DIMENSIONS


PR-132 *see attached*
Feb. 5, 2021

3 of 30

COMMERCIAL-STYLE RANGES

PRODUCT DIMENSIONS

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J	
	in	cm	in	cm
Depth with Control Panel Overhang (G)	27 ³ / ₄	70.5	27 ³ / ₄	70.5
Depth with Handle (H)	30 ¹ / ₄	76.9	30 ¹ / ₄	76.9
Depth with Door Fully Open (I)	46 ¹ / ₂	118.1	46 ¹ / ₂	118.1



TOP VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid

DIMENSIONS

8V-132 see attached
Feb. 5, 2021


5 of 30

COMMERCIAL-STYLE RANGES

PRODUCT DIMENSIONS

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
	in	cm	in	cm	in	cm
Grates Top Height (A)	37 ³ / ₁₆	94.5	37 ³ / ₁₆	94.5	37 ³ / ₁₆	94.5
Cooking Surface Top Height (B)	36	91.4	36	91.4	36	91.4
Door Top Height (C)	27 ⁷ / ₈	70.8	27 ⁷ / ₈	70.8	27 ⁷ / ₈	70.8
Handle Top Height (D)	27 ¹ / ₈	68.9	27 ¹ / ₈	68.9	27 ¹ / ₈	68.9
Toe-Kick Height (E)	6 ⁵ / ₈	16.9	6 ⁵ / ₈	16.9	6 ⁵ / ₈	16.9
OTHER DIMENSIONS						
Maximum Feet Extension Height*	1 ¹ / ₂	3.8	1 ¹ / ₂	3.8	1 ¹ / ₂	3.8

* **IMPORTANT:** Minimum height dimensions are at the lowest point of the height adjustment range.
When the leveling legs are fully extended, all heights have 1¹/₂" (3.8 cm) of added height.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.

Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid

DIMENSIONS

PV-132
Feb 5, 2021
see attached


6 of 30

COMMERCIAL-STYLE RANGES

PRODUCT DIMENSIONS

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
Unit of Measurement	in	cm	in	cm	in	cm
Depth with Door Fully Open (F)	46½	118.1	46½	118.1	46½	118.1
Depth with Handle (G)	30¼	76.9	30¼	76.9	30¼	76.9
Depth with Control Panel Overhang (H)	27¾	70.5	27¾	70.5	27¾	70.5
Depth to Toe-Kick with Door (I)	27	68.6	27	68.6	27	68.6
Depth with Door (J)	27	68.6	27	68.6	27	68.6
OTHER DIMENSIONS						
Gas Vent Height (K)*	39	99.1	39	99.1	39	99.1

*Gas Units only: KFGC500J, KFGC506J and KFGC558J.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.

Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PR-132 *see attached*
Feb. 5, 2021

DIMENSIONS

7 of 30


COMMERCIAL-STYLE RANGES

OPENING/CLEARANCE DIMENSIONS



MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
Unit of Measurement	in	cm	in	cm	in	cm
Combustible Area above Cooking Surface Width (min.) (A)	30	76.2	36	91.4	48	121.9
Bottom of Cabinet Height above Cooking Surface (min.) (B)*	42	106.7	58	147.3	58	147.3
Bottom of Cabinet Height above Countertop (min.) (C)	18	45.7	18	45.7	18	45.7
Distance to Fixed Wall or Combustible Material (min.) (D)	12	30.5	12	30.5	12	30.5
Opening Width (min.) (E)	30	76.2	36	91.4	48	121.9

* If installing a hood or hood liner above the range, follow the hood or hood liner instructions for dimensional clearances above the cooking surface.



FRONT VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid

DIMENSIONS

PV-132
Feb. 5, 2021

see attached

8 of 30


COMMERCIAL-STYLE RANGES

OPENING/CLEARANCE DIMENSIONS

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
	in	cm	in	cm	in	cm
Upper Cabinet Depth (max.) (F)	13	33	13	33	13	33
Depth from Wall to Grates (G)*	1½	3.9	1½	3.9	1½	3.9
Depth from Wall to back of Unit**	0	0	0	0	0	0

* If the back wall is constructed of a combustible material and a backsplash is not installed a 7½" (19.1 cm) minimum clearance is required.

** If the back wall is constructed of a combustible material and a backsplash is not installed a 6" (15.2 cm) minimum clearance is required.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.

Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All KitchenAid® appliances are appropriately UL, CUL or CSA approved.


KitchenAid®

PV-132 *attached*
Feb. 5, 2021

KitchenAid®

30" Combination Wall Oven

KOCE500E



Stainless Steel
KOCE500ESS

Capacity

Oven 6.4 cu. ft.

General Features & Properties

Temperature Probe

EasyConvert™ Conversion System

5.0 Cu. Ft. Total Capacity (lower oven)

1.4 Cu. Ft. Capacity (upper oven)

Crispwave™ Microwave Technology and
Crisper Pan (upper oven)

SatinGlide™ Roll-Out Extension Rack (lower
oven)

Electrical Details

Amps 40

Volts 240

Technical Details

Fuel Type Electric

Oven Type Combination

Number of Oven Racks 3

Cleaning Type Adjustable
Self-Cleaning

Dimensions

Product Dimensions
(H x W x D) 42-1/2" x
30" x
27-1/8"

Depth with Door Open 90° 46-3/4"

Cutout Dimensions
(H x W x D) 41-5/16" x
28-1/2" x
24"

Reference Material

[Dimension Guide](#)

[Install Guide](#)

[Use & Care Guide](#)

[Warranty](#)

Also available in:

- ☐ White KOCE500EWH
- ☒ Black KOCE500EBL
- ☒ Black Stainless KOCE500EBS

Key Features & Benefits

Even-Heat™ True Convection Oven (lower oven)


Provides consistent heating and even cooking on all racks with a unique bow-tie shaped design and convection fan that helps ensure the most even baking.

Microwave Convection Cooking (upper oven)

Increases the speed of cooking and provides a secondary convection cooking option.

Professionally-Inspired Design

Combines a bold blend of professionally-inspired styling with sleek touches for the home. This beautiful built-in wall oven features Satin Textured Handles and the KitchenAid® Badge, a symbol of uncompromised quality.



NOTE: Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.


©/™ © 2020. All rights reserved. Printed in the U.S.A. D200104XXE. KOCE500ESpecSheetV01.

- Electrical supply junction box should be located 3" (7.6 cm) maximum below the support surface when the oven is installed in a wall cabinet. A 1" (2.5 cm) minimum diameter hole should have been drilled in the left rear corner of the support surface to pass the appliance cable through to the junction box.
- Oven support surface must be solid, level and flush with bottom of cabinet cutout. Floor must be able to support a total weight (microwave and built-in oven) of 208 lbs (95 kg) for 27" (68.6 cm) models or 249 lbs (113 kg) for 30" (76.2 cm) models.

IMPORTANT: To avoid damage to your cabinets, check with your builder or cabinet supplier to make sure that the materials used will not discolor, delaminate or sustain other damage. This oven has been designed in accordance with the requirements of UL and CSA International and complies with the maximum allowable wood cabinet temperatures of 194°F (90°C).

Product Dimensions

27" and 30" (68.6 cm and 76.2 cm) Ovens



27" (68.6 cm) models


- A. 42 $\frac{5}{16}$ " (108.0 cm) overall height
- B. 25 $\frac{7}{16}$ " (64.6 cm) recessed width
- C. 41" (104.1 cm) recessed height
- D. 23 $\frac{1}{4}$ " (59.1 cm) max. recessed depth
- E. 27" (68.6 cm) overall width
- F. 48" (121.9 cm) flexible conduit length measured from the conduit clamp located at the rear of the oven. Do not remove the conduit clamp.

30" (76.2 cm) models

- A. 42 $\frac{5}{16}$ " (108.0 cm) overall height
- B. 28 $\frac{7}{16}$ " (72.2 cm) recessed width
- C. 41" (104.1 cm) recessed height
- D. 23 $\frac{1}{4}$ " (59.1 cm) max. recessed depth
- E. 30" (76.2 cm) overall width
- F. 48" (121.9 cm) flexible conduit length measured from the conduit clamp located at the rear of the oven. Do not remove the conduit clamp.

Cabinet Dimensions

27" and 30" (68.6 cm and 76.2 cm) Ovens



27" (68.6 cm) models

- A. 27" (68.6 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 19 $\frac{1}{4}$ " (48.9 cm) bottom of cutout to floor is recommended. 4"-19 $\frac{1}{4}$ " (10.2-48.9 cm) bottom of cutout to floor is acceptable.
- D. 25 $\frac{1}{2}$ " (64.8 cm) cutout width
- E. 1 $\frac{1}{2}$ " (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 41 $\frac{5}{16}$ " (105 cm)* recommended cutout height
- G. 24" (60.7 cm) cutout depth

30" (76.2 cm) models

- A. 30" (76.2 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 19 $\frac{1}{4}$ " (48.9 cm) bottom of cutout to floor is recommended. 4"-19 $\frac{1}{4}$ " (10.2-48.9 cm) bottom of cutout to floor is acceptable.
- D. 28 $\frac{1}{2}$ " (72.4 cm) cutout width
- E. 1 $\frac{1}{2}$ " (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 41 $\frac{5}{16}$ " (105 cm)* recommended cutout height
- G. 24" (60.7 cm) cutout depth

***NOTE:** The cutout height can be between 41" and 41 $\frac{1}{2}$ " (104.1 cm and 105.6 cm) for microwave/oven combination.

Electrical Requirements

If codes permit and a separate ground wire is used, it is recommended that a qualified electrical installer determine that the ground path and wire gauge are in accordance with local codes.

Check with a qualified electrical installer if you are not sure the oven is properly grounded.

This oven must be connected to a grounded metal, permanent wiring system.

Be sure that the electrical connection and wire size are adequate and in conformance with the National Electrical Code, ANSI/NFPA 70-latest edition or CSA Standards C22.1-94, Canadian Electrical Code, Part 1 and C22.2 No. O-M91-latest edition, and all local codes and ordinances.

A copy of the above code standards can be obtained from:

National Fire Protection Association
1 Batterymarch Park
Quincy, MA 02169-7471

CSA International
8501 East Pleasant Valley Road
Cleveland, OH 44131-5575

PV-132


Feb. 5, 2021

See attached

KitchenAid®

24" Undercounter Wine Cellar KUWL204E

PR-132 *See Attached*
Feb. 5, 2021



Stainless Steel
KUWL204ESB

Also available in:

Panel-Ready
with Glass Door **KUWL204EPA**

Capacity	
Bottle Capacity	46
General Features & Properties	
Auto Light Interior LED Lighting	
Touch Controls	
SatinGlide® Wood-Front Racks	
Built-In or Freestanding Installation	
Over-Temp Alarm	
Door Alarm	
Electrical Details	
Amps	15 or 20
Volts	15

Technical Details	
Refrigerator Type	Undercounter
Number of Wine Racks	6
Rack Fronts	Wood
Lighting Type	LED
Control Location	Interior Up Front
Installation Option	Freestanding or Built-In
Dimensions	
Product Dimensions (H x W x D)	34-1/4" x 23-3/4" x 26-3/4"
Depth with Door Open 90°	47-3/4"
Cutout Dimensions (H x W)	34-1/4" x 24"
Reference Material	

[Dimension Guide](#)

[Use & Care Guide](#)

[Warranty](#)

Key Features & Benefits

Two Temperature-Controlled Zones


Allows for two temperature zones to chill both whites and reds at their optimal temperatures to help preserve the flavor and integrity of individual wines.

46 Wine Bottle Capacity

Provides large capacity to easily chill and display a full selection of wines.

UV-Protected Thermal Glass Door

Filters UV rays to help protect wine and other beverages from premature aging.



(LEFT swing)

NOTE: Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

®/™ © 2020. All rights reserved. Printed in the U.S.A. D200052XXC. KUWL204ESPECSHEETV01.

FOR THE WAY IT'S MADE.®

Wine Cellar

PV 132 *see attached*
Feb. 5, 2021


PRODUCT MODEL NUMBERS

CUWL204E KUWL304E
CUWR204E KUWR304E

Electrical: A 115 volt, 60 Hz., AC only, 5- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your wine cellar be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

NOTE: Before performing any type of installation, cleaning, or removing a light bulb, unplug wine cellar or disconnect power.

OPENING DIMENSIONS




A. 14 3/4" (37.5 cm) utility opening
B. 24" (60.96 cm) minimum opening width

- Height dimensions are shown with the leveling legs extended to the minimum height.

NOTE: When leveling legs are fully extended, add 5/8" (15 mm) to the height dimensions.

- If the floor of the opening is not level with the kitchen floor, shim the opening to make it level with the kitchen floor.

LOCATION REQUIREMENTS




- For the wine cellar to be flush with the front of the base cabinets, remove any baseboards or moldings from the rear of the opening. See "Opening Dimensions" later in this section.
- It is recommended that you do not install the wine cellar near an oven, radiator, or other heat source.
- Do not install in a location where the temperature will fall below 55°F (13°C). For best performance, do not install the wine cellar behind a cabinet door or block the base grille.

SPECIFICATIONS

MODEL	CPM2 (36" AND 42")	CPM2 (48")
BLOWER	DUAL	DUAL
VOLTS	120 VAC	120 VAC
Hz	60	60
AMPS	9.0	9.0
CFM (LOW SPEED)	370	410
CFM (HIGH SPEED)	1000	1080
SONES (LOW SPEED)	1.5	1.5
SONES (HIGH SPEED)	12.0	10.5
DUCTING SIZE	10" ROUND	10" ROUND
2 SHIELDED HALOGEN BULBS	120 V, 50 W MAX., GU10 BASE	120 V, 50 W MAX., GU10 BASE
WARRANTY	5 YEARS	5 YEARS

DIMENSIONS




* DIMENSIONS INCLUDE
RIVET HEADS.

HK0099A

REQUIREMENTS & STANDARDS

- Complies with the CSA C22.2 no. 113 Standard
- Complies with the UL 507 requirements
- HVI certified

AIR FLOW PERFORMANCE



HG0054A



HVI-2100 CERTIFIED RATINGS comply with new testing technologies and procedures prescribed by the Home Ventilating Institute, for off-the-shelf products, as they are available to consumers. Product performance is rated at 0.1 in. (2.54 mm) static pressure, based on tests conducted in a state-of-the-art test laboratory. Sones are a measure of humanly-perceived loudness, based on laboratory measurements.

www.venmar.ca



Venmar Ventilation Inc., 550 Lemire Blvd., Drummondville, Québec, Canada J2C 7W9 - Tel.: 1-800-567-3855 Fax: 1-800-567-1715



PROJECT	REMARKS
LOCATION	
MODEL No.	
QTY.	
SUBMITTED BY	
DATE	

PV-132 ~~See~~ attached
Feb. 5, 2021

- CPM1 AND CPM2 POWER PACK SYSTEMS -




KitchenAid®

44 dBA* Top Control Dishwasher

KDTM504E

PV-132 See attached
Feb. 5, 2021



Panel Ready
KDTM504EPA

Key Features & Benefits

Panel-Ready Design

Allows you to match your dishwasher to your kitchen cabinets for a high-end look, seamless look. A custom front panel and handle (not included) can be affixed to the dishwasher.

Dynamic Wash Arm

Features nine wash arms in one for 3 times better coverage. This unique design directly sprays water everywhere in the dishwasher, including hard to reach places. This means dishes get a powerful clean no matter where they are placed in the rack.

Clean Water Wash System

Continuously removes food particles from the wash water. The result of this advanced technology is clean wash water for excellent performance. Plus, the filter requires no routine maintenance.

Capacity

Total Place Settings 16

General Features & Properties

ProScrub® Option

ProScrub™ Upper (was Trio)

Third Level Rack

Advanced ProDry™ System

ProWash™ Cycle

SatinGlide® Max Rails (Upper and Lower Racks)

2 Rows Fold-Down Tines in Upper Rack

Fold-Down Tines in the Lower Rack

2 Fold-Down Cup Shelves with Integrated Stemware Holders

Electrical Details

Amps 15 or 20

Volts 120

Hz 60

Certifications

ADA Compliant No

ENERGY STAR® Certified Yes

Connected/Smart Appliance No

Technical Details

Dishwasher Type Built-In

Control Location Hidden

Control Type Tap Touch

Number of Wash Cycles 6

Number of Options 7

dBA* 44

Number of Racks 3

Tub Material Stainless Steel

Wash System Filter

Wash System Type Maintenance Free Microfilter

Number of Wash Arms 3

Dimensions

Product Dimensions (H x W x D) 34-1/2" x 23-7/8" x 24-3/4"

Depth with Door Open 90° 49-1/2"

Reference Material


[Dimension Guide](#)

[Install Guide](#)

[Use & Care Guide](#)

[Energy Guide](#)

[Warranty](#)



*Per IEC standards. NOTE: Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

®/™ © 2020. All rights reserved. Printed in the U.S.A. D200052XXA. KDTM504ESPECSHEETV01.

KitchenAid™

FOR THE WAY IT'S MADE.®

Undercounter Dishwasher

PRODUCT MODEL NUMBERS

IFE204E, KDTE104E, KDTE204E, KDTE254E, KDTM354E, ITM384E, KDTM404E, **KDTM504E**, KDTM704E, KDTM804E

Electrical Requirements: 120-volt, 60 Hz, AC-only, 15- or 1-amp. fused electrical supply. Copper wire only. A time delay fuse or circuit breaker and separate circuit is recommended.



Direct wiring dishwasher: Use flexible, armored or nonmetallic, sheathed copper wire with grounding wire that meets the wiring requirements for your home and local codes and ordinances.

Use a UL Listed or CSA Approved conduit connector.

connecting dishwasher with a power supply cord:

Use power supply cord kit (Part number 4317824) marked for use with dishwashers. Follow the kit instructions for installing the power supply cord.

Power supply cord must plug into a grounded three-prong outlet located in the cabinet next to the dishwasher opening. Outlet must meet all local codes and ordinances.




Water Supply Requirements: A hot water line with 20 to 100 psi (138 to 862 kPa) water pressure. Water temperature must be 120°F (49°C) water at dishwasher. Use 3/8" O.D. copper tubing with compression fitting or flexible braided water supply line.

Note: 1/2" minimum plastic tubing is not recommended.

Use a 90° elbow with 3/4" hose connection with rubber washer (part number W10273460). Do not solder within 6" (5.2 cm) from water inlet valve.

Drain Requirements: A new drain hose is supplied with your dishwasher. If this is not long enough, use a new drain hose with a maximum length of 12' (3.7 m) (Part No. 855556) that meets all current AHAM/IAPMO test standards, is resistant to heat and detergent, and fits the 1" (2.5 cm) drain connector of the dishwasher.

Make sure to connect the drain hose to waste tee or disposer inlet above drain trap in house plumbing and 20" (50.8 cm) minimum above the floor. It is recommended



that the drain hose either be looped up and securely fastened to the underside of the counter, or be connected to an air gap.


Make sure to use an air gap if the drain hose is connected to house plumbing lower than 20" (50.8 cm) above subfloor or

or.

Use 1/2" (1.3 cm) minimum I.D. drain line fittings.

If required, the air gap should be installed in accordance with the air gap installation instructions. When connecting the air gap a rubber hose (not provided) will be needed to connect to the waste tee or disposer inlet.

PRODUCT DIMENSIONS



A. Insulation may be compressed (not used on all models).

B. For panel-ready models, dishwasher depth is 24" (60 cm) not including 3/4" (1.9 cm) custom door panel.

C. Door handles may protrude forward of the face of the dishwasher; vary by model.


panel ready

NOTE: Shaded areas of cabinet walls show where utility connections may be installed.

PV-132 *see attached*
Feb. 5, 2021

*Measure from the lowest point on the underside of the countertop. May be reduced to 33½" (85.1 cm) by removing the rear leveling legs from dishwasher.

**Minimum, measured from narrowest point of opening.



PV-132 *see attached*
Feb. 5, 2021

JENN-AIR® DETAILED PLANNING DIMENSIONS


1 of 6

48" FULLY INTEGRATED SIDE-BY-SIDE REFRIGERATOR


(BASE UNIT REQUIRES SUITE-COORDINATING PANEL KIT OR CUSTOM PANELS AND HANDLES)

JS48NXFXDW – 47 $\frac{7}{8}$ " x 83 $\frac{1}{8}$ " x 24"

PRODUCT DIMENSIONS



FRONT VIEW



TOP VIEW

MODEL #		JS48NXFXDW	
		in	cm
A	Width of freezer door	20 $\frac{1}{8}$	51.2
B	Width of refrigerator door	27 $\frac{1}{8}$	68.9
C	Space between doors	$\frac{1}{8}$	0.3
D	Overall width	47 $\frac{7}{8}$	121.7
E	Height of top grille and bracket	6 $\frac{1}{2}$	16.5
F	Space between doors and top grille	$\frac{3}{8}$	0.8
G	Height of door handles Pro-Style® Stainless	63	160
	Euro-Style Stainless	50	127.1
H	Height to top of door handles Pro-Style® Stainless	67	170.3
	Euro-Style Stainless	66 $\frac{3}{8}$	169.1
I	Height of doors	74 $\frac{1}{4}$	188.6
J	Height of bottom grille	3	7.6
K	Width of recessed refrigerator	47 $\frac{7}{8}$	121.6
L	Width from side of refrigerator to freezer door handle – door fully open 110° Pro-Style® Stainless	8 $\frac{3}{8}$	21.3
	Euro-Style Stainless	8	20.3
M	Width from side of refrigerator to handle – doors open 90° Pro-Style® Stainless	2	5.1
	Euro-Style Stainless	1 $\frac{1}{2}$	3.9
N	Width from side of refrigerator to refrigerator door handle – door fully open 110° Pro-Style® Stainless	9 $\frac{5}{8}$	24.4
	Euro-Style Stainless	9 $\frac{1}{8}$	23.1
O	Depth without door panel kit	24	61.0
P	Depth with doors Pro-Style® Stainless panel kit	24 $\frac{3}{4}$	62.9
	Euro-Style Stainless panel kit	24 $\frac{3}{4}$	62.9
	Custom panel (¾"/1.9 cm)	24 $\frac{3}{4}$	62.9
Q	Depth with handles Pro-Style® Stainless	27 $\frac{3}{8}$	69.5
	Euro-Style Stainless	26 $\frac{7}{8}$	68.3
R	Depth with refrigerator door open 90°	50 $\frac{3}{4}$	128.8

PR-132 *see attached*
Feb. 5, 2021

JENN-AIR® DETAILED PLANNING DIMENSIONS


2 of 6

48" FULLY INTEGRATED SIDE-BY-SIDE REFRIGERATOR

(BASE UNIT REQUIRES SUITE-COORDINATING PANEL KIT OR CUSTOM PANELS AND HANDLES)

JS48NFXDW – 47 $\frac{7}{8}$ " x 83 $\frac{1}{8}$ " x 24"


DIMENSIONS AS INSTALLED



SIDE VIEW

MODEL #		JS48NFXDW	
		in	cm
A*	Height without compressor (min.)	74 $\frac{3}{8}$	188.9
B*	Height of recessed refrigerator (min.)	83 $\frac{1}{8}$	211.1
C	Depth with refrigerator door open 90° (min.)	50 $\frac{3}{4}$	128.8
D	Depth with handles (min.)		
	Pro-Style® Stainless	27 $\frac{3}{8}$	69.5
E	Euro-Style Stainless	26 $\frac{7}{8}$	68.3
	Depth with doors (min.)		
	Pro-Style® Stainless panel kit	24 $\frac{3}{4}$	62.9
F	Euro-Style Stainless panel kit	24 $\frac{3}{4}$	62.9
	Custom panel (3/4"/1.9 cm)	24 $\frac{3}{4}$	62.9
G	Depth without door panel kit (min.)	24	61.0
H	Depth of compressor (min.)	19 $\frac{7}{8}$	50.5
I	Space between top grille and soffit	1	2.5
J	Height of top grille	5 $\frac{1}{2}$	14.0

*Add 1 $\frac{1}{8}$ " (2.9 cm) to the height dimension when leveling legs are fully extended.



SIDE VIEW – PANEL KIT

Product dimension, cutout and installation specifications are provided for planning purposes only. Before installing any product, be sure to verify cutout dimensions and electrical/gas connections as actual product dimensions may vary.



JRC120073A 07/2012

OPTION THREE

JENN-AIR® DETAILED PLANNING DIMENSIONS


5 of 6

48" FULLY INTEGRATED SIDE-BY-SIDE REFRIGERATOR


(BASE UNIT REQUIRES SUITE-COORDINATING PANEL KIT OR CUSTOM PANELS AND HANDLES)

JS48NFXDW – 47 $\frac{7}{8}$ " x 83 $\frac{1}{8}$ " x 24"


INTEGRATED INSTALLATION REQUIREMENTS – ARMOIRE-STYLE PANEL KIT



FRONT VIEW – OPEN TO CEILING



FRONT VIEW – FALSE FRONT



SIDE VIEW

- Attach the grille bracket assembly and grille panel provided in the armoire-style panel kit.
- Requires a minimum of 6" (15.2 cm) of open space above the refrigerator, which must not be blocked in any way, including soffits.

INTEGRATED INSTALLATION –


ARMOIRE-STYLE CUSTOM OVERLAY PANEL DIMENSIONS

The armoire-style door panel kit for Jenn-Air® fully integrated built-in refrigerators enables full-height custom door panels with a hidden top panel for the ultimate in integrated design.

MODEL #		JS48NFXDW	
		in	cm
REVEAL*		$\frac{3}{8}$	1.0
A	Width of freezer door panel	20 $\frac{1}{16}$	51.0
B	Width of refrigerator door panel	27 $\frac{1}{16}$	68.7
C	Height of door panels	81	205.7
REVEAL*		$\frac{1}{8}$	0.3
A	Width of freezer door panel	20 $\frac{5}{16}$	51.6
B	Width of refrigerator door panel	27 $\frac{5}{16}$	69.3
C	Height of door panels	81	205.7

*Gap between door panel and adjacent cabinet.

NOTE: The required thickness for all panels is $\frac{1}{2}$ " (1.9 cm). This installation does not require filler or backer panels.



PV-132 *see attached*
Feb. 5, 2021

JENN-AIR® DETAILED PLANNING DIMENSIONS


6 of 6

48" FULLY INTEGRATED SIDE-BY-SIDE REFRIGERATOR


(BASE UNIT REQUIRES SUITE-COORDINATING PANEL KIT OR CUSTOM PANELS AND HANDLES)

JS48NXFXDW – 47⁷/₈" x 83¹/₈" x 24"

OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



BACK VIEW

MODEL #		JS48NXFXDW	
		in	cm
A*	Width (min.)	48	121.9
B	Width of recommended electrical location	4	10.2
C	Distance from side of cabinet to recommended water connection location	6	15.2
D	Height (min.)	84 ¹ / ₄	214.0
E	Height to recommended electrical location	77	195.6
F	Depth of recommended water connection location (max.)	1	2.5
e	Recommended electrical connection location		
w	Recommended water connection location		

*Minimum width must extend behind the face of the cabinet for at least 2" (5.1 cm).

ELECTRICAL REQUIREMENTS

115 volt, 60 Hz, AC only, 15- or 20-amp fused, grounded circuit is required. A dedicated circuit is recommended. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

WATER PRESSURE REQUIREMENTS

A cold water supply with water pressure between 30 and 120 psi (207 and 827 kPa) is required to operate the ice maker. Call a licensed, qualified plumber with any questions about the water pressure.

Reverse Osmosis Water Supply

IMPORTANT: The pressure of the water coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 30 and 120 psi (207 and 827 kPa).


If a reverse osmosis water filtration system is connected to the cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).

LOCATION REQUIREMENTS

Floor must be able to support refrigerator (more than 600 lb [272 kg]), door panels and contents of the refrigerator and must be at the same level as flooring in the room.



The water shutoff should be located in the base cabinet on either side of the refrigerator or some other easily accessible area. If the water shutoff valve is not in the cabinets, the plumbing for the water line can come through the floor. See "Water Supply Requirements" for more information.



Model	Width A (as shown above)	Dimension B (as shown above)
42	42" (106.7 cm)	7½" (19.1 cm)
48	48" (121.9 cm)	13½" (34.3 cm)

Installation Type	Depth C (as shown above)
Standard Flush (new installation)	25" (63.5 cm) minimum
Retrofit Installations	24" (60.9 cm) minimum

NOTE: On retrofit installations, door panels will not be flush with adjacent cabinets.

Electrical Requirements

⚠ WARNING



Electrical Shock Hazard

Plug into a grounded 3 prong outlet.

Do not remove ground prong.

Do not use an adapter.

Do not use an extension cord.

Failure to follow these instructions can result in death, fire, or electrical shock.

See attached PV-132 Feb 5, 2021

Before you move your refrigerator into its final location, it is important to make sure you have the proper electrical connection.

Recommended Grounding Method

A 115 volt, 60 Hz., AC only, 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

IMPORTANT: If this product is connected to a GFCI (Ground Fault Circuit Interrupter) protected outlet, nuisance tripping of the power supply may occur, resulting in loss of cooling. Food quality and flavor may be affected. If nuisance tripping has occurred, and if the condition of the food appears poor, dispose of it.


NOTE: Before performing any type of installation or cleaning, remove the top grille and turn the master power switch to OFF or disconnect power at the circuit breaker box.

When you are finished, turn ON the master power switch or reconnect power at the circuit breaker box. Then reset the control to the desired setting.

Water Supply Requirements

IMPORTANT:

- All installations must meet local plumbing code requirements.
- There is not enough clearance to achieve a flush installation if a water shutoff valve is located in the wall behind the refrigerator.
- The water shutoff should be located in the base cabinet on either side of the refrigerator or some other easily accessible area. The water supply line, however, must come up through the floor in the gray shaded area shown.



1. A 1/2" (12.7 mm) hole for plumbing should be drilled on the floor at least 6" (15.2 cm) from the right- or left-hand side cabinet and should be no more than 1" (2.54 cm) away from the back wall. See "Connect the Water Supply."

- 1 The water supply connection is made at the front of the refrigerator.
- 1 If additional tubing is needed, use copper tubing and check for leaks. Install the copper tubing only in areas where the household temperatures will remain above freezing.
- 1 Do not use a piercing-type or 3/16" (4.76 mm) saddle valve which reduces water flow and also clogs more easily.

NOTE: Your refrigerator dealer has a kit available with a 1/4" (6.35 mm) saddle-type shutoff valve, a union, and copper tubing. Before purchasing, make sure a saddle-type valve complies with your local plumbing codes.

Water Pressure

A cold water supply with water pressure between 30 and 120 psi (207 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.

Reverse Osmosis Water Supply

IMPORTANT: The pressure of the water supply coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 30 and 120 psi (207 and 827 kPa).

If a reverse osmosis water filtration system is connected to your cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).

If the water pressure to the reverse osmosis system is less than 40 to 60 psi (276 to 414 kPa):

- 1 Check to see whether the sediment filter in the reverse osmosis system is blocked. Replace the filter if necessary.
- 1 Allow the storage tank on the reverse osmosis system to refill after heavy usage.
- 1 If your refrigerator has a water filter, it may further reduce the water pressure when used in conjunction with a reverse osmosis system. Remove the water filter cartridge.

If you have questions about your water pressure, call a licensed, qualified plumber.

Product Dimensions

IMPORTANT:

- 1 The depth from the front face of the doors to the back of the refrigerator cabinet is 24" (60.96 cm) without panels.
- 1 The power cord is 84" (213 cm) long.
- 1 The water supply connection is made at the bottom front of the refrigerator.

PR-132 see attached
Feb. 5, 2021


Top View



Model	A
42	41 ³ / ₄ " (106 cm)
48	47 ³ / ₄ " (121.3 cm)

Front View

- Width dimensions were measured from hinge to hinge.
- When leveling legs are fully extended to 1¹/₄" (3.2 cm) below rollers, add 1¹/₄" (3.2 cm) to the height dimensions.



Model	Width A (hinge edge to hinge edge)
42	41 ³ / ₄ " (106 cm)
48	47 ³ / ₄ " (121.3 cm)