

APPLIANCES

Invoice	Qty.	Description
2699 72,351 09Apr21 NoCat	1	APPLIANCE SPECIFICATIONS ATTACHED - SIGNED COPY

BASEMENT WINDOWS

Invoice	Qty.	Description
2657 72,351 25Mar21	2	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME

DRYWALL

Invoice	Qty.	Description
2657 72,351 25Mar21 **	2	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME

ELECTRICAL

Invoice	Qty.	Description
2657 72,351 25Mar21 **	2	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME
2657 72,261 08Apr21	1	4.0 TON AC - WITH LOW VOLTAGE WIRING & WALL BRACKETS
2670 72,280 08Apr21	1	KITCHEN: INSTALL VAC PAN UNDER KITCHEN SINK
2670 72,273 08Apr21	1	KITCHEN: 110V WALL RECEPTACLE ON SEPARATE CIRCUIT - GAS FIRED APPLIANCE - FOR AUX. EQUIPMENT - NOT A STOVE PLUG - SEE PLAN
2670 72,307 08Apr21	1	KITCHEN: RELOCATE STANDARD CEILING MOUNT FIXTURE - APPROX. CENTERED ABOVE ISLAND - SEE PLAN
2670 72,280 08Apr21	1	KITCHEN: ADDITIONAL REINFORCED CEILING OUTLET - APPROX. CENTERED ABOVE KITCHEN ISLAND - SAME SWITCH AS STANDARD
2670 72,303 08Apr21	1	KITCHEN: UNDER CABINET FLUORESCENT LIGHT FIXTURES - BUNDLE INCLUDING LIGHT VALANCE
2670 72,289 08Apr21	6	GREAT ROOM: 4" E/S LED INTERIOR POT LIGHT - GROUND FLOOR - INCLUDES ONE SWITCH INCLUDED IN APS

ELECTRICAL

Invoice	Qty.	Description
2670 72,281 08Apr21	1	GREAT ROOM: INTERIOR WALL OUTLET; ADDITIONAL .110V WALL INTERIOR RECEPTACLE ON EXISTING CIRCUIT FOR WALL MOUNTED TV - APPROX. 64" A.F.F.
2670 72,307 08Apr21	1	UPPER HALL: RELOCATE STANDARD CEILING MOUNT FIXTURE TO APPROX. CENTRE AT OTB - SEE PLAN

FORM - FORMING

Invoice	Qty.	Description
2657 72,351 25Mar21 **	2	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME

FORMING

Invoice	Qty.	Description
2657 72,202 25Mar21	1	PINE VALLEY MODEL 40.06 LILAC ELEV A - 9 FOOT BASEMENT CEILING HEIGHT IN LIEU OF STANDARD 8 FOOT CEILING. INCLUDED IN APS

HVAC

Invoice	Qty.	Description
2657 72,241 25Mar21	1	4.0 TON AC - WITH LOW VOLTAGE WIRING & WALL BRACKETS INCLUDED IN APS
2670 72,224 08Apr21	1	KITCHEN: GAS LINE ROUGH-IN - MAIN FLOOR FOR APPLIANCE - SEE PLAN
2670 08Apr21 NoCat	1	KITCHEN: INSTALL VAC PAN UNDER KITCHEN SINK

INTERIOR TRIM/MOULDINGS

Invoice	Qty.	Description
2657 72,351 25Mar21 **	2	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME

KITCHEN AND BATH CABINETRY

Invoice	Qty.	Description
2670 08Apr21 NoCat	1	FYI - KITCHEN: GAS LINE ROUGH-IN - MAIN FLOOR FOR APPLIANCE - SEE PLAN
2670 08Apr21 NoCat	1	KITCHEN: UNDER CABINET FLUORESCENT LIGHT FIXTURES - BUNDLE INCLUDING LIGHT VALANCE
2670 08Apr21 NoCat	1	KITCHEN: INSTALL VAC PAN UNDER KITCHEN SINK
2670 08Apr21 NoCat	1	TOE KICK CUT OUT REQUIRED

NETWORK AND WIRING

Invoice	Qty.	Description
2670 72.259 08Apr21	1	GREAT ROOM: CONDUIT PIPE - FOR WALL MOUNT TV - APPROX 64" A.F.F., ABOVE FIREPLACE, THRU BASEMENT, TERMINATE AT CABLE LOCATION

PAINTING

Invoice	Qty.	Description
2657 72.351 25Mar21 **	2	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME

PANL - FRAMING

Invoice	Qty.	Description
2657 72.351 25Mar21 **	2	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME

PLUMBING

Invoice	Qty.	Description
2670 72.332 08Apr21	1	KITCHEN: ROUGH-IN 1/4" COLD WATER LINE TO FRIDGE

ROUGH CARPENTRY

Invoice	Qty.	Description
2657 72.351 25Mar21 **	2	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME


WINDOWS - BASEMENT

Invoice	Qty.	Description
2657 72.351 25Mar21 **	2	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME

SCHEDULE 'F'

PV-26 attach
March 23, 2021
PV-26 attach
April 6, 2021

The
Lilac
40' SERIES
→ Elevation A • 3,425 sq.ft.
Elevation B • 3,385 sq.ft.




VENDOR
PURCHASER
PURCHASER

GOLDPARK
WORTH MORE

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 4006

SCHEDULE 'F'
PV-26 attach
March 23, 2021
PV-26 attached
April 6, 2021

The
Lilac
40' SERIES
→ Elevation A • 3,425 sq.ft.
Elevation B • 3,385 sq.ft.



SECOND FLOOR | ELEV. A

VENDOR _____
PURCHASER _____
PURCHASER _____

GOLDPARK
WORTH MORE™

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 4006

PINE VALLEY
FOREVERGREEN

9 FT
BASEMENT


SCHEDULE 'F'

PV-26 attach
March 23, 2021
PV-26 attach
April 6, 2021

The
Lilac
40' SERIES
→ Elevation A • 3,425 sq.ft.
Elevation B • 3,385 sq.ft.

24" x 30"

24" x 30"



VENDOR _____
PURCHASER _____
PURCHASER _____


GOLDPARK
WORTH MORE™

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 4006

PINE VALLEY
RESORTS

SCHEDULE P
PV-26 
March 13, 2011
PV-26 42 48
April 6, 2011

The
Lilac
40' SERIES
Elevation A - 3,425 sq.ft.
Elevation B - 3,585 sq.ft.



GROUND FLOOR | ELEV. A

VENDOR
PURCHASER
PURCHASER

Plans, figures, illustrations, specs, notes and notes are subject to change without notice. Areas and dimensions are approximate and actual field conditions may vary from the stated area. Layout may be revised by the unit purchaser. E. & O.E. 2006.


GOLDPARK
WORTH MORE



PINE VALLEY

SCHEDULE F
PV-26 afford
March 23, 2021
PV-26 02 147
April 6, 2021

The
Lilac
40' SERIES
→ Elevation A • 3,425 sq.ft.
Elevation B • 3,385 sq.ft.



SECOND FLOOR | ELEV. A

VENDOR	
PURCHASER	
PURCHASER	

GOLDPARK
WORTH, MO

Prices, figures, illustrations, sites, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area depending on the unit purchased. E. 8/25/2005

PINE VALLEY

PAVEMENT

9 FT
BASEMENT

SCHEDULE F

PV-26 OK'd

March 23, 2011


PV-26 OK'd

April 6, 2011

The
Lilac
40' SERIES
→ Elevation A = 3,425 sq.ft.
Elevation B = 3,385 sq.ft.

24' x 30'

24' x 30'



VENDOR
PURCHASER
PURCHASER

GOLDPARK

WORTHMORE

Notes: Figures, dimensions, areas, finishes and fixtures subject to change without notice. Area and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be revised at the time of purchase. E & O.E. 4/06.

PV-26
March 23, 2021
attach

KitchenAid®

FOR THE WAY IT'S MADE.®

PRODUCT MODEL NUMBERS

KRMF606E KRMF706E

Electrical: A 115 volt, 60 Hz, AC only, 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

Water: A cold water supply with water pressure between 35 and 120 psi (241 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.

NOTE: If the water pressure is less than what is required, the flow of water from the water dispenser could decrease or ice cubes could be hollow or irregular shaped.


Reverse Osmosis Water Supply:

IMPORTANT: The pressure of the water supply coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 35 and 120 psi (241 and 827 KPa).

If a reverse osmosis water filtration system is connected to your cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 KPa).

Bottom Mount Refrigerator

PRODUCT DIMENSIONS




Model Size	Height - Overall "A"	Height - Top of Cabinet "B"	Depth - With Handles "C"	Depth - Without Handles "D"	Depth - Cabinet Only "E"	Width - Cabinet "F"
25.8	70 1/8" (178.1 cm)	68 3/8" (173.7 cm)	36 1/4" (92.1 cm)	34 1/2" (87.7 cm)	29" (73.7 cm)	36" (91.4 cm)

LOCATION REQUIREMENTS

IMPORTANT: This refrigerator is designed for indoor, household use only.

To ensure proper ventilation for your refrigerator, allow for a 1/2" (1.25 cm) of space on each side and at the top. Allow for a 1" (2.54 cm) space behind the refrigerator. If your refrigerator has an ice maker, allow extra space at the back for the water line connections. When installing your refrigerator next to a fixed wall, leave a 3 3/4" (9.5 cm) minimum space between the refrigerator and wall to allow the door to swing open.

NOTE: This refrigerator is intended for use in a location where the temperature ranges from a minimum of 55°F (13°C) to a maximum of 110°F (43°C). The preferred room temperature range for optimum performance, which reduces electricity usage and provides superior cooling, is between 60°F (15°C) and 90°F (32°C). It is recommended that you do not install the refrigerator near a heat source, such as an oven or radiator.




NV-26
March 23, 2021
attest

24" Dishwasher

DETAILED PLANNING DIMENSIONS GUIDE

Applies to all model numbers starting with:
KDFE104K, KDFE204K, KDTE204K, KDTE204LPA, KDFM404K,
KDTM404K, KDPM604K, KDTM604K, KDPM704K, KDTM704K,
KDTM704LPA, KDPM804K, KDTM804K

PRODUCT DIMENSIONS



*Dishwasher can be raised 17/8" (3.7 cm) with feet fully extended.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

PV-26 attached


March 23, 2021

KitchenAid®

24" Dishwasher

DETAILED PLANNING DIMENSIONS GUIDE

PRODUCT DIMENSIONS (CONTD.)



DESCRIPTION		DIMENSIONS
A	Width of door	23½" (59.7 cm)
B*	Height to top of handle	30⅜" (78.3 cm)
C	Height of adjustable toe kick	3⅝" (8.4 cm) - min. 4⅛" (11.8 cm) - max.
D	Width of recessed dishwasher	22⅝" (57.4 cm)
E†	Depth without door	22⅝" (57.5 cm)
F††	Depth with Towel Bar Handle	26⅞" (68.3 cm)
G†††	Depth with Pocket Handle	24½" (62.6 cm)
H*	Depth of Panel-Ready Models	24" (61.0 cm)
I*	Height to bottom of door (min.)	3⅝" (8.4 cm)
J*	Height to top of door (min.)	33⅞" (84.9 cm)
K†	Height of recessed dishwasher (min.)	33⅝" (85.4 cm)
L*	Depth with door fully open (min.)	50⅜" (127.4 cm)
M†	Depth with toe kick (min.)	20⅜" (52.9 cm)

†Insulation blanket thickness adds up to 11/16" (1.8 cm) but can crush up to 1/8" (0.3 cm).

*Dishwasher can be raised 1⅞" (3.7 cm) with feet fully extended.

††For panel-ready models, dishwasher depth is 24" (61.0 cm), not including the 3/4" (1.9 cm) custom door panel.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.


PV-26 check
March 23, 2021

KitchenAid® 24" Dishwasher

DETAILED PLANNING DIMENSIONS GUIDE

OPENING/CLEARANCE DIMENSIONS

IMPORTANT: Check that all surfaces have no protrusions that would prohibit dishwasher installation.



A. Measured from the lowest point on the underside of the countertop. May be reduced to 33 1/2" (85.1 cm) by removing the wheels and perforated area of insulation (blanket) on dishwasher.

B. Minimum, measured from narrowest point of opening.

NOTE: Corner locations require a 2" (5.1 cm) minimum clearance between the side of the dishwasher door and the wall or cabinet.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

RV-26 attack

March 23, 2021

KitchenAid®

FOR THE WAY IT'S MADE.®

30" (77.2 cm) and 36" (91.4 cm) Wall-Mount Canopy Range Hood

PRODUCT MODEL NUMBERS

KVMB600D KVMB606D

Electrical: A 120 volt, 60 Hz, AC only, 15-amp, fused electrical circuit is required.

VENTING METHODS

This canopy range hood is factory set for venting through the roof or through the wall.

A 6" (15.2 cm) round vent system is needed for installation (not included). The hood exhaust opening is 6" (15.2 cm) round.

NOTE: Flexible vent is not recommended. Flexible vent creates back pressure and air turbulence that greatly reduce performance.

Vent system can terminate either through the roof or wall. To vent through a wall, a 90° elbow is needed.


Rear Discharge

A 90° elbow may be installed immediately above the hood.

For Non-Vented (Recirculating) Installations

If it is not possible to vent cooking fumes and vapors to the outside, the hood can be used in the non-vented (recirculating) version, using a Recirculation Kit (which includes charcoal filters and a deflector). To order, see the "Assistance or Service" section.

Roof Venting Wall Venting Non-Vented (Recirculating)



A. Roof cap
B. 6" (15.2 cm) round vent

A. Wall cap
B. 6" (15.2 cm) round vent

A. Diverter
B. 6" (15.2 cm) round vent

Calculating Vent System Length

To calculate the length of the system you need, add the equivalent feet (meters) for each vent piece used in the system.


Vent System

Vent Piece	6" (15.2 cm) Round
45° elbow	2.5 ft (0.8 m)
90° elbow	5.0 ft (1.5 m)

Maximum equivalent vent length is 35 ft (10.7 m).




Example Vent System



The following example falls within the maximum recommended vent length of 35 ft (10.7 m).

1 - 90° elbow	= 5.0 ft (1.5 m)
1 - wall cap	= 0.0 ft (0.0 m)
8 ft (2.4 m) straight	= 8.0 ft (2.4 m)
Length of system	= 13.0 ft (3.9 m)

PRODUCT DIMENSIONS




* For non-vented (recirculating) installations

** For vented installations

PV-26 attached
March 23, 2021

CABINET DIMENSIONS



*For non-vented (recirculating) installations

IMPORTANT:

- Minimum distance "X": 24" (61.0 cm) from electric cooking surface.
- Minimum distance "X": 27" (68.6 cm) from gas cooking surfaces.
- Suggested maximum distance "X": 36" (91.4 cm)

The chimneys can be adjusted for different ceiling heights. See the following chart.

Vented Installations	
Min. ceiling height	Max. ceiling height
Electric cooking 7' 1" (2.16 m)	9' 2" (2.79 m)
Gas cooking 7' 4" (2.23 m)	9' 2" (2.79 m)
Non-vented (recirculating) Installations	
Min. ceiling height	Max. ceiling height
Electric cooking 7' 1" (2.16 m)	9' 6" (2.9 m)
Gas cooking 7' 4" (2.23 m)	9' 6" (2.9 m)

*NOTE: The range hood chimneys are adjustable and designed to meet varying ceiling or soffit heights depending on the distance "X" between the bottom of the range hood and the cooking surface. For higher ceilings, a Chimney Extension Kit is available from your dealer or an authorized parts distributor. The chimney extension replaces the chimney shipped with the range hood. To order, see the "Assistance or Service" section.

PV-26
March 23, 2021

attach



KitchenAid® 27" (68.6 cm) and 30" (76.2 cm) Electric Built-In Microwave/Oven Combination

PRODUCT MODEL NUMBERS

KEMS309E KOCE500E KOCE507E

ELECTRICAL CONNECTION


If codes permit and a separate ground wire is used, it is recommended that a qualified electrical installer determine that the ground path and the wire gauge are in accordance with local codes. Check with a qualified electrical installer if you are not sure the oven is properly grounded.

This oven must be connected to a grounded metal, permanent wiring system.

Be sure that the electrical connection and wire size are adequate and in conformance with the National Electrical Code, ANSI/NFPA 70-latest edition or CSA Standards C22.1-94, Canadian Electrical Code, Part 1 and C22.2 No. 0-M91-latest edition, and all local codes and ordinances.

To properly install your oven, you must determine the type of electrical connection you will be using and follow the instructions provided for it here.

• Oven must be connected to the proper electrical voltage and frequency as specified on the model/serial/rating plate. See the following illustration.



A. Model/serial/rating plate

- Models rated from 7.3 to 9.6 kW at 240 volts (5.4 to 7.4 kW at 208 volts) require a separate 40-amp circuit. Models rated at 4.8 kW and below at 240 volts (3.6 kW and below at 208 volts) require a separate 30-amp circuit.
- A circuit breaker is recommended.
- Connect directly to the fused disconnect (or circuit breaker box) through flexible, armored or nonmetallic sheathed, copper cable (with grounding wire). See "Make Electrical Connection" section.
- Flexible conduit from the oven should be connected directly to the junction box.
- Do not cut the conduit. The length of conduit provided is for serviceability of the oven.
- A UL listed or CSA approved conduit connector must be provided.
- If the house has aluminum wiring, follow the procedure below:
 1. Connect a section of solid copper wire to the pigtail leads.
 2. Connect the aluminum wiring to the added section of copper wire using special connectors and/or tools designed and UL listed for joining copper to aluminum.

Follow the electrical connector manufacturer's recommended procedure. Aluminum/copper connection must conform with local codes and industry accepted wiring practices.

For power requirements, refer to the following table.

Model	Voltage	Amperage (L1)*	Amperage (L2)*	Rating (W)
KOCE507E/KOCE500E	120/240	32	30	8000
KOCE507E/KOCE500E	120/208	30	28	6600


*Amperage values noted above are for information purposes only; the units are rated in watts.

Because Whirlpool Corporation includes a continues commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see installation instructions packed with product. Specifications subject to change without notice.

Ref. W107256835
2/10/15

PRODUCT DIMENSIONS



27" (68.6 cm) models

A. 42³/₁₆" (108.0 cm) overall height

B. 25⁷/₁₆" (64.6 cm) recessed width

C. 41" (104.1 cm) recessed height

D. 23¹/₂" (59.1 cm) max. recessed depth

E. 27" (68.6 cm) overall width

F. 48" (121.9 cm) flexible conduit length measured from the conduit clamp located at the rear of the oven. Do not remove the conduit clamp.

30" (76.2 cm) models

A. 42³/₁₆" (108.0 cm) overall height

B. 28¹/₁₆" (72.3 cm) recessed width


C. 41" (104.1 cm) recessed height

D. 23¹/₂" (59.1 cm) max. recessed depth

E. 30" (76.2 cm) overall width

F. 48" (121.9 cm) flexible conduit length measured from the conduit clamp located at the rear of the oven. Do not remove the conduit clamp.

Cabinet Dimensions



27" (68.6 cm) models

A. 27" (68.6 cm) min. cabinet width

B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door

C. 19¹/₄" (48.9 cm) bottom of cutout to floor is recommended.

4"-19¹/₄" (10.2-48.9 cm) bottom of cutout to floor is acceptable.

D. 25¹/₂" (64.8 cm) cutout width

E. 1¹/₂" (3.8 cm) min. bottom of cutout to top of cabinet door

F. 41³/₁₆" (105 cm)* recommended cutout height

G. 24" (60.7 cm) cutout depth

30" (76.2 cm) models

A. 30" (76.2 cm) min. cabinet width

B. 1" (2.5 cm) top of cutout to bottom of cutout to floor is recommended.

C. 19¹/₄" (48.9 cm) bottom of cutout to floor is acceptable.

4"-19¹/₄" (10.2-48.9 cm) bottom of cutout to floor is acceptable.

D. 28¹/₂" (72.4 cm) cutout width

E. 1¹/₂" (3.8 cm) min. bottom of cutout to top of cabinet door

F. 41³/₁₆" (105 cm)* recommended cutout

G. 24" (60.7 cm) cutout depth


* NOTE: The cabinet height can be between 41" (104.1 cm) and 41¹/₂" (105.6 cm) for microwave/oven combination.

PV-26 ~~after~~ ~~ok~~
March 23, 2021

DIMENSIONS

COMMERCIAL-STYLE RANGETOPS
PRODUCT DIMENSIONS

MODEL #	30" (76.2 cm) Rangetop KCGG500J		36" (91.4 cm) Rangetop KCGG506J		48" (121.9 cm) Rangetop KCGG558J	
Unit of Measurement	in	cm	in	cm	in	cm
Overall Width (A)	29 3/4	75.6	35 3/4	90.8	47 3/4	121.3
Grate Depth (B)	22	55.9	22	55.9	22	55.9
Depth without Control Panel (C)	23 3/4	59.1	23 3/4	59.1	23 3/4	59.1
Depth with Control Panel Overhang (D)	27 7/8	70.8	27 7/8	70.8	27 7/8	70.8
Depth with Knobs (E)	29 3/8	74.6	29 3/8	74.6	29 3/8	74.6



TOP VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

PV-26 attached
March 23, 2021


DIMENSIONS

COMMERCIAL-STYLE RANGETOPS
PRODUCT DIMENSIONS




MODEL #	30" (76.2 cm) Rangetop KCGC500J		36" (91.4 cm) Rangetop KCGC506J		48" (121.9 cm) Rangetop KCGC568J	
Unit of Measurement	in	cm	in	cm	in	cm
Grate Width (F)*	27 ⁷ / ₁₆	69.7	33	83.8	44 ³ / ₈	112.7
Gas Inlet to Surface (G)	10 ³ / ₄	27.3	10 ³ / ₄	27.3	10 ³ / ₄	27.3
Center to Gas Inlet (H)	11	27.9	14 ¹ / ₈	35.9	19 ⁵ / ₈	49.8
Recessed Rangetop Width (I)	29 ¹ / ₈	74	35 ¹ / ₈	89.2	47 ¹ / ₈	119.7

*Includes width of grates and gridde.



FRONT VIEW



BACK VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before
selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.


Pr-26 attach
March 23, 2021

DIMENSIONS

COMMERCIAL-STYLE RANGETOPS
PRODUCT DIMENSIONS

MODEL #	30" (76.2 cm) Rangetop KCGC500J		36" (91.4 cm) Rangetop KCGC506J		48" (121.9 cm) Rangetop KCGC558J	
Unit of Measurement	in	cm	in	cm	in	cm
Height with Grates (J)	9	22.9	9	22.9	9	22.9
Control Panel Height (K)	7 ³ / ₁₆	19.8	7 ⁹ / ₁₆	19.8	7 ³ / ₁₆	19.8
Recessed Rangetop Height (L)	7	17.8	7	17.8	7	17.8
Cooking Surface Height (M)	7 ⁷ / ₁₆	18.9	7 ⁷ / ₁₆	18.9	7 ⁷ / ₁₆	18.9
Recessed Rangetop Depth (N)	21 ⁷ / ₈	55.6	21 ⁷ / ₈	55.6	21 ⁷ / ₈	55.6
Depth with Control Panel (O)	25 ¹ / ₂	64.8	25 ¹ / ₂	64.8	25 ¹ / ₂	64.8

IMPORTANT: Supplied regulator does not come preattached and is pictured for reference purposes only.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-26 *after ok*
March 23, 2021


DIMENSIONS

COMMERCIAL-STYLE RANGETOPS
OPENING/CLEARANCE DIMENSIONS



MODEL #	30" (76.2 cm) Rangetop KCGGC500J		36" (91.4 cm) Rangetop KCGGC506J		48" (121.9 cm) Rangetop KCGGC558J	
Unit of Measurement	in	cm	in	cm	in	cm
Combustible Area above Cooking Surface Width (min.) (A)	30	76.2	36	91.4	48	121.9
Bottom of Cabinet Height above Cooking Surface (min.) (B)*	42	106.7	58	147.3	58	147.3
Bottom of Cabinet Height above Countertop (min.) (C)	18	45.7	18	45.7	18	45.7
Distance to Fixed Wall or Combustible Material (D)	12	30.5	12	30.5	12	30.5

*If installing a hood above the rangetop, follow the hood instructions for dimensional clearances above the cooking surface.



FRONT VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

9V-26 offset

March 23, 2021

DIMENSIONS


5 of 24

COMMERCIAL-STYLE RANGETOPS OPENING/CLEARANCE DIMENSIONS

MODEL #	30" (76.2 cm) Rangetop KCGG500J		36" (91.4 cm) Rangetop KCGG506J		48" (121.9 cm) Rangetop KCGG558J	
Unit of Measurement	in	cm	in	cm	in	cm
Recommended Upper Cabinet Depth (E)	13	33	13	33	13	33
Cutout to Wall Depth (if backwall is constructed of non-combustible material) (F)*	1 3/4	4.4	1 3/4	4.4	1 3/4	4.4
Cutout to Wall Depth (if backwall is constructed of combustible material) (F)*	7 3/4	19.7	7 3/4	19.7	7 3/4	19.7
Cabinet to Countertop Height (G)**	7 1/4	18.4	7 1/4	18.4	7 1/4	18.4
Cabinet Depth (H)	24	61	24	61	24	61

*If the back wall is constructed of a combustible material and a backsplash is not installed, a 7 3/4" (19.7 cm) minimum clearance is required from the cutout or 6" (15.2 cm) minimum clearance from the back edge of the rangetop.

**The bottom of the cutout supports the product. Unlike many cooktops, these models do not hang from the side flanges, but rather sit on the floor of the cutout.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-26 extra
March 23, 2021

DIMENSIONS


6 of 24

COMMERCIAL-STYLE RANGETOPS OPENING/CLEARANCE DIMENSIONS



MODEL #	30" (76.2 cm) Rangetop KCGC500J		36" (91.4 cm) Rangetop KCGC506J		48" (121.9 cm) Rangetop KCGC558J	
Unit of Measurement	in	cm	in	cm	in	cm
Countertop and Cabinet Cutout Width (I)	29 1/4	74.3	35 1/4	89.5	47 1/4	120.0
Countertop and Cutout Depth (J)	22 1/4	56.5	22 1/4	56.5	22 1/4	56.5
Notch Width (K)	1/4	0.6	1/4	0.6	1/4	0.6
Cutout Width (L)	29 3/4	75.5	35 3/4	90.8	47 3/4	121.2

NOTE: Due to manufacturing factory tolerances, these are nominal dimensions. You may need to readjust to meet your clearance.



IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

RV-210

LP (HX)

March 23, 2021

KitchenAid®

FOR THE WAY IT'S MADE®

PRODUCT MODEL NUMBERS

KSMF000E KSMF700E

Electrical: A 115 volt, 60 Hz, AC only 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord. Water: A cold water supply with water pressure between 35 and 120 psi (241 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.

NOTE: If the water pressure is less than what is required, the flow of water from the water dispenser could decrease or be cut off, could be noisy or irregular stopped.


Reverse Osmosis Water Supply:

IMPORTANT: The pressure of the water supply coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 35 and 120 psi (241 and 827 kPa).

If a reverse osmosis water filtration system is connected to your cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).


Bottom Mount Refrigerator

PRODUCT DIMENSIONS



Model Size	Height - Overall in. (76 1/2)	Height - Total Cabinet in. (68 1/2)	Depth - With Handle in. (24 1/2)	Depth - Without Handle (only) in. (22)	Width - Cabinet in. (36 1/4)
238	76 1/2 (192.7 cm)	68 1/2 (173.2 cm)	24 1/2 (62.1 cm)	22 (55.9 cm)	36 1/4 (91.4 cm)

LOCATION REQUIREMENTS



IMPORTANT: This refrigerator is designed for indoor, household use only. To ensure proper ventilation for your refrigerator allow for a 1/4" (1.25 cm) or space on each side and at the top. Allow for a 1" (2.54 cm) space behind the refrigerator. If your refrigerator has an ice maker, allow extra space at the back for the water line connections. When installing your refrigerator next to a fixed wall, leave a 3/4" (1.9 cm) minimum space between the refrigerator and wall to allow the door to swing open.

NOTE: This refrigerator is intended for use in a location where the temperature ranges from a minimum of 55°F (13°C) to a maximum of 110°F (43°C). The preferred room temperature range for optimum performance, which reduces electricity usage and provides superior cooling, is between 60°F (16°C) and 80°F (27°C). It is recommended that you do not install the refrigerator near a heat source, such as an oven or radiator.


N=26
March 23, 2021
(1A)
(1A)
(1A)

24" Dishwasher

DETAILED PLANNING DIMENSIONS GUIDE

Applies to all model numbers starting with:
KDFE104K, KDFE204K, KDFE204LPA, KDFM404K,
KDTM404K, KDFM604K, KDTM604K, KDFM704K, KDTM704K,
KDFM704LPA, KDFM804K, KDTM804K

PRODUCT DIMENSIONS



*Dishwasher can be raised 1 1/2" (3.7 cm) with feet fully extended.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.


Dimensions are for planning purposes only. For complete details, see installation instructions packed with product. Specifications subject to change without notice.

PV-2L (RB) (HX)
March 23, 2021

KitchenAid® 24" Dishwasher

DETAILED PLANNING DIMENSIONS GUIDE

PRODUCT DIMENSIONS (CONT'D.)



Width of door	23 1/2" (59.7 cm)
Height to top of handle	30 3/4" (78.3 cm)
Height of adjustable toe kick	3 3/4" (8.4 cm) - min. 4 1/2" (11.8 cm) - max.
Width of recessed dishwasher*	22 3/4" (57.4 cm)
Depth without door	22 5/8" (57.6 cm)
Depth with Tower Bar Handle	23 7/8" (60.3 cm)
Depth with Pocket Handle	24 1/2" (62.6 cm)
Depth of PanelReady Models	24" (61.0 cm)
Height to bottom of door (min.)	3 3/4" (8.4 cm)
Height to top of door (min.)	33 3/4" (84.6 cm)
Height of recessed dishwasher (min.)	33 5/8" (85.4 cm)
Depth with door fully open (min.)	50 3/4" (127.4 cm)
Depth with toe kick (min.)	20 3/4" (52.9 cm)

*Including 1/8" (3.2 mm) thickness adds up to 11 1/8" (28.6 cm) but can crush up to 1/8" (3.2 mm).

*Dishwasher can be raised 1 3/4" (3.8 cm) with feet fully extended.

**For panel-ready models, dishwasher depth is 24" (61.0 cm), not including the 3/4" (1.9 cm) custom door panel.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.


Dimensions are for planning purposes only. For complete details, see installation instructions packed with product. Specifications subject to change without notice.

PV-26 (AP) (HX)
March 25, 2002

KitchenAid® 24" Dishwasher DETAILED PLANNING DIMENSIONS GUIDE

OPENING/CLEARANCE DIMENSIONS

IMPORTANT: Check that all surfaces have no protrusions that would prohibit dishwasher installation.



- A. Measured from the lowest point on the underside of the countertop. May be reduced to 33 1/2" (85.1 cm) by removing the wheels and perforated area of insulation (depicted) on dishwasher.
 - B. Minimum, measured from narrowest point of opening.
- NOTE: Corner locations require a 2" (5.1 cm) minimum clearance between the side of the dishwasher door and the wall or cabinet.

Because KitchenAid Corporation is not a certified manufacturer, we cannot warrant the performance of our products. We warrant the right to change materials and specifications without notice.

Dimensions and for clearing purposes only. For complete details, see installation instructions. Always use proper specifications and change without notice.

PN-26 (M) (M)

March 23, 2021

KitchenAid®

FOR THE WALL MOUNTED 30" (76.2 cm) and 36" (91.4 cm) Wall-Mount Canopy Range Hood

PRODUCT MODEL NUMBERS

KVM6600D KVM6608D

Electrical: A 120 volt, 60 Hz, 15-amp, fused electrical circuit is required.

VENTING METHODS

The canopy range hood is factory set for venting through the roof or through the wall.

A 6" (15.2 cm) round vent system is needed for installation (not included). The hood exhaust opening is 6" (15.2 cm) round.

NOTE: Flexible vent is not recommended. Flexible vent creates back pressure and air turbulence that greatly reduces performance. Vent system can terminate either through the roof or wall. To vent through a wall, a 90° elbow is needed.

Heat Discharge


A 90° elbow may be installed immediately above the hood.

For Non-Vented (Recirculating) installations
If it is not possible to vent cooking fumes and vapors to the outside, the hood can be used in the non-vented (recirculating) version, using a Recirculation Kit which includes charcoal filters and a deflector. In order, see the Assistance or Service section.

Roof Venting

Wall Venting

Non-Vented (Recirculating)



1. Roof cap
B, 6" (15.2 cm)
round vent

2. Wall cap
B, 6" (15.2 cm)
round vent

3. Deflector
B, 6" (15.2 cm)
round vent

Calculating Vent System Length

To calculate the length of the system you need, add the equivalent length (in feet) for each vent piece used in the system.

Vent System

Vent Piece 6" (15.2 cm) Round 2.5 ft (0.8 m)


45° elbow

90° elbow 5.0 ft (1.5 m)

Maximum equivalent vent lengths 35 ft (10.7 m).



Example Vent System




The following example falls within the maximum recommended vent length of 35 ft (10.7 m).

1 x 90° elbow = 5.0 ft (1.5 m)

1 x Wall cap = 8.0 ft (2.4 m)

Length of system = 13.0 ft (3.9 m)


PRODUCT DIMENSIONS



*For non-vented (recirculating) installations
For vented installations

PN-26 (AB) (AV)
 March 23, 2021

CABINET DIMENSIONS



*For non-vented (recirculating) installations.

IMPORTANT:

- Minimum distance "X": 24" (61.0 cm) from electric cooking surface.
- Minimum distance "Y": 27" (68.6 cm) from gas cooking surfaces.
- Suggested maximum distance "X": 36" (91.4 cm).

The chimneys can be adjusted for different ceiling heights. See the following chart.			
Vented installations			
	Min. ceiling height	Max. ceiling height	
Electric cooking surface	7' 3" (2.18 m)	9' 2" (2.78 m)	
Gas cooking surface	7' 4" (2.23 m)		
Non-vented (recirculating) installations			
	Min. ceiling height	Max. ceiling height	
Electric cooking surface	7' 4" (2.18 m)	9' 6" (2.9 m)	
Gas cooking surface	7' 4" (2.23 m)		

*NOTE: The range hood chimneys are adjustable and designed to meet varying ceiling or soffit heights depending on the distance "X" between the bottom of the range hood and the cooking surface. For higher ceilings, a Chimney Extension Kit is available from your dealer or an authorized parts distributor. The chimney extension replaces the chimney shipped with the range hood. To order, see the "Assistance or Service" section.

PV-26 (1841X)
March 13, 1991



KitchenAid® 27" (68.6 cm) and 30" (76.2 cm) Electric Built-In

PRODUCT MODEL NUMBERS

KEMS303E KOES500E KOES607E

ELECTRICAL CONNECTION


If codes permit and a separate ground wire is used, it is recommended that a qualified electrical installer determine that the ground path and the wire gauge are in accordance with local codes. Check with a qualified electrical installer if you are not sure the oven is properly grounded.

The oven must be connected to a grounded, metal, permanent wiring system.

Be sure that the electrical connection and wire size are adequate, and in conformance with the National Electrical Code, ANSI/NFPA 70E, latest edition or CSA Standards C22.1-91, Canadian Electrical Code, Part 1 and C22.2 No. 0-MB1, latest edition, and all local codes and ordinances.

To properly install your oven, you must determine the type of electrical connection you will be using and follow the instructions provided for it here.

Oven must be connected to the proper electrical voltage and frequency as specified on the model/naming plate. See the following illustration.



A. Model/naming plate

* Models rated from 7.2 to 9.6 kW at 240 volts (6.4 to 7.4 kW at 208 volts) require a separate 40-amp circuit. Models rated at 4.6 kW and below at 240 volts (3.6 kW and below at 208 volts) require a separate 30-amp circuit.

* A circuit breaker is recommended.

* Connect directly to the fused disconnect (or circuit breaker box) through flexible, armored or nonmetallic sheathed copper cable (with grounding wire). See "Make Electrical Connection" section.

* Flexible conduit from the oven should be connected directly to the junction box.

* Do not cut the conduit. The length of conduit provided is for serviceability of the oven.

* If the house has aluminum wiring, follow the procedure below:

1. Connect a section of solid copper wire to the pigtail leads.

2. Connect the aluminum wiring to the solid section of copper wire using special connectors and/or code designed and UL listed for joining copper to aluminum.

Follow the electrical contractor manufacturer's recommended procedure. Aluminum copper connection must conform with local codes and industry accepted wiring practices.


For power requirements, refer to the following table.

Model	Voltage (V)	Amperage (A)	Rating (W)
KOES507E/KOES500E	120/240	32	48
KOES607E/KOES600E	120/208	30	38
			6500


* Amperage values noted above are for information purposes only; the units are rated in watts.

Because Whirlpool Corporation provides complete safety features to improve our products, we make the right to change available and specifications subject to change without notice.

PRODUCT DIMENSIONS



Cabinet Dimensions



- A: 27" (68.6 cm) inside height
- B: 25 1/4" (64.6 cm) measured height
- C: 41" (104.1 cm) recessed height
- D: 30 1/2" (77.8 cm) inside height
- E: 27" (68.6 cm) clear inside height
- F: 48" (121.9 cm) measured height
- G: 24" (61.2 cm) inside height
- H: 24" (61.2 cm) inside height
- I: 24" (61.2 cm) inside height
- J: 24" (61.2 cm) inside height
- K: 24" (61.2 cm) inside height
- L: 24" (61.2 cm) inside height
- M: 24" (61.2 cm) inside height
- N: 24" (61.2 cm) inside height
- O: 24" (61.2 cm) inside height
- P: 24" (61.2 cm) inside height
- Q: 24" (61.2 cm) inside height
- R: 24" (61.2 cm) inside height
- S: 24" (61.2 cm) inside height
- T: 24" (61.2 cm) inside height
- U: 24" (61.2 cm) inside height
- V: 24" (61.2 cm) inside height
- W: 24" (61.2 cm) inside height
- X: 24" (61.2 cm) inside height
- Y: 24" (61.2 cm) inside height
- Z: 24" (61.2 cm) inside height

* NOTE: The cabinet height can be between 41" (104.1 cm) and 41 1/2" (105.6 cm) for microwave/oven combination.


PV-26 (A) (H)
March 23, 2021

DIMENSIONS

COMMERCIAL-STYLE RANGE TOPS
PRODUCT DIMENSIONS

1 of 24

MODEL	30" (76.2 cm) Rangetop KCGG500J	36" (91.4 cm) Rangetop KCCG500J	48" (121.9 cm) Rangetop KCGG568J
U. S. of Measurement			
Overall Width (A)	29 3/4"	35 3/4"	47 3/4"
Grate Depth (B)	22"	22"	22"
Depth without Control Panel (C)	23 1/4"	23 1/4"	23 1/4"
Depth with Control Panel Overhang (D)	27 1/4"	27 1/4"	27 1/4"
Depth with Knobs (E)	29 1/4"	29 1/4"	29 1/4"



TOP VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before reflecting tabline, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

PN-26
March 23, 2021



DIMENSIONS

COMMERCIAL-STYLE RANGETOPS

2 of 24

PRODUCT DIMENSIONS

MODEL #	30 (76.2 cm) Rangetop KCCG500J	36 (91.4 cm) Rangetop KCCG506J	48 (121.9 cm) Rangetop KCCG58J
Unit of Measurement	cm	cm	cm
Grate Width (B)	27 1/8	35	44 1/4
Gas Inlet to Surface (G)	10 1/4	10 1/4	10 1/4
Cabinet to Gas Inlet (H)	11	14 1/4	19 1/4
Recessed Rangetop Width (I)	29 1/4	35 1/4	47 1/4
Includes width of grates and guides.	89.7	89.2	119.7



IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinet, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, ETL or CSA approved.

KitchenAid®

PV-26 (AP) (HY)
March 25, 2021

DIMENSIONS


COMMERCIAL-STYLE RANGETOPS

3 of 24

PRODUCT DIMENSIONS

MODEL #	30 (66.2 cm) Rangetop KCGC3001	36 (91.4 cm) Rangetop KCGC3606	48 (121.9 cm) Rangetop KCGC4803
Unit Width (cm)	40	48	64
Height with Grates (J)	9	9	9
Control Panel Height (K)	22.9	22.9	22.9
Recessed Rangetop Height (L)	19.8	19.8	19.8
Cooking Surface Height (M)	17.8	17.8	17.8
Recessed Rangetop Depth (N)	7 1/4	7 1/4	7 1/4
Depth with Control Panel (O)	25 1/4	25 1/4	25 1/4

IMPORTANT: Supplied regulator does not come preattached and is pictured for reference purposes only.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before
selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-26 (R) (H)
March 23, 2021


DIMENSIONS

COMMERCIAL-STYLE RANGE TOPS
OPENING/CLEARANCE DIMENSIONS

4 of 24

MODEL #	30" (76.2 cm) Range Top KCGG300J	36" (91.4 cm) Range Top KCGG506J	48" (121.9 cm) Range Top KCGG553J
Unit of Measurement	in	in	in
Combustible Area above Cooking Surface Width (min.) (A)	30	76.2	36
Bottom of Cabinet Height Above Cooking Surface (min.) (B)	42	106.7	66
Bottom of Cabinet Height Above Countertop (min.) (C)	18	45.7	18
Distances to Fixed Wall or Combustible Material (D)	12	30.5	12
			30.5
			12
			80.5

If installing a hood above the range top, follow the hood instructions for dimensional clearances above the cooking surface.



FRONT VIEW

IMPORTANT: Dimensions and specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the installation guide before selecting cabinet, verifying electrical connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-26 (M) (H)
March 23, 2021

DIMENSIONS

COMMERCIAL-STYLE RANGETOPS


5 of 24

OPENING/CLEARANCE DIMENSIONS

MODEL #	30" (76.2 cm) Rangertop KCG6500J	36" (91.4 cm) Rangertop KCG6500J	48" (121.9 cm) Rangertop KCG6550J
Left Cutout Depth (D)	18"	18"	18"
Recommended Upper-Cabinet Depth (E)	18"	18"	18"
Cutout to Wall Depth (if backwall is constructed of non-combustible material) (F)*	1 1/4"	1 1/4"	1 1/4"
Cutout to Wall Depth (if backwall is constructed of combustible material) (F)*	7 3/4"	7 3/4"	7 3/4"
Cabinet to Counter-top Height (G)†	18.4"	19.4"	18.4"
Cabinet Depth (H)	24"	24"	24"

*If the backwall is constructed of a combustible material and a backsplash is not installed, a 7 3/4" (19.7 cm) minimum clearance is required from the cutout or 6" (15.2 cm) minimum clearance from the back edge of the rangertop.

†The bottom of the cabinet supports the product. Unlike many cooktops, these models do not hang from the side flanges, but rather sit on the floor of the cutout.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinet. Verify electrical/gas connections, mating controls or piping prior to installation. All KitchenAid appliances are appropriately UL, CUL or CSA approved.

KitchenAid

PV-26 (A) (M)
March 23, 2021


DIMENSIONS

COMMERCIAL-STYLE RANGETOPS
OPENING/CLEARANCE DIMENSIONS

6 of 24

MODEL #	30" (76.2 cm) Rangetop KCCG500J	36" (91.4 cm) Rangetop KCCG506J	48" (121.9 cm) Rangetop KCCG588J
Unit of Measurement	in	in	in
Countertop and Cabinet Cutout Width (D)	29 1/8	36 1/4	47 1/4
Countertop and Cabinet Depth (G)	22 1/4	22 1/4	22 1/4
Moth Width (K)	1/4	1/4	1/4
Cutout Width (I)	29 3/4	36 3/4	47 3/4

NOTE: Due to manufacturing tolerances, these are nominal dimensions. You may need to readjust to meet your clearance.



IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before
selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®