



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

APPLIANCES

Invoice	Qty.	Description
2845 16Jul21 NoCat	1	APPLIANCE SPECIFICATIONS ATTACHED - SIGNED COPY.

BASEMENT WINDOWS

Invoice	Qty.	Description
2813 72,351 21Jun21 **	3	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME

CERAMIC

Invoice	Qty.	Description
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** DINING ROOM / POWDER ROOM: DELETE BUFFET NICHE IN DINING ROOM, EXTEND POWDER ROOM INTO NICHE SPACE VANITY SIZE AND STYLE TO BE DETERMINED AT COLOURS APPOINTMENT
2845 37 16Jul21	1	FOYER: TILE, FLOOR - LEVEL 5 - 12x24" LAID IN STRAIGHT STACKED PATTERN - SEE PLAN FOR DIRECTION
2845 37 16Jul21	1	POWDER ROOM: TILE, FLOOR - LEVEL 5 - 12x24" LAID IN STRAIGHT STACKED PATTERN - SEE PLAN FOR DIRECTION
2845 37 16Jul21	1	MUD ROOM: TILE, FLOOR , LEVEL 5 - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2845 35 16Jul21	1	BASEMENT FOYER: TILE, FLOOR , LEVEL 3 - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION.
2845 37 16Jul21	1	ENSUITE 2: TILE, FLOOR , LEVEL 3 - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2845 46 16Jul21	1	ENSUITE 2: TILE, WALL, LEVEL 2 - 3X12" LAID IN HORIZONTAL.
2845 26 16Jul21	1	ENSUITE 2: TILE INSTALLATION UPGRADE, WALL- BRICK PATTERN
2845 37 16Jul21	1	MASTER ENSUITE: TILE, FLOOR , LEVEL 5 - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2845 44 16Jul21	1	MASTER ENSUITE: TILE, SHOWER FLOOR, LEVEL 3 - PENNY ROUND



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

CERAMIC

Invoice	Qty.	Description
2845 51 16Jul21	1	MASTER ENSUITE: TILE, WALL, LEVEL 5 - 10X30" LAID IN VERTICAL STACKED PATTERN
2845 37 16Jul21	1	SHARED ENSUITE: TILE, FLOOR , LEVEL 3 - 12X24" LAID IN STRAIGHT, STACKED PATTERN. SEE PLAN FOR TILE DIRECTION
2845 44 16Jul21	1	SHARED ENSUITE: TILE, SHOWER FLOOR, LEVEL 3 - PENNY ROUND
2845 51 16Jul21	1	SHARED ENSUITE: TILE, WALL, LEVEL 5 - 12X24" LAID IN HORIZONTAL STACKED PATTERN.
2845 16Jul21 NoCat	1	KITCHEN/BREAKFAST: VINTAGE SERIES, 5" WHITE OAK, NSS ENGINEERED HARDWOOD, 3/4" THK, SCULPTED TEXTURE, UVF FINISH - LEVEL 4 KITCHE/BREAKFAST: DO NOT SUPPLY/ INSTALL CERAMIC - CREDIT

CONCRETE AND DRAIN

Invoice	Qty.	Description
2813 21Jun21 NoCat	1	BACK FLOW PREVENTER VALVE



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

DRYWALL

Invoice	Qty.	Description
2813 72,351 21Jun21 **	3	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME
2813 72,324 21Jun21 **	2	GARAGE DOOR OPENER (CHAMBERLAIN BELT DRIVE) - WITH 1 REMOTE - PRICE IS PER DOOR
2813 72,690 21Jun21 **	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** DINING ROOM / POWDER ROOM: DELETE BUFFET NICHE IN DINING ROOM, EXTEND POWDER ROOM INTO NICHE SPACE VANITY SIZE AND STYLE TO BE DETERMINED AT COLOURS APPOINTMENT
2813 21Jun21 NoCat	1	KITCHEN: INSTALL 6 FOOT WIDE PATIO SLIDING DOOR WITH NO GRILLS - APPROX. 8 FOOT HIGH - IN LIEU OF STANDARD DOUBLE FRENCH DOORS SMALL TRANSOM ABOVE TO REMAIN
2813 21Jun21 NoCat	1	FRONT EXTERIOR: ADDITIONAL EXTERIOR COACH LIGHT ON SAME SWITCH (BUILDERS STANDARD FIXTURE)
2813 21Jun21 NoCat	1	REAR EXTERIOR: ADDITIONAL EXTERIOR COACH LIGHT ON SAME SWITCH (BUILDERS STANDARD FIXTURE)
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 NoCat	1	THRU OUT 2ND FLOOR: INCREASE HEIGHT OF DOOR TO 8FT SECOND FLOOR - PER DOOR



CONSTRUCTION SUMMARY

Lot: 21

Model: 40.03 A BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

DRYWALL

Invoice	Qty.	Description
2813 21Jun21 NoCat	1	BEDROOM 4: RELOCATE DOOR OF WIC TO BEDROOM 3 - SEE PLAN
2813 21Jun21 NoCat	1	BEDROOM 3: DELETE STANDARD CLOSET AND FURNITURE NICHE
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** KITCHEN: DELETE STANDARD ENTRANCE FROM KITCHEN TO DINING ROOM - INSTALL FULL HEIGHT WALL



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

ELECTRICAL

Invoice	Qty.	Description
2813 72,351 21Jun21 **	3	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME
2813 72,268 21Jun21	1	GARAGE: INTERIOR WALL OUTLET: 110V WALL INTERIOR RECEPTACLE ON EXISTING CIRCUIT - SEE PLAN FOR LOCATION
2813 72,281 21Jun21	1	GREAT ROOM: INTERIOR WALL OUTLET: ADDITIONAL 110V WALL INTERIOR RECEPTACLE ON EXISTING CIRCUIT FOR WALL MOUNTED TV - ABOVE FIREPLACE, APPROX. 66" A.F.F.
2813 72,292 21Jun21	1	FRONT EXTERIOR: ADDITIONAL EXTERIOR COACH LIGHT ON SAME SWITCH (BUILDERS STANDARD FIXTURE)
2813 72,292 21Jun21	1	REAR EXTERIOR: ADDITIONAL EXTERIOR COACH LIGHT ON SAME SWITCH (BUILDERS STANDARD FIXTURE)
2813 72,272 21Jun21	1	KITCHEN: 110V WALL RECEPTACLE ON SEPARATE CIRCUIT - FOR MICROWAVE @ ISLAND - MICROWAVE NOT INCLUDED
2813 72,280 21Jun21	2	KITCHEN: INSTALL CAPPED CEILING LIGHT FIXTURE ON CEILING ABOVE KITCHEN ISLAND - SEE PLAN FOR APPROX. LOCATION
2813 72,278 21Jun21	1	KITCHEN: ADDITIONAL INTERIOR SWITCH FOR LIGHTS ABOVE ISLAND
2813 72,289 21Jun21	6	GREAT ROOM: 4" E/S LED INTERIOR POT LIGHT - GROUND FLOOR - EACH - INCLUDES ONE SWITCH INCLUDED IN APS // DELETE STANDARD CEILING LIGHT FIXTURE
2813 72,307 21Jun21	1	UPPER HALL: FIXTURE: RELOCATE STANDARD CEILING MOUNT FIXTURE TO APPROX. CENTRE ON CEILING AT OTB
2813 72,273 21Jun21	1	KITCHEN: 110V WALL RECEPTACLE ON SEPARATE CIRCUIT - GAS FIRED APPLIANCE - FOR AUX. EQUIPMENT - NOT A STOVE PLUG
2813 21Jun21 NoCat	1	STUDY: DELETE STANDARD CEILING FIXTURE AND SWITCH
2813 21Jun21 NoCat	1	MASTER ENSUITE: DELETE STANDARD CEILING FIXTURE(S) AND SWITCH - VANITY LIGHT FIXTURE AND SWITCH TO REMAIN



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

ELECTRICAL

Invoice	Qty.	Description
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** DINING ROOM / POWDER ROOM: DELETE BUFFET NICHE IN DINING ROOM, EXTEND POWDER ROOM INTO NICHE SPACE VANITY SIZE AND STYLE TO BE DETERMINED AT COLOURS APPOINTMENT
2813 21Jun21 NoCat	1	KITCHEN: INSTALL 6 FOOT WIDE PATIO SLIDING DOOR WITH NO GRILLS - APPROX. 8 FOOT HIGH - IN LIEU OF STANDARD DOUBLE FRENCH DOORS SMALL TRANSOM ABOVE TO REMAIN
2813 21Jun21 NoCat	1	KITCHEN: CONVERT STANDARD BASE CABINET ON ISLAND INTO BUILT-IN MICROWAVE CABINET WITH DRAWER BELOW
2813 21Jun21 NoCat	1	THRU OUT 2ND FLOOR: INCREASE HEIGHT OF DOOR TO 8FT SECOND FLOOR - PER DOOR
2813 21Jun21 NoCat	1	BEDROOM 4: RELOCATE DOOR OF WIC TO BEDROOM 3 - SEE PLAN
2813 21Jun21 NoCat	1	BEDROOM 3: DELETE STANDARD CLOSET AND FURNITURE NICHE
2845 16Jul21 NoCat	1	APPLIANCE SPECIFICATIONS ATTACHED - SIGNED COPY.

EXTERIOR DOORS

Invoice	Qty.	Description
2813 72,363 21Jun21	1	GARAGE: INCREASED HEIGHT TO MAN DOOR FROM HOUSE TO GARAGE - TALL HEIGHT * WOOD FRAME - IF GRADE PERMITS [EACH]
2813 72,359 21Jun21	1	KITCHEN: INSTALL 6 FOOT WIDE PATIO SLIDING DOOR WITH NO GRILLS - APPROX. 8 FOOT HIGH - IN LIEU OF STANDARD DOUBLE FRENCH DOORS SMALL TRANSOM ABOVE TO REMAIN



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

FRAMING

Invoice	Qty.	Description
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** DINING ROOM / POWDER ROOM: DELETE BUFFET NICHE IN DINING ROOM, EXTEND POWDER ROOM INTO NICHE SPACE VANITY SIZE AND STYLE TO BE DETERMINED AT COLOURS APPOINTMENT
2813 72,690 21Jun21	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 NoCat	1	BEDROOM 4: RELOCATE DOOR OF WIC TO BEDROOM 3 - SEE PLAN
2813 21Jun21 NoCat	1	BEDROOM 3: DELETE STANDARD CLOSET AND FURNITURE NICHE
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** KITCHEN: DELETE STANDARD ENTRANCE FROM KITCHEN TO DINING ROOM - INSTALL FULL HEIGHT WALL
2813 21Jun21 NoCat	1	KITCHEN: INSTALL 6 FOOT WIDE PATIO SLIDING DOOR WITH NO GRILLS - APPROX. 8 FOOT HIGH - IN LIEU OF STANDARD DOUBLE FRENCH DOORS SMALL TRANSOM ABOVE TO REMAIN
2813 21Jun21 NoCat	1	FRONT EXTERIOR: ADDITIONAL EXTERIOR COACH LIGHT ON SAME SWITCH (BUILDERS STANDARD FIXTURE)
2813 21Jun21 NoCat	1	REAR EXTERIOR: ADDITIONAL EXTERIOR COACH LIGHT ON SAME SWITCH (BUILDERS STANDARD FIXTURE)
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

FRAMING

Invoice	Qty.	Description
2813	1	THRU OUT 2ND FLOOR: INCREASE HEIGHT OF DOOR TO 8FT SECOND FLOOR - PER DOOR
21Jun21 NoCat		

GARAGE DOORS

Invoice	Qty.	Description
2813 72,324 21Jun21	2	GARAGE DOOR OPENER (CHAMBERLAIN BELT DRIVE) - WITH 1 REMOTE - PRICE IS PER DOOR

GLASS AND MIRROR

Invoice	Qty.	Description
2845 16Jul21 NoCat	2	MASTER ENSUITE + SHARED ENSUITE: UPGRADE SHOWER DOOR HARDWARE - CHROME

GRANITE MARBLE QUARTZ

Invoice	Qty.	Description
2813 21Jun21 NoCat	1	SHARED ENSUITE: DELETE ONE STANDARD VANITY SINK, RELOCATE SINGLE SINK TO APPROX. CENTRE OF VANITY
2845 16Jul21 NoCat	1	KITCHEN: UPGRADE QUARTZ COUNTERTOP - LEVEL 6 **INCLUDES AT FORMER OPENING TO DINING ROOM**
2845 74,429 16Jul21	2	KITCHEN: QUARTZ, 48" WATERFALL LEG (PRICE PER LEG) - LEVEL 6
2845 16Jul21 NoCat	1	POWDER ROOM: UPGRADE 6 QUARTZ COUNTER
2845 16Jul21 NoCat	1	ENSUITE 2: UPGRADE 5 QUARTZ COUNTER
2845 16Jul21 NoCat	1	MASTER ENSUITE: UPGRADE 6 QUARTZ COUNTER
2845 16Jul21 NoCat	1	SHARED ENSUITE: UPGRADE 6 QUARTZ



CONSTRUCTION SUMMARY

Lot: 21

Model: 40.03 A BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

HARDWOOD

Invoice	Qty.	Description
2845 7 16Jul21	1	KITCHEN/BREAKFAST: VINTAGE SERIES, 5" WHITE OAK, NSS ENGINEERED HARDWOOD, 3/4" THK, SCULPTED TEXTURE, UVF FINISH - LEVEL 4
2845 7 16Jul21	1	THRU OUT STANDARD AREAS: MAIN HALL, DINING ROOM, STUDY, GREAT ROOM, UPPER HALL, MASTER BEDROOM, BEDROOM 2, BEDROOM 3, BEDROOM 4, LOWER MEDIA ROOM - VINTAGE SERIES, 5" WHITE OAK, NSS ENGINEERED HARDWOOD, 3/4" THK, SCULPTED TEXTURE, UVF FINISH - LEVEL 4



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

HVAC

Invoice	Qty.	Description
2813 72,239 21Jun21	1	3.5 TON AC - WITH LOW VOLTAGE WIRING & WALL BRACKETS (14ACX)
2813 72,215 21Jun21	1	FURNACE - LENNOX 2 STAGE VARIABLE SPEED FURNACE (90,000 TO 110,000 BTU FOOT S) IN LIEU OF STANDARD OFFERING - (PINE VALLEY SITE ONLY - REFERENCE MODEL SPECIFIC FOR FURANCE UPGRADE EXTRA)
2813 72,690 21Jun21 **	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 72,224 21Jun21	1	KITCHEN: GAS LINE ROUGH-IN - MAIN FLOOR FOR APPLIANCE - SEE PLAN FOR APPROX. LOCATION FINAL LOCATION, ORIENTATION AND CONNECTION TO BE COMPLETED BY A LICENSED GAS FITTER AND ARRANGED BY HOMEOWNER AFTER CLOSING AT THEIR OWN EXPENSE AND WARRANTY
2813 21Jun21 ** NoCat	1	3.5 TON AC - WITH LOW VOLTAGE WIRING & WALL BRACKETS (14ACX)
2813 21Jun21 ** NoCat	1	FURNACE - LENNOX 2 STAGE VARIABLE SPEED FURNACE (90,000 TO 110,000 BTU FOOT S) IN LIEU OF STANDARD OFFERING - (PINE VALLEY SITE ONLY - REFERENCE MODEL SPECIFIC FOR FURANCE UPGRADE EXTRA) VANITY SIZE AND STYLE TO BE DETERMINED AT COLOURS APPOINTMENT
2813 21Jun21 NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

INTERIOR TRIM AND DOORS

Invoice	Qty.	Description
2813 72,644 21Jun21	14	THRU OUT 2ND FLOOR: INCREASE HEIGHT OF DOOR TO 8FT SECOND FLOOR - PER DOOR
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** DINING ROOM / POWDER ROOM: DELETE BUFFET NICHE IN DINING ROOM, EXTEND POWDER ROOM INTO NICHE SPACE VANITY SIZE AND STYLE TO BE DETERMINED AT COLOURS APPOINTMENT
2813 21Jun21 NoCat	1	BEDROOM 4: RELOCATE DOOR OF WIC TO BEDROOM 3 - SEE PLAN
2813 21Jun21 NoCat	1	BEDROOM 3: DELETE STANDARD CLOSET AND FURNITURE NICHE
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** KITCHEN: DELETE STANDARD ENTRANCE FROM KITCHEN TO DINING ROOM - INSTALL FULL HEIGHT WALL
2845 153,300 16Jul21	1	THRU OUT: UPGRADE 3 1/4" STEP BEVEL BB CASING, 7 1/4" BASE BOARD UPGRADE



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

KITCHEN AND BATH CABINETRY

Invoice	Qty.	Description
2813 72,272 21Jun21	1	KITCHEN: CONVERT STANDARD BASE CABINET ON ISLAND INTO BUILT-IN MICROWAVE CABINET WITH DRAWER BELOW
2813 72,690 21Jun21 **	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 NoCat	1	MUD ROOM: INSTALL OPTIONAL STANDARD UPPER LAUNDRY CABINETS (BUILDERS STANDARD OFFERING)
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 ** NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 NoCat	1	DELETE KITCHEN BULKHEAD, IF POSSIBLE, SITE APPROVAL REQUIRED
2813 21Jun21 NoCat	1	SHARED ENSUITE: DELETE ONE STANDARD VANITY SINK, RELOCATE SINGLE SINK TO APPROX. CENTRE OF VANITY
2845 16Jul21 NoCat	1	THRU OUT: SEE ATTACHED CABINETRY SCHEDULE
2845 16Jul21 NoCat	1	APPLIANCE SPECIFICATIONS ATTACHED - SIGNED COPY.



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

MASONRY

Invoice	Qty.	Description
2813 21Jun21 NoCat	1	KITCHEN: INSTALL 6 FOOT WIDE PATIO SLIDING DOOR WITH NO GRILLS - APPROX. 8 FOOT HIGH - IN LIEU OF STANDARD DOUBLE FRENCH DOORS SMALL TRANSOM ABOVE TO REMAIN
2813 21Jun21 NoCat	1	FRONT EXTERIOR: ADDITIONAL EXTERIOR COACH LIGHT ON SAME SWITCH (BUILDERS STANDARD FIXTURE)
2813 21Jun21 NoCat	1	REAR EXTERIOR: ADDITIONAL EXTERIOR COACH LIGHT ON SAME SWITCH (BUILDERS STANDARD FIXTURE)

NETWORK AND WIRING

Invoice	Qty.	Description
2813 72,259 21Jun21	1	GREAT ROOM: CONDUIT PIPE - FOR WALL MOUNT TV - APPROX. 66" A.F.F., ABOVE FIREPLACE, THRU BASEMENT, TERMINATE AT STD OUTLET
2813 72,281 21Jun21	1	GREAT ROOM: STANDARD CABLE TO BE INSTALLED ABOVE FIREPLACE, APPROX. 66" A.F.F.

PAINT

Invoice	Qty.	Description
2813 21Jun21 NoCat	1	KITCHEN: INSTALL 6 FOOT WIDE PATIO SLIDING DOOR WITH NO GRILLS - APPROX. 8 FOOT HIGH - IN LIEU OF STANDARD DOUBLE FRENCH DOORS SMALL TRANSOM ABOVE TO REMAIN
2813 21Jun21 NoCat	1	THRU OUT 2ND FLOOR: INCREASE HEIGHT OF DOOR TO 8FT SECOND FLOOR - PER DOOR
2813 21Jun21 NoCat	1	BEDROOM 3: DELETE STANDARD CLOSET AND FURNITURE NICHE
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** KITCHEN: DELETE STANDARD ENTRANCE FROM KITCHEN TO DINING ROOM - INSTALL FULL HEIGHT WALL
2845 16Jul21 NoCat	2	MAIN STAIRS - 2ND FLOOR TO BASEMENT: STAIN STAIRS AND LANDINGS WILL NOT MATCH HARDWOOD IN COLOUR, SPECIES, OR TEXTURE



CONSTRUCTION SUMMARY

Lot: 21

Model: 40.03 A BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1



CONSTRUCTION SUMMARY

Lot: 21

Model: 40.03 A BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1



CONSTRUCTION SUMMARY

Lot: 21
Model: 40.03 A BROOKSIDE
Project/Phase: Pine Valley Forevergreen / 1

PLUMBING

Invoice	Qty.	Description
2813 21Jun21 NoCat	1	SHARED ENSUITE: DELETE ONE STANDARD VANITY SINK, RELOCATE SINGLE SINK TO APPROX. CENTRE OF VANITY
2813 75,845 21Jun21	1	MASTER ENSUITE: UPGRADE TO MOEN ARRIS SHOWER FAUCET W/ HANDSHOWER AND SLIDE BAR - CHROME
2813 75,845 21Jun21	1	SHARED ENSUITE: UPGRADE TO MOEN ARRIS SHOWER FAUCET W/ HANDSHOWER AND SLIDE BAR - CHROME
2813 75,841 21Jun21	1	MASTER ENSUITE: UPGRADE TO MOEN ARRIS FREE-STANDING TUB FILLER - INCLUDES TUB DRAIN HALF KIT - CHROME
2813 21Jun21 NoCat	1	**CUSTOM LAYOUT** DINING ROOM / POWDER ROOM: DELETE BUFFET NICHE IN DINING ROOM, EXTEND POWDER ROOM INTO NICHE SPACE VANITY SIZE AND STYLE TO BE DETERMINED AT COLOURS APPOINTMENT
2845 16Jul21 NoCat	1	KITCHEN: UPGRADE SINK

STAIR AND RAILINGS

Invoice	Qty.	Description
2845 93,781 16Jul21	2	MAIN STAIRS: UPGRADE - EURONLINE (ALL PLAIN) PICKET, 3" HALF-ROUND W/V-GROOVE HANDRAIL, 3 1/2" ALL SQUARE POST WITH PYRAMID TOP POST CAP - PACKAGE A-2

PURCHASER'S EXTRAS QUOTATION
Pine Valley Forevergreen - Phase 1

PURCHASER: INESSA GOLD

TEL: RES.: 416-768-2677 BUS.: 416-768-2677

Table with 3 columns: LOT NUMBER (21), PHASE (1), HOUSE TYPE (40.03 A BROOKSIDE)

Main table with 5 columns: ITEM, EXTRA / CHANGE, QTY, UNIT PRICE, EXTENDED. Contains 16 line items detailing construction extras such as thru outs, kitchen upgrades, and tile installations.

Initials: [Signature]

CONSTRUCTION SCHEDULING APPROVAL
PER:
DATE:

PURCHASER'S EXTRAS QUOTATION
Pine Valley Forevergreen - Phase 1

PURCHASER: INESSA GOLD TEL: RES.: 416-768-2677 BUS.: 416-768-2677

Table with 3 columns: LOT NUMBER (21), PHASE (1), HOUSE TYPE (40.03 A BROOKSIDE)

Table with 5 columns: ITEM, EXTRA / CHANGE, QTY, UNIT PRICE, EXTENDED. Contains 11 rows of item details including tile upgrades, counter upgrades, and handrail packages.

Initials: [Signature]

CONSTRUCTION SCHEDULING APPROVAL
PER:
DATE:

PURCHASER'S EXTRAS QUOTATION
Pine Valley Forevergreen - Phase 1

PURCHASER: INESSA GOLD

TEL: RES.: 416-768-2677 BUS.: 416-768-2677

Table with 3 columns: LOT NUMBER (21), PHASE (1), HOUSE TYPE (40.03 A BROOKSIDE)

Table with 4 columns: ITEM, EXTRA / CHANGE, QTY, UNIT PRICE, EXTENDED

Summary table with 2 columns: Description, Amount. Rows: Sub Total (\$113,639.80), HST (\$14,773.17), Total (\$128,412.97)

- 50% deposit

\$ 64,206.48 (due)

This is your direction to install the above extras in accordance with the following terms and conditions:

- 1. In the event the work on the house has progressed beyond the point where the items covered by this extra cannot be installed without entailing any unusual expense, then this order is to be cancelled and any deposit paid in connection with the same is to be refunded to the purchaser.
2. The Vendor will undertake to incorporate the work covered by the sales extra in the construction of the house but will not be liable to the purchaser in any way, if for any reason the work covered by the extra is not carried out. In that event, any monies paid in connection with the same shall be returned to the purchaser.
3. It is understood and agreed that if for any reason whatsoever the transaction of Purchase and Sale is not completed, the total cost of extras ordered are not refundable to the Purchaser(s).
4. Extras or changes will not be processed unless signed by the Vendor.
5. These extras may not be amended without the written consent of GOLDPARK (PINE VALLEY) INC.
6. The purchaser(s) and the builder acknowledge and agree that this "Purchaser's Extra" form shall not be deemed to be part of the agreement of purchase and sale entered into between them, nor an addendum thereto.
7. Prices are estimates only and guaranteed for a period of 5 days only.
8. No post dated cheques will be accepted.
9. No Estimates or orders will be accepted once construction has commenced.
10. All extras/selections are final with signature. All enquiries to re-open a file and/or request changes to any extras/selections is subject to a fee of \$500.00 (five hundred dollars).
11. No estimates will be considered official orders until resubmitted on a signed Purchaser Extras Form, accompanied by payment in full.

Payment Summary table with 2 columns: Paid By, Amount. Rows: Amendment (\$64,206.49), Cheque (\$64,206.48), Total Payment (\$128,412.97)

Bonus Summary table with 2 columns: Description, Amount. Rows: Bonus Package Offering (\$25,000.00), Invoice Number, Date, Amount

PURCHASER:

Signature of Inessa Gold

14-Jul-21
DATE

VENDOR:

PER: GOLDPARK (PINE VALLEY) INC.

CONSTRUCTION SCHEDULING APPROVAL
PER:
DATE:



ROOM	DESCRIPTION	PRICE	QTY	TOTAL
KITCHEN	UPGRADE FROM SERIES 2 TO SERIES 5 - MEDIO 6 OYSTER	7,421.70	1	\$ 7,421.70
	UPGRADE HARDWARE - H050-21	1,640.00	1	\$ 1,640.00
	ADD DECORATIVE HOOD CANOPY - CLASSIC	3,680.00	1	\$ 3,680.00
	ADJUST BASE CABINETRY FOR 36" RANGE (N/C)	-	1	\$ -
	ADD CABINETRY VALANCE ONLY (NO ELECTRICAL)	1,440.00	1	\$ 1,440.00
	CONVERT BASE CABINETS TO BASE POTS AND PANS DRAWERS	990.00	2	\$ 1,980.00
	CLOSE OPENING BETWEEN DINING ROOM AND KITCHEN, ADD UPPERS AND BASE CABINETS TO ACCOMMODATE	2,780.00	1	\$ 2,780.00
	RETURN TRIP FOR HARDWOOD	320.00	1	\$ 320.00
	REDUCE UPPERS AND ADD 18"H MINI STACKED UPPERS WITH CROWN MOULDING (ADJUST CABINETRY DEPTH TO ACCOMMODATE DUCT WORK/ PIPING/ ELECTRICAL AS REQUIRED)	21,760.00	1	\$ 21,760.00
				\$ 41,021.70
ISLAND	UPGRADE FROM SERIES 2 TO SERIES 5 - MEDIO 6 OYSTER	1,266.10	1	\$ 1,266.10
	ADD PROUD FURNITURE KICK TO REAR ISLAND ONLY	375.00	1	\$ 375.00
	CONVERT STD CABINETRY TO BUILT IN MICROWAVE CABINET WITH DRAWER BELOW (PURCHASED ON STRUCTURAL ORDER)	-	1	\$ -
	RELOCATE STANDARD BANK OF 4 DRAWERS TO ISLAND (N/C)	-	1	\$ -
	NOTE: NO PLUG ON ISLAND			
			\$ 1,641.10	
CABINETRY TOTAL:			\$	42,662.80

*****HARDWARE: HORIZONTAL ON DRAWERS, VERTICAL ON DOORS*****

LOT #:	PR-21	DATE:	July 13, 2021
SIGNATURE:			
SIGNATURE:			

GOLDPARK
WORTH MORE

REVISED:
2021-07-13

PV-Z1

July 13, 2021


5.6

- * No plug on island *
- * Hardwood in Kitchen *
- * Stacked mini uppers *

GOLDPARK HOMES
PINE VALLEY
VAUGHAN, ONTARIO
MODEL: (4003)
BROOKSIDE

SITE STANDARD: WHITE 3/4" EXTENSION
SOFT-CLOSE DRAWERS & SOFT-CLOSE
HINGES TO KITCHEN AREA

10' CEILING - 12"H COFFERED CEILING -
M.H. = 102" + 3/4"H CONTEMPORARY
MOLDING + 5 1/4"H FURRING RAIL
+ LARGE CORNICE MOLDING TO
UNDERSIDE OF BOX



'Classic' Decorative Canopy Hood Cabinet





PLAN VIEW

PV-21
July 13, 2021
IG.



**GOLDPARK HOMES
PINE VALLEY
VAUGHAN, ONTARIO
MODEL: (4003) BROOKSIDE**

SITE STANDARD: WHITE 3/4" EXTENSION
SOFT-CLOSE DRAWERS & STANDARD SLAM DOOR HINGES
TO VANITIES

ONE TOP DRAWER WHERE POSSIBLE THROUGHOUT EACH
VANITY, ONE BANK OF DRAWERS WHERE POSSIBLE
THROUGHOUT EACH MASTER ENSUITE VANITY



* Revised on floor plan - one sink



PLAN VIEW

Scheduled Closing Date: November 25, 2021

Purchaser: INESSA GOLD

Property: 21 of Plan -

Telephone Res. / Bus: (416) 768-2677 / (416) 768-2677

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Angela Phim

Model and Elevation: 40.03 A BROOKSIDE

Layout Changes: Yes No

Sketch Attached: Yes No

Exterior Colour Scheme:

1. Cabinetry

Table with 4 columns: Room, Style and Colour, Counter, Hardware. Rows include Kitchen / Breakfast, Laundry Room, Powder Room, Mud Room, Master Ensuite Bathroom, Second Ensuite Bathroom (If Applicable), and Ensuite 3/4.

Comment

2. Floor Tile

Table with 2 columns: Room, Selection. Rows include Entrance Vestibule, Main Hall, Kitchen / Breakfast, Laundry Room, Powder Room, Mud Room, Master Ensuite Bathroom, Second Ensuite Bathroom (If Applicable), Lower Landing (If Applicable), and Ensuite 3/4.

Comment

Master Ensuite + Ensuite 3/4 Shower Floor: *Penny Round 'white' polished

3. Wall Tile

Table with 4 columns: Room, Selection, Listello/Inserts, Describe. Rows include Master Ensuite Bathroom (Tub Deck, Shower Stall, Bathroom Walls), Second Ensuite Bathroom (If Applicable), Ensuite 3/4, and Kitchen Backsplash.

Comment

Ensuite 3/4 Wall Tile: 12x24" Marmorea 'Bianco Calacatta' polished

16

*** NOTE: This is not an approved document. Document must be locked ***

Scheduled Closing Date: November 25, 2021

Purchaser: INESSA GOLD
Telephone Res. / Bus: (416) 768-2677 / (416) 768-2677
Decor Advisor: Angela Phim
Property: 21 of Plan -
Project: Pine Valley Forevergreen - Phase 1
Model and Elevation: 40.03 A BROOKSIDE

4. Plumbing Fixtures

Master Ensuite Bathroom
Second Ensuite
Powder Room
Other Room - Specify
Other Washroom

Comment
*see attached

5. Hardwood Flooring

Main Hall
Kitchen / Breakfast
Living Room
Dining Room
Family Room
Den/Library
Entrance Vestibule
Lower Landing (If Applicable)
Upper Landing
Upper Hall
Master Bedroom
Bedroom #2
Bedroom #3
Bedroom #4
Bedroom #5
Other Room - Specify thru-out standard areas

Comment

6. Carpeting

Ground Floor
Second Floor
Upgrade
Description

Upgrade Underpad
Carpet on Stairs
Type
Area
Capped
Runner - *Upgrade

Comment

7. Fireplace

Living Room
Family Room
Other Room - Specify Great Room
Fireplace Type
Mantle Type
Colour / Stain
Surround
Hearth

Comment

16

Purchaser: INESSA GOLD

Property: 21 of Plan -

Telephone Res. / Bus: (416) 768-2677 / (416) 768-2677

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Angela Phim

Model and Elevation: 40.03 A BROOKSIDE

8. Trim Carpentry

Interior Doors Front Door Glass Inserts Door Handles

Interior Trim

Comment

9. Plaster Mouldings and Medallions

Standard Throughout ☐ Yes ☐ No ☐ N/A

Entrance Vestibule			Kitchen/Breakfast		
Main Hall			Den/Library		
Living Room			Lower Landing		
Dining Room			Other Room - Specify		
Family Room					

Comment

10. Railings and Spindles

Railing Package

Railing Colour

Stringer / Riser

Spindle Colour

Treads

Comment

Oak Stairs ☒ Yes ☐ No ☐ N/A

11. Wall Paint / Ceilings

Throughout Finished Areas

Trim Paint

Smooth Ceilings

Ground Floor ☒

Second Floor ☒

Note

Comment

I.6

Scheduled Closing Date: November 25, 2021

Purchaser: INESSA GOLD

Property: 21 of Plan -

Telephone Res. / Bus: (416) 768-2677 / (416) 768-2677

Project: Pine Valley Forevergreen - Phase 1

Decor Advisor: Angela Phim

Model and Elevation: 40.03 A BROOKSIDE

12. Electrical

Hood Fan ☐ White ☐ Stainless ☒ N/A

Above Kitchen Cabinet Light ☐ Yes ☒ No

Standard Appliances ☐

Below Kitchen Cabinet Light ☐ Yes ☒ No

Over The Range Microwave ☐

Chimney Style Fan ☐

Comment

13. Heating and Air Conditioning

Air Conditioning

Gas Provisions Stove

Gas Provisions Dryer

Gas Provisions Barbecue

Comment

14. Additional Comments

15. Disclaimers and Notes

- 1) Colours of all materials are as close as possible to builder's selection, but not necessarily identical due to variances in manufacturing.
- 2) Any extras listed above are null and void unless accompanied by a separate invoice/amendment. Said invoice must be paid in full.
- 3) The Purchaser acknowledges that after Interior Colour Selection form is signed and dated, no further changes will be permitted other than re-selection due to unavailability. I.G. Purchaser's Initials
- 4) The Purchaser acknowledges reading and accepting the "Gold Park Homes Decor Centre Disclaimers" form. This document contains other miscellaneous disclaimers.

This Interior Colour Selection is final and approved by:

Signature: I.G.

Date: July 14, 2021



SCHEDULE 'F'

PV-21

June 17, 2021

attached

PV-21


July 13, 2021

(I6.)

The Brookside

40' SERIES

Elevation A • 3,380 sq.ft.
Elevation B • 3,350 sq.ft.



VENDOR

PURCHASER

PURCHASER

GOLDPARK
WORTH MORE™

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 4003



8' DOORS
THRU OUT


SCHEDULE 'F'
PV-21
June 17, 2021
PV-21
July 13, 2021

attached

16

The Brookside 40' SERIES

Elevation A • 3,380 sq.ft.
Elevation B • 3,350 sq.ft.



VENDOR	
PURCHASER	
PURCHASER	

GOLDPARK
WORTH MORE™

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 4003



SCHEDULE 'F'

PV-21

June 17, 2021

attached

PV-21


July 13, 2021

E.G.

The Brookside

40' SERIES

Elevation A • 3,380 sq.ft.
Elevation B • 3,350 sq.ft.



BASEMENT | ELEV. A

VENDOR	
PURCHASER	
PURCHASER	


GOLDPARK
WORTH MORE™

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 4003



PINE VALLEY
FOREVERGREEN


STONE COUNTERTOP EDGE PROFILES



STANDARD 2CM EASED EDGE

LOCATION:

* thru-out *



UPGRADE 3CM EASED EDGE


LOCATION:



UPGRADE 4CM MITRED EDGE



LOCATION:



UPGRADE 2CM OGEE EDGE

LOCATION:

LOT #: PV-21

DATE: July 13, 2021

SIGNATURE:

I.G.

SIGNATURE:

I.G.



PINE VALLEY
FOREVERGREEN

STANDARD HARDWARE / KNOBS



☐ K002-02



☒ K002-03

→ Powder Room → Master Ensuite
→ Ensuite 2 → Ensuite 3/4



☐ K002-04



☐ K002-06



☐ K002-05



☐ K008-14



☐ K024-03

☐ *NO HARDWARE

☐ TOUCH-LATCH

*DISCLAIMER: NO HARDWARE OR HOLES THRU-OUT: HOMEOWNER IS RESPONSIBLE FOR THE INSTALLATION OF THEIR OWN HARDWARE AFTER CLOSING AT THEIR OWN EXPENSE AND WARRANTY.

LOT # PV-21

DATE: July 13, 2021

SIGNATURE:

I.G.

SIGNATURE:

I.G.



PINE VALLEY
FOREVERGREEN

STANDARD HARDWARE / HANDLES

☐

H001-02

☐

H001-03

☐

H001-04

☐

H009-03

☐

H009-09

☐

TOUCH-LATCH

☐

H011-03

☐

H011-05

☐

H011-06

☐

H033-01

☒

H039-03

→ Mud Room

☐

*NO HARDWARE

*DISCLAIMER: NO HARDWARE OR HOLES THRU-OUT: HOMEOWNER IS RESPONSIBLE FOR THE INSTALLATION OF THEIR OWN HARDWARE AFTER CLOSING AT THEIR OWN EXPENSE AND WARRANTY.

LOT # PV-21

DATE: July 13, 2021

SIGNATURE:

S.G.

SIGNATURE:

S.G.

GOLDPARK
WORTH MORE

H050-21

Pull - 'Antiqued Nickel'



LOCATION:

→ Kitchen

LOT # PV-21

DATE: July 13, 2021

SIGNATURE: 




SIGNATURE: 



PINE VALLEY
FOREVERGREEN

UPGRADE KITCHEN SINK

BLANCO - QUATRUS R15 U 2
Stainless Steel - Undermount
32" x 18" x 9"



Stainless Steel

MODEL 401519 Stainless Steel /

Lot#

PV-21

Room:

Kitchen

Signature:

Date:

July 13, 2021


Signature:

GOLDPARK
WORTH MORE™

UPGRADE SHOWER HARDWARE

SQ6X6

Shower Door Handle



SQ6X6
Shower Door Handle

6" x 6" back-to-back
3/4" square tube

- ☒ CHROME
- ☐ MATTE BLACK


Lot# PY-21	Date: July 13, 2021	Room: Master Ensuite + Ensuite 3/4
Signature: I.B.		
Signature:		

BATHROOM ACCESSORIES




PINE VALLEY

FOREVERGREEN



Tissue Holder
Mason - Chrome



Towel Bar
Mason - Chrome

Please select one of the following:

☐ INSTALL STANDARD BATHROOM ACCESSORIES THRU OUT
(tissue holder + towel bar) **location as per vendors discretion**

☒ ***DO NOT*** INSTALL STANDARD BATHROOM ACCESSORIES
THRU OUT **tissue holder + towel bar will not be provided**

LOT #

PV-21

DATE:

July 13, 2021

SIGNATURE:

E.G.

SIGNATURE:

E.G.



Project: Pine Valley

Lot: 21

Purchaser(s): NESSA GOLD

Standard Hood Fan Deletion

We acknowledge that the builder's standard hood fan will not be installed.
Do not supply, install and/or credit. We will install our own hood fan after closing.

Signature:

I.G.

Signature:

Date:


July 13, 2021

UPGRADE KITCHEN EXTRA



CLASSIC RANGE HOOD

(Insert fan not included)



LOT # *PV-21*

ROOM: *Kitchen*

DATE: *July 13, 2021*

SIGNATURE:

I. G.

SIGNATURE:



Bank Draft / Traite de Banque

3567 7870 4

27-43345

MRS INESSA GOLD

03392 HWY 400 & MAJOR MACKENZIE DR BK CTR
VAUGHAN, ONT

2021-07-14

Date Y/A M/M D/J

Name of remitter / Donneur d'ordre

Transit No.
N° d'identification

Banking Centre
Centre bancaire

\$*****64,206.48

Pay to the
order of

Payez à
l'ordre de

GOLDPARK (PINEVALLEY) INC. *****

Canadian Dollars CAD
Dollars Canadiens

The sum of *****SIXTY FOUR THOUSAND TWO HUNDRED SIX 48/100
La somme de

For Canadian Imperial Bank of Commerce
Pour La Banque Canadienne Impériale de Commerce

To
Tiré:
129-2020/04

Canadian Imperial Bank of Commerce
Toronto
Canada

HEAL
Chief Executive Officer / Chef de la Direction

⑈356778704⑈ ⑆09502⑈010⑆ 03392⑈2743345⑈

PV-21

July 15, 2021

Invoice # 2845


'Colours'



PLUMBING UPGRADES

MOEN - ARRIS

Posi-Temp Tub/Shower Faucet with 3 Function Transfer Valve/Trim and Slide Bar
with Handshower



☒ CHROME

*from CEILING

☐ BRUSHED NICKEL (BN)

☐ MATTE BLACK (BL)

MODEL: TS22002EP / U361CI / UTS23005 / 62320 / 3887EP / A725 / 226651

Lot# PV-21

Date: June 17, 2021

Room: Master Ensuite, Shared Ensuite

Signature:

attached

Signature:




PINE VALLEY
FOREVERGREEN

PLUMBING UPGRADES

MOEN - ARRIS

Single Freestanding Tub Filler



☒ CHROME

☐ BRUSHED NICKEL (BN)

MODEL: TS50100 / S93005 / T90331 / 140680


Lot# PV-21	Date: June 17, 2021	Room: Master Ensuite
Signature: attached		
Signature:		

PLUMBING UPGRADES



MOEN - ARRIS

Posi-Temp Tub/Shower Faucet with 3 Function Transfer Valve/Trim and Slide Bar with Handshower



- ☒ CHROME
- ☐ BRUSHED NICKEL (BN)
- ☐ MATTE BLACK (BL)

*from CEILING

MODEL: TS22002EP / U361CI / UTS23005 / 62320 / 3887EP / A725 / 226651


Lot# PV-21	Date: June 17, 2021	Room: Master Ensuite, Shared Ensuite
Signature: 		
Signature:		

GOLDPARK
WORK 2011

PLUMBING UPGRADES



MOEN - ARRIS
Single Freestanding Tub Filler



- ☒ CHROME
- ☐ BRUSHED NICKEL (BN)

MODEL: TS50100 / S99005 / T90331 / 140680

Lot# PV-21	Date: June 17, 2021	Room: Master Ensuite
Signature:		
Signature:		

GOLDPARK
WORTH BUTY

PV-ZI
July 13 2021
I.G.

DIMENSIONS


1 of 30

COMMERCIAL-STYLE RANGES

PRODUCT DIMENSIONS

✱

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J	
	in	cm	in	cm
Overall Width (A)	29 $\frac{7}{8}$	75.9	35 $\frac{7}{8}$	91.1
Bullnose Height (B)	2 $\frac{3}{16}$	5.6	2 $\frac{3}{16}$	5.6
Control Panel Height (C)	5 $\frac{5}{16}$	13.5	5 $\frac{5}{16}$	13.5
Door Height (D)	20 $\frac{11}{16}$	52.6	20 $\frac{11}{16}$	52.6
Door Bottom to Handle Top (E)	20	50.8	20	50.8
Toe-Kick Height (F)	5 $\frac{1}{2}$	14	5 $\frac{1}{2}$	14



FRONT VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

W11255637A

PV-ZI

July 13, 2021

Σ.6

DIMENSIONS


3 of 30

COMMERCIAL-STYLE RANGES

PRODUCT DIMENSIONS



MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J	
	in	cm	in	cm
Depth with Control Panel Overhang (G)	27 ³ / ₄	70.5	27 ³ / ₄	70.5
Depth with Handle (H)	30 ¹ / ₄	76.9	30 ¹ / ₄	76.9
Depth with Door Fully Open (I)	46 ¹ / ₂	118.1	46 ¹ / ₂	118.1



TOP VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-21

July 13 2021

1-6

DIMENSIONS

5 of 30


COMMERCIAL-STYLE RANGES

PRODUCT DIMENSIONS

*

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
	in	cm	in	cm	in	cm
Grates Top Height (A)	37 ³ / ₁₆	94.5	37 ³ / ₁₆	94.5	37 ³ / ₁₆	94.5
Cooking Surface Top Height (B)	36	91.4	36	91.4	36	91.4
Door Top Height (C)	27 ⁷ / ₁₆	70.8	27 ⁷ / ₁₆	70.8	27 ⁷ / ₁₆	70.8
Handle Top Height (D)	27 ⁷ / ₁₆	68.9	27 ⁷ / ₁₆	68.9	27 ⁷ / ₁₆	68.9
Toe-Kick Height (E)	6 ⁵ / ₁₆	16.9	6 ⁵ / ₁₆	16.9	6 ⁵ / ₁₆	16.9
OTHER DIMENSIONS						
Maximum Feet Extension Height*	1 ¹ / ₂	3.8	1 ¹ / ₂	3.8	1 ¹ / ₂	3.8

* IMPORTANT: Minimum height dimensions are at the lowest point of the height adjustment range. When the leveling legs are fully extended, all heights have 1¹/₂" (3.8 cm) of added height.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-Z1
July 13 2021

5.8

DIMENSIONS

6 of 30


COMMERCIAL-STYLE RANGES

PRODUCT DIMENSIONS



MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
	in	cm	in	cm	in	cm
Depth with Door Fully Open (F)	46½	118.1	46½	118.1	46½	118.1
Depth with Handle (G)	30¼	76.9	30¼	76.9	30¼	76.9
Depth with Control Panel Overhang (H)	27¾	70.5	27¾	70.5	27¾	70.5
Depth to Toe-Kick with Door (I)	27	68.6	27	68.6	27	68.6
Depth with Door (J)	27	68.6	27	68.6	27	68.6
OTHER DIMENSIONS						
Gas Vent Height (K)*	39	99.1	39	99.1	39	99.1

*Gas Units only: KFGC500J, KFGC506J and KFGC558J.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-21

July 13 2021

I-6

DIMENSIONS

COMMERCIAL-STYLE RANGES


7 of 30

OPENING/CLEARANCE DIMENSIONS

*

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
	in	cm	in	cm	in	cm
Combustible Area above Cooking Surface Width (min.) (A)	30	76.2	36	91.4	48	121.9
Bottom of Cabinet Height above Cooking Surface (min.) (B)*	42	106.7	58	147.3	58	147.3
Bottom of Cabinet Height above Countertop (min.) (C)	18	45.7	18	45.7	18	45.7
Distance to Fixed Wall or Combustible Material (min.) (D)	12	30.5	12	30.5	12	30.5
Opening Width (min.) (E)	30	76.2	36	91.4	48	121.9

* If installing a hood or hood liner above the range, follow the hood or hood liner instructions for dimensional clearances above the cooking surface.



FRONT VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-21

July 13 2021

5.6

DIMENSIONS

COMMERCIAL-STYLE RANGES

8 of 30


OPENING/CLEARANCE DIMENSIONS

*

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC566J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
	in	cm	in	cm	in	cm
Upper Cabinet Depth (max.) (F)	13	33	13	33	13	33
Depth from Wall to Grates (G)*	1½	3.9	1½	3.9	1½	3.9
Depth from Wall to back of Unit**	0	0	0	0	0	0

* If the back wall is constructed of a combustible material and a backsplash is not installed a 7½" (19.1 cm) minimum clearance is required.

** If the back wall is constructed of a combustible material and a backsplash is not installed a 6" (15.2 cm) minimum clearance is required.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-21

July 13 2021

5.9

DIMENSIONS

9 of 30

COMMERCIAL-STYLE RANGES


ELECTRICAL REQUIREMENTS

*

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
	in	cm	in	cm	in	cm
Electrical Zone Width (A)	22	55.9	28	71.1	40	101.6
Electrical Zone Height (B)	15	38.1	15	38.1	15	38.1
Electrical Zone Depth (C)	5	12.7	5	12.7	5	12.7


ELECTRIC REQUIREMENTS CHECKLIST	
☐	A 240 V, 60 Hz, fused, grounded circuit is required.
☐	For 30" (76.2 cm) and 36" (91.4 cm) ranges, use a 40 A circuit.
☐	For 48" (121.9 cm) ranges, use a 50 A circuit.
☐	A dedicated circuit is recommended.

RECOMMENDED ELECTRICAL ZONE



FRONT VIEW

WIDTH TO ELECTRICAL CONDUIT



BACK VIEW

NOTE: If you have questions about your electrical supply, call a licenced, qualified electrician.

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

PV-Z1

July 13 2021

5.9

DIMENSIONS

COMMERCIAL-STYLE RANGES


10 of 30

GAS REQUIREMENTS

*


MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J		48" (121.9 cm) RANGES DUAL-FUEL/GAS KFDC558J/KFGC558J	
	in	cm	in	cm	in	cm
Gas Opening Width (A)	6	15.2	14	35.6	24	61
Gas Opening Height (B)	3	7.6	3	7.6	3	7.6
Gas Opening Depth (C)	5	12.7	5	12.7	5	12.7
Distance from Side Cabinet to Gas Opening (D)	9	22.9	9	22.9	9	22.9
Width to Gas Inlet (E)	12 $\frac{3}{4}$	32.4	12 $\frac{3}{4}$	32.4	12 $\frac{3}{4}$	32.4

RECOMMENDED GAS ZONE



FRONT VIEW

WIDTH TO GAS INLET



BACK VIEW

NOTE: If you have questions about your gas supply, call a licenced, qualified service technician.

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®
W11255637A

PV-21
July 13 2021



KitchenAid®

→*
24" (61.0 CM) MICROWAVE DRAWER
INSTALLATION INSTRUCTIONS

INSTRUCTIONS D'INSTALLATION DU TIROIR À
MICRO-ONDES DE 24 PO (61,0 CM)

Table of Contents/Table des matières

MICROWAVE DRAWER SAFETY	2	SÉCURITÉ DU TIROIR À MICRO-ONDES	9
INSTALLATION REQUIREMENTS	3	EXIGENCES D'INSTALLATION	10
Tools and Parts	3	Outils et pièces	10
Location Requirements	3	Exigences d'emplacement	10
Minimum Dimensions	3	Dimensions minimales	10
Electrical Requirements	4	Spécifications électriques	11
24" (61.0 CM) STANDARD MOUNT	5	SUPPORT STANDARD DE 24 PO (61,0 CM)	11
Cabinet Preparation	5	Préparation de l'armoire	11
INSTALLATION INSTRUCTIONS	6	INSTRUCTIONS D'INSTALLATION	12
Install the Anti-Tip Block	6	Installation de la cale de bride anti-basculement	12
Install the Microwave Drawer	6	Installation du tiroir à micro-ondes	12
Complete Installation	7	Terminer l'installation	13
ASSISTANCE	7	ASSISTANCE	13

IMPORTANT:

Installer: Leave installation instructions with the homeowner.
Homeowner: Keep installation instructions for future reference.

IMPORTANT:

Save for local electrical inspector's use.

IMPORTANT :

Installateur : Remettre les instructions d'installation au propriétaire.
Propriétaire : Conserver les instructions d'installation pour référence ultérieure.

IMPORTANT :

À conserver pour consultation par l'inspecteur local des installations électriques.

PV-21

July 13 2021



INSTALLATION REQUIREMENTS

These installation instructions cover different models. The appearance of your particular model may differ slightly from the illustrations in these Installation Instructions.

Tools and Parts

Gather the required tools and parts before starting installation. Read and follow the instructions provided with any tools listed here.

Tools needed

- Tape measure
- 1/8" (3.17 mm) drill bit
- #2 Phillips screwdriver
- Marker or pencil
- Drill

Parts supplied

The Microwave Drawer is preassembled.

- 1" (2.5 cm) mounting screws (4)

Verification needed

- Installer must confirm presence of anti tip block. Refer to the anti-tip block section in the manual.
- Check local codes. Check existing electrical supply. See "Electrical Requirements".
- It is required that all electrical connections be made by a licensed, qualified electrical installer.

Location Requirements

This product is suitable for use below electric or gas built-in ovens. This product is not suitable for use below cooktops. The Microwave Drawer may be located in a cabinet or below the counter, and/or below a built-in oven. Check the opening where the Microwave Drawer will be installed. The location must provide:

IMPORTANT: Observe all governing codes and ordinances.


- Wood cabinetry.
- Cutout opening that is plumb and square. See "Minimum Cutout Dimensions" in the "Minimum Dimensions" section.
- Cutout floor that is solid, level, and flush with bottom of cabinet cutout.
- Support for weight of at least 100 lbs (45.4 kg), which includes Microwave Drawer and items placed inside.
- Grounded electrical outlet. See the "Electrical Requirements" section.
- Minimum installation clearances for installation location. See the "Minimum Dimensions" section.
- Complete enclosure around the recessed portion of the Microwave Drawer.

Minimum Dimensions

Minimum Wall Oven Combination Installation Clearances

For proper installation, the following minimum clearances must exist above and below the cutout opening.

NOTE : Upper oven must have heat deflector kit installed to direct exhaust away from microwave console (Refer to Wall Oven Manual for Deflector Kit Installation)



A. Upper oven cutout
B. Microwave drawer cutout

PV-21
July 13 2021

1.4

Electrical Requirements

⚠ WARNING



Electrical Shock Hazard

Plug into a grounded 3 prong outlet.
Do not remove ground prong.
Do not use an adapter.
Do not use an extension cord.
Failure to follow these instructions can result in death, fire, or electrical shock.

IMPORTANT: Observe all governing codes and ordinances.

Required:

- A 120 V, 60 Hz, AC-only, 15 or 20 A electrical supply with a fuse or circuit breaker.

Recommended:

- A time-delay fuse or time-delay circuit breaker
- A separate circuit serving only this Microwave Drawer

GROUNDING INSTRUCTIONS


- **For all cord connected appliances:**
The microwave oven must be grounded. In the event of an electrical short circuit, grounding reduces the risk of electric shock by providing an escape wire for the electric current. The microwave oven is equipped with a cord having a grounding wire with a grounding plug. The plug must be plugged into an outlet that is properly installed and grounded.

WARNING: Improper use of the grounding plug can result in a risk of electric shock. Consult a qualified electrician or serviceman if the grounding instructions are not completely understood, or if doubt exists as to whether the microwave oven is properly grounded.


Do not use an extension cord. If the power supply cord is too short, have a qualified electrician or serviceman install an outlet near the microwave oven. A short power supply cord is provided to reduce the risks resulting from becoming entangled in or tripping over a longer cord.

SAVE THESE INSTRUCTIONS

Product Dimensions



The drawer opens 15 1/4" (38.7 cm).



PV-21



July 13 2021

F.S.

24" (61.0 CM) STANDARD MOUNT

Cabinet Preparation

Cabinet Dimensions



- A. 6" (15.2 cm) minimum
16" (40.6 cm) maximum
- B. Suggested electrical receptacle location
- C. Anti-Tip block
- D. 3" (7.6 cm)
- E. 3 1/2" (8.9 cm)
- F. 4.5" (11.4 cm)
- G. 22 1/8" (61.4 cm) opening
- H. 14 13/16" (37.6 cm) to bottom of Anti-Tip block
- I. Allow 7/8" (2.2 cm) overlap
- J. 24" (61.0 cm) minimum depth
- K. Allow 1/16" (5.6 mm)
- L. Platform must support 100 lb (45.4 kg)
- M. 15 9/16" (39.5 cm) opening
- N. Allow 7/8" (1.9 cm) overlap
- O. 1 3/4" (3.9 cm)

PV-21

July 13 2021

IG

INSTALLATION INSTRUCTIONS

Install the Anti-Tip Block

⚠ WARNING



Crush Hazard

Microwave drawer can tip and fall out of opening.
Install anti-tip block to wall per installation instructions.
Failure to do so can result in serious injury or burns.


To reduce the risk of tipping of the drawer, the Anti-Tip block must be properly installed located $14\frac{13}{16}$ " (37.6 cm) above the floor on which the Microwave Drawer will sit. If the Microwave Drawer is ever moved to a different location, the Anti-Tip block must also be moved and installed.

1. Measure $14\frac{13}{16}$ " (37.6 cm) from the cutout floor where the Microwave Drawer will sit and mark a line on the wall.
2. Position the bottom of the anti-tip block on the line marked on the wall and attach the anti-tip block to the wall with screws. Make sure the screws are secured to wood or metal studs.

NOTES:

- The anti-tip block is required before installing the Microwave Oven Drawer.
- The anti-tip block is to be provided by the installer.
- When fastening, be sure that the screws do not penetrate electrical wiring or plumbing.

Anti-Tip Block Dimensions.



Using sturdy wood screws (installer to provide), securely install the anti-tip block in the upper-right corner of the cutout, making sure the block is completely stable. The bottom of the block must be $14\frac{13}{16}$ " (37.6 cm) from the cutout floor.

Install the Microwave Drawer

⚠ WARNING

Excessive Weight Hazard

Use two or more people to move and install microwave oven.

Failure to do so can result in back or other injury.

1. Empty Microwave Drawer of any loose contents.
2. Using two or more people, slide Microwave Drawer all the way into the opening, and center the Microwave Drawer.
3. Open the Microwave Drawer, and mark the four holes in the mounting flange.

NOTE: The screw holes in the mounting flange of both sides must be fully over the wood of the wall or cabinet.

4. Remove Microwave Drawer.
5. Using $\frac{1}{8}$ " (3.17 mm) drill, drill four pilot holes into the cabinet through the marks made in Step 3.
6. Prepare the holes by installing a 1" (2.5 cm) screw in and out of each pilot hole.

⚠ WARNING



Electrical Shock Hazard

Plug into a grounded 3 prong outlet.


Do not remove ground prong.

Do not use an adapter.

Do not use an extension cord.

Failure to follow these instructions can result in death, fire, or electrical shock.

7. With the Microwave Drawer near the opening, plug the Microwave Drawer into the grounded 3 prong outlet.
8. Reinsert Microwave Drawer into the opening, open the drawer, and align holes in mounting flange with pilot holes in the cabinet.



A. 1" (2.5 cm) mounting screws (4)

B. Mounting flange screw holes

C. Mounting flange

PV-21

July 13 2021

1.6

KitchenAid® French Door Bottom Mount Refrigerator

PRODUCT MODEL NUMBER:

KRFF507H

ELECTRICAL AND WATER REQUIREMENTS:

Electrical: A 115 volt, 60 Hz, AC only 15 or 20 A fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator and approved accessories be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

Water: A cold water supply with water pressure between 35 and 120 psi (241 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.



NOTE: If the water pressure is less than what is required, the flow of water from the water dispenser could decrease or ice cubes could be hollow or irregular shaped.

Reverse Osmosis Water Supply

IMPORTANT: The pressure of the water supply coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 35 and 120 psi (241 and 827 kPa).


If a reverse osmosis water filtration system is connected to your cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).

PRODUCT DIMENSIONS:



Model Number	KRFF507H
Model Size	27 cu. ft. (764.6 L)
Height - Overall "A"	70 1/8" (178.1 cm)
Height - Top of Cabinet "B"	68 3/4" (174.8 cm)
Depth - Doors Open 90° "C"	48 5/8" (123.5 cm)
Depth - Drawer Open With Handles "D"	54 1/4" (137.8 cm)
Depth - With Handles "E"	36" (91.4 cm)
Depth - Without Handles "F"	33 3/4" (85.7 cm)
Depth - Cabinet Only "G"	29 5/8" (75.2 cm)
Width - Cabinet Only "H"	35 1/8" (90.5 cm)
Width - Doors Open 90° "I"	38 3/4" (97.5 cm)

LOCATION REQUIREMENTS:



To ensure proper ventilation for your refrigerator, allow for a 1/2" (1.25 cm) of space on each side and at the top. Allow for a 1" (2.54 cm) space behind the refrigerator. If your refrigerator has an ice maker, allow extra space at the back for the water line connections. When installing your refrigerator next to a fixed wall, leave a 3 3/4" (9.5 cm) minimum space between the refrigerator and wall to allow the door to swing open.

NOTE: This refrigerator is intended for use in a location where the temperature ranges from a minimum of 55°F (13°C) to a maximum of 110°F (43°C). The preferred room temperature range for optimum performance, which reduces electricity usage and provides superior cooling, is between 60°F (15°C) and 90°F (32°C). It is recommended that you do not install the refrigerator near a heat source, such as an oven or radiator.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.



Ref. W11218735A
03/18

KitchenAid
Model # KDTM604 KPS

PV-21
July 13 2021


56

PRODUCT AND CABINET OPENING DIMENSIONS:



- A. Insulation may be compressed (not used on all models).
 B. For panel-ready models, dishwasher depth is $24"$ (61.0 cm), not including the $\frac{3}{4}"$ (1.9 cm) custom door panel.
 C. Door handles may protrude forward of the face of the dishwasher, varies by model.

Check that all surfaces have no protrusions that would prohibit dishwasher installation.



- D. Measured from the lowest point on the underside of the countertop. May be reduced to $33\frac{5}{8}"$ min. (85.4 cm) min. by removing the feet and perforated area of insulation (blanket) on dishwasher.
 E. Minimum, measured from narrowest point of opening.