

Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

APPLIA	CES	
Invoice	ty. Description	

1930	3	KITCHEN APPLIANCES - SEE ATTACHED SIGNED SPECIFICATIONS
72,351		
14SEP21		

BASEMENT WINDOWS

Invoice	Qt	ty.	Description
1930	3	3	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME
72,351			
21Oct20			

CERAMIC

Invoice	Qty.	Description
2529	1	MASTER ENSUITE: SHOWER NICHE [SHAMPOO SHELF] - COMPLETE WITH MATCHING MARBLE JAMBS ON 4 SIDES, STANDARD TILE, APPROX. 12 X 18 INSTALLED VERTICALLY - SEE PLAN FOR LOCATION
13Jan21 NoCat		
2896 43 10Sep21	1	MASTER ENSUITE: TILE, SHOWER FLOOR, LEVEL 2 - HEX
2896 20 10Sep21	1	MASTER ENSUITE: TILE GROUT UPGRADE, SHOWER FLOOR, UPG GROUT

CONCRETE AND DRAIN

Invoice	Qty.	Description
1930	1	BACK-FLOW PREVENTER VALVE
21Oct20		
NoCat		

CROWN MOULDING

Invoice	Qty.	Description
2529	1	GREAT ROOM: MODEL OPTIONS 40.03 - GREAT ROOM - OPT. WAFFLE CEILING , BEAM DETAIL AS PER PLAN (6 BOXES) OPTION # 1 CTR-B07
13Jan21 NoCat		
2529	1	STUDY: MODEL OPTIONS 40.03 - STUDY- OPT. WAFFLE CEILING , BEAM DETAIL AS PER PLAN (4 BOXES) OPTION # 1 CTR-B07
13Jan21 NoCat		

DisciplineMS.rpt 23feb21 Page 1 of 10



Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

DRYWALL

Invoice	Qty.	Description
1930 72,351 21Oct20 **	3	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME
2529 72,398 13Jan21	1	GREAT ROOM: MODEL OPTIONS 40.03 - GREAT ROOM - OPT. COFFERED CEILING AS PER PLAN
2529 72,397 13Jan21	1	GREAT ROOM: MODEL OPTIONS 40.03 - GREAT ROOM - OPT. WAFFLE CEILING , BEAM DETAIL AS PER PLAN (6 BOXES) OPTION # 1 CTR-B07
2529 72,401 13Jan21	1	STUDY: MODEL OPTIONS 40.03 - STUDY - OPT. COFFERED CEILING AS PER PLAN
2529 72,400 13Jan21	1	STUDY: MODEL OPTIONS 40.03 - STUDY- OPT. WAFFLE CEILING , BEAM DETAIL AS PER PLAN (4 BOXES) OPTION # 1 CTR-B07
2529 72,401 13Jan21	1	MAIN HALL: MODEL OPTIONS 40.03 - OPT. COFFERED CEILING AS PER PLAN
2529 13Jan21 NoCat	1	STUDY: MODEL OPTIONS 40.03 - STUDY - OPT. 8 FOOT HIGH DOUBLE FRENCH DOORS WITH FLAT CLEAR GLASS COMPLETE WITH BUILDERS STANDARD OFFERINGS
2529 13Jan21 NoCat	1	MASTER ENSUITE: SHOWER NICHE [SHAMPOO SHELF] - COMPLETE WITH MATCHING MARBLE JAMBS ON 4 SIDES, STANDARD TILE, APPROX. 12 X 18 INSTALLED VERTICALLY - SEE PLAN FOR LOCATION
2529 13Jan21 NoCat	1	THRU OUT 2ND FLOOR: INCREASE HEIGHT OF DOOR TO 8FT SECOND FLOOR - PER DOOR
2529 13Jan21 NoCat	1	BREAKFAST: UPGRADE TO 96" FRENCH DOOR ASSEMBLY

DisciplineMS.rpt 23feb21 Page 2 of 10 Printed and Sent: 14-Sep-21



Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

ELECTRICAL

Invoice Qty. Description				
1930 72,351 21Oct20 **	3	BASEMENT WINDOWS - UPGRADE BASEMENT WINDOW SIZE TO 30 " X 24" - 8" FRAME		
2529 72,281 13Jan21	1	GREAT ROOM: INTERIOR WALL OUTLET: ADDITIONAL 110V WALL INTERIOR RECEPTACLE ON EXISTING CIRCUIT FOR WALL MOUNTED TV - LOCATE APPROX 66" A.F.F. ABOVE FIREPLACE		
2529 72,289 13Jan21	6	GREAT ROOM: 4" E/S LED INTERIOR POT LIGHT - GROUND FLOOR - EACH - USE STANDARD SWITCH INCLUDED IN APS		
2529 72,307 13Jan21	1	KITCHEN: FIXTURE: RELOCATE STANDARD CEILING MOUNT FIXTURE - LOCATE APPROX CENTERED ABOVE ISLAND - SEE PLAN FOR LOCATION		
2529 72,280 13Jan21	1	KITCHEN: CEILING OUTLET: ADDITIONAL REINFORCED CEILING OUTLET - LOCATE APPROX CENTERED ABOVE ISLAND - SEE PLAN FOR LOCATION USE SAME SWITCH AS STANDARD		
2529 72,303 13Jan21	1	KITCHEN: FIXTURE: UNDER CABINET FLUORESCENT LIGHT FIXTURES - DOES NOT INCLUDE (AND REQUIRES) LIGHT VALANCE		
2529 72,289 13Jan21	7	KITCHEN: 4" E/S LED INTERIOR POT LIGHT - GROUND FLOOR - EACH		
2529 72,278 13Jan21	1	KITCHEN: ADDITIONAL INTERIOR SWITCH FOR POTLIGHTS		
2529 72,282 13Jan21	1	KITCHEN: ADDITIONAL 220V RECEPTACLE ON A SEPARATE CIRCUIT - FOR BUILT-IN WALL OVEN - APPLIANCE NOT INCLUDED - DOES NOT INCLUDE BREAKER THAT IS TO BE INSTALLED BY LICENSED ELECTRICIAN AND ARRANGED BY HOMEOWNER AFTER CLOSING		
2529 72,273 13Jan21	1	KITCHEN: 110V WALL RECEPTACLE ON SEPARATE CIRCUIT - GAS FIRED COOKTOP - FOR AUX. EQUIPMENT - NOT A STOVE PLUG		
2529 72,289 13Jan21	4	BREAKFAST: 4" E/S LED INTERIOR POT LIGHT - GROUND FLOOR - EACH - SEE PLAN FOR LOCATION		
2529 72,278 13Jan21	1	BREAKFAST: ADDITIONAL INTERIOR SWITCH FOR POTLIGHTS		
2529 72,289 13Jan21	4	DINING ROOM: 4" E/S LED INTERIOR POT LIGHT - GROUND FLOOR - EACH SEE PLAN FOR LOCATION		

DisciplineMS.rpt 23feb21

Page 3 of 10



Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

ELECTRICAL

Invoice	Qty.	Description
2529 72,289	4	STUDY: 4" E/S LED INTERIOR POT LIGHT - GROUND FLOOR - EACH - SEE PLAN FOR LOCATION
13Jan21		USE STANDARD SWITCH
2529 72,290	6	UPPER HALL: 4" E/S LED INTERIOR POT LIGHT (INSULATED CEILING) - SECOND FLOOR - EACH
13Jan21		USE STANDARD SWITCHES
2529 72,280 13Jan21	1	MASTER ENSUITE: CEILING OUTLET: ADDITIONAL REINFORCED CEILING OUTLET - USE SAME SWITCH AS VANITY LIGHTS
2529 72,288	2	MASTER ENSUITE: ROUGH-IN FOR ADDITIONAL WALL SCONCE (1) CAPPED OUTLET ON EXISTING SWITCH - FIXTURE NOT INCLUDED
13Jan21		SAME HEIGHT AND SWITCH AS STANDARD VANITY LIGHT
2529 72,278	1	DINING ROOM: ADDITIONAL INTERIOR SWITCH
13Jan21		FOR POTLIGHTS
2529 72,289	6	MAIN HALL: 4" E/S LED INTERIOR POT LIGHT - GROUND FLOOR - EACH
13Jan21		
2529 72,290	4	MASTER BEDROOM: 4" E/S LED INTERIOR POT LIGHT (INSULATED CEILING) - SECOND FLOOR - EACH
13Jan21		SEE PLAN FOR LOCATION
2529 72,278	1	MASTER BEDROOM: ADDITIONAL INTERIOR SWITCH
13Jan21		FOR POTLIGHTS
2896	1	KITCHEN: UPGRADE TO QUARTZ FULL HEIGHT KITCHEN BACKSPLASH - LEVEL 2
10Sep21 NoCat		

DisciplineMS.rpt 23feb21 Page 4 of 10 Printed and Sent: 14-Sep-21



Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

FRAMING

Invoice	Qty.	Description
2529 72,631 13Jan21	1	MASTER ENSUITE: SHOWER NICHE [SHAMPOO SHELF] - COMPLETE WITH MATCHING MARBLE JAMBS ON 4 SIDES, STANDARD TILE, APPROX. 12 X 18 INSTALLED VERTICALLY - SEE PLAN FOR LOCATION
2529	1	GREAT ROOM: MODEL OPTIONS 40.03 - GREAT ROOM - OPT. COFFERED CEILING AS PER PLAN
13Jan21 NoCat		
2529	1	GREAT ROOM: MODEL OPTIONS 40.03 - GREAT ROOM - OPT. WAFFLE CEILING , BEAM DETAIL AS PER PLAN (6 BOXES) OPTION # 1 CTR-B07
13Jan21 NoCat		
2529	1	MASTER BEDROOM: MODEL OPTIONS 40.03 - MASTER BEDROOM - OPT. 10 FOOT TRAY CEILING
13Jan21 NoCat		
2529	1	STUDY: MODEL OPTIONS 40.03 - STUDY - OPT. COFFERED CEILING AS PER PLAN
13Jan21 NoCat		
2529	1	STUDY: MODEL OPTIONS 40.03 - STUDY- OPT. WAFFLE CEILING , BEAM DETAIL AS PER PLAN (4 BOXES) OPTION # 1 CTR-B07
13Jan21 NoCat		
2529	1	STUDY: MODEL OPTIONS 40.03 - STUDY - OPT. COFFERED CEILING AS PER PLAN
13Jan21 NoCat		
2529	1	STUDY: MODEL OPTIONS 40.03 - STUDY - OPT. 8 FOOT HIGH DOUBLE FRENCH DOORS WITH FLAT CLEAR GLASS COMPLETE WITH BUILDERS STANDARD OFFERINGS
13Jan21 NoCat		
2529	1	THRU OUT 2ND FLOOR: INCREASE HEIGHT OF DOOR TO 8FT SECOND FLOOR - PER DOOR
13Jan21 NoCat		
2529	1	BREAKFAST: UPGRADE TO 96" FRENCH DOOR ASSEMBLY
13Jan21 NoCat		

GLASS AND MIRROR

GLINDS			
Invoice	Qty.	Description	
2896	1	MASTER ENSUITE: UPGRADE SHOWER DOOR HANDLE	
10Sep21 NoCat			
2896	1	SHARED ENSUITE: UPGRADE SHOWER DOOR HANDLE	
10Sep21			

DisciplineMS.rpt 23feb21 Page 5 of 10



Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

GRANITE MARBLE QUARTZ

Invoice	Qty.	Description
2896	1	KITCHEN: UPGRADE QUARTZ COUNTERTOP - LEVEL 2
10Sep21 NoCat		
2896 75,834 10Sep21	2	KITCHEN: QUARTZ, 48" WATERFALL LEG (PRICE PER LEG) - LEVEL 2
2896 78,974 10Sep21	1	KITCHEN: UPGRADE TO QUARTZ FULL HEIGHT KITCHEN BACKSPLASH - LEVEL 2
2896	1	KITCHEN: COOKTOP CUT OUT
10Sep21 NoCat		

HARDWOOD

Invoice	Qty.	Description
2901 1	_	**CHANGE FROM TILE ON ORIGINAL ORDER PE #2896** KITCHEN/BREAKFAST - MIRAGE, 3 5/16" RED OAK, TRUE BALANCE ENGINEERED HARDWOOD, 3/4", ADMIRATION TEXTURE CASHMERE FINISH
14Sep21		**PRICE INCLUDES CABINETRY ADJUSTMENT**

HVAC

Invoice	Qty.	Description
2529	1	KITCHEN: GAS LINE ROUGH-IN - MAIN FLOOR FOR GAS COOKTOP
72,224		
13Jan21		

INTERIOR TRIM AND DOORS

Invoice	Qty.	Description
2529 72,402 13Jan21	1	STUDY: MODEL OPTIONS 40.03 - STUDY - OPT. 8 FOOT HIGH DOUBLE FRENCH DOORS WITH FLAT CLEAR GLASS COMPLETE WITH BUILDERS STANDARD OFFERINGS
2529 72,644 13Jan21	16	THRU OUT 2ND FLOOR: INCREASE HEIGHT OF DOOR TO 8FT SECOND FLOOR - PER DOOR

DisciplineMS.rpt 23feb21 Page 6 of 10



Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

KITCHEN AND BATH CABINETRY

Invoice	Qty.	Description
2529	1	KITCHEN: GAS LINE ROUGH-IN - MAIN FLOOR FOR GAS COOKTOP
13Jan21 NoCat		
2896	1	THRU OUT: SEE ATTACHED CABINETRY SCHEDULE
10Sep21 NoCat		

NETWORK AND WIRING

Invoice	Qty.	Description
2529 72,258 13Jan21	1	GREAT ROOM: ADDITIONAL CAT6 ETHERNET OUTLET - EACH SEE PLAN FOR LOCATION
2529 72,259 13Jan21	1	GREAT ROOM: CONDUIT PIPE - FOR WALL MOUNT TV - LOCATE APPROX 66" A.F.F. ABOVE FIREPLACE TERMINATING AT CABLE LOCATION

DisciplineMS.rpt 23feb21 Page 7 of 10



Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

D A		NT
\mathbf{F}	М	

Invoice	Qty.	Description
2529	1	GREAT ROOM: MODEL OPTIONS 40.03 - GREAT ROOM - OPT. COFFERED CEILING AS PER PLAN
13Jan21 NoCat		
2529	1	GREAT ROOM: MODEL OPTIONS 40.03 - GREAT ROOM - OPT. WAFFLE CEILING , BEAM DETAIL AS PER PLAN (6 BOXES) OPTION # 1 CTR-B07
13Jan21 NoCat		
2529	1	MASTER BEDROOM: MODEL OPTIONS 40.03 - MASTER BEDROOM - OPT. 10 FOOT TRAY CEILING
13Jan21 NoCat		
2529	1	STUDY: MODEL OPTIONS 40.03 - STUDY - OPT. COFFERED CEILING AS PER PLAN
13Jan21 NoCat		
2529	1	STUDY: MODEL OPTIONS 40.03 - STUDY- OPT. WAFFLE CEILING , BEAM DETAIL AS PER PLAN (4 BOXES) OPTION # 1 CTR-B07
13Jan21 NoCat		
2529	1	STUDY: MODEL OPTIONS 40.03 - STUDY - OPT. COFFERED CEILING AS PER PLAN
13Jan21 NoCat		
2529	1	STUDY: MODEL OPTIONS 40.03 - STUDY - OPT. 8 FOOT HIGH DOUBLE FRENCH DOORS WITH FLAT CLEAR GLASS COMPLETE WITH BUILDERS STANDARD OFFERINGS
13Jan21 NoCat		
2529	1	THRU OUT 2ND FLOOR: INCREASE HEIGHT OF DOOR TO 8FT SECOND FLOOR - PER DOOR
13Jan21 NoCat		
2529	1	BREAKFAST: UPGRADE TO 96" FRENCH DOOR ASSEMBLY
13Jan21 NoCat		
2896	2	MAIN STAIRS - 2ND FLOOR TO BASEMENT: STAIN STAIRS AND LANDINGS
10Sep21 NoCat		WILL NOT MATCH HARDWOOD IN COLOUR, SPECIES, OR TEXTURE

DisciplineMS.rpt 23feb21 Page 8 of 10 Printed and Sent: 14-Sep-21



Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

PLUMBING					
Invoice Qty. Description					
2529 72,332 13Jan21	1	KITCHEN: ROUGH-IN 1/4" COLD WATER LINE TO FRIDGE			
2529 72,346 13Jan21	1	KITCHEN: MOEN 'MODERN' POT FILLER - BRUSHED GOLD INCLUDES ROUGH IN			
2529 13Jan21 NoCat	1	MASTER ENSUITE: UPGRADE TO MOEN 'ALIGN' RAIN SHOWER (from ceiling) + HAND SHOWER w/SLIDE BAR - CHROME			
2896 75,857 10Sep21	1	KITCHEN: UPGRADE MOEN MODERN POT FILLER - MATTE BLACK **in lieu of BRUSHED GOLD ON PE#2529**			
2896 10Sep21 NoCat	1	KITCHEN: UPGRADE SINK - SUPER SINGLE, STAINLESS			
2896 10Sep21	1	KITCHEN: UPGRADE FAUCET - MOEN SLEEK - MATTE BLACK			

STAIR AND RAILINGS

SIAIN	STAIR AND RAILINGS				
Invoice	Qty.	Description			
2896 93,782 10Sep21	_	MAIN STAIRS: UPGRADE - EURONLINE (ALL PLAIN) PICKET, 3" HALF-ROUND W/V-GROOVE HANDRAIL, 3 1/2" ALL SQUARE POST WITH PYRAMID TOP POST CAP - PACKAGE A-2			

DisciplineMS.rpt 23feb21 Page 9 of 10



Lot: 5

Model: 40.03 B BROOKSIDE

Project/Phase: Pine Valley Forevergreen / 1

WINDOWS AND DOORS


Invoice	Qty.	Description
2529	1	BREAKFAST: UPGRADE TO 96" FRENCH DOOR ASSEMBLY
13Jan21		
NoCat		

DisciplineMS.rpt 23feb21 Page 10 of 10

Decor Advisor: Yolan	NIFER LITTLEJOHN & AD, 760-9595 nde Somerville	INTERIOR COLOUR SCHEME of an approved document. Document m Scheduled Closing Date: PAM JOSHUA LITT Property: 5 of Plan - Project: Pine Valley Foreverg Model and Elevation: 40.03 B BROOKSID	reen - Phase 1
Layout Changes: O Yes	No Sketch Attach	hed: Yes No Exterior Colour Scheme:	for the desire of the second second second second
1. Cabinetry —	Style and Colour	Counter	· L
Kitchen / Breakfast	*Medio 'Fog'	*Quartz: 'Organic White'	Hardware
Laundry Room	n/a	n/a	attched
Powder Room	Tribecca 'Timber'	Quartz: 'Nordic Loft'	n/a
Mud Room	Tribecca 'Timber'	P-Lam: 'White'	attched
Master Ensuite Bathroom	Tribecca 'Timber'		attched
Second Ensuite		Quartz: 'Nordic Loft'	attched
Bathroom (If Applicable)	Bowery 'Ello'	Quartz: 'Ice Snow'	attched
Shared Ensuite	Bowery 'Ello'		Jauched
Comment	Dowery Ello	Quartz: 'Ice Snow'	attched
Entrance Vestibule Main Hall	Selection 13x13" Capri "White" n/a	arthur	
	the same of the sa		
Kitchen / Breakfast	13x13" Capri White' 5	SEE HARDWOOD	
Laundry Room	n/a	300-100-100-100-100-100-100-100-100-100-	
Powder Room Mud Room	13x13" Capri 'White'	150	
Master Ensuite	13x13" Capri 'White'		
Bathroom	13x13" Capri 'White'		
(A. A. A. Philodolo)	13x13" Costa 'White'		
Lower Landing (If Applicable)	13x13" Capri 'White'		
Shared Ensuite	13x13" Costa 'White'		
	ebec HEX. 'Dark Grey' + Grout: 'F	Pewter Grey' / Shared Ensuite Shower Floor: 2x2" Standard "V	Vhite'
Wall Tile —	Selection	Listello/Inserts Describe	
Shared Ensuite Master Ensuite Bathroom Tub Deck	8x10" Splendour 'White'	○ Yes ● No	
	8x10" Weave 'Tender Gr	O Yes No	
Bathroom Walls	The frequency of the first of t	rey' Yes No Yes No	
Second Ensuite	8x10" Splendour 'White'		
Bathroom (If Applicable)	OX 10 Objetidont Avuite.	Yes No	
	-	○ Yes No	
Kitchen Backenlach	A 1/2- C 11		
Kitchen Backsplash Comment	Yes No *FHBS slab - same as co	Backsplash Behind Fridge	

GOLDPARK INTERIOR COLOUR SCHEME *** NOTE: This is not an approved document. Document must be locked *** Scheduled Closing Date: JENNIFER LITTLEJOHN & ADAM JOSHUA LITT Property: 5 of Plan -Purchasers: Telephone Res. / Bus: (905) 760-9595 Project: Pine Valley Forevergreen - Phase 1 Decor Advisor: Yolande Somerville Model and Elevation: 40.03 B BROOKSIDE 4. Plumbing Fixtures Second Ensuite Powder Room Master Ensuite Bathroom Other Room - Specify Other Washroom Comment See extras *REVISED * 5. Hardwood Flooring Type and Stain Type and Stain Main Hall **Upper Landing** Kitchen / Breakfast 3/4x35/16" Red Oak, Smooth, Rio Upper Hall Living Room Master Bedroom **Dining Room** Bedroom #2 Family Room Bedroom #3 Den/Library Bedroom #4 **Entrance Vestibule** Bedroom #5 Lower Landing Other Room - Specify (If Applicable) *3/4x3-5/16" RedOak,Smooth,Rio Thru out standard areas Comment 6. Carpeting Upgrade Description **Ground Floor** Second Floor Type Upgrade Underpad Capped Runner - *Upgrade Carpet on Stairs Comment 7. Fireplace Living Room Family Room Other Room - Specify Great Room Purchased As Per Plan NA Purchased As Per Plan N/A Purchased As Per Plan N/A 0 0 \bigcirc \bigcirc Fireplace Type Standard Gas Mantle Type Mediterranean Colour / Stain Arctic White Surround n/a Hearth none Comment


GOLDPARI	K	INTERIOR COLOUR SCH	HEME		·
WORTH MC	ore " NOTE: This is not a	an approved documen	t. Docum	ent must b	e locked *
Purchasers: Ji	. 5	cheduled Closing Date:			
Telephone Res. / Bus: (9	ENNIFER LITTLEJOHN & ADAM 205) 760-9595				
	olande Somerville			revergreen - F	hase 1
	SIGNIGO COMO VINO	Model and Elevation: 40	.03 B BRO	OKSIDE	
8. Trim Carpentry	The state of the s				
Interior Doors Carrara	Front Door Glass	s Inserts standard	Door Hand	fles Standard	
Interior Trim Standa				ind <u>Plandard</u>	(0-m)
Comment	A CONTRACTOR OF THE CONTRACTOR				
				-	9-
:		Total Control of Contr			
O Dioctor Mandata					
9. Plaster Moulding		yr.			
Standard Throughout	○ Yes ○ No ○ N/A		100		
Entrance Vestibule		Kitchen/Breakfast			
Main Hall		Den/Library		_	
Living Room		Lower Landing			
Dining Room		Other Room - Specify			
Family Room			L		
Comment	Market State of the Control of the C				
				,	1
			9		
10. Railings and Spir	ndles				
Railing Package Package	A-2				
Railing Colour *Rio		Spindle Colour	*Black		
Stringer / Riser *Rio		Treads	*Rio		
Comment		Oak Stairs	Yes	O No (O N/A
The state of the s					
	The state of the s				
1. Wall Paint / Ceilin	, , , , , , , , , , , , , , , , , , ,				
Throughout Finished Are			The same of the sa		
		•			
Trim Paint White					
Smooth Ceilings					
Ground Floor	7				
Second Floor					
Note					





Comment

GOLDPARK	*** NOTF: This is no	INTERIOR COLOUR SCHEME	
WOKIH MORE	1101211111515110	ot an approved document. Document must be lo Scheduled Closing Date:	cked
Purchasers: JEN	INIFER LITTLEJOHN & AD	AM JOSHUA LITT Property: 5 of Plan -	
relephone Res. / Bus: (908	5) 760-9595	Project: Pine Valley Forevergreen - Phas	e 1
Decor Advisor: Yola	inde Somerville	Model and Elevation: 40.03 B BROOKSIDE	•
12. Electrical			
Hood Fan	O Stainless O N/A	Above Kitchen Cabinet Light O Yes	- A
		Below Kitchen Cabinet Light Yes	
Standard Appliances		165	, O IV
Over The Range Microwa	ive		
Chimney Style Fan			
Comment	-		
13. Heating and Air Co	onditioning		
Air Conditioning	none	Gas Provisions Stove yes	
Gas Provisions Dryer	none	Gas Provisions Barbecue standard	
Comment		Contraction of Contra	
7.00 (10.00)		:	
4. Additional Comme	nts		
		-	
		9	
-			
. Disclaimers and No	tes-	AND SPACE SPACE	
		· · · · · · · · · · · · · · · · · · ·	
2) Any extras listed above are null a	and void unless accompanied by a	ion, but not necessarily identical due to variances in manufacturing. separate invoice/amendment. Said invoice must be paid in full.	
o) The Purchaser acknowledges the	at after Interior Colour Selection for	orm is signed and dated, no further changes will be	
	,	s Initials rk Homes Decor Centre Disclaimers" form. This document contains	
his Interior Colour Selection is fir		Sontains	
O Section is in	and approved by:		
Signature:	Date:		
DIS		7 2001	
Printed 9/7/2021 12:53:48	ataphed sept.	3,2011 Page 4 c	of 4
mnteg 9///2021 12:53:48			



VENDOR **PURCHASER** PURCHASER

Prices, figures, illustrations, sizes, features and finishes notice, rigures, inustrations, sizes, reatures and finishes are subject to thorige without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 4003





०० १९ ३३ 12 202

The Brookside


40' SERIES

Elevation A • 3,380 sq.ft. Elevation B • 3,350 sq.ft.





ce. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 4003




The Brookside

40' SERIES

Elevation A • 3,380 sq.ft. Elevation B • 3,350 sq.ft.

74×30"



BASEMENT | ELEV. A

VENDOR PURCHASER PURCHASER

GOLDPARK

WORTH MORE

Prices, figures, illustrations, sizes, features and finishes are subject to change without notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased. E. & O.E. 4003




PV-5 Oct 19 226 Dec 12 222 Sept. 7, 204 90 12


The Brookside

40' SERIES


Elevation A • 3,380 sq.ft. Elevation B • 3,350 sq.ft.


Sept. 13, 2021





PART, OPT, GROUND FLOOR W/ OPT, SIDE ENTRANCE | ELEV. A (ELEV. B SIMILAR)





VENDOR
PURCHASER
PURCHASER

GOLDPARK

WORTH MORE

notice. Areas and dimensions are approximate and actual usable floor space may vary from the stated area. Layout may be reverse of the unit purchased, E. & O.E. 4003

GOLDPARK		INTERIOR COLOUR SCHEME	
WORDS MORE	NOTE: This is not	an approved document. Document	t must be locked *
Purchasers; JEN	NIFER LITTLEJOHN & ADA	Scheduled Closing Date: M JOSHUA LITI Property: 5 of Plan -	
Telephone Res. / Bus: (905	760-9595		
t de	nde Somerville	Project: Pine Valley Forev	ergreen - Phase 1
Layout Changes: O Yes	-	Model and Elevation: 40.03 B BROOKS	NOE
1. Cabinetry —		d: Yes No Exterior Colour Scher	ner[
Kitchen / Breakfast	Style and Colour	Counter	
	'Medio 'Fog'	Quartz 'Organic V/hite'	Hardware
Laundry Room	n/a	Wa	
Powder Room	Tribecca Timber	Quartz: Nordic Loft	n/a
Mud Room	Tribecca 'Timber'	P-Lam: White'	
Master Ensuite Bathroom	Habana Maria		attched
P. C.	Tribecca Timber	Quartz: "Nordic Loft"	attched
Second Ensuite Bathroom (if Applicable)	Bowery "Ello"	16	
		Quartz "Ice Snow	attched
Shared Ensuite	Bowery 'Ello'	Quartz: 'Ice Snow'	T
Comment			attched
	400	VISEN	
	\\C	VISED #	
	Sept	.13, 2021	
2. Floor Tile		9100	
	Selection	90-2	
Entrance Vestibule	13x13" Capri White'		
Main.Hall	n/a		
Kitchen / Breakfast	13x13"-Capri-White SF	E HARDWOOD	
Laundry Room	n/a	- 11112	
Powder Room	13x13" Capri White'		
Mud Room	(13x13" Capri "White"		
Master Ensuite	13x13" Capri White'		
Bathroom	Lox 19 Cabu Mute.		
Second Ensuite	13x13" Costa White'		
Bathroom (If Applicable)	The state of the s		
Lower Landing (if Applicable)	13x13" Capri White'		-
Shared Ensuite	13x13" Costa "White'		
Comment			
Master Ensuite Shower Floor: "2" Q	uebec HEX. Dark Grey + Grout Te	what Grey / Shared Ensuite Shower Floor: 242" Standar	d White
MET CONTRACTOR			
10/-11 77/			
3. Wall Tile —	Selection	Listello/inserts Describe	***************************************
Shared Ensuite	8x10" Splendour 'White'	O Yes O No	
Master Ensulte Bathroom			
Tub Dec		O Yes O No	
	II 8x10° Weave Tender Grey		
Bathroom Wal	5	O Yes No	
Second Ensuite Bathroom (If Applicable)	lix10" Splendour 'White'	O Yes O No	
1			-
Kitchen Backsplash	0.4-0.11	O Yes No	
	Yes O No	Backsplash Behind Fridge	
Comment	FHBS slab - same as cou	Inter	LEW ZYN
			O ANI
			20) (18)
			XW MI


GOLDPARI	(INTERIOR COLOUR S	CHEME
WORTH MO	NOTE: This is n	ot an approved docume	ent. Document must be locked ***
Purchasers: JF		ocheduled Closing Date:	
Telephone Res. / Bus: (9	OST TENLOSOS	DAM JOSHUA LITT Property:	
	olande Somerville	Model and Clausters	Pine Valley Forevergreen - Phase 1
		Model and Elevation:	40.03 B BROOKSIDE
4. Plumbing Fixture			
Master Ensuite Bathro	Second		Powder Room
	Other Ro	oom - Specify	Other Washroom
See extras	*REVISED #		
	PV-5		
L -	Sipt-13, 2021		
5. Hardwood Flooring	940.2		
	a and Stain		
Main Hall		Upper Landing	Type and Stain
Kitchen / Breakfast 31	4x35114 PodOak, Smrt	h Rin Upper Hall	
Living Room		Master Bedroom	
Dining Room Family Room		Bedroom #2	
Den/Library		Bedroom #3	
Entrance Vestibule		Bedroom #4	
Lower Landing		Bedroom #5	
(If Applicable)		Other Room - Specify Thru out standard area	73/4x3-5/16* Red Oak, Smooth, Rio
Comment			
			The state of the s
6. Carpeting	Upgrade Description		
Ground Floor	Opgrade Description		
Second Floor			
	Туре	Area	
Upgrade Underpad			
Carpet on Stairs	Capped	Runner - "U	pgrade
Comment			
7. Fireplace			
Living Re		Family Room Purchased As PerPlin NIA	Other Room - Specify Great Room
0		O O O	Puthased As Pur Plan NO.
Fireplace Type			Standard Gas
Mantle Type Colour / Stain			Mediterranean
Surround			Arctic White
Hearth			h/a
Comment	No. of the last of		none
		· · · · · · · · · · · · · · · · · · ·	
			600

001001-	
GOLDPARK	ERIOR COLOUR SCHEME
WORTH MORE NOTE: This is not an a	pproved document. Document must be locked
Sche	Med Closing Date:
THE STATE OF THE S	SHUA LITT Property: 5 of Plan-
rerephotie Res. / Bus: (905) 760-9595	Project: Pine Valley Forevergreen - Phase 1
Decor Advisor: Yolande Somerville Mo	odel and Elevation: 40.03 B BROOKSIDE
8. Trim Carpentry	
Interior Doors Carrara Front Door Glass Ins Interior Trim Standard	erts Standard Door Handles Standard
Comment	
Plaster Mouldings and Medallions	
Standard Throughout O Yes O No O N/A	
Entrance Vestibule K	Glchen/Breakfast
Main Hall D	Pen/Library
Living Room	ower Landing
Dining Room C	ther Room - Specify
Family Room	
Comment	
10 P-11	
10. Railings and Spindles	
Railing Package Package A-2	
Railing Colour (Rio	Spindle Colour Black
Stringer / Riser Rio	Treads Rio
Comment	Oak Stairs Yes O No O NVA
d Well put a to an	
1. Wall Paint / Ceilings	
Throughout Finished Areas Warm Grey	
Trim Paint White	- Walter - Company of the Company of
stant and write	
Smooth Cellings	
Ground Floor	
Ground Floor Second Floor	
Note	
Comment	

Page 3 of 4

Printed 9/7/2021 12:53:48

COLDRADIA	
GOLDPARK	INTERIOR COLOUR SCHEME
WORTH MORE TO NOTE: TH	ils is not an approved document. Document must be locked
Telephone Res. / Bus: (905) 760-9595	HN & ADAM JOSHUA LITT Property: 5 of Plan -
Decor Advisor: Yolande Somerville	Project: Pine Valley Forevergreen - Phase 1
Totalide Somerville	Model and Elevation: 40.03 B BROOKSIDE
12. Electrical	
Hood Fan O White O Stainless O	N/A
	Above Attenen Cabinet Light () Yes No
Standard Appliances	Below Kitchen Cabinet Light Ves No
Over The Range Microwave	
Chimney Style Fan	
Comment	
10 11 0	
13. Heating and Air Conditioning	
Air Conditioning none	Gas Provisions Stove yes
Gas Provisions Dryer hone	Gas Provisions Barbecue standard
Comment	
4. Additional Comments	
. Disclaimers and Notes	
Colours of all materials are as dose as possible to build	in's selection, but not necessarily identical due to variances in stanulacturing.
Any extras fished above are null and void unless accome	serviced by a separate involce/amendment. Said involce must be paid in full.
The Purchaser arknowledges that after between Prince 9	Selection form in signed and duted, no further changes will be possibled other Purchaser's initials
The Purchaser acknowledges reading and accepting the	a "Gold Park Homes Decor Centre Disclaimers" form, This document contains
	som, this document contains
his Interior Colour Selection is final and approved by:	
921	
Date:	
1/2 00 (83°	Sept. 13, 2021 Page 4 of 4
	Page 4 of 4
rinted 97/2021 12:53:48	



VENDOR
PURCHASER
PURCHASER

GOLDPARK

Prices, Spares, Madrature, Sixts, Sonhares and Sciales we subject to change without motics. Areas and directained are approximate and actual weight four space may very from the stated area. Layout may be reverse of the unit purchased E. S.O.E. 4003

SCHEDULET


PINE VALLEY

PN-5 CONT 10 22 DEC 12 22 Sept. 7, 2021 (P) 0 Sept. 13, 2021 (P) 0.2

The Brookside

40' SERIES

Elevation A - 3,380 sq.ft. Elevation B - 3,350 sq.ft.




VENDOR
PURCHASER
PURCHASER

GOLDPARK

Prices, Squares, Standardons, Store, Seabour and Salabour are subject to change without notice. Areas and discontinuous are approximate and actual tamble from spaces may may from the stated area. Layout may be reserve of the and purchased to a con-


SCHEDULET



The Brookside

40' SERIES Elevation A • 3,380 sq.ft. Elevation B • 3,350 sq.ft.

Sept. 7, 2021 (9 Sept. 13, 2011



VENDOR PURCHASER **PURCHASER** GOLDPARK


SCHEDULET




PV-5 COT 19 222 DE 12 22 Sept. 7, 2021 90 (3) Sept. 13, 2021


The Brookside 40' SERIES


Elevation A • 3,380 sq.ft. Elevation B • 3,350 sq.ft.






PART, OPT, GROUND FLOOR W/ OPT, SIDE ENTRANCE | ELEV. A (ELEV. B SIMILAR)







GOLDPARK

from the stated area. Layout may be m




PV - 5 Cabinetry Schedule

ROOM	DESCRIPTION	PRICE	QTY	TOTAL
KITCHEN	UPGRADE FROM SERIES 2 TO SERIES 5 - MEDIO 6 'FOG'			
	LEAVE 42" SPACE IN UPPER CABINETS ABOVE COOKTOP FOR FUTURE CHIMNEY HOOD FAN (N/C)		1	
	ADD POTS AND PANS DRAWERS BELOW COOKTOP		1	
	ADD CABINETRY VALANCE (ELECTRICAL INCLUDED IN APS)		1	
	ADD ROLL OUT DRAWERS TO BOTTOM OF PANTRY + CABINET BESIDE (2 EACH)		4	
	CONVERT CABINETRY TO TALL DEEP BUILT IN OVEN UNIT WITH DRAWER BELOW		1	
	ADD TWO-BIN RECYCLE CENTRE		4	
	ADD TOUCH LATCH HARDWARE TO REAR ISLAND		1	
	ADD PROUD FURNITURE KICK TO REAR ISLAND		1	
MUD ROOM	ADD OPTIONAL UPPERS IN STANDARD DOOR - TRIBECCA 'TIMBER'		1	
	CABINETI	RY TOTAL:		

HARDWARE PLACEMENT: HORIZONTAL ON DRAWERS, VERTICAL ON DOORS

LOT #: N-5 DATE: Sept-7, 2021	
SIGNATURE:	
SIGNATURE:	
	GOLDPARK





NyA


GOLDPARK HOMES PINE VALLEY VAUGHAN, ONTARIO MODEL: (4003) BROOKSIDE


SITE STANDARD: WHITE 3/4" EXTENSION SOFT-CLOSE DRAWERS & STANDARD SLAM DOOR HINGES TO VANITIES


ONE TOP DRAWER WHERE POSSIBLE THROUGHOUT EACH VANITY, ONE BANK OF DRAWERS WHERE POSSIBLE THROUGHOUT EACH MASTER ENSUITE VANITY

















52 * 10 22 C C C C C 5-20


1.5 My 1.2


GOLDPARK HOMES
PINE VALLEY
VAUGHAN, ONTARIO
MODEL: (4003) BROOKSIDE


STIL STANDARD: WHITE MY EXTRASION
SOFT-CLOSE DRAWERS & STANDARD SLAM DOOR HINGES
TO VANITIES

CAZIO DEAWELM HAVE POSSIBLE INCOUGHOUT FACH PANTA ON BANK OF DEAWERS WHERE POSSIBLE THROUGHOUT FACH MASTER EXSUITE VANTY

SOME THE OTHER








Pages 11/22

PLAN VIEW



BLANCO - QUATRUS R15 U SUPER SINGLE Stainless Steel - Undermount 32" x 18"





Stainless Steel

MODEL 401518 Stainless Steel

Lot# PV-5	
Room: Kitchen	Signature:
Date: Sept. 7,2021	Signature:



MOEN - SLEEK

One-Handle Pulldown Kitchen Faucet



CHROME	
MATTE BLACK (BL)	
STAINLESS (SRS)	
MODEL: 7864 (BL, SRS) Kitchen Faucet	
Lot# PV-5 Date: Sept. 7, 2021 Room: KITCHEM.	
Signature:	
Signature:	

CHROME



MOEN - MODERN

Pot Filler



STAINLESS (SRS)	
POLISHED NICKEL (NL)	
MATTE BLACK (BL)	
BRUSHED GOLD (BG)	
MODEL: S665 Pot Filler	
Lot# PV-5 Date: Room: KITCHEN.	
Signature:	
Signature: A. h.	
	COLDANDA



LP6X6

Shower Door Handle



LP6X6 Shower Door Handle

10" Overall back-to-back 6" hole spacing 3/4" dia. tube (Also available single sided)


V	CHROME	CHROME		
	NAATTE DI	۸ ۵۱		

Lot# PV-5	Date: Sept. 7, 2021	Room: Master Ensuite	
Signature:	9.7		
Signature:	U.lin		



MT6X6

Shower Door Handle



MT6X6 Shower Door Handle

6" x 6" back-to-back 3/4" dia. tube Cut and mitred corners with washers

CHROME		
	MATTE BLACK	

Lot# PV-5	Date: Sept. 7, 2021	Room: Shared Ensuite	
Signature:	9.2mg		
Signature:	a.h		



STONE COUNTERTOP EDGE PROFILES


	STANDARD 2CM EASED EDGE	LOCATION: * thru-out *
	UPGRADE 3CM EASED EDGE	LOCATION:
	UPGRADE 4CM MITRED EDGE	LOCATION:
	UPGRADE 2CM OGEE EDGE	LOCATION:
LOT#: PV-5 SIGNATURE: SIGNATURE:	DATE: Septumber	7,2021


GOLDPARK



H001-02	H001-03	H001-04
6	6	TOUCH-LATCH
H009-03	H009-09	
H011-03	H011-05	H011-06
H033-01	H030.03	*NO HARDWARE
AIMER: NO HARDWARE OR HOLES THRU-OUT: HOM XPENSE AND WARRANTY.	H039-03 Kitchen Powder Room Shared Hud Room Shared ECOWNER IS RESPONSIBLE FOR THE INSTALLATION	r Enoute te 2 d'Enoute on of their own HARDWARE AFTER CLOSING AT
LOT # PV-5	jept. 7, 2021	
SIGNATURE:	6	
SIGNATURE:		







Tissue Holder Mason - Chrome

Towel Bar Mason - Chrome

Please select one of the following:

V	INSTALL STA (tissue holder	NDARD E + towel	BATHROOM bar) *locatio	ACCESSORIES	S THRU dors discre	OUT etion*
	.0		**			
	DO NOT THRU OUT *ti		STANDARD + towel bar	BATHROOM will not be pro	ACCESSO	RIES

LOT # PV-5	DATE: Sept. 7, 2021	
SIGNATURE:	2.25	
SIGNATURE:	hij	



Purchaser(s): Jennifer Little john Adam Little John

Standard Hood Fan Deletion

We acknowledge that the builder's standard hood fan will not be installed.

Do not supply, install and/or credit. We will install our own hood fan after closing.

Signature:

Signature:

CHROME



MOEN - MODERN

Pot Filler



STAINLESS (SRS)		
BRUSHED G	OLD (BG)		
MATTE BLAC			
	12		
MODEL: S665 (SRS, B	G, BL) Pot Filler		
Lot#	Date:	Room:	
PV-5	Dec 11, 2020.	Kitchen	
Signature:			
Signature:			



UPGRADE PLUMBING

MOEN - ALIGN

3 Function SHOWER ONLY* Rain Shower and Handshower



MODEL: T2192EP Shower Trim Only* / T4191 Transfer Trim + 3372 Transfer Valve / 62320 1/2" CC Valve / 3887EP Handshower + A725 Drop El / 226651 Shower Arm (from ceiling) / S6360 Showerhead

10T#: PV-6	Dec. 11, 2020.	ROOM Master Ensuite
SIGNATURE:		

falmec

VULCANO

Version

FPVUX36W6SS-R / VulcanoXL Wall 36" (90cm) 600 CFM

Collection Potenza

EAN code 8034122502687



Scotch brite stainless steel
(AISI 304)
Electronic control
LED lighting
Optional charcoal filter
Labyrinth filter
SRS Speed reduction system

Recommended mounting height from cooking surface to hood bottom: 24" - 35"

OPTIONAL ACCESSORIES

FFCHASQCOBL

FFCHASQCOBL - Square charcoal filter - Type 3 KACL.510#I


Extension H700 - Wall

KACL.512#1

Extension H960 - Wall

KACL.815

Protective cleaning cloths for stainless steel (box 10 pcs)



90 RD -5 7 2021



Photograph is for information purposes only May not correspond to the selected version

TECHNICAL FEATURES

Installation type Wall Dimensions

Dimensions 36 / 90 cm Finish

Scotch brite stainless steel (AISI

304) Motor 600 CFM

Type of control
Electronic control

Speed settings

4

Lighting

Led 2x1,2 W - 3200 K Minimum distance Gas hob: 24 in

Electric hob: 21 in

PACKAGING:WEIGHTS AND VOLUMES

Gross weight 49 lbs Net weight

38 lbs Volumes 11 ft³

Packaging size

Length 40 in Height 21 in

Depth 24 in CONSUMPTION AND CONNECTION FEATURES

Maximum consumption


430 W


Plug type

Hood comes standard with Nema

5-15P power cord









EZ-2-LIFT™ HINGED CAST-IRON GRATES



Get quick access to spills on the cooktop with our industry-first EZ-2-Lift™ hinged cast-iron grates. The hinged design lets you wipe up underneath without removing them. For a more thorough clean, the grates are also dishwasher safe.

UPSWEPT SPILLGUARD™ COOKTOP



Clean up faster with a cooktop that has raised edges to help contain spills.


DISHWASHER-SAFE KNOBS



Make cleanup easy by washing knobs right in the dishwasher.

OTHER FEATURES

- Upswept SpillGuard™ cooktop
- SpeedHeat™ burner
- ccuSimmer® burner
- Fifth Burner
- Sealed burners
- Full width grates
- Wall oven compatible







White	(VV)

Black (B)

Silver (S)

MODEL	WCG55US6HW	WCG55US6HB	WCG55US6HS
Max height (in)	4-1/8"	4-1/8"	4-1/8"
Width (in)	36"	36"	36"
Depth (in)	21"	21"	21"













Stainless Steel WCG55US6HS

General Features & Prope	rties	
AccuSimmer® Burner		
Fifth Burner		
Sealed Burners		
Full-Width Grates		
Dishwasher-Safe Knobs		
Wall Oven Compatible		
Electrical Details		35
Amps	15	
Volts	120	
Certifications		

Yes

ADA Compliant

Technical Details	
Fuel Type	Gas
Number of Burners/ Elements	5
Burner/Element Power	(1) 15000 BTU (2) 9100 BTU (1) 12,000 BTU (1) 5000 BTU
Burner/Element Type/Size	SpeedHeat™, Burner, Sealed Burner, Simme
Dimensions	
Product Dimensions (H x W x D)	4-1/8" x 36" x 21"
Cutout Dimensions (W x D)	33-7/8" x 19"
Reference Material	

Install Guide

Use & Care Guide

Warranty

Also available in:

White	WCG55US6HW
Black	WCG55US6HB
Black Stainless Steel	WCG55US6HV

Key Features & Benefits

EZ-2-Lift™ Hinged Cast-Iron Grates


Get quick access to spills on the cooktop with our industry-first EZ-2-Lift™ hinged cast-iron grates. The hinged design lets you wipe up underneath without removing them. For a more thorough clean, the grates are also dishwasher-safe.

Upswept SpillGuard™ Cooktop

Clean up faster with a cooktop that has raised edges to help contain spills.

SpeedHeat™ Burner

Get dinner to the table fast with this burner that generates the high heat needed to sear and boil quickly.





In the State of Massachusetts, the following installation instructions apply:

- Installations and repairs must be performed by a qualified or licensed contractor, plumber, or gas fitter qualified or licensed by the State of Massachusetts.
- Acceptable Shut-off Devices: Gas Cocks and Ball Valves installed for use shall be listed.

Marker or pencil

Pipe-joint compound

Noncorrosive leak-

detection solution

resistant to Propane gas

A flexible gas connector, when used, must not exceed 4 feet (121.9 cm).

INSTALLATION REQUIREMENTS

Tools and Parls

Gather the required tools and parts before starting installation.

Tools needed

- Tape measure
- Screwdriver
- 15/16" (24 mm) combination wrench
- Pipe wrench
- Wrench or pliers

Parts supplied

- Gas pressure regulator
- Burner grates
- Burner caps
- Clamping brackets (2)
- 21/2" (6.4 cm) clamping screws (2)


Parts needed

Check local codes and consult gas supplier. Check existing gas supply and electrical supply. See the "Electrical Requirements" and "Gas Supply Requirements" sections.

Location Requirements

IMPORTANT: Observe all governing codes and ordinances. Do not obstruct flow of combustion and ventilation air.

It is the installer's responsibility to comply with installation clearances specified on the model/serial/rating plate. The model/serial/rating plate is located on the underside of the cooktop base.



A. Model/serial/rating plate

- The cooktop should be installed in a location away from strong draft areas, such as windows, doors, and strong heating vents or fans.
- All openings in the wall or floor where cooktop is to be installed must be sealed.
- Cabinet opening dimensions that are shown must be used. Given dimensions are minimum clearances.
- Grounded electrical supply is required. See the "Electrical Requirements" section. Proper gas supply connection must be available. See the "Gas Supply Requirements" section.
- The cooktop is designed to hang from the countertop by its side or rear flanges.
- The gas and electric supply should be located as shown in "Cabinet Dimensions" section so that they are accessible without requiring removal of the cooktop.
- Provide cutout in right rear corner of cutout enclosure as shown to provide clearance for gas inlet, power supply cord, and to allow the rating label to be visible.

IMPORTANT: To avoid damage, check with your builder or cabinet supplier to make sure that the materials used will not discolor, delaminate or sustain other damage.


Mobile Home - Additional Installation Requirements

The installation of this cooktop must conform to the Manufactured Home Construction and Safety Standard, Title 24 CFR, Part 3280 (formerly the Federal Standard for Mobile Home Construction and Safety, Title 24, HUD Part 280). When such standard is not applicable, use the Standard for Manufactured Home Installations, ANSI A225.1/NFPA 501A or with local codes.

In Canada, the installation of this cooktop must conform with the current standards CAN/CSA-A240-latest edition, or with local codes.


Product Dimensions

Metal Cooktops



A. 31⁷/₁₆" (79.8 cm) on 30" (76.2 cm) models, 37 %₁₆" (95.4 cm) on 36" (91.4 cm) models B. 21½" (53.4 cm) C. 2½" (7.3 cm)

Cabinet Dimensions



- A. 30" (76.2 cm) on 30" models; 36" (91.4 cm) on 36" models
- B. Combustible area above countertop (shown by dashed box above)
- C. 30" (76.2 cm) minimum clearance between top of cooktop platform and bottom of uncovered wood or metal cabinet (24" [61 cm] minimum clearance if bottom of wood or metal cabinet is covered by not less than ¼" [0.6 cm] flame retardant millboard covered with not less than No. 28 MSG sheet steel, 0.015" [0.04 cm] stainless steel, or 0.024" [0.06 cm] aluminum or 0.020" [0.05 cm] copper)
- D. 15" (38.1 cm) maximum upper cabinet depth
- E. 21/8" (5.4 cm)
- F. 19" (48.3 cm)
- G. 18" (45.7 cm) minimum clearance from upper cabinet to countertop within minimum horizontal clearances to cooktop
- H. Grounded outlet locate within 24" (61 cm) of right rear corner of cutout
- I. 29" (73.7 cm) on 30" models; 351/4" (89.5 cm) on 36" models
- J. 8%" (21.3 cm) minimum distance to nearest left and right side combustible surface
- K. 21/6" (7.3 cm) minimum distance to rear combustible surface
- L. Gas line opening Wall: anywhere 5" (12.7 cm) below underside of countertop. Cabinet floor: anywhere within 6" (15.2 cm) of rear wall is recommended
- M. 24" (61 cm) minimum countertop depth is required

NOTES: After making the countertop cutout, some installations may require notching down the base cabinet side walls to clear the cooktop base. To avoid this modification, use a base cabinet with sidewalls wider than the cutout.

If cabinet has a drawer, a 4" (10.2 cm) depth clearance from the countertop to the top of the drawer (or other obstruction) in base cabinet is required. The drawer depth may need to be shortened to avoid interfering with the regulator.



AWARNING



Electrical Shock Hazard

Plug into a grounded 3 prong outlet.

Do not remove ground prong.

Do not use an adapter.

Do not use an extension cord.

Failure to follow these instructions can result in death, fire, or electrical shock.

IMPORTANT: The cooktop must be electrically grounded in accordance with local codes and ordinances, or in the absence of local codes, with the National Electrical Code, ANSI/NFPA 70 or Canadian Electrical Code, CSA C22.1.

This cooktop is equipped with an electronic ignition system that will not operate if plugged into an outlet that is not properly polarized.

If codes permit and a separate ground wire is used, it is recommended that a qualified electrical installer determine that the ground path is adequate.

A copy of the above code standards can be obtained from:

National Fire Protection Association 1 Batterymarch Park Quincy, MA 02169-7471 CSA International 8501 East Pleasant Valley Road Cleveland, OH 44131-5575

- A 120-volt, 60 Hz., AC-only, 15-amp fused, electrical circuit is required. A time-delay fuse or circuit breaker is also recommended. It is recommended that a separate circuit serving only this cooktop be provided.
- Electronic ignition systems operate within wide voltage limits, but proper grounding and polarity are necessary. Check that the outlet provides 120-volt power and is correctly grounded.
- The wiring diagrams are provided with this cooktop. See "Wiring Diagrams" section.

INSTALLATION INSTRUCTIONS 27" (68.6 CM) AND 30" (76.2 CM) ELECTRIC MICROWAVE/OVEN COMBINATION FLUSH INSTALLATION KIT

INSTRUCTIONS D'INSTALLATION POUR TROUSSE D'INSTALLATION EN AFFLEUREMENT D'UN ENSEMBLE FOUR À MICRO-ONDES ÉLECTRIQUE/ FOUR DE 27" (68,6 CM) ET 30" (76,2 CM)

Flush Installation Kit Part Number Ensemble d'installation en affleurement référence	Size and Color Dimensions et couleur	UL Listed for Model Numbers Homologation UL pour les modèles numéro
W11173682	27" (68.6 cm), white	WOC54EC7HW
W11173684	30" (76.2 cm), white	WOC54EC0HW, WOC75EC0HW
W11173686	27" (68.6 cm), black	WOC54EC7HB
W11173692	30" (76.2 cm), black	WOC54EC0HB, WOC75EC0HB
W11173695	27" (68.6 cm), stainless steel	WOC54EC7HS, WOC75EC7HS
W11123004	30" (76.2 cm), stainless steel	WOC54EC0HS, WOC75EC0HS, WOC97EC0HZ, WOCA7EC0HZ
W11173701	27" (68.6 cm), black stainless	WOC75EC7HV
W11173704	30" (76.2 cm), black stainless	WOC75EC0HV
W11123006	30" (76.2 cm), bronze	WOCA7EC0HN

Table of Contents/Table des matières

BUILT-IN OVEN SAFETY2	SÉCURITÉ DU FOUR ENCASTRÉ9
INSTALLATION REQUIREMENTS2	EXIGENCES D'INSTALLATION9
Tools and Parts2	Outillage et pièces9
Location Requirements2	Exigences d'emplacement9
INSTALLATION INSTRUCTIONS4	INSTRUCTIONS D'INSTALLATION11
Prepare Built-In Microwave/Oven Combination4	Préparation de l'ensemble des fours encastrés (micro-ondes/four)11
Remove Oven Door4	
Replace Oven Door5	Dépose de la/des porte du four11
Positioning Oven Feet5	Réinstallation de la/des porte du four11
Replace Plastic Spacers6	Positionnement des pieds du four12
Install Oven7	Remplacement des cales d'espacement en plastique13
Install Deflector Kit Bracket7	Installation du four14
Complete Installation8	Installation du support de la trousse du déflecteur14
Complete installation	Achever l'installation15

IMPORTANT:

Save for local electrical inspector's use.

IMPORTANT:

À conserver pour consultation par l'inspecteur local des installations électriques.



SCAN-TO-COOK TECHNOLOGY*



Get the right settings every time. Scan a frozen food barcode with your smartphone or tablet and send recommended or customized cooking instructions straight to your oven for dinner done the way your family wants it.**

TOUCHSCREEN



Get instant access to the settings you use most with a touchscreen that learns, adapts and suggests customized presets based on your family's routines.

FROZEN BAKE™ TECHNOLOGY



Skip preheating and cook frozen favorites like pizza in fewer steps with preprogrammed settings that automatically adjust cooking times for you.

OTHER FEATURES

- Smart Appliance
- Multi-Step Cooking
- Fingerprint Resistant
- True Convection Cooking
- Convection Conversion
- Nest Learning Thermostat[™] integration
- Remote Start
- Party mode
- Enhanced troubleshooting
- Guided Service
- Self-close door
- Temperature Sensor
- Rapid Preheat
- Control Lock Mode
- Sabbath Mode
- Tap Touch Controls
- . 6.4 cu. ft. total capacity
- Extra-large window
- Scan-to-Connect Technology









Fingerprint Resistant Black Stainless Steel (V)

MODEL	WOC75EC0HW	WOC75EC0HB	WOC75EC0HS	WOC75EC0HV
Max height (in)	42-9/16"	42-9/16"	42-9/16"	42-9/16"
Width (in)	30"	30"	30°	30"
Depth (in)	26-1/2"	26-1/2"	26-1/2"	26-1/2"





Whirlpool® 6.4 cu. ft. Smart Combination Wall Oven





Stainless Steel WOC75EC0HS


Also available in:

0	White

WOC75EC0HW



WOC75EC0HB



WOC75EC0HV

Oven	6.4 cu. ft.
ieneral Features & Prop	perties
ouchscreen	
oice control with a convoice-enabled device	mpatible
ingerprint Resistant	
rozen Bake [™] technolo	gy
Multi-Step Cooking	
True Convection Cooking	ng
Convection Conversion	r
Steam Clean option	
Scan-to-Connect Tech	nology
lectrical Details	
mps	40
folts	240
ertifications	
Connected/Smart appliance	Yes

Star-K Certified/Kosher

Technical Details	
Fuel Type	Electric
Oven Type	Combination
Oven Cooking System	True Convection
Number of Oven Racks	3
Cleaning Type	Self-Cleaning
Dimensions	
Product Dimensions (H x W x D)	42-9/16" x 30" x 23-1/4"
Depth with Door Open 90°	46-3/4"
Cutout Dimensions (H x W x D)	41-5/16" x 28-1/2" x 24"
Reference Material	
Install Guide	
Use & Care Guide	
Energy Guide	
Warranty	

Key Features & Benefits

Smart Appliance


Care smarter with connected features that let you send cooking instructions to the oven from your smartphone, control your kitchen with voice commands using a compatible voice-enabled device* or skip preheating.

Scan-to-Cook Technology"

Get the right settings every time. Scan a frozen food barcode with your smartphone or tablet and send recommended or customized cooking instructions straight to your oven or microwave for dinner done the way your family wants it.


Yummly® Guided Cooking"

Prompts in the app even send cooking instructions straight to your Whirlpool® smart wall oven† at the right times, so dinner's ready when your family's hungry.



*Appliance must be set to remote enable. WiFi & App Required. Features subject to change. Details and privacy info at whirlpool.com/connect. **U.S. Only. †Select recipes only. Compatible smart appliance required. Appliance must be set to remote enable. Features subject to change. For details and privacy statements, visit whirlpool.com/connect and yummly.com/privacy. NOTE: Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice. ®/™ © 2020. All rights reserved. Printed in the U.S.A. D200104XXE. WOC75EC0HSpecSheetV01.

Deflector Bracket Dimensions



27" (68.6 cm) Models

30" (76.2 cm) Models

A. 2615/16" (68.4 cm) overall width

A. 2915/16" (76.0 cm) overall width




Cabinet Dimensions - Flush Installations

A 25" (63.5 cm) minimum cutout depth is required.

These dimensions will result in a 1/4" (6 mm) reveal on the top. a 1/4" (6 mm) reveal on the sides, and a 1/8" (3 mm) reveal on the bottom of the wall oven.

The front face of the cleats and platform will be visible and should be treated as a finished surface.



Front View


Side View

27" (68.6 cm) Models

- A. 5/8" (16 mm) top cleat*
- B. 271/4" (69.2 cm) minimum width of flush inset cutout
- C. 257/8" (65.7 cm) minimum width of opening
- D. 431/8" (109.5 cm) minimum height of flush inset cutout
- E. 421/2" (107.9 cm) recommended cutout height
- 11/16" (17 mm) side cleat*
- G. 1/2" x 2" (13 mm x 51 mm) spacer the entire depth of the cutout*
- H. Recommended junction box location
- 45/8" 191/4" (11.7 cm -48.9 cm) bottom of cutout to
- J. 25" (63.5 cm) minimum depth of cutout

30" (76.2 cm) Models

- A. 5/8" (16 mm) top cleat*
- B. 301/4" (76.8 cm) minimum width of flush inset cutout
- 287/s" (73.3 cm) minimum width of opening
- 431/8" (109.5 cm) minimum height of flush inset cutout
- E. 421/2" (107.9 cm) recommended cutout height
- 11/16" (17 mm) side cleat*
- G. 1/2" x 2" (13 mm x 51 mm) spacer the entire depth of the cutout*
- H. Recommended junction box location
- 45/8" 191/4" (11.7 cm -48.9 cm) bottom of cutout to floor
- J. 25" (63.5 cm) minimum depth of cutout



Top View

27" (68.6 cm) Models

- A. 1/2" x 2" (13 mm x 51 mm) spacer the entire depth of the cutout*
- B. 25" (63.5 cm) depth of cutout
- C. 13/8" (3.5 cm) recess from front of cabinet
- D. 11/16" (17 mm) side cleat*

30" (76.2 cm) Models

- A. 1/2" x 2" (13 mm x 51 mm) spacer the entire depth of the cutout*
- B. 25" (63.5 cm) depth of cutout
- 13/8" (3.5 cm) recess from front of cabinet
- D. 11/16" (17 mm) side cleat*

^{*}Cleats and spacers must be recessed 13/8" (3.5 cm) from the front of the cabinet.

^{*} Cleats and spacers must be recessed 13/8" (3.5 cm) from the front of the cabinet.



French Door Bottom Mount Refrigerator

PRODUCT MODEL NUMBERS

WRF532SMB WRF535SMB WRF535SWB WRFA32SMH WRF540CWB WRF535SWH WRFA35SWH

Electrical: A 115 Volt, 60 Hz, AC only 15 or 20 A fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

NOTE: Before performing any type of installation, cleaning, or removing a light bulb, turn the control (Thermostat, Refrigerator or Freezer Control depending on the model) to OFF and then disconnect the refrigerator from the electrical source. When you are finished, reconnect the refrigerator to the electrical source and reset the control (Thermostat, Refrigerator or Freezer Control depending on the model) to the desired setting. See "Using the Controls."

Water: A cold water supply with water pressure between 35 and 120 psi (241 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.


IMPORTANT: The pressure of the water coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 35 and 120 psi (241 and 827 kPa).


Reverse Osmosis Water Supply:

If a reverse osmosis water filtration system is connected to your cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).




PRODUCT DIMENSIONS





Model Number/ Size	Height - Overall "A"	Height - Top of Cabinet "B"	Depth - Doors Open 90° "C"	Depth - Drawer Open "D"	Depth - With Handles "E"	Depth - Without Handles "F"	Depth - Cabinet Only "G"	Width - Cabinet "H"	Width - Door Open 90° "1"
WRF535SWB	701/s"	68 ¹³ /16"	48 ¹³ / ₁₆ "	53½"	35%s"	32 ¹⁵ /16"	291/8"	35%"	43%"
25.2 cu. ft.	(178.1 cm)	(174.8 cm)	(122.1 cm)	(135 cm)	(90 cm)	(83.7 cm)	(74 cm)	(90.5 cm)	(110.2 cm)
WRF535SMB	701/8"	68 ¹³ /16"	48 ¹³ / ₁₆ "	53½"	35% ₆ "	32 ¹⁵ / ₁₆ "	291/8"	35%"	43%"
25.2 cu. ft.	(178.1 cm)	(174.8 cm)	(122.1 cm)	(135 cm)	(90 cm)	(83.7 cm)	(74 cm)	(90.5 cm)	(110.2 cm)
WRF532SMB	701/s"	68 ¹³ / ₁₆ "	42¾"	521/8"	34½;"	31 ¹⁵ / ₁₆ "	281/8"	325/8"	40¾"
22.1 cu. ft.	(178.1 cm)	(174.8 cm)	(107.6 cm)	(132.4 cm)	(87.5 cm)	(81.1 cm)	(71.4 cm)	(82.9 cm)	(102.6 cm)
WRF540CWB	701/8"	68 ¹³ / ₁₆ "	43 ¹ / ₁₆ "	44½"	29¾"	28"	24½"	35%"	43%"
20 cu. ft.	(178.1 cm)	(174.8 cm)	(109.4 cm)	(113.0 cm)	(74.6 cm)	(71.1 cm)	(61.3 cm)	(90.5 cm)	(110.2 cm)
WRF535SWH	70½"	68%"	481/8"	52½"	35½"	33"	291/8"	355/s"	41"
20 cu. ft.	(178.1 cm)	(174.9 cm)	(122.2 cm)	(132.4 cm)	(90.2 cm)	(83.8 cm)	(74 cm)	(90.5 cm)	(104.1 cm)
WRFA35SWH	701/s"	68%"	481/s"	53½"	35½"	33"	291/8"	35%"	43"
25.2 cu. ft.	(178.1 cm)	(174.9 cm)	(122.2 cm)	(135 cm)	(90.2 cm)	(83.8 cm)	(74 cm)	(90.5 cm)	(109.2 cm)
WRFA32SMH	701/8"	681/8"	47 ¹ / ₈ "	521/8"	34½"	32"	281/ ₈ "	32%"	40"
22.1 cu. ft.	(178.1 cm)	(174.9 cm)	(119.7 cm)	(132.4 cm)	(87.6 cm)	(81.3 cm)	(71.4 cm)	(82.9 cm)	(101.6 cm)

LOCATION REQUIREMENTS




To ensure proper ventilation for your refrigerator, allow for a 1/2" (1.25 cm) space on each side and at the top. Allow for 1" (2.54 cm) of space behind the refrigerator. If your refrigerator has an ice maker, make sure you leave some extra space at the back for the water line connections.

If you are installing your refrigerator next to a fixed wall, leave 2½" (6.3 cm) minimum on the hinge side (some models require more) to allow for the door to swing open.


NOTE: This refrigerator is intended for use in a location where the temperature ranges from a minimum of 55°F (13°C) to a maximum of 110°F (43°C). The preferred room temperature range for optimum performance, which reduces electricity usage and provides superior cooling, is between 60°F (15°C) and 90°F (32°C). It is recommended that you do not install the refrigerator near a heat source, such as an oven or radiator.



DETAILED PLANNING DIMENSIONS GUIDE



PRODUCT DIMENSIONS




*Dishwasher can be raised 11/16" (3.7 cm) with feet fully extended.





PRODUCT DIMENSIONS (CONTD.)



	DESCRIPTION	DIMENSIONS
A	Width of door	23%" (60.6 cm)
B*	Height to top of handle	31%s" (80.1 cm)
С	Height of adjustable toe kick	3½" (8.8 cm) - minimum 4¼" (10.8 cm) - maximum
D	Width of recessed dishwasher	23%" (60.6 cm)
E [†]	Depth without door	22%" (57.5 cm)
F†	Depth with Towel Bar Handle	26½" (67.3 cm)
	Depth with Pocket Handle	24½" (62.2 cm)
G*	Height to bottom of door (minimum)	35/₁6" (8.4 cm)
H*	Height to top of door (minimum)	33¾6" (84.9 cm)
[†*	Height of recessed dishwasher (minimum)	33%" (85.4 cm)
J†	Depth with door fully open (minimum)	50% (127.4 cm)
Κ [†]	Depth with toe kick (minimum)	20 ¹³ / ₁₆ " (52.9 cm)

[†]Insulation blanket thickness not included, can be crushed up to 1/8" (0.3 cm), or removed along the top perforate section for additional clearance.


^{*}Dishwasher can be raised 11/16" (3.7 cm) with feet fully extended.





OPENING/CLEARANCE DIMENSIONS

IMPORTANT: Check that all surfaces have no protrusions that would prohibit dishwasher installation.



- A. Measured from the lowest point on the underside of the countertop. May be reduced to 335/8" minimum (85.4 cm) minimum by removing the feet and perforated area of insulation (blanket) on dishwasher.
- B. Minimum, measured from narrowest point of opening.

NOTE: Corner locations require a 2" (5.1 cm) minimum clearance between the side of the dishwasher door and the wall or cabinet.

1 of 15

WHIRLPOOL® FRONT LOAD WASHER WITH LOAD & GO™ XL DISPENSER - 5.0 cu ft







WHIRLPOOL® FRONT LOAD WASHER WITH LOAD & GO™ XL DISPENSER - 5.0 cu ft


ELECTRICAL REQUIREMENTS

WARNING: To reduce the risk of fire, electric shock, or injury to persons, read the IMPORTANT SAFETY INSTRUCTIONS and INSTALLATION INSTRUCTIONS, located in your appliance's Owner's Manual, before installing and operating this appliance.

Electrica	I Requirements
WFW9620HBK WFW9620HC WFW9620HW	5.0 cu ft DOE (US)/5.8 cu ft IEC (CAN)
Minimum Circuit Amperage Rating	15 A
Maximum Ampere Draw	10.36 A
Operating Voltage	120 V AC only
Operating Frequency	60 Hz

PRODUCT DIMENSIONS

WFW9620HBK WFW9620HC WFW9620HW				
Unit of Measurement	in (minimum)	mm (minimum)	in (maximum)	mm (maximum)
Height (with feet) (A)	38%	981	40	1016
Product Width (B)	27	686	-	-








WHIRLPOOL® FRONT LOAD WASHER WITH LOAD & GO™ XL DISPENSER - 5.0 cu ft

PRODUCT DIMENSIONS

WFW9620HBK WFW9620HC WFW9620HW		5.0 cu ft DOE (U	S)/5.8 cu ft IEC (CAN)	
Unit of Measurement	in (minimum)	mm (minimum)	in (maximum)	mm (maximum)
Door Width (C)	2511/16	652	÷ .	-
Product Depth (D)	331/4	844	1-	ي
Product Depth with Door Open (E)	56½	1435	1-	-
Door Height (F)	2511/16	652	T-P	-
Height to Bottom of Door (G)	9½	241		



SIDE VIEW








4 of 15

WHIRLPOOL® FRONT LOAD WASHER WITH LOAD & GO™ XL DISPENSER - 5.0 cu ft PRODUCT DIMENSIONS

WFW9620HBK WFW9620HC WFW9620HW	5.0 cu ft DOE (US)/5.8 cu ft IEC (CAN)				
Unit of Measurement	in (minimum)	mm (minimum)	in (maximum)	mm (maximum)	
Position of Power Cord (H)	355/16	897	-	-	
Power Cord Length	72	1830	i H	-,	
Position of Water Inlet Valves (I)	35⁵∕16	897	-	-	
Position of Drain Hose (J)	8	205	13	-	
Drain Hose Length	52	1321		-	
Diameter of Drain Hose	1	26	-	_	










5 of 15

WHIRLPOOL® FRONT LOAD WASHER WITH LOAD & GO™ XL DISPENSER - 5.0 cu ft


All Dimensions show recommended spacing allowed, except for closet door ventilation openings which are minimum required. This washer has been tested for installation with spacing of 0" (0 mm) clearance on the sides. Consider allowing more space for ease of installation and servicing, and spacing for companion appliances and clearances for walls, doors, and floor moldings. Add spacing of 1" (25 mm) on all sides of washer to reduce noise transfer. If a closet door or louvered door is installed, top and bottom air openings in door are required.

*For additional details (or information) specific to your model, refer to your Quick Start Guide.

CUSTOM UNDER COUNTER INSTALLATION



RECESSED AREA OR CLOSET INSTALLATION



NOTE: All 27" wide washers should have 19" clearance, while all 29" wide washers should have 22" clearance.



Additional parts may be required, depending on your installation. Check local codes. Check existing electrical supply and venting. Read "Electrical Requirements" and "Venting Requirements" before purchasing parts.

If using a power supply cord:

Use a UL Listed power supply cord kit marked for use with clothes dryers. The kit should contain:

- A UL Listed 30 A power supply cord, rated 120/240 V minimum. The cord should be type SRD or SRDT and be at least 4 ft. (1.22 m) long. The wires that connect to the dryer must end in ring terminals or spade terminals with upturned ends.
- A UL Listed strain relief.

Optional Equipment (not supplied with dryer):

Refer to your Use and Care Guide for information about accessories available for your dryer.

LOCATION REQUIREMENTS

Check code requirements. Some codes limit, or do not permit, installing dryer in garages, closets, mobile homes, or sleeping quarters. Contact your local building inspector.

AWARNING



Explosion Hazard

Keep flammable materials and vapors, such as gasoline, away from dryer.

Place dryer at least 18 inches (460 mm) above the floor for a garage installation.

Failure to do so can result in death, explosion, or fire.


You will need:

- A location allowing for proper exhaust installation. See "Venting Requirements."
- A separate 15 or 20 A circuit for a gas dryer or 30 A circuit for an electric dryer.
- If using power supply cord, a grounded electrical outlet located within 2 ft. (610 mm) of either side of dryer. See "Electrical Requirements."
- Floor must support dryer weight of 200 lbs. (90.7 kg). Also consider weight of companion appliance.
- Cold water faucets located within 4 ft. (1.2 m) of the water fill valves, and water pressure of 20–120 psi (138–827 kPa). You may use your washer's water supply by purchasing the necessary parts noted in "Parts needed."
- Level floor with maximum slope of 1" (25 mm) under entire dryer. If slope is greater than 1" (25 mm), install Extended Dryer Feet Kit, Part Number 279810. If not level, clothes may not tumble properly and automatic sensor cycles may not operate correctly.
- For garage installation, place dryer at least 18" (460 mm) above floor. If using a pedestal, you will need 18" (460 mm) to bottom of dryer.
- The dryer must not be installed or stored in an area where it will be exposed to water and/or weather.

IMPORTANT: Do not operate, install, or store dryer where it will be exposed to water, weather, or at temperatures below 40°F (4°C). Lower temperatures may cause dryer not to shut off at end of automatic sensor cycles, resulting in longer drying times.


DRYER DIMENSIONS Front view:






Side view:

Whirlpool® Models




*Approx. measurement

Maytag® Models



*Approx. measurement

Back view:



NOTE: Most installations require a minimum of 5" (127 mm) clearance behind dryer for exhaust vent with elbow. See "Venting Requirements."

Installation Clearances

For each arrangement, consider allowing more space for ease of installation and servicing, spacing for companion appliances, and clearances for walls, doors, and floor moldings. Space must be large enough to allow door to fully open. Add spacing on all sides of dryer to reduce noise transfer. If a closet door or louvered door is installed, top and bottom air openings in door are required.

Check code requirements. Some codes limit, or do not permit, installation of the dryer in garages, closets, mobile homes, or sleeping quarters. Contact your local building inspector.


NOTE: No other fuel-burning appliance can be installed in the same closet as a dryer.

Installation spacing for recessed area or closet installation

All dimensions show recommended and minimum spacing allowed.


- Additional spacing should be considered for ease of installation and servicing.
- Additional clearances might be required for wall, door, floor moldings, dryer venting, and gas line.
- Additional spacing should be considered on all sides of the dryer to reduce noise transfer.
- For closet installation with a door, minimum ventilation openings in the top and bottom of the door are required. Louvered doors with equivalent ventilation openings are acceptable.
- Companion appliance spacing should also be considered.

Recommended installation clearances (dryer only):



0" (0 mm) rear spacing is allowed for straight back venting only. For steam models only, inlet hose must not be kinked.

Custom under-counter installation:



Mobile home - Additional installation requirements:

This dryer is suitable for mobile home installations.
The installation must conform to the Manufactured Home
Construction and Safety Standard, Title 24 CFR, Part 3280
(formerly the Federal Standard for Mobile home construction and
Safety, Title 24, HUD Part 280) or Standard CAN/CSA-Z240 MH.

Mobile home installations require:

- Metal exhaust system hardware, available for purchase from your dealer. For further information, see "Assistance or Service" in your Use and Care Guide.
- Special provisions must be made in mobile homes to introduce outside air into dryer. Openings (such as a nearby window) should be at least twice as large as dryer exhaust opening.

For mobile home installation of gas dryers:

Mobile Home Installation Hold-down Kit Part Number 346764 is available to order. For further information, see "Assistance or Service" in your Use and Care Guide.