


Schedule 1: Designer Information

Use one form for each individual who reviews and takes responsibility for design activities with respect to the project.

A. Project Information			
Building number, street name		Unit no.	Lot/con.
Municipality VAUGHAN (WOODBIDGE)	Postal code	Plan number/ other description	
B. Individual who reviews and takes responsibility for design activities			
Name MICHAEL O'ROURKE		Firm HVAC DESIGNS LTD.	
Street address 375 FINLEY AVE		Unit no. 202	Lot/con. N/A
Municipality AJAX	Postal code L1S 2E2	Province ONTARIO	E-mail info@hvacdesigns.ca
Telephone number (905) 619-2300	Fax number (905) 619-2375	Cell number ()	
C. Design activities undertaken by individual identified in Section B. [Building Code Table 3.5.2.1 OF Division C]			
<input type="checkbox"/> House <input type="checkbox"/> Small Buildings <input type="checkbox"/> Large Buildings <input type="checkbox"/> Complex Buildings			
<input checked="" type="checkbox"/> HVAC – House <input type="checkbox"/> Building Services <input type="checkbox"/> Detection, Lighting and Power <input type="checkbox"/> Fire Protection			
<input type="checkbox"/> Building Structural <input type="checkbox"/> Plumbing – House <input type="checkbox"/> Plumbing – All Buildings <input type="checkbox"/> On-site Sewage Systems			
Description of designer's work HEAT LOSS / GAIN CALCULATIONS DUCT SIZING RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY RESIDENTIAL SYSTEM DESIGN per CSA-F280-12		Model: 6001 - QUEENSLAND - ELEV C OPT 2ND - ELEVATOR - WOB Project: PINE VALLEY PH 2	
D. Declaration of Designer			
I, <u>MICHAEL O'ROURKE</u>		declare that (choose one as appropriate):	
(print name)			
<input type="checkbox"/> I review and take responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Division C, of the Building Code. I am qualified, and the firm is registered, in the appropriate classes/categories. Individual BCIN: _____ Firm BCIN: _____			
<input checked="" type="checkbox"/> I review and take responsibility for the design and am qualified in the appropriate category as an "other designer" under subsection 3.2.5. of Division C, of the Building Code. Individual BCIN: <u>19669</u> Basis for exemption from registration and qualification: <u>O.B.C SENTENCE 3.2.4.1 (4)</u>			
<input type="checkbox"/> The design work is exempt from the registration and qualification requirements of the Building Code. Basis for exemption from registration and qualification: _____			
I certify that:			
1. The information contained in this schedule is true to the best of my knowledge. 2. I have submitted this application with the knowledge and consent of the firm.			
April 14, 2022			
Date		Signature of Designer	

NOTE:

- For the purposes of this form, "individual" means the "person" referred to in Clause 3.2.4.7(1) d) of Division C, Article 3.2.5.1. of Division C, and all other persons who are exempt from qualification under Subsections 3.2.4. and 3.2.5. of Division C.
- Schedule 1 is not required to be completed by a holder of a license, temporary license, or a certificate of authorization, issued by the Ontario Association of Architects. Schedule 1 is also not required to be completed by a holder of a license to practise, a limited license to practise, or a certificate of authorization, issued by the Association of Professional Engineers of Ontario.

Application for a Permit Construct or Demolish – Effective January 1, 2015

SITE NAME: PINE VALLEY PH 2
 BUILDER: GOLD PARK HOMES

OPT 2ND - ELEVATOR - WOB
 TYPE: 6001 - QUEENSLAND - ELEV C GFA: 5742

DATE Apr-22
 LO# 96176

WINTER NATURAL AIR CHANGE RATE 0.486
 SUMMER NATURAL AIR CHANGE RATE 0.162

HEAT LOSS ΔT °F. 76
 HEAT GAIN ΔT °F. 13

CSA-F280-12
 SB-12 PACKAGE A1

ROOM USE	GREAT		KIT			DIN			LIBR			FOY			MUD					
EXP. WALL	58		56			25			33			43			29					
CLG. HT.	11		11			11			11			11			13					
FACTORS																				
GRS.WALL AREA	LOSS	GAIN	594			265			350			456			365					
GLAZING	LOSS	GAIN	LOSS	GAIN	LOSS	GAIN	LOSS	GAIN	LOSS	GAIN	LOSS	GAIN	LOSS	GAIN	LOSS	GAIN				
NORTH	21.3	16.0	26	553	415	0	0	0	0	0	0	0	0	0	0	0	0			
EAST	21.3	41.6	0	0	0	0	0	0	0	0	65	1383	2701	15	319	623	0	0	0	
SOUTH	21.3	24.9	0	0	0	0	0	0	41	872	1021	18	383	448	0	0	0	0	0	0
WEST	21.3	41.6	78	1660	3241	119	2532	4945	0	0	0	0	0	0	0	0	0	0	0	0
SKYLT.	37.2	101.5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
DOORS	25.2	4.3	0	0	0	15	379	64	0	0	0	0	0	0	40	1010	170	20	505	85
NET EXPOSED WALL	4.5	0.8	511	2280	384	460	2051	345	224	1000	168	267	1191	201	401	1789	301	345	1541	260
NET EXPOSED BSMT WALL ABOVE GR	3.6	0.6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
EXPOSED CLG	1.3	0.6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
NO ATTIC EXPOSED CLG	2.7	1.3	10	27	13	0	0	0	0	0	0	10	27	13	0	0	0	0	0	0
EXPOSED FLOOR	2.6	0.4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
BASEMENT/CRAWL HEAT LOSS			0			0			0			0			0			0		
SLAB ON GRADE HEAT LOSS			0			0			0			0			0			0		
SUBTOTAL HT LOSS			4520			4962			1872			2984			3118			2046		
SUB TOTAL HT GAIN			4053			5354			1189			3362			1095			345		
LEVEL FACTOR / MULTIPLIER	0.30	0.82	0.30			0.82			0.30			0.82			0.30			0.82		
AIR CHANGE HEAT LOSS			3706			4068			1535			2447			2556			1678		
AIR CHANGE HEAT GAIN			340			449			100			282			92			29		
DUCT LOSS			0			0			0			0			0			0		
DUCT GAIN			0			0			0			0			0			0		
HEAT GAIN PEOPLE	240		0			0			0			0			0			0		
HEAT GAIN APPLIANCES/LIGHTS			860			860			860			860			0			0		
TOTAL HT LOSS BTU/H			8226			9030			3407			5431			5674			3724		
TOTAL HT GAIN x 1.3 BTU/H			6828			8661			2793			5855			1542			486		

ROOM USE	WOB		BAS	
EXP. WALL	67		175	
CLG. HT.	10		10	
FACTORS				
GRS.WALL AREA	LOSS	GAIN	LOSS	GAIN
NORTH	21.3	16.0	0	0
EAST	21.3	41.6	0	0
SOUTH	21.3	24.9	0	0
WEST	21.3	41.6	0	0
SKYLT.	37.2	101.5	0	0
DOORS	25.2	4.3	3	64
NET EXPOSED WALL	4.5	0.8	153	3256
NET EXPOSED BSMT WALL ABOVE GR	3.6	0.6	0	0
EXPOSED CLG	1.3	0.6	0	0
NO ATTIC EXPOSED CLG	2.7	1.3	0	0
EXPOSED FLOOR	2.6	0.4	0	0
BASEMENT/CRAWL HEAT LOSS			0	0
SLAB ON GRADE HEAT LOSS			0	0
SUBTOTAL HT LOSS			1085	
SUB TOTAL HT GAIN			7152	
LEVEL FACTOR / MULTIPLIER				0.50
AIR CHANGE HEAT LOSS				2.52
AIR CHANGE HEAT GAIN				26650
DUCT LOSS				586
DUCT GAIN				0
HEAT GAIN PEOPLE	240		0	0
HEAT GAIN APPLIANCES/LIGHTS			0	0
TOTAL HT LOSS BTU/H			8238	30073
TOTAL HT GAIN x 1.3 BTU/H			8880	969

TOTAL HEAT GAIN BTU/H: 79382 TONS: 6.62 LOSS DUE TO VENTILATION LOAD BTU/H: 6156 STRUCTURAL HEAT LOSS: 109582 TOTAL COMBINED HEAT LOSS BTU/H: 115738



SITE NAME: PINE VALLEY PH 2
 BUILDER: GOLD PARK HOMES

OPT 2ND - ELEVATOR - WOB
 TYPE: 6001 - QUEENSLAND - ELEV C GFA: 5742

DATE Apr-22
 LO# 96176

WINTER NATURAL AIR CHANGE RATE 0.486
 SUMMER NATURAL AIR CHANGE RATE 0.162

HEAT LOSS AT °F. 76
 HEAT GAIN AT °F. 13

CSA-F280-12
 SB-12 PACKAGE A1

ROOM USE	MBR		ENS		BED-2		BED-3		BED-4		BED-5		ENS-2		ENS-3		ENS-4		ENS-5					
EXP. WALL	20		32		18		20		45		16		6		18		6		0					
CLG. HT.	10		9		9		10		10		9		9		9		9		9					
FACTORS																								
GRS.WALL AREA	200		288		162		200		450		144		54		162		54		0					
GLAZING	LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN		LOSS GAIN					
NORTH	21.3	16.0	0	0	0	0	38	809	607	18	383	288	0	0	0	0	0	0	0	0	0			
EAST	21.3	41.6	0	0	0	0	0	0	0	65	1383	2701	0	0	0	0	0	0	0	0	0			
SOUTH	21.3	24.9	0	0	0	22	468	548	0	0	0	18	383	448	19	404	473	0	0	0	0			
WEST	21.3	41.6	42	894	1745	8	170	332	0	0	0	0	0	0	0	0	0	0	0	0	0			
SKYLT.	37.2	101.5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
DOORS	25.2	4.3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
NET EXPOSED WALL	4.5	0.8	158	705	119	258	1151	194	124	553	93	117	522	88	367	1638	276	125	558	94	46	205	35	
NET EXPOSED BSMT WALL ABOVE GR	3.6	0.6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
EXPOSED CLG	1.3	0.6	380	488	223	240	308	141	438	562	257	323	415	190	348	447	204	232	298	136	66	85	39	
NO ATTIC EXPOSED CLG	2.7	1.3	0	0	0	0	0	0	0	0	0	55	151	69	55	151	69	0	0	0	0	0	0	
EXPOSED FLOOR	2.6	0.4	0	0	0	0	0	0	200	510	86	228	581	98	0	0	0	66	168	28	72	184	31	
BASEMENT/CRAWL HEAT LOSS	0		0		0		0		0		0		0		0		0		0		0		0	
SLAB ON GRADE HEAT LOSS	0		0		0		0		0		0		0		0		0		0		0		0	
SUBTOTAL HT LOSS	2087		2087		2098		2434		3436		4002		1260		629		1167		483		92		42	
SUB TOTAL HT GAIN	2087		1215		1044		3433		3699		703		229		603		283		283		42		42	
LEVEL FACTOR / MULTIPLIER	0.20 0.44		0.20 0.44		0.20 0.44		0.20 0.44		0.20 0.44		0.20 0.44		0.20 0.44		0.20 0.44		0.20 0.44		0.20 0.44		0.20 0.44		0.20 0.44	
AIR CHANGE HEAT LOSS	926		931		1081		1525		1777		559		279		518		215		41		41		41	
AIR CHANGE HEAT GAIN	175		102		87		288		310		59		19		51		24		4		4		4	
DUCT LOSS	0		0		351		496		0		0		91		169		0		0		0		0	
DUCT GAIN	0		0		223		482		0		0		111		151		0		0		0		0	
HEAT GAIN PEOPLE	240	2	480	0	0	1	240	0	1	240	0	1	240	0	0	0	0	0	0	0	0	0	0	
HEAT GAIN APPLIANCES/LIGHTS	860		860		860		860		860		860		860		860		860		860		860		860	
TOTAL HT LOSS BTU/H	3013		3029		3866		5457		5778		1819		998		1854		698		133		133		133	
TOTAL HT GAIN x 1.3 BTU/H	4682		1712		3190		6894		6641		2421		1585		2164		1517		1177		1177		1177	

ROOM USE	LAUN		HALL		DRESS	
EXP. WALL	0		18		38	
CLG. HT.	9		10		9	
FACTORS						
GRS.WALL AREA	0		180		342	
GLAZING	LOSS GAIN		LOSS GAIN		LOSS GAIN	
NORTH	21.3	16.0	0	0	27	575
EAST	21.3	41.6	0	0	0	0
SOUTH	21.3	24.9	0	0	0	0
WEST	21.3	41.6	0	0	12	255
SKYLT.	37.2	101.5	0	0	24	894
DOORS	25.2	4.3	0	0	30	757
NET EXPOSED WALL	4.5	0.8	0	0	106	473
NET EXPOSED BSMT WALL ABOVE GR	3.6	0.6	0	0	0	0
EXPOSED CLG	1.3	0.6	84	108	212	272
NO ATTIC EXPOSED CLG	2.7	1.3	0	0	50	137
EXPOSED FLOOR	2.6	0.4	0	0	0	0
BASEMENT/CRAWL HEAT LOSS	0		0		0	
SLAB ON GRADE HEAT LOSS	0		0		0	
SUBTOTAL HT LOSS	108		3470		2747	
SUB TOTAL HT GAIN	49		4660		1416	
LEVEL FACTOR / MULTIPLIER	0.20 0.44		0.20 0.44		0.20 0.44	
AIR CHANGE HEAT LOSS	48		1541		1219	
AIR CHANGE HEAT GAIN	4		391		119	
DUCT LOSS	0		0		0	
DUCT GAIN	0		0		0	
HEAT GAIN PEOPLE	240	0	0	0	0	0
HEAT GAIN APPLIANCES/LIGHTS	860		860		860	
TOTAL HT LOSS BTU/H	156		5011		3966	
TOTAL HT GAIN x 1.3 BTU/H	1187		6566		3113	

TOTAL HEAT GAIN BTU/H: 79382 TONS: 6.62 LOSS DUE TO VENTILATION LOAD BTU/H: 6156 STRUCTURAL HEAT LOSS: 109582 TOTAL COMBINED HEAT LOSS BTU/H: 115738



SITE NAME: PINE VALLEY PH 2
 BUILDER: GOLD PARK HOMES

OPT 2ND - ELEVATOR - WOB
 TYPE: 6001 - QUEENSLAND - ELEV C DATE: Apr-22

GFA: 5742 LO# 96176

FURNACE 1

HEATING CFM 1170 COOLING CFM 1170
 TOTAL HEAT LOSS 73,804 TOTAL HEAT GAIN 36,014
 AIR FLOW RATE CFM 15.85 AIR FLOW RATE CFM 32.49

furnace pressure 0.6
 furnace filter 0.05
 a/c coil pressure 0.2
 available pressure for s/a & r/a 0.35

FURNACE HEAT LOSS +
 HRV / ERV HEAT LOSS
 = 76882 BTUH

\$LENNOX
 ML196UH090XE36C
 FAN SPEED 90
 LOW 0
 MEDLOW 0
 MEDIUM 0
 MEDIUM HIGH 1170
 HIGH 1300

AFUE = 96 %
 INPUT (BTU/H) = 88,000
 OUTPUT (BTU/H) = **85,600**
 DESIGN CFM = **1170**
 CFM @ .6" E.S.P.
 TEMPERATURE RISE 68 °F

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	0	14	9
R/A	0	0	0	3	1

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5"Ø unless noted otherwise on layout.

RUN #	1	2	5	6	7	8	9	10	11	12	13	14	15	18	21	22	23	24
ROOM NAME	GREAT	GREAT	GREAT	KIT	KIT	KIT	KIT	DIN	DIN	LIBR	LIBR	LIBR	FOY	MUD	BAS	BAS	BAS	BAS
RM LOSS MBH.	2.74	2.74	2.74	2.26	2.26	2.26	2.26	1.70	1.70	1.81	1.81	1.81	5.67	3.72	4.26	4.26	4.26	4.26
CFM PER RUN HEAT	43	43	43	36	36	36	36	36	27	29	29	29	90	59	67	67	67	67
RM GAIN MBH.	2.28	2.28	2.28	2.17	2.17	2.17	2.17	1.40	1.40	1.95	1.95	1.95	1.54	0.49	1.09	1.09	1.09	1.09
CFM PER RUN COOLING	74	74	74	70	70	70	70	45	45	63	63	63	50	16	36	36	36	36
ADJUSTED PRESSURE	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.16	0.17	0.17	0.17	0.17	0.17
ACTUAL DUCT LGH.	74	89	72	67	59	45	46	46	10	22	27	31	40	48	82	56	65	71
EQUIVALENT LENGTH	140	130	170	160	170	170	110	120	150	150	110	120	140	150	140	120	150	150
TOTAL EFFECTIVE LENGTH	214	219	242	227	229	215	156	166	160	172	137	151	180	198	222	176	215	221
ADJUSTED PRESSURE	0.08	0.08	0.07	0.08	0.08	0.08	0.11	0.1	0.11	0.1	0.13	0.11	0.09	0.09	0.08	0.1	0.08	0.08
ROUND DUCT SIZE	6	6	6	6	6	6	6	5	5	5	5	5	6	5	5	5	5	5
HEATING VELOCITY (ft/min)	219	219	219	184	184	184	184	198	198	213	213	213	459	433	492	492	492	492
COOLING VELOCITY (ft/min)	377	377	377	357	357	357	357	330	330	463	463	463	255	117	264	264	264	264
OUTLET GRILL SIZE	4X10	4X10	4X10	4X10	4X10	4X10	4X10	4X10	3X10	3X10	3X10	3X10	4X10	3X10	3X10	3X10	3X10	3X10
TRUNK	A	A	A	A	A	A	B	C	C	D	D	D	D	C	B	B	A	A

RUN #	25	26	27	28	29
ROOM NAME	BAS	BAS	BAS	BAS	BAS
RM LOSS MBH.	4.26	4.26	4.26	4.26	4.26
CFM PER RUN HEAT	67	67	67	67	67
RM GAIN MBH.	1.09	1.09	1.09	1.09	1.09
CFM PER RUN COOLING	36	36	36	36	36
ADJUSTED PRESSURE	0.17	0.17	0.17	0.17	0.17
ACTUAL DUCT LGH.	39	44	23	41	58
EQUIVALENT LENGTH	140	160	100	130	170
TOTAL EFFECTIVE LENGTH	179	204	123	171	228
ADJUSTED PRESSURE	0.1	0.08	0.14	0.1	0.08
ROUND DUCT SIZE	5	5	5	5	5
HEATING VELOCITY (ft/min)	492	492	492	492	492
COOLING VELOCITY (ft/min)	264	264	264	264	264
OUTLET GRILL SIZE	3X10	3X10	3X10	3X10	3X10
TRUNK	C	D	D	D	A

SUPPLY AIR TRUNK SIZE										RETURN AIR TRUNK SIZE					
TRUNK	STATIC	ROUND	RECT	VELOCITY						TRUNK	STATIC	ROUND	RECT	VELOCITY	
CFM	PRESS.	DUCT	DUCT	(ft/min)						CFM	PRESS.	DUCT	DUCT	(ft/min)	
TRUNK A	402	0.07	10.3	12	x	8	603	TRUNK G	0	0.00	0	0	x	8	0
TRUNK B	170	0.08	7.2	8	x	8	383	TRUNK H	0	0.00	0	0	x	8	0
TRUNK C	788	0.07	13.3	16	x	12	591	TRUNK I	0	0.00	0	0	x	8	0
TRUNK D	378	0.08	9.7	12	x	8	567	TRUNK J	0	0.00	0	0	x	8	0
TRUNK E	0	0.00	0	0	x	8	0	TRUNK K	0	0.00	0	0	x	8	0
TRUNK F	0	0.00	0	0	x	8	0	TRUNK L	0	0.00	0	0	x	8	0

RETURN AIR #	1	2	3	BR														
AIR VOLUME	275	305	330	0	0	0	0	0	0	0	0	0	0	0	0	0	0	260
PLENUM PRESSURE	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15
ACTUAL DUCT LGH.	76	47	41	1	1	1	1	1	1	1	1	1	1	1	1	1	1	19
EQUIVALENT LENGTH	180	165	140	0	0	0	0	0	0	0	0	0	0	0	0	0	0	145
TOTAL EFFECTIVE LH	256	212	181	1	1	1	1	1	1	1	1	1	1	1	1	1	1	164
ADJUSTED PRESSURE	0.06	0.07	0.08	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	0.09	8.2
ROUND DUCT SIZE	9.3	9.3	9.3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	8
INLET GRILL SIZE	8	8	8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	8
	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
INLET GRILL SIZE	30	30	30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	24

SITE NAME: PINE VALLEY PH 2
 BUILDER: GOLD PARK HOMES

OPT 2ND - ELEVATOR - WOB
 TYPE: 6001 - QUEENSLAND - ELEV C DATE: Apr-22

GFA: 5742 LO# 96176

FURNACE 2

HEATING CFM 1270 COOLING CFM 1270
 TOTAL HEAT LOSS 35,779 TOTAL HEAT GAIN 42,849
 AIR FLOW RATE CFM 35.5 AIR FLOW RATE CFM 29.64

furnace pressure 0.6
 furnace filter 0.05
 a/c coil pressure 0.2
 available pressure for s/a & r/a 0.35

**FURNACE HEAT LOSS +
 HRV / ERV HEAT LOSS
 = 38857 BTUH**

**\$*LENNOX
 ML196UH070XE48B
 FAN SPEED 70
 LOW 0
 MEDLOW 1070
 MEDIUM 1270
 MEDIUM HIGH 1515
 HIGH 1595**

AFUE = 96 %
 INPUT (BTU/H) = 66,000
 OUTPUT (BTU/H) = **63,900**
 DESIGN CFM = **1270**
 CFM @ .6" E.S.P.
 TEMPERATURE RISE 47 °F

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	24	0	0
R/A	0	0	6	0	0

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5"Ø unless noted otherwise on layout.

RUN #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
ROOM NAME	MBR	MBR	MBR	ENS	ENS	BED-2	BED-2	ENS-2	BED-3	BED-3	BED-3	ENS-3	BED-4	BED-4	BED-4	ENS-5	ENS-4	BED-5	BED-5	LAUN	HALL	HALL	DRESS	DRESS
RM LOSS MBH.	1.00	1.00	1.00	2.27	0.76	1.93	1.93	1.00	1.82	1.82	1.85	1.93	1.93	1.93	0.13	0.70	0.91	0.91	0.16	2.51	2.51	1.98	1.98	1.98
CFM PER RUN HEAT	36	36	36	81	27	69	69	35	65	65	66	68	68	68	5	25	32	32	6	89	89	70	70	70
RM GAIN MBH.	1.56	1.56	1.56	1.28	0.43	1.59	1.59	1.59	2.30	2.30	2.16	2.21	2.21	2.21	1.18	1.52	1.21	1.21	1.19	3.28	3.28	1.56	1.56	1.56
CFM PER RUN COOLING	46	46	46	38	13	47	47	47	68	68	64	66	66	66	35	45	36	36	35	97	97	46	46	46
ADJUSTED PRESSURE	0.17	0.17	0.17	0.16	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.16	0.16	0.17	0.17
ACTUAL DUCT LGH.	67	72	83	75	69	85	95	102	79	85	91	86	37	30	42	32	24	28	67	82	34	48	91	90
EQUIVALENT LENGTH	150	160	220	180	180	160	170	180	170	180	170	160	170	150	140	200	210	180	180	190	110	140	160	170
TOTAL EFFECTIVE LENGTH	217	232	303	255	249	245	265	282	249	265	261	246	207	180	182	232	234	208	247	272	144	188	251	260
ADJUSTED PRESSURE	0.08	0.07	0.06	0.06	0.07	0.07	0.06	0.06	0.07	0.06	0.07	0.07	0.08	0.1	0.09	0.07	0.07	0.08	0.07	0.06	0.11	0.09	0.07	0.07
ROUND DUCT SIZE	6	6	6	6	4	6	6	5	6	6	6	6	5	5	5	4	5	4	4	6	6	6	6	6
HEATING VELOCITY (ft/min)	184	184	184	413	310	352	352	257	331	331	331	337	499	499	499	57	184	367	367	31	454	454	357	357
COOLING VELOCITY (ft/min)	235	235	235	194	149	240	240	345	347	347	347	326	485	485	485	402	330	413	413	178	495	495	235	235
OUTLET GRILL SIZE	4X10	4X10	4X10	4X10	3X10	4X10	4X10	3X10	4X10	4X10	4X10	4X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	4X10	4X10	4X10	4X10	4X10
TRUNK	B	B	A	B	B	A	A	A	C	C	C	C	D	D	D	C	C	C	B	A	D	D	A	A

RUN #	ROOM NAME	RM LOSS MBH.	CFM PER RUN HEAT	RM GAIN MBH.	CFM PER RUN COOLING	ADJUSTED PRESSURE	ACTUAL DUCT LGH.	EQUIVALENT LENGTH	TOTAL EFFECTIVE LENGTH	ADJUSTED PRESSURE	ROUND DUCT SIZE	HEATING VELOCITY (ft/min)	COOLING VELOCITY (ft/min)	OUTLET GRILL SIZE	TRUNK

SUPPLY AIR TRUNK SIZE										RETURN AIR TRUNK SIZE					
TRUNK	STATIC	ROUND	RECT	VELOCITY	TRUNK	STATIC	ROUND	RECT	VELOCITY	TRUNK	STATIC	ROUND	RECT	VELOCITY	
CFM	PRESS.	DUCT	DUCT	(ft/min)	CFM	PRESS.	DUCT	DUCT	(ft/min)	CFM	PRESS.	DUCT	DUCT	(ft/min)	
TRUNK A	355	0.06	10.2	10	x	10	511	TRUNK G	0	0.00	0	0	x	8	0
TRUNK B	567	0.06	12.2	14	x	10	583	TRUNK H	0	0.00	0	0	x	8	0
TRUNK C	890	0.06	14.4	18	x	12	593	TRUNK I	0	0.00	0	0	x	8	0
TRUNK D	382	0.08	9.8	12	x	8	573	TRUNK J	0	0.00	0	0	x	8	0
TRUNK E	0	0.00	0	0	x	8	0	TRUNK K	0	0.00	0	0	x	8	0
TRUNK F	0	0.00	0	0	x	8	0	TRUNK L	0	0.00	0	0	x	8	0

RETURN AIR #	1	2	3	4	5	6	BR
AIR VOLUME	230	115	260	185	115	365	0
PLENUM PRESSURE	0.15	0.15	0.15	0.15	0.15	0.15	0.15
ACTUAL DUCT LGH.	75	71	71	60	83	65	1
EQUIVALENT LENGTH	230	215	195	185	225	190	0
TOTAL EFFECTIVE LH	305	286	266	245	308	255	1
ADJUSTED PRESSURE	0.05	0.05	0.06	0.06	0.05	0.06	14.80
ROUND DUCT SIZE	9.1	7	9.1	8	7	10.3	0
INLET GRILL SIZE	8	8	8	8	8	8	0
INLET GRILL SIZE	X	X	X	X	X	X	X
INLET GRILL SIZE	30	14	30	24	14	30	0

TRUNK	STATIC	ROUND	RECT	VELOCITY			
CFM	PRESS.	DUCT	DUCT	(ft/min)			
TRUNK O	0	0.05	0	0	x	8	0
TRUNK P	0	0.05	0	0	x	8	0
TRUNK Q	0	0.05	0	0	x	8	0
TRUNK R	0	0.05	0	0	x	8	0
TRUNK S	0	0.05	0	0	x	8	0
TRUNK T	0	0.05	0	0	x	8	0
TRUNK U	0	0.05	0	0	x	8	0
TRUNK V	0	0.05	0	0	x	8	0
TRUNK W	550	0.05	12.6	14	x	10	566
TRUNK X	925	0.05	15.3	18	x	12	617
TRUNK Y	720	0.05	13.9	14	x	12	617
TRUNK Z	345	0.05	10.6	10	x	10	497
DROP	1270	0.05	17.3	24	x	12	635

TYPE: 6001 - QUEENSLAND - ELEV C
 SITE NAME: PINE VALLEY PH 2

LO # 96176
 OPT 2ND - ELEVATOR - WOB

RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY

COMBUSTION APPLIANCES 9.32.3.1(1)

a) Direct vent (sealed combustion) only

b) Positive venting induced draft (except fireplaces)

c) Natural draft, B-vent or induced draft gas fireplace

d) Solid Fuel (including fireplaces)

e) No Combustion Appliances

HEATING SYSTEM

Forced Air Non Forced Air

Electric Space Heat

HOUSE TYPE 9.32.1(2)

I Type a) or b) appliance only, no solid fuel

II Type I except with solid fuel (including fireplaces)

III Any Type c) appliance

IV Type I, or II with electric space heat

Other: Type I, II or IV no forced air

SYSTEM DESIGN OPTIONS O.N.H.W.P.

1 Exhaust only/Forced Air System

2 HRV with Ducting/Forced Air System

3 HRV Simplified/connected to forced air system

4 HRV with Ducting/non forced air system

Part 6 Design

TOTAL VENTILATION CAPACITY 9.32.3.3(1)

Basement + Master Bedroom	<u>2</u>	@ 21.2 cfm	<u>42.4</u>	cfm
Other Bedrooms	<u>4</u>	@ 10.6 cfm	<u>42.4</u>	cfm
Kitchen & Bathrooms	<u>6</u>	@ 10.6 cfm	<u>63.6</u>	cfm
Other Rooms	<u>5</u>	@ 10.6 cfm	<u>53.0</u>	cfm
Table 9.32.3.A.		TOTAL	<u>201.4</u>	cfm

PRINCIPAL VENTILATION CAPACITY REQUIRED 9.32.3.4.(1)

1	Bedroom	31.8	cfm
2	Bedroom	47.7	cfm
3	Bedroom	63.6	cfm
4	Bedroom	79.5	cfm
5	Bedroom	95.4	cfm
	TOTAL	95.4	cfm

SUPPLEMENTAL VENTILATION CAPACITY 9.32.3.5.

Total Ventilation Capacity	<u>201.4</u>	cfm
Less Principal Ventil. Capacity	<u>150</u>	cfm
Required Supplemental Capacity	<u>51.4</u>	cfm

PRINCIPAL EXHAUST FAN CAPACITY

Model: VANEE V150H Location: BSMT

150.0 cfm HVI Approved

PRINCIPAL EXHAUST HEAT LOSS CALCULATION

CFM		ΔT °F		FACTOR		% LOSS
150.0 CFM	X	76 F	X	1.08	X	0.25

SUPPLEMENTAL FANS BY INSTALLING CONTRACTOR

Location	Model	cfm	HVI	Sones
ENS	BY INSTALLING CONTRACTOR	50	<input checked="" type="checkbox"/>	3.5
ENS-2	BY INSTALLING CONTRACTOR	50	<input checked="" type="checkbox"/>	3.5
ENS-3	BY INSTALLING CONTRACTOR	50	<input checked="" type="checkbox"/>	3.5
ENS-4	BY INSTALLING CONTRACTOR	50	<input checked="" type="checkbox"/>	3.5

HEAT RECOVERY VENTILATOR 9.32.3.11.

Model: VANEE V150H INSTALL 2 HRV / ERV's

150 cfm high 35 cfm low

75 % Sensible Efficiency HVI Approved
 @ 32 deg F (0 deg C)

LOCATION OF INSTALLATION

Lot: Concession

Township: Plan:

Address:

Roll # Building Permit #

BUILDER: GOLD PARK HOMES

Name:

Address:

City:

Telephone #: Fax #:

INSTALLING CONTRACTOR

Name:

Address:

City:

Telephone #: Fax #:

DESIGNER CERTIFICATION

I hereby certify that this ventilation system has been designed in accordance with the Ontario Building Code.

Name: HVAC Designs Ltd.

Signature: *Michael O'Rourke*

HRAI # 001820

Date: April-22

CSA F280-12 Residential Heat Loss and Heat Gain Calculations																																																																
Formula Sheet (For Air Leakage / Ventilation Calculation)																																																																
LO#: 96176	Model: 6001 - QUEENSLAND - ELEV C	Builder: GOLD PARK HOMES	Date: 4/14/2022																																																													
Volume Calculation			Air Change & Delta T Data																																																													
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4">House Volume</th> </tr> <tr> <th>Level</th> <th>Floor Area (ft²)</th> <th>Floor Height (ft)</th> <th>Volume (ft³)</th> </tr> </thead> <tbody> <tr> <td>Bsmt</td> <td>2581</td> <td>10</td> <td>24777.6</td> </tr> <tr> <td>First</td> <td>2581</td> <td>11</td> <td>27358.6</td> </tr> <tr> <td>Second</td> <td>3175</td> <td>9</td> <td>28575</td> </tr> <tr> <td>Third</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td>Fourth</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td colspan="3" style="text-align: right;">Total:</td> <td>80,711.2 ft³</td> </tr> <tr> <td colspan="3" style="text-align: right;">Total:</td> <td>2285.5 m³</td> </tr> </tbody> </table>			House Volume				Level	Floor Area (ft ²)	Floor Height (ft)	Volume (ft ³)	Bsmt	2581	10	24777.6	First	2581	11	27358.6	Second	3175	9	28575	Third	0	9	0	Fourth	0	9	0	Total:			80,711.2 ft ³	Total:			2285.5 m ³	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width: 70%;">WINTER NATURAL AIR CHANGE RATE</td> <td style="width: 30%;">0.486</td> </tr> <tr> <td>SUMMER NATURAL AIR CHANGE RATE</td> <td>0.162</td> </tr> </table> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="5">Design Temperature Difference</th> </tr> <tr> <th></th> <th>Tin °C</th> <th>Tout °C</th> <th>ΔT °C</th> <th>ΔT °F</th> </tr> </thead> <tbody> <tr> <td>Winter DTDh</td> <td>22</td> <td>-20</td> <td>42</td> <td>76</td> </tr> <tr> <td>Summer DTDc</td> <td>24</td> <td>31</td> <td>7</td> <td>13</td> </tr> </tbody> </table>		WINTER NATURAL AIR CHANGE RATE	0.486	SUMMER NATURAL AIR CHANGE RATE	0.162	Design Temperature Difference						Tin °C	Tout °C	ΔT °C	ΔT °F	Winter DTDh	22	-20	42	76	Summer DTDc	24	31	7	13
House Volume																																																																
Level	Floor Area (ft ²)	Floor Height (ft)	Volume (ft ³)																																																													
Bsmt	2581	10	24777.6																																																													
First	2581	11	27358.6																																																													
Second	3175	9	28575																																																													
Third	0	9	0																																																													
Fourth	0	9	0																																																													
Total:			80,711.2 ft ³																																																													
Total:			2285.5 m ³																																																													
WINTER NATURAL AIR CHANGE RATE	0.486																																																															
SUMMER NATURAL AIR CHANGE RATE	0.162																																																															
Design Temperature Difference																																																																
	Tin °C	Tout °C	ΔT °C	ΔT °F																																																												
Winter DTDh	22	-20	42	76																																																												
Summer DTDc	24	31	7	13																																																												
5.2.3.1 Heat Loss due to Air Leakage			6.2.6 Sensible Gain due to Air Leakage																																																													
$HL_{airb} = LR_{airh} \times \frac{V_b}{3.6} \times DTD_h \times 1.2$ <p>0.486 x 634.86 x 42 °C x 1.2 = 15621 W</p> <p>= 53299 Btu/h</p>			$HG_{salb} = LR_{airc} \times \frac{V_b}{3.6} \times DTD_c \times 1.2$ <p>= 0.162 x 634.86 x 7 °C x 1.2 = 876 W</p> <p>= 2989 Btu/h</p>																																																													
5.2.3.2 Heat Loss due to Mechanical Ventilation			6.2.7 Sensible heat Gain due to Ventilation																																																													
$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E) \times 2 \text{ HRV / ERV's}$ <p>300 CFM x 76 °F x 1.08 x 0.25 = 6156 Btu/h</p>			$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E)$ <p>300 CFM x 13 °F x 1.08 x 0.25 = 1,037 Btu/h</p>																																																													
5.2.3.3 Calculation of Air Change Heat Loss for Each Room (Floor Multiplier Section)																																																																
$HL_{airr} = Level \ Factor \times HL_{airbv} \times \{ (HL_{agcr} + HL_{bgcr}) \div (HL_{agclevel} + HL_{bgclevel}) \}$																																																																
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Level</th> <th>Level Factor (LF)</th> <th>HLairve Air Leakage + Ventilation Heat Loss (Btu/h)</th> <th>Level Conductive Heat Loss: (HL_{level})</th> <th>Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>0.5</td> <td rowspan="5" style="text-align: center;">53,299</td> <td>10,576</td> <td>2.520</td> </tr> <tr> <td>2</td> <td>0.3</td> <td>19,503</td> <td>0.820</td> </tr> <tr> <td>3</td> <td>0.2</td> <td>24,012</td> <td>0.444</td> </tr> <tr> <td>4</td> <td>0</td> <td>0</td> <td>0.000</td> </tr> <tr> <td>5</td> <td>0</td> <td>0</td> <td>0.000</td> </tr> </tbody> </table>					Level	Level Factor (LF)	HLairve Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{level})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)	1	0.5	53,299	10,576	2.520	2	0.3	19,503	0.820	3	0.2	24,012	0.444	4	0	0	0.000	5	0	0	0.000																																		
Level	Level Factor (LF)	HLairve Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{level})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)																																																												
1	0.5	53,299	10,576	2.520																																																												
2	0.3		19,503	0.820																																																												
3	0.2		24,012	0.444																																																												
4	0		0	0.000																																																												
5	0		0	0.000																																																												
<p>*HLairbv = Air leakage heat loss + ventilation heat loss *For a balanced or supply only ventilation system HLairve = 0</p>																																																																
				Michael O'Rourke BCIN# 19669 																																																												

HEAT LOSS AND GAIN SUMMARY SHEET

MODEL: 6001 - QUEENSLAND - ELEV C	OPT 2ND - ELEVATOR - WOB	BUILDER: GOLD PARK HOMES
SFQT: 5742	LO# 96176	SITE: PINE VALLEY PH 2

DESIGN ASSUMPTIONS

HEATING	°F	COOLING	°F
OUTDOOR DESIGN TEMP.	-4	OUTDOOR DESIGN TEMP.	88
INDOOR DESIGN TEMP.	72	INDOOR DESIGN TEMP. (MAX 75°F)	75
		WINDOW SHGC	0.50

BUILDING DATA

ATTACHMENT:	DETACHED	# OF STORIES (+BASEMENT):	3
FRONT FACES:	EAST	ASSUMED (Y/N):	Y
AIR CHANGES PER HOUR:	3.57	ASSUMED (Y/N):	Y
AIR TIGHTNESS CATEGORY:	AVERAGE	ASSUMED (Y/N):	Y
WIND EXPOSURE:	SHELTERED	ASSUMED (Y/N):	Y
HOUSE VOLUME (ft ³):	80711.2	ASSUMED (Y/N):	Y
INTERNAL SHADING:	BLINDS/CURTAINS	ASSUMED OCCUPANTS:	6
INTERIOR LIGHTING LOAD (Btu/h/ft ²):	1.65	DC BRUSHLESS MOTOR (Y/N):	Y
FOUNDATION CONFIGURATION	BCIN_1	DEPTH BELOW GRADE:	8.1 ft
LENGTH: 66.0 ft	WIDTH: 55.0 ft	EXPOSED PERIMETER:	175.0 ft
WOB INSULATION CONFIGURATION	SCB_9	WOB EXPOSED PERIMETER	67.0 ft

2012 OBC - COMPLIANCE PACKAGE

Component	Compliance Package	
	A1	
	Nominal	Min. Eff.
Ceiling with Attic Space Minimum RSI (R)-Value	60	59.22
Ceiling Without Attic Space Minimum RSI (R)-Value	31	27.65
Exposed Floor Minimum RSI (R)-Value	31	29.80
Walls Above Grade Minimum RSI (R)-Value	22	17.03
Basement Walls Minimum RSI (R)-Value	20 ci	21.12
Below Grade Slab Entire surface > 600 mm below grade Minimum RSI (R)-Value	-	-
Edge of Below Grade Slab ≤ 600 mm Below Grade Minimum RSI (R)-Value	10	10
Heated Slab or Slab ≤ 600 mm below grade Minimum RSI (R)-Value	10	11.13
Windows and Sliding Glass Doors Maximum U-Value	0.28	-
Skylights Maximum U-Value	0.49	-
Space Heating Equipment Minimum AFUE	0.96	-
HRV Minimum Efficiency	75%	-
Domestic Hot Water Heater Minimum EF	0.8	-

INDIVIDUAL BCIN: 19669
MICHAEL O'ROURKE

Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description		
Province:	Ontario	
Region:	Vaughan (Woodbridge)	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Floor Length (m):	4.9	<p>Insulation Configuration</p>
Floor Width (m):	16.8	
Exposed Perimeter (m):	53.3	
Wall Height (m):	2.9	
Depth Below Grade (m):	2.19	
Window Area (m ²):	0.3	
Door Area (m ²):	1.9	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Foundation Loads		
Heating Load (Watts):	836	

TYPE: 6001 - QUEENSLAND - ELEV C
 LO# 96176

OPT 2ND - ELEVATOR - WOB

Residential Slab on Grade Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description		
Province:	Ontario	
Region:	Vaughan (Woodbridge)	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Length (m):	1.8	
Width (m):	16.8	
Exposed Perimeter (m):	20.4	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Results		
Heating Load (Watts):	318	

TYPE: 6001 - QUEENSLAND - ELEV C
 LO# 96176

OPT 2ND - ELEVATOR - WOB

Air Infiltration Residential Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description				
Province:	Ontario			
Region:	Vaughan (Woodbridge)			
Weather Station Location:	Open flat terrain, grass			
Anemometer height (m):	10			
Local Shielding				
Building Site:	Suburban, forest			
Walls:	Heavy			
Flue:	Heavy			
Highest Ceiling Height (m):	11.95			
Building Configuration				
Type:	Detached			
Number of Stories:	Two			
Foundation:	Full			
House Volume (m ³):	2285.5			
Air Leakage/Ventilation				
Air Tightness Type:	Present (1961-) (3.57 ACH)			
Custom BDT Data:	ELA @ 10 Pa.	3046.6 cm ²		
	3.57	ACH @ 50 Pa		
Mechanical Ventilation (L/s):	Total Supply	Total Exhaust		
	70.8	70.8		
Flue Size				
Flue #:	#1	#2	#3	#4
Diameter (mm):	0	0	0	0
Natural Infiltration Rates				
Heating Air Leakage Rate (ACH/H):	0.486			
Cooling Air Leakage Rate (ACH/H):	0.162			

TYPE: 6001 - QUEENSLAND - ELEV C
 LO# 96176

OPT 2ND - ELEVATOR - WOB

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD. AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.


INSTALLATION TO COMPLY WITH THE LATEST ONTARIO BUILDING CODE. ALL SUPPLY BRANCH OUTLETS SHALL BE EQUIPPED WITH MANUAL BALANCING DAMPER. DUCTWORK WHICH PASSES THROUGH THE GARAGE OR UNHEATED SPACES SHALL BE ADEQUATELY INSULATED AND GAS-PROOFED

ALL S/A DIFFUSERS 4"x10" UNLESS NOTED OTHERWISE ON LAYOUT. ALL S/A RUNS 5"Ø UNLESS NOTED OTHERWISE ON LAYOUT. UNDERCUT DOORS 1" min. FOR R/A

FURNACE 1 (F-1)
 LENNOX ML196UH090XE36C
 85600 BTU/H OUTPUT
 3.0 TONS A/C @ 1170 cfm

FURNACE 2 (F-2)
 LENNOX ML196UH070XE48B
 63900 BTU/H OUTPUT
 3.5 TONS A/C @ 1270 cfm

	S/A	R/A	FANS
2ND	22	6	7
1ST	14	3	2
BAS	9	1	0



BASEMENT W/ ELEVATOR PLAN, EL. 'C'

	4X10 SUPPLY GRILLE
	14X8 RETURN GRILLE
	4X10 SUPPLY GRILLE WITH BOOT
	30X8 RETURN GRILLE
	SUPPLY DUCTWORK
	RETURN DUCTWORK
	EXHAUST FAN
	LOW WALL
	HIGH WALL

I, THE DESIGNER, HEREBY CERTIFY THAT I AM A REGISTERED PROFESSIONAL ENGINEER IN THE PROVINCE OF ONTARIO AND AM QUALIFIED UNDER DIVISION 1.2 OF THE REGULATION.

1. ISSUED FOR PERMIT	APRIL 2022	EG
NO. Revision	Date	By

SB-12 PACKAGE **A1**

HVAC DESIGNS LTD.
 375 Finley Ave - Unit 202 - Ajax, Ontario L1S 2E2
 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375
 Email: info@hvacedesigns.ca
 Web: www.hvacedesigns.ca
 Specializing in Residential Mechanical Design Services

Client: **GOLDPARK HOMES**
 Project Name: **PINE VALLEY PH2**
 Home Name: **VAUGHAN, ONTARIO**
6001 - QUEENSLAND - ELEV C
 OPT 2ND - ELEVATOR - WOB
 5742 SQFT


Sheet Title:	BASEMENT HVAC LAYOUT	
Drawn By:	EG	Checked By: MO
Scale:	3/16"=1'-0"	
Date:	APRIL 2022	
LD #	96176	1

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD. © AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

INSTALLATION TO COMPLY WITH THE LATEST ONTARIO BUILDING CODE. ALL SUPPLY BRANCH OUTLETS SHALL BE EQUIPPED WITH MANUAL BALANCING DAMPER. DUCTWORK WHICH PASSES THROUGH THE GARAGE OR UNHEATED SPACES SHALL BE ADEQUATELY INSULATED AND GAS-PROOFED

ALL S/A DIFFUSERS "4x10" UNLESS NOTED OTHERWISE ON LAYOUT. ALL S/A RUNS 5"Ø UNLESS NOTED OTHERWISE ON LAYOUT. UNDERCUT DOORS 1" min. FOR R/A

	S/A	R/A	FANS
2ND	22	6	7
1ST	14	3	2
BAS	9	1	0



GROUND FLOOR W/ ELEVATOR PLAN, EL.'C'

	4X10 SUPPLY GRILLE
	14X8 RETURN GRILLE
	4X10 SUPPLY GRILLE (W/ BOOT)
	30X8 RETURN GRILLE
	SUPPLY DUCTWORK
	RETURN DUCTWORK
	EXHAUST FAN
	LW LOW WALL
	HW HIGH WALL

I, THE DESIGNER, HEREBY DECLARE THAT I AM A REGISTERED PROFESSIONAL ENGINEER IN THE PROVINCE OF ONTARIO AND AM QUALIFIED TO BE RESPONSIBLE FOR THE DESIGN WORK AND AM NOT PROVIDING THESE SERVICES AS AN AGENT FOR THE REGISTERED PROFESSIONAL ENGINEER.

1 ISSUED FOR PERMIT APRIL 2022 EG

SB-12 PACKAGE A1

HVAC DESIGNS LTD.
 375 Finley Ave - Unit 202 - Ajax, Ontario L1S 2E2
 Tel: 905.619.2300 - 905.420.5300 Fax: 905.619.2375
 Email: info@hvacadesigns.ca
 Web: www.hvacadesigns.ca
 Specializing in Residential Mechanical Design Services

Client: GOLDPARK HOMES
 Project: PINE VALLEY PH2
 Name: VAUGHAN, ONTARIO
 6001 - QUEENSLAND - ELEV C
 OPT 2ND - ELEVATOR - WOB
 5742 SQFT


Sheet Title: FIRST FLOOR HVAC LAYOUT
 Drawn By: EG
 Scale: 3/16"=1'-0"
 Date: APRIL 2022
 LO #: 96176

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD. AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

INSTALLATION TO COMPLY WITH THE LATEST ONTARIO BUILDING CODE. ALL SUPPLY BRANCH OUTLETS SHALL BE EQUIPPED WITH MANUAL BALANCING DAMPER. DUCTWORK WHICH PASSES THROUGH THE GARAGE OR UNHEATED SPACES SHALL BE ADEQUATELY INSULATED AND GAS-PROOFED

ALL S/A DIFFUSERS 4x10" UNLESS NOTED OTHERWISE ON LAYOUT. ALL S/A RUNS 5"Ø UNLESS NOTED OTHERWISE ON LAYOUT. UNDERCUT DOORS 1" min. FOR R/A

	S/A	R/A	FANS
2ND	22	6	7
1ST	14	3	2
BAS	9	1	0



	4X10 SUPPLY GRILLE
	14X8 RETURN GRILLE
	4X10 SUPPLY GRILLE WITH BOOT
	30X8 RETURN GRILLE
	SUPPLY DUCTWORK
	RETURN DUCTWORK
	EXHAUST FAN
	LW LOW WALL
	HW HIGH WALL

I, THE CLIENT, HEREBY RELEASES AND ACCEPTS RESPONSIBILITY FOR THE DESIGN WORK AND ANY MODIFICATIONS THEREAFTER EXCEPT AS NOTED ON THIS DRAWING.

1. ISSUED FOR PERMIT	APRIL 2022	EG
NO. Revision	Date	By

SB-12 PACKAGE **A1**

HVAC DESIGNS LTD.
 375 Finley Ave - Unit 202 - Ajax, Ontario L1S 2E2
 Tel: 905.619.2300 - 905.420.5300 Fax: 905.619.2375
 Email: info@hvacedesigns.ca
 Web: www.hvacedesigns.ca
 Specializing in Residential Mechanical Design Services

Client: **GOLDPARK HOMES**
 Project Name: **PINE VALLEY PH2 VAUGHAN, ONTARIO**
6001 - QUEENSLAND - ELEV C
 OPT 2ND - ELEVATOR - WOB
 5742 SQFT

Sheet Title: SECOND FLOOR HVAC LAYOUT	Checked By: MO	Sheet No.: 3
Drawn By: EG	Scale: 3/16"=1'-0"	Date: APRIL 2022
LO # 96176		