



Specifications for Project

Stefano Breda

Location

Vaughan

905-303-6909



REMINDER: To ensure a smooth project it is the responsibility of the homeowner / purchaser of appliances for this project to share all the attached specifications to ensure the cabinet provider, contractor, or any other tradesperson have all the information required to complete their work accurately.

Specifications are subject to change. If any tradesperson has questions regarding the attached specifications please contact our sales associate.

Powered by SteelCod

PV2-04-002

04/03/24

A handwritten signature in blue ink, possibly reading "SZ", enclosed within a red circular stamp.

A handwritten signature in blue ink, possibly reading "NB", enclosed within a red circular stamp.

Stefano Breda



Coast Appliances

coastappliances.com

Andrew Haidari

Commercial Sales Representative
905-303-6909

Search **20240328141026268SC**
Version 1.1

Thu, Mar 28, 2024
10:10 AM EDT

To ensure a smooth project it is the responsibility of the homeowner / purchaser of appliances for this project to share all the attached specifications to ensure the cabinet provider, contractor, or any other tradesperson have all the information required to complete their work accurately.

Specifications are subject to change. If any tradesperson has questions regarding the attached specifications please contact our sales associate.



enterprise.steelcod.com/sp/csta/3AATNJB

Contents

Page no.

WM6500HBA

4-7

LG Washer

5.8 cu. ft. Mega Capacity Smart Front Load Energy Star Washer with TurboWash® 360° and AI DD® Built-In Intelligence

DLEX6500B

8-12

LG Dryer

7.4 cu. ft. Capacity Energy Star Smart Front Load Dryer with AI Sensor Dry & TurboSteam®

G 7366 SCVi

13-14

Miele Dishwasher

G 7366 SCVi 24" Fully Integrated Dishwasher

CL3650UID/O/L

15-27

Sub-Zero Refrigeration

36" Classic Over-and-Under Refrigerator/Freezer with Internal Dispenser - Panel Ready

CI30460C/B

28-31

Note about page numbers:

Because the original manufacturer's documents are not altered in any way, the page numbers displayed on the page may not correspond to the page number within this package.

All specifications are intended for initial planning purposes only.

Manufacturers reserve the right to change specifications at any time without notice. Always consult the installation instructions found on the manufacturer's website or included with the appliances before installation.

04/03/24 -

Wolf Cooktop

30" Contemporary Induction Cooktop

MDD30CM/B/TH

32-35

Wolf Microwave

30" M Series Contemporary Drop-down Door
Microwave Oven

SO3050CM/B

36-39

Wolf Wall Oven

30" M Series Contemporary Built-In Single
Oven

SU2230X

40-41

Sirius Ventilation


30" Wall Hood

Note about page numbers:

Because the original manufacturer's documents are not altered in any way, the page numbers displayed on the page may not correspond to the page number within this package.

All specifications are intended for initial planning purposes only.

Manufacturers reserve the right to change specifications at any time without notice. Always consult the installation instructions found on the manufacturer's website or included with the appliances before installation.

04/03/24 



WM6500H


5.8 cu. ft. Mega Capacity Smart Front Load
 Energy Star Washer with TurboWash®
 360° and AI DD® Built-In Intelligence

5.8 cu. ft. Mega Capacity
 Digital Dial Control with LCD Display & Touch Button Control Panel
 TurboWash® 360° Technology
 AI DD®: AI Fabric and Weight Sensors with Smart Pairing
 LG ThinQ® Technology
 Allergiene® Cycle
 Cold Wash Technology
 NeveRust® Stainless Steel Drum
 ENERGY STAR® Certified & ENERGY STAR Most Efficient
 Direct Drive Motor 10-Year Limited Warranty

AVAILABLE COLOURS



BLACK STEEL



Proactive Smart Alerts to Keep Your Appliances Running Smoothly

ThinQ Care

- Preventative Alerts help you stay a step ahead of potential issues to find proactive solutions before problems arise.
- Avoid preventable repairs and service calls with real-time diagnostics for a hassle-free experience.
- Integrated within LG's ThinQ app—a smart home hub for managing your smart devices and appliances.

SUMMARY

| | |
|-------------------------|------------------|
| Type | Front Load Dryer |
| Capacity (cu. ft.) | 5.8 cu. ft. |
| Matching Electric Dryer | DLEX6500B |
| Color | Black Steel (B) |

APPEARANCE

| | |
|---------------|-----|
| LCD Display | Yes |
| Touch Buttons | Yes |
| Dial-A-Cycle® | Yes |

ENERGY

| | |
|-----------------------------|-------|
| ENERGY STAR® Most Efficient | Yes |
| ENERGY STAR® Certified | Yes |
| CEE Tier | Tier2 |
| IMEF | 2.92 |
| IWF | 3.0 |

WASH PROGRAMS

| | |
|-----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| No. of Programs | 25 |
| Wash Programs | Normal, AI Wash, Bedding, Delicates, Towels, Quick Wash, Heavy Duty, Allergiene®, Perm. Press, Tub Clean, Bright Whites™, Sanitary, Rinse+Spin, Spin Only, Hand/Wool, Active Wear, Swimwear, Kids Wear, Jeans, Dresses, Color Care, Sweat Stains, Small Load, Large Load, X Large Load |

WASH OPTIONS

| | |
|----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| No. of Options | 15 |
| Options | TurboWash®, Steam, Fresh Care, Pre-wash, Remote Start, Delay Wash, Wi-Fi, Add Item, Extra Rinse, Control Lock, Drum Light, ColdWash, Signal, Cycle List Edit, Cycle Optimization |

WASH DETAILS

| | |
|-------------------------|------------------------------------|
| No. of Wash/Rinse Temps | 5 |
| Wash/Rinse Temps | Ex. Hot, Hot, Warm, Cold, Tap Cold |
| No. of Spin Speeds | 5 |

| | |
|--------------------|--------------------------------------|
| Spin Speeds | Ex. High, High, Medium, Low, No Spin |
| Max RPM | 1300 |
| Water Levels | Load Sensing |
| No. of Soil Levels | 5 |

FABRIC CARE FEATURES

| | |
|----------------------------|-----|
| AI DD® | Yes |
| TurboWash® 360° Technology | Yes |
| Steam Technology | Yes |
| Allergiene® Cycle | Yes |
| Sanitary Cycle | Yes |
| Cold Wash Option | Yes |

CONVENIENCE FEATURES

| | |
|----------------------------------------------|-----|
| Vibration Sensing (Cabinet Vibration Sensor) | Yes |
| TrueBalance® Anti-Vibration System | Yes |

| | |
|---------------------|-------------------------------------------------------------------------|
| 4 Tray Dispenser | Prewash, Main Wash (with liquid detergent cup), Bleach, Fabric Softener |
| End of Cycle Signal | Yes |
| LoadSense | Yes |
| Control Lock | Yes |
| Auto Suds Removal | Yes |
| Leveling Legs | 4 Adjustable Legs |
| Drum Light | Yes |

ThinQ® TECHNOLOGY

| | |
|-------------------|-----|
| Smart Diagnosis | Yes |
| Wi-Fi | Yes |
| Energy Monitoring | Yes |
| Tub Clean Coach | Yes |

MOTOR AND AGITATOR

| | |
|------------|-----------------------------|
| Motor Type | Inverter Direct Drive Motor |
| Axis | Horizontal |

MATERIALS AND FINISHES

| | |
|--------------------------------|-----|
| NeveRust® Stainless Steel Drum | Yes |
|--------------------------------|-----|

| | |
|----------------------|--------------------------|
| Cabinet | Painted Steel (One unit) |
| Control Panel | |
| Top Plate | Painted Steel |
| Door / Rim | Glass / Shiny Rose Gold |
| Door Cover | Tempered Glass Door |
| All Available Colors | Black Steel (B) |

CERTIFICATION

| | |
|---------------|-----|
| Asthma Canada | Yes |
|---------------|-----|

POWER SOURCE

| | |
|-------------------------|---------------|
| Ratings | UL Listed |
| Electrical Requirements | 120V, 10 Amps |
| Type | Electric |

OPTIONS/ACCESSORIES

| | |
|--------------------------------------|------------------------------------------------------|
| Pedestal | WDP68 |
| Pedestal (WxHxD) | 27" x 13 5/8" x 25 3/8" (43 7/8" D with door open) |
| LG Sidekick™ Pedestal Washer | WD300C8 |
| LG Sidekick™ Pedestal Washer (WxHxD) | 27" x 14 1/8" x 30 3/4" (50 1/2" D with drawer open) |
| Stacking Kit | KSTK4 |

DIMENSIONS

| | |
|-------------------------|-----------------------------|
| Product (WxHxD) | 27" x 39" x 33 1/8" |
| Depth with Door Open | 57 3/4" |
| Carton (WxHxD) | 29 1/2" x 42 1/8" x 34 1/4" |
| Weight (Product/Carton) | 202.6 / 216.5 lbs. |

LIMITED WARRANTY

| | |
|--------------------|----------|
| Parts & Labor | 1 Year |
| Drum | 3 Years |
| Direct Drive Motor | 10 Years |

UPC CODES

| | |
|-------------------|--------------|
| WM6500HBA (Black) | 195174052921 |
|-------------------|--------------|

04/03/24
 SB
 TB

⚠ WARNING

- Certain internal parts are intentionally not grounded and may present a risk of electric shock only during servicing. Service personnel- Do not contact the following parts while the appliance is energized: pump, valve, motor, control board.

Tools Needed

- ① Pliers
- ② Flat-Blade Screwdriver
- ③ Level

Choosing the Proper Location

Check the following requirements for the install location before installing the washer.

- Allow for sufficient space between the walls and the washer for installation.
- Make sure that the floor is clean, dry and free of dust, dirt, water and oil so the leveling feet cannot slide easily. Leveling feet that can move or slide on the floor can contribute to excess vibration and noise.
- If the floor has too much flex, reinforce it to make it more rigid. If the floor is not solid, it may cause severe vibration and noise.
- If a drain pan must be used, take extra care to follow the instructions provided with the drain pan and make sure the leveling feet are adjusted for firm and even contact with the pan. Use of drain pans and failure to properly level the washer may result in increased vibration and noise during operation.

Power Outlet

- The power outlet must be within **60 inches (1.5 m)** of either side of the washer.
- Position the washer so that the outlet and plug are easily accessible.
- Do not overload the outlet with more than one appliance.
- The outlet must be grounded in accordance with current electrical wiring codes and regulations.
- Use a time-delay fuse or circuit breaker.


- It is the personal responsibility and obligation of the washer owner to have a proper outlet installed by a qualified electrician.

Flooring

- To minimize noise and vibration, install the washer on a level, solidly constructed floor capable of supporting the washer without flexing or bouncing.
- The washer must be installed on firm flooring to minimize vibration during the spin cycle. Concrete flooring is best, but a wood floor is sufficient, provided it is built to FHA standards.
- The floor under the washer must not slope more than 1 inch (2.5 cm) from front to back or side to side.
- Installing on carpeting and soft tile surfaces is not recommended.
- Never install the washer on a platform or weakly supported structure.

Floor Installation

To ensure sufficient clearance for water inlet hoses, drain hose and airflow, allow minimum clearances of at least **1 inch (2.5 cm)** at the sides and **4 inches (10 cm)** behind the washer. Be sure to allow for wall, door, or floor moldings that may increase the required clearances.



| Dimensions and Clearances | | |
|---------------------------|-----------------|--------------------|
| Model | WM5500H*A | WM6500H*A |
| A | 55" (139.6 cm) | 57 3/4" (146.6 cm) |
| B | 30 1/4" (77 cm) | 33 1/8" (84 cm) |
| C | 4" (10 cm) | |


04/03/24 SB

WB

| Dimensions and Clearances | | |
|---------------------------|---------------|-----------|
| Model | WM5500H*A | WM6500H*A |
| D | 1" (2.5 cm) | |
| E | 27" (70 cm) | |
| F | 1/4" (0.5 cm) | |

Stacking or Pedestal Installation

The washer can be stacked under a dryer or on top of a pedestal or pedestal washer.



| Dimensions and Clearances | | |
|---------------------------|--------------------|-----------------|
| Model | WM5500H*A | WM6500H*A |
| A | 30 1/4" (77 cm) | 33 1/8" (84 cm) |
| B | 4" (10 cm) | |
| C | 1" (2.5 cm) | |
| D | 27" (70 cm) | |
| E | 77 1/2" (196.8 cm) | |
| F | 1/4" (0.5 cm) | |

NOTE

- Refer to the instructions packaged with the optional pedestal kit before stacking appliance on pedestal.
- Do not use a drain pan with a pedestal or pedestal washer installation as it can block the drawer. Using a drain pan may result in increased vibration and noise during operation.

Unpacking and Removing Shipping Material

Remove all shipping materials from the washer for proper operation and inspect it for shipping damage.

CAUTION


- Failure to remove shipping materials can cause excessive noise and vibration.

Unpacking Shipping Material

*Some models do not ship with drum support.


Lift the washer off the foam base.

- After removing the carton and shipping material, lift the washer off the foam base.
- Make sure the plastic drum support ①* comes off with the base and is not stuck to the bottom of the washer.
- If you must lay the washer down to remove the carton base ②, always protect the side of the washer and lay it carefully on its side. Do not lay the washer on its front or back.



Removing Shipping Material

- Remove the bolt assemblies.
 - Starting with the bottom two shipping bolts ③, use the included wrench to fully loosen all 4 shipping bolts by turning them counterclockwise.
 - Remove the bolt assemblies (bolts and retainers) by wiggling them slightly while pulling them out.




- Install the hole caps.
 - Locate the hole caps ④ included in the accessory pack or attached to the back of

04/03/24 SS MB


14 INSTALLATION

hoses with the provided tie strap ③ (ribbed side on inside).




Using the Laundry Tub to Drain


- 1 Clip the end of the hose into the elbow bracket.
 - Connect the elbow bracket ① within **4 inches (10 cm)** of the end of the drain hose. If the drain hose is extended more than **4 inches (10 cm)** beyond the end of the elbow bracket, mold or microorganisms could spread to the inside of the washer.



- 2 Hang the end of the drain hose over the side of the laundry tub.



- 3 Use the provided tie strap to secure the drain hose in place.



Leveling the Washer

The drum of the washer spins at very high speeds. To minimize vibration, noise, and unwanted movement, the floor must be a solid, level surface.

CAUTION


- Using the washer without leveling it may cause excess vibration and noise, leading to a washer malfunction.
- Adjust the leveling feet only as far as necessary to level the washer. Extending the leveling feet more than necessary can cause the washer to vibrate.

NOTE

- Before installing the washer, make sure that the floor is clean, dry and free of dust, dirt, water and oil so the washer feet cannot slide easily. Feet that move or slide on the floor can contribute to excessive vibration and noise.

How to Level the Washer

- 1 Position the washer in its final location.
 - Take special care not to pinch, strain, or crush the water and drain hoses. If you have a carpenter's level ①, you can use it to check that the washer is level. The slope beneath the washer should not exceed **1 inch**, and all 4 leveling feet must rest firmly on the floor.



04/03/24  

LG LAUNDRY

DLEX6500B


7.4 cu. ft. Capacity Energy Star Smart Front Load Dryer with AI Sensor Dry & TurboSteam®

7.4 cu. ft. Ultra Large Capacity
 Digital Dial Control with LCD Display & Touch Button Control Panel
 AI Sensor Dry with Smart Pairing
 TurboSteam®, SteamFresh®, and SteamSanitary® Technology
 Wrinkle Care Option
 LG ThinQ® Technology with ThinQ Care
 FlowSense® Duct Clogging Indicator
 Tempered Glass Door (Reversible)
 NeveRust® Stainless Steel Drum
 ENERGY STAR® Certified

AVAILABLE COLOURS



BLACK STEEL



Proactive Smart Alerts to Keep Your Appliances Running Smoothly

ThinQ Care

- Preventative Alerts help you stay a step ahead of potential issues to find proactive solutions before problems arise.
- Avoid preventable repairs and service calls with real-time diagnostics for a hassle-free experience.
- Integrated within LG's ThinQ app—a smart home hub for managing your smart devices and appliances.

SUMMARY

| | |
|-----------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Type | Front Load Dryer |
| Vent Type | Vented |
| Dryer Type | DLEX6500B |
| Capacity | 7.4 cu. ft. |
| Matching Washer | WM6500HBA / WM6500HWA |
| Sensor Dry | Yes |
| Steam | Yes |
| Color | Black Steel (B) |
| APPEARANCE | |
| LCD Display | Yes |
| Touch Buttons | Yes |
| Dial-A-Cycle® | Yes |
| DRYER PROGRAMS | |
| No. of Programs | 23 |
| Programs (Sensor Dry) | Normal, AI Dry, Bedding, Delicates, Towels, Quick Dry, Timed Dry, Power Dry, Perm. Press, SteamFresh™, Heavy Duty, Air Dry, Steam Sanitary™, Super Dry, Active Wear, Denim -> Jeans, Blanket Refresh, Low Temp Dry, Overnight Dry, Easy Ironing, Small Load, Large Load Dry, X Large Load Dry |
| No. of Options | 11 |
| Options | Cycle Optimization, Damp Dry Signal, Wrinkle Care, Control Lock, Wi-Fi, Energy Saver, TurboSteam®, Reduce Static, Remote Start, Drum Light, Signal |
| Temperature Settings | High, Med. High, Medium, Low, Ultra Low |
| Drying Levels | Very Dry, More Dry, Normal Dry, Less Dry, Damp Dry |
| Manual Dry Times | 10 min ~ 100 min (10 min increments) |

FABRIC CARE FEATURES

| | |
|--------------------------------------------------|---------------------|
| AI Sensor Dry | Yes |
| Sensor Dry | Yes |
| Precise Temperature Control with Variable Heater | Yes |
| Steam | TurboSteam® |
| CONVENIENCE FEATURES | |
| 3 Minute Installation Check | Yes |
| End of Cycle Signal | Yes |
| Drum Light (Door Open) | Yes |
| Reversible Door | Yes |
| FlowSense® Duct Clogging Indicator | Yes |
| Wrinkle Care Option | Yes |
| Control Lock | Yes |
| Venting Option | 4 Way Venting |
| 4 Adjustable Legs | Yes |
| Remaining Time Display / Status Indicator(s) | Yes |
| ThinQ® TECHNOLOGY | |
| Smart Diagnosis | Yes |
| Wi-Fi | Yes |
| Remote Start and Cycle Monitor | Yes |
| Energy Monitoring | Yes |
| ENERGY | |
| ENERGY STAR® Certified | Yes |
| CEF | 3.94 |
| MATERIALS AND FINISHES | |
| NeveRust® Stainless Steel Drum | Yes |
| Cabinet | Painted Steel |
| Door | Tempered Glass Door |
| All Available Colors | Black Steel (B) |

POWER SOURCE

| | |
|-------------------------|------------------------------------------------|
| Ratings | CSA Listed |
| Electrical Requirements | 120/240V, 60Hz, 26A |
| Type | Electric |
| OPTIONS | |
| Side Venting Kit | 3911EZ9131X |
| Pedestal | WDP6B |
| Pedestal (WxHxD) | 27" x 13 5/8" x 28" (43 7/8" D with door open) |
| DIMENSIONS | |
| Product (W x H x D) | 27" x 39" x 29 3/4" |
| Depth with Door Open | 51 3/8" |
| Carton (W x H x D) | 28 31/32" x 46 29/64" x 31 27/64" |
| Product Weight (lbs.) | Electric: 124.3 lbs. |
| Carton Weight (lbs.) | Electric: 136.5 lbs. |
| LIMITED WARRANTY | |
| Parts & Labor | 1 Year |
| Drum | 3 Years |
| UPC CODES | |
| DLEX6500B (Black) | 195174052945 |

04/03/24

SB


NR

Dimensions and Clearances

The following clearances are recommended for the appliance.

- Additional clearances should be considered for ease of installation and servicing.
- Additional clearances should be considered on all sides of the dryer to reduce noise transfer.

Installation Spacing for Recessed Area or Closet Installation



| - | Description | Dimension/Clearance |
|---|----------------------------------------|-------------------------------------|
| A | Upper Ventilation Opening | ≥ 48 sq. in. (310 cm ²) |
| B | Lower Ventilation Opening | ≥ 24 sq. in. (155 cm ²) |
| C | Distance to Ventilation Opening | ≥ 3" (76 mm) |
| D | Overhead Cabinet Depth | ≤ 14" (356 mm) |
| E | Distance to the Overhead Cabinet/Shelf | ≥ 18" (457 mm) |
| F | Front Clearance | 1" (25 mm) |
| G | Depth | 29 3/4" (756 mm) |
| H | Back Clearance | ≥ 5" (127 mm) |
| I | Side Clearance | ≥ 1" (25 mm) |
| J | Width | 27" (686 mm) |
| K | Height of Cabinet Opening | 39" (989 mm) |

04/03/24  


Closet Ventilation Requirements

Closets with doors must have both an upper and lower vent to prevent heat and moisture buildup in the closet. One upper vent opening with a minimum opening of 48 sq. in. (310 cm²) must be installed no lower than 6 feet above the floor. One lower vent opening with a minimum opening of 24 sq. in. (155 cm²) must be installed no more than one foot above the floor. Install vent grilles in the door or cut down the door at the top and bottom to form openings. Louvered doors with equivalent ventilation openings are also acceptable.

NOTE

- There should be at least a little space around the dryer (or any other appliance) to eliminate the transfer of vibration from one appliance to another. If there is enough vibration, it could cause appliances to make noise or come into contact, causing paint damage and further increasing noise.
- No other fuel-burning appliance can be installed in the same closet as a dryer.

Installation Spacing for Recessed Area or Closet, with Stacked Washer and Dryer




| - | Description | Dimension/Clearance |
|---|------------------------------------------------------|-------------------------------------|
| A | Upper Ventilation Opening | ≥ 48 sq. in. (310 cm ²) |
| B | Lower Ventilation Opening | ≥ 24 sq. in. (155 cm ²) |
| C | Distance to Ventilation Opening | ≥ 3" (76 mm) |
| D | Front Clearance | ≥ 1" (25 mm) |
| E | Back Clearance | ≥ 5 1/2" (140 mm) |
| F | Top Clearance to the Ceiling | ≥ 6" (152 mm) |
| G | Height to the Top of Stacked Appliances [†] | 78" (1980 mm) |
| H | Side Clearance | ≥ 1" (25 mm) |
| I | Width [†] | 27" (686 mm) |

[†] Differs depending on the washer dimensions.

04/03/24  

Installation Spacing for Cabinet





For cabinet installation with a door, minimum ventilation openings in the top of the cabinet are required.

| - | Description | Dimension/Clearance |
|---|------------------------------|---------------------|
| A | Depth of Ventilation Opening | ≥ 7" (178 mm) |
| B | Back Clearance | ≥ 5" (127 mm) |
| C | Depth | 29 3/4" (756 mm) |
| D | Front Clearance | ≥ 1" (25mm) |
| E | Side Clearance | ≥ 1" (25 mm) |
| F | Width | 27" (686 mm) |
| G | Clearance to Top of Cabinet | ≥ 9" (229 mm) |

04/03/24 RB

Ductwork

| Wall Cap Type | No. of 90° Elbows | Maximum length of 4-inch diameter rigid metal duct |
|------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|----------------------------------------------------|
|  a: 4" (10.2 cm) | 0 | 65 ft. (19.8 m) |
| | 1 | 55 ft. (16.8 m) |
| | 2 | 47 ft. (14.3 m) |
| | 3 | 36 ft. (11.0 m) |
| | 4 | 28 ft. (8.5 m) |
| Use for only short run installations  b: 2.5" (6.35 cm) | 0 | 55 ft. (16.8 m) |
| | 1 | 47 ft. (14.3 m) |
| | 2 | 41 ft. (12.5 m) |
| | 3 | 30 ft. (9.1 m) |
| | 4 | 22 ft. (6.7 m) |

NOTE

- Deduct 6 ft. (1.8 m) for each additional elbow. Do not use more than four 90° elbows.
- In Canada, only those foil-type flexible ducts, if any, specifically identified for use with the appliance by the manufacturer should be used. In the United States, only those foil-type flexible ducts, if any, specifically identified for use with the appliance by the manufacturer and that comply with the Outline for Clothes Dryer Transition Duct, Subject 2158A, should be used.


Routing and Connecting Ductwork

Follow the guidelines below to maximize drying performance and reduce lint buildup and condensation in the ductwork. Ductwork and fittings are NOT included and must be purchased separately.


- Use 4-inch (10.2 cm) diameter rigid, semi-rigid or flexible metal ductwork.
- The exhaust duct run should be as short as possible.
- Use as few elbow joints as possible.
- The male end of each section of exhaust duct must point away from the dryer.
- Use duct tape on all duct joints.
- Insulate ductwork that runs through unheated areas in order to reduce condensation and lint buildup on duct surfaces.

- Incorrect or inadequate exhaust systems are not covered by the dryer warranty. Dryer failures or service required because of such exhaust systems will not be covered by the dryer warranty.

Correct Venting



Incorrect Venting



Connecting Gas Dryers

⚠ WARNING

- To reduce the risk of fire or explosion, electric shock, property damage, injury to persons, or death when using this appliance, follow requirements including the following.

Electrical Requirements for Gas Models

⚠ WARNING

- This dryer is equipped with a three-prong grounding plug for protection against shock hazard which should be plugged directly into a properly grounded three-prong receptacle. Do not cut or remove the grounding prong from this plug.
- Do not, under any circumstances, cut or remove the third (ground) prong from the power cord.
- For personal safety, this dryer must be properly grounded.

04/03/24 SB


RR

Miele

G 7366 SCVi 24" Fully Integrated Dishwasher Material# 11388350


Features:

- AutoDos
- 3D MultiFlex Cutlery Tray
- QuickIntenseWash
- WifiConn@ct
- DirectSensor Controls
- Panel-Ready
- Water Softener




| SPECIFICATIONS | |
|--------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Overall Unit Dimensions | 23 ⁹ / ₁₆ " (598 mm) W x 33 ¹¹ / ₁₆ " - 36 ¹ / ₄ " (855 - 920 mm) H x 22 ⁷ / ₁₆ " (570 mm) D [Depth does not include door panel] |
| Niche | |
| Minimum Cabinet Niche Opening | 23 ⁵ / ₈ " (600 mm) W x 33 ³ / ₄ " (857 mm) H x 22 ⁷ / ₁₆ " (570 mm) D |
| Plumbing | |
| Water Supply Requirements | <ul style="list-style-type: none"> • Cold or Hot (max 150°F/65°C) water connection • Male 3/8" compression fitting • Water pressure range 7.25 psi (0.5 bar) and 145 psi (10 bar) |
| Water Connection Line (Supplied) | Length: 5 ft (1.5 m) Female 3/8" compression. |
| Drain Hose (Supplied) | Length: 5 ft (1.5 m) 7/8" (22 mm) internal diameter |
| Electrical | |
| Electrical Requirements | 110V / 120V, 60Hz, 15 Amps |
| Power Cord (Convertible to hardwire) | NEMA 5-15 plug, 5 ft (1.52 m) |
| Shipping | |
| Shipping Weight | 121 lbs (55 kg) |
| Shipping Dimensions | 27 ¹ / ₈ " W x 38 ¹ / ₈ " H x 26 ³ / ₈ " D |


Product Dimensions



Cutout Dimensions



Custom Panel



Width: 23 7/16" (595 mm) in all Cases
Thickness: 3/4" (19 mm) in all Cases
Height: Determined using the following calculation:

$$\text{Panel Height} = \text{HTC} - \text{TKH}$$

HTC = Height to the underside of countertop
TKH = Toe kick height

Note: Control panel is along the top edge of the unit. It is not visible when the unit is closed. A handle **MUST** be located on front of panel in order to open unit. (Except K2o models).

Maximum panel height: 31 7/8" (810 mm)

Minimum panel height: 27 1/8" (690 mm)

Maximum panel weight: 26 lbs (12 kg)

04/03/24
 SIB
 NB

36" CLASSIC OVER-AND-UNDER REFRIGERATOR/FREEZER WITH INTERNAL DISPENSER - PANEL READY

SUB-ZERO

CL3650UID/O



FEATURES

Legacy product image shown; actual product varies slightly.

Split Climate™ intelligent cooling system revolutionizes Sub-Zero's already-superior preservation capabilities, keeping food even fresher for longer

ClearSight™ LED lighting system fully illuminates the interior and reduces shadows

Sleek stainless accents trim the interior, matching the sophistication of the exterior

Touch control panel is conveniently located for easy access at the tap of a finger

Night Mode optimizes the interior lighting based on the detected ambient light, reducing the brightness by 90% in dim environments

Delivers fresh, filtered water through an internal dispenser located discreetly within the refrigerator

Lift the base of the flip-up dairy compartment to store taller items on the shelf below

The base of the expandable freezer basket conveniently slides out of the way, offering customizable storage for taller items below

Wi-Fi enabled for convenient remote access using the Sub-Zero Group Owner's App

Sub-Zero offers an industry-leading full two-year warranty on appliances, along with a full five-year sealed system warranty

ACCESSORIES

Egg Container

Grille Frame - 84"

Stainless Steel Flush Inset Grille Panel

Stainless Steel Side Panel

Water Filter

Dual Installation Kits

Custom Front and Side Panel Mounting Kits

Stainless Steel Flush Inset Door and Drawer Panels with Pro Handle

Stainless Steel Flush Inset Door and Drawer Panels with Tubular Handle

Classic Stainless Steel Pro Louvered Grilles

Stainless Steel Pro and Tubular Handles

Stainless Steel Kickplate

Accessories are available through an authorized dealer.
For local dealer information, visit subzero-wolf.com/locator.



HANDLE ACCESSORIES

PRO



TUBULAR



PRODUCT DETAILS

REFRIGERATOR

- 4 glass refrigerator shelves (3 adjustable; 1 stationary)
- 2 crisper drawers with removable dividers
- 3 refrigerator door bins (2 adjustable; 1 stationary)
- 1 flip-up dairy compartment
- Air purification system
- Internal water dispenser
- LED refrigerator and freezer lights

FREEZER

- Full-extension drawer
- Water filtration system
- Automatic ice maker with removable ice container

04/03/24  


36" CLASSIC OVER-AND-UNDER REFRIGERATOR/FREEZER WITH INTERNAL DISPENSER - PANEL READY

SUB#ZERO


PRODUCT SPECIFICATIONS

| | |
|-----------------------|-------------------------------------------------------|
| Model | CL3650UID/O |
| Dimensions | 36"W x 84"H x 24"D |
| Refrigerator Capacity | 15.5 cu. ft. |
| Freezer Capacity | 5.2 cu. ft. |
| Weight | 552 lbs |
| Electrical Supply | 115 VAC, 60 Hz |
| Electrical Service | 15 amp dedicated circuit |
| Plumbing Supply | 1/4" OD copper, braided stainless steel or PEX tubing |
| Plumbing Pressure | 35–120 psi |
| Receptacle | 3-prong grounding-type |

ELECTRICAL



PLUMBING



PANEL SPECIFICATIONS For complete panels specifications including width/height, weight requirements, thickness requirements and offset details visit subzero-wolf.com/builtinconfigurator.


NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified

INTERIOR VIEW




This illustration is intended for interior reference only and may not represent the exterior of the model being specified.

DIMENSIONS



FLUSH INSET INSTALLATION



NOTE: 3/16 inch (8 mm) finished returns and shaded areas will be visible and should be finished to match cabinetry. Shaded line represents profile of unit with 3/4 inch (19 mm) panel.

04/03/24 SB M

36" CLASSIC OVER-AND-UNDER REFRIGERATOR/FREEZER WITH INTERNAL DISPENSER - PANEL READY

SUB-ZERO

CL3650UID/O



FEATURES

Legacy product image shown; actual product varies slightly.

Split Climate™ intelligent cooling system revolutionizes Sub-Zero's already-superior preservation capabilities, keeping food even fresher for longer

ClearSight™ LED lighting system fully illuminates the interior and reduces shadows

Sleek stainless accents trim the interior, matching the sophistication of the exterior

Touch control panel is conveniently located for easy access at the tap of a finger

Night Mode optimizes the interior lighting based on the detected ambient light, reducing the brightness by 90% in dim environments

Delivers fresh, filtered water through an internal dispenser located discreetly within the refrigerator

Lift the base of the flip-up dairy compartment to store taller items on the shelf below

The base of the expandable freezer basket conveniently slides out of the way, offering customizable storage for taller items below

Wi-Fi enabled for convenient remote access using the Sub-Zero Group Owner's App

Sub-Zero offers an industry-leading full two-year warranty on appliances, along with a full five-year sealed system warranty

ACCESSORIES

Egg Container

Grille Frame - 84"

Stainless Steel Flush Inset Grille Panel

Stainless Steel Side Panel

Water Filter

Dual Installation Kits

Custom Front and Side Panel Mounting Kits

Stainless Steel Flush Inset Door and Drawer Panels with Pro Handle

Stainless Steel Flush Inset Door and Drawer Panels with Tubular Handle

Classic Stainless Steel Pro Louvered Grilles

Stainless Steel Pro and Tubular Handles

Stainless Steel Kickplate

Accessories are available through an authorized dealer.
For local dealer information, visit subzero-wolf.com/locator.



HANDLE ACCESSORIES

PRO



TUBULAR



PRODUCT DETAILS

REFRIGERATOR

- 4 glass refrigerator shelves (3 adjustable; 1 stationary)
- 2 crisper drawers with removable dividers
- 3 refrigerator door bins (2 adjustable; 1 stationary)
- 1 flip-up dairy compartment
- Air purification system
- Internal water dispenser
- LED refrigerator and freezer lights

FREEZER

- Full-extension drawer
- Water filtration system
- Automatic ice maker with removable ice container

04/03/24 ES M


36" CLASSIC OVER-AND-UNDER REFRIGERATOR/FREEZER WITH INTERNAL DISPENSER - PANEL READY

SUB-ZERO


PRODUCT SPECIFICATIONS

| | |
|-----------------------|-------------------------------------------------------|
| Model | CL3650UID/O |
| Dimensions | 36"W x 84"H x 24"D |
| Refrigerator Capacity | 15.5 cu. ft. |
| Freezer Capacity | 5.2 cu. ft. |
| Weight | 552 lbs |
| Electrical Supply | 115 VAC, 60 Hz |
| Electrical Service | 15 amp dedicated circuit |
| Plumbing Supply | 1/4" OD copper, braided stainless steel or PEX tubing |
| Plumbing Pressure | 35–120 psi |
| Receptacle | 3-prong grounding-type |

ELECTRICAL



PLUMBING



PANEL SPECIFICATIONS For complete panels specifications including width/height, weight requirements, thickness requirements and offset details visit subzero-wolf.com/builtinconfigurator.


NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified

INTERIOR VIEW




This illustration is intended for interior reference only and may not represent the exterior of the model being specified.

DIMENSIONS



STANDARD INSTALLATION



SIDE VIEW


FRONT VIEW

NOTE: 3 1/2" (89) finished returns will be visible and should be finished to match cabinetry. Shaded line represents profile of unit.

04/03/24 SB RB

Panel Specifications

Single Model: CL3650UID/O



| PANEL | FRONT | SPACER | BACKER | MAX WEIGHT |
|--------|---------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|------------|
| Door | 37" <small>W</small> 50 ⁵ / ₈ " <small>H</small> | 35 ¹ / ₈ " <small>W</small> 49 ¹³ / ₁₆ " <small>H</small> | 35 ³ / ₄ " <small>W</small> 50 ⁷ / ₁₆ " <small>H</small> | 50 lbs |
| Drawer | 37" <small>W</small> 20" <small>H</small> | 35 ¹ / ₈ " <small>W</small> 19 ¹ / ₁₆ " <small>H</small> | 35 ³ / ₄ " <small>W</small> 19 ¹¹ / ₁₆ " <small>H</small> | 50 lbs |
| Grille | 37" <small>W</small> 7 ³ / ₄ " <small>H</small> | 35 ¹ / ₈ " <small>W</small> 6 ¹³ / ₁₆ " <small>H</small> | 35 ³ / ₄ " <small>W</small> 7 ⁷ / ₁₆ " <small>H</small> | 13 lbs |

04/03/24

Panel Planning Notes

Single Model: CL3650UID/O


The flush inset application is an overlay model with flush inset panels. It is not a separate model.

The flush inset design allows custom panels to be installed flush with adjacent cabinets. Similar to overlay, flush inset panels are typically created by combining a 3/4" (19) custom panel, a .10" (3) spacer panel and a 1/4" (6) backer panel.

For flush inset panels thicker than 3/4" (19), a 90° door stop may be required to prevent interference with adjacent cabinets.

Minimum Panel Thickness

3/4" (19) typical



Panel assembly (rear view).

Standard Handle Lengths (Optional)

HANDLE

TUBULAR

PRO

CL3650UID/O Door

40 1/8"

36 1/16"

CL3650UID/O Drawer


31"

30"


09/03/24

Panel Offsets


Single Model: CL3650UID/O




Door (hinge) / Drawer / Grille Sides




Grille Top



Grille Bottom / Door Top



Door Bottom / Drawer Top



Door/Drawer Bottom


04/03/24

LB

NB

Templates

Single Model: CL3650UID/O




Flush inset application—110° door opening (top view).

04/03/24

SB

NR




Overlay and flush inset panel thickness.

04/03/24  

Panel Specifications

Single Model: CL3650UID/O



| PANEL | FRONT | SPACER | BACKER | MAX WEIGHT |
|--------|---------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|------------|
| Door | 36" <small>W</small> 50 ⁵ / ₈ " <small>H</small> | 35 ¹ / ₈ " <small>W</small> 49 ¹³ / ₁₆ " <small>H</small> | 35 ³ / ₄ " <small>W</small> 50 ⁷ / ₁₆ " <small>H</small> | 50 lbs |
| Drawer | 36" <small>W</small> 20" <small>H</small> | 35 ¹ / ₈ " <small>W</small> 19 ¹ / ₁₆ " <small>H</small> | 35 ³ / ₄ " <small>W</small> 19 ¹¹ / ₁₆ " <small>H</small> | 50 lbs |
| Grille | 36" <small>W</small> 7 ³ / ₄ " <small>H</small> | 35 ¹ / ₈ " <small>W</small> 6 ¹³ / ₁₆ " <small>H</small> | 35 ³ / ₄ " <small>W</small> 7 ⁷ / ₁₆ " <small>H</small> | 13 lbs |

04/03/24

ES

RB


Panel Planning Notes

Single Model: CL3650UID/O


Overlay panels are typically created by combining a 3/4" (19) custom panel, a .10" (3) spacer panel and a 1/4" (6) backer panel.

Minimum Panel Thickness

5/8"



Panel assembly (cross section).



Panel assembly (rear view).

Standard Handle Lengths (Optional)

HANDLE

TUBULAR

PRO

CL3650UID/O Door

40 1/8"

36 1/16"

CL3650UID/O Drawer

31"

30"


04/03/24

SB

NB


Templates

Single Model: CL3650UID/O



Overlay application—90° door opening (top view).

09/03/24  



Overlay and flush inset panel thickness.

04/03/24  

CI30460C/B

FEATURES

Consistent, precise control and nearly instantaneous temperature response

More efficient heat transfer—energy is supplied directly to the cookware

Intuitive, full-color LCD touchscreen controls are sleek and easy to use

17 power settings enhance precision with half increment adjustments

Sensors regulate consistent low heat for simmering, melting, and warming without scorching

Independent cooking zone timers make it easy to prepare a variety of dishes at once

Boost Mode delivers rapid heat for 40% faster boil times, surpassing the speed of gas or electric

Bridge two cooking zones into one larger surface for induction-capable griddles, open roasters, and fish poachers

Sleek, subtle surface graphics make it easy to properly center cookware

The pause feature suspends the cooktop and all timers for up to 10 minutes

Turn off an individual cooking zone with two quick taps or power off the entire cooktop surface with one tap

Cooktop controls automatically lock when not in use for increased safety

Sleek black glass surface resists scratching, staining, impact, and heat

Because spills don't stick to the surface, cleanup is quick and easy

Frameless design installs flush against counter for a clean contemporary look



COOKTOP SPECIFICATIONS


- Unframed edge for flush installation
- Black ceramic glass surface
- Sensor based simmer, melt, and keep warm modes
- Boost Mode for rapid heat
- 1 - 6" 1,400 W Zone with 2,200 W Boost
- 2 - 8" 2,100 W Element with 3,700 W Boost
- 1 - 11" 2,600 W Zone with 3,700 W Boost

04/03/24
 CB
 RB

PRODUCT SPECIFICATIONS


| | |
|--------------------|----------------------------|
| Model | CI30460C/B |
| Dimensions | 30"W x 2 1/2"H x 21"D |
| Weight | 49 lbs |
| Electrical Supply | 3-wire, 240/208 VAC, 60 Hz |
| Electrical Service | 40 amp dedicated circuit |
| Conduit Length | 4 Feet |

ELECTRICAL





NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified


DIMENSIONS



FLUSH INSTALLATION



COUNTERTOP CUT-OUT



SIDE VIEW

FRONT VIEW

NOTE: Shaded area above countertop indicates minimum clearance to combustible surfaces, combustible materials cannot be located within this area.
Electrical supply location only applies to installations with built-in oven.
Outside corner radius 7/16 inch (11).

04/03/24
SB
NB

CI30460C/B

FEATURES

Consistent, precise control and nearly instantaneous temperature response

More efficient heat transfer—energy is supplied directly to the cookware

Intuitive, full-color LCD touchscreen controls are sleek and easy to use

17 power settings enhance precision with half increment adjustments

Sensors regulate consistent low heat for simmering, melting, and warming without scorching

Independent cooking zone timers make it easy to prepare a variety of dishes at once

Boost Mode delivers rapid heat for 40% faster boil times, surpassing the speed of gas or electric

Bridge two cooking zones into one larger surface for induction-capable griddles, open roasters, and fish poachers

Sleek, subtle surface graphics make it easy to properly center cookware

The pause feature suspends the cooktop and all timers for up to 10 minutes

Turn off an individual cooking zone with two quick taps or power off the entire cooktop surface with one tap

Cooktop controls automatically lock when not in use for increased safety

Sleek black glass surface resists scratching, staining, impact, and heat

Because spills don't stick to the surface, cleanup is quick and easy

Frameless design installs flush against counter for a clean contemporary look



COOKTOP SPECIFICATIONS

- Unframed edge for flush installation
- Black ceramic glass surface
- Sensor based simmer, melt, and keep warm modes
- Boost Mode for rapid heat
- 1 - 6" 1,400 W Zone with 2,200 W Boost
- 2 - 8" 2,100 W Element with 3,700 W Boost
- 1 - 11" 2,600 W Zone with 3,700 W Boost

04/03/24


SS

7B

PRODUCT SPECIFICATIONS


| | |
|--------------------|----------------------------|
| Model | CI30460C/B |
| Dimensions | 30"W x 2 1/2"H x 21"D |
| Weight | 49 lbs |
| Electrical Supply | 3-wire, 240/208 VAC, 60 Hz |
| Electrical Service | 40 amp dedicated circuit |
| Conduit Length | 4 Feet |

ELECTRICAL




NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified


DIMENSIONS



STANDARD INSTALLATION



COUNTERTOP CUT-OUT



SIDE VIEW

FRONT VIEW

NOTE: Shaded area above countertop indicates minimum clearance to combustible surfaces, combustible materials cannot be located within this area.
Electrical supply location only applies to installations with built-in oven.

04/03/24
EB
MB

MDD30CM/B/TH

FEATURES

Distributes heat evenly with no hot or cold spots allowing for oven-like operation

Installs standard or flush to conceal the oven from view

Matches M series ovens, coffee systems, convection steam oven

Utilizes 900 watts of power to cook meals with delicious results

Select from 10 power levels, a warming mode, and sensor cooking

Rely on quick-start controls for tasks like melting, softening, defrosting, and popcorn

Let the microwave do the cooking with intuitive "gourmet mode" settings

Install into surrounding cabinetry to coordinate with other Wolf built-in ovens and warming drawers



04/03/24


SB

MP

PRODUCT SPECIFICATIONS


| | |
|--------------------|----------------------------|
| Model | MDD30CM/B/TH |
| Dimensions | 29 7/8"W x 17 7/8"H x 20"D |
| Capacity | 1.6 cu. ft. |
| Door Clearance | 14 3/16" |
| Electrical Supply | 120 VAC, 60 Hz |
| Electrical Service | 15 amp dedicated circuit |
| Power Cord Length | 4 Feet |
| Receptacle | 3-prong grounding-type |

ELECTRICAL




NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified

DIMENSIONS



FLUSH INSTALLATION



SIDE VIEW

FRONT VIEW

*Will be visible and should be finished to match cabinetry.
**Dimension provides minimum reveals.

04/03/24 SB MB

MDD30CM/B/TH

FEATURES

Distributes heat evenly with no hot or cold spots allowing for oven-like operation

Installs standard or flush to conceal the oven from view

Matches M series ovens, coffee systems, convection steam oven


Utilizes 900 watts of power to cook meals with delicious results

Select from 10 power levels, a warming mode, and sensor cooking

Rely on quick-start controls for tasks like melting, softening, defrosting, and popcorn

Let the microwave do the cooking with intuitive "gourmet mode" settings

Install into surrounding cabinetry to coordinate with other Wolf built-in ovens and warming drawers




04/03/24 



PRODUCT SPECIFICATIONS


| | |
|--------------------|----------------------------|
| Model | MDD30CM/B/TH |
| Dimensions | 29 7/8"W x 17 7/8"H x 20"D |
| Capacity | 1.6 cu. ft. |
| Door Clearance | 14 3/16" |
| Electrical Supply | 120 VAC, 60 Hz |
| Electrical Service | 15 amp dedicated circuit |
| Power Cord Length | 4 Feet |
| Receptacle | 3-prong grounding-type |

ELECTRICAL




NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified

DIMENSIONS



STANDARD INSTALLATION



04/03/24 SB MS

SO3050CM/B



FEATURES

Preheats faster and cooks more consistently across all racks due to its advanced Dual VertiFlow™ convection system

Assures predictably delicious results with a variety of modes, including Convection Roast, Proof, and Dehydrate

Prepares 50 popular dishes with the Gourmet feature that automatically adjusts cook times and temperatures

Handles multiple dishes simultaneously with our largest capacity oven (13 percent larger)

Insert a temperature probe to tell you exactly when it is done—and in Gourmet Mode, it will alert you the moment the dish is ready.

Uncomplicate cooking with innovative, interactive color touchscreen controls

Blends in with a sleek black glass, handleless design

Integrates beautifully into surrounding cabinetry with flush installation

Ensures excellent visibility via three bright halogen lights and large, triple-panel-glass door windows

Master your technique with tips and recipes from the Mastering the M Series Oven guide

ACCESSORIES

30" Broiler Pan

30" Full-Extension Ball-Bearing Oven Rack

30" Premier Baking Sheet

30" Standard Oven Rack

Bake Stone Kit

Dehydration Kit

Dual Installation Kit

Multi-Function Pan

Temperature Probe

Accessories available through an authorized dealer.

For local dealer information, visit subzero-wolf.com/locator.




04/03/24  

PRODUCT SPECIFICATIONS


| | |
|----------------------------|--------------------------------|
| Model | SO3050CM/B |
| Dimensions | 29 7/8"W x 28 1/2"H x 23"D |
| Oven 1 Interior Dimensions | 25 1/4"W x 17 1/2"H x 19 7/8"D |
| Overall Capacity | 5.1 cu. ft. |
| Usable Capacity | 3.3 cu. ft. |
| Door Clearance | 21 3/8" |
| Electrical Supply | 240/208 VAC, 60 Hz |
| Electrical Service | 30 amp dedicated circuit |
| Conduit Length | 4 Feet |

ELECTRICAL




NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified

DIMENSIONS



FLUSH INSTALLATION



SIDE VIEW

FRONT VIEW

*1" (25) minimum depth. Shaded areas will be visible and should be finished to match cabinetry.

**Dimension provides minimum reveals

NOTE: Location of electrical supply within opening may require additional cabinet depth.

04/03/24 SB NB

SO3050CM/B



FEATURES

Preheats faster and cooks more consistently across all racks due to its advanced Dual VertiFlow™ convection system

Assures predictably delicious results with a variety of modes, including Convection Roast, Proof, and Dehydrate

Prepares 50 popular dishes with the Gourmet feature that automatically adjusts cook times and temperatures

Handles multiple dishes simultaneously with our largest capacity oven (13 percent larger)

Insert a temperature probe to tell you exactly when it is done—and in Gourmet Mode, it will alert you the moment the dish is ready.

Uncomplicate cooking with innovative, interactive color touchscreen controls

Blends in with a sleek black glass, handleless design

Integrates beautifully into surrounding cabinetry with flush installation

Ensures excellent visibility via three bright halogen lights and large, triple-panel-glass door windows

Master your technique with tips and recipes from the Mastering the M Series Oven guide

ACCESSORIES

30" Broiler Pan

30" Full-Extension Ball-Bearing Oven Rack

30" Premier Baking Sheet

30" Standard Oven Rack

Bake Stone Kit

Dehydration Kit

Dual Installation Kit

Multi-Function Pan

Temperature Probe

Accessories available through an authorized dealer.

For local dealer information, visit subzero-wolf.com/locator.




04/03/24  

PRODUCT SPECIFICATIONS


| | |
|----------------------------|--------------------------------|
| Model | SO3050CM/B |
| Dimensions | 29 7/8"W x 28 1/2"H x 23"D |
| Oven 1 Interior Dimensions | 25 1/4"W x 17 1/2"H x 19 7/8"D |
| Overall Capacity | 5.1 cu. ft. |
| Usable Capacity | 3.3 cu. ft. |
| Door Clearance | 21 3/8" |
| Electrical Supply | 240/208 VAC, 60 Hz |
| Electrical Service | 30 amp dedicated circuit |
| Conduit Length | 4 Feet |

ELECTRICAL




NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified


DIMENSIONS




STANDARD INSTALLATION



TOP VIEW



SIDE VIEW



FRONT VIEW

NOTE: Location of electrical supply within opening may require additional cabinet depth.

04/03/24




04/03/24

ES

MS

SU2230X
SU2236X

SU 22
stainless steel AISI 430



| | |
|-----------------------|------------------------------------------------------------------------------------|
| MOTOR | 600 CFM Aluminium die-cast motor housing Pressure: 680Pa Noise level: 64 dBA |
| LIGHTING | 2x2,10 Led spot |
| CONTROL PANEL | 4 speeds push-button + delay off timer + light switch |
| GREASE FILTER | Anodized aluminium (5+1 layers) and semi baffle filter |
| AIR OUTLET | 6"round |
| DISCHARGE | Vertical |
| ACCESSORIES | Charcoal filters: KF2 (order 1 pc) 60071099999 |
| AIR DEVIATOR | Def 2 75050200199 |
| FLUE EXTENSION | 36" CE6 75091200022 |

04/03/24  