



Specifications for Project

**11 Hemphill Road**

Salesperson

**Mathew Gauthier**

**mathew.gauthier@caplans.ca**



## **REMINDER:**

To ensure a smooth project it is the responsibility of the homeowner / purchaser of appliances for this project to share all the attached specifications to ensure the cabinet provider, contractor, or any other tradesperson have all the information required to complete their work accurately.

Specifications are subject to change. If any tradesperson has questions regarding the attached specifications please contact our sales associate.

# 11 Hemphill Road



<i>Contents</i>	<i>Page no.</i>
<b>KF 2982 Vi</b> Miele Refrigeration 36" MasterCool Fully Integrated	4-6
<b>KM 3475 G</b> Miele Cooktop 36" 5-Burner KM 3475 G Gas Cooktop	7-11
<b>DGC 7370 XL</b> Miele Wall Oven 30" DGC 7370 XL ContourLine Combi-Steam Oven	12-14
<b>H 7180 BP</b> Miele Wall Oven 30" H 7180 BP ContourLine Convection Oven	15-17
<b>G 7266 SCVi</b> Miele Dishwasher Fully-integrated, full-size dishwasher with 3D MultiFlex Tray	18-19
<b>SU90134X</b>	20-21

## Caplan's Appliances

caplans.ca

### Mathew Gauthier

Account Manager

4377795233

Search **20250624192617351SC**

Version 1.1

Tue, Jun 24, 2025

3:26 PM EDT



[enterprise.steelcod.com/sp/cpln/1RN8SHUX](https://enterprise.steelcod.com/sp/cpln/1RN8SHUX)

#### Note about page numbers:

Because the original manufacturer's documents are not altered in any way, the page numbers displayed on the page may not correspond to the page number within this package.

#### All specifications are intended for initial planning purposes only.

Manufacturers reserve the right to change specifications at any time without notice. Always consult the installation instructions found on the manufacturer's website or included with the appliances before installation.

Sirius Ventilation

34" Hood Insert

---

**PFQ97HSPVDS** 22-28

GE Washer-Dryer

5.5 cu. ft. Capacity UltraFast Combo, Ventless  
Heat Pump Technology Washer/Dryer Carbon  
Graphite

---

**GFR0728PTDS** 29

GE Pedestal

**Note about page numbers:**

Because the original manufacturer's documents are not altered in any way, the page numbers displayed on the page may not correspond to the page number within this package.

**All specifications are intended for initial planning purposes only.**

Manufacturers reserve the right to change specifications at any time without notice. Always consult the installation instructions found on the manufacturer's website or included with the appliances before installation.

KF 2982 Vi  
MasterCool FrenchDoor  
For high-end design and technology on a large scale.



- Push2open for convenient door-opening assistance
- Food stays fresh for up to 3 x longer thanks to SmartFresh
- Light floods the interior thanks to LED elements – BrilliantLight
- Convenient control thanks to colour touch display MasterSensor

EAN: 4002516322016 / Material number: 11503020 / Old Material Number: 38298201USA

Appliance category	
Fridge / freezer	•
Construction type	
Built-in appliance	•
Integrated appliance	•
Door hinging	Left and right
Can be installed side by side	•
Design	
Lighting	BrilliantLight
User convenience	
Networking with Miele@home	•
Freshness system	MasterFresh
ComfortClean	•
DynaCool	•
NoFrost	•
DuplexCool Pro	•
SoftClose	•
SelfClose	•
IceMaker with fresh-water connection	•
Push2open	•
FullAccess	•
EasyClean	•
MaxLoad hinge	•
Controls	
User interface	MasterSensor
Independent temperature regulation of fridge and freezer compartments	Yes
SuperCool	•
SuperFrost	•
Number of temperature zones	3
Sabbath mode	•
Holiday mode	•
Eco mode	•
Fridge / Fridge section	
Height-adjustable tempered glass shelves	2
Number of crisper drawers	2
SlidingShelf	•
Door rack for tins	2
Door rack for bottles	4
Freezer / Freezer section	
Number of freezer baskets	2
Efficiency and sustainability	
Energy Star	•
Safety	
Safety lock	•
Overflow protection	•
Acoustic door alarm	•
Acoustic temperature alarm, freezer section	•
Optical door alarm	•
Optical temperature alarm	•



KF 2982 Vi  
MasterCool FrenchDoor  
For high-end design and technology on a large scale.




EAN: 4002516322016 / Material number: 11503020 / Old Material Number: 38298201USA

Technical data	
Niche width in inches (mm), min.	36 (914)
Niche width in inches (mm), max.	36 (914)
Niche height in inches (mm), min.	84 1/8 (2134)
Niche height in inches (mm), max.	84 1/8 (2134)
Niche depth in mm	24 7/8 (629)
Appliance width in mm	35 3/4 (908)
Appliance height in mm	83 3/4 (2125)
Appliance depth in mm	24 (608)
Weight in lbs (kg)	449 (203.3)
Door hinge technology	Fixed door
Max. weight of door, fridge section, in kg	150 (68)
Max. weight of door, freezer section, in kg	23 (10)
Total usable capacity in l	19.42 (550) ft <sup>3</sup> (l)
Current consumption in milliamps (mA)	4000
Voltage in V	110-120
Fuse rating in A	10
Number of phases	1
Frequency in Hz	60
Length of power cable in m	9 (3.0)
Replacing lamps	Customer Service
Accessories supplied	
Active AirClean filter	•
Available display languages	

Available display languages via Language Options


bahasa malaysia, dansk, deutsch, eesti, english, english (AU), english (CA), english (GB), english (US), español, français, français (CA), français (FR), hrvatski, italiano, latviesu, lietuviu, magyar, nederland, norsk, polski, português, русский, română, slovenčina, slovenščina, srpski, suomi, svenska, türkçe, українська, čeština, ελληνικά, ????????, ??, ???, ?????, ???

KF 2982 Vi  
MasterCool FrenchDoor  
For high-end design and technology on a large scale.




Side-by-side, MasterCool, without partition wall, with heating mat (Sketch) (with footnote)


1) Heating mat KSK 2001 (EU, AUS, CN) or KSK 2002 (US, CA, MX, BR)



KF2982Vi, KF2981Vi, installation, MasterCool, installation drawings




KF2901Vi/SF, KF2911Vi/SF, KF2801Vi/SF, KF2811Vi/SF, KF2981Vi/SF, sideview, MasterCool, installation drawings




Side-by-Side, MasterCool, footnote, installation drawings

1. KSK 2001/2002, 2. Device A, 3. Device B, A = niche device A, B = niche device B



KFP3635ed/cs, KFP3634ed/cs R, KFP3634ed/cs L, KFP3634ed/cs, Front panel, Front dimensions, MasterCool, sketch



KF2902Vi/SF, KF2912Vi/SF, KF2982Vi/SF, KF2901Vi/SF, KF2911Vi/SF, KF2981Vi/SF, installation, MasterCool

1. View from the front, 2. Mains Connection cable, L = 3000 mm (118 inch), 3. Water inlet position, L = 2000mm (not for KON USA), 4. No water/ELT connections permitted in this area

## 36" 5-Burner Gas Cooktop

KM 3475 G/LP



# 36" 5-Burner Gas Cooktop

## KM 3475 G/LP



### KM 3475 G/LP

#### Features:

- 5 completely sealed burners:  
(2) 15,300 BTU Double inset super (wok) burners  
(1) 12,000 BTU Super burner  
(2) 9,000 BTU High-speed burners
- Center control panel
- Stainless steel knobs
- Fast ignition system
- Ignition safety control
- Wok ring included

#### SPECIFICATIONS

KM 3475 G

KM 3475 LP

Unit Width 36" (914 mm)

Unit Height 3<sup>3</sup>/<sub>8</sub>" (86 mm)

Unit Depth 21<sup>5</sup>/<sub>16</sub>" (542 mm)

#### Niche Dimensions

Cut-Out Dimensions 35" (889 mm) W x 20<sup>3</sup>/<sub>8</sub>" (518 mm) D

Minimum Back Spacing From Wall 2<sup>3</sup>/<sub>4</sub>" (70 mm)

Minimum Countertop Thickness 1<sup>3</sup>/<sub>16</sub>" (20 mm)

Minimum Recommended Distance to Ventilation Hood 30" (760 mm)

#### Gas Burners

High-Speed Burner (2) 9,000 BTU (G/LP)

Super Burner (1) 12,000 BTU (G/LP)

Wok Burner (2) 15,300 BTU (G/LP)

Total Maximum BTU Output 60,600 BTU (G/LP)

#### Gas

Gas Connection 1/2" NPT

Maximum Gas Pressure 1/2 psi (3.5 kPa)

#### Electrical

Electrical Requirements 120 V, 60 Hz, 15 A

Power Cord NEMA 5-15P, 4 ft (1.2 m)

#### Shipping

Shipping Weight 64 lbs (29 kg)

Shipping Dimensions 23<sup>5</sup>/<sub>8</sub>" W x 7<sup>7</sup>/<sub>8</sub>" H x 39<sup>3</sup>/<sub>8</sub>" D

#### Support


Phone 800.565.6435

Miele Website [www.miele.ca](http://www.miele.ca)

# 36" 5-Burner Gas Cooktop KM 3475 G/LP



## PRODUCT OVERVIEW




- ① Wok ring
- ② Normal burners
- ③ Fast burner
- ④ Grates  
(Design depends on model)
- ⑤ Wok burners

The layout of the control knobs corresponds with the layout of the burners.

# 36" 5-Burner Gas Cooktop KM 3475 G/LP



## INSTALLATION DIMENSIONS



- ① Front
- ② Built-in depth
- ③ Gas connection R  $\frac{1}{2}"$  NPT
- ④ Mains connection box

# 36" 5-Burner Gas Cooktop

## KM 3475 G/LP



KM 3475 G/LP GAS COOKTOP INSTALLATION IN COMBINATION  
WITH UNDERCOUNTER 30" MIELE OVEN H6x80BP

### Countertop Thickness vs. Toekick Height

Taken into consideration:

- 35" tall cabinetry
- Gas pressure regulator mounted on back wall or in adjacent cabinetry
- 90 degree street elbow used on bottom of cooktop
- $\frac{3}{8}$ " of cooktop above countertop (proud)
- $\frac{3}{4}$ " (exact) platform thickness under oven/above toekick

		Toekick Height (Inches)									
		$3\frac{1}{2}$	$3\frac{3}{4}$	4	$4\frac{1}{4}$	$4\frac{1}{2}$	$4\frac{3}{4}$	5	$5\frac{1}{4}$	$5\frac{3}{4}$	6
Countertop Thickness (Inches)	$\frac{13}{16}$	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	1	OK	NA	NA	NA	NA	NA	NA	NA	NA	NA
	$1\frac{1}{4}$	OK	OK	NA	NA	NA	NA	NA	NA	NA	NA
	$1\frac{1}{2}$	OK	OK	OK	NA	NA	NA	NA	NA	NA	NA
	$1\frac{3}{4}$	OK	OK	OK	OK	NA	NA	NA	NA	NA	NA
	2	OK	OK	OK	OK	OK	NA	NA	NA	NA	NA

 = Standard Kitchen



## DGC 7370 XL 30" Combi-Steam Oven - ContourLine

### Features:

- Combi-Steam Ovens: Steam ovens with full fledged oven function
- Lift up panel - conveniently stores the water containers
- Dual Steam - quickly and evenly distribute steam for perfect cooking results
- Mix & Match - use your Miele@home app or the WiFi enabled appliance to create recipes for full meals

### Included:

- 1 Universal Tray with Perfect Clean
- 1 Wire rack with Perfect Clean
- 1 perforated stainless steel container
- 1 solid stainless steel container




### MATERIAL #

11875800

SPECIFICATIONS	
Overall Unit Dimensions	29 <sup>13</sup> / <sub>16</sub> " (757 mm) W x 18 <sup>7</sup> / <sub>8</sub> " (479 mm) H x 23 <sup>1</sup> / <sub>8</sub> " (587 mm) D
Niche	
Minimum Cabinet Niche Opening	28 <sup>1</sup> / <sub>2</sub> " (724 mm) W x 18 <sup>1</sup> / <sub>2</sub> " (470 mm) H x 24" (610 mm) D
Electrical	
Electrical Requirements	208 - 240V, 60Hz, 20 Amps
Power Cord	NEMA 6-20 plug, 5 ft (1.52 m)
Shipping	
Shipping Weight	143 lbs (65 kg)
Shipping Dimensions	28 <sup>5</sup> / <sub>8</sub> " (726 mm) W x 29 <sup>1</sup> / <sub>4</sub> " (743 mm) H x 32 <sup>1</sup> / <sub>2</sub> " (825 mm) D

### PRODUCT DIMENSIONS




E = Electrical connection






## FLUSH CUTOUT DIMENSIONS

Front View



Side View




A - Cut-out (4" x 28" [100 mm x 720 mm]) in the bottom of the cabinet for the power cord and Ventilation

ⓘ - Electrical and water supplies are recommended to be placed in adjacent cabinetry.




Additional cabinet depth is required when placing the electrical and water supplies behind the appliance.

## PROUD CUTOUT DIMENSIONS

Front View



Side View



A - Cut-out (4" x 28" [100 mm x 720 mm]) in the bottom of the cabinet for the power cord and Ventilation

① - Electrical and water supplies are recommended to be placed in adjacent cabinetry.

Additional cabinet depth is required when placing the electrical and water supplies behind the appliance.

## H 7180 BP

### 30" Convection Oven - ContourLine

#### Features:

- DirectSensor S - Intuitive touch controls
- Miele@Home - Control the appliances with your app
- Self Cleaning Oven
- Automatic programs - easily master new recipes

#### Included:

- 1 Universal baking tray
- 1 Self Clean Ready Baking and Roasting Rack with Perfect Clean
- 1 Self Clean Ready Rack with rail system




#### MATERIAL #

11805340

SPECIFICATIONS	
Overall Unit Dimensions	29 <sup>13</sup> / <sub>16</sub> " (757 mm) W x 28 <sup>5</sup> / <sub>8</sub> " (727 mm) H x 23 <sup>3</sup> / <sub>4</sub> " (603 mm) D
Niche	
Minimum Cabinet Niche Opening	28 <sup>1</sup> / <sub>2</sub> " (724 mm) W x 28 <sup>1</sup> / <sub>4</sub> " (718 mm) H x 24" (610 mm) D
Electrical	
Electrical Requirements	120/208-240V, 60Hz, 30 Amps
Power Cord	NEMA 14-30 plug, 5 ft (1.52 m)
Shipping	
Shipping Weight	215 lbs (98 kg)
Shipping Dimensions	30 <sup>7</sup> / <sub>16</sub> " (776 mm) W x 35 <sup>3</sup> / <sub>4</sub> " (907 mm) H x 32 <sup>15</sup> / <sub>16</sub> " (836 mm) D

#### PRODUCT DIMENSIONS




E = Electrical Connection




W = No water connection in this model, please disregard

## FLUSH CUTOUT DIMENSIONS

Front View



Side View




A - Cut-out (4" x 28" [100 mm x 720 mm]) in the bottom of the cabinet for the power cord and Ventilation

ⓘ - Electrical and water supplies are recommended to be placed in adjacent cabinetry.




Additional cabinet depth is required when placing the electrical and water supplies behind the appliance.

## PROUD CUTOUT DIMENSIONS

Front View



Side View



A - Cut-out (4" x 28" [100 mm x 720 mm]) in the bottom of the cabinet for the power cord and Ventilation

ⓘ - Electrical and water supplies are recommended to be placed in adjacent cabinetry.

Additional cabinet depth is required when placing the electrical and water supplies behind the appliance.

## G 7266 SCVi XXL

Fully-integrated, full-size dishwasher  
with 3D MultiFlex Tray for maximum convenience.



- Perfect results in less than one hour – QuickIntenseWash
- Everything completely dry – AutoOpen assisted drying
- Incredibly low sound emissions of just 42 dB(A)
- Very easy door opening and closing – ComfortClose
- Versatile and secure – ExtraComfort basket design

EAN: 4002516770978 / Material number: 12497380 / Article Number: 21726662CDN

Type	
Fully integrated dishwashers	•
60 cm dishwashers	•
Design	
Control panel colour	Stainless Steel
Control panel version	Fully integrated fascia
Control type	Program selector button
Display	1-line text display
Display colour	White
Language Options	•
Convenience	
Networking with Miele@home	•
Door closing aid	ComfortClose
Operating noise dB(A) re 1 pW	42
Time left display	•
Delay start up to 24 h	•
In-operation indicator light	optical and acoustic
Display language selection	•
Efficiency and sustainability	
EcoPower technology	•
Proven hygiene	•
Hot-water connection	•
Half load	•
Quality of results	
Fresh-water dishwasher	•
AutoOpen drying	•
SensorDry	•
Recirculation turbothermic drying	•
PerfectGlassCare	•
Wash programs	
Intensive 75°C	•
QuickIntenseWash	•
Sanitize	•
ExtraQuiet 40 dB(A)	•
Clean Machine	•
Rinse & Hold	•
Cleaning options	
IntenseZone	•
Express	•
Extra clean	•
Extra dry	•
Basket design	
Cutlery loading	3D MultiFlex tray
FlexCare glass holder	2
FlexCare cup rack	1
Basket design	ExtraComfort
MultiClip	•
Safety	
Waterproof system	•
Check filter indicator	•


G 7266 SCVi XXL  
Fully-integrated, full-size dishwasher  
with 3D MultiFlex Tray for maximum convenience.



EAN: 4002516770978 / Material number: 12497380 / Article Number: 21726662CDN

Child lock	•
Technical data	
Minimum niche width in mm	23 5/8 (600)
Maximum niche width in mm	23 5/8 (600)
Minimum niche height in mm	33 3/4 (855)
Maximum niche height in mm	36 1/4 (920)
Niche depth in mm	21 3/4 (550)
Appliance depth with door open in cm	47 1/2 (120.5)
Net weight in kg	109 (49.0)
Total rated load in kW	1.40
Voltage in V	120
Fuse rating in A	15
Number of phases	1
Electrical frequency standard	60
Length of water inlet hose in cm	5 (1.50)
Length of water drain hose in cm	5 (1.50)
Length of power cable in m	4 (1.20)
Min. front panel weight in kg	4.0
Max. front panel weight in kg	12.0
Available display languages	
Available display languages via Language Options	deutsch, english (US), español, français (CA). [?][?][?]
Accessories supplied	
1 x UltraTabs box (20 tabs)	•








SU90134X

**SU 901**  
stainless steel AISI 430



<b>MOTOR</b>	Dual Motor EBM 1100 CFM Pressure: 800 Pa Noise level: 66 dBA/5.1 Sones
<b>LIGHTING</b>	2x4W led spot
<b>CONTROL PANEL</b>	4 speed push-button + delay off timer + light switch
<b>GREASE FILTER</b>	Commercial style baffle filters with oil catcher
<b>AIR OUTLET</b>	8" round
<b>DISCHARGE</b>	Vertical
<b>CUT OUT</b>	32 <sup>13/32</sup> x 16 <sup>3/16</sup>
<b>ACCESSORIES</b>	Adjustable pro liners: Pro liner 36" stainless PLSS36A Cod. 00915813601 Pro liner 42" stainless PLSS42A Cod. 00915813901 Pro liner 48" stainless PLSS48A Cod. 00915813701 Charcoal filters: KF7 (order 2 pcs) 60080477002



**Profile 5.5 cu. ft. Capacity  
UltraFast Combo, Ventless Heat  
Pump Technology Washer/Dryer  
Carbon Graphite PFQ97HSPVDS**

Model PFQ97HSPVDS

## Specifications

Height	118.62 cm - 46.70 in
Width	71.12 cm - 28.00 in
Depth	81.28 cm - 32.00 in
Weight	136.98 kg - 301.99 lb
Adjustable Leveling Legs	Yes Yes
Wash Basket Type	Stainless Steel Stainless Steel
Child Lock	Yes Yes
Colour	Carbon Graphite Carbon Graphite
Dispenser	Fabric Softener Timed Flow Through Protected with Microban Bleach / Detergent (Liquid/Powder) / Fabric Softener Bleach Timed Flow Through Dual Drawer Bulk Dispenser Fabric Softener Timed Flow Through Protected with Microban
Dry Cycles	Speed Wash Wrinkle Care Spin and dry Steam Timed Dry Towels Whites Active Wear Bulky/Bedding

	Delicates Dewrinkle Downloaded EcoCool™ Normal Speed Wash
End-of-Cycle Signal	Yes Yes
Fuel Type	Electric Electric
Temperature Levels	5 5
Number of Cycles	12 12
Optional Soil Levels	Extra Heavy / Heavy / Normal / Light / Extra Light Extra Heavy / Heavy / Normal / Light / Extra Light
Options	Delay Start Delay Start
Spin Speed	5 Speeds 5 Speeds
Control Type	Electronic Touch Electronic Touch
Style	Front Load Front Load
Maximum Spin Speed	1300 RPM 1300 RPM
Volts / Hertz	120 v / 60 Hz 120 v / 60 Hz
Warranty	Limited 5-Year Drying Sealed System 1 Year Parts & Labour 10-Year Motor Warranty Limited 5-Year Drying Sealed System
Wash Cycles	Whites Active Wear Bulky/Bedding Delicates Downloaded EcoCool™ Normal Speed Wash Rinse & Dry Sanitize with Oxi Basket Clean Towels Whites
Width	28" 28"
Capacity (cu. ft.)	5

	5.5 5 5.5
Functions	Extra Rinse Wash+Dry; Wash Only; Dry Only Extra Rinse
Features	Round Door with Glass Viewing Window Attached PowerCord Auto Load Sensing Drain Hose Included Round Door with Glass Viewing Window EZ Access dual lint mesh & foam filter Drum Light Wash Complete Alert
ADA Compliant	Yes Yes
Additional Cycles	Swimwear Additional made available through Download Cycle Air Fluff Jeans Power Clean Swimwear
Automatic Dry Control	Yes Yes
Dryer Control Features	Control Sounds On/Off Add Garment Available in 3 Languages Brightness High/Medium/Low Control Sounds On/Off Brightness High/Medium/Low Control Sounds On/Off LED Indicators
Cycle Progression Information	Yes Yes
Help Functions / Menu	Yes Yes
Add remote Start	Yes Yes
SmartDispense™	Bulk Detergent 50 oz and Bulk Softener 32 oz Bulk Detergent 50 oz and Bulk Softener 32 oz
Exhaust Options	Ventless Heat Pump Ventless Heat Pump
Sensor Dry	Yes Yes
OdorBlock Capabilities	UltraFresh Ventless System with OdorBlock™ UltraFresh Ventless System with OdorBlock™
Receptacle Type	3-Prong Grounding 3-Prong Grounding

Vibration Control	dBT™ Dynamic Balancing Technology dBT™ Dynamic Balancing Technology
Wash System	Tumble Wash & Condenser Dryer Tumble Wash & Condenser Dryer
Timed Dry	Timed Dry Timed Dry
Washer Options	PreWash PreWash
Water Levels	More Water Load-Sensing Adaptive Fill More Water
Water Temp System	Tap Cold, Cold, Warm, Hot, Extra Hot Tap Cold, Cold, Warm, Hot, Extra Hot
Handle	Pocket Pocket
Wifi Connect	Yes Yes
Energy Star	Yes Yes

# PFQ97HSPVDS

GE Profile™ 4.8 cu. ft. Capacity UltraFast Combo with Ventless Heat Pump Technology Washer/Dryer

## DIMENSIONS AND INSTALLATION INFORMATION (IN INCHES)

ELECTRIC RATING	
120V	11.0A, 60Hz


**INSTALLATION INFORMATION:** For complete information, see installation instructions packed with your Combo.

**CIRCUIT REQUIREMENTS:** An individual, properly grounded branch circuit, protected by a 15-amp circuit breaker or a time-delay fuse, is required.

**NOTE:** Combo wall outlet must be located within 36" of service cord entry and accessible when combo is mounted in position.

**INCLUDED POWER CORD LENGTH - Up to 66"**

**INCLUDED DRAIN HOSE LENGTH - Up to 60"**



For answers to your Monogram, GE Café™, GE Profile™ or GE Appliances product questions, visit our website at [geappliances.com](http://geappliances.com) or call GE Answer Center® Service, 800.626.2000.

# PFQ97HSPVDS

GE Profile™ 4.8 cu. ft. Capacity UltraFast Combo with Ventless Heat Pump Technology Washer/Dryer

### ALCOVE OR CLOSET INSTALLATION:

-Approved for closet installation. Closet doors must be louvered or otherwise ventilated and have at least 60 square inches (387.1 cm2) of open area.

### -No Venting Required.

-Minimum clearances between Combo cabinet and adjacent walls or other surfaces are: 0" all sides and top.\*

### MINIMUM CLEARANCE OTHER THAN ALCOVE OR CLOSET INSTALLATIONS:

-Minimum clearances to combustible surfaces 0" all sides and top.\*

### WEIGHT

- Carton weight 323 lbs
- Product weight 302 lbs

\*For improved performance, a 1/2" clearance is suggested on each side.

### ACCESSORIES



Fill Hoses	WH41X10207 (sold separately)
Optional Riser	GFR0728PTDS (sold separately)
Sink Uncoupler Hook-up	WH41X27468 (sold separately)
Drain Hose Extension Kit- Approx. 44"	WH49X316 (sold separately)
Universal low profile washer floor tray	PM7X2 (sold separately)
Touch-Up-Paint - 0.6 OZ.	WR97X27706 (sold separately)

### WARRANTY

Labor Warranty	Limited 1-year entire appliance
Parts Warranty	Limited 1-year entire appliance Limited 5-year sealed system Limited 10-year motor




For answers to your Monogram, GE Café™, GE Profile™ or GE Appliances product questions, visit our website at [geappliances.com](http://geappliances.com) or call GE Answer Center® Service, 800.626.2000.



### RISER DIMENSIONS (IN INCHES) GFR0728PTDS - CARBON GRAPHITE

This optional 7" riser raises the door opening and height of the Combo unit. On a riser this unit is no longer ADA compliant. Not suggested for installation on a 16" pedestal.



BACK VIEW

# Installation Instructions

## ELECTRICAL REQUIREMENTS

### ⚠ WARNING ⚡ - Electrical Shock Hazard

Plug into a grounded 3-prong outlet.

**DO NOT** remove ground prong.

**DO NOT** use an adapter.

**DO NOT** use an extension cord.


Failure to follow these instructions can result in death, fire or electrical shock.

**CIRCUIT** – Individual, properly polarized and grounded 15 or 20 amp circuit breaker or time-delay fuse.

**POWER SUPPLY** – 2 wire plus ground, 120 Volt, single phase, 60 Hz, alternating current.

**Outlet Receptacle** – Properly grounded 3-prong receptacle to be located so the power cord is accessible when the Combo is in an installed position. If a 2-prong receptacle is present, it is the owner's responsibility to have a licensed electrician replace it with a properly grounded 3-prong grounding type receptacle.

Unit must be electrically grounded in accordance with local codes and ordinances, or in the absence of local codes, with latest edition of the NATIONAL ELECTRICAL CODE, ANSI/NFPA NO. 70 or CANADIAN ELECTRICAL CODE, CSA C22.1. Check with a licensed electrician if you are not sure that the Combo is properly grounded.



## GROUNDING INSTRUCTIONS

This appliance must be grounded. In the event of malfunction or breakdown, grounding will reduce the risk of electric shock by providing a path of least resistance for electric current. This appliance is equipped with a cord having an equipment-grounding conductor and a grounding plug. The plug must be plugged into an appropriate outlet that is properly installed and grounded in accordance with all local codes and ordinances.

**⚠ WARNING** Improper connection of the equipment-grounding conductor can result in a risk of electrical shock. Check with a qualified electrician, or service representative or personnel, if you are in doubt as to whether the appliance is properly grounded. **DO NOT** modify the plug on the power supply cord. If it will not fit the outlet, have a proper outlet installed by a qualified electrician.

If required by local codes, an external 18 gauge or larger copper ground wire (not provided) may be added. Attach to Combo cabinet with a #10-16 x 1/2" sheet metal screw (available at any hardware store) to rear of Combo.

### ⚠ WARNING ⚡ - Electrical Shock Hazard

Disconnect power supply before servicing.

Replace all parts and panels before operating.

Failure to do so can result in death or electrical shock.

### ⚠ WARNING - Shock Hazard

Certain internal parts are intentionally not grounded and may present a risk of electric shock only during servicing.



**Service personnel – DO NOT** contact the following parts while the appliance is energized: water valve, drain pump, NTC, door lock, inverter board, motor and MC board.

## WATER SUPPLY REQUIREMENTS

The faucets **MUST** be 3/4" (1.9 cm) garden hose-type so inlet hoses can be connected. Water pressure **MUST** be between 10 and 120 pounds per square inch. Your water department can advise you of your water pressure. The hot water temperature should be set to deliver water at 120° to 140°F (48°–60°C) to provide proper Automatic Temperature Control (ATC) performance.

## DRAIN REQUIREMENTS

1. Drain capable of eliminating 10 gallons (38 L) per minute.
2. A standpipe diameter of 1-1/4" (3.18 cm) minimum.
3. The standpipe height above the floor should be:  
Minimum height: 24" (61 cm)  
Maximum height: 96" (244 cm)








**GFR0728PTDS**

**GE Laundry 7" RightHeight  
Riser**



Color Appearance	Carbon Graphite
Installation	Compatible with GFW510, GFW550, GFW650, GFW850, GFD55, GFD65, GFD85
Parts Warranty	Limited 1-year entire appliance
Approximate Shipping Weight	30 lb
Net Weight	29.5 lb
Overall Depth	28 7/16 in
Overall Height	7 in
Overall Width	28 in

*Specifications are subject to change without warning. Specifications are intended for initial planning purposes and any final planning, cabinet & countertop cutouts, etc. should be calculated using the manufacturer's installation guide or actual appliance.*

## G 7266 SCVi

### 24" Fully Integrated Dishwasher

#### Features:

- DirectSelect Controls
- QuickIntenseWash - a full wash and dry cycle in 58 minutes
- 42 dBa
- 3D MultiFlex Cutlery Tray
- Panel-Ready
- Water Softener
- EnergyStar


#### MATERIAL #

12497140




SPECIFICATIONS	
Overall Unit Dimensions	23 <sup>9</sup> / <sub>16</sub> " (598 mm) W x 33 <sup>11</sup> / <sub>16</sub> " - 36 <sup>1</sup> / <sub>4</sub> " (855 - 920 mm) H x 22 <sup>7</sup> / <sub>16</sub> " (570 mm) D [Depth does not include door panel]
Niche	
Minimum Cabinet Niche Opening	23 <sup>5</sup> / <sub>8</sub> " (600 mm) W x 33 <sup>3</sup> / <sub>4</sub> " (857 mm) H x 22 <sup>7</sup> / <sub>16</sub> " (570 mm) D
Plumbing	
Water Supply Requirements	<ul style="list-style-type: none"> <li>• Cold or Hot (max 150°F/65°C) water connection</li> <li>• Male 3/8" compression fitting</li> <li>• Water pressure range 7.25 psi (0.5 bar) and 145 psi (10 bar)</li> </ul>
Water Connection Line (Supplied)	Length: 5 ft (1.5 m) Female 3/8" compression.
Drain Hose (Supplied)	Length: 5 ft (1.5 m) 7/8" (22 mm) internal diameter
Electrical	
Electrical Requirements	110V / 120V, 60Hz, 15 Amps
Power Cord (Convertible to hardwire)	NEMA 5-15 plug, 5 ft (1.52 m)
Shipping	
Shipping Weight	121 lbs (55 kg)
Shipping Dimensions	27 <sup>1</sup> / <sub>8</sub> " W x 38 <sup>1</sup> / <sub>8</sub> " H x 26 <sup>3</sup> / <sub>8</sub> " D


#### PRODUCT DIMENSIONS



## CUTOUT DIMENSIONS



## CUSTOM PANEL



**Width:** 23 7/16" (595 mm) in all Cases  
**Thickness:** 3/4" (19 mm) in all Cases  
**Height:** Determined using the following calculation:

$$\text{Panel Height} = \text{HTC} - \text{TKH}$$

**HTC** = Height to the underside of countertop

**TKH** = Toe kick height

**Note:** Control panel is along the top edge of the unit. It is not visible when the unit is closed. A handle **MUST** be located on front of panel in order to open unit. (Except K2o models).

Maximum panel height: 31 7/8" (810 mm)

Minimum panel height: 27 1/8" (690 mm)

Maximum panel weight: 22 lbs (10 kg)