




RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION

TOWN OF MILTON
PLANNING AND DEVELOPMENT
JUNIPER 8 MODEL

BUILDING: REVIEWED
SCOTT SHERRIFFS MAR 30, 2017
PLANS EXAMINER DATE

Neither the issuance of a permit nor carrying out of inspections by the Town of Milton relieves the owner from full responsibility for compliance with the provisions of the Ontario Building Code Act and the Ontario Building Code, both as amended, as well as other applicable statutes and regulations of the Province of Ontario, By-laws of the Region of Halton and Town of Milton

CONVENTIONAL FRAMING BY OTHERS

ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 OF THE O.B.C.
ROOF RAFTERS THAT CROSS MEET OVER TRUSSES TO BE 2x4 S.P.F. @ 24"O/C WITH A 2x4 VERTICAL POST TO THE TRUSS UNDERNEATH EACH CROSS POINT. VERTICAL POST LONGER THAN 6' TO HAVE LATERAL BRACING SO THAT THE DISTANCE BETWEEN END POINT AND BETWEEN ROWS OF BRACING DOES NOT EXCEED 6'.

HANGER LEGEND:

▼ LUS24 ■ LJS26DS
● HGUS26 ✕ HGUS26-2

SIZE AND LOCATION OF CONVENTIONAL FRAMING IS APPROXIMATE. ALL AREAS MAY NOT BE SHOWN. REFER TO ARCHITECTURAL PLANS FOR DETAILS.

Model: **JUNIPER 8 EL 3**
Customer: **GREENPARK**
Project: **LECCO RIDGE**
Location: **MILTON**
Date: **10/13/2016** Drawn by: **BB**

ENGINEERING NOTE PAGE (ENP-1)

PLEASE READ PRIOR TO INSTALLATION

RESPONSIBILITIES

THIS DESIGN IS FOR AN INDIVIDUAL BUILDING COMPONENT AND HAS BEEN BASED ON INFORMATION PROVIDED BY THE DESIGN OFFICE OF KOTT LUMBER. THE UNDERSIGNED ENGINEER DISCLAIMS ANY RESPONSIBILITY FOR DAMAGES AS A RESULT OF FAULTY OR INCORRECT INFORMATION, SPECIFICATION AND/OR DESIGNS FURNISHED TO THE ENGINEER. THE UNDERSIGNED ENGINEER IS ONLY RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THIS BUILDING COMPONENT FOR THE CONDITIONS AND LOADS SHOWN ON THIS DRAWING. THE STRUCTURAL INTEGRITY OF THE BUILDING AND THE VERIFICATION OF THE DIMENSIONS AND THE DESIGN LOADS USED ARE THE RESPONSIBILITY OF THE BUILDING DESIGNER.

TRUSSES ARE DESIGNED IN CONFORMANCE WITH THE RELEVANT SECTIONS OF THE NATIONAL BUILDING CODE OF CANADA OR THE CANADIAN CODE FOR FARM BUILDINGS, WHICHEVER APPLIES TO THE BUILDING TYPE INDICATED ON THE DRAWING

IT IS THE RESPONSIBILITY OF KOTT LUMBER TO ENSURE THAT TRUSSES ARE MANUFACTURED IN CONFORMANCE WITH THESE DESIGNS AND WITH THE SPECIFICATIONS OUTLINED BELOW. THE UNDERSIGNED ENGINEER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

USE AND OCCUPANCY

- The building is of the type indicated on the drawing

LOADING

- The truss loading intensity and distribution as well as load transfer mechanism is that indicated on the drawing
- No buildings, trees, parapets or other projections higher than the roof for which the trusses are used are located within a distance less than ten (10) times the difference in height, or five metres (16 ft) whichever is greater, unless the drawing indicates that the snow drifting has been taken into account

HANDLING, INSTALLATION AND BRACING

- The trusses must be handled and installed by a qualified professional as per the supplied document titled *Information for Truss Installers* and the BCSI-B1 and BCSI-B3 Summary Sheets
- The compression chords are laterally braced by continuous rigid diaphragm sheathing or as specified on the drawing
- Temporary and permanent bracing must be installed as indicated on the truss drawing and according to the BCSI-B1 and BCSI-B3 Summary Sheets. Bracing for the lateral stability of the truss is to be provided by the building designer
- **It is recommended that a Professional Engineer's advice be obtained for the bracing of trusses spanning more than 12.37m (40'-7")**

SUPPORTS

- The trusses are to be supported at the bearing points indicated and anchored to the supports where considered necessary by the designer of the overall structure
- Bearing sizes shown are the minimum required to prevent crushing of the truss members and do not necessarily take into account stability of the overall building structure
- Elevation of bearings must be carefully checked and shimmed to alignment for solid bearings
- Adequate wood truss bearing is the responsibility of the building designer.


DIMENSIONS

- Geometry of the truss and dimensions indicated on the drawing are identical to those of the installed truss.

WHERE CONTINUOUS LATERAL BRACING IS REQUIRED FOR WEBS BUT CAN NOT BE PROVIDED SUBSTITUTE EACH WITH ONE SPF #2 2" X 4" T-BRACE COVERING 90% OF WEB LENGTH AND FASTENED TO EDGE OF WEB USING 3 1/4" SPIRAL NAILS @ 6" C/C

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION

01/29/2013



LUMBER

N. L. G. A. RULES

CHORDS

SIZE

LUMBER

DESCR.

1 - 3

2x4

DRY

No.2

SPF

3 - 7

2x6

DRY

No.2

SPF

7 - 10

2x6

DRY

No.2

SPF

10 - 12

2x4

DRY

No.2

SPF

23 - 2

2x6

DRY

No.2

SPF

13 - 11

2x6

DRY

No.2

SPF

23 - 19

2x6

DRY

2100F 1.8E

SPF

19 - 16

2x6

DRY

2100F 1.8E

SPF

16 - 13

2x6

DRY

2100F 1.8E

SPF

ALL WEBS

2x3

DRY

No.2

SPF

EXCEPT

17 - 9

2x4

DRY

No.2

SPF

15 - 10

2x4

DRY

No.2

SPF

2 - 22

2x4

DRY

No.2

SPF

14 - 11

2x4

DRY

No.2

SPF

DRY: SEASONED LUMBER.

TOTAL WEIGHT = 197 lb

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
BEARINGS									
		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
		GROSS REACTION		GROSS REACTION		BRG		BRG	
JT		VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
23		3098	0	3098	0	0	5-8	5-8	
13		4010	0	4010	0	0	5-8	5-8	

UNFACTORED REACTIONS									
		1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT		COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
23		2171	1534 / 0	0 / 0	0 / 0	0 / 0	638 / 0	0 / 0	
13		2812	1980 / 0	0 / 0	0 / 0	0 / 0	832 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 23, 13

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 1.97 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***

GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.

LOADS WERE DERIVED FROM USER INPUT

NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF

DL = 3.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.0 PSF

TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

LOADING									
TOTAL LOAD CASES: (4)									
		CHORDS		WEBS					
		MAX. FACTORED		MAX. FACTORED					
MEMB.		FORCE	VERT. LOAD	FORCE	VERT. LOAD	MEMB.		FORCE	VERT. LOAD
(LBS)		(LBS)	(PLF)	(LBS)	(PLF)	(LBS)		(LBS)	(PLF)
FR-TO			FROM TO		FROM TO				FROM TO
1-2		0 / 29	-77.3	-77.3	0.11 (1)	10.00	22-3	-618 / 0	0.15 (1)
2-3		-3761 / 0	-77.3	-77.3	0.53 (1)	3.16	3-21	0 / 3756	0.93 (1)
3-4		-6001 / 0	-77.3	-77.3	0.37 (1)	3.33	21-4	-2369 / 0	0.58 (1)
4-5		-8352 / 0	-77.3	-77.3	0.60 (1)	2.65	4-20	0 / 3059	0.76 (1)
5-6		-10139 / 0	-77.3	-77.3	0.86 (1)	2.12	20-5	-1822 / 0	0.45 (1)
6-7		-10139 / 0	-110.1	-110.1	0.97 (1)	1.97	5-18	0 / 2324	0.58 (1)
7-8		-10139 / 0	-110.1	-110.1	0.97 (1)	1.97	18-6	-424 / 0	0.10 (1)
8-9		-9779 / 0	-110.1	-110.1	0.84 (1)	2.21	18-8	0 / 446	0.11 (1)
9-10		-7762 / 0	-110.1	-110.1	0.66 (1)	2.67	17-8	-837 / 0	0.20 (1)
10-11		-5020 / 0	-77.3	-77.3	0.74 (1)	2.54	17-9	0 / 2514	0.44 (1)
11-12		0 / 29	-77.3	-77.3	0.11 (1)	10.00	15-9	-2135 / 0	0.52 (1)
23-2		-3075 / 0	0.0	0.0	0.22 (1)	5.97	15-10	0 / 4445	0.79 (1)
13-11		-4014 / 0	0.0	0.0	0.29 (1)	5.31	14-10	-372 / 0	0.09 (1)
							2-22	0 / 3224	0.57 (1)
23-22		0 / 0	-17.5	-17.5	0.03 (4)	10.00	14-11	0 / 4303	0.76 (1)
22-21		0 / 3122	-17.5	-17.5	0.19 (1)	10.00			
21-20		0 / 6001	-17.5	-17.5	0.35 (1)	10.00			
20-19		0 / 8352	-17.5	-17.5	0.55 (1)	10.00			
19-18		0 / 8352	-17.5	-17.5	0.55 (1)	10.00			
18-17		0 / 9779	-24.9	-24.9	0.62 (1)	10.00			
17-24		0 / 7762	-24.9	-24.9	0.60 (1)	10.00			
24-16		0 / 7762	-24.9	-24.9	0.60 (1)	10.00			
16-15		0 / 7762	-24.9	-24.9	0.60 (1)	10.00			
15-25		0 / 4179	-24.9	-24.9	0.42 (1)	10.00			
25-14		0 / 4179	-24.9	-24.9	0.42 (1)	10.00			
14-13		0 / 0	-24.9	-24.9	0.10 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)									
JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE		
10	32-8-4	-142	-142	---	FRONT	VERT	TOTAL		
18	17-6-4	-1352	-1352	---	FRONT	VERT	TOTAL		
24	23-9-12	-634	-634	---	FRONT	VERT	TOTAL		
25	31-0-4	-634	-634	---	FRONT	VERT	TOTAL		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014

- CSA 086-09

- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.23")

CALCULATED VERT. DEFL.(LL) = L/902 (0.49")

ALLOWABLE DEFL.(TL)= L/360 (1.23")

CALCULATED VERT. DEFL.(TL) = L/513 (0.86")

CSI: TC=0.97 (6-8:1), BC=0.62 (17-18:1), WB=0.93 (3-21:1), SSI=0.35 (15-17:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION

(PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN

MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 0.250 degrees

RECEIVED

TOWN OF MILTON

MAR 29, 2017


JUNIPER 8

BUILDING DIVISION

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

KOTT

CONTINUED ON PAGE 2



SCALE = 1:30.2

TOTAL WEIGHT = 2 X 29 = 59 lb
[M]

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 3	2x4	DRY	No.2	SPF
4 - 3	2x4	DRY	No.2	SPF
6 - 1	2x4	DRY	No.2	SPF
6 - 4	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
1	TMWW-t	MT20	3.0	5.0	1.50	2.25
2	TMWW-t	MT20	3.0	4.0	1.50	1.75
3	TMV+p	MT20	2.0	4.0		
4	BMVW1-t	MT20	4.0	4.0		
5	BMWW+t	MT20	3.0	4.0	1.75	1.50
6	BMV1+p	MT20	2.0	4.0		

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

HANGERS NOTES

1) SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 511.5 lbs FACTORED DOWN AT 4-1-4 ON BOTTOM CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
JT		VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX
4		634	0	634	0	0	IN-SX
						HANGER BY OTHERS	
						MIN. SEAT SIZE: 3-8	
6		446	0	446	0	0	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
4	445	311 / 0	0 / 0	0 / 0	0 / 0	134 / 0	0 / 0
6	313	219 / 0	0 / 0	0 / 0	0 / 0	94 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 6

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (3)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED (LC1) (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED (LC1) (LC)	
FR-TO		FROM TO		FR-TO			
1-2	-524 / 0	-77.3	-77.3 0.12 (1)	6.25	5-2	0 / 320	0.08 (1)
2-3	-11 / 0	-77.3	-77.3 0.11 (1)	6.25	2-4	-601 / 0	0.15 (1)
4-3	-91 / 0	0.0	0.0 0.02 (1)	7.81	1-5	0 / 494	0.12 (1)
6-1	-454 / 0	0.0	0.0 0.05 (1)	7.81			
6-5	0 / 0	-17.5	-17.5 0.07 (1)	10.00			
5-7	0 / 479	-17.5	-17.5 0.29 (1)	10.00			
7-4	0 / 479	-17.5	-17.5 0.29 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
7	4-1-4	-512	-512	---	FRONT	VERT	TOTAL

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP	CH.	LL	=	23.3	PSF
		DL	=	3.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.0	PSF
TOTAL LOAD		=	33.3	PSF	

SPACING = 24.0 IN./C

*** NON STANDARD GIRDER ***
ADDT'L USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.02")

CSI: TC=0.12 (1-2:1), BC=0.29 (4-5:1), WB=0.15 (2-4:1), SSI=0.25 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (5) (INPUT = 0.90)
JSI METAL= 0.21 (5) (INPUT = 0.25)

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
6 - 1	2x4	DRY	No.2	SPF
1 - 3	2x6	DRY	No.2	SPF
4 - 3	2x4	DRY	No.2	SPF
6 - 4	2x6	DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF				
DRY: SEASONED LUMBER.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
1	TMW-t	MT20	3.0	4.0	
2	TMW-w	MT20	2.0	4.0	
3	TMW-t	MT20	3.0	4.0	
4	BMV1+p	MT20	2.0	4.0	
5	BMVWW-t	MT20	4.0	6.0	
6	BMV1+p	MT20	2.0	4.0	

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT		VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX		
6		511	0	511	0	0		HANGER BY OTHERS	
4		511	0	511	0	0		HANGER BY OTHERS	
								MIN. SEAT SIZE: 1-8	

UNFACTORED REACTIONS		1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT		COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
6		359	251 / 0	0 / 0	0 / 0	0 / 0	108 / 0	0 / 0	
4		359	251 / 0	0 / 0	0 / 0	0 / 0	108 / 0	0 / 0	

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)		CHORDS		WEBS					
MEMB.		MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRAC LENGTH	MEMB.		MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)
FR-TO			FROM	TO		FR-TO			
6-1		-409 / 0	0.0	0.0	0.06 (1)	7.81	1-5	0 / 479	0.12 (1)
1-2		-380 / 0	-77.3	-77.3	0.07 (1)	6.25	5-2	-316 / 0	0.06 (1)
2-3		-380 / 0	-77.3	-77.3	0.07 (1)	6.25	5-3	0 / 479	0.12 (1)
4-3		-409 / 0	0.0	0.0	0.06 (1)	7.81			
6-5		0 / 0	-66.9	-66.9	0.06 (1)	10.00			
5-4		0 / 0	-66.9	-66.9	0.06 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:		
TOP CH.	LL =	23.3 PSF
	DL =	3.0 PSF
BOT CH.	LL =	0.0 PSF
	DL =	7.0 PSF
TOTAL LOAD = 33.3 PSF		

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CStdGirder
START DISTANCE = 0-0
START SPAN CARRIED = 4-1-0
END DISTANCE = 7-1-0
END SPAN CARRIED = 4-1-0
END WALL WIDTH = 0-0
APPLIED TO FRONT SIDE OF BOTTOM CHORD.
- ADDT'L LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.24")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.24")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.01")

CSI: TC=0.07 (1-2:1) , BC=0.06 (5-6:1) , WB=0.12 (1-5:1) , SSI=0.10 (1-2:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES		
PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)
	MAX MIN	MAX MIN
MT20	618 354	1667 822

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION = 0.000

JSI GRIP= 0.73 (3)
JSI METAL= 0.14

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





SCALE = 1:30.2

TOTAL WEIGHT = 29 lb

LUMBER				DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	
1 - 3	2x4	DRY	No.2	SPF
4 - 3	2x4	DRY	No.2	SPF
6 - 1	2x4	DRY	No.2	SPF
6 - 4	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
1	TMVW-t	MT20	3.0	6.0		
2	TMVW-t	MT20	4.0	4.0	1.75	1.25
3	TMV+p	MT20	2.0	4.0		
4	BMVW1-t	MT20	4.0	4.0	1.75	1.75
5	BMVW-t	MT20	4.0	6.0	3.00	1.75
6	BMV1+p	MT20	2.0	4.0		

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT		VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
4		1352	0	1352	0	0	HANGER BY OTHERS		
6		1352	0	1352	0	0	MIN. SEAT SIZE: 3-8	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS						
JT		COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
4		949	664 / 0	0 / 0	0 / 0	0 / 0	285 / 0	0 / 0
6		949	664 / 0	0 / 0	0 / 0	0 / 0	285 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 6

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.78 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM	TO	FR-TO			
1-2	-1152 / 0	-77.3	-77.3 0.11 (1)	5-78	5-2	0 / 1033	0.26 (1)
2-3	-9 / 0	-77.3	-77.3 0.09 (1)	10.00	2-4	-1304 / 0	0.32 (1)
4-3	-95 / 0	0.0	0.0 0.02 (1)	7.81	1-5	0 / 1073	0.27 (1)
6-1	-883 / 0	0.0	0.0 0.10 (1)	7.81			
6-5	0 / 0	-373.2	-373.2 0.22 (1)	10.00			
5-4	0 / 1039	-373.2	-373.2 0.35 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL	=	23.3	PSF
		DL	=	3.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.0	PSF
TOTAL LOAD		=	33.3	PSF	

SPACING = 24.0 IN. C/C

GIRDER TYPE: CStdGirder
START DISTANCE = 0-0
START SPAN CARRIED = 17-5-8
END DISTANCE = 6-0-0
END SPAN CARRIED = 17-5-8
END WALL WIDTH = 5-8
APPLIED TO FRONT SIDE OF BOTTOM CHORD.
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.11 (1-2:1), BC=0.35 (4-5:1), WB=0.32 (2-4:1), SSI=0.43 (5-6:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES		PLATE GRIP(DRY) SHEAR		SECTION	
(PSI)	(PLI)	(PLI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1667	822	2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.90 (1) (INPUT = 0.90)
JSI METAL= 0.39 (2) (INPUT = 1.00)

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.







SCALE = 1:26.9

TOTAL WEIGHT = 23 lb [M]

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
1 - 3	2x4	DRY	No.2		SPF
4 - 3	2x4	DRY	No.2		SPF
6 - 1	2x4	DRY	No.2		SPF
6 - 4	2x6	DRY	No.2		SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
1	TMWW-t	MT20	3.0	5.0	1.50	2.00
2	TMWW-t	MT20	3.0	4.0	1.50	1.50
3	TMV+p	MT20	2.0	4.0		
4	BMVW1-t	MT20	4.0	4.0		
5	BMWW+t	MT20	3.0	4.0		
6	BMV1+p	MT20	2.0	4.0		

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

HANGERS NOTES

- 1) SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 454.5 lbs FACTORED DOWN AT 1-9-4 ON BOTTOM CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT		VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
4		577	0	577	0	0	HANGER BY OTHERS		
							MIN. SEAT SIZE: 3-8		
6		470	0	470	0	0	5-8	5-8	

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
4	405	283 / 0	0 / 0	0 / 0	0 / 0	122 / 0	0 / 0		
6	330	231 / 0	0 / 0	0 / 0	0 / 0	99 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 6

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	FORCE (LBS)	MAX. LC1 (LC)	
FR-TO		FROM	TO	FR-TO			
1-2	-373 / 0	-77.3	-77.3 0.05 (1)	6.25	5-2	0 / 396	0.10 (1)
2-3	-8 / 0	-77.3	-77.3 0.05 (1)	10.00	2-4	-487 / 0	0.10 (1)
4-3	-62 / 0	0.0	0.0 0.01 (1)	7.81	1-5	0 / 354	0.09 (1)
6-1	-432 / 0	0.0	0.0 0.05 (1)	7.81			
6-5	0 / 0	-17.5	-17.5 0.03 (1)	10.00			
5-4	0 / 317	-124.2	-124.2 0.10 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
5	1-9-4	-455	-455	---	FRONT	VERT	TOTAL

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP	CH.	LL	=	23.3	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.0	PSF
		TL	=	33.3	PSF

SPACING = 24.0 IN. C/C

GIRDER TYPE: CStdGirder
START DISTANCE = 1-9-4
START SPAN CARRIED = 6-11-8
END DISTANCE = 4-0-0
END SPAN CARRIED = 6-11-8
END WALL WIDTH = 5-8
APPLIED TO FRONT SIDE OF BOTTOM CHORD.
- ADDT'L LOADS BASED ON 55 % OF GSL.

*** NON STANDARD GIRDER ***
ADDT'L USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.01")

CSI: TC=0.05 (1-6:1) , BC=0.10 (4-5:1) , WB=0.10 (2-5:1) , SSI=0.10 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.72 (5) (INPUT = 0.90)
JSI METAL= 0.14 (5) (INPUT = 1.00)



RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 30 lb [M]

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
1 - 2	2x4	DRY	No.2		SPF
2 - 4	2x4	DRY	No.2		SPF
7 - 1	2x4	DRY	No.2		SPF
5 - 3	2x4	DRY	No.2		SPF
7 - 5	2x4	DRY	No.2		SPF
ALL WEBS EXCEPT	2x3	DRY	No.2		SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
1	TMVW-t	MT20	3.0	5.0	1.50	2.00
2	TTW+p	MT20	3.0	4.0	2.25	1.50
3	TMVW-t	MT20	3.0	5.0	1.50	2.00
5	BMV1+p	MT20	2.0	4.0		
6	BMVWW-t	MT20	3.0	6.0		
7	BMV1+p	MT20	2.0	4.0		

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

HANGERS NOTES

- SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 198.1 lbs FACTORED DOWN AT 3-3-0 ON TOP CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS						INPUT BRG	REQRD BRG
FACTORED GROSS REACTION			FACTORED GROSS REACTION				
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
7	455	0	455	0	0	HANGER BY OTHERS	
						MIN. SEAT SIZE: 1-8	
5	548	0	548	0	0	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
7	319	226 / 0	0 / 0	0 / 0	0 / 0	93 / 0	0 / 0	
5	382	282 / 0	0 / 0	0 / 0	0 / 0	100 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX LC1 (LC)	
FR-TO		FROM TO		FR-TO			
1-2	-330 / 0	-77.3	-77.3 0.16 (1)	6-2	-101 / 54	0.02 (1)	
2-3	-330 / 0	-77.3	-77.3 0.20 (1)	1-6	0 / 299	0.07 (1)	
3-4	0 / 29	-77.3	-77.3 0.11 (1)	6-3	0 / 286	0.07 (1)	
7-1	-426 / 0	0.0	0.0 0.05 (1)				
5-3	-513 / 0	0.0	0.0 0.06 (1)				
7-6	0 / 0	-23.0	-23.0 0.09 (4)				
6-5	0 / 0	-23.0	-23.0 0.09 (4)				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
2	3-3-0	-198	-198	---	FRONT	VERT	TOTAL

DESIGN CRITERIA

SPECIFIED LOADS:			
TOP CH.	LL	=	23.3 PSF
	DL	=	3.0 PSF
BOT CH.	LL	=	0.0 PSF
	DL	=	7.0 PSF
TOTAL LOAD	=	33.3	PSF

SPACING = 24.0 IN./C

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 3-3-0
RIGHT SETBACK = 3-8-8
END SETBACK = 3-8-8
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.23")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.23")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.01")

CSI: TC=0.20 (2-3:1) , BC=0.09 (5-6:4) , WB=0.07 (1-6:1) , SSI=0.10 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES				
PLATE	GRIP(DRY)	SHEAR	SECTION	
(PSI)	(PLI)	(PLI)		
MAX MIN	MAX MIN	MAX MIN		
MT20	618	354	1667	822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.54 (6) (INPUT = 0.90)
JSI METAL= 0.14 (3) (INPUT = 1.00)



RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.





LUMBER

N. L. G. A. RULES

CHORDS

SIZE

DRY

No.2

SPF

DESCR.

SPF

SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT

TYPE

PLATES

W

LEN

Y

X

2

TMV+p

MT20

2.0

4.0

5

BMV1+p

MT20

2.0

4.0

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED

MAXIMUM FACTORED

INPUT

REQRD

GROSS REACTION

GROSS REACTION

BRG

BRG

JT

VERT

HORZ

DOWN

HORZ

UPLIFT

IN-SX

IN-SX

5

457

0

457

0

0

5-8

5-8

3

174

0

174

0

0

1-8

1-8

4

43

0

49

0

0

1-8

1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 3 , 4

UNFACTORED REACTIONS

1ST LCASE

MAX./MIN. COMPONENT REACTIONS

JT

COMBINED

SNOW

LIVE

PERM.LIVE

WIND

DEAD

SOIL

5

318

238 / 0

0 / 0

0 / 0

0 / 0

80 / 0

0 / 0

3

118

105 / 0

0 / 0

0 / 0

0 / 0

14 / 0

0 / 0

4

35

0 / 0

0 / 0

0 / 0

0 / 0

35 / 0

0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS

WEBS

MAX. FACTORED

FACTORED

MAX. FACTORED

MEMB.

FORCE

VERT. LOAD

LC1

MAX

MAX.

MEMB.

FORCE

MAX

FR-TO

FROM

TO

LENGTH

FR-TO

5-2

-395 / 0

0.0

0.0

0.13 (4)

7.81

1-2

0 / 23

-77.3

-77.3

0.10 (1)

10.00

2-3

-26 / 0

-77.3

-77.3

0.47 (1)

6.25

5-4

0 / 0

-17.5

-17.5

0.13 (4)

10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.

LL = 23.3 PSF

DL = 3.0 PSF

BOT CH.

LL = 0.0 PSF

DL = 7.0 PSF

TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014

- CSA 086-09

- TPIC 2011

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")

CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")

ALLOWABLE DEFL.(TL)= L/360 (0.20")

CALCULATED VERT. DEFL.(TL) = L/ 999 (0.03")

CSI: TC=0.47 (2-3:1) , BC=0.13 (4-5:4) , WB=0.00 (n/a:0) , SSI=0.20 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10

COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION

(PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN


MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.23 (2) (INPUT = 0.90)

JSI METAL= 0.09 (2) (INPUT = 1.00)



LUMBER

N. L. G. A. RULES

CHORDS

SIZE

DRY

No.2

DESCR.

SPF

SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT

TYPE

PLATES

W

LEN

Y

X

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED

GROSS REACTION

MAXIMUM FACTORED

INPUT

REQRD

JT

VERT

HORZ

DOWN

HORZ

UPLIFT

IN-SX

BRG

BRG

IN-SX

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 3, 4

UNFACTORED REACTIONS

1ST LCASE

MAX./MIN. COMPONENT REACTIONS

JT

COMBINED

SNOW

LIVE

PERM.LIVE

WIND

DEAD

SOIL

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5, 3

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS

MAX. FACTORED

FACTORED

WEBS

MAX. FACTORED

MEMB.

FORCE

VERT. LOAD

LC1

MAX

MAX.

MEMB.

FORCE

MAX

CSI (LC)

UNBRAC

LENGTH

FR-TO

FROM

TO

FR-TO

5-2

-204 / 0

0.0

0.0

0.05 (4)

7.81

1-2

0 / 29

-77.3

-77.3

0.10 (1)

10.00

2-3

-11 / 0

-77.3

-77.3

0.05 (1)

6.25

5-4

0 / 0

-17.5

-17.5

0.06 (4)

10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP

CH.

LL

=

23.3

PSF

DL

=

3.0

PSF

BOT

CH.

LL

=

0.0

PSF

DL

=

7.0

PSF

TOTAL LOAD

=

33.3

PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014

- CSA 086-09

- TPIC 2011

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")

CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")

ALLOWABLE DEFL.(TL)= L/360 (0.19")

CALCULATED VERT. DEFL.(TL) = L/ 999 (0.01")

CSI: TC=0.10 (1-2:1), BC=0.06 (4-5:4), WB=0.00 (n/a:0), SSI=0.07 (1-2:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10

COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION

(PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN

MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.13 (2) (INPUT = 0.90)


JSI METAL= 0.05 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION





TOTAL WEIGHT = 2 X 8 = 16 lb [M]

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
5 - 2	2x4	DRY	No.2	SPF
1 - 3	2x4	DRY	No.2	SPF
5 - 4	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0		
5	BMV1+p	MT20	2.0	4.0		

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION			MAXIMUM FACTORED GROSS REACTION			INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX		IN-SX	
5	223	0	223	0	0	5-8		5-8	
3	60	0	60	0	0	1-8		1-8	
4	16	0	18	0	0	1-8		1-8	

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 3 , 4

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
5	154	123 / 0	0 / 0	0 / 0	0 / 0	31 / 0	0 / 0	
3	40	36 / 0	0 / 0	0 / 0	0 / 0	5 / 0	0 / 0	
4	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MEMB.	FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
5-2	-204 / 0	0.0	0.0 0.01 (4)	7.81			
1-2	0 / 29	-77.3	-77.3 0.10 (1)	10.00			
2-3	-11 / 0	-77.3	-77.3 0.05 (1)	6.25			
5-4	0 / 0	-17.5	-17.5 0.02 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.10 (1-2:1) , BC=0.02 (4-5:4) , WB=0.00 (n/a:0) , SSI=0.07 (1-2:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES		PLATE GRIP(DRY)		SHEAR (PSI)		SECTION (PLI)	
MAX	MIN	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1667	822	2284	1656	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.13 (2) (INPUT = 0.90)
JSI METAL= 0.05 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION





SCALE = 1:26.9

TOTAL WEIGHT = 4 X 13 = 52 lb [M]

LUMBER					DESCR.
N. L. G. A. RULES	SIZE	LUMBER	No.2	SPF	
CHORDS	2x4	DRY	No.2	SPF	
1 - 3	2x4	DRY	No.2	SPF	
5 - 4	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0		
5	BMV1+p	MT20	2.0	4.0		

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
5	339	0	339	0	0
3	116	0	116	0	0
4	30	0	34	0	0

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 3 , 4

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. SNOW	MAX./MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
5	235	180 / 0	0 / 0	0 / 0	0 / 0	55 / 0	0 / 0
3	79	70 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
4	24	0 / 0	0 / 0	0 / 0	0 / 0	24 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX. (LC)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM	TO	FR-TO	
5-2	-299 / 0	0.0	0.0 0.05 (4)	7.81	
1-2	0 / 29	-77.3	-77.3 0.10 (1)	10.00	
2-3	-21 / 0	-77.3	-77.3 0.21 (1)	6.25	
5-4	0 / 0	-17.5	-17.5 0.06 (4)	10.00	

DESIGN CRITERIA

SPECIFIED LOADS:		
TOP CH.	LL =	23.3 PSF
	DL =	3.0 PSF
BOT CH.	LL =	0.0 PSF
	DL =	7.0 PSF
TOTAL LOAD	=	33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.01")

CSI: TC=0.21 (2-3:1) , BC=0.06 (4-5:4) , WB=0.00 (n/a:0) , SSI=0.13 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES		PLATE GRIP(DRY)		SHEAR		SECTION	
(PSI)	(PLI)	(PSI)	(PLI)	(PSI)	(PLI)	(PSI)	(PLI)
MAX	MIN	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1667	822	2284	1656	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.19 (2) (INPUT = 0.90)
JSI METAL= 0.07 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION





<u>LUMBER</u>				
N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
5 - 2	2x4	DRY	No.2	SPF
1 - 3	2x4	DRY	No.2	SPF
5 - 4	2x4	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
5	322	0	322	0	0	5-8	5-8
3	108	0	108	0	0	1-8	1-8
4	28	0	31	0	0	1-8	1-8

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
5	223	172 / 0	0 / 0	0 / 0	0 / 0	52 / 0	0 / 0
3	73	65 / 0	0 / 0	0 / 0	0 / 0	8 / 0	0 / 0
4	22	0 / 0	0 / 0	0 / 0	0 / 0	22 / 0	0 / 0

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM TO			FR-TO		
5-2	-285 / 0	0.0	0.0	0.04 (4)	7.81		
1-2	0 / 29	-77.3	-77.3	0.10 (1)	10.00		
2-3	-20 / 0	-77.3	-77.3	0.18 (1)	6.25		
5-4	0 / 0	-17.5	-17.5	0.05 (4)	10.00		

						NAIL VALUES				
						PLATE	GRIP(DRY)		SHEAR	SECTION
							(PSI)		(PLI)	(PLI)
							MAX	MIN	MAX	MIN
						MT20	618	354	1667	822
										2284 1656

SPECIFIED LOADS:				
TOP	CH.	LL =	23.3	PSF
		DL =	3.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.0	PSF
TOTAL LOAD		=	33.3	PSF


NAIL VALUES						
PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1667	822	2284	1656

JSI GRIP= 0.18 (2) (INPUT = 0.90)
JSI METAL= 0.07 (2) (INPUT = 1.00)



RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION






LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. SPF 1 - 3 2x4 No.2 SPF 3 - 5 2x4 No.2 SPF 5 - 7 2x4 No.2 SPF 2 - 6 2x4 No.2 SPF ALL WEBS 2x3 DRY No.2 SPF ALL GABLE WEBS 2x3 DRY No.2 SPF DRY: SEASONED LUMBER. GABLE STUDS SPACED AT 3-0-0 OC.					DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS. BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): 8 , 9 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (4)					DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 3.0 PSF BOT CH. LL = 0.0 PSF DL = 7.0 PSF TOTAL LOAD = 33.3 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010 THIS DESIGN COMPLIES WITH: - PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014 - CSA 086-09 - TPIC 2011 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD CSI: TC=0.09 (4-5:1) , BC=0.03 (9-10:4) , WB=0.03 (4-9:1) , SSI=0.11 (4-5:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10 COMPANION LIVE LOAD FACTOR = 0.50 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 618 354 1667 822 2284 1656 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.30 (8) (INPUT = 0.90) JSI METAL= 0.02 (2) (INPUT = 1.00)																																																																																																																															
PLATES (table is in inches) JT TYPE PLATES W LEN Y X 2 TMB1-I MT20 3.0 4.0 3 TT-m MT20 3.0 4.0 Edge 4, 5, 8, 9 4 6 TMB1-I MT20 3.0 4.0 8 TTBW1*+h MT20 3.0 10.0 3.50 3.75 9 TMBMW1-I MT20 8.0 8.0 Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD. A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.					<table><tr><th colspan="4">CHORDS</th><th colspan="4">WEBS</th></tr><tr><th>MEMB.</th><th>MAX. FACTORED FORCE (LBS)</th><th>FACTORED VERT. LOAD (PLF)</th><th>MAX. UNBRACED LENGTH</th><th>MEMB.</th><th>MAX. FACTORED FORCE (LBS)</th><th>MAX. UNBRACED LENGTH</th><th></th></tr><tr><td>FR-TO</td><td></td><td>FROM TO</td><td></td><td>FR-TO</td><td></td><td></td><td></td></tr><tr><td>1- 2</td><td>0 / 10</td><td>-94.8 -94.8 0.02 (1)</td><td>10.00</td><td>8- 5</td><td>-80 / 0</td><td>0.01 (1)</td><td></td></tr><tr><td>2-11</td><td>-62 / 0</td><td>-77.3 -77.3 0.02 (1)</td><td>6.25</td><td>9- 4</td><td>-240 / 0</td><td>0.03 (1)</td><td></td></tr><tr><td>11- 3</td><td>-46 / 0</td><td>-77.3 -77.3 0.01 (1)</td><td>6.25</td><td>10-11</td><td>-6 / 17</td><td>0.00 (1)</td><td></td></tr><tr><td>3- 4</td><td>-33 / 0</td><td>-77.3 -77.3 0.09 (1)</td><td>6.25</td><td>12-13</td><td>-35 / 0</td><td>0.00 (1)</td><td></td></tr><tr><td>4- 5</td><td>-33 / 0</td><td>-77.3 -77.3 0.09 (1)</td><td>6.25</td><td></td><td></td><td></td><td></td></tr><tr><td>5-13</td><td>-45 / 0</td><td>-77.3 -77.3 0.01 (4)</td><td>6.25</td><td></td><td></td><td></td><td></td></tr><tr><td>13- 6</td><td>-42 / 0</td><td>-77.3 -77.3 0.01 (4)</td><td>6.25</td><td></td><td></td><td></td><td></td></tr><tr><td>6- 7</td><td>0 / 2</td><td>-94.8 -94.8 0.01 (1)</td><td>10.00</td><td></td><td></td><td></td><td></td></tr><tr><td>2-10</td><td>0 / 33</td><td>-17.5 -17.5 0.01 (1)</td><td>10.00</td><td></td><td></td><td></td><td></td></tr><tr><td>10- 9</td><td>0 / 33</td><td>-17.5 -17.5 0.03 (4)</td><td>10.00</td><td></td><td></td><td></td><td></td></tr><tr><td>9- 8</td><td>0 / 33</td><td>-17.5 -17.5 0.03 (4)</td><td>10.00</td><td></td><td></td><td></td><td></td></tr><tr><td>8-12</td><td>0 / 33</td><td>-17.5 -17.5 0.03 (4)</td><td>10.00</td><td></td><td></td><td></td><td></td></tr><tr><td>12- 6</td><td>0 / 33</td><td>-17.5 -17.5 0.01 (1)</td><td>10.00</td><td></td><td></td><td></td><td></td></tr></table>					CHORDS				WEBS				MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH		FR-TO		FROM TO		FR-TO				1- 2	0 / 10	-94.8 -94.8 0.02 (1)	10.00	8- 5	-80 / 0	0.01 (1)		2-11	-62 / 0	-77.3 -77.3 0.02 (1)	6.25	9- 4	-240 / 0	0.03 (1)		11- 3	-46 / 0	-77.3 -77.3 0.01 (1)	6.25	10-11	-6 / 17	0.00 (1)		3- 4	-33 / 0	-77.3 -77.3 0.09 (1)	6.25	12-13	-35 / 0	0.00 (1)		4- 5	-33 / 0	-77.3 -77.3 0.09 (1)	6.25					5-13	-45 / 0	-77.3 -77.3 0.01 (4)	6.25					13- 6	-42 / 0	-77.3 -77.3 0.01 (4)	6.25					6- 7	0 / 2	-94.8 -94.8 0.01 (1)	10.00					2-10	0 / 33	-17.5 -17.5 0.01 (1)	10.00					10- 9	0 / 33	-17.5 -17.5 0.03 (4)	10.00					9- 8	0 / 33	-17.5 -17.5 0.03 (4)	10.00					8-12	0 / 33	-17.5 -17.5 0.03 (4)	10.00					12- 6	0 / 33	-17.5 -17.5 0.01 (1)	10.00				
CHORDS				WEBS																																																																																																																																					
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH																																																																																																																																			
FR-TO		FROM TO		FR-TO																																																																																																																																					
1- 2	0 / 10	-94.8 -94.8 0.02 (1)	10.00	8- 5	-80 / 0	0.01 (1)																																																																																																																																			
2-11	-62 / 0	-77.3 -77.3 0.02 (1)	6.25	9- 4	-240 / 0	0.03 (1)																																																																																																																																			
11- 3	-46 / 0	-77.3 -77.3 0.01 (1)	6.25	10-11	-6 / 17	0.00 (1)																																																																																																																																			
3- 4	-33 / 0	-77.3 -77.3 0.09 (1)	6.25	12-13	-35 / 0	0.00 (1)																																																																																																																																			
4- 5	-33 / 0	-77.3 -77.3 0.09 (1)	6.25																																																																																																																																						
5-13	-45 / 0	-77.3 -77.3 0.01 (4)	6.25																																																																																																																																						
13- 6	-42 / 0	-77.3 -77.3 0.01 (4)	6.25																																																																																																																																						
6- 7	0 / 2	-94.8 -94.8 0.01 (1)	10.00																																																																																																																																						
2-10	0 / 33	-17.5 -17.5 0.01 (1)	10.00																																																																																																																																						
10- 9	0 / 33	-17.5 -17.5 0.03 (4)	10.00																																																																																																																																						
9- 8	0 / 33	-17.5 -17.5 0.03 (4)	10.00																																																																																																																																						
8-12	0 / 33	-17.5 -17.5 0.03 (4)	10.00																																																																																																																																						
12- 6	0 / 33	-17.5 -17.5 0.01 (1)	10.00																																																																																																																																						




READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION






LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. 1 - 3 2x4 DRY No.2 SPF 3 - 6 2x4 DRY No.2 SPF 6 - 9 2x4 DRY No.2 SPF 9 - 11 2x4 DRY No.2 SPF 21 - 2 2x4 DRY No.2 SPF 12 - 10 2x4 DRY No.2 SPF 21 - 18 2x4 DRY No.2 SPF 18 - 15 2x4 DRY No.2 SPF 15 - 12 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF EXCEPT DRY: SEASONED LUMBER.				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS FACTORED MAXIMUM FACTORED INPUT REQ'D GROSS REACTION GROSS REACTION BRG BRG JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX 21 1853 0 1853 0 0 5-8 5-8 12 1853 0 1853 0 0 5-8 5-8 UNFACTORED REACTIONS 1ST LCASE MAX/MIN. COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL 21 1298 921 / 0 0 / 0 0 / 0 377 / 0 0 / 0 12 1298 921 / 0 0 / 0 0 / 0 377 / 0 0 / 0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 21, 12 BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.48 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (4) CHORDS WEBS MAX. FACTORED MAX. FACTORED MAX. FACTORED MEMB. FORCE VERT. LOAD LC1 MAX. MAX. MEMB. FORCE MAX. (LBS) (PLF) CSI (LC) UNBRAC (LBS) CSI (LC) FR-TO FROM TO LENGTH FR-TO 1-2 0 / 29 -77.3 -77.3 0.10 (1) 10.00 20-3 -216 / 25 0.09 (1) 2-3 -2088 / 0 -77.3 -77.3 0.60 (1) 4.09 3-19 0 / 1445 0.33 (1) 3-4 -2783 / 0 -77.3 -77.3 0.44 (1) 3.79 19-4 -908 / 0 0.36 (1) 4-5 -3272 / 0 -77.3 -77.3 0.50 (1) 3.48 4-17 0 / 678 0.15 (1) 5-6 -3271 / 0 -77.3 -77.3 0.41 (1) 3.59 17-5 -380 / 0 0.15 (1) 6-7 -3271 / 0 -77.3 -77.3 0.41 (1) 3.59 5-16 -2 / 0 0.00 (1) 7-8 -3271 / 0 -77.3 -77.3 0.50 (1) 3.48 16-7 -380 / 0 0.15 (1) 8-9 -2783 / 0 -77.3 -77.3 0.44 (1) 3.78 16-8 0 / 676 0.15 (1) 9-10 -2088 / 0 -77.3 -77.3 0.60 (1) 4.09 14-8 -907 / 0 0.36 (1) 10-11 0 / 29 -77.3 -77.3 0.10 (1) 10.00 14-9 0 / 1445 0.33 (1) 21-2 -1812 / 0 0.0 0.0 0.19 (1) 6.21 13-9 -216 / 25 0.09 (1) 12-10 -1812 / 0 0.0 0.0 0.19 (1) 6.21 2-20 0 / 1765 0.40 (1) 21-20 0 / 0 -17.5 -17.5 0.13 (4) 10.00 20-19 0 / 1730 -17.5 -17.5 0.35 (1) 10.00 19-18 0 / 2783 -17.5 -17.5 0.49 (1) 10.00 18-17 0 / 2783 -17.5 -17.5 0.49 (1) 10.00 17-16 0 / 3272 -17.5 -17.5 0.57 (1) 10.00 16-15 0 / 2784 -17.5 -17.5 0.49 (1) 10.00 15-14 0 / 2784 -17.5 -17.5 0.49 (1) 10.00 14-13 0 / 1730 -17.5 -17.5 0.35 (1) 10.00 13-12 0 / 0 -17.5 -17.5 0.13 (4) 10.00				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 3.0 PSF BOT CH. LL = 0.0 PSF DL = 7.0 PSF TOTAL LOAD = 33.3 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010 THIS DESIGN COMPLIES WITH: - PART 9 OF OBC 2012, BCBC 2012, ABC 2014 - CSA 086-09 - TPIC 2011 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (1.23") CALCULATED VERT. DEFL.(LL) = L/ 999 (0.22") ALLOWABLE DEFL.(TL)= L/360 (1.23") CALCULATED VERT. DEFL.(TL) = L/ 999 (0.38") CSI: TC=0.60 (2-3:1), BC=0.57 (16-17:1), WB=0.40 (2-20:1), SSI=0.19 (8-9:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10 COMPANION LIVE LOAD FACTOR = 0.50 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 618 354 1667 822 2284 1656 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.88 (4) (INPUT = 0.90) JSI METAL= 0.71 (15) (INPUT = 1.00)			
---	--	--	--	--	--	--	--	---	--	--	--



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. </									
---	--	--	--	--	--	--	--	--	--




LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. 1 - 4 2x4 DRY No.2 SPF 4 - 6 2x4 DRY No.2 SPF 6 - 8 2x4 DRY No.2 SPF 8 - 11 2x4 DRY No.2 SPF 19 - 2 2x4 DRY No.2 SPF 12 - 10 2x4 DRY No.2 SPF 19 - 16 2x4 DRY No.2 SPF 16 - 15 2x4 DRY No.2 SPF 15 - 12 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF EXCEPT DRY: SEASONED LUMBER.				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS FACTORED MAXIMUM FACTORED INPUT REQRD GROSS REACTION GROSS REACTION BRG BRG JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX 19 1853 0 1853 0 0 5-8 5-8 12 1853 0 1853 0 0 5-8 5-8 UNFACTORED REACTIONS 1ST LCASE MAX/MIN. COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL 19 1298 921 / 0 0 / 0 0 / 0 377 / 0 0 / 0 12 1298 921 / 0 0 / 0 0 / 0 377 / 0 0 / 0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 19, 12 BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.86 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. 1 - 2x3 SPF No.2 LATERAL BRACE(S) AT 1/2 LENGTH OF 7-16. DBS = 20-0-0 . CBF = 0 LBS. DBS = DIAGONAL BRACE SPACING (MAX). CBF = CUMULATIVE BRACING FORCE. FASTEN LATERAL BRACE(S) USING (0.122"x3") SPIRAL NAILS : 1 NAIL FOR 2x3 BRACE(S), 2 FOR 1x4, 2x4, 2x5, 3 FOR 2x6, 4 FOR 2x8, 5 FOR 2x10, AND 6 FOR 2x12. END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW LOADING TOTAL LOAD CASES: (4) C H O R D S MEMB. MAX. FACTORED FORCE (LBS) FACTORED VERT. LOAD (PLF) MAX. LC1 MAX. UNBRAC LENGTH FR-TO FR-TO 0 / 29 -77.3 -77.3 0.10 (1) 10.00 18-3 -352 / 0 0.10 (1) 2-3 -2060 / 0 -77.3 -77.3 0.31 (1) 4.43 3-17 -55 / 0 0.03 (1) 3-4 -2057 / 0 -77.3 -77.3 0.31 (1) 4.44 17-4 0 / 140 0.04 (4) 4-5 -2321 / 0 -77.3 -77.3 0.64 (1) 3.87 4-16 0 / 910 0.20 (1) 5-6 -2321 / 0 -77.3 -77.3 0.64 (1) 3.86 16-5 -545 / 0 0.49 (1) 6-7 -2321 / 0 -77.3 -77.3 0.64 (1) 3.86 16-7 -2 / 0 0.00 (1) 7-8 -2322 / 0 -77.3 -77.3 0.65 (1) 3.86 15-7 -545 / 0 0.49 (1) 8-9 -2057 / 0 -77.3 -77.3 0.31 (1) 4.44 15-8 0 / 912 0.21 (1) 9-10 -2060 / 0 -77.3 -77.3 0.31 (1) 4.43 14-8 0 / 139 0.04 (4) 10-11 0 / 29 -77.3 -77.3 0.10 (1) 10.00 14-9 -55 / 0 0.03 (1) 19-2 -1817 / 0 0.0 0.0 0.19 (1) 6.21 13-9 -352 / 0 0.10 (1) 12-10 -1817 / 0 0.0 0.0 0.19 (1) 6.21 2-18 0 / 1782 0.40 (1) 13-10 0 / 1782 0.40 (1) 19-18 0 / 0 -17.5 -17.5 0.07 (4) 10.00 18-17 0 / 1731 -17.5 -17.5 0.35 (1) 10.00 17-16 0 / 1693 -17.5 -17.5 0.34 (1) 10.00 16-15 0 / 2322 -17.5 -17.5 0.45 (1) 10.00 15-14 0 / 1693 -17.5 -17.5 0.35 (1) 10.00 14-13 0 / 1731 -17.5 -17.5 0.34 (1) 10.00 13-12 0 / 0 -17.5 -17.5 0.07 (4) 10.00 W E B S MEMB. MAX. FACTORED FORCE (LBS) MAX. FACTORED CSI (LC) FR-TO 0 / 29 -77.3 -77.3 0.10 (1) 10.00 18-3 -352 / 0 0.10 (1) 2-3 -2060 / 0 -77.3 -77.3 0.31 (1) 4.43 3-17 -55 / 0 0.03 (1) 3-4 -2057 / 0 -77.3 -77.3 0.31 (1) 4.44 17-4 0 / 140 0.04 (4) 4-5 -2321 / 0 -77.3 -77.3 0.64 (1) 3.87 4-16 0 / 910 0.20 (1) 5-6 -2321 / 0 -77.3 -77.3 0.64 (1) 3.86 16-5 -545 / 0 0.49 (1) 6-7 -2321 / 0 -77.3 -77.3 0.64 (1) 3.86 16-7 -2 / 0 0.00 (1) 7-8 -2322 / 0 -77.3 -77.3 0.65 (1) 3.86 15-7 -545 / 0 0.49 (1) 8-9 -2057 / 0 -77.3 -77.3 0.31 (1) 4.44 15-8 0 / 912 0.21 (1) 9-10 -2060 / 0 -77.3 -77.3 0.31 (1) 4.43 14-8 0 / 139 0.04 (4) 10-11 0 / 29 -77.3 -77.3 0.10 (1) 10.00 14-9 -55 / 0 0.03 (1) 19-2 -1817 / 0 0.0 0.0 0.19 (1) 6.21 13-9 -352 / 0 0.10 (1) 12-10 -1817 / 0 0.0 0.0 0.19 (1) 6.21 2-18 0 / 1782 0.40 (1) 13-10 0 / 1782 0.40 (1) 19-18 0 / 0 -17.5 -17.5 0.07 (4) 10.00 18-17 0 / 1731 -17.5 -17.5 0.35 (1) 10.00 17-16 0 / 1693 -17.5 -17.5 0.34 (1) 10.00 16-15 0 / 2322 -17.5 -17.5 0.45 (1) 10.00 15-14 0 / 1693 -17.5 -17.5 0.35 (1) 10.00 14-13 0 / 1731 -17.5 -17.5 0.34 (1) 10.00 13-12 0 / 0 -17.5 -17.5 0.07 (4) 10.00				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 3.0 PSF BOT CH. LL = 0.0 PSF DL = 7.0 PSF TOTAL LOAD = 33.3 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010 THIS DESIGN COMPLIES WITH: - PART 9 OF OBC 2012, BCBC 2012, ABC 2014 - CSA 086-09 - TPIC 2011 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (1.23") CALCULATED VERT. DEFL.(LL) = L/999 (0.13") ALLOWABLE DEFL.(TL)= L/360 (1.23") CALCULATED VERT. DEFL.(TL) = L/999 (0.24") CSI: TC=0.65 (7-8:1) , BC=0.45 (15-16:1) , WB=0.49 (7-15:1) , SSI=0.24 (7-8:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10 COMPANION LIVE LOAD FACTOR = 0.50 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 618 354 1667 822 2284 1656 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.89 (4) (INPUT = 0.90) JSI METAL= 0.50 (15) (INPUT = 1.00)			
---	--	--	--	---	--	--	--	---	--	--	--




READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION







LUMBER				N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.	CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2	1 - 4	2x4	DRY	No.2
4 - 6	2x4	DRY	No.2	4 - 6	2x4	DRY	No.2
6 - 9	2x4	DRY	No.2	6 - 9	2x4	DRY	No.2
18 - 2	2x4	DRY	No.2	18 - 2	2x4	DRY	No.2
10 - 8	2x4	DRY	No.2	10 - 8	2x4	DRY	No.2
18 - 15	2x4	DRY	No.2	18 - 15	2x4	DRY	No.2
15 - 13	2x4	DRY	No.2	15 - 13	2x4	DRY	No.2
13 - 10	2x4	DRY	No.2	13 - 10	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2	ALL WEBS	2x3	DRY	No.2
EXCEPT				EXCEPT			
4 - 14	2x4	DRY	No.2	4 - 14	2x4	DRY	No.2
14 - 6	2x4	DRY	No.2	14 - 6	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-p	MT20	4.0	8.0	1.00	3.50
3	TMVW-t	MT20	3.0	4.0	1.50	1.50
4	TTWW+m	MT20	5.0	6.0	Edge	1.75
5	TMVW+w	MT20	2.0	4.0		
6	TTWW+m	MT20	5.0	6.0	Edge	1.75
7	TMVW-t	MT20	3.0	4.0	1.50	1.50
8	TMVW-p	MT20	4.0	8.0	1.00	3.50
10	BMV1+p	MT20	2.0	4.0	2.25	1.00
11	BMVW-t	MT20	4.0	5.0	1.75	1.50
12	BMVW-t	MT20	3.0	4.0		
13	BS-t	MT20	3.0	6.0		
14	BMVW-t	MT20	3.0	8.0		
15	BS-t	MT20	3.0	6.0		
16	BMVW-t	MT20	3.0	4.0		
17	BMVW-t	MT20	4.0	5.0	1.75	1.50
18	BMV1+p	MT20	2.0	4.0	2.25	1.00

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQRD
GROSS REACTION		DOWN	HORZ	BRG	BRG
JT	VERT	DOWN	HORZ	UPLIFT	IN-SX
18	1853	0	1853	0	5-8
10	1853	0	1853	0	5-8

UNFACTORED REACTIONS		1ST LCASE	MAX/MIN.	COMPONENT REACTIONS
COMBINED		SNOW	LIVE	PERM.LIVE
JT	DOWN	SNOW	LIVE	PERM.LIVE
18	1298	921 / 0	0 / 0	0 / 0
10	1298	921 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 18, 10

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 - 2x3 SPF No.2 LATERAL BRACE(S) AT 1/2 LENGTH OF 5-14. DBS = 20-0-0 . CBF = 80 LBS.

DBS = DIAGONAL BRACE SPACING (MAX). CBF = CUMULATIVE BRACING FORCE. FASTEN LATERAL BRACE(S) USING (0.122"x3") SPIRAL NAILS : 1 NAIL FOR 2x3 BRACE(S), 2 FOR 1x4, 2x4, 2x5, 3 FOR 2x6, 4 FOR 2x8, 5 FOR 2x10, AND 6 FOR 2x12.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING		TOTAL LOAD CASES: (4)	
CHORDS		WEBS	
MEMB.	MAX. FACTORED	MEMB.	MAX. FACTORED
FORCE (LBS)	VERT. LOAD (PLF)	FORCE (LBS)	MAX. FACTORED
FR-TO	FROM TO	FR-TO	FROM TO
1-2	0 / 29	17-3	-219 / 31
2-3	-2131 / 0	3-16	-296 / 0
3-4	-1924 / 0	4-14	0 / 303
4-5	-1868 / 0	14-5	0 / 480
5-6	-1868 / 0	14-5	-643 / 0
6-7	-1924 / 0	14-6	0 / 480
7-8	-2131 / 0	12-6	0 / 303
8-9	0 / 29	12-7	-296 / 0
18-2	-1809 / 0	11-7	-219 / 31
10-8	-1809 / 0	2-17	0 / 1827
		11-8	0 / 1827
18-17	0 / 0		
17-16	0 / 1798		
16-15	0 / 1577		
15-14	0 / 1577		
14-13	0 / 1577		
13-12	0 / 1577		
12-11	0 / 1798		
11-10	0 / 0		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.23")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.10")
ALLOWABLE DEFL.(TL)= L/360 (1.23")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.19")

CSI: TC=0.53 (4-5:1) , BC=0.36 (16-17:1) , WB=0.41 (2-17:1) , SSI=0.25 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.88 (2) (INPUT = 0.90)
JSI METAL= 0.54 (11) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION







DRY: SEASONED LUMBER.

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

20-19	0 / 0	-17.5	-17.5	0.19 (4)	10.00
19-18	0 / 1812	-17.5	-17.5	0.38 (1)	10.00
18-17	0 / 1503	-17.5	-17.5	0.31 (1)	10.00
17-16	0 / 1503	-17.5	-17.5	0.31 (1)	10.00
16-15	0 / 1503	-17.5	-17.5	0.31 (1)	10.00
15-14	0 / 1503	-17.5	-17.5	0.31 (1)	10.00
14-13	0 / 1812	-17.5	-17.5	0.38 (1)	10.00
13-12	0 / 0	-17.5	-17.5	0.19 (4)	10.00

JSI GRIP= 0.90 (10) (INPUT = 0.90)
JSI METAL= 0.54 (19) (INPUT = 1.00)





TOTAL WEIGHT = 78 lb
[M][F]

LUMBER				DESCR.	
N. L. G. A. RULES		LUMBER	SIZE	DRY	SPF
CHORDS	SIZE				
1 - 3	2x4	DRY	No.2		SPF
3 - 4	2x4	DRY	No.2		SPF
4 - 5	2x4	DRY	No.2		SPF
10 - 2	2x4	DRY	No.2		SPF
6 - 5	2x4	DRY	No.2		SPF
10 - 8	2x4	DRY	No.2		SPF
8 - 6	2x4	DRY	No.2		SPF
ALL WEBS EXCEPT	2x3	DRY	No.2		SPF
DRY: SEASONED LUMBER.					

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	3.0	5.0	1.50	2.00
3	TTWW-m	MT20	4.0	5.0	1.75	1.25
4	TTWW-m	MT20	3.0	4.0	2.00	1.25
5	TMVW-t	MT20	3.0	5.0	1.50	2.00
6	BMV1+p	MT20	2.0	4.0		
7	BMVWW-t	MT20	3.0	8.0		
8	BS-t	MT20	3.0	4.0		
9	BMVWW-t	MT20	3.0	4.0		
10	BMV1+p	MT20	2.0	4.0		

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS				FACTORED				MAXIMUM FACTORED				INPUT		REQRD	
JT		GROSS REACTION		GROSS REACTION		GROSS REACTION		DOWN		HORZ		UPLIFT		BRG	
		VERT		HORZ		DOWN		HORZ		UPLIFT		IN-SX		IN-SX	
10		934		0		934		0		0		5-8		5-8	
6		828		0		828		0		0		HANGER BY OTHERS		MIN. SEAT SIZE: 1-8	

UNFACTORED REACTIONS

JT		1ST LCASE		MAX./MIN. COMPONENT REACTIONS		PERM. LIVE		WIND		DEAD		SOIL	
		COMBINED		SNOW		LIVE		PERM. LIVE		WIND		DEAD	
10		653		470 / 0		0 / 0		0 / 0		0 / 0		183 / 0	
6		581		406 / 0		0 / 0		0 / 0		0 / 0		175 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 10

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 - 2x3 SPF No.2 LATERAL BRACE(S) AT 1/2 LENGTH OF 3-7. DBS = 20-0-0 . CBF = 4 LBS.

DBS = DIAGONAL BRACE SPACING (MAX). CBF = CUMULATIVE BRACING FORCE. FASTEN LATERAL BRACE(S) USING (0.122"x3") SPIRAL NAILS : 1 NAIL FOR 2x3 BRACE(S), 2 FOR 1x4, 2x4, 2x5, 3 FOR 2x6, 4 FOR 2x8, 5 FOR 2x10, AND 6 FOR 2x12.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

C H O R D S				W E B S			
MEMB.		MAX. FACTORED FORCE (LBS)		MAX. FACTORED VERT. LOAD (PLF)		MAX. FACTORED UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FROM TO		FR-TO	
1-2		0 / 29		-77.3 -77.3		10.00 9-3	
2-3		-609 / 0		-77.3 -77.3		6.25 3-7	
3-4		-484 / 0		-77.3 -77.3		6.25 7-4	
4-5		-584 / 0		-77.3 -77.3		6.25 2-9	
10-2		-891 / 0		0.0 0.0		7.81 7-5	
6-5		-788 / 0		0.0 0.0		7.81	
10-9		0 / 0		-17.5 -17.5		10.00	
9-8		0 / 504		-17.5 -17.5		10.00	
8-7		0 / 504		-17.5 -17.5		10.00	
7-6		0 / 0		-17.5 -17.5		10.00	

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL	=	23.3	PSF
		DL	=	3.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.0	PSF
TOTAL		LOAD	=	33.3	PSF

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.58")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.58")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.04")

CSI: TC=0.36 (2-3:1) , BC=0.18 (7-9:4) , WB=0.12 (2-9:1) , SSI=0.18 (3-4:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.87 (4) (INPUT = 0.90)
JSI METAL= 0.24 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION





LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2
4 - 5	2x4	DRY	No.2
5 - 7	2x4	DRY	No.2
12 - 2	2x4	DRY	No.2
8 - 7	2x4	DRY	No.2
12 - 9	2x4	DRY	No.2
9 - 8	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2
SPF			
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
2	TMV+p	MT20	2.0	4.0	
3	TMVW-t	MT20	3.0	5.0	
4	TTW+m	MT20	3.0	4.0	2.00 1.25
5	TTW+m	MT20	4.0	16.0	Edge 1.00
6	TMVW-t	MT20	3.0	5.0	
7	TMV+p	MT20	2.0	4.0	
8	BMVW1-t	MT20	4.0	4.0	
9	BS-t	MT20	3.0	4.0	
10	BMVW-t	MT20	3.0	4.0	
11	BMVW-t	MT20	3.0	8.0	
12	BMVW1-t	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS			
FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION	
JT	VERT	DOWN	HORZ
12	934	0	0
8	828	0	0

UNFACTORED REACTIONS							
JT	1ST LCASE	MAX./MIN.	SNOW	LIVE	PERM.LIVE	WIND	DEAD
12	653	470 / 0	0 / 0	0 / 0	0 / 0	0 / 0	183 / 0
8	581	406 / 0	0 / 0	0 / 0	0 / 0	0 / 0	175 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 12

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

CHORDS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)
1-2	0 / 29	-77.3	-77.3 0.10 (1)
2-3	0 / 20	-77.3	-77.3 0.20 (1)
3-4	-580 / 0	-77.3	-77.3 0.16 (1)
4-5	-466 / 0	-77.3	-77.3 0.04 (1)
5-6	-570 / 0	-77.3	-77.3 0.14 (1)
6-7	0 / 19	-77.3	-77.3 0.18 (1)
12-2	-225 / 0	0.0	0.0 0.03 (1)
8-7	-113 / 0	0.0	0.0 0.02 (1)
12-11	0 / 498	-17.5	-17.5 0.29 (4)
11-10	0 / 459	-17.5	-17.5 0.30 (4)
10-9	0 / 462	-17.5	-17.5 0.25 (4)
9-8	0 / 462	-17.5	-17.5 0.25 (4)

DESIGN CRITERIA

SPECIFIED LOADS:			
TOP CH.	LL	=	23.3 PSF
	DL	=	3.0 PSF
BOT CH.	LL	=	0.0 PSF
	DL	=	7.0 PSF
TOTAL LOAD = 33.3 PSF			

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.58")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.58")
CALCULATED VERT. DEFL.(TL) = L/999 (0.11")

CSI: TC=0.20 (2-3:1), BC=0.30 (10-11:4), WB=0.63 (3-12:1), SSI=0.12 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES					
PLATE	GRIP(DRY)	SHEAR	SECTION	(PSI)	(PLI)
				MAX	MIN
MT20	618	354	1667	822	2284

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.88 (5) (INPUT = 0.90)
JSI METAL= 0.23 (3) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION





TOTAL WEIGHT = 81 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
1 - 4	2x4	DRY	No.2		SPF
4 - 6	2x4	DRY	No.2		SPF
10 - 2	2x4	DRY	No.2		SPF
7 - 6	2x4	DRY	No.2		SPF
10 - 8	2x4	DRY	No.2		SPF
8 - 7	2x4	DRY	No.2		SPF
ALL WEBS	2x3	DRY	No.2		SPF
EXCEPT					
DRY: SEASONED LUMBER.					

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0		
3	TMVW-t	MT20	3.0	4.0	1.50	1.75
4	TTW+p	MT20	3.0	4.0	2.25	1.50
5	TMVW-t	MT20	3.0	5.0		
6	TMV+p	MT20	2.0	4.0		
7	BMVW1-t	MT20	4.0	4.0		
8	BS-t	MT20	3.0	4.0		
9	BMVW-t	MT20	3.0	6.0		
10	BMVW1-t	MT20	3.0	4.0	1.50	1.75

A SIZE FOR SIZE SUBSTITUTION OF MITEK MII20 WITH TEE-LOK TL20 PLATES IS ALLOWED.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	GROSS REACTION	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
10	934	0	934	0	0	5-8	5-8		
7	828	0	828	0	0				HANGER BY OTHERS
MIN. SEAT SIZE: 1-8									

UNFACTORED REACTIONS							
JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS				
10	653	470 / 0	0 / 0	0 / 0	0 / 0	183 / 0	0 / 0
7	581	406 / 0	0 / 0	0 / 0	0 / 0	175 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 10

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX (LC)	
FR-TO		FROM	TO	FR-TO			
1-2	0 / 29	-77.3	-77.3 0.10 (1)	10.00	3-9	-113 / 25	0.11 (1)
2-3	0 / 23	-77.3	-77.3 0.26 (1)	10.00	9-4	0 / 332	0.07 (1)
3-4	-553 / 0	-77.3	-77.3 0.20 (1)	6.25	9-5	-68 / 35	0.07 (1)
4-5	-552 / 0	-77.3	-77.3 0.18 (1)	6.25	10-3	-816 / 0	0.77 (1)
5-6	0 / 21	-77.3	-77.3 0.23 (1)	10.00	5-7	-806 / 0	0.76 (1)
10-2	-239 / 0	0.0	0.0 0.04 (1)	7.81			
7-6	-126 / 0	0.0	0.0 0.02 (1)	7.81			
10-9	0 / 512	-17.5	-17.5 0.42 (4)	10.00			
9-8	0 / 481	-17.5	-17.5 0.42 (4)	10.00			
8-7	0 / 481	-17.5	-17.5 0.42 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.58")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.58")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.14")

CSI: TC=0.26 (2-3:1), BC=0.42 (9-10:4), WB=0.77 (3-10:1), SSI=0.14 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES					
PLATE	GRIP(DRY)	SHEAR	SECTION		
(PSI)	(PLI)	(PLI)	MAX	MIN	MAX
MT20	618	354	1667	822	2284

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (3) (INPUT = 0.90)
JSI METAL= 0.29 (3) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B37579H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177
COMMON SPIRAL	3.00	0.122	97	108
	3.25	0.122	97	108
	3.50	0.152	145	162

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-09, section 10.9.4.1.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: G = 0.42 (SPF), G = 0.49 (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to **wind** the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-09, section 10.9.4
10. This design is not valid after April 30, 2017.



TOE-NAIL INSTALLATION

Nail type	Common wire	Common spiral	Common wire	Common spiral
Nail dia. (in)	0.160	0.152	0.144	0.122
	(3.5" nail)		(3" and 3.25" nail)	
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS			
2X4 SPF	2	2	3	3
2X4 D. Fir	2	2	2	2
2X6 SPF	4	4	4	5
2X6 D. Fir	3	3	3	4



MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION



April 24, 2015

BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING





B37579H2

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52
COMMON SPIRAL	3.00	0.122	26	36
	3.25	0.122	28	40
	3.50	0.152	36	50

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.

NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to **wind** or **earthquake** load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-09, section 10.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-09, section 10.9.5
9. This design is not valid after April 30, 2017

Toe-nailing on 2x6 Bearing Plate**Toe-nailing on 2x4 Bearing Plate**

MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION

PEO
Certificate No. 10889485



April 24, 2015

JOB NAME

JOB DESC.

LECCO RIDGE-JUNIPER 8 EL 3

DRWG NO.


ENC JOB: PT0317-175

DETAILS

PIGGYBACK TRUSS DETAIL

B375791


FOR SLOPES BETWEEN
4/12 AND 12/12



FOR SLOPES BETWEEN
4/12 AND 12/12

SPLICES (IF REQUIRED) MUST BE LOCATED AT
THE 1/4 POINT OF A PANEL. SPLICES MAY NOT
BE LOCATED NEAR A PITCH BREAK OR IN THE
FIRST PANEL ADJACENT TO THE HEEL.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION



THIS PIGGYBACK DETAIL IS VALID FOR THE
PROJECT DESIGN LOADS LISTED BELOW:

SPECIFIED LOADS:

TOP CHORD	LL =	60.0	PSF OR LESS
	DL =	6.0	PSF OR LESS
BOT CHORD	LL =	0	PSF
	DL =	7.0	PSF
TOTAL LOAD	=	73.0	PSF OR LESS

MAX. SPACING OF TRUSSES NOT TO EXCEED 24" C/C



MiTek Canada, Inc.
100 Industrial Rd.
Bradford, Ontario, L3Z 3G7

PEO
Certificate No. 10889485



Notes:



- Piggyback truss lumber : Top chord = 2x4, Webs = 2x3 or 2x4, Bottom chord = 2x3 or 2x4. All chord/web lumber to be SPF or D. Fir species and No. 2 DRY or better grade.
- Maximum web length is not to exceed 12 ft.
- One continuous lateral brace required at 1/2 length of any web that exceeds 6 ft in length. Minimum brace (or purlin) size shall be 1x4 as per NBCC 2010, section 9.23.14.11.4 For L-brace or Scab brace connection details see MiTek details B37337K, B37337P.
- Purlins supporting piggyback trusses, as well as overall roof bracing, are specified by building designer.
- Purlin spacing to be equal to main truss maximum unbraced top chord length (as shown on main truss MiTek engineering drawing), but not to exceed 24" c/c.
- This detail is not valid for projects that require a wind analysis to be incorporated into the truss design.
- Piggyback truss must be installed directly on top of each main truss.
- Maximum span of the piggyback is not to exceed 24'-0" (contact MiTek engineering dept. for spans > 24'-0").
- All plates specified are MiTek MT20, centered at each joint, and pressed into both faces of piggyback truss.
- This detail is not valid after April 30, 2017.

April 24, 2015


JOB NAME DETAILS

JOB DESC. 5000 RIDGE-JUNIPER 8 EL 3


DRAWING NO. B37579J



DETAIL "A"




DETAIL "C"



CANTILEVER DETAIL "C"

SLOPE	MAX CANTILEVER	PLATE "B"	WEDGE SIZE
3/12	17"	3 X 5	2 X 3
4/12	14"	3 X 5	2 X 3
5/12	12"	3 X 5	2 X 4
6/12	10"	3 X 5	2 X 4
7/12	9"	3 X 5	2 X 6
8/12	8.5"	3 X 5	2 X 6
9/12	8"	3 X 5	2 X 6
10/12	7.5"	3 X 5	2 X 6


DETAIL "B"



NOTES:

- ALL LUMBER SHALL BE 2x4 SPF OR D. Fir No. 2 DRY OR BETTER.
- THIS TRUSS IS DESIGNED FOR HOUSING AND SMALL BUILDING REQUIREMENTS OF PART 9 NBC 2010, WHERE GROUND SNOW LOAD IS 60.0 PSF OR LESS AND RAIN LOAD DOES NOT EXCEED 12.53 PSF; TOP CHORD DEAD LOAD IS 6 PSF OR LESS; BC LIVE LOAD IS 0 PSF AND BC DEAD LOAD IS 7 PSF.
- HIP RAFTER DESIGN SHALL CONFORM TO SECTION 9.23.14.6 OF NBC 2010.
- FASTEN HIGH END OF RAFTERS USING MITEK CANADA INC. "BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY" STANDARD DETAIL B37579H1.
- FASTEN RIGHT END OF CEILING USING MITEK CANADA INC. "BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY" STANDARD DETAIL B37579H1.
- OVERHANG LENGTH SHALL NOT EXCEED 2 FT.
- WHEN SETBACK IS 6 FT OR LESS, DIAGONAL WEB MAY BE OMITTED AND HIGH END OF TOP CHORD SHALL BE CONNECTED AS PER NOTE 4.
- ALL PLATES SPECIFIED ARE PRESSED INTO BOTH FACES OF THE TRUSS.
- MITEK REFERENCE PAGE MII-7473C FORMS AN INTEGRAL PART OF THIS DETAIL.
- THIS DETAIL IS NOT VALID AFTER APRIL 30, 2017

SEE DETAIL A, B or C



RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 8
BUILDING DIVISION

PEO
Certificate No. 10889485



MiTek Canada, Inc.
100 Industrial Rd.
Bradford, Ontario, L3Z 3G7

April 24, 2015