

Engineering Note Page (ENP-2)

REVISION 2009-10-09

Please read all notes prior to installation of the component**DESIGN INFORMATION**

This building component is certified as an individual component for the loads and conditions shown on the calculation and drawing page.

The responsibility of the undersigned engineer is only limited to the calculation of this building component for the loads and conditions shown on this drawing.

The responsibility of the undersigned is limited to the verification of the structural capacity of the NASCOR floor joists and LVL beams based on placement as shown on the layout. The loads applied are limited to the gravity effects of the specified loads. The structural integrity of the building and the effect of wind, uplift, seismic, lateral or other forces, calculation of adequate support and anchorage of components, as well as the dimensions and design loads used to calculate components are the responsibility of the overall building designer.

Floor joists and OSB rim board are designed to carry uniformly distributed loads only. Point loads should be transferred through the floor cavity with squash blocks. Structural elements such as walls, posts, connectors, and squash blocks are the responsibility of the overall building designer.

The undersigned engineer disclaims any responsibility for damages as a result of being furnished faulty or incorrect information, specifications and/or designs.

Installation of NASCOR joists is to be carried out in accordance with the current edition of the manufacturer's approved literature available at <http://www.nascor.ca>.

CODE

This building component is designed in accordance with the National Building Code of Canada, the Ontario Building Code, CCMC and Canadian Standards Association guidelines.

COMPONENT

1. The building component used in construction must be the same as indicated on the drawings.
2. The building component must be installed and assembled as per specification shown on the drawing and in accordance with the manufacturer's assembly and installation.
3. Members consisting of multiple plies must be connected as per the document "Multi-ply Connection Details".
4. Pass-thru squash block framing is required at all point loads over bearings.


HANDLING AND INSTALLATION

Do not drill any hole, cut or notch a certified building component without a written pre-authorization.



MULTIPLE MEMBER CONNECTIONS


Conventional Connections (for uniform distributed loads)



Conventional connection notes:

- Nails to be 3" 10d spiral wire nails.
- Nails to be located a minimum of 2" from the top and bottom of the member. Start all nails a minimum of 2 1/2" in from ends.
- Number of rows and spacing as per details shown, unless noted otherwise.
- "X" represents nail driven from the opposite side.

LVL Connections (for uniform distributed loads)




LVL connection notes:

- Nails to be 3 1/2" spiral wire nails.
- Nails to be located a minimum of 2 1/2" from the top and bottom of the member. Start all nails a minimum of 2 1/2" in from ends.
- Minimum 3 1/4" spacing between rows.
- Number of rows and spacing as per details shown, unless noted otherwise.
- "X" represents nail or screw driven from the opposite side.

For side-loaded 4-ply LVL Connections, please consult the engineering calculation page for the component and the Nascor layout

Vertical I-Joist Connections (for uniform distributed loads)



Vertical I-Joist connection notes:

- Nails to be 3" spiral wire nails.
- Nails to be located at centre of top and bottom flanges. Start all nails a minimum of 2 1/2" in from ends.
- Number of rows and spacing as per details shown, unless noted otherwise.
- "X" represents nail driven from the opposite side.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION



MULTI -PLY
CONNECTION
DETAILS

Date: November 30, 2016


Scale: NTS

KOTT
3228 Moodie Drive
Ottawa, ON
K2H 7V1
Ph: 613-838-2775
Fx: 613-838-4751



----- Floor Framing Material -----

Type	Qty.	Product	Length
J1	5	NJH12	18' 0"
J2	9	NJH12	16' 0"
J3	12	NJH12	14' 0"
J4	12	NJH12	12' 0"
J5	12	NJH12	10' 0"
J6	3	NJH12	6' 0"
J7	21	NJH12	2' 0"
J8	17	NJ60H12	18' 0"
G1	1	1 3/4x11 7/8 West Fraser 2.0E-	4' 0"
G2	1	NJH12	2' 0"
G3	1	NJH12	2' 0"
G4	1	NJH12	2' 0"
G5	1	NJH12	2' 0"
G6	1	1 3/4x11 7/8 West Fraser 2.0E-	6' 0"
G7	1	1 3/4x11 7/8 West Fraser 2.0E-	6' 0"
G8	1	NJH12	2' 0"
G9	1	NJH12	2' 0"
G12	2	NJ12	20' 0"
G13	2	NJ12	14' 0"
G14	1	NJ12	10' 0"
R1	14	11 7/8" RIMBOARD	12' 0"



HATCH AREA INDICATED REPRESENTS
CERAMIC TILED FLOOR WITH AN
ADDITIONAL DEAD LOAD OF 5.00 PSF

Refer to Multiple Member Connection
Detail to ply to ply nailing or bolting
requirements.

PASS-THRU FRAMING SQUASH BLOCK
IS REQUIRED AT ALL POINT LOADS
OVER BEARINGS.

All product names are trademarks of their respective owners

DESIGN ASSUMPTIONS
=====

Loads:(un-factored)
T/C Live: 40 psf B/C Live: 0 psf
T/C Dead: 15 psf B/C Dead: 0 psf
Load Case: Live
Deflection Criteria:
L/480 Live L/360 Total
Building Code: OBC-2012 (Limit States Design
Building Type: Residential
Importance Category: Normal (Part 9)
Design assumes top edge continuously braced,
and bottom edge unbraced.
Joist Design Includes CCMC Vibration Check
Subfloor: 3/4" OSB Glued and Nailed
Ceiling: (None)
Blocking: (None)

All Loads are UN-FACTORED Loads


----- Connector List -----

ID#	Qty	Model Number
H1	4	LT251188
H2	23	LT251188

NOTES:

1. Framers to verify dimensions on the architectural drawings.
2. Double joist only require filler/backer ply when supporting another member using a face-mounted hanger.
3. Install 2x4 blocking @ 24" o/c under parallel non-loadbearing walls.
4. Install single-ply flush window header along inside face of rimboard/rimjoist.
5. Refer to Nascor specifier guide for installation details.
6. Squash blocks recommended to be installed at end bearing on all first level joists which support loading from above exceeding two levels floor or roof.
7. Load transfer blocks to be installed under all point loads.
8. It shall be the framer's responsibility that floor joists and beams are fastened as per the hanger manufacturer's standards.

Rim parallel to joists: 1-1/8" rimboard with
2"x4" block (1/16" longer than rim depth) @ 16" o/c.
All other components and structural elements supporting
the floor system such as beams, walls, columns and
foundation walls and footings including anchorage of
components and bracing for lateral stability are the
responsibility of others.



TOWN OF MILTON
PLANNING AND DEVELOPMENT
JUNIPER 12F MODEL
BUILDING: REVIEWED
SCOTT SHERRIFFS **APR 11, 2017**
PLANS EXAMINER DATE
Neither the issuance of a permit nor carrying out of inspections by the Town of Milton relieves the owner from full responsibility for compliance with the provisions of the Ontario Building Code Act and the Ontario Building Code, both as amended, as well as other applicable statutes and regulations of the Province of Ontario, By-laws of the Region of Halton and Town of Milton

FIRST FLOOR FRAMING

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION



Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca

Project Tag:

JUNIPER 12 EL 1

GREEN PARK HOMES
LECCO RIDGE
MILTON, ON

SALESMAN: RM

Time: 02:42 PM

DATE: 11/04/16

Designer: SB

Not Scaled

License Name:

KEYMARK ENTERPRISES, INC.

Member Data**Description:** CalcG1**Comments:**

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed

Member Weight: 5.9 PLF


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Additional Uniform (PLF)	Top	0' 0.00"	2' 9.50"		0		7		Live
Replacement Uniform (PLF)	Top	0' 0.00"	2' 9.50"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	2' 9.50"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	2' 9.50"		53		60		Live
Point (LBS)	Top	0' 4.63"			0		32		Live
Point (LBS)	Top	0' 4.63"			70		26		Live
Point (LBS)	Top	0' 4.63"			149		56		Live
Point (LBS)	Top	0' 4.63"			307		134		Live
Point (LBS)	Top	2' 4.88"			0		32		Live
Point (LBS)	Top	2' 4.88"			210		101		Live
Point (LBS)	Top	2' 4.88"			249		102		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravit Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	1378#	--
2	2' 9.500"	Wall	N/A	N/A	1.500"	1263#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	633#	343#
2	567#	330#

Design spans

2' 0.250"



March 24, 2017

Product: 1 3/4x11 7/8 West Fraser 2.0E-3100F 1 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.

Design assumes no lateral bracing along the bottom chord.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	141.1#	17693.1#	0%	1.4'	Total Load 1.25D+1.5L
Shear	6.1#	6908.1#	0%	1.5'	Total Load 1.25D+1.5L
TL Deflection	0.0010"	0.0674"	L/999+	1.4'	Total Load D+L
LL Deflection	0.0010"	0.0505"	L/999+	1.4'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Bearing length from point load of top loaded beams assumed to be 3.50"

Control: TL Deflection

Pass-Thru Framing Squash Block is required at all point loads over bearings**Refer to Multiple Member Connection Detail for ply to ply nailing or bolting requirements****READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.****RECEIVED**
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet. The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca

Member Data**Description: CalcG2**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Additional Uniform (PLF)	Top	0' 0.00"	1' 7.50"		0		7		Live
Replacement Uniform (PLF)	Top	0' 0.00"	1' 7.50"		9		3		Live
Replacement Uniform (PLF)	Top	0' 0.00"	1' 7.50"		27		10		Live
Point (LBS)	Top	0' 2.75"			65		20		Snow
Point (LBS)	Top	0' 2.75"			0		130		Live
Point (LBS)	Top	0' 2.75"			57		151		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	539#	--
2	1' 7.500"	Girder	N/A	N/A	N/A	45#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Snow	Dead
1	78#	65#	312#
2	21#	0#	12#

Design spans

1' 1.875"



March 24, 2017

Product: NJH12 1 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.

Design assumes no lateral bracing along the bottom chord.

Lateral support is required at each bearing.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	13.1#	5390.1#	0%	0.8'	Total Load 1.25D+1.5L
End Reaction	539.1#	1735.1#	31%	0'	Total Load 1.25D+1.5L+1.00*0.5S
TL Deflection	0.0010"	0.0385"	L/999+	0.8'	Total Load D+L
LL Deflection	0.0010"	0.0289"	L/999+	0.8'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Control: Max End React.

Shear cannot be calculated because member's length is less than 2d.

Web stiffener and minimum bearing length requirements at hungared connections depend on the connection style and are not included in this design.

Pass-Thru Framing Squash Block is required at all point loads over bearings**Refer to Multiple Member Connection Detail for ply to ply nailing or bolting requirements****READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.****RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION**

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet. The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca

Member Data**Description:** CalcG3**Comments:**

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Additional Uniform (PLF)	Top	0' 0.00"	1' 7.50"		0		7		Live
Replacement Uniform (PLF)	Top	0' 0.00"	1' 7.50"		9		3		Live
Replacement Uniform (PLF)	Top	0' 0.00"	1' 7.50"		27		10		Live
Point (LBS)	Top	0' 2.75"			34		10		Snow
Point (LBS)	Top	0' 2.75"			0		65		Live
Point (LBS)	Top	0' 2.75"			0		65		Live
Point (LBS)	Top	0' 2.75"			29		76		Live
Point (LBS)	Top	0' 2.75"			29		76		Live
Point (LBS)	Top	0' 2.75"			140		140		Live
Point (LBS)	Top	0' 2.75"			321		0		Snow

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	1194#	--
2	1' 7.500"	Girder	N/A	N/A	N/A	45#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Snow	Dead
1	218#	355#	442#
2	21#	0#	12#

Design spans

1' 1.875"



March 24, 2017

Product: NJH12 1 ply

Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.
Lateral support is required at each bearing.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

PASSES DESIGN CHECKS**Limit States Design**

	Actual	Limit	Capacity	Location	Loading
Positive Moment	13.7#	5390.7#	0%	0.8'	Total Load 1.25D+1.5L
End Reaction	1194.7#	1735.7#	68%	0'	Total Load 1.25D+1.00*1.5S+0.5L
TL Deflection	0.0010"	0.0385"	L/999+	0.8'	Total Load D+L
LL Deflection	0.0010"	0.0289"	L/999+	0.8'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Control: Max End React.

Shear cannot be calculated because member's length is less than 2d.

Web stiffness and minimum bearing length requirements at hangared connections depend on the connection style and are not included in this design.

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet. The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB

Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



Member Data**Description: CalcG4**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	1' 10.50"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	1' 10.50"		27		10		Live
Point (LBS)	Top	0' 2.75"			29		11		Live
Point (LBS)	Top	0' 2.75"			32		139		Snow

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	321#	--
2	1' 10.500"	Girder	N/A	N/A	N/A	74#	--


Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Snow	Dead
1	66#	32#	164#
2	38#	0#	14#

Design spans

1' 4.875"



March 24, 2017

Product: NJH12 1 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.
Lateral support is required at each bearing.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	26.7#	5390.7#	0%	0.92'	Total Load 1.25D+1.5L
End Reaction	321.7#	1735.7#	18%	0'	Total Load 1.25D+1.5L+1.00*0.5S
TL Deflection	0.0010"	0.0469"	L/999+	0.92'	Total Load D+L
LL Deflection	0.0010"	0.0352"	L/999+	0.92'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Control: Max End React.

Shear cannot be calculated because member's length is less than 2d.

Web stiffener and minimum bearing length requirements at hungared connections depend on the connection style and are not included in this design.

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet.
The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



Member Data**Description: CalcG5**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	1' 10.50"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	1' 10.50"		27		10		Live
Point (LBS)	Top	0' 2.75"			29		11		Live
Point (LBS)	Top	0' 2.75"			32		139		Snow

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	321#	--
2	1' 10.500"	Girder	N/A	N/A	N/A	74#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Snow	Dead
1	66#	32#	164#
2	38#	0#	14#

Design spans

1' 4.875"



March 24, 2017

Product: NJH12 1 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.
Lateral support is required at each bearing.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	26.7#	5390.7#	0%	0.92'	Total Load 1.25D+1.5L
End Reaction	321.7#	1735.7#	18%	0'	Total Load 1.25D+1.5L+1.00*0.5S
TL Deflection	0.0010"	0.0469"	L/999+	0.92'	Total Load D+L
LL Deflection	0.0010"	0.0352"	L/999+	0.92'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Control: Max End React.

Shear cannot be calculated because member's length is less than 2d.

Web stiffener and minimum bearing length requirements at hungared connections depend on the connection style and are not included in this design.

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet.
The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



Member Data**Description: CalcG6**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed

Member Weight: 5.9 PLF


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	4' 5.75"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	4' 5.75"		240		90		Live
Point (LBS)	Top	0' 4.63"			0		32		Live
Point (LBS)	Top	0' 4.63"			134		51		Live
Point (LBS)	Top	0' 4.63"			186		72		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	1706#	--
2	4' 5.750"	Wall	N/A	N/A	1.500"	1031#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	836#	361#
2	517#	205#

Design spans

3' 10.500"



March 24, 2017

Product: 1 3/4x11 7/8 West Fraser 2.0E-3100F 1 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	999. #	17693. #	5%	2.32'	Total Load 1.25D+1.5L
Shear	505. #	6908. #	7%	0.4'	Total Load 1.25D+1.5L
TL Deflection	0.0077"	0.1292"	L/999+	2.32'	Total Load D+L
LL Deflection	0.0055"	0.0969"	L/999+	2.32'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Bearing length from point load of top loaded beams assumed to be 3.50"
Control: Shear

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet.
The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



Member Data**Description: CalcG7**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed

Member Weight: 5.9 PLF


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	4' 7.50"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	4' 7.50"		40		15		Live
Point (LBS)	Top	4' 2.88"			0		32		Live
Point (LBS)	Top	4' 2.88"			0		32		Live
Point (LBS)	Top	4' 2.88"			65		25		Live
Point (LBS)	Top	4' 2.88"			65		25		Live
Point (LBS)	Top	4' 2.88"			287		108		Live
Point (LBS)	Top	4' 2.88"			287		108		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	279#	--
2	4' 7.500"	Wall	N/A	N/A	1.500"	1748#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	134#	62#
2	838#	393#

Design spans

4' 0.250"

March 24, 2017

Product: 1 3/4x11 7/8 West Fraser 2.0E-3100F 1 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.

Design assumes no lateral bracing along the bottom chord.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	280. #	17693. #	1%	2.23'	Total Load 1.25D+1.5L
Shear	142. #	6908. #	2%	3.44'	Total Load 1.25D+1.5L
TL Deflection	0.0023"	0.1340"	L/999+	2.23'	Total Load D+L
LL Deflection	0.0015"	0.1005"	L/999+	2.23'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Bearing length from point load of top loaded beams assumed to be 3.50"

Control: Shear

Pass-Thru Framing Squash Block is required at all point loads over bearings**Refer to Multiple Member Connection Detail for ply to ply nailing or bolting requirements****READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.****RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION**

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet. The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca

Member Data**Description: CalcG8**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	1' 6.88"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	1' 6.88"		27		10		Live
Point (LBS)	Top	0' 2.75"			0		65		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravit Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	144#	--
2	1' 6.875"	Girder	N/A	N/A	N/A	63#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	32#	77#
2	32#	12#

Design spans

1' 2.500"



March 24, 2017

Product: NJH12 1 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.
Lateral support is required at each bearing.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	19.7#	5390.7#	0%	0.82'	Total Load 1.25D+1.5L
End Reaction	144.7#	1735.7#	8%	0'	Total Load 1.25D+1.5L
TL Deflection	0.0010"	0.0403"	L/999+	0.82'	Total Load D+L
LL Deflection	0.0010"	0.0302"	L/999+	0.82'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Control: Max End React.

Shear cannot be calculated because member's length is less than 2d.

Web stiffener and minimum bearing length requirements at hangared connections depend on the connection style and are not included in this design.

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet.
The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



Member Data**Description: CalcG9**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	1' 6.88"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	1' 6.88"		27		10		Live
Point (LBS)	Top	0' 2.75"			0		65		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravit Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	144#	--
2	1' 6.875"	Girder	N/A	N/A	N/A	63#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	32#	77#
2	32#	12#

Design spans

1' 2.500"



March 24, 2017

Product: NJH12 1 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.
Lateral support is required at each bearing.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	19.7#	5390.7#	0%	0.82'	Total Load 1.25D+1.5L
End Reaction	144.7#	1735.7#	8%	0'	Total Load 1.25D+1.5L
TL Deflection	0.0010"	0.0403"	L/999+	0.82'	Total Load D+L
LL Deflection	0.0010"	0.0302"	L/999+	0.82'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Control: Max End React.

Shear cannot be calculated because member's length is less than 2d.

Web stiffener and minimum bearing length requirements at hangared connections depend on the connection style and are not included in this design.

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet.
The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



Member Data**Description:** CalcG12

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads

Type (Description)	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	2' 1.69"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	3' 2.00"		30		15		Live
Additional Uniform (PLF)	Top	0' 0.00"	18' 1.75"		0		7		Live
Replacement Uniform (PLF)	Top	2' 1.69"	2' 10.38"		27		10		Live
Replacement Uniform (PLF)	Top	2' 10.38"	3' 2.00"		27		10		Live
Replacement Uniform (PLF)	Top	3' 2.00"	5' 8.00"		9		3		Live
Replacement Uniform (PLF)	Top	5' 8.00"	11' 7.63"		27		10		Live
Replacement Uniform (PLF)	Top	5' 8.00"	18' 1.75"		30		15		Live
Replacement Uniform (PLF)	Top	11' 7.63"	12' 4.31"		27		10		Live
Replacement Uniform (PLF)	Top	12' 4.31"	18' 1.75"		27		10		Live
Point (LBS)	Top	0' 2.75"			49		65		Snow
Point (LBS)	Top	0' 2.75"			308		194		Live
Point (LBS)	Top	3' 2.00"			0		11		Live
Point (LBS)	Top	5' 8.00"			0		11		Live
Point (LBS)	Top	17' 9.13"			0		32		Live
Point (LBS)	Top	17' 9.13"			420		158		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	1735#	--
2	18' 1.750"	Wall	N/A	N/A	1.500"	1908#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Snow	Dead
1	714#	49#	511#
2	889#	0#	460#

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

Design spans
17' 6.500"

March 24, 2017

Product: NJ12 2 ply**PASSES DESIGN CHECKS**

NOTE: Web stiffeners are required at point loads > 0#.
Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.
Lateral support is required at each bearing.

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	4329. #	9020. #	47%	8.99'	Total Load 1.25D+1.5L
Shear	1040. #	3400. #	30%	18.15'	Total Load 1.25D+1.5L
End Reaction	1908. #	4100. #	46%	18.15'	Total Load 1.25D+1.5L
TL Deflection	0.3632"	0.5847"	L/579	8.99'	Total Load D+L
LL Deflection	0.2271"	0.4385"	L/926	8.99'	Total Load L

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet.
The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



Member Data**Description: CalcG13**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	5' 3.00"		35		13		Live
Replacement Uniform (PLF)	Top	8' 3.00"	14' 0.00"		35		13		Live
Point (LBS)	Top	0' 5.00"			0		30		Live
Point (LBS)	Top	0' 5.00"			204		76		Live
Point (LBS)	Top	0' 5.00"			234		117		Live
Point (LBS)	Top	5' 3.00"			0		12		Live
Point (LBS)	Top	8' 3.00"			0		12		Live
Point (LBS)	Top	13' 9.25"			30		0		Snow
Point (LBS)	Top	13' 9.25"			0		61		Live
Point (LBS)	Top	13' 9.25"			234		170		Live

**Bearings and Factored Reactions**


	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	1298#	--
2	14' 0.000"	Wall	N/A	N/A	1.500"	1050#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Snow	Dead
1	614#	0#	301#
2	427#	30#	315#

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.



Design spans

13' 6.750"

March 24, 2017

Product: NJ12 2 ply**PASSES DESIGN CHECKS**

NOTE: Web stiffeners are required at point loads > 0#.
Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.
Lateral support is required at each bearing.

**Pass-Thru Framing Squash Block is
required at all point loads over bearings**

**Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements**

**RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION**

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	1137. #	9020. #	12%	8.25'	Total Load 1.25D+1.5L
Shear	1298. #	3400. #	38%	0'	Total Load 1.25D+1.5L
End Reaction	1298. #	4100. #	31%	0'	Total Load 1.25D+1.5L
TL Deflection	0.0646"	0.4521"	L/999+	7'	Total Load D+L
LL Deflection	0.0433"	0.3391"	L/999+	7'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Control: Shear

Manufacturer's installation guide MUST be consulted for multi-ply connection details and alternatives

Manufacturer's installation guide MUST be consulted to determine if web stiffeners are required at point loads

Member Data**Description: CalcG14**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	8' 6.56"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	0' 4.00"		8		120		Live
Replacement Uniform (PLF)	Top	0' 4.00"	1' 4.00"		20		47		Live
Replacement Uniform (PLF)	Top	1' 4.00"	2' 11.25"		30		11		Live
Replacement Uniform (PLF)	Top	2' 11.25"	5' 7.25"		0		0		Live
Replacement Uniform (PLF)	Top	5' 7.25"	7' 2.56"		30		11		Live
Replacement Uniform (PLF)	Top	7' 2.56"	7' 4.06"		29		38		Live
Replacement Uniform (PLF)	Top	7' 4.06"	8' 6.56"		17		52		Live
Point (LBS)	Top	0' 2.63"			0		90		Live
Point (LBS)	Top	0' 2.63"			0		90		Live
Point (LBS)	Top	2' 11.25"			0		11		Live
Point (LBS)	Top	5' 7.25"			0		11		Live
Point (LBS)	Top	8' 3.94"			0		90		Live
Point (LBS)	Top	8' 3.94"			0		90		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravit Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	652#	--
2	8' 6.562"	Wall	N/A	N/A	1.500"	646#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	177#	309#
2	177#	305#

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

Design spans

8' 1.312"



March 24, 2017

Product: NJ12 1 ply**PASSES DESIGN CHECKS**

NOTE: Web stiffeners are required at point loads > 0#.
Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.
Lateral support is required at each bearing.

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	704. #	4510. #	15%	4.27'	Total Load 1.25D+1.5L
Shear	427. #	1700. #	25%	0'	Total Load 1.25D+1.5L
End Reaction	652. #	2050. #	31%	0'	Total Load 1.25D+1.5L
TL Deflection	0.0334"	0.2703"	L/999+	4.27'	Total Load D+L
LL Deflection	0.0215"	0.2027"	L/999+	4.27'	Total Load L

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.


**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet.
The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



----- Floor Framing Material -----

Type	Qty.	Product	Length
J1	9	NJH12	18' 0"
J2	15	NJH12	16' 0"
J3	22	NJH12	14' 0"
J4	11	NJH12	12' 0"
J5	18	NJH12	10' 0"
J6	3	NJH12	6' 0"
J7	19	NJ60H12	18' 0"
G1	2	1 3/4x11 7/8 West Fraser 2.0E-	8' 0"
G2	2	1 3/4x11 7/8 West Fraser 2.0E-	10' 0"
G3	2	1 3/4x11 7/8 West Fraser 2.0E-	6' 0"
G4	1	1 3/4x11 7/8 West Fraser 2.0E-	6' 0"
G5	2	1 3/4x11 7/8 West Fraser 2.0E-	10' 0"
R1	15	11 7/8" RIMBOARD	12' 0"



HATCH AREA INDICATED REPRESENTS
CERAMIC TILED FLOOR WITH AN
ADDITIONAL DEAD LOAD OF 5.00 PSF

All product names are trademarks of their respective owners

DESIGN ASSUMPTIONS
=====

Loads:(un-factored)
T/C Live: 40 psf B/C Live: 0 psf
T/C Dead: 15 psf B/C Dead: 0 psf
Load Case: Live
Deflection Criteria:
L/480 Live L/360 Total
Building Code: OBC-2012 (Limit States Design
Building Type: Residential
Importance Category: Normal (Part 9)
Design assumes top edge continuously braced,
and bottom edge unbraced.
Joist Design Includes CCMC Vibration Check
Subfloor: 5/8" OSB Glued and Nailed
Ceiling: 1/2" gypsum
Blocking: (None)

All Loads are UN-FACTORED Loads

- NOTES:
1. Framers to verify dimensions on the architectural drawings.
 2. Double joist only require filler/backer ply when supporting another member using a face-mounted hanger.
 3. Install 2x4 blocking @ 24" o/c under parallel non-loadbearing walls.
 4. Install single-ply flush window header along inside face of rimboard/rimjoist.
 5. Refer to Nascor specifier guide for installation details.
 6. Squash blocks recommended to be installed at end bearing on all first level joists which support loading from above exceeding two levels floor or roof.
 7. Load transfer blocks to be installed under all point loads.
 8. It shall be the framer's responsibility that floor joists and beams are fastened as per the hanger manufacturer's standards.


**PASS-THRU FRAMING SQUASH BLOCK
IS REQUIRED AT ALL POINT LOADS
OVER BEARINGS.**

**Refer to Multiple Member Connection
Detail to ply to ply nailing or bolting
requirements.**

----- Connector List -----

ID#	Qty	Model Number
H1	1	HUS1.81/10
H2	3	LT251188
H3	11	LT251188
H1	9	UPLIFT ANCHOR

Rim parallel to joists: 1-1/8" rimboard with
2"x4" block (1/16" longer than rim depth) @ 16" o/c.
All other components and structural elements supporting
the floor system such as beams, walls, columns and
foundation walls and footings including anchorage of
components and bracing for lateral stability are the
responsibility of others.



TOWN OF MILTON
PLANNING AND DEVELOPMENT
JUNIPER 12F MODEL

BUILDING: REVIEWED
SCOTT SHERRIFFS APR 11, 2017

PLANS EXAMINER DATE

Neither the issuance of a permit nor carrying out of inspections by the Town of Milton relieves the owner from full responsibility for compliance with the provisions of the Ontario Building Code Act and the Ontario Building Code, both as amended, as well as other applicable statutes and regulations of the Province of Ontario, By-laws of the Region of Halton and Town of Milton

RECEIVED
TOWN OF MILTON

MAR 29, 2017

JUNIPER 12F

BUILDING DIVISION

SECOND FLOOR FRAMING



Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca

Project Tag:

JUNIPER 12 EL 1

**GREEN PARK HOMES
LECCO RIDGE
MILTON, ON**

SALESMAN: RM

Time: 01:05 PM

DATE: 11/03/16

Designer: SB

Not Scaled

License Name:

KEYMARK ENTERPRISES, INC.



Member Data**Description:** CalcG1**Comments:**

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed

Member Weight: 11.8 PLF


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads

Type (Description)	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	3' 10.00"		263		99		Live
Replacement Uniform (PLF)	Top	0' 0.00"	7' 2.00"		163		61		Live
Replacement Uniform (PLF)	Top	3' 10.00"	7' 2.00"		263		114		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	2925#	--
2	7' 2.000"	Wall	N/A	N/A	1.500"	2957#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	1453#	596#
2	1453#	622#

Design spans
6' 9.750"**Product: 1 3/4x11 7/8 West Fraser 2.0E-3100F 2 ply****PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.

Design assumes no lateral bracing along the bottom chord.

Compression edge maximum unbraced length calculation is based on ply width.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	5006.1#	35386.1#	14%	3.58'	Total Load 1.25D+1.5L
Shear	2093.1#	13815.1#	15%	6.31'	Total Load 1.25D+1.5L
TL Deflection	0.0398"	0.2271"	L/999+	3.58'	Total Load D+L
LL Deflection	0.0280"	0.1703"	L/999+	3.58'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Bearing length from point load of top loaded beams assumed to be 3.50"

Control: TL Deflection

Manufacturer's installation guide MUST be consulted for multi-ply connection details and alternatives

Pass-Thru Framing Squash Block is required at all point loads over bearings**Refer to Multiple Member Connection Detail for ply to ply nailing or bolting requirements****READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.****RECEIVED**
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

March 24, 2017

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet. The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca

Member Data**Description: CalcG2**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed

Member Weight: 11.8 PLF


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	4' 3.75"		80		30		Live
Replacement Uniform (PLF)	Top	0' 0.00"	8' 9.75"		9		3		Live
Replacement Uniform (PLF)	Top	0' 0.00"	8' 9.75"		27		10		Live
Replacement Uniform (PLF)	Top	4' 3.75"	8' 9.75"		160		60		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	1140#	--
2	8' 9.750"	Wall	N/A	N/A	1.500"	1456#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	549#	253#
2	710#	314#

Design spans

8' 0.500"

Product: 1 3/4x11 7/8 West Fraser 2.0E-3100F 2 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.

Design assumes no lateral bracing along the bottom chord.

Compression edge maximum unbraced length calculation is based on ply width.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	2653. #	35386. #	7%	4.81'	Total Load 1.25D+1.5L
Shear	1061. #	13815. #	7%	7.62'	Total Load 1.25D+1.5L
TL Deflection	0.0270"	0.2681"	L/999+	4.41'	Total Load D+L
LL Deflection	0.0186"	0.2010"	L/999+	4.41'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Bearing length from point load of top loaded beams assumed to be 3.50"

Control: TL Deflection

Manufacturer's installation guide MUST be consulted for multi-ply connection details and alternatives

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION



March 24, 2017

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet.
The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



Member Data**Description: CalcG3**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Deck Connection: Nailed

Member Weight: 11.8 PLF


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	4' 5.50"		9		3		Live
Replacement Uniform (PLF)	Top	0' 0.00"	4' 5.50"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	4' 5.50"		80		30		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	467#	--
2	4' 5.500"	Wall	N/A	N/A	1.500"	467#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	223#	106#
2	223#	106#

Design spans
3' 10.250"**Product: 1 3/4x11 7/8 West Fraser 2.0E-3100F 2 ply****PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.

Design assumes no lateral bracing along the bottom chord.

Compression edge maximum unbraced length calculation is based on ply width.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	450.1#	35386.1#	1%	2.15'	Total Load 1.25D+1.5L
Shear	227.1#	13815.1#	1%	3.11'	Total Load 1.25D+1.5L
TL Deflection	0.0017"	0.1285"	L/999+	2.15'	Total Load D+L
LL Deflection	0.0012"	0.0964"	L/999+	2.15'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Bearing length from point load of top loaded beams assumed to be 3.50"

Control: Shear

Manufacturer's installation guide MUST be consulted for multi-ply connection details and alternatives

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

Pass-Thru Framing Squash Block is
required at all point loads over bearings

Refer to Multiple Member Connection
Detail for ply to ply nailing or bolting
requirements

RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION



March 24, 2017

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet.
The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca



Member Data**Description: CalcG4**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed

Member Weight: 5.9 PLF

Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

Replacement Uniform (PLF)

Point (LBS)

Side

Top

Top

Begin

0' 0.00"

0' 2.63"


End

5' 0.50"

**Trib.
Width****Other
Start****End****Dead
Start****End****Category**

Live

Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	507#	--
2	5' 0.500"	Girder	N/A	N/A	N/A	381#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	249#	107#
2	185#	83#

Design spans

4' 6.375"

Product: 1 3/4x11 7/8 West Fraser 2.0E-3100F 1 ply**PASSES DESIGN CHECKS**Design assumes continuous lateral bracing along the top chord.
Design assumes no lateral bracing along the bottom chord.**Limit States Design**

	Actual	Limit	Capacity	Location	Loading
Positive Moment	432.1#	17693.1#	2%	2.48'	Total Load 1.25D+1.5L
Shear	215.1#	6908.1#	3%	0.23'	Total Load 1.25D+1.5L
TL Deflection	0.0040"	0.1510"	L/999+	2.48'	Total Load D+L
LL Deflection	0.0027"	0.1133"	L/999+	2.48'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Bearing length from point load of top loaded beams assumed to be 3.50"

Control: Shear

Minimum bearing length requirements at hanged connections depend on the connection style and are not included in this design.

Pass-Thru Framing Squash Block is required at all point loads over bearings**Refer to Multiple Member Connection Detail for ply to ply nailing or bolting requirements****RECEIVED**
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION

March 24, 2017

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet. The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca

Member Data**Description: CalcG5**

Comments:

Member Type: Girder

Application: Floor

Top Lateral Bracing: Continuous

Bottom Lateral Bracing: None

Moisture Condition: Dry

Building Code: OBC-2012

Standard Load:

Live Load: 0 PLF

Deflection Criteria: L/480 live, L/360 total

0.720" max. LL

Dead Load: 0 PLF

Deck Connection: Nailed

Member Weight: 11.8 PLF


Filename: D:\SAUMIL\GR

Building Type: Residential

Importance Category: Normal (Part 9)

Other Loads**Type****(Description)**

	Side	Begin	End	Trib. Width	Other Start	End	Dead Start	End	Category
Replacement Uniform (PLF)	Top	0' 0.00"	4' 3.75"		27		10		Live
Replacement Uniform (PLF)	Top	0' 0.00"	8' 9.75"		27		10		Live
Replacement Uniform (PLF)	Top	4' 3.75"	8' 9.75"		9		3		Live
Replacement Uniform (PLF)	Top	4' 3.75"	8' 9.75"		160		60		Live
Point (LBS)	Top	4' 3.75"			194		106		Live

**Bearings and Factored Reactions**

	Location	Type	Material	Input Length	Min Required	Gravity Reaction	Gravity Uplift
1	0' 0.000"	Wall	N/A	N/A	1.500"	993#	--
2	8' 9.750"	Wall	N/A	N/A	1.500"	1546#	--

Maximum Unfactored Load Case Reactions

Used for applying point loads (or line loads) to carrying members

	Live	Dead
1	463#	238#
2	745#	343#

Design spans

8' 0.500"



March 24, 2017

Product: 1 3/4x11 7/8 West Fraser 2.0E-3100F 2 ply**PASSES DESIGN CHECKS**

Design assumes continuous lateral bracing along the top chord.

Design assumes no lateral bracing along the bottom chord.

Compression edge maximum unbraced length calculation is based on ply width.

Limit States Design

	Actual	Limit	Capacity	Location	Loading
Positive Moment	2983.>#	35386.>#	8%	4.41'	Total Load 1.25D+1.5L
Shear	1150.>#	13815.>#	8%	7.62'	Total Load 1.25D+1.5L
TL Deflection	0.0292"	0.2681"	L/999+	4.41'	Total Load D+L
LL Deflection	0.0197"	0.2010"	L/999+	4.41'	Total Load L

(Actual is factored load effects, Limit is design resistance)

Bearing length from point load of top loaded beams assumed to be 3.50"

Control: TL Deflection

Manufacturer's installation guide MUST be consulted for multi-ply connection details and alternatives

Pass-Thru Framing Squash Block is required at all point loads over bearings**Refer to Multiple Member Connection Detail for ply to ply nailing or bolting requirements****READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-2. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.****RECEIVED
TOWN OF MILTON
MAR 29, 2017
JUNIPER 12F
BUILDING DIVISION**

All product names are trademarks of their respective owners

Copyright (C) 2016 by Simpson Strong-Tie Company Inc. ALL RIGHTS RESERVED.

**Passing is defined as when the member, floor joist, beam or girder shown on this drawing meets applicable design criteria for Loads, Loading Conditions, and Spans listed on this sheet. The design must be reviewed by a qualified designer or design professional as required for approval. This design assumes product installation according to the manufacturer's specifications.

SB
Nascor by KOTT
14 Anderson Blvd.
Uxbridge, ON.
www.nascor.ca