

FROM PLAN DATED: APRIL 2017

BUILDER: GREENPARK HOMES

SITE: RUSSEL GARDENS

MODEL: ROSEWOOD 5

ELEVATION: 1

LOT:

CITY: WATERDOWN

SALESMAN: M D DESIGNER: AJ REVISION:

NOTES:


REFER TO THE NORDIC **INSTALLATION** GUIDE FOR PROPER STORAGE AND INSTALLATION. SQUASH BLOCKS OF 2x4, 2x6, 2x8 #2 S.P.F REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. MULTIPLE SQUASH BLOCKS REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. CANTILEVERED JOISTS INCLUDING CANT' OVER BRICK REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR HOLES INCLUDING DUCT CHASE AND FIELD CUT OPENINGS SEE FIGURE 7, TABLES 1 & 2. CERAMIC TILE APPLICATION AS PER O.B.C 9.30.6. LOADING:


DESIGN LOADS: L/480.000 LIVE LOAD: 40.0 lb/ft² DEAD LOAD: 15.0 lb/ft TILED AREAS: 20 lb/ft


SUBFLOOR: 3/4" GLUED AND NAILED

DATE: 6/12/2017

1st FLOOR








Products									
PlotID	Length	Product	Plies	Net Qty					
J1	18-00-00	11 7/8" NI-40x	1	46					
J2	14-00-00	11 7/8" NI-40x	1	15					
J3	10-00-00	11 7/8" NI-40x	1	1					
J4	8-00-00	11 7/8" NI-40x	1	7					
J5	20-00-00	11 7/8" NI-80	1	19					
B8 DR	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2					
B5	12-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1					
B6	12-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1					
B7	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2					

Connector Summary									
Manuf	Product								
H1	IUS2.56/11.88								
H2	HGUS410								
	Manuf H1								



FROM PLAN DATED: APRIL 2017

BUILDER: GREENPARK HOMES

SITE: RUSSEL GARDENS

MODEL: ROSEWOOD 5

ELEVATION: 1

LOT:

CITY: WATERDOWN

SALESMAN: M D DESIGNER: AJ REVISION:

NOTES:


REFER TO THE NORDIC INSTALLATION GUIDE FOR PROPER STORAGE AND INSTALLATION. **SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. MULTIPLE SQUASH BLOCKS REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. CANTILEVERED JOISTS INCLUDING CANT' OVER BRICK REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR HOLES INCLUDING DUCT CHASE AND FIELD CUT OPENINGS SEE FIGURE 7 TABLES 1 & 2 OF THE INSTALLATION GUIDE. CERAMIC TILE APPLICATION AS PER O.B.C. 9.30.6 LOADING:


DESIGN LOADS: L/480.000 LIVE LOAD: 40.0 lb/ft² DEAD LOAD: 15.0 lb/ft TILED AREAS: 20 lb/ft


SUBFLOOR: 5/8" GLUED AND NAILED


DATE: 6/12/2017

2nd FLOOR










	Products									
PlotID	Length	Product	Plies	Net Qty						
J1	18-00-00	11 7/8" NI-40x	1	65						
J2	14-00-00	11 7/8" NI-40x	1	17						
J3	10-00-00	11 7/8" NI-40x	1	1						
J4	8-00-00	11 7/8" NI-40x	1	7						
B8 DR	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2						
B5	12-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1						
B6	12-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1						
B7	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2						

	Connector Summary								
Qty	Manuf	Product							
7	H1	IUS2.56/11.88							
1	H1	IUS2.56/11.88							
2	H2	HGUS410							



FROM PLAN DATED: APRIL 2017

BUILDER: GREENPARK HOMES

SITE: RUSSEL GARDENS

MODEL: ROSEWOOD 5

ELEVATION: 2,3

LOT:

CITY: WATERDOWN

SALESMAN: M D **DESIGNER: AJ REVISION:**

NOTES:

REFER TO THE NORDIC INSTALLATION GUIDE FOR PROPER STORAGE AND INSTALLATION. SQUASH BLOCKS OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. MULTIPLE SQUASH BLOCKS REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. CANTILEVERED JOISTS INCLUDING CANT' OVER BRICK REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR HOLES INCLUDING DUCT CHASE AND FIELD CUT OPENINGS SEE FIGURE 7 TABLES 1 & 2 OF THE INSTALLATION GUIDE. CERAMIC TILE APPLICATION AS PER O.B.C. 9.30.6 LOADING:

DESIGN LOADS: L/480.000 LIVE LOAD: 40.0 lb/ft2 DEAD LOAD: 15.0 lb/ft TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 6/12/2017

2nd FLOOR



COMPANYJune 12, 2017 15:32

PROJECT
J5 2ND FLOOR ABOVE GARAGE
NORDIC SIZER


Design Check Calculation Sheet

Nordic Sizer - Canada 6.4

Loads:

Load	Type	Distribution	Pat-	Location	[ft]	Magnitude	Unit
	11	İ	tern	Start	End	Start End	
Load1	Dead	Full Area				20.00	psf
Load2	Live	Full Area	ľ			40.00	psf
Self-weight	Dead	Full UDL				3.4	plf

Maximum Reactions (lbs), Bearing Resistances (lbs) and Bearing Lengths (in):



Unfactored: Dead Live	218 371	218 371
Factored: Total	829	829
Bearing:		-
Resistance		
Joist	2243	2243
Support	7426	7426
Des ratio		
Joist	0.37	0.37
Support	0.11	0.11
Load case	#2	#2
Length	3	3
Min req'd	1-3/4	1-3/4
Stiffener	No	No
Kd	1.00	1.00
KB support	1.00	1.00
fcp sup	769	769
Kzcp sup	1.15	1.15

Nordic 11-7/8" NI-80 Floor joist @ 12" o.c.

Supports: All - Lumber Sill plate, No.1/No.2
Total length: 18'-11.0"; 5/8" nailed and glued OSB sheathing
This section PASSES the design code check.

Limit States Design using CSA-086-09 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 829	Vr = 2336	lbs	Vf/Vr = 0.35
Moment(+)	Mf ≈ 3847	Mr = 11609	lbs-ft	Mf/Mr = 0.33
Perm. Defl'n	$0.12 = \langle L/999$	0.62 = L/360	in grade	FESSION 0.19
Live Defl'n	$0.20 = \langle L/999 \rangle$	0.46 = L/480	in Por	0.43
Total Defl'n	0.32 = L/698	0.93 = L/240	in &	0.34
Bare Defl'n	$0.22 = \langle L/999$	0.62 = L/360	in/s	0.36
Vibration	Lmax = 18'-7	Lv = 19'-11	ft o cki	TSOULAKOS BL . 84
Defl'n	= 0.028	= 0.034	in 3 S. N	0.84

DWO NO.TAM 42813.17 STRUCTURAL COMPONENT ONLY

SOUNCE OF ONTER

NORDIC SIZER

Nordic Sizer - Canada 6.4

Page 2

	Additional	Data:								
	FACTORS:		KD	KH	KZ	KL	KT	KS	KN	LC#
	Vr	2336	1.00	1.00	. -	_	_	-	_	#2
ı	Mr+	11609	1.00	1.00	-	1.000	-	-	_	#2
١	EI	547.1 m	illion	_	-	***	_	-	-	#2
ı	CRITICAL LO	DAD COMBI	NATIONS	: :						
		: LC #2								
	Moment(+)									
Ì	Deflection	on: LC #1								
) + 1.0L				÷		
				+ 1.0L						
				+ 1.0L						
l	Bearing	: Suppor	ct 1 - I	$_{1}C #2 = 1$	L.25D +	1.5L				
		Suppor	ct 2 - I	C #2 = 1	L.25D +	1.5L		_	1	
	Load Type	es: D=dead	d W=win	id S=sno	ow H=ea	arth,grou	ındwateı	r E=ear	tnquake	
1		L=live	e(use,oc	cupancy)	Ls=li	ve(stora	.ge, equi	pment)	r=r1re	
	All Load		lons (LC	s) are l	listed :	in the An	alysis	output		
	CALCULATION									
	Deflection	on: Eleft	f = 6	313e06 lk	o-in2 E	\leftarrow 6.18e	06 lbs			
	"Live" de	eflection	= Defle	ction fr	com all	non-dead	lloads	(live,	wind, sr	now)
Ĺ								-		

Design Notes:

- 1. WoodWorks analysis and design are in accordance with the 2010 National Building Code of Canada (NBC Part 4) and the CSA O86-09 Engineering Design in Wood standard, which includes Update No.1. **CONFORMS TO OBC 2012**
- 2. Please verify that the default deflection limits are appropriate for your application.
- 3. Refer to technical documentation for installation guidelines and construction details.
- 4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
- 5. Joists shall be laterally supported at supports and continuously along the compression edge.
- 6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.



COMPANYJune 12, 2017 15:27

PROJECT J1 2ND FLOOR NORDIC SIZER


Design Check Calculation Sheet

Nordic Sizer – Canada 6.4

Loads:

Load	Type	Distribution	Pat-	Location	[ft]	Magnitu	de	Unit
	11		tern	Start	End	Start	End	
Load1	Dead	Full Area				20.00		psf
Load2	Live	Full Area				40.00		psf
Self-weight	Dead	Full UDL				2.9		plf

Maximum Reactions (lbs), Bearing Resistances (lbs) and Bearing Lengths (in):



Unfactored:		
Dead	197	197
Live	345	345
Factored:		
Total	763	763
Bearing:		
Resistance		
Joist	2189	2189
Support	5304	• 5304
Des ratio		
Joist	0.35	0.35
Support	0.14	0.14
Load case	#2	#2
Length	3	3
Min req'd	1-3/4	1-3/4
Stiffener	No	No
Kd	1.00	1.00
KB support	1.00	1.00
fcp sup	769	769
Kzcp sup	1.15	1.15

Nordic 11-7/8" NI-40x Floor joist @ 12" o.c.

Supports: All - Lumber Sill plate, No.1/No.2

Total length: 17'-7.0"; 5/8" nailed and glued OSB sheathing with 1/2" gypsum ceiling

This section PASSES the design code check.

Limit States Design using CSA-086-09 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 763	Vr = 2336	lbs	Vf/Vr = 0.33
Moment(+)	Mf = 3287	Mr = 6255	lbs-ft	EESS/MIMMr = 0.53
Perm. Defl'n	$0.12 = \langle L/999 \rangle$	0.57 = L/360	in PR	0.21
Live Defl'n	$0.21 = \langle L/999$	0.43 = L/480	in /	0.48
Total Defl'n	0.32 = L/637	0.86 = L/240	in/2 (MID 2 0.38
Bare Defl'n	0.24 = L/873	0.57 = L/360	ing	图 0.41
Vibration	Lmax = 17'-3	Lv = 18'-11	ft 3 S.KF	TSOULAKOS 🛒
Defl'n	= 0.028	= 0.037	in gran	0.77

DWO NO.TAM 4281417 STRUCTURAL COMPONENT ONLY

POLINCE OF ONTE

NORDIC SIZER

Nordic Sizer - Canada 6.4

Page 2

Additiona	il Data:									
FACTORS:	f/E	KD	KH	KZ		KT	KS	KN	LC#	
Vr	2336	1.00	1.00	-	_	-	-	_	#2	
Mr+	6255	1.00	1.00	-	1.000	-	-	-	#2	
EI	371.1 m			-	-	-	_	_	#2	
CRITICAL L	OAD COMBI	NATIONS	S :							
	: LC #2									
) : LC #2									
Deflecti	on: LC #1									
			0 + 1.0L							
			0 + 1.0L							
			0 + 1.0L							
Bearing	: Suppor									
			LC #2 = 1					<u></u>		
Load Typ	es: D=dead									
					ive(stora			r=rre		
	Combinat	ions (L	Cs) are 1	listed 1	in the An	alysis	output			
CALCULATI						0.6.11				
Deflecti	on: Elef:	E = 4	133e06 lk	o-in2 F	K= 6.18e	06 lbs		. ,		
"Live" d	eflection	= Defle	ection fi	com all	non-dead	loads	(live,	wind, sn	OW)	

Design Notes:

- 1. WoodWorks analysis and design are in accordance with the 2010 National Building Code of Canada (NBC Part 4) and the CSA O86-09 Engineering Design in Wood standard, which includes Update No.1.
- 2. Please verify that the default deflection limits are appropriate for your application.
- 3. Refer to technical documentation for installation guidelines and construction details.
- 4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
- 5. Joists shall be laterally supported at supports and continuously along the compression edge.
- 6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.

S. KATSOULAKOS E

DWG NO. YAM 4281417 STRUCTURAL COMPONENT ONLY



COMPANY

June 12, 2017 15:28

PROJECT

J1 2ND FLOOR ABOVE GARAGE NORDIC SIZER


Design Check Calculation Sheet

Nordic Sizer - Canada 6.4

Loads:

Load	Type	Distribution	Pat-	Location	[ft]	Magnitud	le	Unit
`	1		tern	Start	End	Start	End	
Load1	Dead	Full Area				20.00		psf
Load2	Live	Full Area				40.00		psf
Self-weight	Dead	Full UDL				2.9		plf

Maximum Reactions (lbs), Bearing Resistances (lbs) and Bearing Lengths (in):



Unfactored: Dead Live	197 345	197 345
Factored:		<u> </u>
Total	763	763
Bearing:	, 05	
Resistance		1
	2189	2189
Joist		5304
Support	5304	3304
Des ratio	i l	
Joist	0.35	0.35
Support	0.14	0.14
Load case	#2	#2
Length	3	3
Min req'd	1-3/4	1-3/4
Stiffener	No	No
Kd	1.00	1.00
KB support	1.00	1.00
fcp sup	769	769
Kzcp sup	1.15	1.15
1 VSCD and 1	1.10	

Nordic 11-7/8" NI-40x Floor joist @ 12" o.c.

Supports: All - Lumber Sill plate, No.1/No.2
Total length: 17'-7.0"; 5/8" nailed and glued OSB sheathing
This section PASSES the design code check.

Limit States Design using CSA-O86-09 and Vibration Criterion:

			T	
Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 763	Vr = 2336	lbs	Vf/Vr = 0.33
Moment(+)	Mf = 3287	Mr = 6255	lbs-ft	Mf/Mr = 0.53
Perm. Defl'n	$0.12 = \langle L/999 \rangle$	0.57 = L/360	in proof	SS/O _{N/2} 0.21
Live Defl'n	$0.21 = \langle L/999$	0.43 = L/480	in	0.48
Total Defl'n	0.32 = L/637	0.86 = L/240	in Co	0.38
Bare Defl'n	0.24 = L/873	0.57 = L/360	i/m	0.41
Vibration	Lmax = 17'-3	Lv = 18'-4	I D C KAT	SOULAKOS G
Defl'n	= 0.030	= 0.037	Arri C	0.83
	<u> </u>		A PRODUCTION	and the second s

POLINCE OF ONTE STRUCTURAL COMPONENT ONLY

NORDIC SIZER

Nordic Sizer - Canada 6.4

Page 2

	Additional	Data:									
	FACTORS:	f/E	KD	KH	KZ	KL	KT	KS	KN	LC#	
	Vr									#2	
	Mr+	6255	1.00	1.00	-	1.000	-	-	-	••	
	EI	371.1 m	illion	-	-	-		_		#2	
ı	CRITICAL LO	DAD COMBI	NATIONS	3 :							
	Shear										
	Moment(+)										
ļ	Deflectio			· <u>-</u>							
١) + 1.0L							
ı				+ 1.0L		•					
ı				+ 1.0L	•	,					
ı	Bearing										
				$_{1}C #2 = 1$				_			
l	Load Type										
ļ						lve(stora		_	i=fire		
l	All Load		lons (LC	s) are .	listed i	in the An	alysis	output			
ļ	CALCULATIO		_								
١	Deflectio					<= 6.18e					
	"Live" de	flection	= Defle	ection fi	rom all	non-dead	Loads	(live,	wind, sr	10W)	
H											

Design Notes:

- 1. WoodWorks analysis and design are in accordance with the 2010 National Building Code of Canada (NBC Part 4) and the CSA O86-09 Engineering Design in Wood standard, which includes Update No.1.
- 2. Please verify that the default deflection limits are appropriate for your application.

CONFORMS TO BBC 2012

- 3. Refer to technical documentation for installation guidelines and construction details.4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
- 5. Joists shall be laterally supported at supports and continuously along the compression edge.
- 6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.





COMPANYJune 12, 2017 15:29

PROJECT
J1 1ST FLOOR
NORDIC SIZER


Design Check Calculation Sheet

Nordic Sizer - Canada 6.4

Loads:

Load	Туре	Distribution	Pat-	Location	[ft]	Magnitud	de	Unit
			tern	Start	End	Start	End	
Load1	Dead	Full Area			-	20.00		psf
Load2	Live	Full Area				40.00		psf
Self-weight	Dead	Full UDL				2.9		plf

Maximum Reactions (lbs), Bearing Resistances (lbs) and Bearing Lengths (in):



Unfactored: Dead Live	197 345	197 345
Factored:	310	343
Total	763	763
Bearing:		
Resistance		
Joist	2189	2189
Support	5304	5304
Des ratio		
Joist	0.35	0.35
Support	0.14	0.14
Load case	#2	#2
Length	3	3
Min req'd	1-3/4	1-3/4
Stiffener	No	No
Kd	1.00	1.00
KB support	1.00	1.00
fcp sup	769	769
Kzcp sup	1.15	1.15

Nordic 11-7/8" NI-40x Floor joist @ 12" o.c.

Supports: All - Lumber Sill plate, No. 1/No.2
Total length: 17'-7.0"; 3/4" nailed and glued OSB sheathing
This section PASSES the design code check.

Limit States Design using CSA-O86-09 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 763	Vr = 2336	lbs	Vf/Vr = 0.33
Moment(+)	Mf = 3287	Mr = 6255	lbs-ft	Mf/Mr = 0.53
Perm. Defl'n	$0.12 = \langle L/999 \rangle$	0.57 = L/360	in March	0.20
Live Defl'n	$0.20 = \langle L/999 \rangle$	0.43 = L/480	in/o	0.47
Total Defl'n	0.32 = L/651	0.86 = L/240	ing / on	M/1 2 0.37
Bare Defl'n	0.24 = L/873	0.57 = L/360	in	0.47 0.37 0.41
Vibration	Lmax = 17'-3	Lv = 19'-6	£₩ S KAT	SOULAKOS S
Defl'n	= 0.026	= 0.037	in	3 0.71

DWG NO.TAM 42015-17 STRUCTURAL COMPONENT ONLY

NORDIC SIZER

Nordic Sizer - Canada 6.4

Page 2

Additiona	l Data:									
FACTORS:							KS		LC#	
	2336								#2	
Mr+	6255	1.00	1.00	-	1.000	_	-	-	—	
	371.1 m			-	_	-	-	-	#2	
CRITICAL LO										
	: LC #2									
) : LC #2									
Deflection	on: LC #1									
1			0 + 1.0L							
			0 + 1.0L	,	•					
			0 + 1.0L							
Bearing	: Suppor									
			LC #2 = 3				-			
Load Type	es: D=dead									
l					ive(stora			r=11re		
	Combinati	ons (LO	Cs) are	Listed :	in the An	alysis	output			
CALCULATION										
	on: Eleff							,		
"Live" de	eflection	= Defle	ection for	rom all	non-dead	loads	(live,	wind, s	now)	

Design Notes:

- 1. WoodWorks analysis and design are in accordance with the 2010 National Building Code of Canada (NBC Part 4) and the CSA O86-09 Engineering Design in Wood standard, which includes Update No.1. CONFORMS TO OBC 2012
- 2. Please verify that the default deflection limits are appropriate for your application.
- 3. Refer to technical documentation for installation guidelines and construction details.
- 4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
- 5. Joists shall be laterally supported at supports and continuously along the compression edge.
- 6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.

BROFESSIONS

S. KATSOULAKOS

S. KATSOULAKOS

DWO NO. TAM 420/617

STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP Basment\...\B1A(i3811)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

August 18, 2017 16:42:50

BC CALC® Design Report

FC1 Floor Material

Build 5033

Job Name: Address:

City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5 EL-2 WITH DECK.mmdl


10

Description: Designs\Flush Beams\Basment\Flush Beams\B1A(i3811

Specifier: Designer: AJ

Company.

Misc:



Total Horizontal Product Length = 03-02-00

Reaction Summary (Down / Uplift) (lbs)									
Be aring	Live	De ad :	Snow	Win	ıd				
B0, 3-3/4"	77 / 0	194/0							
B1, 4"	78 / 0	196/0							
Load Summary				Live	Dead	Snow	Wind	Trib	
Tag Description	Load Type	Ref. Start	En d	1.00	0.65	1.00	1.15		
0 E1(i714)	Unf. Lin. (lb/ft)	L 00-00-00	03-02-00	28	101			n/a	

00-00-00 03-02-00 21

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	151 ft-lbs	25,173 ft-lbs	0.6%	0	01-06-14
End Shear	105 lbs	14,464 lbs	0.7%	1	01-10-02
Total Load Defl.	L/999 (0")	n/a	n/a	4	01-06-14
Live Load Defl.	L/999 (0")	n/a	n/a	5	01-06-14
Max Defl.	0"	n/a	n/a	4	01-06-14
Span / Depth	2.7	n/a	n/a		00-00-00

Unf. Lin. (lb/ft)

				De mand/	De mand/	
				Resistance	Resistance	
Bear	ring Supports	Dim. (L x W)	Demand	Support	Member	Material
B0	Wall/Plate	3-3/4" x 3-1/2"	271 lbs	6%	2.6%	Unspecified
B1	Wall/Plate	4" x 3-1/2"	275 lbs	5.7%	2.5%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA CONFORMS TO OBG 2012

O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

NOVINCE OF ONTRE

n/a



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP Basment\...\B1A(i3811)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

August 18, 2017 16:42:50

BC CALC® Design Report

*

D.::4.5000

Build 5033 Job Name: Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5 EL-2 WITH DECK.mmdl

Description: Designs\Flush Beams\Basment\Flush Beams\B1A(i38


Specifier:

Designer: AJ

Company.

Misc:

Connection Diagram



a minimum = 2" b minimum = 3"

c=7-7/8"6"

Member has no side loads.

Connectors are: 16d sin er Nails

3½" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone w ho w ould rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered w ood products must be in accordance w ith current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

S. KATSOULAKOS E

DWOND.TAM 4201 STRUCTURAL COMPONENT ONLY



Boise Cascade Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP Basment\Flush Beams\B1(i3000)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:29

BC CALC® Design Report

Build 5033 Job Name: Address:

City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5.mmdl

Description: Designs\Flush Beams\Basment\Flush Beams\B1(i3000)

Specifier:

Designer: AJ Company:

Misc:

2/	③ ✓	4/
		ZZ
⊠ B0	11-03-14	⊠ B1

Total Horizontal Product Length = 11-03-14

Reaction Summary (Down / Uplift) (lbs)										
Bearing	Live	De ad	Snow	Wind						
B0, 4"	1,272 / 0	730/0								
B1. 4-3/8"	1,059 / 0	640/0								

10	ad Summary					Live	Dead	Snow	Wind	Trib.
	g Description	Load Type	Re	f. Start	En d	1.00	0.65	1.00	1.15	
0	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	04-03-04	20	10	-		n/a
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	04-03-04	11-03-14	28	14			n/a
2	8(i789)	Conc. Pt. (lbs)	L	00-01-00	00-01-00	132	94			n/a
3	B3(i3001)	Conc. Pt. (lbs)	L	04-05-00	04-05-00	1,643	874			n/a
4	3(i767)	Conc. Pt. (lbs)	L	11-01-11	11-01-11	269	191			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	9,901 ft-lbs	19,364 ft-lbs	51.1%	1	04-05-00
End Shear	2,439 lbs	7,232 lbs	33.7%	1	01-03-14
Total Load Defl.	L/532 (0.242")	0.538"	45.1%	4	05-03-07
Live Load Defl.	L/826 (0.156")	0.358"	43.6%	5	05-03-07
Max Defl.	0.242"	n/a	n/a	4	05-03-07
Span / Depth	10.9	n/a	n/a		00-00-00

Beari	ng Supports	Dim . (L x W)	Demand	De mand/ Resistance Support	Resistance Member	Material
B0	Wall/Plate	4" x 1-3/4"	2,820 lbs	94.3%	33%	Un specified
B1	Wall/Plate	4-3/8" x 1-3/4"	2,389 lbs	73%	25.6%	Un specified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

CONFORMS TO OBC 2012



DWG NO. TAM 4281617 STRUCTURAL COMPONENT ONLY



Boise Cascade Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP Basment\Flush Beams\B2(i2986)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:33:20

BC CALC® Design Report

*

Build 5033 Job Name:

Addres s: City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5.mmdl

Description: Designs\Flush Beams\Basment\Flush Beams\B2(i2986)

Specifier:

Designer: AJ Company:

Misc:

2/	3	
	J J J Q J J J J J J J J J J J J J J J J	
B0	11-03-14	≊ ₹ B1

Total Horizontal Product Length = 11-03-14

Reaction Summary (Down / Uplift) (lbs)										
Be aring	Live	De ad	Snow	Wind						
B0,4"	1,537/0	891/0								
B1, 4-3/8"	783/0	446/0								

Lo	ad Summary					Live	Dead	Snow	Wind	Trib.
	g Description	Load Type	Re	f. Start	En d	1.00	0.65	1.00	1.15	
0	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	04-03-04	20	10			n/a
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	04-03-04	11-03-14	27	13			n/a
2	9(i791)	Conc. Pt. (lbs)	L	00-02-00	00-02-00	397	255			n/a
3	B3(i3001)	Conc. Pt. (lbs)	L	04-05-00	04-05-00	1,649	877			n/a

	Factored	Factored	Demand /	Load	Location	
Controls Summary	Dem and	Resistance	Resistance	Case		
Pos. Moment	9,902 ft-lbs	19,364 ft-lbs	51.1%	1	04-05-00	
End Shear	2,439 lbs	7,232 lbs	33.7%	1	01-03-14	
Total Load Defl.	L/533 (0.242")	0.538"	45%	4	05-03-07	
Live Load Defl.	L/827 (0.156")	0.358"	43.5%	5	05-03-07	
Max Defl.	0.242"	n/a	n/a	4	05-03-07	
Span / Depth	10.9	n/a	n/a		00-00-00	

			Demand/ Resistand		Demand/ Resistance		
Bear	ing Supports	Dim.(LxW)	Demand	Support	Member	Material	
B0	Wall/Plate	4" x 1-3/4"	3,4191bs	91.5%	40%	Unspecified	
B1	Wall/Plate	4-3/8" x 1-3/4"	1,731 lbs	42.3%	18.5%	Unspecified	

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA

O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SY STEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO.TAM YZELY 17 STRUCTURAL COMPONENT ONLY

CONFORMS TO OBG 2012



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP Basment

Basment\...\B3(i3001)--

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:30

Build 5033

Job Name: Address:

City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5.mmdl

Description: Designs\Flush Beams\Basment\Flush Beams\B3(i3001)

Specifier:

Designer: AJ Company:

Misc:

2/		3
В0	08-09-00	<u>—</u> В1

Total Horizontal Product Length = 08-09-00

Reaction Summary (Down / Uplift) (Ibs)								
Be aring	Live	De ad	Snow	Wind				
B0	1,643 / 0	874/0						
B1	1.649 / 0	877/0						

Lo	ad Summary					Live	Dead	Snow	Wind	Trib.
	g Description	Load Type	Ret	f. Start	En d	1.00	0.65	1.00	1.15	
0	Us er Load	Unf. Lin. (lb/ft)	L	00-00-00	08-09-00	240	120			n/a
1	Smoothed Load	Unf. Lin. (lb/ft)	L	01-01-00	07-09-00	141	70.			n/a
2	J6 (i2999)	Conc. Pt. (lbs)	L	00-05-00	00-05-00	129	64			n/a
3	J6(i2982)	Conc. Pt. (lbs)	L	08-05-00	08-05-00	123	61			n/a

De mand/

De mand/

	Factored	Factored	Demand /	Load	Location	
Controls Summary	Demand	Resistance	Resistance	Case		
Pos. Moment	7,527 ft-lbs	38,727 ft-lbs	19.4%	1	04-05-00	
End Shear	2,745 lbs	14,464 lbs	19%	1	01-01-14	
Total Load Deff.	L/999 (0.071")	n/a	n/a	4	04-05-00	
Live Load Defl.	L/999 (0.046")	n/a	n/a	5	04-05-00	
Max Defl.	0.071"	n/a	n/a	4	04-05-00	
Span / Depth	8.6	n/a	n/a		00-00-00	

Resistance Resistance **Bearing Supports** Dim. (L x W) Demand Support Member Material BO 2" x 3-1/2" 3,557 lbs Hanger 41.6% Hanger n/a **B1** 3,569 lbs Hanger 2" x 3-1/2" n/a 41.8% Hanger

Notes

Design meets Code minimum (L/240) Total load deflection criteria. Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA $\,$

O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO OBC 2012



DWG NO.TAM 4262217 STRUCTURAL COMPONENT ONLY



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP Basment\...\B3(i3001)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:30

BC CALC® Design Report

Build 5033 Job Name:

Address:

City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5.mmdl


Description: Designs\Flush Beams\Basment\Flush Beams\B3(i300

Specifier: Designer: AJ

Company:

Misc:

Connection Diagram



a minimum = 2" b minimum = 3" c = 7-7/8"

Calculated Side Load = 289.3 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d 3 Nails 3½ ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BCRIM BOARD™, BC/®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

> NOT OF ON THE DWG NO. TAN 4202017 STRUCTURAL

COMPONENT ONLY



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP Basment\...\B4(i3069)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:30

BC CALC® Design Report

*

Build 5033

Job Name: Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports:

CCMC 12472-R


File Name: ROSEWOOD 5.mmdl

Description: Designs\Flush Beams\Basment\Flush Beams\B4(i3069)

Specifier:

Designer: AJ Company:

Misc:



Total Horizontal Product Length = 07-08-12

Reaction Summary (Down / Uplift) (lbs)										
Bearing	Live	De ad	Snow	Wind						
B0, 3-1/2"	743/0	417/0								
B1, 5-1/2"	533/0	1,115/0								

Lo	ad Summary					Live	Dead	Snow	Wind	Trib.
	g Description **	Load Type	Re	f. Start	En d	1.00	0.65	1.00	1.15	
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-00-00	06-01-04	170	85			n/a
1	J6(i3088)	Conc. Pt. (lbs)	L	06-09-04	06-09-04	148	74			n/a
2	3(i767)	Conc. Pt. (lbs)	L	07-06-00	07-06-00	85	843			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,843 ft-lbs	38,727 ft-lbs	4.8%	1	04-01-04
End Shear	876 lbs	14,464 lbs	6.1%	1	01-03-06
Total Load Defl.	L/999 (0.012")	n/a	n/a	4	03-09-04
Live Load Defl.	L/999 (0.008")	n/a	n/a	5	03-09-04
Max Defl.	0.012"	n/a	n/a	4	03-09-04
Span / Depth	7.2	n/a	n/a		00-00-00

				De mand/	Demand/	
				Resistance	Resistance	
Bear	ring Supports	Dim.(LxW)	Demand	Support	Member	Material
В0	Post	3-1/2" x 3-1/2"	1,636 lbs	20.6%	10.9%	Unspecified
B1	Wall/Plate	5-1/2" x 3-1/2"	1,560 lbs	29.2%	10.2%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

CONFORMS TO OBC 2012

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

S. KATSOULAKOS E

STRUCTURAL COMPONENT ONLY



BC CALC® Design Report

Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP Basment\...\B4(i3069)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:30

Build 5033

Job Name:

Address:

City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5.mmdl


Description: Designs\Flush Beams\Basment\Flush Beams\B4(i306

Specifier:

Designer: AJ Company:

Misc:

Connection Diagram



a minimum = 2" b minimum = 3" c=7-7/8" d= 4 6

Calculated Side Load = 277.7 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d ₩ Nails

312" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone w ho w ould rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered w ood products must be in accordance w ith current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

S. KATSOULAKOS S

DWG ND. TAM 4282117

STRUCTURAL

COMPONENT ONLY



Boiso Cascado Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B5(i2972)

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:30

Build 5033

Job Name: Address:

City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\85(i2972)

Specifier:

Designer:

Company:

Misc:



Total Horizontal Product Length = 11-07-00

Reaction Summary (Down / Uplift) (lbs)									
Bearing	Live	De ad	Snow	Wind	•				
B0, 4"	586/0	358/0							
B1, 5-1/2"	468/0	290/0							

	ead Summary	Load Tons	5-			Live	Dead	Snow		Trib.
Ia	g bescription	Load Type	Ke'	f. Start	En d	1.00	0.65	1.00	1.15	
0	FC2 FloorMaterial	Unf. Lin. (lb/ft)	L	00-00-00	11-07-00	16	8			n/a
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	04-07-12	6	3			n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	04-07-12	11-07-00	8	4			n/a
3	B7 (i2917)	Conc. Pt. (lbs)	L	04-09-08	04-09-08	775	439			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	5,375 ft-lbs	19,364 ft-lbs	27.8%	1	04-09-08
End Shear	1,255 lbs	7,232 lbs	17.4%	1	01-03-14
Total Load Defl.	L/940 (0.139")	0.546"	25.5%	4	05-05-08
Live Load Defl.	L/999 (0.087")	n/a	n/a	5	05-05-08
Max Defl.	0.139"	n/a	n/a	4	05-05-08
Span / Depth	11	n/a	n/a		00-00-00

Beari	ing Supports	Dim . (L x W)	Demand	Resistance Support	Resistance Member	Material
B0	Wall/Plate	4" x 1-3/4"	1,327 lbs	44.4%	15.5%	Unspecified
B1	Wall/Plate	5-1/2" x 1-3/4"	1,064 lbs	25.9%	9.1%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria. Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86. CONFORMS TO OBC 2012

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered w ood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-RIM PLUS®, VERSA-RIM®,

VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood

Products L.L.C.





Boiso Cascado Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B6(i2944)

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:30

Build 5033

Job Name:

Address:

City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\86(i2944)

Specifier: Designer: AJ

Company:

Misc:

<u> </u>	
B0 11-05-00	⊠ B1

Total Horizontal Product Length = 11-05-00

Reaction Summary (Down / Uplift) (lbs)										
Bearing	Live	De ad	Snow	Wind						
B0,4"	875/0	502/0								
B1, 5-1/2"	651/0	381/0								

Lo	ad Summary					Live	Dead	Snow	Wind	Trib.
	g Description	Load Type	Re	f. Start	En d	1.00	0.65	1.00	1.15	
0	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	11-02-04	15	7			n/a
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	04-05-12	6	3			n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	04-05-12	11-02-04	12	6			n/a
3	B7(i2917)	Conc. Pt. (lbs)	L	04-07-08	04-07-08	1,256	680			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	7,907 ft-lbs	19,364 ft-lbs	40.8%	1	04-07-08
End Shear	1,873 lbs	7,232 lbs	25.9%	1	01-03-14
Total Load Defl.	L/661 (0.195")	0.538"	36.3%	4	05-05-08
Live Load Defl.	L/999 (0.125")	n/a	n/a	5	05-05-08
Max Defl.	0.195"	n/a	n/a	4	05-05-08
Span / Depth	10.9	n/a	n/a		00-00-00

				Demand/ Resistance	Demand/ Resistance	
Bear	ing Supports	Dim.(LxW)	De man d	Support	Member	Material
B0	Wall/Plate	4" x 1-3/4"	1,941 lbs	64.9%	22.7%	Unspecified
B1	Wall/Plate	5-1/2" x 1-3/4"	1,454 lbs	35.4%	12.4%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO OBC 2012

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered w ood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BCRIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood

Products L.L.C.

Disclosure



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B7(i2917)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:30

BC CALC® Design Report

Build 5033 Job Name:

Address: City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R


File Name: ROSEWOOD 5.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\87(i2917)

Specifier:

Designer: Company:

Misc:



Total Horizontal Product Length = 08-10-04

Reaction Summary (Down / Uplift) (lbs)							
Be aring	Live	De ad	Snow	Wind			
B0	769/0	437/0					
B1 .	1,262 / 0	683/0					

Lo	ad Summary					Live	Dead	Snow	Wind	Trib.
	g Description	Load Type	Re	f. Start	En d	1.00	0.65	1.00	1.15	
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-11-14	07-07-14	140	70			n/a
1	Us er Load	Unf. Lin. (lb/ft)	L	05-03-06	08-09-06	240	120			n/a
2	J4 (i2890)	Conc. Pt. (lbs)	L	00-03-14	00-03-14	120	60			n/a
3	J4 (i2956)	Conc. Pt. (lbs)	L	08-03-14	08-03-14	136	68			n/a

	Factored	Factored	Demand /	Load	Location
Controls Summary	Demand	Resistance	Resistance	Case	
Pos. Moment	4,628 ft-lbs	38,727 ft-lbs	12%	1	05-07-14
End Shear	1,993 lbs	14,464 lbs	13.8%	1	07-08-06
Total Load Defl.	L/999 (0.044")	n/a	n/a	4	04-06-12
Live Load Defl.	L/999 (0.028")	n/a	n/a	5	04-06-12
Max Defl.	0.044"	n/a	n/a	4	04-06-12
Span / Depth	8.7	n/a	n/a		00-00-00

				Demand/ Resistance	De mand/ Resistance	
Bear	ing Supports	Dim.(LxW)	Demand	Support	Member	Material
B0	Hanger	2" x 3-1/2"	1,700 lbs	n/a	19.9%	Hanger
B1	Hanger	2" x 3-1/2"	2,746 lbs	n/a	32.2%	Hanger

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO OBC 2012





Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B7(i2917)

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:30

Build 5033

Job Name: Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports: CCMC 12472-R File Name: ROSEWOOD 5.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B7(i291;

Specifier:

Designer: Company:

Misc:

Connection Diagram



a minimum = 2" b minimum = 3"

c = 7-7/8" d = 🚳

Calculated Side Load = 285.5 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d Nails
3½ ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

POLINICE OF ONLY DWGNO. TAN CHECKIT



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0.3100 SP. 1st Floor\...\B8 DR(i2681)

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:31

Build 5033

Job Name:

Address:

City, Province, Postal Code:WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: ROSEWOOD 5.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\88 D

Specifier:

Designer: AJ

Company.

Misc:

Ţ		
B0	08-06-00	B≊t B1

Total Horizontal Product Length = 08-06-00

Reaction Summary (Dow	n / Uplift) (lbs)	<u> </u>			
Be aring	Live	De ad	Snow	Wind	
B0, 4"	2,732/0	1,409/0		, , , , , , , , , , , , , , , , , , ,	
B1, 4"	2,620/0	1,353/0			

Load Summary				Live	Dead	Snow Wind	Trib.
Ta	g Description	Load Type	Ref. Start	En d 1.00	0.65	1.00 1.15	
0	Smoothed Load	Unf. Lin. (lb/ft)	L 00-02-00	08-02-00 669	335		n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	11,403 ft-lbs	25,408 ft-lbs	44.9%	1	04-08-00
End Shear	5,083 lbs	11,571 lbs	43.9%	1	07-04-08
Total Load Defl.	L/519 (0.184")	0.398"	46.2%	4	04-03-08
Live Load Defl.	L/999 (0.121")	n/a	n/a	5	04-03-08
Max Defl.	0.184"	n/a	n/a	4	04-03-08
Span / Depth	10.1	n/a	n/a		00-00-00

Beari	ng Supports	Dim . (L x W)	Demand	De mand/ Resistance Support	De mand/ Resistance Member	Material
B0	Wall/Plate	4" x 3-1/2"	5,860 lbs	64.4%	34.3%	Unspecified
B1	Wall/Plate	4" x 3-1/2"	5,621 lbs	61.8%	32.9%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume unbraced length of Top: 00-03-02, Bottom: 00-03-02.

Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA

O86.


Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO DBG 2012



DWO NO. TAM 4284517 STRUCTURAL COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B8 DR(i2681)

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 9, 2017 10:31:31

Build 5033

Job Name: Address:

City, Province, Postal Code: WATERDOWN.

Customer:

Code reports: CCMC 12472-R File Name: ROSEWOOD 5.mmdl


Description: Designs\Dropped Beams\1stFloor\Dropped Beams\B8

Specifier:

Designer: AJ Company.

Misc:

Connection Diagram



a minimum = 2" b minimum = 3"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record. Member has no side loads.

Connectors are: 16d Story Nails
3½ NARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BCRIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

CE OF ONLY

DWG NO TAM 42002 STRUCTURAL COMPONENT ONLY



Live Load = 40 psf, Dead Load = 15 psf Simple Spans, L/480 Deflection Limit 3/4" OSB G&N Sheathing







			В	are			1/2" Gyr	sum Ceiling	
Depth	Series		On Cent	re Spacing			On Cen	tre Spacing	
-		12"	16"	19.2"	24"	12"	16"	/ 19.2"	24"
	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"
	NI-40x	17'-0"	16'-0"	15'-5"	14'-9"	17'-5"	16'-5"	15'-10"	15'-2"
9-1/2"	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-6"	16'-7"	15'-11"	15'-3"
	N!-70	18'-0"	16'-11"	16'-3"	15'-7"	18'-5"	17'-3"	16'-7"	15'-11"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
	NI-20	17'-10"	16'-10"	16'-2"	15'-6"	18'-6"	17'-4"	16'-9"	16'-1"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-6"	19'-11"	18'-6"	17'-9"	17'-0"
44.7/08	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
11-7/8"	N!-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
	NI-90x	21' - 8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
141125	NI-40x	21'-5"	19'-10"	18'-11"	17'-11"	22'-1"	20'-6"	19'-7"	18'-7"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
14"	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23' - 8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22 '- 3"	21'-2"	20'-0"
	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
4.69	NI-70	25'-1"	23' - 2"	22'-0"	20'-10"	25 '- 9"	23'-10"	22'-9"	21'-6"
16"	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24' - 2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

			Mid-Spa	n Blocking		Mid-S	pan Blocking ar	nd 1/2" Gypsum	Ceiling
Depth	Series	-	On Cent	re Spacing			On Cent	re Spacing	
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"
	NI-40x	18'-8"	17'-2"	16'-3"	15'-2"	18'-10"	17'-2"	16'-3"	15'-2"
9-1/2"	NI-60	18'-11"	17'-6"	16'-6"	15'-5"	19'-2"	17'-6"	16'-6"	15'-5"
	NI-70	20'-0"	18'-7"	17'-9"	16'-7"	20'-5"	18'-11"	17'-10"	16'-7"
	NI-80	20'-3"	18'-10"	17'-11"	16'-10"	20'-8"	19'-3"	18'-2"	16'-10"
	NI-20	20'-1"	18'-5"	17'-5"	16'-2"	20'-1"	18'-5"	17'-5"	16'-2"
	NI-40x	21'-10"	20'-4"	19'-4"	17!-8"	22'-5"	20'-6"	19'-4"	17'-8"
!=!	NI-60	22'-1"	20'-7"	19'-7"	18'-4"	22'-8"	20'-10"	19'-8"	18'-4"
11-7/8"	NI-70	23'-4"	21'-8"	20'-8"	19'-7"	23'-10"	22'-3"	21'-2"	19'-9"
	NI-80	23'-7"	21'-11"	20'-11"	19'-9"	24'-1"	22'-6"	21'-5"	20'-0"
	NI-90x	24'-3"	22'-6"	21'-6"	20'-4"	24'-8"	23'-0"	22'-0"	20'-9"
	NI-40x	24'-5"	22'-9"	21'-8"	19'-5"	25'-1"	23'-2"	21'-9"	19'-5"
	NI-60	24'-10"	23'-1"	22'-0"	20'-10"	25'-6"	23'-8"	22'-4"	20'-10"
14"	NI-70	26'-1"	24'-3"	23' - 2"	21'-10"	26'-8"	24'-11"	23' -9 "	22'-4"
	NI-80	26'-6"	24'-7"	23 '- 5"	22'-2"	27'-1"	25 '- 3"	24'-1"	22'-9"
	NI-90x	27'-3"	25'-4"	24'-1"	22' - 9"	27'-9"	25'-11"	24'-8"	23'-4"
	NI-60	27'-3"	25'-5"	24'-2"	22'-10"	28'-0"	26'-2"	24'-9"	23'-1"
4.511	NI-70	28'-8"	26'-8"	25'-4"	23'-11"	29'-3"	27'-4"	26'-1"	24'-8"
16"	NI-80 .	29'-1"	27'-0"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
	NI-90x	29'-11"	27'-10"	26'-6"	25'-0"	30'-6"	28'-5"	27'-2"	25'-8"

^{1.} Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.

^{2.} Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.

^{3.} Minimum bearing length shall be 1-3/4 inches for the end bearings.

^{4.} Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.

^{5.} This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.

^{6.} Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



Live Load = 40 psf, Dead Load = 15 psf Simple Spans, L/480 Deflection Limit 5/8" OSB G&N Sheathing







			В	are			1/2" Gyp	sum Ceiling	
Depth	Series		On Cent	re Spacing			On Cent	re Spacing	
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	15'-1"	14'-2"	13'-9"	N/A	15'-7"	14'-8"	14'-2"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
9-1/2"	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
11-7/8"	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
11-//0	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
14"	N1-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
16"	NI-70	23'-6"	21' - 9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
10	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

			Mid-Spa	n Blocking		Mid-S	Span Blocking a	nd 1/2" Gypsum	Ceiling
Depth	Series		On Cent	re Spacing			On Cent	re Spacing	
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	16'-8"	15'-3"	14'-5"	N/A	16'-8"	15'-3"	14'-5"	N/A
	NI-40x	17'-11"	16'-11"	16'-1"	N/A	18'-5"	17'-1"	16'-1"	N/A
9-1/2"	NI-60	18'-2"	17'-1"	16'-4"	N/A	18'-7"	17'-4"	16'-4"	N/A
	NI-70	19'-2"	17'-10"	17'-2"	N/A	19'-7"	. 18'-3"	17'-7"	N/A
	NI-80	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
	NI-20	19'-6"	18'-1"	17'-3"	N/A	19'-11"	18'-3"	17'-3"	N/A
	NI-40x	21'-0"	19'-6"	18'-8"	N/A	21'-7"	20'-2"	19'-2"	N/A
44 7/08	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-6"	N/A
11-7/8"	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-11"	20'-11"	N/A	24'-3"	22'-7"	21'-7"	N/A
	NI-60	24'-0"	22' - 3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
14"	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-2"	N/A
16"	NI-70	27' -9 "	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
10	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

^{1.} Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.

^{2.} Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.

^{3.} Minimum bearing length shall be 1-3/4 inches for the end bearings.

^{4.} Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.

^{5.} This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.

^{6.} Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



Live Load = 40 psf, Dead Load = 30 psf Simple Spans, L/480 Deflection Limit 5/8" OSB G&N Sheathing







			8	Bare			1/2" Gyp	sum Ceiling	
Depth	Series		On Cent	re Spacing				re Spacing	
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	15'-1"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
9-1/2"	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
	Ni-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NJ-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
11-7/8"	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
11-7/6	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
	N!-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
14"	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	N!-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
16"	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
10	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

			Mid-Spa	ın Blocking		Mid-	Span Blocking ar	nd 1/2" Gypsum	n Ceiling
Depth	Series		On Cent	re Spacing			On Cent	re Spacing	
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	15'-7"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	17'-9"	16'-1"	15'-1"	N/A	17'-9"	16'-1"	15'-1"	N/A
9-1/2"	NI-60	18'-1"	16'-4"	15'-4"	N/A	18'-1"	16'-4"	15'-4"	N/A
	NI-70	19'-2"	17'-10"	16'-9"	N/A	19'-7"	17'-10"	16'-9"	N/A
	NI-80	19'-5"	18'-0"	17'-1"	N/A	19'-10"	18'-3"	17'-1"	N/A
	NI-20	18'-9"	17'-0"	16'-0"	N/A	18'-9"	17'-0"	16'-0"	N/A
	NI-40x	21'-0"	19'-3"	17'-9"	N/A	21'-3"	19'-3"	17'-9"	N/A
11-7/8"	NI-60	21'-4"	19'-8"	18'-5"	N/A	21'-8"	19'-8"	18'-5"	N/A
11-7/0	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-4"	20'-0"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-5"	N/A
	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-5"	19'-6"	N/A	24'-1"	21'-5"	19'-6"	N/A
	NI-60	24'-0"	22'-3"	21'-0"	N/A	24'-8"	22'-5"	21'-0"	N/A
14"	NI-70	25' - 3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-9"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	24'-10"	23'-4"	N/A
16"	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
10	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26' - 9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

^{1.} Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.

^{2.} Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.

3. Minimum bearing length shall be 1-3/4 inches for the end bearings.

^{4.} Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.

^{5.} This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.

^{6.} Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



Live Load = 40 psf, Dead Load = 30 psf Simple Spans, L/480 Deflection Limit 3/4" OSB G&N Sheathing







			В	are		ľ	1/2" Gyp	sum Ceiling	
Depth	Series		On Cent	re Spacing			On Cent	re Spacing	
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-0"	16'-0"	15'-1"	13'-11"	17'-5"	16'-1"	15'-1"	13'-11"
9-1/2"	N!-60	17'-2"	16'-2"	15'-5"	14'-3"	17'-6"	16'-5"	15'-5"	14'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-6"	18'-5"	17'-3"	16'-7"	15'-6"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'- 5"	16'-9"	15'-10"
	NI-20	17'-10"	16'-10"	16'-0"	14'-10"	18'-6"	17'-1"	16'-0"	14'-10"
	NI-40x	19'-4"	17'-11"	17'-3"	15'-10"	19'-11"	18'-6"	17'-9"	15'-10"
11-7/8"	N1-60	19'-7"	18'-2"	17' - 5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-1"
11-//0	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-5"	22'-1"	20'-6"	19'-6"	17'-5"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
14"	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20' -7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
16"	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
10	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26' - 4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

			Mid-Spa	n Blocking		Mid-9	pan Blocking ar	nd 1/2" Gypsum	Ceiling
Depth	Series		On Cent	re Spacing			On Cent	re Spacing	
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-9"	16'-1"	15'-1"	13'-11"	17'-9"	16'-1"	15'-1"	13'-11"
9-1/2"	NI-60	18'-1"	16'-5"	15'-5"	14'-3"	18'-1"	16'-5"	15'-5"	14'-3"
	NI-70	19'-10"	17'-11"	16'-9"	15'-6"	19'-10"	17'-11"	16'-9"	15'-6"
	NI-80	20'-2"	18'-3"	17'-1"	15'-10"	20'-2"	18'-3"	17'-1"	15'-10"
	NI-20	18'-10"	17'-1"	16'-0"	14'-10"	18'-10"	17'-1"	16'-0"	14'-10"
	NI-40x	21'-3"	19'-3"	17'-9"	15'-10"	21'-3"	19'-3"	17'-9"	15'-10"
11-7/8"	NI-60	21' -9 "	19'-8"	18'-5"	17'-1"	21'-9"	19'-8"	18'-5"	17'-1"
11-//0	NI-70	23'-4"	21'-5"	20'-1"	18'-6"	23'-8"	21'-5"	20'-1"	18'-6"
	NI-80	23'-7"	21'-10"	20'-5"	18'-11"	24'-1"	21'-10"	20'-5"	18'-11"
	NI-90x	24'-3"	22'-6"	21'-3"	19'-7"	24'-8"	22'-7"	21'-3"	19'-7"
	NI-40x	24'-2"	21'-5"	19'-6"	17'-5"	24'-2"	21'-5"	19'-6"	17'-5"
	NI-60	24'-9"	22'-5"	21'-0"	19'-6"	24'-9"	22'-5"	21'-0"	19'-6"
14"	NI-70	26'-1"	24'-3"	22'-9"	21'-0"	26'-8"	24'-3"	22'-9"	21'-0"
	NI-80	26'-6"	24'-7"	23'-3"	21'-6"	27'-1"	24'-10"	23' - 3"	21'-6"
	NI-90x	27'-3"	25'-4"	24'-1"	22'-4"	27'-9"	25'-10"	24'-3"	22'-4"
	NI-60	27'-3"	24'-11"	23'-5"	21'-7"	27'-6"	24'-11"	23'-5"	21'-7"
16"	NI-70	28'-8"	26'-8"	25'-3"	23'-4"	29'-3"	26'-11"	25'-3"	23'-4"
10	NI-80	29'-1"	27'-0"	25'-9"	23'-10"	29'-8"	27'-6"	25'-10"	23'-10"
	NI-90x	29'-11"	27'-10"	26'-6"	24'-10"	30'-6"	28'-5"	26'-11"	24'-10"

^{1.} Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.

^{2.} Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.


^{3.} Minimum bearing length shall be 1-3/4 inches for the end bearings.

^{4.} Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.

^{5.} This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.

^{6.} Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.

NSTALLATION GUIDE FOR RESIDENTIAL FLOORS ENGINEERED WOOD







Distributed by:

N-C301 / November 2014

SAFETY AND CONSTRUCTION PRECAUTIONS

WARNING



braced, or serious injuuntil fully fastened and Do not walk on I-joists ries can result



Once sheathed, do not over-stress I-joist with Never stack building unsheathed I-joists. materials over





concentrated loads from building materials. Never install a damaged I-joist.

braced and sheathed. Hoists are not stable until completely installed, and will not carry any load until fully


Avoid Accidents by Following these Important Guidelines:

- 1. Brace and nail each 1-joist as it is installed, using hangers, blocking panels, rim blocking will be required at the interior support. board, and/or cross-bridging at joist ends. When I-joists are applied continuous over interior supports and a load-bearing wall is planned at that location,
- 2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, to prevent l-joist rollover or buckling. temporary bracing, often called struts, or temporary sheathing must be applied
- Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and must be secured with a the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail bracing over at least two 1-joists.
- Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
- 3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bridging.
- 4. Install and fully nail permanent sheathing to each Lioist before placing loads on the floor system. Then, stack building materials over beams or walls only,

can result in serious accidents. Follow these installation guidelines carefully, Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required

STORAGE AND HANDLING GUIDELINES

- Bundle wrap can be slippery when wet. Avoid walking on wrapped
- Store, stack, and handle 1-joists vertically and level only.
- Always stack and handle I-joists in the upright position only.
- 4. Do not store I-joists in direct contact with the ground and/or flatwise Protect I-joists from weather, and use spacers to separate bundles.
- Bundled units should be kept intact until time of installation.
- 7. When handling I-joists with a crane on the job site, take a few to your work crew. simple precautions to prevent damage to the Ljoists and injury
- Pick 1-joists in bundles as shipped by the supplier.
- ■Orient the bundles so that the webs of the I-joists are vertical.
- Pick the bundles at the 5th points, using a spreader bar if necessary
- 8. Do not handle Lioists in a horizontal orientation.
- 9. NEVER USE OR TRY TO REPAIR A DAMAGED I-JOIST





MAXIMUM FLOOR SPANS

- . Maximum **clear** spans applicable to simple-span or or more of the adjacent span. For multiple-span applications, the end spans shall be 40% 1.25D. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of L/480. limit states are based on the factored loads of 1.50L + live load of 40 psf and dead load of 15 psf. The ultimate multiple-span residential floor construction with a design
- Spans are based on a composite floor with glued-nailed thickness of 5/8 inch for a joist spacing of 19.2 inches or less, or 3/4 inch for joist spacing of 24 inches, Adhesive shall meet the requirements given in CGBS-71.26 of gypsum and/or a row of blocking at mid-span. Standard. No concrete topping or bridging element was assumed. Increased spans may be achieved with the used oriented strand board (OSB) sheathing with a minimum
- Minimum bearing length shall be 1-3/4 inches for the end bearings, and 3-1/2 inches for the intermediate bearings.
- Bearing stiffeners are not required when I-joists are used required for hangers. with the spans and spacings given in this table, except as
- 5. This span chart is based on uniform loads. For applications be required based on the use of the design properties. with other than uniform loads, an engineering analysis may
- Tables are based on Limit States Design per CAN/CSA O86-09 Standard, and NBC 2010.
- 1 foot = 0.305 m

SIMPLE AND MULTIPLE SPANS MAXIMUM FLOOR SPANS FOR NORDIC I-JOISTS

	Depth Se			22									
) ist	Series 12"						70						24.5 24.5
Simple													22.80 23.80
spans	19.2	19-91	14-10	15:6°	15:5	167	17:65 17:10	-17-10:	18:1	19:50	19-91	20:95	21-5
	24"	13.5.			5 5 6 6	16:9		17.48	1912 1922 1	9.5	10.0E	20-10-	22.6
	12"	16.8	17:7) 18 14	2013	22 Sq.	22.2	2257 23-10°	21.3	24.7	26-0	2691
Multiple	Jn centre 16"	15.15			3	ij	2012	2030	2047		23-11		
spans	spacing 19.2"												
	24"	7.67	. U	6-10	1617	8		10.1	90 T	2116 2116	22:2	23.0	23.4

CCMC EVALUATION REPORT 13032-R

NORDIC I-JOIST SERIES

I-JOIST HANGERS

- Hangers shown illustrate the three to support I-joists. most commonly used metal hangers
- All nailing must meet the hanger manufacturer's recommendations.
- Hangers should be selected based maximum spans. and load capacity based on the on the joist depth, flange width
- Web stiffeners are required when the sides of the hangers do not laterally brace the top flange of the I-joist.










Face Mount

WEB STIFFENERS

RECOMMENDATIONS:

- A bearing stiffener is required in all engineered applications with factored the stiffener and the flange is at the top. Construction Guide (C101).The gap between l-joist properties table found of the *l-joist* reactions greater than shown in the
- support, the top flange. The gap between the A bearing stiffener is required when stiffener and flange is at the top. sides of the hanger do not extend up to, and the I-joist is supported in a hanger and the
- and the flange is at the bottom. by the code. The gap between the stiffener adjusted for other load durations as permitted tip and the support. These values are for cantilever, anywhere between the cantilever A load stiffener is required at locations standard term load duration, and may be between supports, or in the case of a than 2,370 lbs is applied to the top flange where a tactored concentrated load greater
- SI units conversion: 1 inch = 25.4 mm

WEB STIFFENER INSTALLATION DETAILS



	ایو _
Chantiers	33 pieces per unit
Chibougar	33 pieces per unit
nav Ltd. h	33 pieces per unit
Chantiers Chibougamau Ltd. harvests its own trees, which enables Nordic	23 pieces per unit
n trees, which	23 pieces per unit
ch enables !	23 pieces per unit
Newlic	23 pieces per unit

S-P-F No.2

1950f MSR 2100f MSR 1950f MSR 2100f MSR

2400f MSR

NPG Lumber

Nordic Engineered Wood I-joists use only finger-jointed back spries with fumber in their flanges, ensuring consistent quality, superior strength strength. longer span carrying capacity. finished product, reflects our commitment to quality.

manufacturing process. Every phase of the operation, from forest to the products to adhere to strict quality control procedures throughout the action of the strict quality control procedures throughout the strict quality control procedures the strict quality control procedures throughout the strict quality control procedures the strict quality control procedures throughout the strict quality control procedure through the strict quality control procedure through the strict quality control procedure through the stri

2015-04-1

INSTALLING NORDIC I-JOISTS

- 1. Before laying out floor system components, verify that I-joist flange widths match hanger widths. If not, copied your
- 2. Except for cutting to length, I-joist flanges should never be cut, drilled, or notched
- 3. Install L-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
- 4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple

Span Joiste must

- 5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings 150 イラーロネート
- 6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement
- 7. Leave a 1/16-inch gap between the I-joist end and a header.
- . Concentrated loads greater than those that can normally be expected in residential construction should only be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment and security cameras. Never suspend unusual or heavy loads from the I-joist's bottom flange. Whenever possible, suspend all concentrated loads from the top of the I-joist. Or, attach the load to blocking that has been securely fastened to the
- 9. Never install Lioists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
- 10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or Ljoist blocking panels.
- 11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (cripple members) to transfer gravity loads through the floor system to the wall or foundation below.
- 12. Due to shrinkage, common framing lumber set on edge **may never** be used as blocking or rim boards. I-joist blocking i-joist-compatible depth selected. panels or other engineered wood products – such as rim board – must be cut to fit between the I-joists, and an
- 13. Provide permanent lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly, support the bottom flange of all cantilevered I-joists at the end support next to the cantilever extension. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used
- 14. If square-edge panels are used, edges must be supported between 1-joists with 2x4 blocking. Glue panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed
- 15. Nail spacing: Space nails installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.

One 2-1/2"


Attach rim board to top

(3)


one nail at top and bottom. Nail Attach rim joist to floor joist with

FIGURE 1

TYPICAL NORDIC I-JOIST FLOOR FRAMING AND CONSTRUCTION DETAILS




All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.



It shall not be used in the design of a bending member such as joist, header, or ratter. For concentrated vertical ınches or less and is based on standard term load duration load transfer, see detail 1d. *The uniform vertical load is limited to a joist depth of 16

ZI Joists

3,300




rafter. For concentrated vertical load transfer, see detail 1d
used in the design of a bending member, such as joist, header, or
or less and is based on standard term load duration. It shall not be
*The uniform vertical load is limited to a rim board depth of 16 inches

1-1/8" Rim Board Plus

Maximum Factored Uniform Vertical Load* (plf)


8,090




Squash block -	ā
	NI or rim board blocking panel per detail 1a
	1/16" for squash blocks

6,600	4,300	1-1/8" Rim Board Plus
8,500	5,500	2x Lumber
5-1/2" wide	3-1/2" wide	
Maximum Factored Vertical per Pair of Squash Blocks (lbs)	Maximum Factored Vertical p Pair of Squash Blocks (lbs)	Pair of Squash Blocks


Provide lateral bracing per detail 1a, 1b, or 1c



to post above. bearing below. Install squash blocks per detail 1d. Match bearing area of blocks below Transfer load from above to



carried to the foundation. required when rim board is used. Bracing per code shall be Rim board may be used in lieu of I-joists. Backer is not




Double I-joist header

backer block will fit. Clinch. Install backer tight to top flange. Use twelve 3" nails, clinched when possible. Maximum factored additional 3" nails through the webs and filler block where the Before installing a backer block to a double I-joist, drive three

resistance for hanger for this detail = 1,620 lbs.

 $\overline{\Xi}$

Backer block (use if hanger load exceeds 360 lbs)



(F)

2x plate flush with

allowed past inside ace of wall or beam.

installed per manufacturer's

beams, see the manutacturer's For nailing schedules for multiple

recommendations.


support the top flange, bearing Note: Unless hanger sides laterally stiffeners shall be used

> support the top flange, bearing Note: Unless hanger sides laterally

stiffeners shall be used

Top-mount hanger installed per .

manutacturer's recommendations



Multiple 1-joist header with full depth headers may also be used. Verify double 1-joist capacity to support

at bearing for lateral Note: Blocking required for clarity support, not shown

l-joist per detail 1b

Attach

(3) - NI blocking panel per detail 1a hanger per detail 1p Filler block Top- or face-mount

> Note: Unless hanges

2019-04-16

hangers)

(both sides for face-mount Backer block required

For hanger capacity see hanger manufacturer's recommendations. Verify double I-joist capacity to support concentrated loads.

Do not bevel-cut face of wall joist beyond inside

BACKER BLOCKS (Blocks must be long enough to permit required nailing without splitting)

3-1/2"	2-1/2"	Flange Width
1-1/2"	1"	Material Thickness Required*
7-1/4"	5-1/2"	Minimum Depth**

- better for solid sawn lumber and wood structural panels conforming to CAN/CSA-O325 or CAN/CSA-O437 Standard. Minimum grade for backer block material shall be S-P-F No. 2 or
- ** For face-mount hangers use net joist depth minus 3-1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4"

(

Filler block

- Leave a 1/8 to 1/4-inch gap between top prevent damage to web/flange connection. of tiller block and bottom of top I-joist
- μ Filler block is required between joists for full length of span.
- Nail joists together with two rows of 3" are required. can be clinched, only two nails per foot nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist Total of four nails per foot required. If nail

 Offset nails from opposite face by 6"

—1/8" to 1/4" gap between top flange and filler block The maximum factored load that may be using this detail is 860 lbf/ft. Verify double applied to one side of the double joist

Support back of I-joist web during nailing to DOUBLE 1-JOIST CONSTRUCTION FILLER BLOCK REQUIREMENTS FOR


Maximum support capacity = 1,620 lbs

clinch when possible.

	Flange Size	Joist Depth	Filler Block Size
	٠ ، ر ١ (١)	9-1/2"	2-1/8"×6"
	2-1/2"×	11-7/8"	2-1/8" x 8"
	1-1/2"	14"	2-1/8" x 10"
		16"	2-1/8" x 12"
		9-1/2"	3" × 6"
+	3-1/2"×	11-7/8"	သူ × ထူ
, 	1-1/2"	14.	3" × 10"
i		16"	3" x 12"
	3-1/2" \	11-7/8"	3" x 7"
	٠ <u>٠</u>	14.	3" x 9"
	١	16"	ယူ ×]]

strap applied to underside of joist at blocking (= Optional: Minimum 1x4 inch nails from each web to lumber piece, Lumber 2x4 min. opposite side. of adjacent web. extend block to face alternate on Two 2-1/2" spiral NI blocking


line or 1/2 inch minimum gypsum ceiling attached to underside of joists



In some local codes, blocking is prescriptively required in the first joist space (or first and second joist space) next to the starter joist. Where required, see local code requirements for spacing of the blocking

All nails are common spiral in this detail

CANTILEVER DETAILS FOR BALCONIES (NO WALL LOAD)






Full depth backer block with 1/8° gap between block and top flange of Lipist. See defail 1h. Nail with 2 rows of 3° nails at 6° o.c. and clinch.

Attach I-joists to plate at all supports per detail 1b

2x8 min. Nail to backer block and joist with 2 rows of -3" nails at 6" o.c. and clinch. (Contilever nails may be used to attach backer block if length of nail is sufficient to allow clinching.)


Cantilever extension supporting uniform floor loads only

cantilevers supporting a maximum specified uniform live load of 60 psf. Note: This detail is applicable to




CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)







Use nailing pattern shown for Method 1 with opposite face nailing offset by 3".

Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4) required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced L-joist capacity.



reinforcement requirements at cantilever. FIGURE 4 (continued) below for NI See table Roof truss span -maximum cantilever 21-0





For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to

be used.

CANTILEVER REINFORCEMENT METHODS ALLOWED

<u>;</u>		11778 11778 1378		JOIST DEPTH (in.)
\$\$ ## # ####	6 0 2 4 2 3 8 4 8 8 2 4 2 3 8	78823986 88823986	6 23 3 8 6 23 8 8 8	ROOF TRUSS SPAN (#)
ZZZZZZZZ	2272272	2	22722	IL = JC 12
	2277222	2222222 241	27	30 psf, D DIST SPAC 16
**************************************	222222			15 ps (in.) 2
	2			~
)OF LOADI IL = 40 ₁ JOIST :
**************************************			×××2000	ing (UNF, psf, DL = SPACING 5 19.2
36 2 <u>- 2</u>	NN	XXX0000		ACTORED 15 psf (in.) ? 24
7-727-72	2722222	2222227	22	.
2,222,242,2 2,222,242,2	-27777			= 50 psf, OIST SPA(
===== = = = ==========================	3-13-1-2 2-13-1-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-2 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-13-1-3 3-1	×000022		DL = 15 p CING (in.) 19.2
100002222	Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z	*******	4,774	bsf 2.4

- 1. N = No reinforcement required.
 1 = NI reinforced with 3/4 wood structural ponel on one side only.
 2 = NI reinforced with 3/4 wood structural ponel on one side only.
 2 = NI reinforced with 3/4 wood structural ponel on both idea; or double I-joist, ponel on both idea; or double I-joist, X = Try a deeper joist or closer spacing.
 2. Maximum design load shall be: 15 psf roof deed load; 35 psf floor thort load; and 80 pff well load. Well load is based on 3.0 pff well load.

Block Hoists together with filler blocks for the full length of the reinforcement. For Hoist flunge widths greater than 3 inches place an additional row of 3" nails along the

centreline of the reinforcing panel from each side. Clinch when possible.

- For larger openings, or multiple 3-0° width openings spaced less than 6-0° o.c., additional joists beneath the opening's cripple studs may be required.

 3. Table applies to joists 12° to 24° o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12° o.c. requirements for lesser spacing.
 - 4. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a
- truss is used.

 5. Cantilevered joists supporting girder trusses or roof beams may require additional

RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

- The distance between the inside edge of the support and the centreline of any Table 1 or 2, respectively. hole or duct chase opening shall be in compliance with the requirements of
- I-joist top and bottom flanges must NEVER be cut, notched, or otherwise modified
- Whenever possible, field-cut holes should be centred on the middle of the web.
- 4. The maximum size hole or the maximum depth of a duct chase opening that can between the top or bottom of the hole or opening and the adjacent I-joist flange. the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained be cut into an I-joist web shall equal the clear distance between the flanges of
- The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
- 6 Where more than one hole is necessary, the distance between adjacent hole opening shall be sized and located in compliance with the requirements of size of the largest square hole (or twice the length of the langest side of the langest rectangular hole or duct chase opening) and each hole and duct chase edges shall exceed twice the diameter of the largest round hole or twice the ables 1 and 2, respectively
- 7. A knockout is **not** considered a hole, may be utilized anywhere it occurs, and and/or duct chase openings. may be ignored for purposes of calculating minimum distances between holes
- œ Holes measuring 1-1/2 inches or smaller shall be permitted anywhere in a camilevered section of a joist. Holes of greater size may be permitted subject to
- 9. A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
- 11. Limit three maximum size holes per span, of which one may be a duct chase 10. All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7
- 12. A group of round holes at approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

LOCATION OF CIRCULAR HOLES IN JOIST WEBS

Joist

Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf

Minimum distance from inside face of any support to centre of hole (ft-in.)

-		r (t				
Above					1	
è ₫				C.		F .
声		Since 4.				
ž						Se
S	6666			deleje je	i de la	
&						
¥ <u>¥</u>						2
ž.	e e e e	lar	a 0 5 i	i Siste je	(eloto) v	
<u>.</u>	9 9 9 7 9 1					ω
Ĕ 오.	SON.		ile e s	, 1947)	4.	4
24						
}	252					5
ŝ						
2				9,995		0
3	300,000	10.00		rivia:		<u>-</u>
7						80
	17					nd 7
		No. 25 comments				
		idis.				8 d
	1,1000	i i e e i		=(===0)		mei
		14,11			O Harris	67 67 8
-						in.)
ı						
						10
1				1		
				rar dala		0-3/4
į			11 11 12		ellerer i	
- 13						
						12
and Comme						∅
1000	by it.	Hilifa			listatsi.	12-3/4
NUMBER.						<u></u>
26,004				i j Presis		octo restu
AND DESCRIPTIONS						Tent

- Note that may be used for rolar spacing or 24 inches on centre or less.
 Hole location distance is measured from inside face of supports to centre of hole
 Distances in this chart are based on uniformly loaded joists.

OPTIONAL:

The above table is based on the I-joists used at their maximum span. If the I-joists are placed at less than their full maximum span (see Maximum Fibrat Spans). The minimum distance from the centreline of the hole to the face of any support (D) as given above may be reduced as follows:

Where: Dreduced = <u>Factual</u> x D Dreduced

짇볹 Factual

Distance from the inside face of any support to centre of hole, reduced for less-than-maximum span applications shall not be less than 6 inches from the face of the support to edge of the hole.

The actual measured span distance between the inside faces of supports (ft).

awns (fit). The jedi

150A

ᇬ

Span Adjustment Factor given in this table.

The minimum distance from the inside face of any support to centre of hole from this table

If <u>tactual</u> is greater than 1, use 1 in the above calculation for <u>tactual</u> SAF

spaced 15 inches on centre along the length of the I-joist. Where possible, it is preterable to use knockouts instead of for the contractor's convenience to install electrical or small plumbing lines. They Knockouts are prescored holes provided /2 inches in diameter, and are

bearing

distance from for minimum See Table 1

 2x diameter of larger hole

2x duct chase

Duct chase opening (see Table 2 for

are 1-

from bearing) minimum distance

field-cut holes

diameter, length or hole whichever is

FIELD-CUT HOLE LOCATOR

FIGURE 7



Y

over-cut the web **Never** drill, cut or notch the flange, or

sharp saw. should be cut with a Holes in webs

the corners is recommended. Starting the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to stress concentrations. Slightly rounding the corners, as this can cause unnecessary For rectangular holes, avoid over-cutting ninimize damage to the I-joist

and may be ignored for purposes of calculating minimum distances A knockout is **NOT** considered a hole, may be utilized wherever it occurs

between holes

Knockouts

See rule 12


all duct chase openings and holes between top and bottom flange — Maintain minimum 1/8" space

DUCT CHASE OPENING SIZES AND LOCATIONS - Simple Span Only

	ORDICERA	m distanc	e from ir	nside tacı	e of any s	inpodus	o centre o	of openia	ng (ft-in.)
Depth Series				Duct ch	nase leng	gth (in.)			
	œ	10	12	14	16	18	20	22	24
					15-15		No Color		A STATE OF THE STA
				i de			7.00		
	.1.13			7.0	11.1	10		8131	9.90
				ı,			i i		
	A MATERIAL PROPERTY.	200	見るのない	RIGHT.					
	なした		1				0	1	
Marie State Control of the Control o					10.00	154			
		1	, ,	T.	į	K. F			
	- 1 - 1 - 1		1	j		· ·			
	A CONTRACTOR	Feb.							
	1117	1: -	K				6.C	0.7	語の対象
			4		=).				
	i.		i i			1			
			ķ					77.7	1257
			受害 なび 長屋						
	0.13	0.5							
		162							
					1276		111-6		
	The second second	Company of the Company	ACCORDING TO SHARE	TO SHAPE AND ADDRESS.	WATER POPULATION AND	権が大力を		Section And Section	

- 1. Above table may be used for Lioist spacing of 24 inches on centre or less.
 2. Dud chase opening location distance is measured from inside tace of supports to centre of opening.
 3. The above table is based on simple-span joists only. For other applications, contact your local distributor.
 4. Distances are based on uniformly located floor joists that meet the span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. For other applications, contact your local distributor

BRICK CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)




E D SET-BACK DETAIL

Bearing walls

structural panel closure (3/4" minimum thickness), attach per detail 1b. Rim board or wood

- between joists over support Provide full depth blocking (not shown for clarity
- supports per detail 1b. 3-1/2" minimum I-joist Attach I-joist to plate at all




(F) SET-BACK CONNECTION

through joist web and web of girder using 2-1/2" nails. Alternate for opposite side. (2x6 S-P-F No. 2 or better) nailed Vertical solid sawn blocks



Notes:



- N = No reinforcement required.
 1 = NI reinforced with 3/4" wood structural panel on one side only.
- 2 = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
- Maximum design load shall be: 15 psf roof dead load, 55 psf floor total load, and 80 plf X = Try a deeper joist or closer spacing. wall load. Wall load is based on 3'-0"

FIGURE 5 (continued) cantilever. requirements at reinforcement See table below for NI BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED ROOF TRUSS SPAN (ff) Roof truss _ 12 LL = 30 psf, DL = 15 psf JOIST SPACING (in.) 16 7 2'-0" -maximum -5" maximum cantilever 19.2 Girder J Roof trusses -24 ROOF LOADING (UNFACTORED) 12 LL = 40 psf, DL = 15 psf

JOIST SPACING (in.)

24

12

16

19.2

LL = 50 psf, DL = 15 psf JOIST SPACING (in.)

Roof trussspan

maximum cantilever <u>ي</u> ام

requirements for a span of 26 ft. shall be permitted to the I-joist reinforcement the cantilevered floor joists,

5" maximum

be used.

<u></u> 13′-0" тахітит

For hip roofs with the jack trusses running parallel to

Jack trusses

- additional joists beneath the opening's cripple For larger openings, or multiple 3'-0" width openings spaced less than 6'-0" o.c., studs may be required.
- μ Table applies to joists 12" to 24" o.c. that meet load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use the floor span requirements for a design live 12" o.c. requirements for lesser spacing.
 - 4. For conventional roof construction using a above is equivalent to the distance between the supporting wall and the ridge beam. ridge beam, the Roof Truss Span column
- Cantilevered joists supporting girder trusses or oot beams may require additional reinforcing

truss is used.

the Roof Truss Span is equivalent to the When the roof is framed using a ridge board,

distance between the supporting walls as if a

INSTALLING THE GLUED FLOOR SYSTEM

- 1. Wipe any mud, dirt, water, or ice from Ljoist flanges before gluing.
- 2. Snap a chalk line across the I-joists four feet in from the wall for panel edge alignment and as a boundary for spreading glue.
- 3. Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from
- Lay the first panel with tongue side to the wall, and nail in place. This protects the tongue of the next panel from damage when tapped into place with a block and sledgehammer.
- 5. Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-joist. Apply glue in a winding pattern on wide areas, such as with double I-joists.
- 6. Apply two lines of glue on I-joists where panel ends butt to assure proper gluing of each end
- 7. After the first row of panels is in place, spread glue in the groove of one or two panels at a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying a thinner line (1/8 inch) than used on I-joist flanges.
- 8. Tap the second row of panels into place, using a block to protect groove edges.
- Stagger end joints in each succeeding row of panels. A 1/8-inch space between all end joints and nail to assure accurate and consistent spacing.) 1/8-inch at all edges, including T&G edges, is recommended. (Use a spacer tool or an 2-1/2" common
- 10. Complete all nailing of each panel before glue sets. Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 2" ring- or screw-shank nails for panels 3/4-inch thick or less, and 2-1/2" ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for diaphragm construction. The finished deck can be walked on right away and will carry construction loads without damage to the

FASTENERS FOR SHEATHING AND SUBFLOORING(1)

24 3/4	. 5/8	16 5/8	Maximum Minimum Joist Panel Spacing Thickness (in.) (in.)
2	2	2	Common Wire or Spiral Nails
1-3/4"	1-3/4"	1-3/4"	ail Size and Ty Ring Thread Nails or Screws
2"	2"	2"	/pe Staples
6"	6ª	6,	Maximun of Fas Edges
12"	12"	12"	n Spacing steners Intern, Supports

- 1. Fasteners of sheathing and subflooring shall conform to the above table.
- Staples shall not be less than 1/16-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
- 3. Flooring screws shall not be less than 1/8-inch in diameter.
- 4. Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
- 5. Use only adhesives conforming to CAN/CGSB-71.26 Standard, Adhesives for Field-Gluing Plywood Lumber Framing for Floor System, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues; check with

Ref.: NRC-CNRC, National Building Code of Canada 2010, Table 9.23.3.5.


IMPORTANT NOTE:


Floor sheathing must be field glued to the I-joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-joist spans must be verified with your local distributor.

RIM BOARD INSTALLATION DETAILS


(8a) ATTACHMENT DETAILS WHERE RIM BOARDS ABUT









(B) TOE-NAIL CONNECTION AT RIM BOARD




(F) 2X LEDGER TO RIM BOARD ATTACHMENT DETAIL

Rim board joint-








MICRO CITY

Engineering services inc.

TEL: (519) 287 - 2242

R.R. #1, P.O. BOX 61, GLENCOE, ONTARIO, NOL 1MO

	LVL HEADER AND CONVENTIONAL					
	LVLHEAL	SER NAILING I	IVENTIONAL DETAILS			
	DETAIL NUMBER	NUMBER OF ROWS	SPACING (INCHES o/c)			
	A	2.	12			
	В	2	8			
	С	2	6			
	D	2	4			
	1A	3	12			
	1B	3	8			
	1C	3	. 6			
	1D	3	4			
- 1	2A	4	12			
	2B	4	8 ·			
	. 2C	4	6			
	2D	4	4			
1	3A	5	12			
L	3B	5	8			
L	3C	5	. 6			
L	3D	5	4			
L	4A	6	12			
Ŀ	4B	6	8			
Ŀ	4C	6	6			
L	4D	6	4			



NOTES:

- (1) MINIMUM LUMBER EDGE DISTANCE "a" = 1"
- (2) MINIMUM LUMBER END DISTANCE "b" = 2"
- (3) MINIMUM NAIL ROW SPACING "c" = 2"
- (4) STAGGER NAILS "d/2" BETWEEN PLIES FOR MULTI-PLY MEMBERS (3 PLY OR MORE)
- (5) ALL NAILS ARE 3-1/2" ARDOX SPIRAL NAILS
- (6) DO NOT USE AIR-DRIVEN NAILS



DNG NO TÄMNIOOI. 14

STRUGTURAL

GOMPONENT DNLY

TO BE USED ONLY

WITH BEAM CALCS

BEARING THE

STAMP BELOWS

PROVICE NATLING DETAIL № ×/SEE DWG #TAMN1001-14