

FROM PLAN DATED: APRIL 2017

BUILDER: GREENPARK HOMES

SITE: RUSSELL GARDENS

MODEL: HIGHGROVE 12

ELEVATION: 1,2

LOT:

CITY: WATERDOWN

SALESMAN: M D

DESIGNER: AJ

REVISION:

NOTES:

REFER TO THE NORDIC
INSTALLATION GUIDE FOR PROPER
STORAGE AND INSTALLATION.
SQUASH BLOCKS OF 2x4, 2x6, 2x8 #2
S.P.F REQ'D UNDER INTERIOR
UNIFORM LOAD BEARING WALLS.
MULTIPLE SQUASH BLOCKS REQ'D
UNDER CONCENTRATED LOADS. SEE
FIGURE 1. CANTILEVERED JOISTS
INCLUDING CANT' OVER BRICK REQ.
I-JOIST BLOCKING ALONG BEARING
AND RIMBOARD CLOSURE AT ENDS.
SEE FIGURES 4 & 5 FOR
REINFORCEMENT REQUIREMENTS.
FOR HOLES INCLUDING DUCT
CHASE AND FIELD CUT OPENINGS
SEE FIGURE 7, TABLES 1 & 2.
CERAMIC TILE APPLICATION AS PER
O.B.C 9.30.6.

LOADING:

DESIGN LOADS: L/480.000

LIVE LOAD: 40.0 lb/ft²


DEAD LOAD: 15.0 lb/ft

TILED AREAS: 20 lb/ft

SUBFLOOR: 3/4" GLUED AND NAILED


DATE: 9/18/2017

1st FLOOR




Products				
PlotID	Length	Product	Plies	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	18
J2	14-00-00	9 1/2" NI-40x	1	20
J3	12-00-00	9 1/2" NI-40x	1	12
J3DJ	12-00-00	9 1/2" NI-40x	2	4
J4	10-00-00	9 1/2" NI-40x	1	2
J5	4-00-00	9 1/2" NI-40x	1	1
J6	2-00-00	9 1/2" NI-40x	1	4
B7	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B1	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B8	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2

Connector Summary		
Qty	Manuf	Product
9	H1	IUS2.56/9.5
2	H1	IUS2.56/9.5
6	H1	IUS2.56/9.5
1	H2	HGUS410



Products				
PlotID	Length	Product	Plies	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	18
J2	14-00-00	9 1/2" NI-40x	1	20
J3	12-00-00	9 1/2" NI-40x	1	12
J3DJ	12-00-00	9 1/2" NI-40x	2	4
J4	10-00-00	9 1/2" NI-40x	1	2
J5	4-00-00	9 1/2" NI-40x	1	1
J6	2-00-00	9 1/2" NI-40x	1	2
B7	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B1	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B1A	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B8	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2

Connector Summary		
Qty	Manuf	Product
9	H1	IUS2.56/9.5
2	H1	IUS2.56/9.5
4	H1	IUS2.56/9.5
1	H2	HGUS410



FROM PLAN DATED: APRIL 2017

BUILDER: GREENPARK HOMES

SITE: RUSSELL GARDENS

MODEL: HIGHGROVE 12

ELEVATION: 1,2

LOT:

CITY: WATERDOWN

SALESMAN: M D

DESIGNER: AJ

REVISION:

NOTES:
REFER TO THE NORDIC
INSTALLATION GUIDE FOR PROPER
STORAGE AND INSTALLATION.
SQUASH BLOCKS OF 2x4, 2x6, 2x8 #2
S.P.F REQ'D UNDER INTERIOR
UNIFORM LOAD BEARING WALLS.
MULTIPLE SQUASH BLOCKS REQ'D
UNDER CONCENTRATED LOADS. SEE
FIGURE 1. CANTILEVERED JOISTS
INCLUDING CANT' OVER BRICK REQ.
I-JOIST BLOCKING ALONG BEARING
AND RIMBOARD CLOSURE AT ENDS.
SEE FIGURES 4 & 5 FOR
REINFORCEMENT REQUIREMENTS.
FOR HOLES INCLUDING DUCT
CHASE AND FIELD CUT OPENINGS
SEE FIGURE 7, TABLES 1 & 2.
CERAMIC TILE APPLICATION AS PER
O.B.C 9.30.6.

LOADING:

DESIGN LOADS: L/480.000

LIVE LOAD: 40.0 lb/ft²

DEAD LOAD: 15.0 lb/ft

TILED AREAS: 20 lb/ft

SUBFLOOR: 3/4" GLUED AND NAILED

DATE: 9/18/2017

1st FLOOR

W.O.D

FROM PLAN DATED: APRIL 2017

BUILDER: GREENPARK HOMES

SITE: RUSSELL GARDENS

MODEL: HIGHGROVE 12

ELEVATION: 1,2

LOT:

CITY: WATERDOWN

SALESMAN: M D

DESIGNER: AJ

REVISION:


NOTES:
REFER TO THE NORDIC INSTALLATION GUIDE FOR PROPER STORAGE AND INSTALLATION. **SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7 TABLES 1 & 2 OF THE INSTALLATION GUIDE. **CERAMIC TILE** APPLICATION AS PER O.B.C. 9.30.6

LOADING:
DESIGN LOADS: L/480.000
LIVE LOAD: 40.0 lb/ft²
DEAD LOAD: 15.0 lb/ft²
TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 2018-02-08

2nd FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	16-00-00	9 1/2" NI-40x	1	12
J2	14-00-00	9 1/2" NI-40x	1	35
J3	12-00-00	9 1/2" NI-40x	1	31
B9	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B3 DR	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	3	3
B6	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B4 DR	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2

Connector Summary		
Qty	Manuf	Product
7	H1	IUS2.56/9.5

NORDIC STRUCTURES

COMPANY
TAMARACK LUMBER
BURLINGTON
Feb. 8, 2018 07:35


PROJECT
J2 GRD FLR

Design Check Calculation Sheet Nordic Sizer – Canada 6.4

Loads:

Load	Type	Distribution	Pat-tern	Location [ft] Start End	Magnitude Start End	Unit
Load1	Dead	Full Area			20.00	psf
Load2	Live	Full Area			40.00	psf

Maximum Reactions (lbs), Bearing Resistances (lbs) and Bearing Lengths (in) :




Unfactored:			
Dead	173		174
Live	346		348
Factored:			
Total	736		740
Bearing:			
Resistance			
Joist	1854		1861
Support	-		3471
Des ratio			
Joist	0.40		0.40
Support	-		0.21
Load case	#2		#2
Length	1-3/4*		2-1/8
Min req'd	1-3/4		1-3/4
Stiffener	No		No
Kd	1.00		1.00
KB support	-		1.00
fcp sup	-		769
Kzcp sup	-		1.06

*Minimum bearing length for joists is 1-3/4" for exterior supports

Nordic 9-1/2" NI-40x Floor joist @ 16" o.c.
Supports: 1 - Steel Beam, W; 2 - Lumber Sill plate, No.1/No.2;
Total length: 13'-0.3"; 3/4" nailed and glued OSB sheathing
This section PASSES the design code check.

Limit States Design using CSA O86-14 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 728	Vr = 1895	lbs	Vf/Vr = 0.38
Moment (+)	Mf = 2338	Mr = 4824	lbs-ft	Mf/Mr = 0.48
Perm. Defl'n	0.07 = <L/999	0.43 = L/360	in	0.16
Live Defl'n	0.14 = <L/999	0.32 = L/480	in	0.44
Total Defl'n	0.21 = L/734	0.64 = L/240	in	0.33
Bare Defl'n	0.17 = L/900	0.43 = L/360	in	0.40
Vibration	Lmax = 12'-10	Lv = 16'-2	ft	
Defl'n	= 0.026	= 0.053	in	0.48



DWG NO. TAM 0205.8
STRUCTURAL
COMPONENT ONLY

J2 GRD FLR

Nordic Sizer – Canada 6.4

Page 2

Additional Data:

FACTORS:	f/E	KD	KH	KZ	KL	KT	KS	KN	LC#
Vr	1895	1.00	1.00	-	-	-	-	-	#2
Mr+	4824	1.00	1.00	-	1.000	-	-	-	#2
EI	218.1 million	-	-	-	-	-	-	-	#2

CRITICAL LOAD COMBINATIONS:

Shear : LC #2 = 1.25D + 1.5L

Moment(+) : LC #2 = 1.25D + 1.5L

Deflection: LC #1 = 1.0D (permanent)

LC #2 = 1.0D + 1.0L (live)

LC #2 = 1.0D + 1.0L (total)

LC #2 = 1.0D + 1.0L (bare joist)

Bearing : Support 1 - LC #2 = 1.25D + 1.5L

Support 2 - LC #2 = 1.25D + 1.5L

Load Types: D=dead W=wind S=snow H=earth,groundwater E=earthquake

L=live(use,occupancy) Ls=live(storage,equipment) f=fire

Load Patterns: s=S/2 L=L+Ls _=no pattern load in this span

All Load Combinations (LCs) are listed in the Analysis output

CALCULATIONS:Deflection: E_Ieff = 276e06 lb-in² K= 4.94e06 lbs

"Live" deflection = Deflection from all non-dead loads (live, wind, snow...)

Design Notes:

1. WoodWorks analysis and design are in accordance with the 2010 National Building Code of Canada (NBC Part 4) and the CSA O86-14 Engineering Design in Wood standard (May 2014 edition).
2. Please verify that the default deflection limits are appropriate for your application.
3. Refer to technical documentation for installation guidelines and construction details.
4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
5. Joists shall be laterally supported at supports and continuously along the compression edge.
6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.



DWG NO. TAM 8285-18
STRUCTURAL
COMPONENT ONLY

NORDIC STRUCTURES

COMPANY
TAMARACK LUMBER
BURLINGTON
Feb. 8, 2018 07:36

PROJECT
J4 GRD FLR


Design Check Calculation Sheet

Nordic Sizer – Canada 6.4

Loads:

Load	Type	Distribution	Pat- tern	Location [ft] Start End	Magnitude Start End	Unit
Load1	Dead	Full Area			20.00	psf
Load2	Live	Full Area			40.00	psf

Maximum Reactions (lbs), Bearing Resistances (lbs) and Bearing Lengths (in) :




Unfactored:			
Dead	131		131
Live	261		263
Factored:			
Total	555		558
Bearing:			
Resistance			
Joist	1854		1861
Support	-		3471
Des ratio			
Joist	0.30		0.30
Support	-		0.16
Load case	#2		#2
Length	1-3/4*		2-1/8
Min req'd	1-3/4		1-3/4
Stiffener	No		No
Kd	1.00		1.00
KB support	-		1.00
fcp sup	-		769
Kzcp sup	-		1.06

*Minimum bearing length for joists is 1-3/4" for exterior supports

Nordic 9-1/2" NI-40x Floor joist @ 16" o.c.
Supports: 1 - Hanger; 2 - Lumber Sill plate, No.1/No.2;
Total length: 9'-9.9"; 3/4" nailed and glued OSB sheathing
This section PASSES the design code check.

Limit States Design using CSA O86-14 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 547	Vr = 1895	lbs	Vf/Vr = 0.29
Moment (+)	Mf = 1319	Mr = 4824	lbs-ft	Mf/Mr = 0.27
Perm. Defl'n	0.02 = <L/999	0.32 = L/360	in	0.08
Live Defl'n	0.05 = <L/999	0.24 = L/480	in	0.21
Total Defl'n	0.07 = <L/999	0.48 = L/240	in	0.15
Bare Defl'n	0.06 = <L/999	0.32 = L/360	in	0.19
Vibration	Lmax = 9'-8	Lv = 16'-2	ft	
Defl'n	= 0.015	= 0.079	in	0.19



DESIGN NO. TAM 820638
STRUCTURAL
COMPONENT ONLY

Additional Data:

FACTORS:	f/E	KD	KH	KZ	KL	KT	KS	KN	LC#
Vr	1895	1.00	1.00	-	-	-	-	-	#2
Mr+	4824	1.00	1.00	-	1.000	-	-	-	#2
EI	218.1 million	-	-	-	-	-	-	-	#2

CRITICAL LOAD COMBINATIONS:

Shear : LC #2 = 1.25D + 1.5L

Moment(+) : LC #2 = 1.25D + 1.5L

Deflection: LC #1 = 1.0D (permanent)

LC #2 = 1.0D + 1.0L (live)

LC #2 = 1.0D + 1.0L (total)

LC #2 = 1.0D + 1.0L (bare joist)

Bearing : Support 1 - LC #2 = 1.25D + 1.5L

Support 2 - LC #2 = 1.25D + 1.5L

Load Types: D=dead W=wind S=snow H=earth,groundwater E=earthquake

L=live(use,occupancy) Ls=live(storage,equipment) f=fire

Load Patterns: s=S/2 L=L+Ls _=no pattern load in this span

All Load Combinations (LCs) are listed in the Analysis output

CALCULATIONS:

Deflection: $EI_{eff} = 276e06 \text{ lb-in}^2$ $K = 4.94e06 \text{ lbs}$

"Live" deflection = Deflection from all non-dead loads (live, wind, snow...)

Design Notes:

1. WoodWorks analysis and design are in accordance with the 2010 National Building Code of Canada (NBC Part 4) and the CSA O86-14 Engineering Design in Wood standard (May 2014 edition).

CONFORMS TO OBC 2012


2. Please verify that the default deflection limits are appropriate for your application.

3. Refer to technical documentation for installation guidelines and construction details.

4. Nordic I-joists are listed in CCMC evaluation report 13032-R.

5. Joists shall be laterally supported at supports and continuously along the compression edge.

6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.



DWG NO. TAM 0206.18
STRUCTURAL
COMPONENT ONLY

NORDIC STRUCTURES

COMPANY
TAMARACK LUMBER
BURLINGTON
Feb. 8, 2018 07:38

PROJECT
J2 2ND FLR


Design Check Calculation Sheet

Nordic Sizer – Canada 6.4

Loads:

Load	Type	Distribution	Pat-tern	Location [ft] Start End	Magnitude Start End	Unit
Load1	Dead	Full Area			20.00	psf
Load2	Live	Full Area			40.00	psf

Maximum Reactions (lbs), Bearing Resistances (lbs) and Bearing Lengths (in) :



Unfactored:			
Dead	165		162
Live	329		323
Factored:			
Total	700		687
Bearing:			
Resistance			
Joist	1878		1854
Support	5525		2758
Des ratio			
Joist	0.37		0.37
Support	0.13		0.25
Load case	#2		#2
Length	3-1/8		1-3/4*
Min req'd	1-3/4		1-3/4
Stiffener	No		No
Kd	1.00		1.00
KB support	1.00		1.00
fcp sup	769		769
Kzcp sup	1.15		1.02

*Minimum bearing length for joists is 1-3/4" for exterior supports

Bearing for wall supports is perpendicular-to-grain bearing on top plate. No stud design included.

Nordic 9-1/2" NI-40x Floor joist @ 16" o.c.

Supports: All - Lumber Wall, No.1/No.2

Total length: 12'-2.9"; 5/8" nailed and glued OSB sheathing

This section PASSES the design code check.



DWG NO. TAM B287-18
STRUCTURAL
COMPONENT ONLY

Limit States Design using CSA O86-14 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 679	Vr = 1895	lbs	Vf/Vr = 0.36
Moment (+)	Mf = 2034	Mr = 4824	lbs-ft	Mf/Mr = 0.42
Perm. Defl'n	0.06 = <L/999	0.40 = L/360	in	0.14
Live Defl'n	0.11 = <L/999	0.30 = L/480	in	0.37
Total Defl'n	0.17 = L/863	0.60 = L/240	in	0.28
Bare Defl'n	0.13 = <L/999	0.40 = L/360	in	0.33
Vibration	Lmax = 12'-0	Lv = 15'-4	ft	
Defl'n	= 0.026	= 0.059	in	0.45

Additional Data:

FACTORS:	f/E	KD	KH	KZ	KL	KT	KS	KN	LC#
Vr	1895	1.00	1.00	-	-	-	-	-	#2
Mr+	4824	1.00	1.00	-	1.000	-	-	-	#2
EI	218.1 million	-	-	-	-	-	-	-	#2

CRITICAL LOAD COMBINATIONS:

Shear : LC #2 = 1.25D + 1.5L

Moment (+) : LC #2 = 1.25D + 1.5L

Deflection: LC #1 = 1.0D (permanent)

LC #2 = 1.0D + 1.0L (live)

LC #2 = 1.0D + 1.0L (total)

LC #2 = 1.0D + 1.0L (bare joist)

Bearing : Support 1 - LC #2 = 1.25D + 1.5L

Support 2 - LC #2 = 1.25D + 1.5L

Load Types: D=dead W=wind S=snow H=earth, groundwater E=earthquake

L=live (use, occupancy) Ls=live (storage, equipment) f=fire

Load Patterns: s=S/2 L=L+Ls =no pattern load in this span

All Load Combinations (LCs) are listed in the Analysis output

CALCULATIONS:Deflection: E_Ieff = 268e06 lb-in² K= 4.94e06 lbs

"Live" deflection = Deflection from all non-dead loads (live, wind, snow...)

Design Notes:

1. WoodWorks analysis and design are in accordance with the 2010 National Building Code of Canada (NBC Part 4) and the CSA O86-14 Engineering Design in Wood standard (May 2014 edition). CONFORMS TO OBC 2012


2. Please verify that the default deflection limits are appropriate for your application.

3. Refer to technical documentation for installation guidelines and construction details.

4. Nordic I-joists are listed in CCMC evaluation report 13032-R.

5. Joists shall be laterally supported at supports and continuously along the compression edge.

6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.



DWG NO. TAM 0287-18
STRUCTURAL
COMPONENT ONLY

NORDIC STRUCTURES

COMPANY
TAMARACK LUMBER
BURLINGTON
Jan. 23, 2018 07:57


PROJECT
J3 2ND FLR

Design Check Calculation Sheet Nordic Sizer – Canada 6.4

Loads:

Load	Type	Distribution	Pat- tern	Location [ft] Start End	Magnitude Start End	Unit
Load1	Dead	Full Area			20.00	psf
Load2	Live	Full Area			40.00	psf

Maximum Reactions (lbs), Bearing Resistances (lbs) and Bearing Lengths (in) :



Unfactored:			
Dead	131		131
Live	262		262
Factored:			
Total	557		557
Bearing:			
Resistance			
Joist	1854		1854
Support	2758		2758
Des ratio			
Joist	0.30		0.30
Support	0.20		0.20
Load case	#2		#2
Length	1-3/4*		1-3/4*
Min req'd	1-3/4		1-3/4
Stiffener	No		No
Kd	1.00		1.00
KB support	1.00		1.00
fcp sup	769		769
Kzcp sup	1.02		1.02

*Minimum bearing length for joists is 1-3/4" for exterior supports

Bearing for wall supports is perpendicular-to-grain bearing on top plate. No stud design included.

Nordic 9-1/2" NI-40x Floor joist @ 16" o.c.


Supports: All - Lumber Wall, No. 1/No.2

Total length: 9'-9.9"; 5/8" nailed and glued OSB sheathing

This section PASSES the design code check.

Limit States Design using CSA O86-14 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 548	Vr = 1895	lbs	Vf/Vr = 0.29
Moment (+)	Mf = 1327	Mr = 4824	lbs-ft	Mf/Mr = 0.28
Perm. Defl'n	0.03 = <L/999	0.32 = L/360	in	0.08
Live Defl'n	0.05 = <L/999	0.24 = L/480	in	0.21
Total Defl'n	0.08 = <L/999	0.48 = L/240	in	0.16
Bare Defl'n	0.06 = <L/999	0.32 = L/360	in	0.19
Vibration	Lmax = 9'-8	Lv = 15'-4	ft	
Defl'n	= 0.017	= 0.079	in	0.22



DWG NO. TAM 0188-8
STRUCTURAL
COMPONENT ONLY

Additional Data:

FACTORS:	f/E	KD	KH	KZ	KL	KT	KS	KN	LC#
Vr	1895	1.00	1.00	-	-	-	-	-	#2
Mr+	4824	1.00	1.00	-	1.000	-	-	-	#2
EI	218.1 million	-	-	-	-	-	-	-	#2

CRITICAL LOAD COMBINATIONS:

Shear : LC #2 = 1.25D + 1.5L

Moment(+) : LC #2 = 1.25D + 1.5L

Deflection: LC #1 = 1.0D (permanent)

LC #2 = 1.0D + 1.0L (live)

LC #2 = 1.0D + 1.0L (total)

LC #2 = 1.0D + 1.0L (bare joist)

Bearing : Support 1 - LC #2 = 1.25D + 1.5L

Support 2 - LC #2 = 1.25D + 1.5L

Load Types: D=dead W=wind S=snow H=earth,groundwater E=earthquake

L=live(use,occupancy) Ls=live(storage,equipment) f=fire

Load Patterns: s=S/2 L=L+Ls _=no pattern load in this span

All Load Combinations (LCs) are listed in the Analysis output

CALCULATIONS:Deflection: E_Ieff = 268e06 lb-in² K= 4.94e06 lbs

"Live" deflection = Deflection from all non-dead loads (live, wind, snow...)

Design Notes:

1. WoodWorks analysis and design are in accordance with the 2010 National Building Code of Canada (NBC Part 4) and the CSA O86-14 Engineering Design in Wood standard (May 2014 edition).
2. Please verify that the default deflection limits are appropriate for your application.
3. Refer to technical documentation for installation guidelines and construction details.
4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
5. Joists shall be laterally supported at supports and continuously along the compression edge.
6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.



DWG NO. TAM B200.8
STRUCTURAL
COMPONENT ONLY



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\...\B1A(i1652)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

September 18, 2017 12:32:53

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports: CCMC 12472-R

File Name: HIGHGROVE 12 WOD.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B1A(i1652

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 03-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 4"	102 / 0	195 / 0		
B1, 4"	102 / 0	195 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	E1(i154)	Unf. Lin. (lb/ft)	L	00-00-00	03-02-00	38	105			n/a
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	03-02-00	27	13			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	148 ft-lbs	8,258 ft-lbs	1.8%	0	01-07-00
End Shear	79 lbs	3,761 lbs	2.1%	0	01-01-08
Total Load Defl.	L/999 (0.001")	n/a	n/a	4	01-07-00
Live Load Defl.	L/999 (0")	n/a	n/a	5	01-07-00
Max Defl.	0.001"	n/a	n/a	4	01-07-00
Span / Depth	3.3	n/a	n/a		00-00-00

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports

			Demand/ Resistance Support	Demand/ Resistance Member	Material
Bearing Supports		Dim. (L x W)	Demand		
B0	Wall/Plate	4" x 1-3/4"	272 lbs	11.2%	4.9% Unspecified
B1	Wall/Plate	4" x 1-3/4"	272 lbs	11.2%	4.9% Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO UBC 2012

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.





Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B1(i1027)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 5, 2017 10:31:22

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports: CCMC 12472-R

File Name: HIGHGROVE 12.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B1(i1027)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 08-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 5-1/2"	2,209 / 0	1,206 / 0		
B1, 7-1/2"	3,618 / 0	2,730 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-04-08	07-00-08	307	154			n/a
1	User Load	Unf. Lin. (lb/ft)	L	00-05-08	07-06-00	240	120			n/a
2	5(i265)	Conc. Pt. (lbs)	L	00-02-12	00-02-12	245	167			n/a
3	-	Conc. Pt. (lbs)	L	07-09-02	07-09-02	1,750	1,770			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	7,698 ft-lbs	25,408 ft-lbs	30.3%	1	03-08-08
End Shear	3,852 lbs	11,571 lbs	33.3%	1	06-09-00
Total Load Defl.	L/999 (0.101")	n/a	n/a	4	03-11-08
Live Load Defl.	L/999 (0.067")	n/a	n/a	5	03-11-08
Max Defl.	0.101"	n/a	n/a	4	03-11-08
Span / Depth	9.1	n/a	n/a		00-00-00

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	5-1/2" x 3-1/2"	4,820 lbs	58.6%	20.5%	Unspecified
B1	7-1/2" x 3-1/2"	8,839 lbs	78.8%	27.6%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

CONFORMS TO OBC 2012

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9



P644

DWG NO. TAM 49655-17
STRUCTURAL
COMPONENT ONLY



Boise Cascade

Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement/Flush Beams/B1(i1027)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 5, 2017 10:31:22

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports: CCMC 12472-R

File Name: HIGHGROVE 12.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B1(i1027)

Specifier:

Designer: AJ

Company:

Misc:

Connection Diagram

a minimum = 2" c = 2-3/4"
 b minimum = 3" d = 6"

Calculated Side Load = 532.4 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d Sinker Nails

3 1/2" ARDOX SPIRAL**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 47658 17
 STRUCTURAL
 COMPONENT ONLY

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports: CCMC 12472-R

File Name: HIGHGROVE 12.mmdl


Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B3 D

Specifier:

Designer: AJ

Company:

Msc:



Total Horizontal Product Length = 10-03-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 4"	2,617 / 0	1,383 / 0		
B1, 5"	2,492 / 0	1,323 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-08-08	10-00-08	465	233			n/a
1	-	Conc. Pt. (lbs)	L	00-01-01	00-01-01	526	263			n/a
2	J2(i778)	Conc. Pt. (lbs)	L	10-01-12	10-01-12	242	121			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	11,929 ft-lbs	39,636 ft-lbs	30.1%	1	05-01-12
End Shear	4,516 lbs	17,356 lbs	26%	1	01-01-08
Total Load Defl.	L/618 (0.187")	0.481"	38.8%	4	05-01-12
Live Load Defl.	L/999 (0.122")	n/a	n/a	5	05-01-12
Max Defl.	0.187"	n/a	n/a	4	05-01-12
Span / Depth	12.2	n/a	n/a		00-00-00

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	4" x 5-1/4"	5,654 lbs	41.4%	22.1%	Unspecified
B1	5" x 5-1/4"	5,392 lbs	31.6%	16.8%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Calculations assume unbraced length of Top: 00-03-02, Bottom: 00-03-02.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 9

CONFORMS TO DBC 2012



DWG NO. TAM 47656-17
 STRUCTURAL
 COMPONENT ONLY

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: HIGHGROVE 12.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B3


Specifier:

Designer: AJ

Company:

Msc:

Connection Diagram




4 rows

a minimum = 3"
b minimum = 3"
c = 6 1/2"
d = 4"
e minimum = 2"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Nailing schedule applies to both sides of the member.

Member has no side loads.

Connectors are: 16d  Nails

3 1/2" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 47656-17
STRUCTURAL
COMPONENT ONLY

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports: CCMC 12472-R

File Name: HIGHGROVE 12.mmdl


Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B4 D

Specifier:

Designer: AJ

Company:

Msc:



Total Horizontal Product Length = 04-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 4"	971 / 0	506 / 0		
B1, 5-1/2"	859 / 0	450 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-00-00	03-10-08	310	156			n/a
1	J2(i622)	Conc. Pt. (lbs)	L	01-10-08	01-10-08	321	160			n/a
2	J3(i624)	Conc. Pt. (lbs)	L	03-02-08	03-02-08	307	154			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,703 ft-lbs	25,408 ft-lbs	6.7%	1	01-10-08
End Shear	1,345 lbs	11,571 lbs	11.6%	1	02-11-00
Total Load Defl.	L/999 (0.005")	n/a	n/a	4	02-00-01
Live Load Defl.	L/999 (0.003")	n/a	n/a	5	02-00-01
Max Defl.	0.005"	n/a	n/a	4	02-00-01
Span / Depth	4.4	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	4" x 3-1/2"	2,089 lbs	23%	12.2%	Unspecified
B1 Wall/Plate	5-1/2" x 3-1/2"	1,851 lbs	14.8%	7.9%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Calculations assume unbraced length of Top: 00-03-09, Bottom: 00-03-09.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor: Normal Part code: Part 9

CONFORMS TO DBC 2012





Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\...B4 DR(i502)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 5, 2017 10:31:22

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports: CCMC 12472-R

File Name: HIGHGROVE 12.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B4


Specifier:

Designer: AJ

Company:

Misc:

Connection Diagram



a minimum = 1 1/2" c = 1 1/2"
b minimum = 3" d = 6"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Member has no side loads.

Connectors are: 16d Sinkers Nails

3 1/2" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 47652-17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B6(i483)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 5, 2017 10:31:23

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports: CCMC 12472-R

File Name: HIGHGROVE 12.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B6(i483)

Specifier:

Designer: AJ

Company:

Msc:



Total Horizontal Product Length = 08-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 5-1/2"	1,403 / 0	742 / 0		
B1, 5-1/2"	1,744 / 0	912 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	01-05-00	07-05-00	324	162			n/a
1	User Load	Unf. Lin. (lb/ft)	L	04-00-08	07-06-08	240	120			n/a
2	J1(i688)	Conc. Pt. (lbs)	L	00-11-00	00-11-00	353	177			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	6,261 ft-lbs	25,408 ft-lbs	24.6%	1	04-04-07
End Shear	3,185 lbs	11,571 lbs	27.5%	1	06-09-00
Total Load Defl.	L/999 (0.082")	n/a	n/a	4	04-00-08
Live Load Defl.	L/999 (0.054")	n/a	n/a	5	04-00-08
Max Defl.	0.082"	n/a	n/a	4	04-00-08
Span / Depth	9.1	n/a	n/a		00-00-00

Bearing Supports

Loading Support						
B0	Wall/Plate	5-1/2" x 3-1/2"	3,032 lbs	36.9%	12.9%	Unspecified
B1	Wall/Plate	5-1/2" x 3-1/2"	3,756 lbs	45.7%	16%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012



P6 1/2
DWG NO. TAM 47658 17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B6(i483)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 5, 2017 10:31:23

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: HIGHGROVE 12.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B6(i483)


Specifier:

Designer: AJ

Company:

Misc:

Connection Diagram



a minimum = 2" c = 2-3/4"
b minimum = 3" d = 6"

Calculated Side Load = 609.5 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d ^{common} Nails

3 1/2" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCK®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 47658-17
STRUCTURAL
COMPONENT ONLY

BC CALC® Design Report

Basement\Flush Beams\B7(i1874)

Dry | 1 span | No cant.

February 8, 2018 07:31:15

Build 6215

Job name:

File name: HIGHGROVE 12.mmdl

Address:

Description: Basement\Flush Beams\B7(i1874)

City, Province, Postal Code: WAT...WN


Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:



Total Horizontal Product Length = 12-05-04

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 5-1/4"	1,964 / 0	1,363 / 0		
B1, 2-1/8"	416 / 0	306 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	12-05-04		10			00-00-00
1	6(i263)	Unf. Lin. (lb/ft)	L	00-00-00	02-07-10		81			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-02-10	12-05-04	13	6			n/a
3	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-02-10	02-05-14	14	7			n/a
4	FC1 Floor Material	Unf. Lin. (lb/ft)	L	02-05-14	12-05-04	22	11			n/a
5	6(i263)	Conc. Pt. (lbs)	L	00-02-06	00-02-06	812	427			n/a
6	-	Conc. Pt. (lbs)	L	02-05-12	02-05-12	1,159	705			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	5,616 ft-lbs	23,220 ft-lbs	24.2%	1	02-05-14
End Shear	2,702 lbs	11,571 lbs	23.4%	1	01-02-12
Total Load Deflection	L/796 (0.18")	n/a	30.1%	4	05-09-12
Live Load Deflection	L/999 (0.105")	n/a	n/a	5	05-09-12
Max Defl.	0.18"	n/a	n/a	4	05-09-12
Span / Depth	15.1				

Bearing Supports	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0 Beam	5-1/4" x 3-1/2"	4,650 lbs	47.4%	20.7%	Unspecified
B1 Wall/Plate	2-1/8" x 3-1/2"	1,006 lbs	25.3%	11.1%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.


DWG NO. TAM0189-18
STRUCTURAL
COMPONENT ONLY

BC CALC® Design Report

Build 6215

Job name:

Address:

City, Province, Postal Code: WAT...WN

Customer:

Code reports: CCMC 12472-R

Basement\Flush Beams\B7(i1874)

Dry | 1 span | No cant.

February 8, 2018 07:31:15

File name: HIGHGROVE 12.mmdl


Description: Basement\Flush Beams\B7(i1874)

Specifier:

Designer: AJ

Company:

Connection Diagram



a minimum = 1"
b minimum = 3"

c = 1-1/2"
d = 4"

Calculated Side Load = 183.6 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: Nails

3-1/2" ARDOX SPIRAL

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.



BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®

DWG NO. TAM 0209-18
STRUCTURAL
COMPONENT ONLY



Boise Cascade

Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B8(i1519)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 20, 2017 09:31:33

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports: CCMC 12472-R

File Name: HIGHGROVE 12.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B8(i1519)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 02-04-12

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	1,078 / 0	645 / 0		
B1, 2-3/4"	1,193 / 0	708 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	5(i265)	Unf. Lin. (lb/ft)	L	00-00-00	02-04-12		81			n/a
1	5(i265)	Unf. Lin. (lb/ft)	L	00-00-00	01-02-08	494	248			n/a
2	5(i265)	Unf. Lin. (lb/ft)	L	01-02-08	02-04-12	443	221			n/a
3	-	Conc. Pt. (lbs)	L	00-08-04	00-08-04	577	288			n/a
4	-	Conc. Pt. (lbs)	L	01-10-08	01-10-08	569	285			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,211 ft-lbs	25,408 ft-lbs	4.8%	1	01-00-04
End Shear	888 lbs	11,571 lbs	7.7%	1	00-11-08
Total Load Defl.	L/999 (0.001")	n/a	n/a	4	01-02-02
Live Load Defl.	L/999 (0.001")	n/a	n/a	5	01-01-12
Max Defl.	0.001"	n/a	n/a	4	01-02-02
Span / Depth	2.7	n/a	n/a		00-00-00

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 3-1/2"	2,423 lbs	n/a	28.4%	HGUS410
B1 Wall/Plate	2-3/4" x 3-1/2"	2,674 lbs	52%	22.8%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO DBC 2012



Boise Cascade

Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement/Flush Beams/B8(i1519)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

June 20, 2017 09:31:33

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: WATERDOWN,

Customer:

Code reports:

CCMC 12472-R

File Name: HIGHGROVE 12.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B8(i1519)

Specifier:

Designer: AJ

Company:

Misc:

Connection Diagram

1" 4 rows
2" (MIN)
1"

a minimum = 2" c = 7-1/2"
b minimum = 3" d = 12"

Calculated Side Load = 690.1 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods.

Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALCO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 4265317
STRUCTURAL
COMPONENT ONLY

1st Floor\Flush Beams\B9(i1725)

Dry | 1 span | No cant.

January 16, 2018 16:35:29

BC CALC® Design Report

Build 6215

Job name:

Address:

City, Province, Postal Code: WAT...WN

Customer:

Code reports: CCMC 12472-R


File name: HIGHGROVE 12.mmdl

Description: 1st Floor\Flush Beams\B9(i1725)

Specifier:

Designer: AJ

Company:



Total Horizontal Product Length = 10-00-12

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 5-1/2"	294 / 0	734 / 0	369 / 0	
B1, 1-3/4"	299 / 0	733 / 0	369 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	10-00-12	10				00-00-00
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-02-12	10-00-12	18	9			n/a
2	User Load	Unf. Lin. (lb/ft)	L	00-05-08	09-11-00	33	130	78		n/a
3	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-10-08	10-00-12	12	6			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	3,914 ft-lbs	23,220 ft-lbs	16.9 %	13	05-02-04
End Shear	1,348 lbs	11,571 lbs	11.7 %	13	01-03-00
Total Load Deflection	L/999 (0.1")	n/a	n/a	45	05-02-04
Live Load Deflection	L/999 (0.041")	n/a	n/a	61	05-02-04
Max Defl.	0.1"	n/a	n/a	45	05-02-04
Span / Depth	12.1				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0	Wall/Plate 5-1/2" x 3-1/2"	1,618 lbs	15.7 %	6.9 %	Unspecified
B1	Wall/Plate 1-3/4" x 3-1/2"	1,620 lbs	49.5 %	21.7 %	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Unbalanced snow loads determined from building geometry were used in selected product's verification.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

Member has no side loads.

CONFORMS TO OBC 2012



DWG NO. TAM 0290-18
STRUCTURAL
COMPONENT ONLY



Boise Cascade

**Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP****PASSED**

BC CALC® Design Report

Build 6215

Job name:

Address:

City, Province, Postal Code: WAT...WN

Customer:

Code reports: CCMC 12472-R

1st Floor\Flush Beams\B9(i1725)

Dry | 1 span | No cant.

January 16, 2018 16:35:29


File name: HIGHGROVE 12.mmdl

Description: 1st Floor\Flush Beams\B9(i1725)

Specifier:

Designer: AJ

Company:

Connection Diagram

a minimum = 1"

b minimum = 3"

c = 1-1/2"

d = 6"

Member has no side loads.

Connectors are: 16d Nails




3-1/2" ARDOX SPIRAL**Disclosure**

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.



BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCi®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®

DWG NO. TAM B290-18
STRUCTURAL
COMPONENT ONLY





Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf
Simple Spans, L/480 Deflection Limit
5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-2"	13'-9"	N/A	15'-7"	14'-8"	14'-2"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
14"	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
16"	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-8"	15'-3"	14'-5"	N/A	16'-8"	15'-3"	14'-5"	N/A
	NI-40x	17'-11"	16'-11"	16'-1"	N/A	18'-5"	17'-1"	16'-1"	N/A
	NI-60	18'-2"	17'-1"	16'-4"	N/A	18'-7"	17'-4"	16'-4"	N/A
	NI-70	19'-2"	17'-10"	17'-2"	N/A	19'-7"	18'-3"	17'-7"	N/A
	NI-80	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
11-7/8"	NI-20	19'-6"	18'-1"	17'-3"	N/A	19'-11"	18'-3"	17'-3"	N/A
	NI-40x	21'-0"	19'-6"	18'-8"	N/A	21'-7"	20'-2"	19'-2"	N/A
	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-6"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
14"	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-11"	20'-11"	N/A	24'-3"	22'-7"	21'-7"	N/A
	NI-60	24'-0"	22'-3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
16"	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-2"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.





Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf
Simple Spans, L/480 Deflection Limit
3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"
	NI-40x	17'-0"	16'-0"	15'-5"	14'-9"	17'-5"	16'-5"	15'-10"	15'-2"
	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-6"	16'-7"	15'-11"	15'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-7"	18'-5"	17'-3"	16'-7"	15'-11"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
11-7/8"	NI-20	17'-10"	16'-10"	16'-2"	15'-6"	18'-6"	17'-4"	16'-9"	16'-1"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-6"	19'-11"	18'-6"	17'-9"	17'-0"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-11"	22'-1"	20'-6"	19'-7"	18'-7"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"
	NI-40x	18'-8"	17'-2"	16'-3"	15'-2"	18'-10"	17'-2"	16'-3"	15'-2"
	NI-60	18'-11"	17'-6"	16'-6"	15'-5"	19'-2"	17'-6"	16'-6"	15'-5"
	NI-70	20'-0"	18'-7"	17'-9"	16'-7"	20'-5"	18'-11"	17'-10"	16'-7"
	NI-80	20'-3"	18'-10"	17'-11"	16'-10"	20'-8"	19'-3"	18'-2"	16'-10"
11-7/8"	NI-20	20'-1"	18'-5"	17'-5"	16'-2"	20'-1"	18'-5"	17'-5"	16'-2"
	NI-40x	21'-10"	20'-4"	19'-4"	17'-8"	22'-5"	20'-6"	19'-4"	17'-8"
	NI-60	22'-1"	20'-7"	19'-7"	18'-4"	22'-8"	20'-10"	19'-8"	18'-4"
	NI-70	23'-4"	21'-8"	20'-8"	19'-7"	23'-10"	22'-3"	21'-2"	19'-9"
	NI-80	23'-7"	21'-11"	20'-11"	19'-9"	24'-1"	22'-6"	21'-5"	20'-0"
14"	NI-90x	24'-3"	22'-6"	21'-6"	20'-4"	24'-8"	23'-0"	22'-0"	20'-9"
	NI-40x	24'-5"	22'-9"	21'-8"	19'-5"	25'-1"	23'-2"	21'-9"	19'-5"
	NI-60	24'-10"	23'-1"	22'-0"	20'-10"	25'-6"	23'-8"	22'-4"	20'-10"
	NI-70	26'-1"	24'-3"	23'-2"	21'-10"	26'-8"	24'-11"	23'-9"	22'-4"
	NI-80	26'-6"	24'-7"	23'-5"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-9"	27'-9"	25'-11"	24'-8"	23'-4"
	NI-60	27'-3"	25'-5"	24'-2"	22'-10"	28'-0"	26'-2"	24'-9"	23'-1"
	NI-70	28'-8"	26'-8"	25'-4"	23'-11"	29'-3"	27'-4"	26'-1"	24'-8"
	NI-80	29'-1"	27'-0"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
	NI-90x	29'-11"	27'-10"	26'-6"	25'-0"	30'-6"	28'-5"	27'-2"	25'-8"

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.





Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf
Simple Spans, L/480 Deflection Limit
5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
14"	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
16"	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	17'-9"	16'-1"	15'-1"	N/A	17'-9"	16'-1"	15'-1"	N/A
	NI-60	18'-1"	16'-4"	15'-4"	N/A	18'-1"	16'-4"	15'-4"	N/A
	NI-70	19'-2"	17'-10"	16'-9"	N/A	19'-7"	17'-10"	16'-9"	N/A
	NI-80	19'-5"	18'-0"	17'-1"	N/A	19'-10"	18'-3"	17'-1"	N/A
11-7/8"	NI-20	18'-9"	17'-0"	16'-0"	N/A	18'-9"	17'-0"	16'-0"	N/A
	NI-40x	21'-0"	19'-3"	17'-9"	N/A	21'-3"	19'-3"	17'-9"	N/A
	NI-60	21'-4"	19'-8"	18'-5"	N/A	21'-8"	19'-8"	18'-5"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-4"	20'-0"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-5"	N/A
14"	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-5"	19'-6"	N/A	24'-1"	21'-5"	19'-6"	N/A
	NI-60	24'-0"	22'-3"	21'-0"	N/A	24'-8"	22'-5"	21'-0"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-9"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
16"	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	24'-10"	23'-4"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.




Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf
Simple Spans, L/480 Deflection Limit
3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-0"	16'-0"	15'-1"	13'-11"	17'-5"	16'-1"	15'-1"	13'-11"
	NI-60	17'-2"	16'-2"	15'-5"	14'-3"	17'-6"	16'-5"	15'-5"	14'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-6"	18'-5"	17'-3"	16'-7"	15'-6"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	15'-10"
11-7/8"	NI-20	17'-10"	16'-10"	16'-0"	14'-10"	18'-6"	17'-1"	16'-0"	14'-10"
	NI-40x	19'-4"	17'-11"	17'-3"	15'-10"	19'-11"	18'-6"	17'-9"	15'-10"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-1"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-5"	22'-1"	20'-6"	19'-6"	17'-5"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-9"	16'-1"	15'-1"	13'-11"	17'-9"	16'-1"	15'-1"	13'-11"
	NI-60	18'-1"	16'-5"	15'-5"	14'-3"	18'-1"	16'-5"	15'-5"	14'-3"
	NI-70	19'-10"	17'-11"	16'-9"	15'-6"	19'-10"	17'-11"	16'-9"	15'-6"
	NI-80	20'-2"	18'-3"	17'-1"	15'-10"	20'-2"	18'-3"	17'-1"	15'-10"
11-7/8"	NI-20	18'-10"	17'-1"	16'-0"	14'-10"	18'-10"	17'-1"	16'-0"	14'-10"
	NI-40x	21'-3"	19'-3"	17'-9"	15'-10"	21'-3"	19'-3"	17'-9"	15'-10"
	NI-60	21'-9"	19'-8"	18'-5"	17'-1"	21'-9"	19'-8"	18'-5"	17'-1"
	NI-70	23'-4"	21'-5"	20'-1"	18'-6"	23'-8"	21'-5"	20'-1"	18'-6"
	NI-80	23'-7"	21'-10"	20'-5"	18'-11"	24'-1"	21'-10"	20'-5"	18'-11"
14"	NI-90x	24'-3"	22'-6"	21'-3"	19'-7"	24'-8"	22'-7"	21'-3"	19'-7"
	NI-40x	24'-2"	21'-5"	19'-6"	17'-5"	24'-2"	21'-5"	19'-6"	17'-5"
	NI-60	24'-9"	22'-5"	21'-0"	19'-6"	24'-9"	22'-5"	21'-0"	19'-6"
	NI-70	26'-1"	24'-3"	22'-9"	21'-0"	26'-8"	24'-3"	22'-9"	21'-0"
	NI-80	26'-6"	24'-7"	23'-3"	21'-6"	27'-1"	24'-10"	23'-3"	21'-6"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-4"	27'-9"	25'-10"	24'-3"	22'-4"
	NI-60	27'-3"	24'-11"	23'-5"	21'-7"	27'-6"	24'-11"	23'-5"	21'-7"
	NI-70	28'-8"	26'-8"	25'-3"	23'-4"	29'-3"	26'-11"	25'-3"	23'-4"
	NI-80	29'-1"	27'-0"	25'-9"	23'-10"	29'-8"	27'-6"	25'-10"	23'-10"
	NI-90x	29'-11"	27'-10"	26'-6"	24'-10"	30'-6"	28'-5"	26'-11"	24'-10"


- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



INSTALLATION GUIDE FOR RESIDENTIAL FLOORS



Distributed by:



N-C301 / November 2014

SAFETY AND CONSTRUCTION PRECAUTIONS

WARNING

I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.

Avoid Accidents by Following these Important Guidelines:

1. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-bridging at joist ends. When I-joists are applied continuous over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
 - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.
 - Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bridging.
4. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
5. Never install a damaged I-joist.

Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.






Do not walk on I-joists until fully fastened and braced, or serious injuries can result.



Never stack building materials over unbraced I-joists. Once sheathed, do not over-stress I-joist with concentrated loads from building materials.

STORAGE AND HANDLING GUIDELINES

1. Bundle wrap can be slippery when wet. Avoid walking on wrapped bundles.
2. Store, stack, and handle I-joists vertically and level only.
3. Always stack and handle I-joists in the upright position only.
4. Do not store I-joists in direct contact with the ground and/or flatwise.
5. Protect I-joists from weather, and use spacers to separate bundles.
6. Bundled units should be kept intact until time of installation.
7. When handling I-joists with a crane on the job site, take a few simple precautions to prevent damage to the I-joists and injury to your work crew.
 - Pick I-joists in bundles as shipped by the supplier.
 - Orient the bundles so that the webs of the I-joists are vertical.
 - Pick the bundles at the 5th points, using a spreader bar if necessary.
8. Do not handle I-joists in a horizontal orientation.
9. NEVER USE OR TRY TO REPAIR A DAMAGED I-JOIST.



101ST HANGOVER

1. Hangers shown illustrate the three most commonly used metal hangers to support I-joists.
2. All nailing must meet the hanger manufacturer's recommendations.
3. Hangers should be selected based on the joist depth, flange width and load capacity based on the maximum spans.
4. Web stiffeners are required when the sides of the hangers do not laterally brace the top flange of the I-joist.

1. Hangers shown illustrate the three most commonly used metal hangers


The diagrams illustrate three mounting methods for a 1/2 inch wide by 1/2 inch high plate:

- Top Mount:** The plate is mounted to the top of the structure, with the mounting holes facing upwards.
- Face Mount:** The plate is mounted to the front face of the structure, with the mounting holes facing outwards.
- Slew Mount:** The plate is mounted to the side of the structure, with the mounting holes facing outwards.

RECOMMENDATIONS:

- FIGURE 2**
WEB STIFFENER INSTALLATION DETAILS
- Flange width
2-1/2" or 3-1/2"
- Approx. 2" I
- 1/8"-1/4" Gap
- (4) 2-1/2" nails,
3" nails required
for I-joists with
3-1/2" flange width
- No Gap
- CONCENTRATED LOAD
(Load stiffener)
- Tight Joint
- No Gap
- Gap
- END BEARING
(Bearing stiffener)
- See table below for web stiffener size requirements
-
- The diagram illustrates two scenarios for web stiffener installation. The top scenario, labeled 'CONCENTRATED LOAD (Load stiffener)', shows a cross-section of a beam with a stiffener. The stiffener's flange width is specified as '2-1/2" or 3-1/2"'. The beam's depth is 'Approx. 2" I'. A '1/8"-1/4" Gap' is indicated between the stiffener flange and the beam web. Four nails are shown: '(4) 2-1/2" nails, 3" nails required for I-joists with 3-1/2" flange width'. A 'No Gap' is noted at the bottom of the stiffener. The bottom scenario, labeled 'END BEARING (Bearing stiffener)', shows a stiffener at the end of a beam. It features a 'Tight Joint' and 'No Gap' between the stiffener and the beam web. A 'Gap' is indicated between the stiffener and the beam flange. A small detail of the end bearing is shown to the left.

Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width



	S-P-F No.2	1950F MSR	2100F MSR	1950F MSR	2100F MSR	2400F MSR	NPG Lumber
33 pieces per unit	33 pieces per unit	33 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit
	<p>NI-20</p>	<p>NI-40x</p>	<p>NI-60</p>	<p>NI-70</p>	<p>NI-80</p>	<p>NI-90</p>	<p>NI-90x</p>

Chamiers Chibougamau Ltd. harvests its own trees, which enables Mercic products to adhere to strict quality control procedures throughout the manufacturing process. Every phase of the operation, from forest to the finished product, reflects our commitment to quality.

Nordic Engineered Wood I-joists use only finger-jointed black spruce lumber in their flanges, ensuring consistent quality, superior strength, longer span carrying capacity.

SI units conversion: 1 inch = 25.4 mm

2015-04-16

INSTALLING NORDIC I-JOISTS

1. Before laying out floor system components, verify that I-joist flange widths match hanger widths. If not, contact your supplier.
2. Except for cutting to length, I-joist flanges should **never** be cut, drilled, or notched.
3. Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple spans must be level.
5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings.
6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement.
7. Leave a 1/16-inch gap between the I-joist end and a header.
8. Concentrated loads greater than those that can normally be expected in residential construction should only be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment and security cameras. Never suspend unusual or heavy loads from the I-joist's bottom flange. Whenever possible, suspend all concentrated loads from the top of the I-joist. Or, attach the load to blocking that has been securely fastened to the I-joist webs.
9. Never install I-joists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or I-joist blocking panels.
11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (cripple members) to transfer gravity loads through the floor system to the wall or foundation below.
12. Due to shrinkage, common framing lumber set on edge **may never** be used as blocking or rim boards. I-joist blocking panels or other engineered wood products – such as rim board – must be cut to fit between the I-joists, and an I-joist-compatible depth selected.
13. Provide permanent lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly, support the bottom flange of all cantilevered I-joists at the end support next to the cantilever extension. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used.
14. If square-edge panels are used, edges must be supported between I-joists with 2x4 blocking. Glue panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed.
15. Nail spacing: Space nails installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.






FIGURE 1
TYPICAL NORDIC I-JOIST FLOOR FRAMING AND CONSTRUCTION DETAILS

Some framing requirements such as erection bracing and blocking panels have been omitted for clarity.




Figures 3, 4 or 5
Holes may be cut in web for plumbing, wiring and duct work. See Tables 1, 2 and Figure 7.
NOTE: Never cut or notch flanges.
Nordic Lam or SCL
Nordic Lam or SCL
Use hangers recognized in current code evaluation reports
Figures 3, 4 or 5

All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.125" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.





Blocking Panel or I-joist	Maximum Factored Uniform Vertical Load* (plf)
Nl joists	3,300

*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.











Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
1-1/8" Rim Board Plus	8,090

*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.



Pair of Squash Blocks	Maximum Factored Vertical per Pair of Squash Blocks (lbs)
2x Lumber	5,500
1-1/8" Rim Board Plus	4,300


Provide lateral bracing per detail 1a, 1b, or 1c



Flange Width	Material Thickness Required†	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid sawn lumber and wood structural panels conforming to CAN/CSA-O325 or CAN/CSA-O437 Standard.
 ** For face-mount hangers use net joist depth minus 3-1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4".



BACKER BLOCKS (Blocks must be long enough to permit required nailing without splitting)



- Notes:**
- Support back of I-joist web during nailing to prevent damage to web/flange connection.
 - Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
 - Filler block is required between joists for full length of span.
 - Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails are clinched, only two nails per foot are required.
 - The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

FILLER BLOCK REQUIREMENTS FOR DOUBLE I-JOIST CONSTRUCTION

Flange Size	Joist Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2"	2-1/8" x 6"
	11-7/8"	2-1/8" x 8"
	14"	2-1/8" x 10"
	16"	2-1/8" x 12"
3-1/2" x 1-1/2"	9-1/2"	3" x 6"
	11-7/8"	3" x 8"
	14"	3" x 10"
	16"	3" x 12"
3-1/2" x 2"	11-7/8"	3" x 7"
	14"	3" x 9"
	16"	3" x 11"




Notes:

- In some local codes, blocking is prescriptively required in the first joist space (or first and second joist space) next to the starter joist. Where required, see local code requirements for spacing of the blocking.
- All nails are common spiral in this detail.


2015-04-16

CANTILEVER DETAILS FOR BALCONIES (NO WALL LOAD)

3a) I-JOIST CANTILEVER DETAIL FOR BALCONIES (No Wall Load)




3b) LUMBER CANTILEVER DETAIL FOR BALCONIES (No Wall Load)




CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

4a) Method 1 — SHEATHING REINFORCEMENT ONE SIDE



Method 2 — SHEATHING REINFORCEMENT TWO SIDES

- Use same installation as Method 1 but reinforce both sides of I-joist with sheathing.
- Use nailing pattern shown for Method 1 with opposite face nailing offset by 3".



Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

4b) Alternate Method 2 — DOUBLE I-JOIST





FIGURE 4 (continued)



See table below for N1 reinforcement requirements at cantilever.

For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in.)	ROOF TRUSS SPAN (ft)	ROOF LOADING (UNFACTORED)			
		LL = 30 psf, DL = 15 psf JOIST SPACING (in.)	LL = 40 psf, DL = 15 psf JOIST SPACING (in.)	LL = 50 psf, DL = 15 psf JOIST SPACING (in.)	LL = 60 psf, DL = 15 psf JOIST SPACING (in.)
26	12	1	1	1	1
28	16	1	1	1	1
30	19.2	1	1	1	1
32	24	1	1	1	1
34	12	1	1	1	1
36	16	1	1	1	1
38	19.2	1	1	1	1
40	24	1	1	1	1
42	12	1	1	1	1
44	16	1	1	1	1
46	19.2	1	1	1	1
48	24	1	1	1	1
50	12	1	1	1	1
52	16	1	1	1	1
54	19.2	1	1	1	1
56	24	1	1	1	1
58	12	1	1	1	1
60	16	1	1	1	1
62	19.2	1	1	1	1
64	24	1	1	1	1
66	12	1	1	1	1
68	16	1	1	1	1
70	19.2	1	1	1	1
72	24	1	1	1	1
74	12	1	1	1	1
76	16	1	1	1	1
78	19.2	1	1	1	1
80	24	1	1	1	1
82	12	1	1	1	1
84	16	1	1	1	1
86	19.2	1	1	1	1
88	24	1	1	1	1
90	12	1	1	1	1
92	16	1	1	1	1
94	19.2	1	1	1	1
96	24	1	1	1	1
98	12	1	1	1	1
100	16	1	1	1	1


1. N = No reinforcement required.
2. N1 = N1 reinforced with 3/4" wood structural panel on one side only.
3. For larger openings, or multiple 3'-0" width openings spaced less than 6'-0" o.c., additional joists beneath the opening's cripple studs may be required.
4. For conventional roof construction using a ridge beam, the roof truss span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge beam, the roof truss span is equivalent to the distance between the supporting walls as if a truss is used.
5. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

WEB HOLES

RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

1. The distance between the inside edge of the support and the centreline of any hole or duct chase opening shall be in compliance with the requirements of Table 1 or 2, respectively.
2. I-joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.
3. Whenever possible, field-cut holes should be centred on the middle of the web.
4. The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the hole or opening and the adjacent I-joist flange.
5. The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
6. Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the longest side of the longest rectangular hole or duct chase opening) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
7. A knockout is **not** considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
8. Holes measuring 1-1/2 inches or smaller shall be permitted anywhere in a ventilated section of a joist. Holes of greater size may be permitted subject to verification.
9. A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
10. All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.
11. Limit three maximum size holes per span, of which one may be a duct chase opening.
12. A group of round holes of approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

FIGURE 7
FIELD-CUT HOLE LOCATOR



A knockout is **NOT** considered a hole, may be utilized wherever it occurs and may be ignored for purposes of calculating minimum distances between holes.

TABLE 1
LOCATION OF CIRCULAR HOLES IN JOIST WEBS
Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf

Joist Depth	Joist Series	2	3	4	5	6	6-1/4	7	8	8-5/8	9	10	10-3/4	11	12	12-3/4	Span adjustment Factor
12	1	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
16	2	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
20	3	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
24	4	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
28	5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
32	6	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
36	7	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
40	8	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
44	9	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
48	10	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
52	11	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
56	12	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0

1. Above table may be used for I-joist spacing of 24 inches on centre or less.
2. Hole location distance is measured from inside face of supports to centre of hole.
3. Distances in this chart are based on uniformly loaded joists.

OPTIONAL:

The above table is based on the I-joists used at their maximum span. If the I-joists are placed at less than their full maximum span (see Maximum Span, Table 2), the minimum distance from the centreline of the hole to the face of any support (D) as given above may be reduced as follows:

$$\text{Reduced } D = \frac{\text{Actual } D}{\text{SAF}} \times D$$

Where:

- $D_{\text{reduced}} =$ Distance from the inside face of any support to centre of hole, reduced for less-than-maximum span applications (ft). The reduced distance shall not be less than 6 inches from the face of the support to edge of the hole.
 $D_{\text{actual}} =$ The actual measured span distance between the inside faces of supports (ft).
 $\text{SAF} =$ Span Adjustment Factor given in this table.
 $D =$ The minimum distance from the inside face of any support to centre of hole from this table.
 If D_{actual} is greater than 1, use 1 in the above calculation for D_{actual} .

2015-04-16

TABLE 2
DUCT CHASE OPENING SIZES AND LOCATIONS — Simple Span Only

Joist Depth	Joist Series	8	10	12	14	16	18	20	22	24
12	1	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
16	2	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
20	3	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
24	4	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
28	5	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
32	6	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
36	7	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
40	8	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
44	9	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
48	10	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
52	11	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
56	12	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0

1. Above table may be used for I-joist spacing of 24 inches on centre or less.
2. Duct chase opening location distance is measured from inside face of supports to centre of opening.
3. The above table is based on simple-span joists only. For other applications, contact your local distributor.
4. Distances are based on uniformly loaded floor joists that meet the span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. For other applications, contact your local distributor.



Never drill, cut or notch the flange, or over-cut the web.
Holes in webs should be cut with a sharp saw.


For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Starting the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the I-joist.

Knockouts are prescored holes provided for the contractor's convenience to install electrical or small plumbing lines. They are 1-1/2 inches in diameter, and are spaced 15 inches on centre along the length of the I-joist. Where possible, it is preferable to use knockouts instead of field-cut holes.

BRICK CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

5a SHEATHING REINFORCEMENT

Provide full depth blocking between joists over support (not shown)




Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

5b SET-BACK DETAIL

Rim board or wood structural panel closure (3/4" minimum thickness), attach per detail 1b.

Notes:
- Provide full depth blocking between joists over support (not shown for clarity)
- Attach I-joist to plate at all supports per detail 1b.
- 3-1/2" minimum I-joist bearing required.



5c SET-BACK CONNECTION

Vertical solid sawn blocks (2x6 S-P-F No. 2 or better) nailed through joist web and web of girder using 2-1/2" nails.

Notes:
- Verify girder joist capacity, if the back span exceeds the joist spacing.
- Attach double I-joist per detail 1p, if required.






FIGURE 5 (continued)



See table below for NI reinforcement requirements at cantilever.



For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in.)	ROOF TRUSS SPAN (ft)		ROOF LOADING (UNFACTORED)				JOIST SPACING (in.)			
			LL = 30 psf, DL = 15 psf		LL = 40 psf, DL = 15 psf		LL = 50 psf, DL = 15 psf			
			12	16	19.2	24	12	16	19.2	24
2-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
3-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
4-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
5-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
6-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
7-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
8-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
9-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
10-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
11-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
12-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
13-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
14-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
15-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
16-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
17-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
18-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
19-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
20-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
21-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
22-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
23-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
24-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
25-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
26-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
27-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
28-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
29-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
30-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
31-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
32-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
33-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
34-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
35-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
36-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
37-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
38-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
39-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X
40-1/2	26	1	X	X	X	X	2	X	X	X
	30	2	X	X	X	X	2	X	X	X
	32	2	X	X	X	X	2	X	X	X
	34	2	X	X	X	X	2	X	X	X

1. N = No reinforcement required.
2 = NI reinforced with 3/4" wood structural panel on one side only.
3 = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
X = Try a deeper joist or closer spacing.
2. Maximum design load shall be: 15 psf roof dead load, 55 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0" maximum width window or door openings.
3. For larger openings, or multiple 3'-0" with openings spaced less than 6'-0" o.c., additional joists beneath the opening's cripple studs may be required.
4. Table applies to joists

1. Wipe any mud, dirt, water, or ice from I-joist flanges before gluing.
2. Snap a chalk line across the I-joists four feet in from the wall for panel edge alignment and as a boundary for spreading glue.
3. Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from the glue manufacturer.
4. Lay the first panel with tongue side to the wall, and nail in place. This protects the tongue of the next panel from damage when topped into place with a block and sledgehammer.
5. Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-joist. Apply glue in a winding pattern on wide crests, such as with double I-joists.
6. Apply two lines of glue on I-joists where panel ends butt to assure proper gluing of each end.
7. After the first row of panels is in place, spread glue in the groove of one or two panels at a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying a thinner line (1/8 inch) than used on I-joist flanges.
8. Tap the second row of panels into place, using a block to protect groove edges.
9. Stagger end joints in each succeeding row of panels. A 1/8-inch space between all end joints and 1/8-inch at all edges, including T&G edges, is recommended. (Use a spacer tool or an 2-1/2" common nail to assure accurate and consistent spacing.)
10. **Complete all nailing of each panel before glue sets.** Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 2" ring- or screw-shank nails for panels 3/4-inch thick or less, and 2-1/2" ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for diaphragm construction. The finished deck can be walked on right away and will carry construction loads without damage to the glue bond.

Maximum Least Spacing (in.)	Minimum Panel Thickness (in.)	Nail Size and Type			Maximum Spacing of Fasteners	Interm. Supports
		Common Wire or Spiral Nails	Ring Thread Nails or Screws	Staples		
1/2	5/8	2"	1-3/4"	2"	6"	12"
20	5/8	2"	1-3/4"	2"	6"	12"
24	3/4	2"	1-3/4"	2"	6"	12"

1. Fasteners or sheathing and subflooring shall conform to the above table.
2. Staples shall not be less than 1/1.6-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
3. Flooring screws shall not be less than 1/8-inch in diameter.
4. Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
5. Use only adhesives conforming to CAN/CGSB-71.26 Standard, Adhesives for Field-Gluing Plywood to Lumber Framing for Floor System, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues; check with panel manufacturer.

IMPORTANT NOTE:
Floor sheathing must be field glued to the I-joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-joist spans must be verified with your local distributor.

8a ATTACHMENT DETAILS WHERE RIM BOARDS ABOUT

Rim board joint Between Floor Joists

2-1/2" nails at 6' o.c. (typical)

(1) 2-1/2" nail top and bottom (typical)

2-1/2" toe-nails at 6' o.c. (typical)

Rim board joint

Rim board joint at Corner

1-1/2"

h

1-1/2"

Rim board joint

The left diagram is a cross-section of a rim board joint between floor joists. It shows a vertical rim board on the left and a horizontal floor joist on the right. The rim board is attached to the joist with two 2-1/2 inch nails, one at the top and one at the bottom, spaced at 6 feet on center. The rim board is also attached to the wall with 2-1/2 inch toe-nails at 6 feet on center. The rim board joint is shown at the bottom of the rim board. The right diagram is a cross-section of a rim board joint at a corner. It shows a vertical rim board on the left and a horizontal rim board on the right. The rim board is attached to the wall with 1-1/2 inch dimensions. The rim board joint is shown at the bottom of the rim board.

The diagram illustrates a cross-section of a roof edge. A horizontal line represents the top of the roof structure, labeled "Top or sole plate". Below this, a vertical line represents the "Rim board". A diagonal line indicates the roof slope, which is labeled "30°". A dimension line perpendicular to the slope is labeled "l/3".

Existing stud wall

Rim board

Floor sheathing

1x10 joist

Existing foundation wall

2x ledger board (preservative-treated)

2x post

Continuous flashing extending at least 3" past joist hanger

Remove siding at ledger prior to installation

Staggered 1/2" diameter lag screws or thru-bolts with washers

Deck joist

Joist hanger


2x ledger board (preservative-treated); must be greater than or equal to the depth of the deck joist

2015-04-16


PRODUCT WARRANTY

Chemtreat Chibuguman guarantees that, in accordance with our specifications, Novite products are free from manufacturing defects in material and workmanship.

Furthermore, *Canter's Chibogmas* warrants that our products, when utilized in accordance with our handling and installation instructions, will meet or exceed our specifications for the lifetime of the structure.



LVL HEADER AND CONVENTIONAL LUMBER NAILING DETAILS		
DETAIL NUMBER	NUMBER OF ROWS	SPACING (INCHES o/c) "d"
A	2	12
B	2	8
C	2	6
D	2	4
1A	3	12
1B	3	8
1C	3	6
1D	3	4
2A	4	12
2B	4	8
2C	4	6
2D	4	4
3A	5	12
3B	5	8
3C	5	6
3D	5	4
4A	6	12
4B	6	8
4C	6	6
4D	6	4



NOTES:

- (1) MINIMUM LUMBER EDGE DISTANCE "a" = 1"
- (2) MINIMUM LUMBER END DISTANCE "b" = 2"
- (3) MINIMUM NAIL ROW SPACING "c" = 2"
- (4) STAGGER NAILS "d/2" BETWEEN PLYS FOR MULTI-PLY MEMBERS (3 PLY OR MORE)
- (5) ALL NAILS ARE 3-1/2" ARDOX SPIRAL NAILS
- (6) DO NOT USE AIR-DRIVEN NAILS



DWG NO TAMN1001.14

STRUCTURAL

COMPONENT ONLY

TO BE USED ONLY
WITH BEAM CALCS
BEARING THE
SEAL BELOW

PROVIDE NAILING

DETAIL # X SEE

DWG #TAMN1001-14