


10/12 roof pitch unless noted



ASPHALT SHINGLES  
 FINISHED OVERHANG: 12"  
 2x6 EXTERIOR WALLS  
 2x6 FASCIA BOARD  
 HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012 ( 2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012 (2019 amendment ) OCCUPANCY: RESIDENTIAL | PART: 9  
 Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:

- TCSL = 25.6 psf
- TCDL = 6.0 psf
- BCLL = 0.0 psf
- BCDL = 7.4 psf

CITY OF HAWAII  
 Building Department  
 Permit No. 20-187707

HARDWARE:

- LUS24 - (O)
- LJS26DS - (V)
- LUS26-2-(VV)

*Ken Smith* Dec 16, 2020

BEAMS:  
 B1= B2 = B3 =  
 2 - 2x10 SPF #2


DENOTES: CONVENTIONAL FRAMING

M13125

	Job Track: <b>51225</b>	Builder / Location: <b>GREEN PARK HOMES / WATERDOWN</b>	Model / Elevation: <b>MOUNTAINASH 4/1-std or opt.</b>	Milek ver 8.3.1.215
	Plan Log: <b>202401</b>	Project: <b>RUSSELL GARDENS PH.3</b>	THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.	
Layout ID: <b>408150</b>	Date: 2020-04-27	Sales: <b>Mario DiCaro</b>	Designer: <b>JG</b>	

CITY OF HAWAII  
 Building Department  
 Permit No. 20-187707  
 Dec 15 2020

10/12 roof pitch unless noted



ASPHALT SHINGLES  
 FINISHED OVERHANG: 12"  
 2x6 EXTERIOR WALLS  
 2x6 FASCIA BOARD  
 HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012 ( 2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012 (2019 amendment) OCCUPANCY: RESIDENTIAL | PART: 9  
 Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:  
 TCSL = 25.6 psf  
 TCDL = 6.0 psf  
 BCLL = 0.0 psf  
 BCDL = 7.4 psf

HARDWARE:  
 LUS24 - (O)  
 LJS26DS - (V)  
 LUS26-2-(VV)

CITY OF CALGARY  
 Building Department

Permit No. 20-187707

BEAMS:  
 B20 = 2 - 2x10 SPF #2

*Ken Smith* Dec 16, 2020

 DENOTES:  
 CONVENTIONAL  
 FRAMING

M13125



Job Track: 51225  
 Plan Log: 202401  
 Layout ID: 408151


Builder / Location: GREEN PARK HOMES / WATERDOWN  
 Project: RUSSELL GARDENS PH.3  
 Date: 2020-04-27 Sales: Mario DiCano Designer: JG

Model / Elevation: MOUNTAINASH 4/2-std or opt.

Milltek ver 8.3.1.215

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

10/12 roof pitch unless noted



ASPHALT SHINGLES  
 FINISHED OVERHANG: 12"  
 2x6 EXTERIOR WALLS  
 2x6 FASCIA BOARD  
 HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012 (2019 amendment) OCCUPANCY: RESIDENTIAL | PART: 9  
 Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:  
 TCSL = 25.6 psf  
 TCDL = 6.0 psf  
 BCLL = 0.0 psf  
 BCDL = 7.4 psf

CITY OF HAMILTON  
 Building Division

HARDWARE: Permit No. 20-187707-2  
 LUS24 - (O)  
 LJS26DS - (V)  
 LUS26-2-(VV)

THESE STAMPED DRAWINGS SHALL BE AVAILABLE ON SITE  
 THE OWNER AND/OR CONTRACTOR SHALL COMPLY WITH THE ONTARIO BUILDING CODE AND ALL OTHER APPLICABLE LAW

These drawings and/or specifications have been reviewed by  
*Kevin Smith* Oct 8, 2021  
 FOR CHIEF BUILDING OFFICIAL DATE

BEAMS:  
 B20 = 2 - 2x10 SPF #2

 DENOTES: CONVENTIONAL FRAMING

CITY OF HAMILTON  
 BUILDING DIVISION  
 Planning & Development Department  
 SEP 14 2021  
 REC'D BY \_\_\_\_\_ DATE \_\_\_\_\_  
 REF'D TO \_\_\_\_\_ DATE \_\_\_\_\_

M13125




Job Track: 51225  
 Plan Log: 202401  
 Layout ID: 408151

Builder / Location: GREEN PARK HOMES / WATERDOWN  
 Project: RUSSELL GARDENS PH. 4  
 Date: 2020-04-27 Sales: Mario DiCaso Designer: JG

Model / Elevation: MOUNTAINASH 4/2-std or opt. (+ DECK CONDITION WITH REAR UPGRADE)

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC. SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

6/12 roof pitch unless noted



ASPHALT SHINGLES  
 FINISHED OVERHANG: 12"  
 2x6 EXTERIOR WALLS  
 2x6 FASCIA BOARD  
 HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012 (2019 amendment) OCCUPANCY: RESIDENTIAL | PART: 9  
 Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:  
 TCSL = 25.6 psf  
 TCDL = 6.0 psf  
 BCLL = 0.0 psf  
 BCDL = 7.4 psf

HARDWARE:  
 LUS24 - (O)  
 LJS26DS - (V)  
 HGUS26-2 - (XX)  
 LUS26-2-(VV)

BEAMS:  
 B40= B41 = B42= *Lead Smith* Dec 16, 2020  
 2 - 2x10 SPF #2

 DENOTES: CONVENTIONAL FRAMING

CITY OF WATERDOWN  
 Permit No. 20-187707

NOV 15 2020

M13125



Job Track: 51225  
 Plan Log: 202401  
 Layout ID: 408152

Builder / Location: GREEN PARK HOMES / WATERDOWN

Project: RUSSELL GARDENS PH.3


Date: 2020-04-27 Sales: Mario DiCano

Designer: JG

Model / Elevation: MOUNTAINASH 4/3- std. or opt.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mitek ver 8.3.1.215



ASPHALT SHINGLES  
 FINISHED OVERHANG: 12"  
 2x6 EXTERIOR WALLS  
 2x6 FASCIA BOARD  
 HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012 (2019 amendment) OCCUPANCY: RESIDENTIAL | PART: 9  
 CITY OF HAMILTON Building Division  
 Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS: Permit No. 20-187707-2  
 TCSL = 25.6 psf  
 TC DL = 6.0 psf  
 BCLL = 0.0 psf  
 BCDL = 7.4 psf

HARDWARE:  
 LUS24 - (O)  
 LJS26DS - (V)  
 HGUS26-2 - (XX)  
 LUS26-2-(VV)  
 HGUS46 (SS)

BEAMS:  
 B40= B41 = B42=  
 2 - 2x10 SPF #2

CITY OF HAMILTON  
 BUILDING DIVISION  
 Planning & Inspection Department  
 SEP 14 2021  
 REC'D BY \_\_\_\_\_ DATE \_\_\_\_\_  
 REF'D TO \_\_\_\_\_ DATE \_\_\_\_\_

 DENOTES:  
 CONVENTIONAL FRAMING




Job Track: 51225  
 Plan Log: 202401  
 Layout ID: 408152

Builder / Location: GREEN PARK HOMES / WATERDOWN  
 Project: RUSSELL GARDENS PH. 4  
 Date: 2021-04-28 Sales: Mario DiCano Designer: JG

Model / Elevation: MOUNTAINASH 4/3-std. or opt. (+ WALKOUT CONDITION WITH REAR UPGRADE)  
 THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mitak ver 8.4.2:286



# DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER  
 Builder: GREEN PARK HOMES  
 Project: RUSSELL GARDENS PH.3  
 Location: WATERDOWN  
 Model: MOUNTAINASH 4  
 Lot #:  
 Elevation: 1-std or opt.

Job Track: 51225  
 PlanLog: 202401  
 Layout ID: 408150  
 Ref #  
 Page: 1 of 2  
 Date: 04-27-2020  
 Designer:  
 Sales Rep: Mario DiCano

## Roof Trusses

PROFILE	QTY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG		HEEL HEIGHT		LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	PLY						LEFT RIGHT	LEFT RIGHT					
	1 2-ply	T1 Flat Girder	0/12	34-10-00	4-01-04	2 x 6			4-01-04 4-01-04	352.6 214.67			
	1 2-ply	T1Z Flat Girder	0/12	34-10-00	4-01-04	2 x 6			4-01-04 4-01-04	352.6 214.67			
	2	T2 Flat	0/12	34-10-00	5-01-04	2 x 4			5-01-04 5-01-04	288.17 179.67			
	2	T3 Flat	0/12	34-10-00	6-01-04	2 x 4			6-01-04 6-01-04	305.44 187.33			
	2	T4 Flat	0/12	34-10-00	7-01-04	2 x 4			7-01-04 7-01-04	313.23 193.33			
	10	T5 Flat	0/12	34-10-00	8-01-04	2 x 4			8-01-04 8-01-04	1784.6 1100.00			
	1	T6 Hip Girder	10/12	16-07-00	4-10-07	2 x 4 2 x 6	1-03-08 1-03-08		1-07-11 1-07-11	83.68 52.50			
	1	T7 Hip	10/12	16-05-00	6-06-07	2 x 4			1-09-06 1-07-11	69.84 44.00			
	1	T8 Hip	10/12	16-05-00	8-02-07	2 x 4			1-09-06 1-07-11	77.45 49.33			
	1	T9 Common	10/12	16-05-00	8-06-10	2 x 4			1-09-06 1-07-11	76.71 48.83			
	2	T10S Roof Special	10/12	10-11-00	6-02-04	2 x 4	1-03-08 1-03-08		1-07-11 1-07-11	111.52 78.33			
	1	T11 Common	10/12	10-11-00	6-02-04	2 x 4	1-03-08 1-03-08		1-07-11 1-07-11	48.78 32.33			
	1	T12 Common	10/12	7-08-00	5-05-08	2 x 4			2-03-03 2-03-03	35.11 22.50			
	2	T12S Roof Special	10/12	7-08-00	5-05-08	2 x 4			2-03-03 2-03-03	85.22 60.67			



# DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER  
 Builder: GREEN PARK HOMES  
 Project: RUSSELL GARDENS PH.3  
 Location: WATERDOWN  
 Model: MOUNTAINASH 4  
 Lot #:  
 Elevation: 1-std or opt.

Job Track: 51225  
 PlanLog: 202401  
 Layout ID: 408150  
 Ref #  
 Page: 2 of 2  
 Date: 04-27-2020  
 Designer:  
 Sales Rep: Mario DiCano

## Roof Trusses


PROFILE	QTY	MARK	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG		HEEL HEIGHT		LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	PLY	TYPE					LEFT	RIGHT	LEFT	RIGHT			
	1	T15 Hip Girder	0 /12	10-11-00	1-09-07	2 x 4			1-08-15 1-08-15	37.09 24.33			
	4	G60 GABLE	6 /12	22-11-00	8-01-04	2 x 4	1-03-08		1-02-00 8-01-04	463.73 294.00			
	17	P1 Common	6 /12	18-01-00	4-06-04	2 x 4				943.11 612.00			
	2	GP1 Common Supported Gable	6 /12	18-01-00	4-06-04	2 x 4				107.34 68.00			
	21	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08		1-02-00 4-01-04	352.68 224.00			
	1	J2 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08		1-07-11 4-10-07	15.23 9.67			
	6	J3 Jack-Open	4 /12	4-04-08	2-02-06	2 x 4	1-03-08		3-15 1-09-07	71.47 48.00			
	1	C1 Jack-Open	10 /12	1-10-15	3-02-13	2 x 4	1-03-08 1-11-09		1-07-11 3-02-13	12.28 8.33			
	1	C2 Jack-Open	10 /12	1-10-15	3-02-13	2 x 4	1-03-08 1-01		1-07-11 3-02-13	10.4 7.50			

TOTAL # TRUSS= 84 TOTAL BFT OF ALL TRUSSES= 3773.99 BFT. TOTAL WEIGHT OF ALL TRSSES 5996.28 LBS

## HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	LJS26DS	
6	Hardware	LUS24	
4	Hardware	LUS26-2	

TOTAL NUMBER OF ITEMS= 12





# DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER  
 Builder: GREEN PARK HOMES  
 Project: RUSSELL GARDENS PH.3  
 Location: WATERDOWN  
 Model: MOUNTAINASH 4  
 Lot #:  
 Elevation: 2-std or opt.

Job Track: 51225  
 PlanLog: 202401  
 Layout ID: 408151  
 Ref #  
 Page: 1 of 2  
 Date: 04-27-2020  
 Designer:  
 Sales Rep: Mario DiCano

## Roof Trusses

PROFILE	QTY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG		HEEL HEIGHT		LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	PLY						LEFT RIGHT	LEFT RIGHT					
	1 2-ply	T20 Hip Girder	10/12	35-02-00	4-01-11	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	365.29 218.00				
	1 2-ply	T20Z Hip Girder	10/12	35-02-00	4-01-11	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	366.29 218.00				
	2	T21 Hip	10/12	35-02-00	5-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	293.44 185.67				
	2	T22 Hip	10/12	35-02-00	6-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	296.43 188.67				
	2	T23 Hip	10/12	35-02-00	7-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	323.09 204.33				
	2	T24 Hip	10/12	35-02-00	8-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	326.19 204.67				
	2	T25 Hip	10/12	35-02-00	9-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	363.03 228.67				
	4	T26 Hip	10/12	35-02-00	10-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	693.28 432.00				
	2	T27 Hip	10/12	35-02-00	11-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	380.36 236.67				
	2	T28 Common	10/12	16-07-00	8-06-10	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	163.16 102.67				
	1	T29 Common	10/12	16-07-00	9-10-10	2 x 4	1-03-08 1-03-08	2-11-11 2-11-11	90.52 56.67				
	1	T30 Hip	10/12	16-07-00	9-05-12	2 x 4	1-03-08 1-03-08	2-11-11 2-11-11	97.28 61.17				
	1	T31 Hip	10/12	16-07-00	8-05-12	2 x 4	1-03-08 1-03-08	2-11-11 2-11-11	91.81 58.17				
	1	T32 Hip	10/12	16-07-00	7-05-12	2 x 4	1-03-08 1-03-08	2-11-11 2-11-11	79.39 48.83				





# DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER  
 Builder: GREEN PARK HOMES  
 Project: RUSSELL GARDENS PH.3  
 Location: WATERDOWN  
 Model: MOUNTAINASH 4  
 Lot #:  
 Elevation: 2-std or opt.

Job Track: 51225  
 PlanLog: 202401  
 Layout ID: 408151  
 Ref #  
 Page: 2 of 2  
 Date: 04-27-2020  
 Designer:  
 Sales Rep: Mario DiCano

## Roof Trusses


PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T33X Common	10 /12	9-00-00	5-02-03	2 x 4		1-05-03 1-05-03	37.02 25.50		
	1	G33 GABLE	10 /12	8-06-00	5-02-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	41.52 27.83		
	2	T34 Common	10 /12	8-06-00	6-06-03	2 x 4		2-11-11 2-11-11	81.91 52.00		
	2 2-ply	T35 Flat Girder	0 /12	5-10-08	1-04-00	2 x 4		1-04-00 1-04-00	80.16 51.33		
	1	G36 GABLE	10 /12	10-11-00	6-02-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	53.04 35.33		
	2	PB20 Piggyback	10 /12	14-10-03	2-00-00	2 x 4			90.38 60.00		
	21	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	352.68 224.00		


TOTAL # TRUSS= 58      TOTAL BFT OF ALL TRUSSES= 2920.18      BFT.      TOTAL WEIGHT OF ALL TRSSES 4665.24 LBS

## HARDWARE

QTY	TYPE	MODEL	LENGTH
3	Hardware	LJS26DS	
4	Hardware	LUS24	
3	Hardware	LUS26-2	

TOTAL NUMBER OF ITEMS= 10





# DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER  
 Builder: GREEN PARK HOMES  
 Project: RUSSELL GARDENS PH.3  
 Location: WATERDOWN  
 Model: MOUNTAINASH 4  
 Lot #:  
 Elevation: 3- std. or opt.

Job Track: 51225  
 PlanLog: 202401  
 Layout ID: 408152  
 Ref #  
 Page: 1 of 3  
 Date: 04-27-2020  
 Designer:  
 Sales Rep: Mario DiCano

## Roof Trusses

PROFILE	QTY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG		HEEL HEIGHT		LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	PLY						LEFT RIGHT	LEFT RIGHT					
	1 2-ply	T40 Hip Girder	6/12	35-02-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	340.74 212.00				
	1 2-ply	T40Z Hip Girder	6/12	35-02-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	340.74 212.00				
	2	T41 Hip	6/12	35-02-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	277.99 174.00				
	2	T42 Hip	6/12	35-02-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	277.12 174.67				
	2	T43 Hip	6/12	35-02-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	289.07 179.67				
	2	T44 Hip	6/12	35-02-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	290.73 183.33				
	2	T45 Hip	6/12	35-02-00	9-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	301.67 191.33				
	6	T46 Common	6/12	35-02-00	9-11-08	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	910.08 558.00				
	1 2-ply	T47 Hip Girder	6/12	16-07-00	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 2-02-00	156.02 100.67				
	1	T48 Hip	6/12	16-07-00	5-01-04	2 x 4	1-03-08	1-02-00 2-02-00	68.15 43.33				
	1	T49 Common	6/12	16-07-00	5-09-12	2 x 4	1-03-08	1-02-00 2-02-00	67.14 42.33				
	1	T50 Hip Girder	6/12	10-11-00	2-07-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	42.73 28.33				
	1	T51 Hip	6/12	10-11-00	4-07-04	2 x 4	1-03-08 1-03-08	2-02-00 2-02-00	51.54 34.50				
	1	T52 Flat	0/12	9-04-00	2-10-00	2 x 4		2-10-00 2-10-00	36.11 23.83				



# DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER  
 Builder: GREEN PARK HOMES  
 Project: RUSSELL GARDENS PH.3  
 Location: WATERDOWN  
 Model: MOUNTAINASH 4  
 Lot #:  
 Elevation: 3- std. or opt.

Job Track: 51225  
 PlanLog: 202401  
 Layout ID: 408152  
 Ref #  
 Page: 2 of 3  
 Date: 04-27-2020  
 Designer:  
 Sales Rep: Mario DiCano

## Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	G52 GABLE	0/12	9-04-00	2-10-00	2 x 4		2-10-00 2-10-00	33.75 23.33		
	1	T53 Flat Girder	0/12	9-04-00	3-10-00	2 x 6		3-10-00 3-10-00	50.9 31.50		
	1 2-ply	T54 Jack-Closed Girder	6/12	6-10-08	4-01-04	2 x 4 2 x 6		8-00 4-01-04	59.61 37.33		
	15	J1 Jack-Open	6/12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	251.92 160.00		
	4	J40 Jack-Open	6/12	3-09-08	4-01-04	2 x 4		2-02-08 4-01-04	52.34 35.33		
	4	J41 Jack-Open	6/12	2-10-08	2-07-04	2 x 4	1-03-08	1-02-00 2-07-04	38.2 24.00		
	4	C40 Jack-Open	6/12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	56.53 34.67		
	4	C41 Jack-Open	6/12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	46.33 29.33		
	4	C42 Jack-Open	6/12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	38.28 24.00		
	4	C43 Jack-Open	6/12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	28.08 18.67		
	2	C44 Jack-Open	6/12	1-10-15	2-01-08	2 x 4	1-03-08 11-09	1-02-00 2-01-08	16.64 10.67		
	2	C45 Jack-Open	6/12	1-10-15	2-01-08	2 x 4	1-03-08 1-01	1-02-00 2-01-08	14.65 9.33		

TOTAL # TRUSS= 74

TOTAL BFT OF ALL TRUSSES= 2596.15

BFT.

TOTAL WEIGHT OF ALL TRSSES 4137.05 LBS

## HARDWARE

QTY	TYPE	MODEL	LENGTH
1	Hardware	HGUS26-2	
4	Hardware	LJS26DS	




# DELIVERY SHIPLIST


Lumber Yard: TAMARACK LUMBER	Job Track: 51225
Builder: GREEN PARK HOMES	PlanLog: 202401
Project: RUSSELL GARDENS PH.3	Layout ID: 408152
Location: WATERDOWN	Ref #
Model: MOUNTAINASH 4	Page: 3 of 3
Lot #:	Date: 04-27-2020
Elevation: 3- std. or opt.	Designer:
	Sales Rep: Mario DiCano

## HARDWARE

QTY	TYPE	MODEL	LENGTH
5	Hardware	LUS24	
3	Hardware	LUS26-2	

TOTAL NUMBER OF ITEMS= **13**





**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
R - A	2x4	DRY No.2	SPF
A - D	2x6	DRY No.2	SPF
D - F	2x6	DRY No.2	SPF
F - I	2x6	DRY No.2	SPF
I - J	2x4	DRY No.2	SPF
R - P	2x4	DRY No.2	SPF
P - L	2x6	DRY No.2	SPF
L - J	2x6	DRY No.2	SPF

ALL WEBS 2x3 DRY SEASONED LUMBER.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	RECORD BRG
	VERT	HORZ	DOWN	HORZ		
R	3052	0	3052	0	3-8	3-8
J	3118	0	3118	0	3-8	3-8

**UNFACTORED REACTIONS**

JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERMLIVE	WIND	DEAD	SOIL
R	2161	1401 / 0	0 / 0	0 / 0	0 / 0	761 / 0	0 / 0
J	2208	1430 / 0	0 / 0	0 / 0	0 / 0	778 / 0	0 / 0

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL = 25.6 PSF  
 DL = 8.0 PSF

BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF

**TOTAL LOAD = 39.0 PSF**

**SPACING = 24.0 IN/C**

**LOADING IN PLAT SECTION BASED ON A SLOPE OF 6.00/12**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, CBC 2012, ABC 2019  
 - PART 9 OF CBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

(85% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

**CHORDS #ROWS SURFACE SPACING (IN) LOAD(PLF)**

TOP CHORDS : (0.122'X3") SPIRAL NAILS

R-A	1	12	TOP
I-J	1	12	TOP
A-D	2	12	SIDE(183.1)
D-F	2	12	SIDE(0.0)
F-I	2	12	SIDE(0.0)

BOTTOM CHORDS : (0.122'X3") SPIRAL NAILS

R-P	2	12	SIDE(183.1)
P-L	2	12	SIDE(183.1)
L-J	2	12	SIDE(0.0)

WEBS : (0.122'X3") SPIRAL NAILS

2x3	1	6	SIDE(0.0)
-----	---	---	-----------

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED (PLF)		MAX. UNBRAC LENGTH	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
		VERT. LOAD	LC1 MAX				
FR-TO	-2974 / 0	0.0	0.0	0.34 (1)	6.88	K-I	0 / 5093
R-A	-4328 / 0	-91.8	-91.8	0.20 (1)	5.32	A-Q	0 / 5078
A-S	-4328 / 0	-91.8	-91.8	0.20 (1)	5.32	K-H	-2485 / 0
S-T	-4328 / 0	-91.8	-91.8	0.20 (1)	5.32	Q-B	-2483 / 0
T-B	-4328 / 0	-91.8	-91.8	0.25 (1)	4.43	M-H	0 / 2804
B-U	-6696 / 0	-91.8	-91.8	0.25 (1)	4.43	E-D	0 / 2808
U-V	-6696 / 0	-91.8	-91.8	0.25 (1)	4.43	M-G	-1325 / 0
V-C	-6696 / 0	-91.8	-91.8	0.25 (1)	4.43	C-C	-1326 / 0
C-D	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25	N-G	0 / 956
D-W	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25	C-N	0 / 958
W-E	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25	N-E	-651 / 0
E-X	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25		
X-Y	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25		
Y-F	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25		
F-Z	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25		
Z-G	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25		
G-AA	-6698 / 0	-91.8	-91.8	0.26 (1)	4.42		
AA-AB	-6698 / 0	-91.8	-91.8	0.26 (1)	4.42		
AB-AC	-6698 / 0	-91.8	-91.8	0.26 (1)	4.42		
AC-H	-6698 / 0	-91.8	-91.8	0.26 (1)	4.42		
H-AD	-4330 / 0	-91.8	-91.8	0.21 (1)	5.30		
AD-AE	-4330 / 0	-91.8	-91.8	0.21 (1)	5.30		
AE-AF	-4330 / 0	-91.8	-91.8	0.21 (1)	5.30		
AF-I	-4330 / 0	-91.8	-91.8	0.21 (1)	5.30		
I-J	-3028 / 0	0.0	0.0	0.35 (1)	6.64		

ALLOWABLE DEFL.(LL) = L/360 (1.16")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.20")  
 ALLOWABLE DEFL.(TL) = L/360 (1.16")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.38")

CSI: TC=0.35/1.00 (I-J); BC=0.49/1.00 (M-N); WB=0.63/1.00 (K-I); SS=0.17/1.00 (H-I)

DOL LUMBER=1.00 NAIL=1.00 LBS TENS=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PL)	FLX (PL)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	818 354	1667 789	1987 1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.86 (K) (INPUT = 0.90)  
 JSI METAL = 0.42 (P) (INPUT = 1.00)

Structural component only  
 DWG# T-2007063

R-AG	0 / 0	-18.5	-18.5	0.06 (4)	10.00
AG-AH	0 / 0	-18.5	-18.5	0.06 (4)	10.00
AH-Q	0 / 0	-18.5	-18.5	0.06 (4)	10.00
Q-AI	0 / 4328	-18.5	-18.5	0.33 (1)	10.00
AI-P	0 / 4326	-18.5	-18.5	0.33 (1)	10.00
P-D	0 / 4326	-18.5	-18.5	0.33 (1)	10.00
O-AJ	0 / 6696	-18.5	-18.5	0.49 (1)	10.00
AJ-AK	0 / 6696	-18.5	-18.5	0.49 (1)	10.00
AK-N	0 / 6696	-18.5	-18.5	0.49 (1)	10.00
N-AL	0 / 6698	-18.5	-18.5	0.49 (1)	10.00
AL-AM	0 / 6698	-18.5	-18.5	0.49 (1)	10.00
AM-AN	0 / 6698	-18.5	-18.5	0.49 (1)	10.00
AN-M	0 / 6698	-18.5	-18.5	0.49 (1)	10.00
M-AO	0 / 4330	-18.5	-18.5	0.33 (1)	10.00
AO-L	0 / 4330	-18.5	-18.5	0.33 (1)	10.00
L-AP	0 / 4330	-18.5	-18.5	0.33 (1)	10.00
AP-AQ	0 / 4330	-18.5	-18.5	0.33 (1)	10.00
AQ-X	0 / 4330	-18.5	-18.5	0.33 (1)	10.00

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	6.0	9.0	Edge
B	TMVW-t	MT20	5.0	6.0	2.50 2.75
C	TMVW-t	MT20	5.0	6.0	
D	TS-t	MT20	5.0	6.0	
E	TMVW+w	MT20	3.0	6.0	
F	TS-t	MT20	5.0	6.0	
G	TMVW-t	MT20	5.0	6.0	
H	TMVW-t	MT20	5.0	6.0	2.50 2.75
I	TMVW-t	MT20	6.0	9.0	Edge
J	BMV1+p	MT20	3.0	6.0	
K	BMVW-t	MT20	6.0	9.0	3.00 4.25
L	BS-t	MT20	5.0	6.0	
M	BMVW-t	MT20	5.0	6.0	2.50 2.75
N	BMVW-t	MT20	5.0	6.0	
O	BMVW-t	MT20	5.0	6.0	2.50 2.75
P	BS-t	MT20	5.0	6.0	
Q	BMVW-t	MT20	6.0	9.0	3.00 4.25
R	BMV1+p	MT20	3.0	6.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**LOADING**

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
K-AR	0 / 0	-18.5	-18.5	0.06 (4)	10.00		
AR-AS	0 / 0	-18.5	-18.5	0.06 (4)	10.00		
AS-AT	0 / 0	-18.5	-18.5	0.06 (4)	10.00		
AT-J	0 / 0	-18.5	-18.5	0.06 (4)	10.00		


**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
B	5-10-12	-110	-110		FRONT	VERT	TOTAL		C1
C	11-10-12	-110	-110		FRONT	VERT	TOTAL		C1
D	13-10-12	-110	-110		FRONT	VERT	TOTAL		C1
O	11-10-12	-26	-26		FRONT	VERT	TOTAL		C1
P	9-10-12	-26	-26		FRONT	VERT	TOTAL		C1
Q	5-10-12	-26	-26		FRONT	VERT	TOTAL		C1
S	1-10-12	-110	-110		FRONT	VERT	TOTAL		C1
T	3-10-12	-110	-110		FRONT	VERT	TOTAL		C1
U	7-10-12	-110	-110		FRONT	VERT	TOTAL		C1
V	9-10-12	-110	-110		FRONT	VERT	TOTAL		C1
W	15-10-12	-110	-110		FRONT	VERT	TOTAL		C1
X	17-10-12	-110	-110		FRONT	VERT	TOTAL		C1
Y	19-10-12	-110	-110		FRONT	VERT	TOTAL		C1
Z	21-10-12	-110	-110		FRONT	VERT	TOTAL		C1
AA	23-10-12	-110	-110		FRONT	VERT	TOTAL		C1
AB	25-10-12	-110	-110		FRONT	VERT	TOTAL		C1
AC	27-10-12	-110	-110		FRONT	VERT	TOTAL		C1
AD	29-10-12	-110	-110		FRONT	VERT	TOTAL		C1
AE	31-10-12	-110	-110		FRONT	VERT	TOTAL		C1
AF	33-10-12	-113	-113		FRONT	VERT	TOTAL		C1
AG	1-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AH	3-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AI	7-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AJ	13-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AK	15-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AL	17-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AM	19-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AN	21-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AO	23-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AP	25-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AQ	27-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AR	29-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AS	31-10-12	-26	-26		FRONT	VERT	TOTAL		C1
AT	33-10-12	-27	-27		FRONT	VERT	TOTAL		C1

**CONNECTION REQUIREMENTS**

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.





**LUMBER**

N. L. G. A. RULES	SIZE	DRY	LUMBER	DESCR.
R - A	2x4	DRY	No.2	SPF
A - D	2x6	DRY	No.2	SPF
D - F	2x6	DRY	No.2	SPF
F - I	2x6	DRY	No.2	SPF
J - L	2x4	DRY	No.2	SPF
R - P	2x6	DRY	No.2	SPF
P - L	2x6	DRY	No.2	SPF
L - J	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY: SEASONED LUMBER. No.2 SPF

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
R - A	12	TOP
I - J	12	TOP
A - D	12	SIDE(0.0)
D - F	12	SIDE(183.1)
F - I	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
R - P	12	SIDE(0.0)
P - L	12	SIDE(183.1)
L - J	12	TOP
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY. GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
R	4002	0	4002	0
J	3132	0	3132	0

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
R	2824	1885/0	0/0	0/0	0/0	938/0	0/0
J	2212	1470/0	0/0	0/0	0/0	742/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.64 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	FORCE (LBS)	VERT. LOAD	HORZ. LOAD	MAX. CSI (LC)	UNBRAC LENGTH	FR-TO	WEBS	MEMB.	FORCE (LBS)	MAX. CSI (LC)
R-A	-3851/0	0.0	0.0	0.44 (1)	6.01	K-I	0/5426	0.67 (1)		
A-S	-5722/0	-91.8	-91.8	0.25 (1)	4.72	A-Q	0/6717	0.83 (1)		
S-T	-5722/0	-91.8	-91.8	0.25 (1)	4.72	K-H	-2763/0	0.33 (1)		
T-B	-5722/0	-91.8	-91.8	0.25 (1)	4.72	Q-B	-2710/0	0.32 (1)		
B-C	-8846/0	-91.8	-91.8	0.27 (1)	3.93	M-H	0/4038	0.50 (1)		
C-D	-10219/0	-91.8	-91.8	0.34 (1)	3.64	B-O	0/3700	0.46 (1)		
D-U	-10219/0	-91.8	-91.8	0.34 (1)	3.64	M-G	-1901/0	0.23 (1)		
U-E	-10219/0	-91.8	-91.8	0.34 (1)	3.64	O-C	-1400/0	0.17 (1)		
E-V	-10219/0	-91.8	-91.8	0.31 (1)	3.67	N-G	0/2591	0.82 (1)		
V-F	-10219/0	-91.8	-91.8	0.31 (1)	3.67	C-N	0/1626	0.20 (1)		
F-G	-10219/0	-91.8	-91.8	0.31 (1)	3.67	N-E	-710/0	0.08 (1)		
G-H	-8031/0	-91.8	-91.8	0.23 (1)	4.14					
H-I	-4622/0	-91.8	-91.8	0.15 (1)	5.25					
I-J	-3871/0	0.0	0.0	0.35 (1)	6.50					

MEMB.	FORCE (LBS)	VERT. LOAD	HORZ. LOAD	MAX. CSI (LC)	UNBRAC LENGTH	FR-TO	WEBS	MEMB.	FORCE (LBS)	MAX. CSI (LC)
R-W	0/0	-18.5	-18.5	0.15 (1)	10.00					
W-X	0/0	-18.5	-18.5	0.15 (1)	10.00					
X-Y	0/0	-18.5	-18.5	0.15 (1)	10.00					
Y-Q	0/0	-18.5	-18.5	0.15 (1)	10.00					
Q-P	0/5722	-18.5	-18.5	0.44 (1)	10.00					
P-O	0/5722	-18.5	-18.5	0.44 (1)	10.00					
O-Z	0/8846	-18.5	-18.5	0.81 (1)	10.00					
Z-AA	0/8846	-18.5	-18.5	0.81 (1)	10.00					
AA-N	0/8846	-18.5	-18.5	0.81 (1)	10.00					
N-AB	0/8031	-18.5	-18.5	0.74 (1)	10.00					
AB-AC	0/8031	-18.5	-18.5	0.74 (1)	10.00					
AC-M	0/8031	-18.5	-18.5	0.74 (1)	10.00					
M-L	0/4822	-18.5	-18.5	0.33 (1)	10.00					
L-K	0/4822	-18.5	-18.5	0.33 (1)	10.00					
K-J	0/0	-18.5	-18.5	0.04 (4)	10.00					

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
S	1-10-12	-110	-110	---	BACK	VERT	TOTAL	C1
T	3-10-12	-110	-110	---	BACK	VERT	TOTAL	C1
U	15-8-12	-110	-110	---	BACK	VERT	TOTAL	C1
V	17-8-12	-110	-110	---	BACK	VERT	TOTAL	C1
W	1-10-12	-26	-26	---	BACK	VERT	TOTAL	C1
X	3-10-12	-26	-26	---	BACK	VERT	TOTAL	C1
Y	5-1-8	-727	-727	---	BACK	VERT	TOTAL	C1
Z	13-0-8	-727	-727	---	BACK	VERT	TOTAL	C1
AA	15-8-12	-26	-26	---	BACK	VERT	TOTAL	C1
AB	17-8-12	-26	-26	---	BACK	VERT	TOTAL	C1

**DESIGN CRITERIA**

SPECIFIED LOADS:  
 TOP CH. LL = 25.6 PSF  
 BOT CH. LL = 8.0 PSF  
 DL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/CIC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, CBC 2012, ABC 2019  
 - PART 9 OF CBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 088-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.18")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.28")  
 ALLOWABLE DEFL.(TL) = L/360 (1.18")  
 CALCULATED VERT. DEFL.(TL) = L/828 (0.50")

CSI: TC=0.44/1.00 (A-R:1), BC=0.81/1.00 (N-C:1),  
 WB=0.83/1.00 (A-Q:1), SS=0.41/1.00 (M-N:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00  
 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354 1667 788 1987 1656	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.88 (M) (INPUT = 0.90)  
 JSI METAL = 0.50 (F) (INPUT = 1.00)



Structural component only  
 DWG# T-2007064 1/2

JOB NAME 408150	TRUSS NAME T1Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:02:49 2020 Page 2  
 ID: i7vF?aG0E03cRU6X1SrkziWYK-SrpIvVtQ3 UVGPVZTPnKeJDIEFIF7bWic7 NRrzNCna

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	6.0	9.0		Edge
B	TMWW-t	MT20	5.0	6.0	2.50	2.75
C	TMWW-t	MT20	5.0	6.0		
D	TS-t	MT20	5.0	6.0		
E	TMW+w	MT20	3.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMWW-t	MT20	5.0	6.0		
H	TMWW-t	MT20	5.0	6.0	2.50	2.75
I	TMVW-t	MT20	6.0	9.0		Edge
J	BMV1+p	MT20	3.0	6.0		
K	BMWW-t	MT20	6.0	9.0	3.00	4.25
L	BS-t	MT20	5.0	6.0		
M	BMWW-t	MT20	5.0	6.0	2.50	2.75
N	BMWW-t	MT20	5.0	6.0		
O	BMWW-t	MT20	5.0	6.0	2.50	2.75
P	BS-t	MT20	5.0	6.0		
Q	BMWW-t	MT20	6.0	9.0	3.00	4.25
R	BMV1+p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
AC	18-3-8	-1293	-1293		BACK	VERT	TOTAL		C1


**CONNECTION REQUIREMENTS**

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only  
 DWG# T-2007064





**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	LUMBER
R - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
C - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
J - L	2x4	DRY	No.2
R - O	2x4	DRY	No.2
O - M	2x4	DRY	No.2
M - J	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-I	MT20	5.0	6.0	2.00 2.25
B	TMVW-I	MT20	5.0	6.0	
C	TS-I	MT20	3.0	5.0	
D	TMVW-I	MT20	4.0	4.0	
E	TMVW-I	MT20	2.0	4.0	
F	TMVW-I	MT20	4.0	4.0	
G	TS-I	MT20	3.0	5.0	
H	TMVW-I	MT20	5.0	6.0	
I	TMVW-I	MT20	5.0	6.0	2.00 2.25
J	BMV1+p	MT20	3.0	4.0	
K	BMVW-I	MT20	5.0	6.0	2.00 2.25
L	BMVW-I	MT20	5.0	6.0	
M	SS-I	MT20	3.0	8.0	
N	BMVWVW-I	MT20	4.0	9.0	
O	SS-I	MT20	3.0	8.0	
P	BMVWVW-I	MT20	5.0	6.0	
Q	BMVWVW-I	MT20	5.0	6.0	2.00 2.25
R	BMV1+p	MT20	3.0	4.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
R	1920	0	1920	0	3-8	3-8
J	1920	0	1920	0	3-8	3-8

**UNFACTORED REACTIONS**

JT	1ST CASE		MAX. MIN. COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
R	1359	891/0	0/0	0/0	0/0	467/0	0/0
J	1359	891/0	0/0	0/0	0/0	467/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.23 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	FR-TO	CHORDS		WEBS	
		MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. MEMB. FORCE (LBS)	MAX. FACTORED FORCE (LBS)
R-A	-1875/0	0.0	0.0	0.83 (1)	6.13
A-B	-2042/0	-91.8	-91.8	0.59 (1)	4.10
B-C	-3149/0	-91.8	-91.8	0.74 (1)	3.28
C-D	-3149/0	-91.8	-91.8	0.74 (1)	3.28
D-E	-3533/0	-91.8	-91.8	0.68 (1)	3.23
E-F	-3533/0	-91.8	-91.8	0.68 (1)	3.23
F-G	-3149/0	-91.8	-91.8	0.74 (1)	3.28
G-H	-3149/0	-91.8	-91.8	0.74 (1)	3.28
H-I	-2042/0	-91.8	-91.8	0.59 (1)	4.10
I-J	-1875/0	0.0	0.0	0.83 (1)	6.13
R-Q	0/0	-18.5	-18.5	0.15 (4)	10.00
Q-P	0/2042	-18.5	-18.5	0.40 (1)	10.00
P-O	0/3149	-18.5	-18.5	0.56 (1)	10.00
O-N	0/3149	-18.5	-18.5	0.56 (1)	10.00
N-M	0/3149	-18.5	-18.5	0.56 (1)	10.00
M-L	0/3149	-18.5	-18.5	0.56 (1)	10.00
L-K	0/2042	-18.5	-18.5	0.40 (1)	10.00
K-J	0/0	-18.5	-18.5	0.15 (4)	10.00

TOTAL WEIGHT = 2 X 143 = 286 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 8.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, CBC 2012, ABC 2019  
 - PART 9 OF CBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.23")  
 ALLOWABLE DEFL.(TL) = L/360 (1.16")  
 CALCULATED VERT. DEFL.(TL) = L/995 (0.42")

CSI=TC=0.03/1.00 (A-R:1), BC=0.56/1.00 (N-P:1),  
 WB=0.59/1.00 (I-K:1), SS=0.25/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PL)
MT20	618	354
	1657	788
	1987	1658


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.89 (A) (INPUT = 0.90)  
 JSI METAL=0.99 (M) (INPUT = 1.00)



Structural component only  
 DWG# T-2007065



**LUMBER**  
 N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
R - A	2x4	DRY No.2	SPF
A - C	2x4	DRY No.2	SPF
C - G	2x4	DRY No.2	SPF
G - I	2x4	DRY No.2	SPF
J - I	2x4	DRY No.2	SPF
R - O	2x4	DRY No.2	SPF
O - M	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
DRY: SEASONED LUMBER.			

**PLATES (table in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMWV-1	MT20	5.0	6.0	2.00	2.50
B	TMWV-1	MT20	5.0	6.0		
C	TS-1	MT20	3.0	6.0		
D	TMWV-1	MT20	4.0	4.0		
E	TMWV-1	MT20	2.0	4.0		
F	TMWV-1	MT20	4.0	4.0		
G	TS-1	MT20	3.0	6.0		
H	TMWV-1	MT20	5.0	6.0		
I	TMWV-1	MT20	5.0	6.0	2.00	2.50
J	BMV1+p	MT20	3.0	4.0		
K	BMWV-1	MT20	5.0	6.0	2.00	2.50
L	BMWV-1	MT20	5.0	6.0		
M	BS-1	MT20	3.0	6.0		
N	BMWV-1	MT20	4.0	9.0		
O	BS-1	MT20	3.0	6.0		
P	BMWV-1	MT20	3.0	8.0		
Q	BMWV-1	MT20	5.0	6.0	2.00	2.50
R	BMV1+p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	REQRD
R	1920	0	1920	0	0	3-8	3-8	3-8
J	1920	0	1920	0	0	3-8	3-8	3-8

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERMALIVE	WIND	DEAD	SOIL
R	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0
J	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLINE SPACING = 3.59 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-R, I-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)			MAX. UNBRAC LENGTH	WEBS MEMB.	MAX. FACTORED FORCE (LBS)	
		FROM TO	CS1 (LC)	MAX			CS1 (LC)	MAX
FR-TO								
R-A	-1875 / 0	0.0	0.0	0.33 (1)	4.90	K-I	0 / 2368	0.53 (1)
A-B	-1691 / 0	-91.8	-91.8	0.55 (1)	4.46	A-Q	0 / 2368	0.53 (1)
B-C	-2608 / 0	-91.8	-91.8	0.86 (1)	3.63	K-H	-1536 / 0	0.80 (1)
C-D	-2608 / 0	-91.8	-91.8	0.86 (1)	3.63	Q-B	-1536 / 0	0.90 (1)
D-E	-2627 / 0	-91.8	-91.8	0.86 (1)	3.59	L-H	0 / 1304	0.29 (1)
E-F	-2627 / 0	-91.8	-91.8	0.86 (1)	3.59	B-P	0 / 1304	0.29 (1)
F-G	-2608 / 0	-91.8	-91.8	0.86 (1)	3.63	L-F	-826 / 0	0.48 (1)
G-H	-2608 / 0	-91.8	-91.8	0.86 (1)	3.63	P-D	-826 / 0	0.48 (1)
H-I	-1891 / 0	-91.8	-91.8	0.55 (1)	4.48	N-F	0 / 453	0.10 (1)
I-J	-1875 / 0	0.0	0.0	0.33 (1)	4.90	D-N	0 / 453	0.10 (1)
						N-E	-537 / 0	0.31 (1)
R-Q	0 / 0	-18.5	-18.5	0.15 (4)	10.00			
Q-P	0 / 1891	-18.5	-18.5	0.35 (1)	10.00			
P-O	0 / 2608	-18.5	-18.5	0.47 (1)	10.00			
O-N	0 / 2608	-18.5	-18.5	0.47 (1)	10.00			
N-M	0 / 2608	-18.5	-18.5	0.47 (1)	10.00			
M-L	0 / 2608	-18.5	-18.5	0.47 (1)	10.00			
L-K	0 / 1691	-18.5	-18.5	0.35 (1)	10.00			
K-J	0 / 0	-18.5	-18.5	0.15 (4)	10.00			

TOTAL WEIGHT = 2 X 153 = 305 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

15% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.18")  
 ALLOWABLE DEFL.(TL) = L/360 (1.16")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.33")  
 CSI: TC=0.66/1.00 (F-H:1), BC=0.47/1.00 (N-P:1),  
 WB=0.80/1.00 (H-K:1), SSI=0.25/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)  
 MAX MIN MAX MIN MAX MIN  
 MT20 618 354 1687 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.88 (1) (INPUT = 0.90)  
 JSI METAL= 0.83 (4) (INPUT = 1.00)



Structural component only  
 DWG# T-2007066

JOB NAME 408150	TRUSS NAME T4	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitok Industries, Inc. Sat Apr 25 11:02:52 2020 Page 1  
 ID:7vF7aG0E03cRUj6X1jSrkziWYK-sQUQ8wVJMv47tE88XL1GyrhNSOJK?q9W4C12AzlNCnX



**LUMBER**  
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
P - A	2x4	DRY No.2	SPF
A - C	2x4	DRY No.2	SPF
C - F	2x4	DRY No.2	SPF
F - H	2x4	DRY No.2	SPF
I - H	2x4	DRY No.2	SPF
P - N	2x4	DRY No.2	SPF
N - K	2x4	DRY No.2	SPF
K - L	2x4	DRY No.2	SPF
ALL WEBS EXCEPT J - H	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	5.0	6.0	2.25	2.00
B	TMVW-t	MT20	4.0	6.0		
C	TS-t	MT20	3.0	6.0		
D	TMVW-t	MT20	4.0	4.0		
E	TMVW-w	MT20	2.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMVW-t	MT20	4.0	6.0		
H	TMVW-t	MT20	5.0	6.0	2.50	2.50
I	BMV1+p	MT20	3.0	4.0		
J	BMVW-t	MT20	5.0	6.0	2.50	2.50
K	BS-t	MT20	3.0	6.0		
L	BMVW-w	MT20	4.0	9.0		
M	BMVW-t	MT20	4.0	6.0		
N	BS-t	MT20	3.0	6.0		
O	BMVW-t	MT20	5.0	8.0	2.00	2.50
P	BMV1+p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
P	VERT	DOWN	IN-SX	IN-SX
P	1920	0	3-8	3-8
I	1920	0	3-8	3-8

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX. MIN. SNOW	MAX. MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
P	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0
I	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, I

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. FURLIN SPACING = 3.31 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-P, H-I, B-O, D-L, G-J.  
END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX (LC)	MEMB. FORCE (LBS)	MAX FACTORED FORCE (LBS)	MAX (LC)	UNBRACED LENGTH (LC)
P-A	-1868 / 0	0.0	0.0	0.43 (1)	4.91	A-O	0 / 2315	0.52 (1)
A-B	-1862 / 0	-91.8	-91.8	0.82 (1)	4.04	C-B	-1465 / 0	0.47 (1)
B-C	-2416 / 0	-91.8	-91.8	0.95 (1)	3.33	B-M	0 / 1059	0.24 (1)
C-D	-2416 / 0	-91.8	-91.8	0.96 (1)	3.33	M-D	-817 / 0	0.54 (1)
D-E	-2415 / 0	-91.8	-91.8	0.74 (1)	3.73	D-L	-2 / 0	0.00 (1)
E-F	-2415 / 0	-91.8	-91.8	0.96 (1)	3.31	L-E	-616 / 0	0.54 (1)
F-G	-2415 / 0	-91.8	-91.8	0.96 (1)	3.31	L-G	0 / 1054	0.24 (1)
G-H	-1863 / 0	-91.8	-91.8	0.82 (1)	4.02	J-G	-1465 / 0	0.47 (1)
H-I	-1868 / 0	0.0	0.0	0.43 (1)	4.91	J-H	0 / 2316	0.37 (1)
P-O	0 / 0	-18.5	-18.5	0.22 (4)	10.00			
C-N	0 / 1862	-18.5	-18.5	0.39 (1)	10.00			
N-M	0 / 1862	-18.5	-18.5	0.39 (1)	10.00			
M-L	0 / 2416	-18.5	-18.5	0.47 (1)	10.00			
L-K	0 / 1863	-18.5	-18.5	0.39 (1)	10.00			
K-J	0 / 1863	-18.5	-18.5	0.39 (1)	10.00			
J-I	0 / 0	-18.5	-18.5	0.22 (4)	10.00			

TOTAL WEIGHT = 2 X 157 = 313 lb

**DESIGN CRITERIA**

SPECIFIED LOADS:  
 TOP CH. LL = 25.8 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L PLUS 6.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")  
 CALCULATED VERT. DEFL.(LL) = L/899 (0.15")  
 ALLOWABLE DEFL.(TL) = L/360 (1.16")  
 CALCULATED VERT. DEFL.(TL) = L/899 (0.29")

CSI: TC=0.96/1.00 (E-G:1), BC=0.47/1.00 (L-M:1),  
 WB=0.54/1.00 (D-M:1), SS=0.30/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00.

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES  
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)  
 MAX MIN MAX MIN MAX MIN  
 MT20 618 354 1667 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.90 (A) (INPUT = 0.90)  
 JSI METAL = 0.53 (K) (INPUT = 1.00)



Structural component only  
 DWG# T-2007067



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
P - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
P - N	2x4	DRY	No.2	SPF
N - K	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF

ALL WEBS EXCEPT

J	G	O	B	L	E	M	D
2x4	DRY	No.2	SPF	2x3	DRY	No.2	SPF
2x3	DRY	No.2	SPF	2x3	DRY	No.2	SPF
2x3	DRY	No.2	SPF	2x3	DRY	No.2	SPF
2x3	DRY	No.2	SPF	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMW-t	MT20	5.0	6.0	2.50	2.50
B	TMW-t	MT20	4.0	6.0		
C	TS-t	MT20	3.0	6.0		
D	TMW-t	MT20	2.0	4.0		
E	TMW-t	MT20	4.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMW-t	MT20	4.0	6.0		
H	TMW-t	MT20	5.0	6.0	2.50	2.50
I	BMV1-p	MT20	3.0	4.0		
J	BMW-t	MT20	5.0	6.0	2.50	2.50
K	BS-t	MT20	3.0	6.0		
L	BMW-t	MT20	4.0	6.0		
M	BMW-t	MT20	4.0	6.0		
N	BS-t	MT20	3.0	6.0		
O	BMW-t	MT20	5.0	6.0	2.50	2.50
P	BMV1-p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
P	1920 0	1920 0	3-8	3-8
I	1920 0	1920 0	3-8	3-8

**UNFACTORED REACTIONS**

JT	1ST CASE COMBINED	MAX. MIN. SNOW	MIN. COMPONENT LIVE	PERM. LIVE	WIND	DEAD	SOIL
P	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0
I	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, I

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.56 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-P, H-I, G-J, B-O, E-M.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LCI MAX CSI (LC)	MEMB. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
P-A	-1668 / 0	0.0	0.0 0.55 (1)	4.91	J-H	0 / 2171 0.35 (1)
A-B	-1458 / 0	-91.8	-91.8 0.80 (1)	4.26	A-O	0 / 2171 0.35 (1)
B-C	-2108 / 0	-91.8	-91.8 0.90 (1)	3.58	J-G	-1463 / 0 0.81 (1)
C-D	-2108 / 0	-91.8	-91.8 0.90 (1)	3.58	C-B	-1462 / 0 0.81 (1)
D-E	-2108 / 0	-91.8	-91.8 0.88 (1)	4.00	L-G	0 / 982 0.16 (1)
E-F	-2108 / 0	-91.8	-91.8 0.90 (1)	3.56	B-M	0 / 980 0.16 (1)
F-G	-2108 / 0	-91.8	-91.8 0.90 (1)	3.56	L-E	-613 / 0 0.78 (1)
G-H	-1458 / 0	-91.8	-91.8 0.79 (1)	4.27	M-D	-612 / 0 0.77 (1)
H-I	-1668 / 0	0.0	0.0 0.55 (1)	4.91	M-E	-2 / 0 0.00 (1)
P-O	0 / 0	-18.5	-18.5 0.22 (4)	10.00		
O-N	0 / 1458	-18.5	-18.5 0.36 (1)	10.00		
N-M	0 / 1458	-18.5	-18.5 0.36 (1)	10.00		
M-L	0 / 2108	-18.5	-18.5 0.42 (1)	10.00		
L-K	0 / 1458	-18.5	-18.5 0.36 (1)	10.00		
K-J	0 / 1458	-18.5	-18.5 0.36 (1)	10.00		
J-I	0 / 0	-18.5	-18.5 0.22 (4)	10.00		

TOTAL WEIGHT = 10 X 178 = 1785 lbs

**DESIGN CRITERIA**

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF

BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.12")  
ALLOWABLE DEFL.(TL) = L/360 (1.16")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.24")

CSI: TC=0.90/1.00 (B-D:1), BC=0.42/1.00 (L-M:1), WB=0.78/1.00 (E-L:1), SS=0.31/1.00 (A-B:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI)


MT20	618	354	1667	788	1967	1656
------	-----	-----	------	-----	------	------

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.87 (A) (INPUT = 0.90)  
JSI METAL = 0.47 (N) (INPUT = 1.00)





**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	DRY	No.2	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
M - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
M - J	2x6	DRY	No.2	SPF
J - H	2x6	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMW+P	MT20	5.0	6.0	Edge 2.75
C	TTW+M	MT20	5.0	8.0	2.00 1.50
D	TMW+M	MT20	2.0	4.0	
E	TTW+M	MT20	5.0	8.0	2.00 1.50
F	TMW+P	MT20	5.0	8.0	Edge 2.75
H	BMV1+P	MT20	3.0	6.0	
I	BMWV-1	MT20	5.0	8.0	2.50 2.75
J	BS-1	MT20	5.0	8.0	
K	BMWVW-1	MT20	5.0	8.0	
L	BMWV-1	MT20	5.0	8.0	2.50 2.75
M	BMV1+P	MT20	3.0	6.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION VERT	FACTORED GROSS REACTION HORZ	MAXIMUM FACTORED GROSS REACTION DOWN	INFLT BRG	REORD BRG
JT	1888	0	1888	0	0
M	1422	0	1422	0	0
H	1422	0	1422	0	0

**UNFACTORED REACTIONS**

JT	1ST LGASE	MAX MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
JT	1329	909 / 0	0 / 0	0 / 0	0 / 0	0 / 0	420 / 0	0 / 0
M	1001	683 / 0	0 / 0	0 / 0	0 / 0	0 / 0	318 / 0	0 / 0
H	1001	683 / 0	0 / 0	0 / 0	0 / 0	0 / 0	318 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M, H

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.56 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	CHORDS		WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MAX. UNBRACED LENGTH	
FR-TO		FROM TO		FR-TO	
A-B	0 / 41	-91.8	-91.8	0.14 (1)	10.00
B-C	-1847 / 0	-91.8	-91.8	0.34 (1)	4.55
C-D	-1841 / 0	-91.8	-91.8	0.36 (1)	4.72
D-E	-1641 / 0	-91.8	-91.8	0.36 (1)	4.72
E-F	-1225 / 0	-91.8	-91.8	0.30 (1)	5.40
F-G	0 / 41	-91.8	-91.8	0.14 (1)	10.00
M-B	-1928 / 0	0.0	0.0	0.22 (1)	6.01
H-F	-1380 / 0	0.0	0.0	0.16 (1)	8.88
M-N	0 / 0	-18.5	-18.5	0.24 (1)	10.00
N-L	0 / 0	-18.5	-18.5	0.24 (1)	10.00
L-O	0 / 1424	-18.5	-18.5	0.70 (1)	10.00
O-K	0 / 1424	-18.5	-18.5	0.70 (1)	10.00
K-J	0 / 932	-18.5	-18.5	0.29 (1)	10.00
J-I	0 / 932	-18.5	-18.5	0.29 (1)	10.00
I-H	0 / 0	-18.5	-18.5	0.04 (4)	10.00

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	3-10-8	-241	-241	---	FRONT	VERT	TOTAL	---	C1
L	3-11-4	-17	-17	---	FRONT	VERT	TOTAL	---	C1
N	2-0-12	-17	-17	---	FRONT	VERT	TOTAL	---	C1
O	5-6-8	-953	-953	---	FRONT	VERT	TOTAL	---	C1

**CONNECTION REQUIREMENTS**  
1) C1: A SUITABLE HANGER MECHANICAL CONNECTION IS REQUIRED.

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF ECBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 089-09, CSA 089-14  
- TPC 2011, TPC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = 1/360 (0.55")  
CALCULATED VERT. DEFL.(LL) = 1/999 (0.06")  
ALLOWABLE DEFL.(TL) = 1/360 (0.55")  
CALCULATED VERT. DEFL.(TL) = 1/999 (0.10")

CSI: TC=0.36/1.00 (C-D:1), BC=0.70/1.00 (K-L:1), WB=0.37/1.00 (B-L:1), SS=0.45/1.00 (K-L:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1687 789 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (C) (INPUT = 0.90)  
JSI METAL = 0.57 (J) (INPUT = 1.00)

TOTAL WEIGHT = 84 lb





**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - B	2x4	DRY	No.2	SPF	
B - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
I - A	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TTWW+m	MT20	5.0	6.0	2.25	1.50
C	TTW-m	MT20	4.0	4.0		
D	TMVW+p	MT20	4.0	4.0	1.00	2.00
E	BMV1+p	MT20	3.0	4.0		
F	BMVWV-t	MT20	4.0	9.0		
G	BS-t	MT20	3.0	6.0		
H	BMVW-t	MT20	4.0	4.0		
I	BMV1+p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	DOWN	UP/LIFT	IN-SX
I	905	0	0	3-8
E	905	0	0	5-8

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX/MIN SNOW	MAX/MIN LIVE	PERM LIVE	WIND	DEAD	SOIL
I	840	420/0	0/0	0/0	0/0	220/0	0/0
E	840	420/0	0/0	0/0	0/0	220/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, E

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	FR-TO	CHORDS			MAX. UNBRAC LENGTH	FR-TO	WEBS		
		MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 (LC)			MEMB.	MAX. FACTORED FORCE (LBS)	MAX LC1 (LC)
A-B		-718/0	-91.8	-91.8	0.39 (1)	6.25	H-B	-34/68	0.02 (4)
B-C		-558/0	-91.8	-91.8	0.28 (1)	6.25	B-F	0/14	0.00 (1)
C-D		-728/0	-91.8	-91.8	0.42 (1)	6.25	F-C	-23/74	0.03 (4)
I-A		-860/0	0.0	0.0	0.09 (1)	7.81	A-H	0/567	0.13 (1)
E-D		-868/0	0.0	0.0	0.09 (1)	7.81	F-D	0/572	0.13 (1)
I-H		0/0	-18.5	-18.5	0.13 (4)	10.00			
H-G		0/550	-18.5	-18.5	0.18 (4)	10.00			
G-F		0/550	-18.5	-18.5	0.18 (4)	10.00			
F-E		0/0	-18.5	-18.5	0.14 (4)	10.00			

TOTAL WEIGHT = 70 lb [M/F]

**DESIGN CRITERIA**

SPECIFIED LOADS:  
 TOP CH. LL = 25.6 PSF  
 DL = 8.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 0.0 PSF  
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, CBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 088-09, CSA 088-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.01")  
 ALLOWABLE DEFL.(TL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.42/1.00 (C-D:1), BC=0.18/1.00 (F-H:4), WB=0.13/1.00 (D-F:1), SSI=0.17/1.00 (B-C:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP (DRY) (PSI)	SHEAR SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667	788 1987 1659


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.85 (D) (INPUT = 0.90)  
 JSI METAL = 0.24 (D) (INPUT = 1.00)



Structural component only  
 DWG# T-2007070



**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER
A - C	2x4	DRY	No.2	
C - D	2x4	DRY	No.2	
D - F	2x4	DRY	No.2	
J - A	2x4	DRY	No.2	
G - F	2x4	DRY	No.2	
J - H	2x4	DRY	No.2	
H - G	2x4	DRY	No.2	

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

**PLATES (table ts in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
B	TMWW-t	MT20	4.0	6.0		
C	TTW-m	MT20	4.0	4.0		
D	TTW-m	MT20	4.0	4.0		
E	TMWW-t	MT20	4.0	6.0		
F	TMV+p	MT20	3.0	4.0		
G	BMVW1-t	MT20	4.0	4.0		
H	BS-t	MT20	3.0	6.0		
I	BMVWWW*4	MT20	5.0	12.0	3.00	6.00
J	BMVW1-t	MT20	4.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED DOWN	INPUT BRG	RECORD BRG
JT	VERT	HORZ	UPLIFT	IN-SX
J	905	0	905	0
G	905	0	905	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

**UNFACTORED REACTIONS**

JT	1ST CASE COMBINED	MAX/MIN. SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	640	420 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 / 0
G	640	420 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. L1 (LC) CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRAC LENGTH	FR-TO
A-B	0 / 27	-91.8	-91.8 0.22 (1)	10.00	B-I	-163 / 0	0.11 (1)
B-C	-649 / 0	-91.8	-91.8 0.17 (1)	6.25	I-E	-190 / 0	0.13 (1)
C-D	-489 / 0	-91.8	-91.8 0.01 (1)	6.25	J-B	-930 / 0	0.54 (1)
D-E	-650 / 0	-91.8	-91.8 0.18 (1)	6.25	E-G	-935 / 0	0.57 (1)
E-F	0 / 27	-91.8	-91.8 0.23 (1)	10.00	C-I	0 / 221	0.05 (1)
J-A	-129 / 0	0.0	0.0 0.01 (1)	7.81	I-D	0 / 222	0.05 (1)
G-F	-137 / 0	0.0	0.0 0.01 (1)	7.81			
J-I	0 / 590	-18.5	-18.5 0.41 (4)	10.00			
I-H	0 / 608	-18.5	-18.5 0.41 (4)	10.00			
H-G	0 / 608	-18.5	-18.5 0.41 (4)	10.00			

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, CBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.02")  
 ALLOWABLE DEFL.(TL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.11")

CSI: TC=0.23/1.00 (E-F-1), BC=0.41/1.00 (G-I-4), WB=0.57/1.00 (E-G-1), SI=0.13/1.00 (D-E-1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP(DRY) SHEAR SECTION (PSI)	(PL)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656


PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.75 (G) (INPUT = 0.90)  
 JSI METAL = 0.23 (G) (INPUT = 1.00)



Structural component only  
 DWG# T-2007071



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
K - A	2x4	DRY No.2	SPF
F - E	2x4	DRY No.2	SPF
K - H	2x4	DRY No.2	SPF
H - F	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TTW+p	MT20	4.0	8.0	Edge	
D	TMVW-t	MT20	4.0	4.0	2.00	1.25
E	TMVW+p	MT20	4.0	4.0	1.00	2.00
F	BMV1+p	MT20	3.0	4.0		
G	BMVW-t	MT20	4.0	6.0		
H	BS-t	MT20	3.0	6.0		
I	BMVW-t	MT20	4.0	9.0		
J	BMVW-t	MT20	4.0	4.0		
K	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	GROSS REACTION VERT	MAXIMUM FACTORED GROSS REACTION HORZ	INPUT BRG	REQD BRG
K	905	0	0	3-8
F	905	0	0	3-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 3-8.

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
K	840	420/0	0/0	0/0	0/0	220/0	0/0
F	840	420/0	0/0	0/0	0/0	220/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS		WEBS	
		VERT. LOAD (PL)	LC1 MAX CSH(LC)	MEMB. UNBRAC LENGTH	MAX. FACTORED FORCE (LBS)
FR-TO					
A-B	-772/0	-91.8	-91.8 0.20 (1)	6.25	J-B -135/21
B-C	-620/0	-91.8	-91.8 0.19 (1)	6.25	B-I -251/0
C-D	-622/0	-91.8	-91.8 0.20 (1)	6.25	I-C 0/478
D-E	-795/0	-91.8	-91.8 0.21 (1)	6.25	I-D -278/0
K-A	-873/0	0.0	0.0 0.10 (1)	7.81	G-D -110/31
F-E	-872/0	0.0	0.0 0.09 (1)	7.81	A-J 0/853
					G-E 0/662
K-J	0/0	-18.5	-18.5 0.07 (4)	10.00	
J-I	0/815	-18.5	-18.5 0.13 (1)	10.00	
I-H	0/633	-18.5	-18.5 0.14 (1)	10.00	
H-G	0/833	-18.5	-18.5 0.14 (1)	10.00	
G-F	0/0	-18.5	-18.5 0.07 (4)	10.00	

TOTAL WEIGHT = 77 lb (MTF)

**DESIGN CRITERIA**

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.02")  
 ALLOWABLE DEFL.(TL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(TL) = L/959 (0.03")

CSI: TC=0.21/1.00 (D-E:1), BC=0.14/1.00 (G-I:1), WB=0.20/1.00 (D-I:1), SS=0.14/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PL)	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1687	728	1987

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.


JSI GRIP = 0.87 (E) (INPUT = 0.90)  
 JSI METAL = 0.24 (E) (INPUT = 1.00)



Structural component only  
 DWG# T-2007072



Tamarack Roof Truss, Burlington Version 8.310 S Oct 29 2019 Mitak Industries, Inc. Sat Apr 25 11:02:56 2020 Page 1



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
N - B	2x4	DRY	No.2
H - F	2x4	DRY	No.2
N - M	2x4	DRY	No.2
M - C	2x4	DRY	No.2
L - J	2x4	DRY	No.2
I - E	2x4	DRY	No.2
I - H	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

N - L 2x4 DRY No.2

J - H 2x4 DRY No.2

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B, C, E, F					
B	TMVW+P	MT20	4.0	4.0	1.00 2.00
D	TTW+P	MT20	4.0	8.0	Edge
H	BMVW-1	MT20	4.0	4.0	
I	BMV+P	MT20	3.0	4.0	
J	BVMW-1	MT20	5.0	12.0	5.00 7.75
K	BMVW-1	MT20	4.0	9.0	
L	BVMW-1	MT20	5.0	12.0	5.00 7.75
M	BMV+P	MT20	3.0	4.0	
N	BMVW-1	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
N	729	0	729	0	5-8	5-8
H	729	0	729	0	5-8	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 1-8.

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
N	513	350/0	0/0	0/0	0/0	183/0	0/0
H	513	350/0	0/0	0/0	0/0	183/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. FURLIN SPACING = 8.25 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT. OR RIGID CEILING DIRECTLY APPLIED.  
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LCI (CSI(LC))	UNBRAC LENGTH	MEMB. FORCE (LBS)	MAX FACTORED FORCE (LBS)	MAX LCI (CSI(LC))	UNBRAC LENGTH
FR-TO								
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	C-K	-211/0	0.07 (1)
B-C	-647/0	-91.8	-91.8	0.14 (1)	8.25	K-D	0/229	0.05 (1)
C-D	-447/0	-91.8	-91.8	0.19 (1)	8.25	K-E	-210/0	0.07 (1)
D-E	-447/0	-91.8	-91.8	0.18 (1)	8.25	N-L	-26/0	0.00 (1)
E-F	-646/0	-91.8	-91.8	0.14 (1)	8.25	B-L	0/527	0.12 (1)
F-G	0/41	-91.8	-91.8	0.13 (1)	10.00	J-F	0/526	0.12 (1)
N-B	-701/0	0.0	0.0	0.07 (1)	7.81	J-H	-26/0	0.00 (1)
H-F	-701/0	0.0	0.0	0.07 (1)	7.81			
N-M	0/20	-18.5	-18.5	0.01 (4)	10.00			
M-L	0/14	0.0	0.0	0.03 (1)	10.00			
L-C	-82/2	0.0	0.0	0.02 (1)	7.81			
L-K	0/528	-18.5	-18.5	0.13 (1)	10.00			
K-J	0/527	-18.5	-18.5	0.13 (1)	10.00			
I-J	0/14	0.0	0.0	0.03 (1)	10.00			
J-E	-93/2	0.0	0.0	0.02 (1)	7.81			
I-H	0/20	-18.5	-18.5	0.01 (4)	10.00			

TOTAL WEIGHT = 2 X 56 = 112 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.8 PSF  
DL = 8.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.36")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")  
ALLOWABLE DEFL.(TL) = L/360 (0.36")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.19/1.00 (C-D-1), BC=0.13/1.00 (K-L-1), WB=0.12/1.00 (B-L-1), SS=0.13/1.00 (C-O-1)

DOL LUMBER=1.00 NAIL=1.00 L5 BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
PLATE GRIP(DRY) SHEAR SECTION (PS) (PLJ) (PL)


MT20 618 354 1667 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.74 (F) (INPUT = 0.80)

JSI METAL = 0.20 (F) (INPUT = 1.00)



Structural component only  
DWG# T-2007073



Scale = 1:25.4

**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
H - B	2x4	DRY No.2	SPF
H - D	2x4	DRY No.2	SPF
H - F	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+P	MT20	4.0	4.0	1.00	2.00
C	TTW+P	MT20	4.0	5.0	Edge	
D	TMVW+P	MT20	4.0	4.0	1.00	2.00
F	SMV+P	MT20	3.0	4.0		
G	BMVW+P	MT20	4.0	9.0		
H	BMV+P	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQRD BRG IN-SX
JT VERT	729	0	5-8
H	729	0	5-8
F	729	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

**UNFACTORED REACTIONS**

JT	1ST LCASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
H	513	350 / 0	0 / 0	0 / 0	0 / 0	0 / 0	163 / 0	0 / 0
F	513	350 / 0	0 / 0	0 / 0	0 / 0	0 / 0	163 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	FR-TO	CHORDS				WEBS			
		MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (CSI (LC))	MAX (LC)	MEMB. MAX. FACTORED FORCE (LBS)	MAX (LC)	UNBRACED LENGTH FR-TO	
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	G-C	-15 / 89	0.03 (4)	
B-C	-360 / 0	-91.8	-91.8	0.35 (1)	6.25	B-G	0 / 300	0.07 (1)	
C-D	-360 / 0	-91.8	-91.8	0.35 (1)	6.25	G-D	0 / 300	0.07 (1)	
D-E	0 / 41	-91.8	-91.8	0.13 (1)	10.00				
H-B	-690 / 0	0.0	0.0	0.07 (1)	7.81				
F-D	-690 / 0	0.0	0.0	0.07 (1)	7.81				
H-G	0 / 0	-18.5	-18.5	0.16 (4)	10.00				
G-F	0 / 0	-18.5	-18.5	0.16 (4)	10.00				

TOTAL WEIGHT = 49 lb (M/F)

**DESIGN CRITERIA**

SPECIFIED LOADS:  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, (OBC 2012, ABC 2019)  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 088-09, CSA 086-14  
 - TPC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.36")  
 CALCULATED VERT. DEFL.(LL) = L/899 (0.00")  
 ALLOWABLE DEFL.(TL) = L/360 (0.36")  
 CALCULATED VERT. DEFL.(TL) = L/998 (0.02")

CSI: TC=0.35/1.00 (B-C:1), BC=0.16/1.00 (G-H:4), WB=0.07/1.00 (D-G:1), SSI=0.15/1.00 (B-C:1)

DDL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10


COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)  
 MAX MIN MAX MIN MAX MIN  
 MT20 618 354 1657 788 1987 1856


PLATE PLACEMENT TOL. = 5.0 inches  
 PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.62 (D) (INPUT = 0.90)  
 JSI METAL= 0.17 (D) (INPUT = 1.00)



Structural component only  
 DWG# T-2007074

Tamarack Roof Truss, Burlington



**LUMBER**  
 N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - B	2x4	DRY	No.2
B - C	2x4	DRY	No.2
F - A	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT TYPE	PLATES	W	LEN	Y	X	
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TTW+p	MT20	4.0	6.0	Edge	
C	TMVW+p	MT20	4.0	4.0	1.00	2.00
D	BMV1+p	MT20	3.0	4.0		
E	BMVWV-t	MT20	4.0	9.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORIZ	DOWN	HORIZ	UPLIFT	IN-SX	IN-SX
F	423	0	423	0	0	MECHANICAL	MECHANICAL
D	423	0	423	0	0	MECHANICAL	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. D. MINIMUM BEARING LENGTH AT JOINT F = 1-8, JOINT D = 1-8.

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0
D	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. (PLF)	FACTORED HORIZ. (LC)	MAX. UNBRACED LENGTH (LC)	MEMB. FORCE (LBS)	FACTORED VERT. (PLF)	FACTORED HORIZ. (LC)	MAX. UNBRACED LENGTH (LC)
A-B	-214 / 0	-91.8	-91.8	0.17 (1)	E-B	-78 / 37	0.03 (1)	
B-C	-214 / 0	-91.8	-91.8	0.17 (1)	A-E	0 / 184	0.04 (1)	
F-A	-385 / 0	0.0	0.0	0.05 (1)	E-C	0 / 184	0.04 (1)	
D-C	-385 / 0	0.0	0.0	0.05 (1)				
F-E	0 / 0	-18.5	-18.5	0.08 (4)				
E-D	0 / 0	-18.5	-18.5	0.08 (4)				

TOTAL WEIGHT = 35 lb [M/F]

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.28")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.00")  
 ALLOWABLE DEFL.(TL) = L/360 (0.28")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.17/1.00 (B-C:1), BC=0.08/1.00 (D-E:4), WB=0.04/1.00 (A-E:1), SS=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)  
 MAX MIN MAX MIN MAX MIN  
 MT20 615 354 1667 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.31 (C) (INPUT = 0.30)  
 JSI METAL= 0.09 (C) (INPUT = 1.00)



Structural component only  
 DWG# T-2007075



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
L - A	2x4	DRY No.2	SPF
F - E	2x4	DRY No.2	SPF
L - K	2x4	DRY No.2	SPF
K - B	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
G - D	2x4	DRY No.2	SPF
G - F	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A, B, D, E						
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
C	TTW+P	MT20	4.0	6.0	Edge	
F	BMVW1-t	MT20	4.0	4.0		
G	BMV+p	MT20	3.0	4.0		
H	BMVW1-t	MT20	5.0	8.0	3.50	5.50
J	BMVW1-t	MT20	4.0	3.0		
K	BMVW1-t	MT20	5.0	8.0	3.50	5.50
L	BMV+p	MT20	3.0	4.0		
L	BMVW1-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	MAXIMUM FACTORED GROSS REACTION DOWN	HORZ	UPLIFT	REQRD BRG IN-SX	REQRD BRG MECHANICAL
L	423	0	423	0	0	MECHANICAL	
F	423	0	423	0	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT L, F. MINIMUM BEARING LENGTH AT JOINT L = 1-8, JOINT F = 1-8.

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX. SNOW	MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
L	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0
F	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT. OR RIGID CEILING DIRECTLY APPLIED.  
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
A-B	-282 / 0	-91.8	-91.8	0.08 (1)	6.25	I-C	0 / 125	0.03 (1)
B-C	-274 / 0	-91.8	-91.8	0.07 (1)	6.25	I-D	-57 / 0	0.01 (1)
C-D	-274 / 0	-91.8	-91.8	0.07 (1)	6.25	B-I	-57 / 0	0.01 (1)
D-E	-282 / 0	-91.8	-91.8	0.06 (1)	6.25	L-J	-13 / 0	0.00 (1)
L-A	-404 / 0	0.0	0.0	0.05 (1)	7.81	A-J	0 / 317	0.07 (1)
F-E	-404 / 0	0.0	0.0	0.05 (1)	7.81	H-F	-13 / 0	0.00 (1)
L-K	0 / 9	-18.5	-18.5	0.01 (4)	10.00	H-E	0 / 317	0.07 (1)
K-J	0 / 11	0.0	0.0	0.01 (1)	10.00			
J-B	-182 / 0	0.0	0.0	0.01 (1)	7.81			
J-I	0 / 247	-18.5	-18.5	0.08 (1)	10.00			
I-H	0 / 247	-18.5	-18.5	0.06 (1)	10.00			
G-H	0 / 11	0.0	0.0	0.01 (1)	10.00			
H-D	-182 / 0	0.0	0.0	0.01 (1)	7.81			
G-F	0 / 9	-18.5	-18.5	0.01 (4)	10.00			

TOTAL WEIGHT = 2 X 43 = 85 lb [M/F]

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
          OL = 8.0 PSF  
BOT CH. LL = 0.0 PSF  
          OL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2018, CBC 2012, ABC 2019  
- PART 9 OF CBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(55% OF 81.3 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.26")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")  
ALLOWABLE DEFL.(TL) = L/360 (0.26")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.07/1.00 (C-D:1), BC=0.08/1.00 (H-I:1), WB=0.07/1.00 (A-J:1), SS=0.09/1.00 (C-D:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00  
AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP (DRY) SHEAR SECTION (PSI)	(PL)	(PL)	(PL)
MAX	618	354	1667
MIN	788	1987	1856

PLATE PLACEMENT TOL. = 0.250 inches  
PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.30 (E) (INPUT = 0.90)  
JSI METAL = 0.08 (E) (INPUT = 1.00)





TOTAL WEIGHT = 37 lb

**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
F - A	2x4	DRY No.2	SPF
D - C	2x4	DRY No.2	SPF
F - D	2x4	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 EXCEPT SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
A	TMVV-t	MT20	4.0	9.0	Edge
B	TMVW-w	MT20	2.0	4.0	
C	TMVV-t	MT20	4.0	9.0	Edge
D	BMV1+p	MT20	3.0	4.0	
E	BMVW-w	MT20	6.0	9.0	
F	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	DOWN	UPLIFT	IN-SX
F	978	0	0	5-8
D	1015	0	0	5-8

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX. SNOW	MIN. LIVE	COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
F	690	453 / 0	0 / 0	0 / 0	0 / 0	0 / 0	237 / 0	0 / 0
D	716	479 / 0	0 / 0	0 / 0	0 / 0	0 / 0	237 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINTS (F), D

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.55 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	FR-TO	CHORDS			WEBS			
		MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PL)	FACTORED LC1 MAX. CSI (LC)	MEMB. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
A-G	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55	A-E	0 / 2157	0.53 (1)
G-H	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55	E-B	-876 / 0	0.14 (1)
H-I	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55	E-C	0 / 2157	0.53 (1)
I-B	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55			
B-J	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55			
J-K	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55			
K-C	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55			
F-A	-889 / 0	0.0	0.0	0.10 (1)	7.81			
D-C	-938 / 0	0.0	0.0	0.11 (1)	7.81			
F-L	0 / 0	-18.5	-18.5	0.22 (4)	10.00			
L-M	0 / 0	-18.5	-18.5	0.22 (4)	10.00			
M-N	0 / 0	-18.5	-18.5	0.22 (4)	10.00			
N-E	0 / 0	-18.5	-18.5	0.22 (4)	10.00			
E-O	0 / 0	-18.5	-18.5	0.22 (4)	10.00			
O-P	0 / 0	-18.5	-18.5	0.22 (4)	10.00			
P-D	0 / 0	-18.5	-18.5	0.22 (4)	10.00			

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	10-11-0	-123	-123		BACK	VERT	TOTAL		C1
G	9-14	-80	-80		BACK	VERT	TOTAL		C1
H	2-9-14	-82	-82		BACK	VERT	TOTAL		C1
J	4-8-14	-82	-82		BACK	VERT	TOTAL		C1
J	6-9-14	-82	-82		BACK	VERT	TOTAL		C1
K	8-9-14	-82	-82		BACK	VERT	TOTAL		C1
L	9-14	-51	-51		BACK	VERT	TOTAL		C1
M	2-9-14	-49	-49		BACK	VERT	TOTAL		C1
N	4-9-14	-49	-49		BACK	VERT	TOTAL		C1
O	6-9-14	-49	-49		BACK	VERT	TOTAL		C1
P	8-9-14	-49	-49		BACK	VERT	TOTAL		C1

**CONNECTION REQUIREMENTS**

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. CC**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2010, NBC2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.38")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.08")  
ALLOWABLE DEFL.(TL) = L/360 (0.38")  
CALCULATED VERT. DEFL.(TL) = L/817 (0.16")

CSI: TC=0.79/1.00 (A-B-1), BC=0.22/1.00 (E-F-4),  
WB=0.53/1.00 (A-E-1), SS=0.39/1.00 (A-B-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00  
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)  
MAX MIN MAX MIN MAX MIN  
MT20 618 354 1667 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (A) (INPUT = 0.90)  
JSI METAL = 0.40 (E) (INPUT = 1.00)



Structural component only  
DWG# T-2007077



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x8 DRY	No.2	SPF		
C - F	2x6 DRY	No.2	SPF		
F - H	2x8 DRY	No.2	SPF		
H - J	2x8 DRY	No.2	SPF		
S - B	2x8 DRY	No.2	SPF		
K - I	2x8 DRY	No.2	SPF		
S - P	2x6 DRY	1650F 1.5E	SPF		
P - N	2x8 DRY	1650F 1.5E	SPF		
N - K	2x8 DRY	1650F 1.5E	SPF		
ALL WEBS EXCEPT	2x3 DRY	No.2	SPF		

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS SURFACE SPACING (IN) LOAD(PLF)

TOP CHORDS : (0.122"x3") SPIRAL NAILS

A-C	2	12	SIDE(122.0)
C-F	2	12	SIDE(61.0)
F-H	2	12	SIDE(61.0)
H-J	2	12	SIDE(122.0)
S-B	2	12	TOP
K-I	2	12	TOP

BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS

S-P	2	12	SIDE(0.0)
P-N	2	12	SIDE(0.0)
N-K	2	12	SIDE(193.1)

WEBS : (0.122"x3") SPIRAL NAILS

2x3 1 6

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLYS FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	DOWN	IN-SX	IN-SX
S 3330	0	0	5-8
K 3379	0	0	5-8

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS
JT COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
S 2354	1553 / 0 0 / 0 0 / 0 0 / 0 801 / 0 0 / 0
K 2388	1572 / 0 0 / 0 0 / 0 0 / 0 816 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.98 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)
A-B	0 / 42	-91.8 -91.8 0.04 (1)	10.00	R-C -682 / 0 0.08 (1)
B-C	-3359 / 0	-91.8 -91.8 0.05 (1)	6.03	C-Q 0 / 4522 0.56 (1)
C-T	-6608 / 0	-91.8 -91.8 0.38 (1)	4.32	Q-D -1799 / 0 0.22 (1)
T-U	-6608 / 0	-91.8 -91.8 0.38 (1)	4.32	D-O 0 / 1375 0.17 (1)
U-V	-6608 / 0	-91.8 -91.8 0.38 (1)	4.32	O-E -980 / 0 0.12 (1)
V-W	-6608 / 0	-91.8 -91.8 0.38 (1)	4.32	C-G 0 / 1388 0.17 (1)
W-D	-6608 / 0	-91.8 -91.8 0.38 (1)	4.32	M-G -1785 / 0 0.21 (1)
D-X	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	M-H 0 / 4493 0.58 (1)
X-Y	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	L-H -873 / 0 0.08 (1)
Y-Z	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	B-R 0 / 2729 0.34 (1)
Z-E	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	L-I 0 / 2764 0.34 (1)
E-AA	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	
AA-F	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	
F-AB	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	
AB-AC	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	
AC-AD	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	
AD-G	-7835 / 0	-91.8 -91.8 0.42 (1)	3.98	
G-AE	-6612 / 0	-91.8 -91.8 0.38 (1)	4.32	
AE-AF	-6612 / 0	-91.8 -91.8 0.38 (1)	4.32	
AF-AG	-6612 / 0	-91.8 -91.8 0.38 (1)	4.32	
AG-H	-6612 / 0	-91.8 -91.8 0.38 (1)	4.32	
H-I	-3401 / 0	-91.8 -91.8 0.05 (1)	6.00	
I-J	0 / 42	-91.8 -91.8 0.04 (1)	10.00	
S-B	-3366 / 0	0.0 0.0 0.12 (1)	7.58	
K-I	-3406 / 0	0.0 0.0 0.12 (1)	7.55	
S-AH	0.0	-18.5 -18.5 0.06 (4)	10.00	
AH-R	0.0	-18.5 -18.5 0.06 (4)	10.00	
R-AI	0.2546	-18.5 -18.5 0.16 (1)	10.00	
AI-AJ	0.2546	-18.5 -18.5 0.16 (1)	10.00	
AJ-AK	0.2546	-18.5 -18.5 0.16 (1)	10.00	
AK-AL	0.2546	-18.5 -18.5 0.16 (1)	10.00	
AL-O	0.2546	-18.5 -18.5 0.16 (1)	10.00	
O-P	0.6805	-18.5 -18.5 0.32 (1)	10.00	
P-AM	0.6805	-18.5 -18.5 0.32 (1)	10.00	
AM-AN	0.6805	-18.5 -18.5 0.32 (1)	10.00	
AN-O	0.6805	-18.5 -18.5 0.32 (1)	10.00	
O-AO	0.6813	-18.5 -18.5 0.32 (1)	10.00	
AO-AP	0.6813	-18.5 -18.5 0.32 (1)	10.00	
AP-AQ	0.6813	-18.5 -18.5 0.32 (1)	10.00	
AQ-N	0.6813	-18.5 -18.5 0.32 (1)	10.00	
N-AR	0.6813	-18.5 -18.5 0.32 (1)	10.00	
AR-M	0.6813	-18.5 -18.5 0.32 (1)	10.00	

DESIGN CRITERIA

\*\*\* SPECIAL LOADS ANALYSIS \*\*\*

GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.

LOADS WERE DERIVED FROM USER INPUT NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF  
 OL = 6.0 PSF

BOT CH. LL = 0.0 PSF  
 OL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

\*\*\* NON STANDARD GIRDER \*\*\*

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 086-14
- TPIC 2011, TPIC 2014

(5% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.20")  
 ALLOWABLE DEFL.(TL) = L/360 (1.17")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.38")

CSI: TC=0.42/1.00 (D-E-1), BC=0.32/1.00 (O-C-1), WB=0.58/1.00 (C-Q-1), SSI=0.22/1.00 (C-D-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00  
 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR SECTION (PSI)	(PL)	(PL)
MT20	818 354 1687 789 1987 1656		

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.62 (M) (INPUT = 0.90 )  
 JSI METAL= 0.32 (P) (INPUT = 1.00 )



Structural component only  
 DWG# T-2007081 1/2

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	7.0	8.0		
C	TTWW+m	MT20	8.0	9.0	3.50	1.75
D	TMWW-t	MT20	5.0	6.0	2.50	2.50
E	TMW+w	MT20	3.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMWW-t	MT20	5.0	6.0	2.50	2.50
H	TTWW+m	MT20	8.0	9.0	3.50	1.75
I	TMW+p	MT20	7.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMWW-t	MT20	5.0	6.0	2.50	2.25
M	BMWW-t	MT20	5.0	6.0	2.50	3.00
N	BS-t	MT20	6.0	9.0		
O	BMWWW-t	MT20	5.0	12.0		
P	BS-t	MT20	6.0	9.0		
Q	BMWW-t	MT20	5.0	6.0	2.50	3.00
R	BMWW-t	MT20	5.0	6.0	2.50	2.25
S	BMV1+p	MT20	3.0	6.0		


**LOADING**  
TOTAL LOAD CASES: 141

CHORDS				WEBS			
MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	LC1 (LBS)	MAX. (LBS)	MEMB. FORCE (LBS)	MAX. (LBS)	CS1 (LBS)
M-AS	0 / 2579	-18.5	-18.5	0.18 (1)	10.00		
AS-AT	0 / 2579	-18.5	-18.5	0.18 (1)	10.00		
AT-AU	0 / 2579	-18.5	-18.5	0.18 (1)	10.00		
AU-L	0 / 2579	-18.5	-18.5	0.18 (1)	10.00		
L-AV	0 / 0	-18.5	-18.5	0.08 (4)	10.00		
AV-K	0 / 0	-18.5	-18.5	0.08 (4)	10.00		

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX.	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
C	2-11-8	-38	-42		FRONT	VERT	DEAD		CI
C	2-11-8	-191	-191		FRONT	VERT	SNOW		CI
H	32-2-8	-38	-42		FRONT	VERT	DEAD		CI
H	32-2-8	-116	-116		FRONT	VERT	TOTAL		CI
H	32-2-8	-191	-191		FRONT	VERT	SNOW		CI
L	31-11-4	-28	-28		FRONT	VERT	TOTAL		CI
P	11-11-4	-26	-26		FRONT	VERT	TOTAL		CI
T	3-11-4	-111	-111		FRONT	VERT	TOTAL		CI
U	5-11-4	-110	-110		FRONT	VERT	TOTAL		CI
V	7-11-4	-110	-110		FRONT	VERT	TOTAL		CI
W	9-11-4	-110	-110		FRONT	VERT	TOTAL		CI
X	11-11-4	-110	-110		FRONT	VERT	TOTAL		CI
Y	13-11-4	-110	-110		FRONT	VERT	TOTAL		CI
Z	15-11-4	-110	-110		FRONT	VERT	TOTAL		CI
AA	17-11-4	-110	-110		FRONT	VERT	TOTAL		CI
AB	19-11-4	-110	-110		FRONT	VERT	TOTAL		CI
AC	21-11-4	-110	-110		FRONT	VERT	TOTAL		CI
AD	23-11-4	-110	-110		FRONT	VERT	TOTAL		CI
AE	25-11-4	-110	-110		FRONT	VERT	TOTAL		CI
AF	27-11-4	-110	-110		FRONT	VERT	TOTAL		CI
AG	29-11-4	-110	-110		FRONT	VERT	TOTAL		CI
AH	1-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AI	3-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AJ	5-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AK	7-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AL	9-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AM	13-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AN	15-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AO	17-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AP	19-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AQ	21-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AR	23-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AS	25-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AT	27-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AU	29-11-4	-26	-26		FRONT	VERT	TOTAL		CI
AV	33-11-4	-26	-26		FRONT	VERT	TOTAL		CI


**CONNECTION REQUIREMENTS**  
 1) CI: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only  
 DWG# T-2007081 3/1

JOB NAME 408151	TRUSS NAME T20Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 5 Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:19:45 2020 Page 1  
 ID:n2dfgC44ws E2tzqPs\_atzllRw-iCOUmk9VL9YAq n0aqaJUZo4EB5KGTB585yzNCX



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x8	DRY	No.2	SPF
C - F	2x6	DRY	No.2	SPF
F - H	2x6	DRY	No.2	SPF
H - J	2x6	DRY	No.2	SPF
S - B	2x6	DRY	No.2	SPF
K - I	2x6	DRY	No.2	SPF
S - P	2x6	DRY	1650F 1.5E	SPF
P - N	2x6	DRY	1650F 1.5E	SPF
N - K	2x6	DRY	1650F 1.5E	SPF

ALL WEBS 2x3 DRY No.2 SPF EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C	2 12	SIDE(122.0)
C-F	2 12	SIDE(183.1)
F-H	2 12	TOP
H-J	2 12	TOP
S-B	2 12	TOP
K-I	2 12	TOP

BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS	SURFACE SPACING (IN)	LOAD(PLF)
S-P	2 12	SIDE(183.1)
P-N	2 12	SIDE(183.1)
N-K	2 12	TOP

WEBS : (0.122"x3") SPIRAL NAILS  
 2x3 1 6

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLYS FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION VERT	FACTORED GROSS REACTION HORZ	MAXIMUM FACTORED GROSS REACTION DOWN	MAXIMUM FACTORED GROSS REACTION HORZ	INPUT BRG UPLIFT	RECORD BRG IN-SX
JT	4991	0	4991	0	5-8	5-8
S	4991	0	4991	0	5-8	5-8
K	3694	0	3694	0	5-8	5-8

**UNFACTORED REACTIONS**

	1ST LCASE COMBINED	MAX. MIN. LIVE	COMPONENT REACTIONS PERMA LIVE	WIND	DEAD	SOIL
JT	3528	2323 / 0	0 / 0	0 / 0	1208 / 0	0 / 0
S	3528	2323 / 0	0 / 0	0 / 0	871 / 0	0 / 0
K	2608	1737 / 0	0 / 0	0 / 0	871 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.20 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	CHORDS MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	UNBRAC LENGTH FR-TO	MEMB.	WEBS MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
A-B	0 / 42	-91.8	-91.8 0.04 (1)	10.00	R-C	-253 / 44	0.03 (1)
B-C	-5342 / 0	-91.8	-91.8 0.07 (1)	5.02	C-Q	0 / 6569	0.81 (1)
C-D	-9971 / 0	-91.8	-91.8 0.39 (1)	3.64	Q-D	-1958 / 0	0.23 (1)
D-T	-12379 / 0	-91.8	-91.8 0.52 (1)	3.20	D-O	0 / 2694	0.33 (1)
T-E	-12379 / 0	-91.8	-91.8 0.52 (1)	3.20	O-E	-782 / 0	0.09 (1)
E-F	-12379 / 0	-91.8	-91.8 0.49 (1)	3.23	O-G	0 / 4229	0.52 (1)
F-G	-12379 / 0	-91.8	-91.8 0.49 (1)	3.23	M-G	-2619 / 0	0.31 (1)
G-H	-8598 / 0	-91.8	-91.8 0.33 (1)	3.93	M-H	0 / 6416	0.79 (1)
H-I	-3750 / 0	-91.8	-91.8 0.06 (1)	5.79	L-H	-864 / 0	0.10 (1)
I-J	0 / 42	-91.8	-91.8 0.04 (1)	10.00	B-R	0 / 4341	0.54 (1)
S-B	-5197 / 0	0.0	0.0 0.19 (1)	6.41	L-I	0 / 3047	0.38 (1)
K-I	-3727 / 0	0.0	0.0 0.13 (1)	7.30			
S-U	0 / 0	-18.5	-18.5 0.20 (1)	10.00			
U-R	0 / 0	-18.5	-18.5 0.20 (1)	10.00			
R-V	0 / 4073	-18.5	-18.5 0.36 (1)	10.00			
V-Q	0 / 4073	-18.5	-18.5 0.36 (1)	10.00			
Q-P	0 / 9971	-18.5	-18.5 0.73 (1)	10.00			
P-W	0 / 9971	-18.5	-18.5 0.73 (1)	10.00			
W-X	0 / 9971	-18.5	-18.5 0.73 (1)	10.00			
X-O	0 / 9971	-18.5	-18.5 0.73 (1)	10.00			
O-Y	0 / 8800	-18.5	-18.5 0.58 (1)	10.00			
Y-N	0 / 8800	-18.5	-18.5 0.58 (1)	10.00			
N-M	0 / 8800	-18.5	-18.5 0.58 (1)	10.00			
M-L	0 / 2839	-18.5	-18.5 0.16 (1)	10.00			
L-K	0 / 0	-18.5	-18.5 0.05 (1)	10.00			

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
C	2-11-8	-38	-42	---	FRONT	VERT	DEAD	C1
C	2-11-8	-117	-117	---	BACK	VERT	TOTAL	C1
C	2-11-8	-191	-191	---	FRONT	VERT	SNOW	C1
E	17-4-12	-110	-110	---	BACK	VERT	TOTAL	C1
O	17-4-12	-26	-26	---	BACK	VERT	TOTAL	C1
R	2-9-4	-26	-26	---	BACK	VERT	TOTAL	C1
T	15-4-12	-110	-110	---	BACK	VERT	TOTAL	C1
U	9-4	-29	-29	---	BACK	VERT	TOTAL	C1
V	4-8-8	-1068	-1068	---	BACK	VERT	TOTAL	C1
W	13-5-8	-1068	-1068	---	BACK	VERT	TOTAL	C1
X	15-4-12	-26	-26	---	BACK	VERT	TOTAL	C1
Y	18-5-8	-1738	-1738	---	BACK	VERT	TOTAL	C1

TOTAL WEIGHT = 2 X 183 = 365 lb

**DESIGN CRITERIA**

\*\*\* SPECIAL LOADS ANALYSIS \*\*\*  
 GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.  
 LOADS WERE DERIVED FROM USER INPUT  
 NO FURTHER MODIFICATIONS WERE MADE

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

\*\*\* NON STANDARD GIRDER \*\*\*  
 ADD'L USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 088-09, CSA 088-14  
 - TPIC 2011, TPIC 2014

(85% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.33")  
 ALLOWABLE DEFL.(TL) = L/360 (1.17")  
 CALCULATED VERT. DEFL.(TL) = L/685 (0.62")

CSI: TC=0.52/1.00 (D-E:1), BC=0.73/1.00 (C-Q:1),  
 WB=0.81/1.00 (C-Q:1), SS=0.57/1.00 (M-O:1)

DOL LUMBER=1.00 NAIL=1.00 LBS BEND=1.00  
 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)  
 MAX MIN MAX MIN MAX MIN  
 MT20 818 354 1867 788 1957 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.88 (D) (INPUT = 0.90)  
 JSI METAL = 0.84 (P) (INPUT = 1.00)



Structural component only  
 DWG# T-2007082 42




JOB NAME 408151	TRUSS NAME T20Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 28 11:19:45 2020 Page 2  
 IDfn2dfiqC44wS E2tzoPs atzIRw-JCOJmko9VL9YAq n0agaJwZo4EB5KGT8585vzNCX



**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	7.0	8.0		
C	TTVW+m	MT20	8.0	9.0	3.50	1.75
D	TMVW-l	MT20	5.0	6.0	2.50	2.50
E	TMVW+w	MT20	3.0	6.0		
F	TS-l	MT20	5.0	6.0		
G	TMVW-l	MT20	5.0	6.0	2.50	2.50
H	TTVW+m	MT20	8.0	9.0	3.50	1.75
I	TMVW+p	MT20	7.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMVW-l	MT20	5.0	6.0	2.50	2.25
M	BMVW-l	MT20	5.0	8.0	2.50	2.75
N	BS-l	MT20	6.0	9.0		
O	BMVW-l	MT20	5.0	12.0	2.75	8.00
P	BS-l	MT20	6.0	9.0		
Q	BMVW-l	MT20	5.0	8.0	2.50	2.75
R	BMVW-l	MT20	5.0	6.0	2.50	2.25
S	BMV1+p	MT20	3.0	6.0		

**CONNECTION REQUIREMENTS**  
 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only  
 DWG# T-2007082 *72*



**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - I	2x4	DRY	No.2	SPF
I - K	2x4	DRY	No.2	SPF
U - B	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
U - R	2x4	DRY	No.2	SPF
R - O	2x4	DRY	No.2	SPF
O - L	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMWW+p	MT20	5.0	6.0	Edge 2.75
C	TTWW+m	MT20	6.0	9.0	Edge 1.75
D, E, H					
D	TMWW-t	MT20	4.0	4.0	
F	TS-t	MT20	3.0	6.0	
G	TMWW-w	MT20	2.0	4.0	
I	TTWW+m	MT20	6.0	9.0	Edge 1.75
J	TMWW+p	MT20	5.0	6.0	Edge 2.75
L	BMV1-p	MT20	3.0	4.0	
M	BMWW-t	MT20	4.0	6.0	2.00 2.75
N	BMWW-t	MT20	5.0	6.0	2.50 2.75
O	BS-t	MT20	3.0	6.0	
P	BMWW-t	MT20	4.0	4.0	
Q	BS-t	MT20	3.0	6.0	
R	BMWW-t	MT20	5.0	6.0	
S	BMWW-t	MT20	4.0	6.0	2.00 2.75
T	BMV1-p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT VERT	2088	0	5-8
U VERT	2066	0	5-8
L VERT	2066	0	5-8

**UNFACTORED REACTIONS**

1ST LCASE	MAX/MIN COMPONENT REACTIONS	WIND	DEAD	SOIL
JT COMBINED	971 / 0	0 / 0	488 / 0	0 / 0
U COMBINED	971 / 0	0 / 0	488 / 0	0 / 0
L COMBINED	971 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, L

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.20 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

**CHORDS**

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX
FR-TO						FR-TO		
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	T-C	-358 / 0	0.14 (1)
B-C	-1960 / 0	-91.8	-91.8	0.38 (1)	4.48	C-S	0 / 1836	0.41 (1)
C-D	-2871 / 0	-91.8	-91.8	0.57 (1)	3.59	S-D	-1118 / 0	0.43 (1)
D-E	-3508 / 0	-91.8	-91.8	0.85 (1)	3.21	D-Q	0 / 856	0.19 (1)
E-F	-3505 / 0	-91.8	-91.8	0.53 (1)	3.36	Q-E	-475 / 0	0.18 (1)
F-G	-3505 / 0	-91.8	-91.8	0.57 (1)	3.59	E-P	-2 / 0	0.08 (1)
G-H	-3505 / 0	-91.8	-91.8	0.57 (1)	3.59	P-G	-474 / 0	0.18 (1)
H-I	-2871 / 0	-91.8	-91.8	0.85 (1)	3.21	H-J	0 / 853	0.19 (1)
I-J	-1960 / 0	-91.8	-91.8	0.13 (1)	10.00	N-I	-1117 / 0	0.43 (1)
J-K	0 / 41	0.0	0.0	0.22 (1)	5.92	M-I	0 / 1837	0.41 (1)
U-B	-2037 / 0	0.0	0.0	0.22 (1)	5.92	M-I	-358 / 0	0.14 (1)
L-J	-2037 / 0	0.0	0.0	0.22 (1)	5.92	B-T	0 / 1571	0.35 (1)
						M-J	0 / 1571	0.35 (1)
U-T	0 / 0	-18.5	-18.5	0.10 (4)	10.00			
T-S	0 / 1494	-18.5	-18.5	0.30 (1)	10.00			
S-R	0 / 2871	-18.5	-18.5	0.51 (1)	10.00			
R-Q	0 / 2871	-18.5	-18.5	0.51 (1)	10.00			
Q-P	0 / 3508	-18.5	-18.5	0.82 (1)	10.00			
P-O	0 / 2872	-18.5	-18.5	0.51 (1)	10.00			
O-N	0 / 2872	-18.5	-18.5	0.51 (1)	10.00			
N-M	0 / 1494	-18.5	-18.5	0.30 (1)	10.00			
M-L	0 / 0	-18.5	-18.5	0.10 (4)	10.00			

TOTAL WEIGHT = 2 X 147 = 293 lb

**DESIGN CRITERIA**

SPECIFIED LOADS:  
TOP CH. LL = 25.6 PSF  
DL = 8.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2010, NBC2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2010, OBC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 088-09, CSA 088-14  
- TPIC 2011, TPIC 2014

(65% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17')  
CALCULATED VERT. DEFL.(LL) = L/999 (0.20')  
ALLOWABLE DEFL.(TL) = L/360 (1.17')  
CALCULATED VERT. DEFL.(TL) = L/999 (0.39')

CSI: TC=0.86/1.00 (G-H-t), BC=0.82/1.00 (P-Q-t), WB=0.43/1.00 (D-S-t), SS=0.23/1.00 (H-t-t)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PL)	MAX MIN	MAX MIN
MT20	618	354	1667	788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 6.0 Deg.


JSI GRIP = 0.90 (S) (INPUT = 0.90)  
JSI METAL = 0.90 (C) (INPUT = 1.00)



Structural component only  
DWG# T-2007083

JOB NAME 408151	TRUSS NAME T22	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:19:47 2020 Page 1  
 ID:h2dlgC44wS\_E2zqPs\_atzllRw-ehJ89'n\_Kml3PrKD6C22v7OAZcpWl3vZwVaFAr2NCXq  
 Scale = 1:57.4



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
H - J	2x4	DRY	No.2	SPF
S - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
S - P	2x4	DRY	No.2	SPF
P - N	2x4	DRY	No.2	SPF
N - K	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2  
EXCEPT

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWV-p	MT20	5.0	6.0	1.50	3.00
C	TTWW-m	MT20	6.0	9.0	Edge	1.75
D	TMWV-l	MT20	4.0	4.0		
E	TMWV-w	MT20	2.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMWV-t	MT20	4.0	4.0		
H	TTWW-m	MT20	6.0	9.0	Edge	1.75
I	TMWV-p	MT20	5.0	6.0	1.50	3.00
K	BMV1-p	MT20	3.0	4.0		
L, M, Q, R						
L	BMWV-t	MT20	5.0	6.0		
N	BS-l	MT20	3.0	6.0		
O	BMWVW-t	MT20	4.0	9.0		
P	BS-l	MT20	3.0	6.0		
S	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	MAXIMUM FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
S	2066	0	2066	0	5-8	5-8
K	2066	0	2066	0	5-8	5-8

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
S	1458	971/0	0/0	0/0	0/0	488/0	0/0
K	1458	971/0	0/0	0/0	0/0	488/0	0/0

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.28 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	UNBRAC LENGTH	FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	F-C	-246/7	0.14 (1)	
B-C	-2004/0	-91.8	-91.8	0.64 (1)	4.11	C-Q	0/1538	0.35 (1)	
C-D	-2653/0	-91.8	-91.8	0.74 (1)	3.50	Q-D	-943/0	0.55 (1)	
D-E	-2978/0	-91.8	-91.8	0.78 (1)	3.28	D-O	0/450	0.10 (1)	
E-F	-2978/0	-91.8	-91.8	0.78 (1)	3.28	O-E	-513/0	0.30 (1)	
F-G	-2978/0	-91.8	-91.8	0.78 (1)	3.28	O-G	0/450	0.10 (1)	
G-H	-2653/0	-91.8	-91.8	0.74 (1)	3.50	M-G	-943/0	0.55 (1)	
H-I	-2004/0	-91.8	-91.8	0.64 (1)	4.11	M-H	0/1538	0.35 (1)	
I-J	0/41	-91.8	-91.8	0.13 (1)	10.00	L-H	-246/7	0.14 (1)	
S-B	-2028/0	0.0	0.0	0.22 (1)	5.94	B-R	0/1580	0.36 (1)	
K-I	-2028/0	0.0	0.0	0.22 (1)	5.94	L-I	0/1580	0.36 (1)	
S-R	0/0	-18.5	-18.5	0.14 (4)	10.00				
R-Q	0/1532	-18.5	-18.5	0.33 (1)	10.00				
Q-P	0/2653	-18.5	-18.5	0.49 (1)	10.00				
P-O	0/2653	-18.5	-18.5	0.49 (1)	10.00				
O-N	0/2653	-18.5	-18.5	0.49 (1)	10.00				
N-M	0/2653	-18.5	-18.5	0.49 (1)	10.00				
M-L	0/1532	-18.5	-18.5	0.33 (1)	10.00				
L-K	0/0	-18.5	-18.5	0.14 (4)	10.00				

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL = 25.8 PSF  
 DL = 6.0 PSF

BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

TOTAL WEIGHT = 2 X 148 = 296 lb

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/380 (1.17")  
 CALCULATED VERT. DEFL.(LL) = L/899 (0.16")  
 ALLOWABLE DEFL.(TL) = L/360 (1.17")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.23")

CSI: TC=0.78/1.00 (D-E:1), BC=0.48/1.00 (O-Q:1),  
 WB=0.55/1.00 (G-M:1), SSI=0.27/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)

MAX MIN MAX MIN  
 MT20 .618 354 1667 788 1987 1658


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.90 (B) (INPUT = 0.90)  
 JSI METAL = 0.85 (N) (INPUT = 1.00)



Structural component only  
 DWG# T-2007084



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - G	2x4	DRY No.2	SPF
G - I	2x4	DRY No.2	SPF
I - L	2x4	DRY No.2	SPF
U - B	2x4	DRY No.2	SPF
M - K	2x4	DRY No.2	SPF
U - R	2x4	DRY No.2	SPF
R - P	2x4	DRY No.2	SPF
P - M	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0		
C TMWW+1	MT20	5.0	8.0	2.50	2.25
D TTWW+m	MT20	5.0	8.0	2.00	1.75
E TMWW-1	MT20	4.0	4.0		
F TMW+w	MT20	2.0	4.0		
G TS+1	MT20	3.0	8.0		
H TMWW+1	MT20	4.0	4.0		
I TTWW+m	MT20	5.0	8.0	2.00	1.75
J TMWW-1	MT20	5.0	8.0	2.50	2.25
K TMV+p	MT20	3.0	4.0		
M BMVW+1	MT20	5.0	8.0	2.25	3.00
N BMWW+1	MT20	4.0	4.0		
O BMWW-1	MT20	4.0	4.0		
P BS+1	MT20	3.0	8.0		
Q BMWWW-1	MT20	4.0	8.0		
R BS+1	MT20	3.0	8.0		
S BMWW+1	MT20	4.0	8.0		
T BMWW-1	MT20	4.0	4.0		
U BMVW+1	MT20	5.0	8.0	2.25	3.00

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT VERT	2066	2066	0	0
U	0	0	5-8	5-8
M	0	0	5-8	5-8

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX. MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
U	1458	971/0	0/0	0/0	488/0	0/0
M	1458	971/0	0/0	0/0	488/0	0/0

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.77 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FORCE (LBS)	CHORDS		WEBS	
		FACTORED	FACTORED	MEMB. FORCE (LBS)	MAX. FACTORED
FR-TO					
A-B	0/141	-91.8	-91.8 0.13 (1)	10.00	C-T 0/156 0.04 (1)
B-C	0/119	-91.8	-91.8 0.14 (1)	10.00	T-D 0/76 0.03 (4)
C-D	2023/0	-91.8	-91.8 0.20 (1)	4.59	D-S 0/1220 0.27 (1)
D-E	2308/0	-91.8	-91.8 0.56 (1)	3.94	S-E -850/0 0.74 (1)
E-F	-2534/0	-91.8	-91.8 0.57 (1)	3.77	E-Q 0/361 0.08 (1)
F-G	-2534/0	-91.8	-91.8 0.57 (1)	3.77	Q-H -461/0 0.40 (1)
G-H	-2534/0	-91.8	-91.8 0.57 (1)	3.77	H-I 0/1261 0.08 (1)
H-I	-2308/0	-91.8	-91.8 0.55 (1)	3.94	O-I -850/0 0.74 (1)
I-J	-2023/0	-91.8	-91.8 0.20 (1)	4.59	O-I 0/1220 0.27 (1)
J-K	0/119	-91.8	-91.8 0.14 (1)	10.00	N-I 0/76 0.03 (4)
K-L	0/141	-91.8	-91.8 0.13 (1)	10.00	N-J 0/156 0.04 (1)
U-B	-246/0	0.0	0.0 0.03 (1)	7.81	U-C -2277/0 0.98 (1)
M-K	-246/0	0.0	0.0 0.03 (1)	7.81	J-M -2277/0 0.98 (1)
U-T	0/1433	-18.5	-18.5 0.33 (1)	10.00	
T-S	0/1535	-18.5	-18.5 0.35 (1)	10.00	
S-R	0/2308	-18.5	-18.5 0.42 (1)	10.00	
R-Q	0/2308	-18.5	-18.5 0.42 (1)	10.00	
Q-P	0/2308	-18.5	-18.5 0.42 (1)	10.00	
P-O	0/2308	-18.5	-18.5 0.42 (1)	10.00	
O-N	0/2308	-18.5	-18.5 0.42 (1)	10.00	
N-M	0/1535	-18.5	-18.5 0.35 (1)	10.00	
N-M	0/1433	-18.5	-18.5 0.33 (1)	10.00	

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF

BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF

TOTAL LOAD = 36.0 PSF

**SPACING = 24.0 IN. OC**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TRIC 2011, TRIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17')  
CALCULATED VERT. DEFL.(LL) = L/999 (0.13')  
ALLOWABLE DEFL.(TL) = L/360 (1.17')  
CALCULATED VERT. DEFL.(TL) = L/999 (0.23')

CSI: TC=0.57/1.00 (E-F:1), BC=0.42/1.00 (C-Q:1), WB=0.98/1.00 (J-M:1), SS=0.24/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PL)	
MAX	818	354	
MIN	1667	788	
MAX	1937	1656	

PLATE PLACEMENT TOL. = 0.250 inches  
PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (I) (INPUT = 0.80)  
JSI METAL = 0.72 (P) (INPUT = 1.00)



Structural component only  
DWG# T-2007085



**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - H	2x4	DRY	No.2	SPF	
H - K	2x4	DRY	No.2	SPF	
S - B	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
S - Q	2x4	DRY	No.2	SPF	
Q - N	2x4	DRY	No.2	SPF	
N - L	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
S - C	2x4	DRY	No.2	SPF	
I - L	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TTWW-t	MT20	5.0	8.0	2.50	2.50
D	TTWW+m	MT20	5.0	8.0	2.00	1.75
E	TTWW-t	MT20	4.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMV+w	MT20	2.0	4.0		
H	TTWW+m	MT20	5.0	8.0	2.00	1.75
I	TTWW-t	MT20	5.0	6.0	2.50	2.50
J	TMV+p	MT20	3.0	4.0		
L	BMVW-t	MT20	5.0	8.0		
M	BMVW-t	MT20	4.0	4.0		
N	BS-t	MT20	3.0	6.0		
O	BMVW-w	MT20	4.0	9.0		
P	BMVW-t	MT20	4.0	6.0		
Q	BS-t	MT20	3.0	8.0		
R	BMVW-t	MT20	4.0	4.0		
S	BMVW-t	MT20	5.0	6.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
S	2068	0	2068	0	0	5-8	5-8
L	2068	0	2068	0	0	5-8	5-8

**UNFACTORED REACTIONS**

JT	1ST CASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
S	1458	971/0	0/0	0/0	0/0	488/0	0/0
L	1458	971/0	0/0	0/0	0/0	488/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.81 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.  
 1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-O.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PL)	MAX. UNBRACED LENGTH (FT)	MAX. FACTORED FORCE (LBS)
FR-TO				
A-B	0/41	-91.8	-91.8 0.13 (1)	10.00
B-C	0/26	-91.8	-91.8 0.21 (1)	10.00
C-D	-2006/0	-91.8	-91.8 0.29 (1)	4.50
D-E	-2163/0	-91.8	-91.8 0.73 (1)	3.81
E-F	-2162/0	-91.8	-91.8 0.73 (1)	3.81
F-G	-2162/0	-91.8	-91.8 0.73 (1)	3.81
G-H	-2162/0	-91.8	-91.8 0.73 (1)	3.82
H-I	-2006/0	-91.8	-91.8 0.29 (1)	4.50
I-J	0/26	-91.8	-91.8 0.21 (1)	10.00
J-K	0/41	-91.8	-91.8 0.13 (1)	10.00
S-B	-284/0	0.0	0.0 0.03 (1)	7.81
L-J	-284/0	0.0	0.0 0.03 (1)	7.81
S-R	0/1487	-18.5	-18.5 0.38 (1)	10.00
R-Q	0/1519	-18.5	-18.5 0.39 (1)	10.00
Q-P	0/1519	-18.5	-18.5 0.39 (1)	10.00
P-O	0/2163	-18.5	-18.5 0.42 (1)	10.00
O-N	0/1519	-18.5	-18.5 0.39 (1)	10.00
N-M	0/1519	-18.5	-18.5 0.39 (1)	10.00
M-L	0/1487	-18.5	-18.5 0.38 (1)	10.00

TOTAL WEIGHT = 2 X 163 = 326 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17)  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.10)  
 ALLOWABLE DEFL.(TL) = L/360 (1.17)  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.21)

CSI: TC=0.73/1.00 (D-E:1), BC=0.42/1.00 (O-P:1),  
 WB=0.97/1.00 (I-L:1), SS=0.28/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) (PLI)  
 MAX MIN MAX MIN MAX MIN  
 MT20 618 354 1667 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.87 (I) (INPUT = 0.80)  
 JSI METAL = 0.56 (I) (INPUT = 1.00)



Structural component only  
 DWG# T-2007086



**LUMBER**  
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - K	2x4	DRY	No.2
U - B	2x4	DRY	No.2
L - J	2x4	DRY	No.2
U - R	2x4	DRY	No.2
R - O	2x4	DRY	No.2
O - L	2x4	DRY	No.2
ALL WEBS EXCEPT D - Q, E - P, P - H	2x3	DRY	No.2

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+P	MT20	5.0	8.0	2.00	2.00
C	TMVW-I	MT20	4.0	4.0	2.00	1.25
D	TTVW-M	MT20	5.0	6.0	2.00	1.75
E	TMVW-I	MT20	4.0	4.0		
F	TS-I	MT20	3.0	6.0		
G	TMV+W	MT20	2.0	4.0		
H	TTVW-M	MT20	5.0	6.0	2.00	1.75
I	TMVW-I	MT20	4.0	4.0	2.00	1.25
J	TMVW+P	MT20	5.0	8.0	2.00	2.00
L	BMV1+P	MT20	3.0	4.0		
M	BMVW-I	MT20	5.0	6.0		
N, Q, S						
N	BMVW-I	MT20	4.0	4.0		
O	BS-I	MT20	3.0	6.0		
P	BMVW+P	MT20	4.0	9.0		
R	BS-I	MT20	3.0	6.0		
T	BMVW-I	MT20	5.0	6.0		
U	BMV1+P	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
U	2066	0	2066	0
L	2066	0	2066	0

**UNFACTORED REACTIONS**

JT	1ST CASE COMBINED	MAX/MIN. SNOW	MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
U	1458	971/0	0/0	0/0	0/0	488/0	0/0
L	1458	971/0	0/0	0/0	0/0	488/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, L

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.44 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, E-P, G-F.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED (PLF)		MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	
		FROM	TO			FR	TO
A-B	0/41	-91.8	-91.8	0.13 (1)	T-C	-357/0	0.16 (1)
B-C	-1994/0	-91.8	-91.8	0.30 (1)	C-S	-121/0	0.10 (1)
C-D	-1857/0	-91.8	-91.8	0.29 (1)	S-D	0/188	0.05 (4)
D-E	-1923/0	-91.8	-91.8	0.40 (1)	D-Q	0/810	0.13 (1)
E-F	-1921/0	-91.8	-91.8	0.37 (1)	Q-E	-569/0	0.31 (1)
F-G	-1921/0	-91.8	-91.8	0.37 (1)	E-P	-3/0	0.00 (1)
G-H	-1921/0	-91.8	-91.8	0.40 (1)	P-G	-568/0	0.31 (1)
H-I	-1957/0	-91.8	-91.8	0.28 (1)	H-H	0/807	0.13 (1)
I-J	-1894/0	-91.8	-91.8	0.30 (1)	N-H	0/189	0.05 (4)
J-K	0/41	0.0	0.0	0.22 (1)	N-I	-121/0	0.10 (1)
U-B	-2028/0	0.0	0.0	0.22 (1)	M-I	-358/0	0.18 (1)
L-J	-2028/0	0.0	0.0	0.22 (1)	B-T	0/1817	0.38 (1)
U-T	0/0	-18.5	-18.5	0.08 (4)	M-J	0/1817	0.38 (1)
T-S	0/1555	-18.5	-18.5	0.30 (1)			
S-R	0/1477	-18.5	-18.5	0.30 (1)			
R-Q	0/1477	-18.5	-18.5	0.30 (1)			
Q-P	0/1923	-18.5	-18.5	0.38 (1)			
P-O	0/1478	-18.5	-18.5	0.30 (1)			
O-N	0/1478	-18.5	-18.5	0.30 (1)			
N-M	0/1555	-18.5	-18.5	0.31 (1)			
M-L	0/0	-18.5	-18.5	0.08 (4)			

TOTAL WEIGHT = 2 X 182 = 363 LB

**DESIGN CRITERIA**

SPECIFIED LOADS:  
TOP CH. LL = 25.8 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2018, OBC 2012, ABC 2018  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17)  
CALCULATED VERT. DEFL.(LL) = L/939 (0.09)  
ALLOWABLE DEFL.(TL) = L/360 (1.17)  
CALCULATED VERT. DEFL.(TL) = L/939 (0.16)

CSI: TC=0.40/1.00 (D-E:1), BC=0.38/1.00 (P-Q:1), WB=0.38/1.00 (B-T:1), SSI=0.25/1.00 (D-E:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**


PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354 1667 798 1987 1666	

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.89 (B) (INPUT = 0.90)  
JSI METAL = 0.50 (C) (INPUT = 1.00)





**LUMBER**  
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - I	2x4	DRY No.2	SPF
R - B	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
R - O	2x4	DRY No.2	SPF
O - M	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
ALL WEBS EXCEPT D - N	2x3	DRY No.2	SPF
N - F	2x4	DRY No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	1.50	3.00
C	TMWW-t	MT20	4.0	4.0	2.00	1.25
D	TTWW-m	MT20	5.0	6.0	2.25	1.50
E	TMVW-w	MT20	2.0	4.0		
F	TTWW-m	MT20	5.0	6.0	2.25	1.50
G	TMWW-t	MT20	4.0	4.0	2.00	1.25
H	TMVW-p	MT20	5.0	6.0	1.50	3.00
J	BMV1-p	MT20	3.0	4.0		
K	BMWW-t	MT20	5.0	6.0		
L	BMWW-t	MT20	4.0	4.0		
M	BS-t	MT20	3.0	6.0		
N	BMWW-t	MT20	4.0	9.0		
O	BS-t	MT20	3.0	6.0		
P	BMWW-t	MT20	4.0	4.0		
Q	BMWW-t	MT20	5.0	6.0		
R	BMV1-p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	VERT	HORZ	UPLIFT	IN-SX
R	2066	0	0	5-8
J	2066	0	0	5-8

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
R	1458	971/0	0/0	0/0	0/0	0/0	488/0	0/0
J	1458	971/0	0/0	0/0	0/0	0/0	488/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.96 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS		WEBS	
		VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB. MAX. FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO	FR-TO	
A-B	0/41	-91.8	-91.8 0.13 (1)	10.00	Q-C -302/0 0.17 (1)
B-C	-2021/0	-91.8	-91.8 0.39 (1)	4.41	C-P -217/0 0.25 (1)
C-D	-1808/0	-91.8	-91.8 0.37 (1)	4.52	P-D 0/278 0.08 (1)
D-E	-1809/0	-91.8	-91.8 0.74 (1)	3.96	D-N 0/615 0.10 (1)
E-F	-1809/0	-91.8	-91.8 0.37 (1)	3.96	N-E -888/0 0.58 (1)
F-G	-1808/0	-91.8	-91.8 0.37 (1)	4.41	N-F 0/615 0.10 (1)
G-H	-2021/0	-91.8	-91.8 0.39 (1)	4.41	L-F 0/278 0.08 (1)
H-I	0/41	-91.8	-91.8 0.13 (1)	10.00	L-G -217/0 0.25 (1)
R-B	-2024/0	0.0	0.0 0.22 (1)	5.94	K-G -302/0 0.17 (1)
J-H	-2024/0	0.0	0.0 0.22 (1)	5.94	B-Q 0/1629 0.37 (1)
R-Q	0/0	-18.5	-18.5 0.10 (4)	10.00	K-H 0/1629 0.37 (1)
Q-P	0/1580	-18.5	-18.5 0.34 (1)	10.00	
P-O	0/1437	-18.5	-18.5 0.35 (1)	10.00	
O-N	0/1437	-18.5	-18.5 0.35 (1)	10.00	
N-M	0/1437	-18.5	-18.5 0.35 (1)	10.00	
M-L	0/1437	-18.5	-18.5 0.35 (1)	10.00	
L-K	0/1580	-18.5	-18.5 0.34 (1)	10.00	
K-J	0/0	-18.5	-18.5 0.10 (4)	10.00	

TOTAL WEIGHT = 4 X 173 = 693 LB

**DESIGN CRITERIA**

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 8.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2010, CBC 2012, ABC 2010  
- PART 9 OF CBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 6.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17')  
CALCULATED VERT. DEFL.(LL) = L/999 (0.08')  
ALLOWABLE DEFL.(TL) = L/360 (1.17')  
CALCULATED VERT. DEFL.(TL) = L/999 (0.17')

CSI: TC=0.74/1.00 (D-E:1), BC=0.35/1.00 (L-N:1), WB=0.58/1.00 (E-N:1), SS=0.33/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES  
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)  
MAX MIN MAX MIN MAX MIN  
MT20 618 354 1667 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (B) (INPUT = 0.90)  
JSI METAL= 0.48 (M) (INPUT = 1.00)



Structural component only  
DWG# T-2007088



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
G - H	2x4	DRY	No.2	SPF
H - K	2x4	DRY	No.2	SPF
T - B	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
T - Q	2x4	DRY	No.2	SPF
O - O	2x4	DRY	No.2	SPF
O - L	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x4	DRY	No.2	SPF
S - C	2x3	DRY	No.2	SPF
C - R	2x3	DRY	No.2	SPF
N - I	2x3	DRY	No.2	SPF
M - I	2x3	DRY	No.2	SPF
B - S	2x3	DRY	No.2	SPF
M - J	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X	
B	TMVW-p	MT20	5.0	8.0	1.50	3.00
C	TMVW-t	MT20	4.0	4.0	2.00	1.25
D	TS-t	MT20	3.0	6.0		
E	TTWV-m	MT20	5.0	8.0	Edge	3.00
F	TMVW-w	MT20	2.0	4.0		
G	TTWV-m	MT20	5.0	8.0	Edge	3.00
H	TS-t	MT20	3.0	6.0		
I	TMVW-t	MT20	4.0	4.0	2.00	1.25
J	TMVW-p	MT20	5.0	6.0	1.50	3.00
L	BMV1-p	MT20	3.0	4.0		
M	BMVW-t	MT20	5.0	6.0		
N	BMVW-t	MT20	4.0	4.0		
O	BS-t	MT20	3.0	6.0		
P	BMVW-w	MT20	4.0	8.0		
Q	BS-t	MT20	3.0	6.0		
R	BMVW-t	MT20	4.0	4.0		
S	BMVW-t	MT20	5.0	6.0		
T	BMV1-p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
T	2068	0	2068	0	0
L	2068	0	2068	0	0

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX. SNOW	MIN. LIVE	PERM. WIND	DEAD	SOIL
T	1458	971/0	0/0	0/0	0/0	488/0
L	1458	971/0	0/0	0/0	0/0	488/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, L

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.27 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-R, F-P, H-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS		WEBS		
		FACTORED VERT. LOAD (PLF)	MAX. CS (LC)	MAX. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)	
FR-TO		FROM TO		FR-TO		
A-B	0/41	-91.8 -91.8	0.13 (1)	10.00	S-C -245/10	0.17 (1)
B-C	-2038/0	-91.8 -91.8	0.50 (1)	4.27	C-R -314/0	0.15 (1)
C-D	-1844/0	-91.8 -91.8	0.46 (1)	4.47	R-E 0/338	0.06 (1)
D-E	-1844/0	-91.8 -91.8	0.46 (1)	4.47	E-P 0/469	0.08 (1)
E-F	-1621/0	-91.8 -91.8	0.50 (1)	4.60	P-F -699/0	0.45 (1)
F-G	-1621/0	-91.8 -91.8	0.50 (1)	4.60	P-G 0/469	0.08 (1)
G-H	-1844/0	-91.8 -91.8	0.46 (1)	4.47	N-G 0/338	0.05 (1)
H-I	-1844/0	-91.8 -91.8	0.46 (1)	4.47	N-I -314/0	0.15 (1)
I-J	-2038/0	-91.8 -91.8	0.50 (1)	4.27	M-I -245/10	0.17 (1)
J-K	0/41	-91.8 -91.8	0.13 (1)	10.00	B-S 0/1637	0.37 (1)
K-B	-2021/0	0.0 0.0	0.21 (1)	5.94	M-J 0/1637	0.37 (1)
L-J	-2021/0	0.0 0.0	0.21 (1)	5.94		
T-S	0/0	-18.5 -18.5	0.14 (4)	10.00		
S-R	0/1597	-18.5 -18.5	0.33 (1)	10.00		
R-Q	0/1367	-18.5 -18.5	0.30 (1)	10.00		
Q-P	0/1367	-18.5 -18.5	0.30 (1)	10.00		
P-O	0/1367	-18.5 -18.5	0.30 (1)	10.00		
O-N	0/1367	-18.5 -18.5	0.30 (1)	10.00		
N-M	0/1597	-18.5 -18.5	0.33 (1)	10.00		
M-L	0/0	-18.5 -18.5	0.14 (4)	10.00		

TOTAL WEIGHT = 2 X 190 = 380 lb

**DESIGN CRITERIA**

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF

BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBC 2018, OBC 2012, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPG 2011, TPC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17')  
CALCULATED VERT. DEFL.(LL) = L/999 (0.07')  
ALLOWABLE DEFL.(TL) = L/360 (1.17')  
CALCULATED VERT. DEFL.(TL) = L/999 (0.14')

CSI: TC=0.50/1.00 (E-F:1), BC=0.33/1.00 (M-N:1), WB=0.45/1.00 (F-P:1), SS=0.28/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)

MAX MIN MAX MIN MAX MIN


MT20 618 354 1667 788 1987 1658

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.89 (J) (INPUT = 0.90)

JSI METAL= 0.47 (O) (INPUT = 1.00)




Structural component only  
DWG# T-2007089



JOB NAME 408151	TRUSS NAME T28	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:19:54 2020 Page 1  
ID:h2dfgC44wS\_E2tzqPs\_atzllRw-x1EndQIngdw3kqMZ0AghhTAWTQH0o87bX5n7vxzNCXZ



**LUMBER**

N. L. G. A. RULES	SIZE	LUMBER	DESCR.
A - D	2x4	No.2	SPF
O - G	2x4	No.2	SPF
L - B	2x4	No.2	SPF
H - F	2x4	No.2	SPF
L - J	2x4	No.2	SPF
J - H	2x4	No.2	SPF

ALL WEBS 2x3 DRY No.2 EXCEPT  
SPF

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0	
C	TMWW-t	MT20	4.0	6.0	
D	TTWW+p	MT20	4.0	6.0	Edge
E	TMWW-t	MT20	4.0	5.0	
F	TMV+p	MT20	3.0	4.0	
H	BMVW-t	MT20	4.0	4.0	
I	BMVW-t	MT20	4.0	6.0	
J	BS-t	MT20	3.0	6.0	
K	BMVW-t	MT20	4.0	6.0	
L	BMVW-t	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
L	1041	0	1041	0
H	1041	0	1041	0

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX./MIN. SNOW	MIN. LIVE	PERMLIVE	WIND	DEAD	SOIL
L	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0
H	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. MOM. (LC)	MAX. MEMB. LENGTH	MAX. FORCE (LBS)	MAX. MOM. (LC)
FR-TO		FROM TO		FR-TO		
A-B	0 / 41	-91.8	-91.8 0.13 (1)	10.00	D-I	0 / 339
B-C	0 / 29	-91.8	-91.8 0.26 (1)	10.00	E-E	-222 / 0
C-D	-764 / 0	-91.8	-91.8 0.20 (1)	6.25	K-D	0 / 339
D-E	-764 / 0	-91.8	-91.8 0.20 (1)	6.25	C-K	-222 / 0
E-F	0 / 29	-91.8	-91.8 0.26 (1)	10.00	L-C	-964 / 0
F-G	0 / 41	-91.8	-91.8 0.13 (1)	10.00	E-H	-964 / 0
L-B	-270 / 0	0.0	0.0 0.03 (1)	7.81		
H-F	-270 / 0	0.0	0.0 0.03 (1)	7.81		
L-K	0 / 832	-18.5	-18.5 0.16 (4)	10.00		
K-J	0 / 459	-18.5	-18.5 0.17 (4)	10.00		
J-I	0 / 459	-18.5	-18.5 0.17 (4)	10.00		
I-H	0 / 832	-18.5	-18.5 0.16 (4)	10.00		

TOTAL WEIGHT = 2 X 92 = 184 LBS

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 888-09, CSA 885-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")  
CALCULATED VERT. DEFL.(LL) = L/899 (0.02")  
ALLOWABLE DEFL.(TL) = L/360 (0.55")  
CALCULATED VERT. DEFL.(TL) = L/898 (0.04")

CSI: TC=0.26/1.00 (B-C:1), BC=0.18/1.00 (H-I:4), WB=0.86/1.00 (E-H:1), SS=0.14/1.00 (C-D:1)


DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)  
MAX MIN MAX MIN MAX MIN  
MT20 518 354 1667 768 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches  
PLATE ROTATION TOL. = 5.0 Deg.  
JSI GRIP= 0.78 (C) (INPUT = 0.90)  
JSI METAL= 0.26 (C) (INPUT = 1.00)



Structural component only  
DWG# T-2007090



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
L - B	2x4	DRY	No.2
H - F	2x4	DRY	No.2
L - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	4.0	4.0	2.00	1.50
D	TTWW+p	MT20	5.0	6.0	Edge	
E	TMWW-t	MT20	4.0	4.0	2.00	1.50
F	TMV+p	MT20	3.0	4.0		
H	BMVW1-t	MT20	4.0	4.0		
I	BMVW-t	MT20	4.0	4.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-t	MT20	4.0	4.0		
L	BMVW1-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

DESCR.	SPF	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
		VERT	MAX DOWN	IN-SX	IN-SX
JT	SPF	1041	1041	5-8	5-8
L	SPF	1041	0	5-8	5-8
H	SPF	1041	0	5-8	5-8

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	MAX/LIVE	MIN/PERM	LIVE	WIND	DEAD	SOIL
L	734	495/0	0/0	0/0	0/0	0/0	239/0	0/0
H	734	495/0	0/0	0/0	0/0	0/0	239/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. (PLF)	FACTORED LOAD (LC1)	MAX. UNBRACED LENGTH	MEMB. LENGTH	WEBS	
						MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO							
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	D-I	0/254
B-C	0/28	-91.8	-91.8	0.26 (1)	10.00	J-E	-138/14
C-D	-633/0	-91.8	-91.8	0.20 (1)	6.25	K-D	0/254
D-E	-633/0	-91.8	-91.8	0.20 (1)	8.25	C-K	-138/14
E-F	0/28	-91.8	-91.8	0.26 (1)	10.00	L-C	875/0
F-G	0/41	-91.8	-91.8	0.13 (1)	10.00	E-H	-875/0
L-B	-278/0	0.0	0.0	0.04 (1)	7.81		
H-F	-278/0	0.0	0.0	0.04 (1)	7.81		
L-K	0/495	-18.5	-18.5	0.17 (4)	10.00		
K-J	0/395	-18.5	-18.5	0.16 (4)	10.00		
J-I	0/395	-18.5	-18.5	0.16 (4)	10.00		
I-H	0/495	-18.5	-18.5	0.17 (4)	10.00		

TOTAL WEIGHT = 91 lb (M/F)

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH.	LL = 25.6 PSF
	DL = 8.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

**SPACING = 24.0 IN./C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, CBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.02")  
 ALLOWABLE DEFL.(TL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.28/1.00 (E-F:1), BC=0.17/1.00 (K-L:4), WB=0.90/1.00 (E-H:1), SS=0.14/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**


PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	818	384	1667
	788	1987	1655

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.88 (E) (INPUT = 0.80)  
 JSI METAL = 0.34 (C) (INPUT = 1.00)





**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER
A - D	2x4	DRY	No.2	
D - E	2x6	DRY	No.2	
E - H	2x4	DRY	No.2	
L - B	2x4	DRY	No.2	
L - G	2x4	DRY	No.2	
L - K	2x4	DRY	No.2	
K - I	2x4	DRY	No.2	
ALL WEBS EXCEPT	2x3	DRY	No.2	

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMV-p	MT20	3.0	4.0	
C	TMWW-t	MT20	4.0	4.0	2.00 1.75
D	TTW-h	MT20	4.0	8.0	
E	TTWW-m	MT20	5.0	8.0	Edge
F	TMWW-t	MT20	4.0	8.0	
G	TMV-p	MT20	3.0	4.0	
I	BMWW-1	MT20	4.0	4.0	
J	BMWW-t	MT20	4.0	4.0	
K	BSWW-1	MT20	6.0	9.0	Edge 3.75
L	BMWW-1	MT20	4.0	4.0	

Edge: INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	1041	0	0
JT HORZ	0	1041	0
L VERT	1041	0	0
L HORZ	0	1041	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 3-8.

**UNFACTORED REACTIONS**

1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0
L	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.  
1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)		MAX. UNBRACED LENGTH	WEBS MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
		FROM	TO				
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	C-K	-98 / 9
B-C	0 / 27	-91.8	-91.8	0.23 (1)	10.00	K-D	0 / 164
C-D	-595 / 0	-91.8	-91.8	0.18 (1)	8.25	K-E	-109 / 0
D-E	-414 / 0	-91.8	-91.8	0.01 (1)	8.25	J-E	0 / 288
E-F	-582 / 0	-91.8	-91.8	0.18 (1)	8.25	J-F	-93 / 15
F-G	0 / 27	-91.8	-91.8	0.23 (1)	10.00	L-C	-846 / 0
G-H	0 / 41	-91.8	-91.8	0.13 (1)	10.00	F-I	-852 / 0
L-B	-265 / 0	0.0	0.0	0.04 (1)	7.81		
L-G	-265 / 0	0.0	0.0	0.04 (1)	7.81		
L-K	0 / 488	-18.5	-18.5	0.38 (4)	10.00		
K-J	0 / 424	-18.5	-18.5	0.30 (4)	10.00		
J-I	0 / 477	-18.5	-18.5	0.30 (4)	10.00		

TOTAL WEIGHT = 97 lb (MIP)

**DESIGN CRITERIA**

DESIGNED LOADS:  
TOP CH. LL = 25.8 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, GSA 086-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")  
ALLOWABLE DEFL.(TL) = L/360 (0.55")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.17")

CSI: TC=0.23/1.00 (B-C:1), BC=0.38/1.00 (K-L:4), WB=0.79/1.00 (F-I:1), SSB=0.14/1.00 (J-K:4)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PL)
MT20	618	354 1667 788 1967 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (C) (INPUT = 0.90)  
JSI METAL = 0.31 (C) (INPUT = 1.00)



Structural component only  
DWG# T-2007092



**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER
A - D	2x4	DRY	No.2	
D - E	2x4	DRY	No.2	
E - H	2x4	DRY	No.2	
M - B	2x4	DRY	No.2	
I - G	2x4	DRY	No.2	
M - K	2x4	DRY	No.2	
K - I	2x4	DRY	No.2	
ALL WEBS EXCEPT	2x3	DRY	No.2	

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-l	MT20	4.0	4.0	2.00	1.75
D	TTW-m	MT20	4.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMWW-l	MT20	4.0	4.0	2.00	1.75
G	TMV+p	MT20	3.0	4.0		
I	BMVW-l	MT20	4.0	4.0		
J	BMVW-l	MT20	4.0	4.0		
K	BS-l	MT20	3.0	6.0		
L	BMVW-l	MT20	4.0	9.0		
M	BMVW-l	MT20	4.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

DESCR.	SPF	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	SPF	VERT	DOWN	UPLIFT	IN-SX
M	SPF	1041	0	0	5-8
I	SPF	1041	0	0	5-8

A SUITABLE HANGERMechanical CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 3-8.

**UNFACTORED REACTIONS**

JT	1ST CASE COMBINED	MAX. SNOW	MIN. LIVE	PERM. LIVE	DEAD	SOIL
M	734	495/0	0/0	0/0	239/0	0/0
I	734	495/0	0/0	0/0	239/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX	MEMB. LENGTH FR-TO	MAX. FACTORED FORCE (LBS)	MAX	CS1 (LC)
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	C-L	-10/34	0.01 (4)
B-C	0/22	-91.8	-91.8	0.16 (1)	10.00	L-D	0/110	0.03 (4)
C-D	-613/0	-91.8	-91.8	0.13 (1)	6.25	L-E	0/0	0.00 (7)
D-E	-483/0	-91.8	-91.8	0.14 (1)	6.25	J-E	0/109	0.03 (4)
E-F	-612/0	-91.8	-91.8	0.13 (1)	6.25	J-F	-11/34	0.01 (4)
F-G	0/22	-91.8	-91.8	0.16 (1)	10.00	M-C	-873/0	0.80 (1)
G-H	0/41	-91.8	-91.8	0.13 (1)	10.00	F-I	-873/0	0.80 (1)
M-B	-245/0	0.0	0.0	0.04 (1)	7.81			
I-G	-245/0	0.0	0.0	0.04 (1)	7.81			
M-L	0/457	-18.5	-18.5	0.21 (4)	10.00			
L-K	0/453	-18.5	-18.5	0.20 (4)	10.00			
K-J	0/453	-18.5	-18.5	0.20 (4)	10.00			
J-I	0/457	-18.5	-18.5	0.21 (4)	10.00			

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF

BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN./C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(LL) = L/989 (0.01")  
 ALLOWABLE DEFL.(TL) = L/360 (0.55")  
 CALCULATED VERT. DEFL.(TL) = L/989 (0.07")

CS1: TC=0.16/1.00 (F-G-1), BC=0.21/1.00 (L-J-4),  
 WB=0.60/1.00 (C-M-1), SS1=0.12/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP (DRY)	(PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	618	354	1687 788 1987 1688

PLATE PLACEMENT TOL = 0.250 inches  
 PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.87 (C) (INPUT = 0.90)  
 JSI METAL = 0.31 (C) (INPUT = 1.00)





TOTAL WEIGHT = 79 lb

**LUMBER**

**N.L.G.A. RULES**

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2
C - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
K - B	2x4	DRY	No.2
G - E	2x4	DRY	No.2
K - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

**PLATES (tablets in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
C	TTWW+m	MT20	5.0	6.0	2.25 1.50
D	TTW-m	MT20	4.0	4.0	
E	TMVW+p	MT20	4.0	4.0	1.00 2.00
G	BMV1+p	MT20	3.0	4.0	
H	BMWWW-t	MT20	4.0	9.0	
I	BS-1	MT20	3.0	6.0	
J	BMWW-t	MT20	4.0	4.0	
K	BMV1+p	MT20	3.0	4.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	RECORD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
K	1041	0	1041	0	5-8	5-8
G	1041	0	1041	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

**UNFACTORED REACTIONS**

JT	COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
K	734	495/0	0/0	0/0	0/0	239/0	0/0
G	734	495/0	0/0	0/0	0/0	239/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	FR-TO	CHORDS		WEBS	
		MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (PLF)
A-B	0/41	-91.8	-91.8	10.00	10.00
B-C	-619/0	-91.8	-91.8	8.25	8.25
C-D	-473/0	-91.8	-91.8	8.25	8.25
D-E	-619/0	-91.8	-91.8	8.25	8.25
E-F	0/41	-91.8	-91.8	10.00	10.00
K-B	-1000/0	0.0	0.0	7.81	7.81
G-E	-1000/0	0.0	0.0	7.81	7.81
K-J	0/0	-18.5	-18.5	10.00	10.00
J-I	0/473	-18.5	-18.5	10.00	10.00
I-H	0/473	-18.5	-18.5	10.00	10.00
H-G	0/0	-18.5	-18.5	10.00	10.00

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.8 PSF  
DL = 8.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. OC**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2010, CBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55')  
CALCULATED VERT. DEFL.(LL) = L/999 (0.01')  
ALLOWABLE DEFL.(TL) = L/360 (0.55')  
CALCULATED VERT. DEFL.(TL) = L/999 (0.03')

CSI: TC=0.39/1.00 (C-D:1), BC=0.17/1.00 (H-J:4), WB=0.12/1.00 (B-J:1), SS=0.21/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PL)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1897 788	1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.82 (B) (INPUT = 0.90)  
JSI METAL = 0.23 (B) (INPUT = 1.00)



Structural component only  
DWG# T-2007094



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
L - B	2x4	DRY	No.2
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
H - F	2x4	DRY	No.2
L - H	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
ALL GABLE WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

GABLE STUDS SPACED AT 2-0-0 OC.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
C	TMW+w	MT20	2.0	4.0	
D	TTW+p	MT20	4.0	6.0	Edge
E	TMW+w	MT20	2.0	4.0	
F	TMVW+p	MT20	4.0	4.0	1.00 2.00
H	BMV1+p	MT20	3.0	4.0	
I	BMW1-t	MT20	4.0	4.0	
J	BMW1+w	MT20	2.0	4.0	
K	BMW1-t	MT20	4.0	4.0	
L	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**  
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.  
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.  
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	FACTORED LC1 MAX CSI(LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI(LC)
L-B	-231 / 0	0.0	0.0 0.02 (1)	7.91	J-D	-123 / 0	0.05 (1)
A-B	0 / 41	-91.8	-91.8 0.13 (1)	10.00	K-C	-236 / 0	0.05 (1)
B-C	-11 / 0	-91.8	-91.8 0.07 (1)	6.25	I-E	-236 / 0	0.05 (1)
C-D	-32 / 0	-91.8	-91.8 0.07 (1)	6.25	B-K	0 / 23	0.01 (1)
D-E	-32 / 0	-91.8	-91.8 0.07 (1)	6.25	I-F	0 / 23	0.01 (1)
E-F	-11 / 0	-91.8	-91.8 0.07 (1)	6.25			
F-G	0 / 41	-91.8	-91.8 0.13 (1)	10.00			
H-F	-231 / 0	0.0	0.0 0.02 (1)	7.91			
L-K	0 / 0	-18.5	-18.5 0.02 (4)	10.00			
K-J	0 / 13	-18.5	-18.5 0.02 (4)	10.00			
J-I	0 / 13	-18.5	-18.5 0.02 (4)	10.00			
I-H	0 / 0	-18.5	-18.5 0.02 (4)	10.00			

TOTAL WEIGHT = 42 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 5.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 38.0 PSF

**SPACING = 2.0 IN. C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019  
- PART 9 OF CBC 2012 (2019 AMENDMENT)  
- CSA 086-08, CSA 086-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TO=0.13/1.00 (F-G:1), BC=0.02/1.00 (J-K:4), WB=0.05/1.00 (C-K:1), SSI=0.08/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	618	354	1667 788 1987 1658


PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.18 (C) (INPUT = 0.30)  
JSI METAL = 0.13 (C) (INPUT = 1.00)



Structural component only  
DWG# T-2007078



Scale = 1/32

TOTAL WEIGHT = 37 lb

**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - B	2x4	DRY	No.2
B - C	2x4	DRY	No.2
F - A	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMW+p	MT20	4.0	4.0	1.00	2.00
B	TTW+p	MT20	4.0	8.0	Edge	
C	TMW+p	MT20	4.0	4.0	1.00	2.00
D	BMV1+p	MT20	3.0	4.0		
E	BMWVW-t	MT20	4.0	9.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX
JT	VERT	HORZ	DOWN	HORZ
F	486	0	486	0
D	486	0	486	0

**UNFACTORED REACTIONS**

JT	1ST LCASE	MAX. SNOW	MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	351	230 / 0	0 / 0	0 / 0	0 / 0	121 / 0	0 / 0
D	351	230 / 0	0 / 0	0 / 0	0 / 0	121 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD				MAX. UNBRAC LENGTH	FR-TO	WEBS			
		VERT.	LC1	MAX	MAX.			MEMB.	FORCE (LBS)	MAX	CSI (LC)
A-B	-311 / 0	-91.8	-91.8	0.24 (1)	6.25	E-B	-14 / 72	0.03	0.06 (4)		
B-C	-311 / 0	-91.8	-91.8	0.24 (1)	6.25	A-E	0 / 248	0.06	0.06 (1)		
F-A	-454 / 0	0.0	0.0	0.05 (1)	7.81	E-C	0 / 248	0.06	0.06 (1)		
D-C	-454 / 0	0.0	0.0	0.05 (1)	7.81						
F-E	0 / 0	-18.5	-18.5	0.11 (4)	10.00						
E-D	0 / 0	-18.5	-18.5	0.11 (4)	10.00						

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 8.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2018, OBC 2012, ABC 2019  
- PART 9 OF CBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPC 2011, TPC 2014

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.30")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")  
ALLOWABLE DEFL.(TL) = L/360 (0.30")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.24/1.00 (A-B:1), BC=0.11/1.00 (E-F:4), WB=0.06/1.00 (C-E:1), SS=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE	GRIP(DRY)	SHEAR (PS)	SECTION (PL)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.42 (A) (INPUT = 0.90)  
JSI METAL = 0.12 (A) (INPUT = 1.00)



Structural component only  
DWG# T-2007095

JOB NAME 408151	TRUSS NAME T34	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	



Version 8.310 S Oct 29 2019 Mitak Industries, Inc. Sat Apr 25 11:20:00 2020 Page 1  
 ID:h2dfhgC44wS\_E2tzqPs\_atzllRw-mBc3uRx8GmODTtpiNfN5xkQXdLlC2aUv0ER7azNCXT  
 Scale = 1/8\"/>

**LUMBER**  
N. L. G. A. RULES

CHORDS	SIZE	DRY	No.2	DESCR.
A - B	2x4	DRY	No.2	SPF
B - C	2x4	DRY	No.2	SPF
F - A	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF EXCEPT

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW+P	MT20	4.0	4.0	1.00 2.00
B	TTW+P	MT20	4.0	6.0	Edge
C	TMVW+P	MT20	4.0	4.0	1.00 2.00
D	BMV1+P	MT20	3.0	4.0	
E	BMVWW-1	MT20	4.0	9.0	
F	BMV1+P	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
F	489	0	489	0	0	MECHANICAL	
D	489	0	489	0	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 1-8, JOINT D = 1-8.

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	331	217 / 0	0 / 0	0 / 0	0 / 0	114 / 0	0 / 0
D	331	217 / 0	0 / 0	0 / 0	0 / 0	114 / 0	0 / 0

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS			WEBS		
		VERT. LOAD (PL)	MAX. CS1 (LC)	MAX. UNBRAC LENGTH	MEMB. FORCE (LBS)	MAX. CS1 (LC)	
FR-TO							
A-B	-218 / 0	-91.8	-91.8 0.21 (1)	6.25	E-B	-111 / 32 0.07 (1)	
B-C	-218 / 0	-91.8	-91.8 0.21 (1)	6.25	A-E	0 / 197 0.04 (1)	
F-A	-438 / 0	0.0	0.0 0.07 (1)	7.81	E-C	0 / 197 0.04 (1)	
D-C	-438 / 0	0.0	0.0 0.07 (1)	7.81			
F-E	0 / 0	-18.5	-18.5 0.09 (4)	10.00			
E-D	0 / 0	-18.5	-18.5 0.09 (4)	10.00			

TOTAL WEIGHT = 2 X 41 = 82 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN/OC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2010, CBC 2012, ABC 2019  
 - PART 9 OF CBC 2012 (2019 AMENDMENT)  
 - CSA 088-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 6.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.28")  
 CALCULATED VERT. DEFL.(LL) = L/989 (0.00")  
 ALLOWABLE DEFL.(TL) = L/360 (0.28")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.21/1.00 (A-B:1), BC=0.09/1.00 (E-F:4), WB=0.07/1.00 (B-E:1), SS=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP(DRY) SHEAR SECTION (PSI)	(PL)		(PL)	
	MAX	MIN	MAX	MIN
MT20	618	354	1667	788
			1987	1656

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.33 (A) (INPUT = 0.90)  
 JSI METAL= 0.09 (A) (INPUT = 1.00)



Structural component only  
 DWG# T-2007096





**LUMBER**  
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
F - A	2x4	DRY No.2	SPF
A - C	2x4	DRY No.2	SPF
D - C	2x4	DRY No.2	SPF
F - D	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F-A 1	12	TOP
A-C 1	12	TOP
C-D 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 1	11	SIDE(19.1)
WEBS : (0.122"x3") SPIRAL NAILS		
B-E 1	8	SIDE(20.3)
2x3 1	8	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.  
GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-1	MT20	4.0	5.0	
B	TMVW-w	MT20	2.0	4.0	
C	TMVW-1	MT20	4.0	5.0	
D	BMV1-p	MT20	3.0	4.0	
E	BMVW-1	MT20	4.0	5.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER.**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
F	1016	0	1016	0
D	1085	0	1085	0

MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	728	436/0	0/0	0/0	0/0	280/0	0/0
D	772	479/0	0/0	0/0	0/0	293/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.23 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	FACTORED				UNBRAC LENGTH	WEBS	
			LC1	MAX	MAX.	MEMB. FORCE (LBS)		MAX. FACTORED CSI (LC)	
FR-TO									
F-A	-865/0	0.0	0.0	0.05 (1)	7.81		A-E	0/1810	0.22 (1)
A-G	-1708/0	-91.8	-91.8	0.28 (1)	6.23		E-B	-482/0	0.04 (1)
G-B	-1708/0	-91.8	-91.8	0.28 (1)	6.23		E-C	0/1810	0.22 (1)
B-C	-1708/0	-91.8	-91.8	0.08 (1)	6.25				
D-C	-707/0	0.0	0.0	0.04 (1)	7.81				
F-E	0/0	-43.5	-43.5	0.05 (4)	10.00				
E-H	0/0	-43.5	-43.5	0.22 (1)	10.00				
H-D	0/0	-43.5	-43.5	0.22 (1)	10.00				

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	3-0-12	-450	-450		FRONT	VERT	TOTAL		C1
G	1-0-12	-404	-404		TOP	VERT	TOTAL		C1
H	5-0-12	-452	-452		FRONT	VERT	TOTAL		C1

**CONNECTION REQUIREMENTS**  
1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

**DESIGN CRITERIA**

\*\*\* SPECIAL LOADS ANALYSIS \*\*\*  
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.  
LOADS WERE DERIVED FROM USER INPUT  
NO FURTHER MODIFICATIONS WERE MADE

**SPECIFIED LOADS:**

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

**SPACING = 24.0 IN. OC**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

\*\*\* NON STANDARD GIRDER \*\*\*  
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 088-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")  
ALLOWABLE DEFL.(TL) = L/360 (0.20")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.28/1.00 (A-B:1), BC=0.22/1.00 (D-E:1), WB=0.22/1.00 (A-E:1), SS=0.16/1.00 (D-E:1)

DDL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

**NAIL VALUES**

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	818	354
	1667	788
	1987	1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP=0.59 (C) (INPUT = 0.80)  
JSI METAL=0.21 (C) (INPUT = 1.00)



Structural component only  
DWG# T-2007097

JOB NAME 408151	TRUSS NAME T35	QUANTITY 2	PLY 2	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:20:01 2020 Page 2  
 ID:h2dflgC44wS E2zqPs atzIRw-EO9R6nvm13W44?Ow8IKTxhdFf xTUd8gz f1zNCS


**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
F	BMV1+p	MT20	3.0	4.0	



Structural component only  
 DWG# T-2007097 3/2

JOB NAME 408151 Tamarack Roof Truss, Burlington	TRUSS NAME G36	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
				TRUSS DESC.	



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
P - B	2x4	DRY No.2
A - E	2x4	DRY No.2
E - I	2x4	DRY No.2
J - H	2x4	DRY No.2
P - J	2x4	DRY No.2

ALL WEBS 2x3 DRY No.2  
 ALL GABLE WEBS 2x3 DRY No.2  
 DRY: SEASONED LUMBER.  
 GABLE STUDS SPACED AT 2-0-0 OC.

**PLATES (tablets in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B TMW+p	MT20	4.0	4.0	1.00	2.00
C, D, F, G					
C TMW+w	MT20	2.0	4.0		
E TMW+p	MT20	4.0	8.0	Edge	
H TMW+p	MT20	4.0	4.0	1.00	2.00
J BMV1+p	MT20	3.0	4.0		
K BMW1+w	MT20	4.0	4.0		
L, M, N					
L BMV1+w	MT20	2.0	4.0		
O BMW1+w	MT20	4.0	4.0		
P BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**  
 THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.  
 THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.  
 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		MAX. UNBRAC LENGTH	WEBS	FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (PLF)	VERT. LOAD (PLF)	CSI (LC)			MEMB. FORCE (LBS)	MAX. CSI (LC)
FR-TO						FR-TO		
P-B	-274 / 0	0.0	0.0	0.03 (1)	7.81	M-E	-139 / 0	0.09 (1)
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	N-D	-223 / 0	0.07 (1)
B-C	-57 / 0	-91.8	-91.8	0.12 (1)	6.25	C-C	-75 / 0	0.01 (1)
C-D	-4 / 0	-91.8	-91.8	0.06 (1)	10.00	L-F	-223 / 0	0.07 (1)
D-E	-22 / 0	-91.8	-91.8	0.06 (1)	6.25	K-G	-75 / 0	0.01 (1)
E-F	-22 / 0	-91.8	-91.8	0.06 (1)	6.25	B-O	0 / 20	0.00 (1)
F-G	-4 / 0	-91.8	-91.8	0.06 (1)	10.00	K-H	0 / 20	0.00 (1)
G-H	-57 / 0	-91.8	-91.8	0.12 (1)	6.25			
H-I	0 / 41	-91.8	-91.8	0.13 (1)	10.00			
J-H	-274 / 0	0.0	0.0	0.03 (1)	7.81			
P-O	0 / 0	-18.5	-18.5	0.01 (4)	10.00			
O-N	0 / 12	-18.5	-18.5	0.02 (4)	10.00			
N-M	0 / 7	-18.5	-18.5	0.02 (4)	10.00			
M-L	0 / 7	-18.5	-18.5	0.02 (4)	10.00			
L-K	0 / 12	-18.5	-18.5	0.02 (4)	10.00			
K-J	0 / 0	-18.5	-18.5	0.01 (4)	10.00			

TOTAL WEIGHT = 53 lb

**DESIGN CRITERIA**  
 SPECIFIED LOADS:  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF  
**SPACING = 24.0 IN. CC**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 088-14  
 - TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
 - OVERHANG NOT TO BE ALTERED OR CUT OFF.  
 (55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.13/1.00 (H-t1), BC=0.02/1.00 (K-L-4),  
 WB=0.08/1.00 (E-M-1), SB=0.08/1.00 (A-B-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10  
 COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE	GRIP (DRY)	SHEAR	SECTION
(FS)	(PL)	(PL)	
MT20	618	354	1667 788 1987 1668

PLATE PLACEMENT TOL. = 0.250 inches  
 PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.21 (B) (INPUT = 0.90)  
 JSI METAL = 0.12 (F) (INPUT = 1.00)



Structural component only  
 DWG# T-2007079



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - F	2x6	DRY No.2	SPF
F - H	2x8	DRY No.2	SPF
H - J	2x4	DRY No.2	SPF
T - B	2x6	DRY No.2	SPF
K - I	2x6	DRY No.2	SPF
T - Q	2x6	DRY No.2	SPF
Q - N	2x6	DRY No.2	SPF
N - K	2x6	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS SURFACE SPACING (IN) LOAD(PLF)

TOP CHORDS : (0.122"x3") SPIRAL NAILS

A-C	1	12	SIDE(81.0)
H-J	1	12	SIDE(81.0)
C-F	2	12	SIDE(81.0)
F-H	2	12	SIDE(81.0)
T-B	2	12	TOP
K-I	2	12	TOP

BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS

T-Q	2	12	SIDE(183.1)
Q-N	2	12	SIDE(0.0)
N-K	2	12	SIDE(183.1)

WEBS : (0.122"x3") SPIRAL NAILS

2x3	1	6	
-----	---	---	--

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLYS FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT 3331	DOWN 3331	0	5-8
T	HORZ 0	HORZ 0	0	5-8
K	VERT 3331	DOWN 3331	0	5-8

**UNFACTORED REACTIONS**

1ST CASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED	2356	1544 / 0	0 / 0	0 / 0	812 / 0	0 / 0
T		2356	1544 / 0	0 / 0	0 / 0	812 / 0	0 / 0
K		2356	1544 / 0	0 / 0	0 / 0	812 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, K

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.87 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	FORCE (LBS)	CHORDS		WEBS	
		MAX. FACTORED	FACTORED	MAX. FACTORED	MAX. FACTORED
FR-TO					
A-B	0 / 28	-91.8	-91.8 0.07 (1)	10.00	S-C -427 / 8 0.05 (1)
B-C	-5077 / 0	-91.8	-91.8 0.52 (1)	3.87	C-R 0 / 3083 0.38 (1)
C-U	-7108 / 0	-91.8	-91.8 0.23 (1)	4.33	R-D -1565 / 0 0.19 (1)
U-V	-7108 / 0	-91.8	-91.8 0.23 (1)	4.33	O-G 0 / 1071 0.13 (1)
V-D	-7108 / 0	-91.8	-91.8 0.23 (1)	4.33	M-G -1565 / 0 0.19 (1)
D-W	-7994 / 0	-91.8	-91.8 0.27 (1)	4.10	L-H -427 / 8 0.05 (1)
W-X	-7994 / 0	-91.8	-91.8 0.27 (1)	4.10	B-S 0 / 4592 0.57 (1)
X-Y	-7994 / 0	-91.8	-91.8 0.27 (1)	4.10	L-I 0 / 4592 0.57 (1)
Y-E	-7994 / 0	-91.8	-91.8 0.27 (1)	4.10	D-P 0 / 1071 0.13 (1)
E-Z	-7994 / 0	-91.8	-91.8 0.27 (1)	4.10	M-H 0 / 3083 0.38 (1)
Z-F	-7994 / 0	-91.8	-91.8 0.27 (1)	4.10	P-E -505 / 0 0.06 (1)
F-AA	-7994 / 0	-91.8	-91.8 0.27 (1)	4.10	E-O -505 / 0 0.06 (1)
AA-AB	-7994 / 0	-91.8	-91.8 0.27 (1)	4.10	
AB-G	-7994 / 0	-91.8	-91.8 0.27 (1)	4.10	
G-AC	-7108 / 0	-91.8	-91.8 0.23 (1)	4.33	
AC-AD	-7108 / 0	-91.8	-91.8 0.23 (1)	4.33	
AD-H	-7108 / 0	-91.8	-91.8 0.23 (1)	4.33	
H-I	-5077 / 0	-91.8	-91.8 0.52 (1)	3.87	
I-J	0 / 28	-91.8	-91.8 0.07 (1)	10.00	
T-B	-3255 / 0	0.0	0.0 0.11 (1)	7.69	
K-I	-3255 / 0	0.0	0.0 0.11 (1)	7.69	

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL = 25.8 PSF  
DL = 8.0 PSF

BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CBA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(65% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17')

CALCULATED VERT. DEFL.(LL) = L/999 (0.21')

ALLOWABLE DEFL.(TL) = L/360 (1.17')

CALCULATED VERT. DEFL.(TL) = L/999 (0.39')

CSI: TC=0.52/1.00 (H-I:1), BC=0.58/1.00 (O-P:1), WB=0.57/1.00 (B-S:1), SS=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP(DRY) SHEAR (PSI)	SECTION (PLI)	MAX MIN MAX MIN MAX MIN
MT20	618 354 1657 788 1987 1658	

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.84 (S) (INPUT = 0.90)

JSI METAL= 0.84 (N) (INPUT = 1.00)



Structural component only  
DWG# T-2007107 1/2

JOB NAME 408152	TRUSS NAME T40	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 8 Oct 29 2019 MITak Industries, Inc. Sat Apr 25 11:29:32 2020 Page 2  
 ID:j7vF?aG0E03cRUj6X1iSkzWYK-0EAix1sxZWS34IYeIz2E6MGCTQSHDeTqR0nCOzNCOX

**PLATES (tablets in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW-t	MT20	5.0	8.0		
C	TTW+m	MT20	5.0	8.0	Edge	
<b>D, E, G</b>						
D	TMW-t	MT20	5.0	8.0		
F	TS-t	MT20	5.0	6.0		
H	TTW+m	MT20	5.0	8.0	Edge	
I	TMW-t	MT20	5.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMW-t	MT20	5.0	6.0	2.50	2.50
<b>M, O, P, R</b>						
M	BMW-t	MT20	5.0	8.0		
N	BS-t	MT20	5.0	6.0		
O	BS-t	MT20	5.0	8.0		
S	BMW-t	MT20	5.0	6.0	2.50	2.50
T	BMV1+p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**LOADING**

TOTAL LOAD CASES: (4)

**CHORDS**


MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	LC1	MAX	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	LC1	MAX
FR-TO					WEBS				
AQ-K	0.0	-18.5	-18.5	0.08 (4)					10.00

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-438	-438		FRONT	VERT	TOTAL		C1
E	17-7-0	-110	-110		FRONT	VERT	TOTAL		C1
H	29-3-8	-438	-438		FRONT	VERT	TOTAL		C1
L	29-2-12	-28	-28		FRONT	VERT	TOTAL		C1
N	23-2-12	-28	-28		FRONT	VERT	TOTAL		C1
O	11-11-4	-28	-28		FRONT	VERT	TOTAL		C1
S	5-11-4	-28	-28		FRONT	VERT	TOTAL		C1
U	7-11-4	-110	-110		FRONT	VERT	TOTAL		C1
V	9-11-4	-110	-110		FRONT	VERT	TOTAL		C1
W	11-11-4	-110	-110		FRONT	VERT	TOTAL		C1
X	13-11-4	-110	-110		FRONT	VERT	TOTAL		C1
Y	15-11-4	-110	-110		FRONT	VERT	TOTAL		C1
Z	19-2-12	-110	-110		FRONT	VERT	TOTAL		C1
AA	21-2-12	-110	-110		FRONT	VERT	TOTAL		C1
AB	23-2-12	-110	-110		FRONT	VERT	TOTAL		C1
AC	25-2-12	-110	-110		FRONT	VERT	TOTAL		C1
AD	27-2-12	-110	-110		FRONT	VERT	TOTAL		C1
AE	1-11-4	-28	-28		FRONT	VERT	TOTAL		C1
AF	3-11-4	-28	-28		FRONT	VERT	TOTAL		C1
AG	7-11-4	-28	-28		FRONT	VERT	TOTAL		C1
AH	9-11-4	-28	-28		FRONT	VERT	TOTAL		C1
AI	13-11-4	-28	-28		FRONT	VERT	TOTAL		C1
AJ	15-11-4	-28	-28		FRONT	VERT	TOTAL		C1
AK	17-7-0	-28	-28		FRONT	VERT	TOTAL		C1
AL	19-2-12	-28	-28		FRONT	VERT	TOTAL		C1
AM	21-2-12	-28	-28		FRONT	VERT	TOTAL		C1
AN	25-2-12	-28	-28		FRONT	VERT	TOTAL		C1
AO	27-2-12	-28	-28		FRONT	VERT	TOTAL		C1
AP	31-2-12	-28	-28		FRONT	VERT	TOTAL		C1
AQ	33-2-12	-28	-28		FRONT	VERT	TOTAL		C1

**CONNECTION REQUIREMENTS**


1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only  
 DWG# T-2007107 2/2

JOB NAME 408152	TRUSS NAME T40Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:29:34 2020 Page 1  
 ID:7vF?ag0E03cRUj6X1jSrKziWYK-ydH2MiuB57mK31?\_4iCnCV?E2GhUjzKgpGJzNCOV



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - F	2x6	DRY No.2	SPF
F - H	2x6	DRY No.2	SPF
H - J	2x4	DRY No.2	SPF
T - B	2x6	DRY No.2	SPF
K - I	2x6	DRY No.2	SPF
T - Q	2x6	DRY No.2	SPF
Q - N	2x6	DRY No.2	SPF
N - K	2x6	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 EXCEPT SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS SURFACE SPACING (IN) LOAD(PLF)

TOP CHORDS : (0.122"x3") SPIRAL NAILS

A-C	1	12	SIDE(61.0)
H-J	1	12	TOP
C-F	2	12	SIDE(61.0)
F-H	2	12	TOP
T-B	2	12	TOP
K-I	2	12	TOP

BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS

T-Q	2	12	SIDE(183.1)
Q-N	2	12	SIDE(0.0)
N-K	2	12	TOP

WEBS : (0.122"x3") SPIRAL NAILS

2x3	1	6	TOP
-----	---	---	-----

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-D INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLYS FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	4474	0	5-8
T HORZ	0	4474	0
K	3775	0	5-8

**UNFACTORED REACTIONS**

1ST LCASE	MAX/MIN COMPONENT REACTIONS	PERALIVE	WIND	SOIL
JT COMBINED	SNOW	LIVE		
T	3162	2088 / 0	0 / 0	1073 / 0
K	2665	1772 / 0	0 / 0	893 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, K

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.19 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
A-B	0 / 28	-91.8	-91.8	0.07 (1)	10.00	S-C	-384 / 25	0.05 (1)
B-C	-7183 / 0	-91.8	-91.8	0.71 (1)	3.19	C-R	0 / 4687	0.58 (1)
C-U	-10289 / 0	-91.8	-91.8	0.32 (1)	3.62	R-D	-2057 / 0	0.25 (1)
U-V	-10289 / 0	-91.8	-91.8	0.32 (1)	3.62	O-G	0 / 3611	0.45 (1)
V-D	-10289 / 0	-91.8	-91.8	0.32 (1)	3.62	M-G	-2637 / 0	0.32 (1)
D-W	-12012 / 0	-91.8	-91.8	0.45 (1)	3.27	L-H	-816 / 0	0.08 (1)
W-X	-12012 / 0	-91.8	-91.8	0.45 (1)	3.27	B-S	0 / 6479	0.80 (1)
X-Y	-12012 / 0	-91.8	-91.8	0.45 (1)	3.27	L-I	0 / 5333	0.66 (1)
Y-E	-12012 / 0	-91.8	-91.8	0.45 (1)	3.27	D-P	0 / 2068	0.28 (1)
E-F	-12381 / 0	-91.8	-91.8	0.40 (1)	3.28	M-H	0 / 4950	0.61 (1)
F-G	-12381 / 0	-91.8	-91.8	0.40 (1)	3.28	P-E	-1110 / 0	0.14 (1)
G-H	-9388 / 0	-91.8	-91.8	0.25 (1)	3.84	E-O	0 / 383	0.05 (1)
H-I	-5898 / 0	-91.8	-91.8	0.59 (1)	3.58			
I-J	0 / 28	-91.8	-91.8	0.07 (1)	10.00			
T-B	-4430 / 0	0.0	0.0	0.16 (1)	6.82			
K-I	-3718 / 0	0.0	0.0	0.13 (1)	7.31			

TOTAL WEIGHT = 2 X 170 = 341 LB

**DESIGN CRITERIA**

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF

BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17)  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.31)  
 ALLOWABLE DEFL.(TL) = L/360 (1.17)  
 CALCULATED VERT. DEFL.(TL) = L/740 (0.57)

CSI: TC=0.71/1.00 (B-C:1), BC=0.91/1.00 (O-P:1),  
 WB=0.80/1.00 (B-S:1), SS=0.15/1.00 (R-S:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00  
 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE GRIP(DRY) SHEAR SECTION

(PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	818	354
	1567	788
	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (S) (INPUT = 0.80)  
 JSI METAL = 0.93 (N) (INPUT = 1.00)



Structural component only  
 DWG# T-2007108

JOB NAME 408152	TRUSS NAME T40Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	2.00	3.50
C	TTWW-m	MT20	8.0	9.0	Edge	
D, E, G						
D	TMWW-l	MT20	5.0	6.0		
F	TS-l	MT20	5.0	6.0		
H	TTWW-m	MT20	8.0	9.0	Edge	
I	TMVW-p	MT20	5.0	8.0	2.00	3.50
K	BMV1-p	MT20	3.0	6.0		
L	BMWW-t	MT20	5.0	8.0	2.50	3.50
M	BMWW-t	MT20	5.0	8.0	2.50	2.00
N	BS-l	MT20	5.0	8.0		
O	BMWW-t	MT20	5.0	8.0	2.75	2.75
P	BMWW-t	MT20	5.0	8.0	2.75	2.75
Q	BS-l	MT20	5.0	8.0		
R	BMWW-t	MT20	5.0	8.0	2.90	2.00
S	BMWW-l	MT20	5.0	8.0	2.50	3.50
T	BMV1-p	MT20	3.0	8.0		


Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**FACTORED CONCENTRATED LOADS (LBS)**


JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
X	14-9-12	-82	-82	---	BACK	VERT	TOTAL	---	C1
Y	16-9-12	-82	-82	---	BACK	VERT	TOTAL	---	C1
Z	1-11-4	-25	-26	---	BACK	VERT	TOTAL	---	C1
AA	3-11-4	-26	-26	---	BACK	VERT	TOTAL	---	C1
AB	7-11-4	-26	-26	---	BACK	VERT	TOTAL	---	C1
AC	8-10-8	-639	-639	---	BACK	VERT	TOTAL	---	C1
AD	10-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1
AE	12-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1
AF	14-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1

**CONNECTION REQUIREMENTS**

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only  
 DWG# T-2007108



**LUMBER**

N. L. C. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - H	2x4	DRY No.2	SPF
H - K	2x4	DRY No.2	SPF
S - B	2x4	DRY No.2	SPF
L - J	2x4	DRY No.2	SPF
S - Q	2x4	DRY No.2	SPF
Q - N	2x4	DRY No.2	SPF
N - L	2x4	DRY No.2	SPF
ALL WEBS EXCEPT S - C I - L	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV-p	MT20	3.0	4.0		
C	TMW-w	MT20	5.0	6.0	2.50	2.75
D	TTW-w	MT20	5.0	6.0	2.25	2.75
E	TMW-t	MT20	4.0	4.0		
F	TS-t	MT20	3.0	8.0		
G	TMW-w	MT20	3.0	4.0		
H	TTW-w	MT20	5.0	6.0	2.25	2.75
I	TMW-t	MT20	5.0	6.0	2.50	2.75
J	TMV-p	MT20	3.0	4.0		
L	BMW-t	MT20	4.0	9.0		Edge
M	BMW-w	MT20	4.0	4.0		
N	BS-t	MT20	3.0	8.0		
O	BMW-w	MT20	4.0	9.0		
P	BMW-t	MT20	4.0	6.0		
Q	BS-t	MT20	3.0	6.0		
R	BMW-t	MT20	4.0	4.0		
S	BMW-t	MT20	4.0	9.0		Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	RECORD BRG IN-SX
JT	VERT	DOWN		
S	2063	0	5-8	5-8
L	2063	0	5-8	5-8

**UNFACTORED REACTIONS**

1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT						
S	1457	989 / 0	0 / 0	0 / 0	488 / 0	0 / 0
L	1457	989 / 0	0 / 0	0 / 0	488 / 0	0 / 0

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.94 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO				
A-B	0 / 28	-91.8 -91.8 0.12 (1)	10.00	C-R 0 / 93
B-C	0 / 16	-91.8 -91.8 0.20 (1)	10.00	R-D 0 / 121
C-D	-2799 / 0	-91.8 -91.8 0.32 (1)	3.88	D-P 0 / 1267
D-E	-3503 / 0	-91.8 -91.8 0.95 (1)	2.94	P-E -643 / 0
E-F	-3507 / 0	-91.8 -91.8 0.93 (1)	2.94	E-D -2 / 0
F-G	-3507 / 0	-91.8 -91.8 0.93 (1)	2.94	O-G -643 / 0
G-H	-3507 / 0	-91.8 -91.8 0.94 (1)	2.95	C-H 0 / 1265
H-I	-2799 / 0	-91.8 -91.8 0.32 (1)	3.88	M-H 0 / 121
I-J	0 / 16	-91.8 -91.8 0.20 (1)	10.00	M-I 0 / 93
J-K	0 / 28	-91.8 -91.8 0.12 (1)	10.00	S-C -2974 / 0
S-B	-270 / 0	0.0 0.0 0.03 (1)	7.81	I-L -2974 / 0
L-J	-270 / 0	0.0 0.0 0.03 (1)	7.81	
S-R	0 / 2417	-18.5 -18.5 0.53 (1)	10.00	
R-O	0 / 2489	-18.5 -18.5 0.54 (1)	10.00	
Q-P	0 / 2489	-18.5 -18.5 0.54 (1)	10.00	
P-O	0 / 3509	-18.5 -18.5 0.54 (1)	10.00	
O-N	0 / 2489	-18.5 -18.5 0.54 (1)	10.00	
N-M	0 / 2489	-18.5 -18.5 0.54 (1)	10.00	
M-L	0 / 2417	-18.5 -18.5 0.53 (1)	10.00	

TOTAL WEIGHT = 2 X 139 = 278 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BDT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, OBC 2012, ABC 2018  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 088-09, CSA 088-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17)  
CALCULATED VERT. DEFL.(LL) = L/999 (0.21)  
ALLOWABLE DEFL.(TL) = L/360 (1.17)  
CALCULATED VERT. DEFL.(TL) = L/999 (0.41)

CSI: TC=0.95/1.00 (D-E-1), BC=0.64/1.00 (O-P-1),  
WB=0.83/1.00 (I-L-1), SS=0.28/1.00 (D-E-1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP (DRY) SHEAR (PSI)	SECTION (PL)	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667	788
		1987	1658	

PLATE PLACEMENT TOL = 0.250 inches  
PLATE ROTATION TOL = 5.0 Deg.  
JSI GRIP = 0.89 (L) (INPUT = 0.90)  
JSI METAL = 0.77 (N) (INPUT = 1.00)




Structural component only  
DWG# T-2007109



JOB NAME 408152	TRUSS NAME T42	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:29:38 2020 Page 1  
 ID:7vF?agOE03cRUj6X1SktzWYK-u?PpnOvRckyJZNSP6G6AHChtN1r19RDGMajwLcZnCOT  
 1.38 0.0 5.0 5.0 10.0 10.0 7.8 17.7 7.8 25.3 4.10 30.1 35.2 39.8  
 Scale = 1:57.0



**LUMBER**  
 N. L. G. A. RULES  
 CHORDS SIZE LUMBER

A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - I	2x4	DRY	No.2
R - B	2x4	DRY	No.2
J - H	2x4	DRY	No.2
R - O	2x4	DRY	No.2
O - M	2x4	DRY	No.2
M - J	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2  
 EXCEPT  
 DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	Edge 3.50
C	TMVW-t	MT20	4.0	4.0	2.00 1.75
D	TTWW-m	MT20	5.0	8.0	2.25 3.75
E	TMVW-w	MT20	2.0	4.0	
F	TTWW-m	MT20	5.0	8.0	2.25 3.75
G	TMVW-t	MT20	4.0	4.0	2.00 1.75
H	TMVW-p	MT20	5.0	8.0	Edge 3.50
J	BMV1-p	MT20	3.0	4.0	
K	BMVW-t	MT20	5.0	8.0	2.50 2.00
L	BMVW-t	MT20	4.0	4.0	
M	BS-t	MT20	3.0	6.0	
N	BMVW-t	MT20	4.0	9.0	
O	BS-t	MT20	3.0	6.0	
P	BMVW-t	MT20	4.0	4.0	
Q	BMVW-t	MT20	5.0	8.0	2.50 2.00
R	BMV1-p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECRD BRG
JT	VERT HORZ	DOWN HORZ	UPLIFT IN-SX IN-SX
R	2063 0	2063 0	0 0
J	2063 0	2063 0	0 0

**UNFACTORED REACTIONS**

1ST CASE	MAX. MIN. COMPONENT REACTIONS	DEAD	SOIL
JT	COMBINED SNOW LIVE	PERM. LIVE	WIND
R	1457 969 / 0	0 / 0	0 / 0
J	1457 969 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J  
**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.78 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)
FR-TO				
A-B	0 / 28	-91.8 -91.8 0.12 (1)	10.00	Q-C -353 / 0
B-C	-2834 / 0	-91.8 -91.8 0.39 (1)	3.81	C-P -210 / 0
C-D	-2687 / 0	-91.8 -91.8 0.37 (1)	3.91	P-D 0 / 246
D-E	-3060 / 0	-91.8 -91.8 0.97 (1)	2.78	D-N 0 / 844
E-F	-3060 / 0	-91.8 -91.8 0.97 (1)	2.78	N-E -872 / 0
F-G	-2687 / 0	-91.8 -91.8 0.37 (1)	3.91	N-F 0 / 844
G-H	-2834 / 0	-91.8 -91.8 0.39 (1)	3.81	L-F 0 / 246
H-I	0 / 28	-91.8 -91.8 0.12 (1)	10.00	L-G -210 / 0
R-B	-2018 / 0	0.0 0.0 0.20 (1)	5.94	K-G -353 / 0
J-H	-2018 / 0	0.0 0.0 0.20 (1)	5.94	B-Q 0 / 2591
R-Q	0 / 0	-18.5 -18.5 0.10 (4)	10.00	K-H 0 / 2591
Q-P	0 / 2555	-18.5 -18.5 0.51 (1)	10.00	
P-O	0 / 2386	-18.5 -18.5 0.49 (1)	10.00	
O-N	0 / 2386	-18.5 -18.5 0.49 (1)	10.00	
N-M	0 / 2386	-18.5 -18.5 0.49 (1)	10.00	
M-L	0 / 2386	-18.5 -18.5 0.49 (1)	10.00	
L-K	0 / 2555	-18.5 -18.5 0.51 (1)	10.00	
K-J	0 / 0	-18.5 -18.5 0.10 (4)	10.00	

TOTAL WEIGHT = 2 X 139 = 277 lb  
 [M/F]

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12  
 THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.17")  
 ALLOWABLE DEFL.(TL) = L/360 (1.17")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.34")

CSI: TC=0.97/1.00 (D-E:1), BC=0.51/1.00 (K-L:1),  
 WB=0.59/1.00 (H-K:1), SS=0.34/1.00 (D-E:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10


COMPANION LIVE LOAD FACTOR = 1.00  
 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354
	1687	789
	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches  
 PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (D) (INPUT = 0.90)  
 JSI METAL= 0.75 (O) (INPUT = 1.00)



Structural component only  
 DWG# T-2007110



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - I	2x4	DRY No.2	SPF
R - B	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
R - O	2x4	DRY No.2	SPF
O - M	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	Edge	3.50
C	TMVW-l	MT20	4.0	4.0	2.00	1.75
D	TTVW-m	MT20	5.0	8.0	2.25	2.00
E	TMVW-w	MT20	2.0	4.0		
F	TTVW-m	MT20	5.0	6.0	2.25	2.00
G	TMVW-l	MT20	4.0	4.0	2.00	1.75
H	TMVW-p	MT20	5.0	8.0	Edge	3.50
J	BMV1-p	MT20	3.0	4.0		
K	BMVW-l	MT20	5.0	8.0	2.50	2.25
L	BMVW-l	MT20	4.0	4.0		
M	BS-l	MT20	3.0	8.0		
N	BMVW-w	MT20	4.0	9.0		
O	BS-l	MT20	3.0	8.0		
P	BMVW-l	MT20	4.0	4.0		
Q	BMVW-l	MT20	5.0	6.0	2.50	2.25
R	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	REQRD BRG IN-SX
R	2063	0	2063	0	0	5-8	5-8
J	2063	0	2063	0	0	5-8	5-8

**UNFACTORED REACTIONS**

JT	1ST CASE	MAX	MIN	COMPONENT REACTIONS
R	1457	969 / 0	0 / 0	PERM LIVE WIND DEAD SOIL
J	1457	969 / 0	0 / 0	488 / 0 0 / 0 488 / 0 0 / 0

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.58 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB. FORCE (LBS)	MAX. FACTORED CSI (LC)
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00	Q-C -255 / 12	0.07 (1)
B-C	-2889 / 0	-91.8	-91.8 0.58 (1)	3.58	C-P -435 / 0	0.42 (1)
C-D	-2539 / 0	-91.8	-91.8 0.52 (1)	3.83	P-D 0 / 350	0.08 (1)
D-E	-2539 / 0	-91.8	-91.8 0.48 (1)	3.85	D-N 0 / 482	0.11 (1)
E-F	-2539 / 0	-91.8	-91.8 0.48 (1)	3.85	N-E -641 / 0	0.56 (1)
F-G	-2539 / 0	-91.8	-91.8 0.52 (1)	3.83	N-F 0 / 482	0.11 (1)
G-H	-2889 / 0	-91.8	-91.8 0.58 (1)	3.58	L-F 0 / 350	0.08 (1)
H-I	0 / 28	-91.8	-91.8 0.12 (1)	10.00	L-G -435 / 0	0.42 (1)
R-B	-2014 / 0	0.0	0.0 0.20 (1)	5.95	K-G -255 / 12	0.07 (1)
J-H	-2014 / 0	0.0	0.0 0.20 (1)	5.95	B-Q 0 / 2635	0.59 (1)
R-Q	0 / 0	-18.5	-18.5 0.15 (4)	10.00	B-Q 0 / 2635	0.59 (1)
C-P	0 / 2809	-18.5	-18.5 0.49 (1)	10.00		
P-O	0 / 2249	-18.5	-18.5 0.43 (1)	10.00		
O-N	0 / 2249	-18.5	-18.5 0.43 (1)	10.00		
N-M	0 / 2249	-18.5	-18.5 0.43 (1)	10.00		
M-L	0 / 2249	-18.5	-18.5 0.43 (1)	10.00		
L-K	0 / 2609	-18.5	-18.5 0.49 (1)	10.00		
K-J	0 / 0	-18.5	-18.5 0.15 (4)	10.00		

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF

BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

TOTAL WEIGHT = 2 X 145 = 289 lb

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.17)  
 CALCULATED VERT. DEFL. (LL) = L/999 (0.15)  
 ALLOWABLE DEFL. (TL) = L/360 (1.17)  
 CALCULATED VERT. DEFL. (TL) = L/999 (0.28)

CSI: TC=0.58/1.00 (G-H:1), BC=0.49/1.00 (K-L:1), WB=0.58/1.00 (B-Q:1), SS=0.25/1.00 (D-E:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)


MAX MIN MAX MIN MAX MIN

MT20 618 354 1667 768 1987 1655

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (Q) (INPUT = 0.90)  
 JSI METAL = 0.69 (M) (INPUT = 1.00)



Structural component only  
 DWG# T-2007111





**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - G	2x4	DRY	No.2	SPF
G - I	2x4	DRY	No.2	SPF
I - L	2x4	DRY	No.2	SPF
T - B	2x4	DRY	No.2	SPF
M - K	2x4	DRY	No.2	SPF
T - R	2x4	DRY	No.2	SPF
R - O	2x4	DRY	No.2	SPF
O - M	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+P	MT20	3.0	4.0		
C	TMWW-1	MT20	5.0	6.0	2.50	2.25
D	TS-1	MT20	3.0	6.0		
E	TMWW-1	MT20	4.0	4.0	2.00	1.50
F	TTW-n	MT20	4.0	4.0	2.00	1.75
G	TTWW-m	MT20	5.0	6.0	2.00	2.00
H	TMWW-1	MT20	4.0	4.0	2.00	1.50
I	TS-1	MT20	3.0	6.0		
J	TMWW-1	MT20	5.0	6.0	2.50	2.25
K	TMV+P	MT20	3.0	4.0		
M	BMWW-1	MT20	5.0	6.0	2.25	2.00
N, P, S						
N	BMWW-1	MT20	4.0	4.0		
O	BS-1	MT20	3.0	6.0		
Q	BMWW-1	MT20	4.0	6.0		
R	BS-1	MT20	3.0	6.0		
T	BMWW-1	MT20	5.0	6.0	2.25	2.00

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT 2063	DOWN 2063	5-8	5-8
T	HORZ 0	HORZ 0	5-8	5-8
M	UPLIFT 0	UPLIFT 0	5-8	5-8

**UNFACTORED REACTIONS**

JT	1ST CASE COMBINED	MAX. SNOW	MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
T	1457	969 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
M	1457	969 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, M

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.86 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, H-P, C-T, J-M

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)
FR-TO						
A-B	0 / 28	-91.8	0.12 (1)	10.00	C-S	-110 / 37
B-C	0 / 19	-91.8	0.32 (1)	10.00	S-E	0 / 276
C-D	-2759 / 0	-91.8	0.40 (1)	3.86	E-Q	-651 / 0
D-E	-2759 / 0	-91.8	0.40 (1)	3.86	Q-F	0 / 613
E-F	-2167 / 0	-91.8	0.36 (1)	4.30	Q-G	0 / 4
F-G	-1925 / 0	-91.8	0.18 (1)	4.71	P-G	0 / 609
G-H	-2166 / 0	-91.8	0.36 (1)	4.30	P-H	-682 / 0
H-I	-2759 / 0	-91.8	0.40 (1)	3.86	H-N	0 / 278
I-J	-2759 / 0	-91.8	0.40 (1)	3.86	N-J	-110 / 37
J-K	0 / 19	-91.8	0.32 (1)	10.00	T-C	-3040 / 0
K-L	0 / 28	-91.8	0.12 (1)	10.00	J-M	-3041 / 0
T-B	-326 / 0	0.0	0.03 (1)	7.81		
M-K	-326 / 0	0.0	0.03 (1)	7.81		
T-S	0 / 2536	-18.5	-18.5	0.55 (1)	10.00	
S-R	0 / 2362	-18.5	-18.5	0.53 (1)	10.00	
R-Q	0 / 2362	-18.5	-18.5	0.53 (1)	10.00	
Q-P	0 / 1924	-18.5	-18.5	0.40 (1)	10.00	
P-O	0 / 2362	-18.5	-18.5	0.53 (1)	10.00	
O-N	0 / 2362	-18.5	-18.5	0.53 (1)	10.00	
N-M	0 / 2537	-18.5	-18.5	0.55 (1)	10.00	

TOTAL WEIGHT = 2 X 151 = 302 lb

**DESIGN CRITERIA**  
SPECIFIED LOADS:  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")  
ALLOWABLE DEFL.(TL) = L/360 (1.17")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.32")  
CSI: TC=0.40/1.00 (H-J), BC=0.58/1.00 (M-N:1), WS=0.85/1.00 (J-M:1), SS=0.20/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)  
MAX MIN MAX MIN MAX MIN  
MT20 618 354 1657 788 1987 1656  
PLATE PLACEMENT TOL = 0.250 inches  
PLATE ROTATION TOL = 5.0 Deg.  
JSI GRIP = 0.89 (M) (INPUT = 0.90)  
JSI METAL = 0.83 (O) (INPUT = 1.00)



Structural component only  
DWG# T-2007113



**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - H	2x4	DRY	No.2	SPF	
H - K	2x4	DRY	No.2	SPF	
S - B	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
S - Q	2x4	DRY	No.2	SPF	
Q - N	2x4	DRY	No.2	SPF	
N - L	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT S - C I - L	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0	
C	TMWW-l	MT20	5.0	6.0	2.25 2.00
D	TS-l	MT20	3.0	6.0	
E	TMWW+l	MT20	5.0	6.0	
F	TTWW+p	MT20	4.0	6.0	Edge
G	TMWW+l	MT20	5.0	6.0	
H	TS-l	MT20	3.0	6.0	
I	TMWW-l	MT20	5.0	6.0	2.25 2.00
J	TMV+p	MT20	3.0	4.0	
L	BMVV-l	MT20	4.0	9.0	Edge
M, O, P, R					
M	BMWW+l	MT20	4.0	6.0	
N	BS-l	MT20	3.0	6.0	
Q	BS-l	MT20	3.0	6.0	
S	BMVV+l	MT20	4.0	9.0	Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
S	2063	0	2063	0	5-8	5-8
L	2063	0	2063	0	5-8	5-8

**UNFACTORED REACTIONS**

JT	1ST CASE		MAX. MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERMLIVE			
S	1457	969/0	0/0	0/0	0/0	488/0	0/0
L	1457	969/0	0/0	0/0	0/0	488/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.75 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.  
 1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-S, I-L.  
 END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO				
A-B	0/28	-91.8	-91.8	0.12 (1)
B-C	0/22	-91.8	-91.8	0.40 (1)
C-D	-2808/0	-91.8	-91.8	0.49 (1)
D-E	-2808/0	-91.8	-91.8	0.49 (1)
E-F	-2322/0	-91.8	-91.8	0.46 (1)
F-G	-2322/0	-91.8	-91.8	0.46 (1)
G-H	-2808/0	-91.8	-91.8	0.49 (1)
H-I	-2808/0	-91.8	-91.8	0.49 (1)
I-J	0/22	-91.8	-91.8	0.40 (1)
J-K	0/28	-91.8	-91.8	0.12 (1)
S-B	-344/0	0.0	0.0	0.03 (1)
L-J	-344/0	0.0	0.0	0.03 (1)
S-R	0/2574	-18.5	-18.5	0.53 (1)
R-O	0/2291	-18.5	-18.5	0.47 (1)
Q-P	0/2291	-18.5	-18.5	0.47 (1)
P-O	0/1762	-18.5	-18.5	0.39 (1)
O-N	0/2291	-18.5	-18.5	0.47 (1)
N-M	0/2291	-18.5	-18.5	0.47 (1)
M-L	0/2574	-18.5	-18.5	0.53 (1)

TOTAL WEIGHT = 8 X 152 = 910 LB

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 8.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17)  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.14)  
 ALLOWABLE DEFL.(TL) = L/360 (1.17)  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.28)

CSI: TC=0.48/1.00 (C-E:1), BC=0.53/1.00 (L-M:1), WB=0.72/1.00 (E-P:1), SS=0.22/1.00 (I-J:1)  
 DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10


COMPANION LIVE LOAD FACTOR = 1.00  
 AUTOSOLVE HEELS OFF  
 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)  
 MAX MIN MAX MIN MAX MIN  
 MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches  
 PLATE ROTATION TOL = 5.0 Deg.  
 JSI GRIP = 0.87 (C) (INPUT = 0.90)  
 JSI METAL = 0.77 (I) (INPUT = 1.00)



JOB NAME 408152	TRUSS NAME T47	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	



**LUMBER**  
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4 DRY	No.2	SPF
C - E	2x4 DRY	No.2	SPF
E - F	2x4 DRY	No.2	SPF
L - B	2x4 DRY	No.2	SPF
G - F	2x4 DRY	No.2	SPF
L - I	2x4 DRY	No.2	SPF
I - G	2x4 DRY	No.2	SPF
ALL WEBS EXCEPT	2x3 DRY	No.2	SPF

DRY: SEASONED LUMBER.  
DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C	12	SIDE(61.0)
C-E	12	SIDE(61.0)
E-F	12	TOP
G-F	12	TOP
L-B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
L-I	12	SIDE(0.0)
I-G	12	TOP
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.  
GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.  
TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLYS FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.  
SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

MEMBER	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
JT	2005	0	2005	0	5-8	5-8
L	2005	0	2005	0	5-8	5-8
G	1397	0	1397	0	MECHANICAL	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 2-0.

**UNFACTORED REACTIONS**

MEMBER	1ST LCASE		MAX/MIN COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
JT	1412	958 / 0	0 / 0	0 / 0	0 / 0	457 / 0	0 / 0
L	2005	0	0 / 0	0 / 0	0 / 0	457 / 0	0 / 0
G	885	662 / 0	0 / 0	0 / 0	0 / 0	323 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L  
**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.18 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)		MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	
		FROM	TO			FR-TO	CS1 (LC)
A-B	0 / 28	-91.8	-91.8	10.00	K-C	0 / 943	0.12 (1)
B-C	-2643 / 0	-91.8	-91.8	5.18	C-J	-848 / 0	0.13 (1)
C-D	-1951 / 0	-91.8	-91.8	6.17	J-D	-371 / 0	0.05 (1)
D-E	-1951 / 0	-91.8	-91.8	6.17	E-E	0 / 1047	0.13 (1)
E-F	-1405 / 0	-91.8	-91.8	6.25	H-E	-446 / 0	0.08 (1)
L-B	-1885 / 0	0.0	0.0	7.81	B-K	0 / 2382	0.29 (1)
G-F	-1369 / 0	0.0	0.0	7.81	H-F	0 / 1375	0.17 (1)
L-M	0 / 0	-18.5	-18.5	10.00			
M-N	0 / 0	-18.5	-18.5	10.00			
N-O	0 / 0	-18.5	-18.5	10.00			
O-K	0 / 0	-18.5	-18.5	10.00			
K-J	0 / 2389	-18.5	-18.5	10.00			
J-I	0 / 1243	-18.5	-18.5	10.00			
I-H	0 / 1243	-18.5	-18.5	10.00			
H-G	0 / 0	-18.5	-18.5	10.00			

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-320	-320		FRONT	VERT	TOTAL		C1
M	1-11-4	-25	-25		FRONT	VERT	TOTAL		C1
N	3-11-4	-25	-25		FRONT	VERT	TOTAL		C1
O	5-8-8	-1076	-1076		FRONT	VERT	TOTAL		C1

**CONNECTION REQUIREMENTS**  
1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 78 = 156 lb (M)

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.8 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN./C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12  
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(85% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")  
ALLOWABLE DEFL.(TL) = L/360 (0.55")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.06")

CSI: TC=0.37/1.00 (B-C:1), BC=0.24/1.00 (J-K:1), WB=0.29/1.00 (B-K:1), SS=0.37/1.00 (K-L:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00  
COMP=1.00 SHEAR=1.00 TENS=1.00


COMPANION LIVE LOAD FACTOR = 1.00  
AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**MAIL VALUES**  
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)  
MAX MIN MAX MIN MAX MIN  
MT20 618 354 1567 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches  
PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.80 (B) (INPUT = 0.90)  
JSI METAL= 0.32 (B) (INPUT = 1.00)




Structural component only  
DWG# T-2007115

JOB NAME 408152	TRUSS NAME T47	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	


Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:28:42 2020 Page 2  
 ID:37vF?aG0E03cRLi6X1jSrkzIWK-i8m42R\_CCaieHlJZTfDaWTXzGSyYZDD6kZDEYrzNCON

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	6.0	1.00 3.00
C	TTWW-m	MT20	5.0	6.0	2.25 2.00
D	TMW+w	MT20	2.0	4.0	
E	TTWW-m	MT20	5.0	6.0	2.25 2.00
F	TMVW+p	MT20	4.0	4.0	1.50 2.00
G	BMV1+p	MT20	3.0	6.0	
H	BMWW-t	MT20	5.0	6.0	
I	BS-t	MT20	5.0	6.0	
J	BMWWW-t	MT20	5.0	6.0	
K	BMWW-t	MT20	5.0	6.0	
L	BMV1+p	MT20	3.0	6.0	



Structural component only  
 DWG# T-2007115 *2/2*



**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
E - F	2x4	DRY	No.2	SPF	
K - B	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
K - I	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWV-t	MT20	4.0	4.0	2.00	1.75
D	TTW-m	MT20	4.0	4.0		
E	TTWV-m	MT20	5.0	6.0	2.25	2.00
F	TMWV+p	MT20	4.0	4.0	1.50	2.00
G	BMV1+p	MT20	3.0	4.0		
H	BMWV-t	MT20	4.0	6.0		
I	BS-t	MT20	3.0	6.0		
J	BMWVW-t	MT20	4.0	9.0		
K	BMWV1-t	MT20	4.0	6.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	MAXIMUM FACTORED GROSS REACTION	MAXIMUM FACTORED DOWN	MAXIMUM FACTORED HORZ	INPUT BRG	REQRD BRG
K	1039	0	1039	0	0	5-8	5-8
G	914	0	914	0	0	MECHANICAL	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

**UNFACTORED REACTIONS**

JT	1ST LC CASE	COMBINED	SNOW	LIVE	PERM/LIVE	WIND	DEAD	SOIL
K	732	494 / 0	0 / 0	0 / 0	0 / 0	0 / 0	238 / 0	0 / 0
G	646	424 / 0	0 / 0	0 / 0	0 / 0	0 / 0	222 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. FURLIN SPACING = 8.12 FT.  
MAX. UNSRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO					FR-TO		
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00	C-J	-232 / 0	0.10 (1)
B-C	0 / 18	-91.8	-91.8 0.22 (1)	10.00	J-D	0 / 134	0.03 (4)
C-D	-916 / 0	-91.8	-91.8 0.18 (1)	6.24	J-E	0 / 152	0.03 (1)
D-E	-806 / 0	-91.8	-91.8 0.10 (1)	6.25	H-E	-163 / 0	0.06 (1)
E-F	-821 / 0	-91.8	-91.8 0.42 (1)	6.12	K-C	-1221 / 0	0.47 (1)
K-B	-265 / 0	0.0	0.0 0.03 (1)	7.81	H-F	0 / 769	0.17 (1)
G-F	-866 / 0	0.0	0.0 0.10 (1)	7.81			
K-J	0 / 993	-18.5	-18.5 0.32 (4)	10.00			
J-I	0 / 731	-18.5	-18.5 0.31 (4)	10.00			
I-H	0 / 731	-18.5	-18.5 0.31 (4)	10.00			
H-G	0 / 0	-18.5	-18.5 0.15 (4)	10.00			

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.8 PSF  
DL = 8.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. CC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2018, CBC 2012, ABC 2019  
- PART 9 OF CBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")  
ALLOWABLE DEFL.(TL) = L/360 (0.55")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.13")

CSI: TC=0.42/1.00 (E-F); BC=0.32/1.00 (J-K:4);  
WB=0.47/1.00 (C-K:1); SSI=0.19/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALLES**  
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)  
MAX MIN MAX MIN MAX MIN  
MT20 618 354 1687 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.87 (C) (INPUT = 0.80)  
JSI METAL = 0.41 (C) (INPUT = 1.00)

TOTAL WEIGHT = 68 lb



Structural component only  
DWG# T-2007116





Scale: 3/8" = 1'

**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
A - D	2x4	DRY No.2
D - F	2x4	DRY No.2
K - B	2x4	DRY No.2
G - F	2x4	DRY No.2
K - I	2x4	DRY No.2
I - G	2x4	DRY No.2
ALL WEBS EXCEPT	2x3	DRY No.2

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMW+1	MT20	4.0	5.0	2.00 3.00
C	TMW+1	MT20	4.0	4.0	2.00 1.75
D	TTW+p	MT20	4.0	4.0	
E	TMW+1	MT20	4.0	6.0	
F	TMV+p	MT20	3.0	4.0	
G	BMVW1-t	MT20	4.0	4.0	
H	BMVW1-t	MT20	4.0	6.0	
I	BS-1	MT20	3.0	6.0	
J	BMVW+1	MT20	4.0	6.0	
K	BMV1+p	MT20	3.0	4.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT VERT	1039	0	0	5-8
K	1039	0	0	5-8
G	914	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX SNOW	MIN LIVE	PERM. LIVE	WIND	DEAD	SOIL
K	732	494 / 0	0 / 0	0 / 0	0 / 0	238 / 0	0 / 0
G	646	424 / 0	0 / 0	0 / 0	0 / 0	222 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.66 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)		MAX. UNBRACED LENGTH	WEBS		
		FROM	TO		MEMB. FORCE (LBS)	MAX. CSI (LC)	
A-B	0 / 28	-91.8	-91.8	10.00	J-C	-114 / 23	0.02 (1)
B-C	-1135 / 0	-91.8	-91.8	5.66	C-H	-418 / 0	0.22 (1)
C-D	-798 / 0	-91.8	-91.8	6.25	H-D	0 / 407	0.09 (1)
D-E	-793 / 0	-91.8	-91.8	6.25	H-E	-39 / 37	0.02 (1)
E-F	0 / 17	-91.8	-91.8	10.00	B-J	0 / 1051	0.24 (1)
K-B	-998 / 0	0.0	0.0	7.81	E-G	-1026 / 0	0.44 (1)
G-F	-129 / 0	0.0	0.0	10.00			
K-J	0 / 0	-18.5	-18.5	10.00			
J-I	0 / 1034	-18.5	-18.5	10.00			
I-H	0 / 1034	-18.5	-18.5	10.00			
H-G	0 / 722	-18.5	-18.5	10.00			

TOTAL WEIGHT = 67 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 085-09, CSA 085-14  
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.55")  
CALCULATED VERT. DEFL. (LL) = L/999 (0.03")  
ALLOWABLE DEFL. (TL) = L/360 (0.55")  
CALCULATED VERT. DEFL. (TL) = L/999 (0.10")

CSI: TC=0.26/1.00 (B-C-1), BC=0.29/1.00 (H-J-4), WB=0.44/1.00 (E-G-1), SSI=0.19/1.00 (B-C-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP (DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MAX	MIN	MAX
MT20	618	354
	1667	788
	1987	1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.84 (G) (INPUT = 0.90)  
JSI METAL = 0.36 (I) (INPUT = 1.00)



Structural component only  
DWG# T-2007117



**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
J - B	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	
J - G	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X	
B	TMVW-p	MT20	4.0	4.0	1.50	2.00
C	TTWW-m	MT20	5.0	6.0	2.00	2.00
D	TTW-m	MT20	4.0	4.0		
E	TMVW-p	MT20	4.0	4.0	1.50	2.00
G	BMV1+p	MT20	3.0	4.0		
H	BMVWW-t	MT20	4.0	9.0		
I	BMVW-t	MT20	4.0	6.0		
J	BMV1+p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ
JT	866	0	866	0
J	866	0	866	0
G	866	0	866	0

**UNFACTORED REACTIONS**

1ST LCASE	MAX. MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED	SNOW			
J	810	416 / 0	0 / 0	0 / 0	195 / 0
G	810	415 / 0	0 / 0	0 / 0	194 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, G

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.09 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	FR-TO	CHORDS			UNBRAC LENGTH	FR-TO	WEBS		
		MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)			MEMB. FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
A-B	0 / 28	-91.8	-91.8	0.13 (1)	10.00	I-C	-121 / 32	0.02 (1)	
B-C	-837 / 0	-91.8	-91.8	0.15 (1)	6.25	C-H	0 / 2	0.00 (4)	
C-K	-743 / 0	-91.8	-91.8	0.50 (1)	6.09	H-D	-118 / 34	0.02 (1)	
K-L	-743 / 0	-91.8	-91.8	0.50 (1)	6.09	B-I	0 / 778	0.19 (1)	
L-D	-743 / 0	-91.8	-91.8	0.50 (1)	6.09	H-E	0 / 783	0.19 (1)	
D-E	-844 / 0	-91.8	-91.8	0.15 (1)	6.25				
E-F	0 / 28	-91.8	-91.8	0.13 (1)	10.00				
J-B	-848 / 0	0.0	0.0	0.09 (1)	7.81				
G-E	-844 / 0	0.0	0.0	0.09 (1)	7.81				
J-M	0 / 0	-18.5	-18.5	0.08 (4)	10.00				
M-I	0 / 0	-18.5	-18.5	0.08 (4)	10.00				
I-N	0 / 742	-18.5	-18.5	0.18 (1)	10.00				
N-O	0 / 742	-18.5	-18.5	0.18 (1)	10.00				
O-H	0 / 742	-18.5	-18.5	0.18 (1)	10.00				
H-P	0 / 0	-18.5	-18.5	0.08 (4)	10.00				
P-G	0 / 0	-18.5	-18.5	0.08 (4)	10.00				

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-10-8	-119	-119		FRONT	VERT	TOTAL		C1
D	8-0-8	-119	-119		FRONT	VERT	TOTAL		C1
H	7-11-12	-5	-5		FRONT	VERT	TOTAL		C1
I	2-11-4	-5	-5		FRONT	VERT	TOTAL		C1
K	3-11-12	-7	-7		FRONT	VERT	TOTAL		C1
L	5-11-12	-7	-7		FRONT	VERT	TOTAL		C1
M	2-0-12	-5	-5		FRONT	VERT	TOTAL		C1
N	3-11-12	-5	-5		FRONT	VERT	TOTAL		C1
O	5-11-12	-5	-5		FRONT	VERT	TOTAL		C1
P	8-10-4	-5	-5		FRONT	VERT	TOTAL		C1

**CONNECTION REQUIREMENTS**

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

**DESIGN CRITERIA**

SPECIFIED LOADS:

TOP CH. LL = 25.8 PSF  
DL = 6.0 PSF

BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.36")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")  
ALLOWABLE DEFL.(TL) = L/360 (0.36")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.50/1.00 (C-D:1), BC=0.18/1.00 (H-I:1), WB=0.19/1.00 (E-H:1), SSI=0.21/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00  
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP(DRY)	SHEAR	SECTION (PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1967 1656	


PLATE PLACEMENT TOL. = 0.250 inches  
PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.77 (E) (INPUT = 0.90)  
JSI METAL = 0.28 (E) (INPUT = 1.00)

TOTAL WEIGHT = 43 lb



Structural component only  
DWG# T-2007118



**LUMBER**

N, L, G, A, RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
J - B	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	
J - G	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	4.0	2.00 1.25
C	TTWW-m	MT20	5.0	6.0	2.25 2.25
D	TTW-m	MT20	4.0	4.0	
E	TMVW-t	MT20	4.0	4.0	2.00 1.25
G	BMV1+p	MT20	3.0	4.0	
H	BMWW-t	MT20	4.0	6.0	2.00 1.50
I	BMWW-t	MT20	4.0	4.0	
J	BMV1+p	MT20	3.0	4.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	DOWN	HORZ	LIPLIFT	IN-SX	IN-SX
J	726	0	726	0	0	MECHANICAL	
G	726	0	726	0	0	5-8	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT J. MINIMUM BEARING LENGTH AT JOINT J = 1-8.

**UNFACTORED REACTIONS**

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
J	511	349 / 0	0 / 0	0 / 0	0 / 0	163 / 0	0 / 0
G	511	349 / 0	0 / 0	0 / 0	0 / 0	163 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS			WEBS			
		FACTORED VERT. LOAD (PLF)	MAX. LCI	MAX. CSI (LC)	MEMB. UNBRAC. LENGTH FR-TO	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	I-C	-78 / 18	0.02 (1)
B-C	-435 / 0	-91.8	-91.8	0.28 (1)	6.25	C-H	-4 / 0	0.00 (1)
C-D	-386 / 0	-91.8	-91.8	0.02 (1)	6.25	H-D	-82 / 19	0.03 (1)
D-E	-434 / 0	-91.8	-91.8	0.28 (1)	6.25	B-I	0 / 415	0.09 (1)
E-F	0 / 28	-91.8	-91.8	0.12 (1)	10.00	H-E	0 / 414	0.09 (1)
J-B	-888 / 0	0.0	0.0	0.08 (1)	7.81			
G-E	-888 / 0	0.0	0.0	0.08 (1)	7.81			
J-I	0 / 0	-18.5	-18.5	0.10 (4)	10.00			
I-H	0 / 387	-18.5	-18.5	0.14 (4)	10.00			
H-G	0 / 0	-18.5	-18.5	0.10 (4)	10.00			

TOTAL WEIGHT = 52 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.36")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.01")  
 ALLOWABLE DEFL.(TL)= L/360 (0.36")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI= TC=0.28/1.00 (B-C:1), BC=0.14/1.00 (H-I:4),  
 WB=0.09/1.00 (B-I:1), SSI=0.18/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE GRIP(DRY) SHEAR SECTION

(P5)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.66 (B) (INPUT = 0.90)  
 JSI METAL = 0.22 (B) (INPUT = 1.00)



Structural component only  
 DWG# T-2007119



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
F - A	2x4	DRY No.2	SPF
A - C	2x4	DRY No.2	SPF
D - C	2x4	DRY No.2	SPF
F - D	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
DRY: SEASONED LUMBER.			

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
A	TMW-t	MT20	4.0	8.0	
B	TMW-w	MT20	2.0	4.0	
C	TMW-t	MT20	4.0	6.0	
D	BMV-t-p	MT20	3.0	4.0	
E	BMWVW-t	MT20	4.0	9.0	
F	BMV-t-p	MT20	3.0	4.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
F	820	0	820	0	5-8	5-8
D	820	0	820	0	5-8	5-8

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED		MAX./MIN. SNOW		MIN. COMPONENT LIVE		PERM. LIVE	WIND	DEAD	SOIL
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX				
F	448	239 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	209 / 0	0 / 0	0 / 0
D	448	239 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	209 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.52 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED				WEBS	
	MAX. FORCE (LBS)	VERT. LOAD (LBS)	LC1	MAX	UNBRAC	MEMB. FORCE (LBS)	MAX FACTORED (LBS)	MAX CSI (LC)
FR-TO			FROM	TO	LENGTH	FR-TO		
F-A	-583 / 0	0.0	0.0	0.11 (1)	7.81	A-E	0 / 792	0.24 (1)
A-B	-695 / 0	-114.3	-114.3	0.55 (1)	5.52	E-B	-658 / 0	0.15 (1)
B-C	-895 / 0	-114.3	-114.3	0.55 (1)	5.52	E-C	0 / 792	0.24 (1)
D-C	-583 / 0	0.0	0.0	0.11 (1)	7.81			
F-E	0 / 0	-18.5	-18.5	0.13 (4)	10.00			
E-D	0 / 0	-18.5	-18.5	0.13 (4)	10.00			

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH.	LL = 25.8 PSF
	DL = 15.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 48.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.31")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.01")  
 ALLOWABLE DEFL.(TL) = L/360 (0.31")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.55/1.00 (B-C:1), BC=0.13/1.00 (E-F:4), WB=0.24/1.00 (A-E:1), SS=0.34/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00  
 FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PS)	(PL)	(PS)	(PL)	(PL)	(PL)
MT20	618	354	1667	788	1987	1556


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.81 (A) (INPUT = 0.90)  
 JSI METAL = 0.24 (A) (INPUT = 1.00)



Structural component only  
 DWG# T-2007120



TOTAL WEIGHT = 34 lb [M/J]

**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
L - A	2x4	DRY	No.2	SPF
A - F	2x4	DRY	No.2	SPF
G - J	2x4	DRY	No.2	SPF
L - G	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF  
 ALL GABLE WEBS 2x3 DRY No.2 SPF  
 DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2-0-0 OC.

**PLATES (table in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
B, C, D, E						
B	TMV+w	MT20	2.0	4.0		
F	TMV+p	MT20	3.0	4.0		
G	BMV1+p	MT20	3.0	4.0		
H, I, J, K						
H	BMV1+w	MT20	2.0	4.0		
L	BMV1+p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**  
 PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING.

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 (LC)	MAX. UNBRAC LENGTH	MEMB. FORCE (LBS)	MAX FACTORED CSI (LC)
FR-TO		FROM TO			FR-TO	
L-A	-101 / 0	0.0	0.0 0.03 (1)	7.81	K-B	-245 / 0 0.06 (1)
A-B	-8 / 0	-114.3	-114.3 0.08 (1)	10.00	J-C	-224 / 0 0.05 (1)
B-C	-8 / 0	-114.3	-114.3 0.08 (1)	10.00	F-D	-237 / 0 0.05 (1)
C-D	-8 / 0	-114.3	-114.3 0.07 (1)	10.00	H-E	-198 / 0 0.04 (1)
D-E	-8 / 0	-114.3	-114.3 0.07 (1)	10.00		
E-F	-8 / 0	-114.3	-114.3 0.05 (1)	10.00		
G-F	-84 / 0	0.0	0.0 0.02 (1)	7.81		
L-K	0 / 8	-18.5	-18.5 0.02 (4)	10.00		
K-J	0 / 8	-18.5	-18.5 0.02 (4)	10.00		
J-I	0 / 8	-18.5	-18.5 0.02 (4)	10.00		
I-H	0 / 8	-18.5	-18.5 0.02 (4)	10.00		
H-G	0 / 8	-18.5	-18.5 0.02 (1)	10.00		

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 15.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 48.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, CBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2018 AMENDMENT)  
 - CSA 086-09, CSA 088-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.08/1.00 (A-B:1), BC=0.02/1.00 (K-L:4),  
 WB=0.06/1.00 (B-K:1), SS=0.13/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.70

COMPANION LIVE LOAD FACTOR = 1.00  
 FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**  
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) (PLI)  
 MAX MIN MAX MIN MAX MIN  
 MT20 618 354 1867 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches  
 PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.17 (K) (INPUT = 0.90)  
 JSI METAL= 0.07 (K) (INPUT = 1.00)



Structural component only  
 DWG# T-2007104



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR
F - A	2x4 DRY	No.2	SPF
A - C	2x6 DRY	No.2	SPF
D - C	2x4 DRY	No.2	SPF
F - D	2x6 DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF  
 DRY, SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	5.0	6.0		
B	TMW+w	MT20	3.0	6.0		
C	TMVW-t	MT20	5.0	6.0		
D	BMV1+p	MT20	3.0	6.0		
E	BMVWW-t	MT20	5.0	6.0		
F	BMV1+p	MT20	3.0	6.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**  
 PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING.

**BEARINGS**

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	IN-SX
F	988	0	988	0	0	MECHANICAL		
D	1012	0	1012	0	0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 3-8, JOINT D = 3-8.

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERM	LIVE	WIND	DEAD	SOIL
F	705	427/0	0/0	0/0	0/0	0/0	279/0	0/0
D	722	439/0	0/0	0/0	0/0	0/0	283/0	0/0

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.  
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED				WEBS			
			VERT. LOAD (PLF)	LC1	MAX	MAX	MEMB.	MAX. FACTORED FORCE (LBS)	MAX	CS1 (LC)
FR-TO			FROM			FR-TO				
F-A	-846/0	0.0	0.0	0.23 (1)	7.45	A-E	0/1072	0.35 (1)		
A-B	-869/0	-114.3	-114.3	0.24 (1)	6.25	E-B	-632/0	0.18 (1)		
B-C	-869/0	-114.3	-114.3	0.24 (1)	6.25	E-C	0/1072	0.35 (1)		
D-C	-846/0	0.0	0.0	0.23 (1)	7.45					
F-G	0/0	-18.5	-18.5	0.24 (1)	10.00					
G-H	0/0	-18.5	-18.5	0.24 (1)	10.00					
H-E	0/0	-18.5	-18.5	0.24 (1)	10.00					
E-I	0/0	-18.5	-18.5	0.24 (1)	10.00					
I-J	0/0	-18.5	-18.5	0.24 (1)	10.00					
J-D	0/0	-18.5	-18.5	0.24 (1)	10.00					

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-8-12	-180	-180	---	FRONT	VERT	TOTAL	---	C1
H	3-8-12	-180	-180	---	FRONT	VERT	TOTAL	---	C1
I	5-8-12	-180	-180	---	FRONT	VERT	TOTAL	---	C1
J	7-8-12	-180	-180	---	FRONT	VERT	TOTAL	---	C1

**CONNECTION REQUIREMENTS**  
 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 51 lb [M/F]

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL	= 25.6 PSF
DL	= 15.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 48.0 PSF

**SPACING = 24.0 IN/C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCG 2010, NBCG 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, CBC 2012, ABC 2019  
 - PART 9 OF CBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIQ 2011, TPIQ 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.31")  
 CALCULATED VERT. DEFL. (LL) = L/999 (0.02")  
 ALLOWABLE DEFL. (TL) = L/360 (0.31")  
 CALCULATED VERT. DEFL. (TL) = L/999 (0.04")

CSI: TC=0.24/1.00 (B-C:1), BC=0.24/1.00 (D-E:1), WB=0.35/1.00 (A-E:1), SSI=0.29/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00  
 FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE	GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MT20	618	354	1667 788 1987 1658


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.76 (E) (INPUT = 0.80)  
 JSI METAL = 0.32 (E) (INPUT = 1.00)



Tamarack Roof Truss, Burlington



TOTAL WEIGHT = 2 X 30 = 60 lb

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
D - C	2x4	DRY No.2	SPF
A - D	2x6	DRY No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF			
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C 1	12	TOP
C-D 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
A-D 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.  
 GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

JT TYPE	PLATES	W	LEN	Y	X
A	TBMH1+m	MT20	5.0	8.0	3.50
B	TMWw-1	MT20	5.0	6.0	2.50 2.25
C	TMV+p	MT20	3.0	4.0	
D	BMVw-1	MT20	5.0	8.0	2.50 2.75
E	BMW+w	MT20	3.0	10.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

JT	GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	RECORD BRG	HEEL WEDGE
	VERT	HORZ	DOWN	HORZ			
A	3467	0	3467	0	5-8	IN-SX	2x4 L
D	2454	0	2454	0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 4-0.

JT	1ST CASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERMLIVE			
A	2449	1822/0	0/0	0/0	0/0	828/0	0/0
D	1735	1144/0	0/0	0/0	0/0	591/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.16 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	FR-TO	CHORDS		WEBS	
		MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)
A-G		-4978/0	-91.8	4.16	0/3365
G-B		-3863/0	-91.8	4.66	-4035/0
B-C		-13/0	-91.8	6.25	0/1740
D-C		-129/0	0.0	7.81	
A-F		0/3490	-18.5	10.00	
F-H		0/3490	-18.5	10.00	
H-I		0/3490	-18.5	10.00	
I-J		0/3490	-18.5	10.00	
J-E		0/3490	-18.5	10.00	
E-K		0/3490	-18.5	10.00	
K-D		0/3490	-18.5	10.00	

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
H	1-4-0	-1378	-1378	---	BACK	VERT	TOTAL	---	C1
I	2-0-0	-1000	-1000	---	FRONT	VERT	TOTAL	---	C1
J	3-0-4	-994	-994	---	FRONT	VERT	TOTAL	---	C1
J	3-3-4	-896	-896	---	BACK	VERT	TOTAL	---	C1
K	5-3-4	-896	-896	---	BACK	VERT	TOTAL	---	C1

**CONNECTION REQUIREMENTS**  
 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

**DESIGN CRITERIA**

\*\*\* SPECIAL LOADS ANALYSIS \*\*\*  
 GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.  
 LOADS WERE DERIVED FROM USER INPUT  
 NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C  
 \*\*\* NON STANDARD GIRDER \*\*\*  
 ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 088-09, CSA 088-14  
 - TPIC 2011, TPIC 2014

(55% OF 91.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.23")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.03")  
 ALLOWABLE DEFL.(TL) = L/360 (0.23")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.19/1.00 (A-G:1), BC=0.88/1.00 (E-F:1),  
 WB=0.53/1.00 (B-D:1), SG=0.90/1.00 (E-F:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.00  
 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667 788 1987 1658


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.88 (B) (INPUT = 0.90)  
 JSI METAL = 0.70 (A) (INPUT = 1.00)



Structural component only  
 DWG# T-2007122



**LUMBER**  
 N. L. G. A. RULES  
 CHORDS SIZE LUMBER DESCR.  
 AC-B 2x4 DRY No.2 SPF  
 A-H 2x4 DRY No.2 SPF  
 H-J 2x4 DRY No.2 SPF  
 J-O 2x4 DRY No.2 SPF  
 P-O 2x4 DRY No.2 SPF  
 AC-T 2x4 DRY No.2 SPF  
 T-P 2x4 DRY No.2 SPF  
 ALL WEBS 2x3 DRY No.2 SPF  
 ALL GABLE WEBS 2x3 DRY No.2 SPF  
 DRY: SEASONED LUMBER.  
 GABLE STUDS SPACED AT 2'-0" O.C.


**PLATES (table in inches)**  
 JT TYPE PLATES W LEN Y X  
 B TMV+p MT20 3.0 4.0  
 C, D, E, F, G, I, K, L, M, N  
 C TMV+w MT20 2.0 4.0  
 H TS+ MT20 3.0 6.0  
 J TTW+m MT20 4.0 4.0  
 O TMV+p MT20 3.0 4.0  
 P BMV1+p MT20 3.0 4.0  
 Q, R, S, U, V, W, X, Y, Z, AA, AB  
 Q BMV1+w MT20 2.0 4.0  
 T BS+ MT20 3.0 6.0  
 AO BMV1+p MT20 3.0 4.0

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**  
**BEARINGS**  
 THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.  
 THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.  
 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)  
**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.  
 1 LATERAL BRACE(S) AT 1/2 LENGTH OF O-P.  
 END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

**LOADING**  
 TOTAL LOAD CASES: (4)


MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	UNBRACED LENGTH	MEMB. MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	FR-TO	MEMB. MAX. FACTORED FORCE (LBS)
FR-TO								
AC-B	-224 / 0	0.0	0.0	0.02 (1)	7.81	C-N	-195 / 0	0.25 (1)
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	R-M	-183 / 0	0.23 (1)
B-C	-28 / 0	-91.8	-91.8	0.04 (1)	6.25	S-L	-188 / 0	0.24 (1)
C-D	-19 / 0	-91.8	-91.8	0.04 (1)	6.25	U-K	-136 / 0	0.17 (1)
D-E	-15 / 0	-91.8	-91.8	0.04 (1)	6.25	V-J	-131 / 0	0.17 (1)
E-F	-11 / 0	-91.8	-91.8	0.04 (1)	6.25	W-I	-185 / 0	0.17 (1)
F-G	-8 / 0	-91.8	-91.8	0.04 (1)	10.00	X-G	-183 / 0	0.11 (1)
G-H	-6 / 0	-91.8	-91.8	0.04 (1)	10.00	Y-F	-182 / 0	0.07 (1)
H-I	-6 / 0	-91.8	-91.8	0.04 (1)	10.00	Z-E	-182 / 0	0.05 (1)
I-J	-6 / 0	-91.8	-91.8	0.04 (1)	10.00	AA-D	-183 / 0	0.03 (1)
J-K	-2 / 0	-91.8	-91.8	0.03 (1)	10.00	AB-C	-176 / 0	0.03 (1)
K-L	-2 / 0	-91.8	-91.8	0.04 (1)	10.00			
L-M	-2 / 0	-91.8	-91.8	0.04 (1)	10.00			
M-N	-2 / 0	-91.8	-91.8	0.04 (1)	10.00			
N-O	-2 / 0	-91.8	-91.8	0.04 (1)	10.00			
P-O	-81 / 0	0.0	0.0	0.01 (1)	6.25			
AC-AB	0 / 24	-18.5	-18.5	0.02 (4)	10.00			
AB-AA	0 / 17	-18.5	-18.5	0.02 (4)	10.00			
AA-Z	0 / 13	-18.5	-18.5	0.02 (4)	10.00			
Z-Y	0 / 10	-18.5	-18.5	0.02 (4)	10.00			
Y-X	0 / 7	-18.5	-18.5	0.01 (4)	10.00			
X-W	0 / 5	-18.5	-18.5	0.02 (4)	10.00			
W-V	0 / 4	-18.5	-18.5	0.02 (4)	10.00			
V-U	0 / 2	-18.5	-18.5	0.02 (4)	10.00			
U-T	0 / 2	-18.5	-18.5	0.01 (4)	10.00			
T-S	0 / 2	-18.5	-18.5	0.02 (4)	10.00			
S-R	0 / 2	-18.5	-18.5	0.02 (4)	10.00			
R-Q	0 / 2	-18.5	-18.5	0.02 (4)	10.00			
Q-P	0 / 2	-18.5	-18.5	0.02 (4)	10.00			

**DESIGN CRITERIA**  
 SPECIFIED LOADS:  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF  
**SPACING = 24.0 IN./C**  
 LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12  
 THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015  
 THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014  
**DESIGN ASSUMPTIONS**  
 OVERHANG NOT TO BE ALTERED OR CUT OFF.  
 (55% OF 31.3 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD  
 CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (Q-R:4), WB=0.25/1.00 (N-Q:1), SS=0.09/1.00 (A-B:1)  
 DOL LUMBER=1.00 NAIL=1.00 LBS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10  
 COMPANION LIVE LOAD FACTOR = 1.00  
 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.  
**NAIL VALUES**  
 PLATE GRIP(DRY) SHEAR SECTION (PS) (PL) (PL)  
 MAX MIN MAX MIN MAX MIN  
 MT20 618 354 1667 788 1987 1656  
 PLATE PLACEMENT TOL. = 0.250 inches  
 PLATE ROTATION TOL. = 5.0 Deg.  
 JSI GRIP= 0.60 (J) (INPUT = 0.90)  
 JSI METAL= 0.08 (I) (INPUT = 1.00)



Structural component only  
 DWG# T-2007057





**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
A - G	2x4	DRY No.2	SPF
G - E	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TBM1-h	MT20	3.0	4.0		
B	TMW-w	MT20	2.0	4.0		
C	TTWW-w	MT20	4.0	6.0	Edge	
D	TMW-w	MT20	2.0	4.0		
E	TBM1-h	MT20	3.0	4.0		
F	BMWW1-t	MT20	4.0	4.0		
G	BS-t	MT20	3.0	6.0		
H	BMWW1-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION VERT	FACTORED GROSS REACTION HORZ	MAXIMUM FACTORED GROSS REACTION DOWN	MAXIMUM FACTORED GROSS REACTION HORZ	INPUT BRG IN-SX	REQD BRG IN-SX
A	134	0	134	0	18-1-0 (9-11-18)	1-0
E	134	0	134	0	18-1-0 (9-11-18)	1-0
F	883	0	883	0	18-1-0 (9-11-18)	1-0
H	883	0	883	0	18-1-0 (9-11-18)	1-0

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

**UNFACTORED REACTIONS**

JT	1ST CASE COMBINED	MAX. MIN. COMPONENT REACTIONS SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
A	94	68 / 0	0 / 0	0 / 0	0 / 0	28 / 0	0 / 0
E	94	68 / 0	0 / 0	0 / 0	0 / 0	28 / 0	0 / 0
F	611	395 / 0	0 / 0	0 / 0	0 / 0	218 / 0	0 / 0
H	611	395 / 0	0 / 0	0 / 0	0 / 0	218 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, F, H

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 16.00 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS		WEBS	
		VERT. LOAD (LBS)	LCI MAX (PL)	MAX. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)
FR-TO					
A-J	0 / 240	-91.8	-91.8 0.12 (1)	10.00	C-F -428 / 0
J-B	0 / 301	-91.8	-91.8 0.34 (1)	10.00	F-D -436 / 0
B-C	0 / 503	-91.8	-91.8 0.37 (1)	10.00	H-C -428 / 0
C-D	0 / 503	-91.8	-91.8 0.37 (1)	10.00	B-H -438 / 0
D-L	0 / 301	-91.8	-91.8 0.34 (1)	10.00	I-J -76 / 35
L-E	0 / 240	-91.8	-91.8 0.12 (1)	10.00	K-L -76 / 35
A-I	-255 / 0	-18.5	-18.5 0.11 (1)	6.25	
I-H	-243 / 0	-18.5	-18.5 0.13 (4)	6.25	
H-G	-246 / 0	-18.5	-18.5 0.13 (4)	6.25	
G-F	-246 / 0	-18.5	-18.5 0.13 (4)	6.25	
F-K	-243 / 0	-18.5	-18.5 0.13 (4)	6.25	
K-E	-255 / 0	-18.5	-18.5 0.11 (1)	6.25	

TOTAL WEIGHT = 2 X 54 = 107 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 088-14  
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.37/1.00 (C-D-I), BC=0.13/1.00 (F-K-4), WB=0.18/1.00 (C-H-1), SS=0.17/1.00 (D-L-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PS)	(PL)	(PL)
MT20	518	354	1667 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.48 (H) (INPUT = 0.90)  
JSI METAL= 0.15 (C) (INPUT = 1.00)



Structural component only  
DWG# T-2007058



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
A - G	2x4	DRY	No.2	SPF
G - E	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2  
 DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
A	TBM1-h	MT20	3.0	4.0		
B	TMWW-1	MT20	4.0	4.0	2.00	1.75
C	TTW-p	MT20	4.0	4.0		
D	TMWW-1	MT20	4.0	4.0	2.00	1.75
E	TBM1-h	MT20	3.0	4.0		
F	BMW1+w	MT20	2.0	4.0		
G	SS-1	MT20	3.0	6.0		
H	BMWW1-1	MT20	4.0	9.0		
I	BMW1+w	MT20	2.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
A	124	0	124	0	18-1-0 (11-11)E20	0
E	124	0	124	0	18-1-0 (11-11)E20	0
H	415	0	415	0	18-1-0 (11-11)E20	0
F	666	0	666	0	18-1-0 (11-11)E20	0
I	666	0	666	0	18-1-0 (11-11)E20	0

**UNFACTORED REACTIONS**

JT	1ST LOASE COMBINED	MAX/MIN COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
A	87	59 / 0	0 / 0	0 / 0	0 / 0	28 / 0	0 / 0
E	87	59 / 0	0 / 0	0 / 0	0 / 0	28 / 0	0 / 0
H	293	192 / 0	0 / 0	0 / 0	0 / 0	101 / 0	0 / 0
F	471	307 / 0	0 / 0	0 / 0	0 / 0	164 / 0	0 / 0
I	471	307 / 0	0 / 0	0 / 0	0 / 0	164 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, H, F, I

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	MEMB.
A-K	0 / 248	-91.8	-91.8 0.07 (1)	10.00	H-C	-445 / 0	0.13 (1)
K-B	0 / 292	-91.8	-91.8 0.32 (1)	10.00	H-D	0 / 59	0.01 (1)
B-C	0 / 188	-91.8	-91.8 0.30 (1)	10.00	F-D	-528 / 0	0.08 (1)
C-D	0 / 188	-91.8	-91.8 0.30 (1)	10.00	S-H	0 / 59	0.01 (1)
D-M	0 / 292	-91.8	-91.8 0.32 (1)	10.00	I-B	-528 / 0	0.08 (1)
M-E	0 / 248	-91.8	-91.8 0.07 (1)	10.00	J-K	-128 / 6	0.00 (1)
A-J	-256 / 0	-18.5	-18.5 0.14 (1)	6.25	L-M	-128 / 6	0.00 (1)
J-I	-240 / 0	-18.5	-18.5 0.14 (1)	6.25			
I-H	-240 / 0	-18.5	-18.5 0.11 (1)	6.25			
H-G	-240 / 0	-18.5	-18.5 0.11 (1)	6.25			
G-F	-240 / 0	-18.5	-18.5 0.11 (1)	6.25			
F-L	-240 / 0	-18.5	-18.5 0.14 (1)	6.25			
L-E	-256 / 0	-18.5	-18.5 0.14 (1)	6.25			

TOTAL WEIGHT = 17 X 55 = 943 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 8.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2018 AMENDMENT)  
 - CSA 086-09, CSA 088-14  
 - TPIC 2011, TPIC 2014

(5% OF 31.3 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.32/1.00 (D-M:1), BC=0.14/1.00 (F-L:1),  
 WB=0.13/1.00 (C-H:1), SSI=0.17/1.00 (D-M:1)

OOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10  
 COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PL)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches  
 PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.51 (B) (INPUT = 0.90)  
 JSI METAL = 0.13 (C) (INPUT = 1.00)



Structural component only  
 DWG# T-2007062



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
E - G	2x4	DRY No.2	SPF
G - I	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0	1.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TMW+w	MT20	2.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMB1-I	MT20	3.0	4.0	1.50	2.00
H	BMW1+w	MT20	2.0	4.0		
I	BMWW1-I	MT20	4.0	9.0		
J	BMW1+w	MT20	2.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	REQRD BRG IN-SX
B	169	0	169	0	0	13-7-1	13-7-1
F	169	0	169	0	0	13-7-1	13-7-1
J	288	0	288	0	0	13-7-1	13-7-1
I	683	0	683	0	0	13-7-1	13-7-1
H	288	0	288	0	0	13-7-1	13-7-1

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	118	93/0	0/0	0/0	0/0	23/0	0/0
F	118	93/0	0/0	0/0	0/0	23/0	0/0
J	207	118/0	0/0	0/0	0/0	89/0	0/0
I	481	327/0	0/0	0/0	0/0	154/0	0/0
H	207	118/0	0/0	0/0	0/0	89/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, J, I, H

**BRACING**

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)		MAX. UNBRAC LENGTH	WIND	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
		FROM	TO				
FR-TO							
A-B	0/14	-91.8	-91.8	0.02 (1)	10.00	J-C -194/0	0.03 (1)
B-L	-31/4	-91.8	-91.8	0.01 (1)	6.25	C-I -22/0	0.01 (1)
L-C	-60/0	-91.8	-91.8	0.03 (1)	6.25	I-D -576/0	0.08 (1)
C-D	-8/0	-91.8	-91.8	0.39 (1)	10.00	I-E -22/0	0.01 (1)
D-E	-8/0	-91.8	-91.8	0.39 (1)	10.00	H-E -194/0	0.03 (1)
E-N	-60/0	-91.8	-91.8	0.03 (1)	6.25	K-L -121/0	0.00 (1)
N-F	-31/4	-91.8	-91.8	0.01 (1)	6.25	M-N -121/0	0.00 (1)
F-G	0/14	-91.8	-91.8	0.02 (1)	10.00		
B-K	0/42	-18.5	-18.5	0.04 (1)	10.00		
K-J	0/42	-18.5	-18.5	0.07 (4)	10.00		
J-I	0/28	-18.5	-18.5	0.10 (4)	10.00		
I-H	0/28	-18.5	-18.5	0.10 (4)	10.00		
H-M	0/42	-18.5	-18.5	0.07 (4)	10.00		
M-F	0/42	-18.5	-18.5	0.04 (1)	10.00		

TOTAL WEIGHT = 2 X 45 = 90 LB

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL = 25.6 PSF  
 DL = 8.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.39/1.00 (C-D-1), BC=0.10/1.00 (I-J-4), WB=0.08/1.00 (D-I-1), SSI=0.22/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP (DRY) (PSI)	SHEAR (PLI)	SELECTION (PLI)
MT20	618	354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.30 (D) (INPUT = 0.90)  
 JSI METAL = 0.12 (D) (INPUT = 1.00)



Structural component only  
 DWG# T-2007080

JOB NAME 408150	TRUSS NAME U1	QUANTITY 21	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	



TOTAL WEIGHT = 21 X 17 = 353 lb

**LUMBER**  
 N. L. G. A. RULES  
 CHORDS SIZE LUMBER  
 E - B 2x4 DRY No.2  
 A - C 2x4 DRY No.2  
 E - D 2x4 DRY No.2  
 DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p MT20	3.0	4.0		
E	BMV1+p MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	BRG IN-SX	REQD BRG IN-SX
E	525	0	525	0	0	5-8	5-8
C	202	0	202	0	0	1-8	1-8
D	45	0	50	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERMLIVE	WIND	DEAD	SOIL
E	389	257/0	0/0	0/0	0/0	111/0	0/0
C	139	113/0	0/0	0/0	0/0	26/0	0/0
D	36	0/0	0/0	0/0	0/0	36/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
 ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD			MAX. UNBRACED LENGTH	FR-TO	WEBS	
		FROM	TO	MAX. FORCE (LBS)			MAX. CSI (LC)	
E-B	-461/0	0.0	0.0	0.13 (4)	7.81			
A-B	0/28	-91.8	-91.8	0.12 (1)	10.00			
B-C	-30/0	-91.8	-91.8	0.54 (1)	6.25			
E-D	0/0	-18.5	-18.5	0.13 (4)	10.00			

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.8 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**  
 THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

**THIS DESIGN COMPLIES WITH:**  
 - PART 9 OF CBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
 - OVERHANG NOT TO BE ALTERED OR CUT OFF.  
 (55% OF 31.3 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.00")  
 ALLOWABLE DEFL.(TL) = L/360 (0.20")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.54/1.00 (B-C:1), BC=0.13/1.00 (D-E:4),  
 WB=0.03/1.00 (1/a:0), SSI=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE	GRIP (DRY) (PSI)	SHEAR (PL) (PL)	SECTION MAX MIN (PL) (PL)
MT20	618	354	1667 788 1987 1656


PLATE PLACEMENT TDL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.19 (E) (INPUT = 0.50)  
 JSI METAL = 0.13 (B) (INPUT = 1.00)



Structural component only  
 DWG# T-2007059



TOTAL WEIGHT = 15 lb

**LUMBER**  
 N. L. G. A. RULES  
 CHORDS SIZE LUMBER

F - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2

DRY: SEASONED LUMBER.

**PLATES (plate is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW+P	MT20	4.0	4.0	1.00 2.00
E	BMW+P	MT20	2.0	4.0	
F	BMV1+P	MT20	3.0	4.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
F	341	0	341	0	5-8	5-8
C	178	0	178	0	1-8	1-8
D	36	0	40	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

**UNFACTORED REACTIONS**

JT	COMBINED	1ST LCASE		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
		MAX.	MIN.						
F	239	170/0	0/0	0/0	0/0	0/0	0/0	89/0	0/0
C	122	99/0	0/0	0/0	0/0	0/0	0/0	23/0	0/0
D	29	0/0	0/0	0/0	0/0	0/0	0/0	29/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (LBS)	LC1 (PLF)	MAX. CSI (LC)	MEMB. FORCE (LBS)	MAX. UNBRAC LENGTH (FT)	FR-TO	MAX. CSI (LC)
F-B	-305/0	0.0	0.0	0.03 (1)	7.81	B-E	0/0	0.00 (1)
A-B	0/41	-91.8	-91.8	0.14 (5)	10.00			
B-C	0/0	-91.8	-91.8	0.23 (1)	10.00			
F-E	0/0	-18.5	-18.5	0.08 (4)	10.00			
E-D	0/0	-18.5	-18.5	0.08 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 8.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 088-14  
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.00")  
 ALLOWABLE DEFL.(TL) = L/360 (0.19")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.23/1.00 (B-C:1), BC=0.08/1.00 (D-E:4), WB=0.09/1.00 (B-E:1), SS=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788
		1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.24 (B) (INPUT = 0.90)  
 JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only  
 DWG# T-2007060



TOTAL WEIGHT = 6 X 12 = 71 lb

**LUMBER**  
N. L. G. A. RULES  
CHORDS SIZE LUMBER  
A - C 2x4 DRY No.2  
B - D 2x4 DRY No.2

DESCR. SPF  
SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMB1-1	MT20	3.0	4.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
C	174	0	174	0	1-8	1-8
B	364	0	364	0	5-8	5-8
D	68	0	68	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

**UNFACTORED REACTIONS**

JT	1ST LOASE COMBINED	MAX. MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
C	120	93/0	0/0	0/0	0/0	27/0	0/0
B	255	180/0	0/0	0/0	0/0	75/0	0/0
D	50	19/0	0/0	0/0	0/0	32/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. (PLF)	LOAD LC1	MAX. CSI (LC)	MEMB. FORCE (LBS)	MAX. FACTORED UNBRAC LENGTH	FR-TO	MAX. CSI (LC)
A-B	0/18	-91.8	-91.8	0.11 (1)	10.00	E-F	-194/7	0.00 (1)
B-F	-14/0	-91.8	-91.8	0.05 (4)	8.25			
F-C	0/2	-91.8	-91.8	0.22 (1)	10.00			
B-E	0/0	-18.5	-18.5	0.17 (1)	10.00			
E-D	0/0	-18.5	-18.5	0.17 (1)	10.00			

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019  
- PART 9 OF CBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

(5% OF 31.3 P.S.F. G.S.L. PLUS 5.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")  
ALLOWABLE DEFL.(TL) = L/360 (0.19")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.22/1.00 (C-F:1), BC=0.17/1.00 (D-E:1), WB=0.00/1.00 (E-F:1), SS=0.18/1.00 (B-E:1)

DOL LUMBER=1.00 NAIL=1.00 LBS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE GRIP/DRY (PS)	SHEAR (PL)	SECTION (PL)
MAX	MIN	MAX
618	354	1657
788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches  
PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.24 (B) (INPUT = 0.80)  
JSI METAL = 0.07 (B) (INPUT = 1.00)



Structural component only  
DWG# T-2007061



Scale = 1/2" = 1'-0"

**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
E - A	2x4 DRY	No.2	SPF
A - B	2x4 DRY	No.2	SPF
E - C	2x4 DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF  
 DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
A TMW-1	MT20	4.0	4.0	2.00	1.25
D BMW-w	MT20	2.0	4.0		
E BMW-f-p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	REQD BRG
E	209	0	209	0	0	MECHANICAL	1-8
B	174	0	174	0	0	1-8	1-8
C	35	0	39	0	0	1-8	1-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) B, C

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	148	97/0	0/0	0/0	0/0	51/0	0/0
B	120	97/0	0/0	0/0	0/0	23/0	0/0
C	28	0/0	0/0	0/0	0/0	28/0	0/0

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.  
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PL)	LC1 MAX	LC2 MAX	MEMB. MAX. FORCE (LBS)	FACTORED UNBRAC LENGTH FR-TO	MEMB. MAX. FORCE (LBS)	FACTORED MAX
E-A	-174/0	0.0	0.0	0.02 (1)	7.81	A-D	0/0	0.00 (1)
A-B	0/0	-91.8	-91.8	0.22 (1)	10.00			
E-D	0/0	-18.5	-18.5	0.07 (4)	10.00			
D-C	0/0	-18.5	-18.5	0.08 (4)	10.00			

TOTAL WEIGHT = 4 X 13 = 52 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 8.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 088-14  
 - TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.00")  
 ALLOWABLE DEFL.(TL) = L/360 (0.18")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.22/1.00 (A-B:1), BC=0.08/1.00 (C-D:4),  
 WB=0.00/1.00 (A-D:1), SSI=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**  
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)  
 MAX MIN MAX MIN MAX MIN  
 MT20 618 354 1667 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.11 (A) (INPUT = 0.90)  
 JSI METAL = 0.03 (A) (INPUT = 1.00)



Structural component only  
 DWG# T-2007105

JOB NAME 408152	TRUSS NAME J41	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:29:31 2020 Page 1  
 ID:17vF7aG0E03cRUj6X1jSrkzWYK-Y2cwkhrJoCKCTbzSJsX?a8a7q0FFUJ5WDM29q\_zNCOY



TOTAL WEIGHT = 4 X 10 = 38 lb

**LUMBER**  
 N. L. G. A. RULES  
 CHORDS SIZE LUMBER

E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DESCR.  
 SPFF  
 SPFF  
 SPFF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	319	0	319	0	5-8	5-8
C	99	0	99	0	1-8	1-8
D	23	0	26	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

**UNFACTORED REACTIONS**

JT	COMBINED	1ST LCASE MAX. MIN. COMPONENT REACTIONS				WIND	DEAD	SOIL
		SNOW	LIVE	PERM. LIVE	DOWN			
E	223	181/0	0/0	0/0	0/0	82/0	0/0	
C	68	55/0	0/0	0/0	0/0	13/0	0/0	
D	18	0/0	0/0	0/0	0/0	18/0	0/0	

BEARING MATERIAL TO BE SPFF NO.2 OR BETTER AT JOINT(S) E

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (5)

MEMB.	CHORDS		WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX	UNBRAC LENGTH	FR-TO
E-B	-289/0	0.0	0.0	0.02 (4)	7.81	
A-B	0/28	-91.8	-91.8	0.13 (5)	10.00	
B-C	-15/0	-91.8	-91.8	0.13 (1)	6.25	
E-D	0/0	-18.5	-18.5	0.03 (4)	10.00	

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TDP CH. LL = 25.6 PSF  
 DL = 8.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 088-09, CSA 086-14  
 - TPC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
 - OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/960 (0.18")  
 CALCULATED VERT. DEFL.(LL) = L/989 (0.00")  
 ALLOWABLE DEFL.(TL) = L/380 (0.16")  
 CALCULATED VERT. DEFL.(TL) = L/989 (0.00")

CSI: TC=0.13/1.00 (B-C:1), BC=0.03/1.00 (D-E:4),  
 WB=0.00/1.00 (W:0), SSI=0.11/1.00 (B-C:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PL)	MIN	MAX	MIN	MAX
MT20	618	354	1667	788	1987	1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.



JSI GRIP = 0.12 (E) (INPUT = 0.90)  
 JSI METAL = 0.08 (B) (INPUT = 1.00)



Structural component only  
 DWG# T-2007106







**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2  
 DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X	
B	TMVW+p	MT20	4.0	4.0	1.00	2.00
D	BMW1-t	MT20	4.0	4.0	2.00	1.25
E	BMV1+p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	RECORD BRG IN-SX
E	278	0	0	5-8
C	42	0	-36	1-8
D	18	0	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D  
 PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

**UNFACTORED REACTIONS**

JT	TST LCASE	MAX. SNOW	MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	194	145/0	0/0	0/0	0/0	48/0	0/0
C	29	23/-26	0/0	0/0	0/0	5/0	0/0
D	14	0/0	0/0	0/0	0/0	14/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (5)

MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS			WEBS		
		FACTORED VERT. LOAD (PLF)	LCI	MAX. CSI (LC)	MEMB. FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM	TO	LENGTH	FR-TO		
E-B	-281/0	0.0	0.0	0.03 (1)	7.81	B-D	
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00		
B-C	-29/0	-91.8	-91.8	0.12 (1)	6.25		
E-D	0/0	-18.5	-18.5	0.02 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN./C/C**  
 THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF CBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
 - OVERHANG NOT TO BE ALTERED OR CUT OFF.  
 (55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (TL) = L/360 (0.19")  
 CALCULATED VERT. DEFL. (TL) = L/999 (0.00")

CSI: TC=0.13/1.00 (A-B:1), BC=0.02/1.00 (D-E:4),  
 WB=0.00/1.00 (B-D:1), SS=0.08/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PL)
MAX MIN	MAX MIN	MAX MIN
MT20	619 354	1887 788

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.20 (B) (INPUT = 0.90)  
 JSI METAL = 0.05 (B) (INPUT = 1.00)


TOTAL WEIGHT = 10 lb



Structural component only  
 DWG# T-2007056

JOB NAME 408152	TRUSS NAME C40	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:21 2020 Page 1  
 ID:i7vF?AG0E03cRUj6X1jSrkiWYK-q778eGk1873dG3CXkLFA19Pt\_o08nd2voddJZzNCO



Scale = 1:17.5

**LUMBER**

N. L. G. A. RULES				
CHORDS	SIZE	DRY	LUMBER	No.2
E - B	2x4	DRY	No.2	
A - C	2x4	DRY	No.2	
E - D	2x4	DRY	No.2	

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p MT20	3.0	4.0		
E	BMV1+p MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION VERT	FACTORED GROSS REACTION HORZ	MAXIMUM FACTORED GROSS REACTION DOWN	MAXIMUM FACTORED GROSS REACTION HORZ	INPUT BRG IN-SX	REQRD BRG IN-SX
E	405	0	405	0	5-8	5-8
C	130	0	130	0	1-8	1-8
D	45	0	50	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

**UNFACTORED REACTIONS**

JT	COMBINED	SNOW	MAX. MIN. COMPONENT REACTIONS LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	288	190 / 0	0 / 0	0 / 0	0 / 0	95 / 0	0 / 0
C	90	73 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	38	0 / 0	0 / 0	0 / 0	0 / 0	38 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	FACTORED LC1 MAX (LC)	MAX. UNBRACED LENGTH FR-TO	MEMB. FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH FR-TO	MEMB. FORCE (LBS)
E-B	-342 / 0	0.0	0.0	0.13 (4)	7.81			
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00			
B-C	-19 / 0	-91.8	-91.8	0.22 (1)	6.25			
E-D	0 / 0	-18.5	-18.5	0.18 (4)	10.00			

TOTAL WEIGHT = 4 X 14 = 57 lb

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN./C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 088-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
 - OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/380 (0.20")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.00")  
 ALLOWABLE DEFL.(TL) = L/350 (0.20")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.22/1.00 (B-C:1), BC=0.13/1.00 (D-E:4),  
 WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP (PSI)	(DRY)	(PL)	SHEAR	SECTION
MT20	618	354	1667	788 1987 1666


PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.14 (E) (INPUT = 0.90)  
 JSI METAL = 0.09 (B) (INPUT = 1.00)



Structural component only  
 DWG# T-2007098



**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
M - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	284	0	284	0	5-8	5-8
C	63	0	63	0	1-8	1-8
D	44	0	52	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					DEAD	SCIL
		SNOW	LIVE	PERM.LIVE	WIND			
E	200	137/0	0/0	0/0	0/0	62/0	0/0	
C	46	21/0	0/0	0/0	0/0	25/0	0/0	
D	35	0/-3	0/0	0/0	0/0	37/0	0/0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (7)

MEMB.	FR-TO	CHORDS		WEBS	
		MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PL)	MAX. MEMB. FORCE (LBS)	MAX. FACTORED FORCE (LBS)
E-B		-227/0	0.0	0.0	7.81
A-B		0/28	-91.8	-91.8	10.00
B-C		-9/9	-91.8	-91.8	10.00
E-F		0/0	-18.5	-18.5	10.00
F-G		0/0	-18.5	-18.5	10.00
G-D		0/0	-18.5	-18.5	10.00

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	1-11-4	7	1	12	BACK	VERT	TOTAL		C1
G	3-11-4	1	1		BACK	VERT	TOTAL		C1

**CONNECTION REQUIREMENTS**

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN./C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

**THIS DESIGN COMPLIES WITH:**  
- PART 9 OF CBC 2018, CBC 2012, ABC 2019  
- PART 9 OF CBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")  
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")  
ALLOWABLE DEFL.(TL) = L/360 (0.20")  
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.12/1.00 (A-B:1), BC=0.14/1.00 (D-E:4),  
WB=0.00/1.00 (m/a:0), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=0.98 NAIL=0.98 LS BEND=1.10  
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.10 (E) (INPUT = 0.80)  
JSI METAL = 0.06 (E) (INPUT = 1.00)

TOTAL WEIGHT = 4 X 12 = 48 LB



Structural component only  
DWG# T-2007099



**LUMBER**

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
E - B	2x4 DRY	No.2
A - C	2x4 DRY	No.2
E - D	2x4 DRY	No.2

DRY: SEASONED LUMBER.

**PLATES (tablets in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p MT20	3.0	4.0		
E	BMV1+p MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	DESCR	SPF	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQRD BRG IN-SX
JT	VERT					
E	361		0	361	0	5-8
C	130		0	130	0	1-8
D	16		0	17	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

**UNFACTORED REACTIONS**

JT	1ST LCASE	COMBINED	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
E	250	190/0	0/0	0/0	0/0	0/0	60/0	0/0
C	90	73/0	0/0	0/0	0/0	0/0	17/0	0/0
D	12	0/0	0/0	0/0	0/0	0/0	12/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (5)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. (LC)	MEMB. UNBRAC LENGTH FR-TO	MAX. FACTORED FORCE (LBS)	MAX. (LC)	
FR-TO		FROM TO						
E-B	-342 / 0	0.0	0.0	0.01 (4)	7.81			
A-B	0 / 28	-91.8	-91.8	0.13 (5)	10.00			
B-C	-19 / 0	-91.8	-91.8	0.22 (1)	6.25			
E-D	0 / 0	-18.5	-18.5	0.02 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 10 = 38 LB

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2018, OBC 2012, ABC 2019  
- PART 9 OF OBC 2012 (2019 AMENDMENT)  
- CSA 066-09, CSA 086-14  
- TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

15% OF 31.3 P.S.F. G.S.L. PLUS 0.4 P.S.F. RAIN LOAD EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19')  
CALCULATED VERT. DEFL.(LL) = L/999 (0.00')  
ALLOWABLE DEFL.(TL) = L/360 (0.19')  
CALCULATED VERT. DEFL.(TL) = L/999 (0.00')

CSI: TC=0.22/1.00 (B-C:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SS=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


**NAIL VALUES**

PLATE GRIP (DRY) (PSI)	SHEAR (PLJ) (PLJ)	SECTION (PLJ) (PLJ)
MAX	MIN	MAX
MT20	518	354
	1987	788
		1987
		1656

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.14 (E) (INPUT = 0.90)  
JSI METAL = 0.09 (B) (INPUT = 1.00)



Structural component only  
DWG# T-2007100

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C43	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	



TOTAL WEIGHT = 4 X 7 = 28 lb

**LUMBER**  
 N. L. G. A. RULES  
 CHORDS SIZE LUMBER  
 E - B 2x4 DRY No.2  
 A - C 2x4 DRY No.2  
 E - D 2x4 DRY No.2

DRY: SEASONED LUMBER.

**PLATES (table is in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p MT20	3.0	4.0		
E	BMV1+p MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION VERT	HORIZ	MAXIMUM FACTORED GROSS REACTION DOWN	HORIZ	INPUT BRG IN-SX	RECORD BRG IN-SX
E	271	0	271	0	5-8	5-8
C	45	0	45	0	1-8	1-8
D	8	0	17	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT  
 PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS FACTORED UPLIFT

**UNFACTORED REACTIONS**

JT	1ST LCASE COMBINED	SNOW	MAX./MIN. COMPONENT REACTIONS LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	188	141/0	0/0	0/0	0/0	47/0	0/0
C	31	24/-16	0/0	0/0	0/0	7/0	0/0
D	7	0/-8	0/0	0/0	0/0	12/0	0/0

BEARING MATERIAL TO BE SFF NO.2 OR BETTER AT JOINT(S) E, C

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.  
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (5)

MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PL)	LC1	MAX	MAX.	WEBS	
						MEMB. FORCE (LBS)	MAX. FACTORED CSI (LC)
E-B	-244/0	0.0	0.0	0.04 (5)	7.81		
A-B	0/28	-91.8	-91.8	0.12 (1)	10.00		
B-C	-17/0	-91.8	-91.8	0.09 (1)	6.25		
E-D	0/0	-18.5	-18.5	0.04 (5)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

**DESIGN CRITERIA**

**SPECIFIED LOADS:**

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 38.0 PSF

SPACING = 24.0 IN./OC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF OBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
 - OVERHANG NOT TO BE ALTERED OR CUT OFF.  
 (55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")  
 CALCULATED VERT. DEFL.(LL) = L/999 (0.00")  
 ALLOWABLE DEFL.(TL) = L/360 (0.19")  
 CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.04/1.00 (D-E:5),  
 WB=0.00/1.00 (n/a:0), SS=0.09/1.00 (A-B:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00  
 AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PL)
MAX	MIN	MAX
618	354	1667
788	1987	1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.10 (E) (INPUT = 0.80)  
 JSI METAL = 0.07 (B) (INPUT = 1.00)



Structural component only  
 DWG# T-2007101



TOTAL WEIGHT = 2 X 8 = 17 lb

**LUMBER**  
 N. L. G. A. RULES  
 CHORDS SIZE LUMBER  
 E - B 2x4 DRY No.2  
 A - C 2x4 DRY No.2  
 E - D 2x4 DRY No.2  
 DRY: SEASONED LUMBER.

**PLATES (tablets in inches)**

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	254	0	254	0	5-8	5-8
C	86	0	65	0	1-8	1-8
D	23	0	25	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

**UNFACTORED REACTIONS**

JT	COMBINED	MAX/MIN COMPONENT REACTIONS					
		1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD
E	165	130/0	0/0	0/0	0/0	55/0	0/0
C	46	37/0	0/0	0/0	0/0	9/0	0/0
D	18	0/0	0/0	0/0	0/0	18/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

**BRACING**  
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.  
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.  
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

**LOADING**  
 TOTAL LOAD CASES: (5)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO		FROM TO	LENGTH	FR-TO		
E-B	-234/0	0.0	0.0 0.02 (4)	7.81		
A-B	0/28	-91.8	-91.8 0.13 (5)	10.00		
B-C	-10/0	-91.8	-91.8 0.06 (1)	10.00		
E-F	0/0	-18.5	-18.5 0.03 (4)	10.00		
F-D	0/0	-18.5	-18.5 0.03 (4)	10.00		

**FACTORED CONCENTRATED LOADS (LBS)**

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	2-0-12	1	1	---	FRONT	VERT	TOTAL	---	C1

**CONNECTION REQUIREMENTS**

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.
- CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
 TOP CH. LL = 25.6 PSF  
 DL = 6.0 PSF  
 BOT CH. LL = 0.0 PSF  
 DL = 7.4 PSF  
 TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN./C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019  
 - PART 9 OF CBC 2012 (2019 AMENDMENT)  
 - CSA 086-09, CSA 086-14  
 - TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
 - OVERHANG NOT TO BE ALTERED OR CUT OFF.  
 (55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.19")  
 CALCULATED VERT. DEFL. (LL) = L/989 (0.00")  
 ALLOWABLE DEFL. (TL) = L/360 (0.19")  
 CALCULATED VERT. DEFL. (TL) = L/999 (0.00")  
 CSI: TC=0.13/1.00 (A-B-5), BC=0.02/1.00 (D-E-4), WB=0.00/1.00 (WB:0), SSI=0.10/1.00 (A-B-5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10  
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**


PLATE	GRIP (DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.10 (E) (INPUT = 0.30)  
 JSI METAL = 0.06 (B) (INPUT = 1.00)





**LUMBER**  
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

**PLATES (table in inches)**

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+P	MT20	3.0	4.0	
E	BMV1+P	MT20	3.0	4.0	

**DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**

**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQRD BRG IN-SX
E	254	254	0	5-8
C	66	66	0	1-8
D	16	16	0	1-8

SEE MITEK STANDARD DETAIL B97781 H FOR CONNECTION TO JOINT(S) C, D

**UNFACTORED REACTIONS**

JT	1ST LCASE	MAX. MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
E	177	130 / 0	0 / 0	0 / 0	47 / 0	0 / 0
C	46	37 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

**BRACING**  
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.  
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.  
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

**LOADING**  
TOTAL LOAD CASES: (5)

MEMB.	CHORDS			WEBS		
	MAX. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 CSI (LC)	MEMB. FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. LC1 CSI (LC)
FR-TO		FROM TO	LENGTH	FR-TO		
E-B	-234 / 0	0.0	0.0 (4)	7.81		
A-B	0 / 28	-91.8	-91.8 (1)	10.00		
B-C	-10 / 0	-91.8	-91.8 (1)	10.00		
E-D	0 / 0	-18.5	-18.5 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

**DESIGN CRITERIA**

**SPECIFIED LOADS:**  
TOP CH. LL = 25.6 PSF  
DL = 6.0 PSF  
BOT CH. LL = 0.0 PSF  
DL = 7.4 PSF  
TOTAL LOAD = 39.0 PSF

**SPACING = 24.0 IN. C/C**

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:  
- PART 9 OF CBC 2018, CBC 2012, ABC 2019  
- PART 9 OF CBC 2012 (2019 AMENDMENT)  
- CSA 086-09, CSA 086-14  
- TPIC 2011, TPIC 2014

**DESIGN ASSUMPTIONS**  
- OVERHANG NOT TO BE ALTERED OR CUT OFF.  
(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.19")  
CALCULATED VERT. DEFL. (LL) = L/989 (0.00")  
ALLOWABLE DEFL. (TL) = L/360 (0.19")  
CALCULATED VERT. DEFL. (TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B-1), BC=0.02/1.00 (D-E-4), WB=0.00/1.00 (n/a.0), SS=0.09/1.00 (A-B-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

**NAIL VALUES**

PLATE	GRIP (DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.10 (E) (INPUT = 0.90)  
JSI METAL = 0.06 (B) (INPUT = 1.00)

TOTAL WEIGHT = 2 X 7 = 15 lb



Structural component only  
DWG# T-2007103



# LUL/LUS/LJS/HUS/HHUS/HGUS

## Standard and Double-Shear Joist Hangers



This product is preferable to similar connectors because of a) easier installation, b) higher capacities, c) lower installed cost, or a combination of these features.

Most hangers in this series have double-shear nailing — an innovation that distributes the load through two points on each joist nail for greater strength. This allows for fewer nails, faster installation, and the use of all common nails for the same connection. (Do not bend or remove tabs)

Double-shear hangers range from the light capacity LUS hangers to the highest capacity HGUS hangers. For medium load truss applications, the HUS offers a lower cost alternative and easier installation than the HGUS hangers, while providing greater load capacity and bearing than the LUS.

**Material:** See table on pp. 258–259.


**Finish:** Galvanized. Some products available in stainless steel or ZMAX<sup>®</sup> coating; see Corrosion Information, pp. 20–24.

**Installation:**


- Use all specified fasteners; see General Notes.
- Nails must be driven at an angle through the joist or truss into the header to achieve the tabulated resistances (except LUL).
- Where 16d commons are specified, 10d commons may be used at 0.83 of the tabulated factored resistance.
- Not designed for welded or nailer applications.
- With single ply 2x carrying members, use 10d x 1½" nails into the header and 10d commons into the joist, and reduce the resistance to 0.64 of the table value where 16d nails are specified and 0.77 where 10d nails are specified.

**Options:**


- LUS, LJS, LUL and HUS hangers cannot be modified.
- Other sizes available; consult your Simpson Strong-Tie representative.
- See Hanger Options information on p. 126.




**LUS28**




**LU26L**



**HUS210**  
(HUS26, HUS28, and HHUS similar)




**HGUS28-2**




**HHUS210-2**



Double-Shear Nailing Top View





Double-Shear Nailing Side View; Do not bend tab



Dome Double-Shear Nailing Side View (available on some models)  
U.S. Patent 5,603,580

**Typical HUS26 Installation with Reduced Heel Height**  
(Truss Designer to provide fastener quantity for connecting multiple members together)



**LJS26DS**

Plated Truss Connectors

# LUL/LUS/LJS/HUS/HHUS/HGUS

## HHUS/HGUS

See Hanger Options information on pp. 125–127.



### HHUS — Sloped and/or Skewed Seat

- HHUS hangers can be skewed to a maximum of 45° and/or sloped to a maximum of 45°
- For skew only, maximum factored down resistance is 0.85 of the table value
- For sloped only or sloped and skewed hangers, the maximum factored down resistance is 0.72 of the table value
- Uplift resistances for sloped/skewed conditions are 0.62 of the table value
- The joist must be bevel-cut to allow for double-shear nailing

### HGUS — Skewed Seat

- HGUS hangers can be skewed only to a maximum of 45°. Factored resistances are:

HGUS Seat Width	Joist	Down Resistance	Uplift
W < 2"	Bevel or square cut	0.62 of table value	0.46 of table value
2" < W < 6"	Bevel cut	0.67 of table value	0.41 of table value
2" < W < 6"	Square cut	0.46 of table value	0.41 of table value
W > 6"	Bevel cut	0.75 of table value	0.41 of table value



**Top View HHUS Hanger Skewed Right**  
(joist must be bevel cut)  
All joist nails installed on the outside angle (non-acute side).

## Standard and Double-Shear Joist Hangers (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32–34 for more information.

Plated Truss Connectors

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance			
		W	H	B	d <sub>e</sub> <sup>3</sup>	Header	Joist	D-Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K <sub>D</sub> = 1.15) lb.	(K <sub>D</sub> = 1.00) lb.	(K <sub>D</sub> = 1.15) lb.	(K <sub>D</sub> = 1.00) lb.
						kN	kN	kN	kN		
Single 2x Sizes											
LUS24	18	1 1/8	3 1/4	1 1/4	2 1/4	(4) 10d	(2) 10d	710	1625	845	1155
								3.16	7.23	2.87	5.14
LU24L	22	1 1/8	3	1 1/4	2 1/8	(4) 10d	(2) 10d x 1 1/2"	360	1020	320	725
								1.60	4.54	1.42	3.22
LU26L	22	1 1/8	5	1 1/4	4 1/4	(6) 10d	(4) 10d x 1 1/2"	720	1805	645	1140
								3.20	7.14	2.87	5.07
SS LUS26	18	1 1/8	4 1/4	1 1/4	3 1/4	(4) 10d	(4) 10d	1420	2170	1290	1630
								6.32	9.65	5.74	7.25
HUS26	16	1 1/8	5 1/4	3	3 1/8	(14) 16d	(6) 16d	2705	4940	2065	3875
								11.90	21.97	9.20	17.24
LJS26DS	18	1 1/8	5	3 1/2	4 1/4	(16) 16d	(6) 16d	2055	4265	1460	4115
								9.14	18.97	6.49	18.31
HGUS26	12	1 1/8	5 1/4	5	4 1/4	(20) 16d	(8) 16d	2685	6625	2685	5700
								11.96	29.51	11.96	25.35
LU28L	20	1 1/8	6 1/4	1 1/4	5 1/4	(8) 10d	(6) 10d x 1 1/2"	1140	2185	1020	1550
								5.07	9.72	4.54	6.89
SS LUS28	18	1 1/8	6 1/4	1 1/4	3 1/4	(6) 10d	(4) 10d	1420	2620	1290	1790
								6.32	11.21	5.74	7.96
HUS28	16	1 1/8	7 1/4	3	6 1/8	(22) 16d	(8) 16d	3605	5385	2675	4345
								16.04	23.88	11.90	19.33
HGUS28	12	1 1/8	7 1/4	5	6 1/8	(36) 16d	(12) 16d	3310	7675	3310	6900
								14.74	34.19	14.74	30.73
LU210L	20	1 1/8	8	1 1/4	7 1/4	(10) 10d	(6) 10d x 1 1/2"	1140	2495	1020	1770
								5.07	11.10	4.54	7.87
SS LUS210	18	1 1/8	7 1/4	1 1/4	3 1/4	(8) 10d	(4) 10d	1420	2785	1290	2210
								6.32	12.39	5.74	9.83

1. Factored uplift resistances have been increased 15% for wind or earthquake loading; no further increase is allowed.
2. Designer must ensure that hanger is compatible with truss when reduced heel height is used.
3. d<sub>e</sub> is the distance from the bearing seat to the top joist nail.
4. Resistances shown require a minimum 2-ply girder truss. For fastening to single-ply truss request technical bulletin T-C-N10TRSSCN and/or see installation notes.
5. Nails: 16d = 0.162" dia. x 3 1/2" long. See pp. 27–28 for other nail sizes and information.


# Face-Mount Hangers



These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32-34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance			
		W	H	B	d <sub>g</sub> <sup>2</sup>	Header	Joist	D-Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K <sub>p</sub> = 1.15)	(K <sub>p</sub> = 1.00)	(K <sub>p</sub> = 1.15)	(K <sub>p</sub> = 1.00)
		lb.	lb.	lb.	lb.			kN	kN		
<b>Double 2x Sizes</b>											
SS LUS24-2	18	3 3/8	3 3/8	2	1 1/2	(4) 16d	(2) 16d	835	2020	590	1435
								3.71	8.99	2.62	6.38
SS LUS26-2	18	3 3/8	4 1/8	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920
								7.85	11.54	6.87	8.54
HHUS26-2	14	3 3/8	5 1/8	3	3 3/8	(14) 16d	(6) 16d	2850	7335	2085	5205
								12.68	32.63	9.20	23.15
HGUS26-2	12	3 3/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3110	6355
								19.51	39.81	13.83	28.27
SS LUS28-2	18	3 3/8	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575
								7.65	14.79	6.87	11.45
HHUS28-2	14	3 3/8	7 3/8	3	6 1/8	(22) 16d	(8) 16d	3765	8940	2675	6345
								16.75	39.77	11.90	28.22
HGUS28-2	12	3 3/8	7 3/8	4	8 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215
								27.00	57.74	19.17	40.99
SS LUS210-2	18	3 3/8	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195
								11.48	20.02	10.32	14.21
HHUS210-2	14	3 3/8	9 3/8	3	8	(30) 16d	(10) 16d	4670	9660	4235	7000
								20.77	42.97	18.84	31.14
HGUS210-2	12	3 3/8	9 3/8	4	8 3/8	(46) 16d	(16) 16d	6840	14015	4855	10270
								30.43	62.34	21.60	45.69
<b>Triple 2x Sizes</b>											
HGUS26-3	12	4 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3110	6355
								19.51	39.81	13.83	28.27
HGUS28-3	12	4 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215
								27.00	57.74	19.17	40.99
HHUS210-3	14	4 1/8	9	3	7 1/8	(30) 16d	(10) 16d	4670	9670	4235	6865
								20.77	43.02	18.84	30.54
HGUS210-3	12	4 1/8	9 1/8	4	8 3/8	(46) 16d	(16) 16d	6840	14645	4855	10400
								30.43	65.14	21.60	46.26
<b>Quadruple 2x Sizes</b>											
HGUS26-4	12	6 3/8	5 7/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3110	6355
								19.51	39.81	13.83	28.27
HGUS28-4	12	6 3/8	7 3/8	4	6 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215
								27.00	57.74	19.17	40.99
HHUS210-4	14	6 1/8	8 3/8	3	7 1/8	(30) 16d	(10) 16d	4670	10155	4235	7210
								20.77	45.17	18.84	32.07
HGUS210-4	12	6 3/8	9 3/8	4	8 3/8	(46) 16d	(16) 16d	6840	14645	4855	10400
								30.43	65.14	21.60	46.26
HGUS212-4	12	6 3/8	10 3/8	4	10 3/8	(56) 16d	(20) 16d	7840	14995	5425	10645
								33.98	66.70	24.13	47.35
HGUS214-4	12	6 3/8	12 3/8	4	11 3/8	(66) 16d	(22) 16d	10130	16400	7195	11645
								45.06	72.95	32.00	51.80
<b>4x Sizes</b>											
LUS46	18	3 3/8	4 3/8	2	3 3/8	(4) 16d	(4) 16d	1720	2595	1545	1920
								7.65	11.54	6.87	8.54
HHUS46	14	3 3/8	5 3/8	3	3 3/8	(14) 16d	(6) 16d	2540	7335	2065	5205
								11.30	32.63	9.20	23.15
HGUS46	12	3 3/8	5 3/8	4	4 3/8	(20) 16d	(8) 16d	4385	8950	3110	6355
								19.51	39.81	13.83	28.27
LUS48	18	3 3/8	6 3/8	2	3 3/8	(6) 16d	(4) 16d	1720	3325	1545	2575
								7.65	14.79	6.87	11.45
HHUS48	14	3 3/8	7 3/8	3	6 1/8	(22) 16d	(8) 16d	3765	8940	2675	6345
								16.75	39.77	11.90	28.22
HGUS48	12	3 3/8	7 3/8	4	6 3/8	(36) 16d	(12) 16d	6070	12980	4310	9215
								27.00	57.74	19.17	40.99
LUS410	18	3 3/8	8 3/8	2	5 3/8	(8) 16d	(6) 16d	2580	4500	2320	3195
								11.48	20.02	10.32	14.21
HGUS410	12	3 3/8	9	4	8 3/8	(46) 16d	(16) 16d	6840	14015	4855	10270
								30.43	62.34	21.60	45.69
HGUS412	12	3 3/8	10 3/8	4	10 3/8	(56) 16d	(20) 16d	7840	14995	5425	10645
								33.98	66.70	24.13	47.35
HGUS414	12	3 3/8	12 3/8	4	11 3/8	(66) 16d	(22) 16d	10130	16400	7195	11645
								45.06	72.95	32.00	51.80



Plated Truss Connectors

See footnotes on p. 258.

# TC - Truss Connectors



The TC truss connector is an ideal connector for scissor trusses and can allow horizontal movement up to 1/4". The TC also attaches plated trusses to top plates or sill plates to resist uplift forces. Typically used on one or both ends of truss as determined by the building designer.

**Material:** 16 gauge

**Finish:** G90 galvanized


**Design:** Factored resistances are in accordance with CSA 086-14

**Installation:**


- Use all specified fasteners.
- Nails: 10d = 0.148" dia. x 3" long common wire, 10d x 1 1/2" = 0.148" dia. x 1 1/2" long.
- Drive 10d nails into the truss at the inside end of the slotted holes (inside end is towards the centre of the truss) and clinch on the back side. Do not seat these nails into the truss—allow room under the nail head for movement of the truss with respect to the wall.

**Optional TC Installation:**


- Bend one flange up 90°. Drive specified nails into the top and face of the top plates or install Titen® screws into the top and face of masonry wall. See optional load tables and installation details.




**TC24**  
U.S. Patent 4,932,173




Typical TC24 Installation



**TC26**  
(TC28 Similar)



Optional TC26 Installation for Grouted Concrete Block using a Wood Nailer (8", 10", 12" Wall Installation Similar)




Optional TC26 Installation for Grouted Concrete Block using Titen Screws

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K <sub>o</sub> =1.15)	Uplift (K <sub>o</sub> =1.15)
lb.	lb.			
TC24	(4) 10d	(4) 10d	605	430
TC26	(5) 10d	(6) 10d	1015	720
TC28	(5) 10d	(6) 10d	1015	720

**Optional TC Installation Table**

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K <sub>o</sub> =1.15)	Uplift (K <sub>o</sub> =1.15)
lb.	lb.			
TC26	(5) 10d	(6) 10d x 1 1/2"	810	680
	(5) 10d	(6) 10d	930	680

1. Factored resistances have been increased 15% for earthquake or wind loading; no further increase allowed; reduce where other loads govern.
2. Grout strength is 15 MPa minimum.
3. Optional TC26 installation with 10d nails requires minimum 3" top plate thickness.
4. TC26 fastener to grouted concrete block with (5) - 3/8" x 2 1/4" Titen screws has a factored uplift resistance of 275 lb.



(800) 999-5099  
strongtie.com

**H/TSP**

**Seismic and Hurricane Ties (cont.)**

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32-34 for more information.

Model No.	Ga.	Fasteners			Factored Resistances (K <sub>D</sub> = 1.15)										
		To Rafters/ Truss	To Plates	To Studs	D.Fir-L			S-P-F							
					Uplift	Lateral		Uplift	Lateral						
						F <sub>1</sub>	F <sub>2</sub>		F <sub>1</sub>	F <sub>2</sub>					
lb.	lb.	lb.	lb.	lb.	lb.	lb.	lb.	lb.							
kN	kN	kN	kN	kN	kN	kN	kN	kN							
H1	18	(6) 8d x 1½"	(4) 8d	—	740	685	300	680	485	215					
					3.29	3.05	1.33	3.02	2.16	0.96					
SS H2A	18	(5) 8d x 1½"	(2) 8d x 1½"	(5) 8d x 1½"	830	220	75	590	155	55					
					3.69	0.98	0.33	2.62	0.69	0.24					
SS H2.5A	18	(5) 8d	(5) 8d	—	805	160	160	755	160	160					
					3.58	0.71	0.71	3.38	0.71	0.71					
H2.5T	18	(5) 8d	(5) 8d	—	835	175	210	740	160	210					
					3.71	0.78	0.93	3.29	0.71	0.93					
SS H3	18	(4) 8d	(4) 8d	—	740	180	265	615	125	190					
					3.29	0.80	1.18	2.74	0.56	0.85					
H6	16	—	(8) 8d	(8) 8d	1585	1085	—	1125	770	—					
					7.05	4.83	—	5.00	3.43	—					
H7Z	16	(4) 8d	(2) 8d	(8) 8d	1390	670	—	990	475	—					
					6.18	2.98	—	4.40	2.11	—					
SS H8 <sup>2</sup>	18	(5) 10d x 1½"	(5) 10d x 1½"	—	1120	—	—	1025	—	—					
					4.98	—	—	4.56	—	—					
SS H10A <sup>2</sup>	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1735	795	410	1505	565	290					
					7.72	3.54	1.82	6.69	2.51	1.29					
H10AR	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1485	690	430	1220	570	305					
					6.61	3.07	1.91	5.43	2.54	1.36					
H10A-2	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1835	1275	430	1645	880	305					
					8.16	5.67	1.91	7.32	3.91	1.36					
H10S <sup>2,3</sup>	18	(8) 8d x 1½"	(8) 8d x 1½"	(8) 8d	1485	795	315	1040	565	225					
					6.52	3.54	1.40	4.63	2.51	1.00					
H11Z	18	(6) 16d x 2½"	(6) 16d x 2½"	—	1095	920	545	780	855	390					
					4.87	4.09	2.42	3.47	2.91	1.73					
H14	18	[1] (12) 8d x 1½"	(13) 8d	—	2390	855	320	1805	610	230					
					10.63	3.80	1.42	8.03	2.71	1.02					
		[2] (12) 8d x 1½"	(15) 8d	—	2390	855	320	1805	610	230					
										10.63	3.80	1.42	8.03	2.71	1.02
TSP	16	(9) 10d x 1½"	(6) 10d x 1½"	—	1295	440	—	920	310	—					
					5.76	1.96	—	4.09	1.38	—					
		(9) 10d x 1½"	(6) 10d	—	1560	440	—	1105	310	—					
										6.94	1.96	—	4.92	1.38	—

1. Factored resistances have been increased 15% for short term loading; no further increase is allowed.
2. Factored resistances are for one anchor. A minimum rafter thickness of 2½" must be used when framing anchors are installed on the same side of the plate (exception: H2.5A).
3. H8 factored uplift resistances for stud-to-bottom plate installations are 595 lb. (2.65 kN) for D.Fir-L and 390 lb. (1.74 kN) for S-P-F.
4. When cross-grain bending or cross-grain tension cannot be avoided, mechanical reinforcement to resist such forces should be considered.
5. Hurricane ties are shown installed on the outside of the wall for clarity. Installation on the inside of the wall is acceptable. For a continuous load path, connections at the top and bottom of the wall must be on the same side of the wall (see technical bulletin T-HTIECONPATH).
6. Factored resistances in the F<sub>1</sub> direction are not intended to replace diaphragm boundary members or prevent cross grain bending of the truss or rafter members. Additional shear transfer elements shall be considered where there may be effects of cross grain bending or tension.

7. H10S can have the stud offset a maximum of 1" from the rafter (centre to centre) for a reduced uplift of 1435 lb. (6.38 kN) D.Fir-L and 1015 lb. (4.51 kN) S-P-F.
8. H10S nails to plates are optional for uplift but required for lateral loads.
9. H10A may be field-bent up to a slope of 8/12. Multiply the tabulated uplift value x 0.75. Full tabulated lateral resistances apply.
10. The factored resistances of stainless-steel connectors match carbon-steel connectors when installed with Simpson Strong-Tie® stainless-steel, GCNR ring-shank nails. For more information, refer to engineering letter L-F-SSNAILS at strongtie.com.
11. D.Fir-L/S-P-F factored uplift resistances for the H2.5A fastened to a 2x4 truss bottom chord and double top plates using (5) 8d x 1½" nails into the top plates and (3) 8d x 1½" nails into the lowest three flange holes into the truss bottom chord is 495 lb. (2.20 kN).
12. Nails: 16d x 2½" = 0.162" dia. x 2½" long, 10d = 0.148" dia. x 3" long, 10d x 1½" = 0.148" dia. x 1½" long, 8d = 0.131" dia. x 2½" long, 8d x 1½" = 0.131" dia. x 1½" long. See pp. 27-28 for other nail sizes and information.

**Straps and Ties**

C-C-CAN2018 ©2017 SIMPSON STRONG-TIE COMPANY INC.



**BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY**

B97791H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177
COMMON SPIRAL	3.00	0.122	97	108
	3.25	0.122	97	108
	3.50	0.152	145	162

**NOTES:**

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for one toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor  $J_A$  in CSA O86-14, section 12.9.4.1.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: G = 0.42 (SPF), G = 0.49 (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to wind the nail lateral capacity in this table may be multiplied by 1.15 ( $K_D$  factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-14, section 12.9.4
10. This design is not valid after March 31, 2021.



**TOE-NAIL INSTALLATION**

Nail type	Common wire	Common spiral	Common wire	Common spiral
Nail dia. (in)	0.160	0.152	0.144	0.122
	( 3.5" nail )		( 3" and 3.25" nail )	
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS			
2X4 SPF	2	2	3	3
2X4 D. Fir	2	2	2	2
2X6 SPF	4	4	4	5
2X6 D. Fir	3	3	3	4

**MiTek**® MiTek Canada Inc  
 100 Industrial Rd.  
 Bradford, Ontario L3Z 3G7



December 2, 2019.

# BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B97791H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON	3.00	0.144	30	42
	3.25	0.144	32	45
WIRE	3.50	0.160	38	52
COMMON	3.00	0.122	26	36
	3.25	0.122	28	40
SPIRAL	3.50	0.152	36	50

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



**NOTES:**

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to wind or earthquake load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for one toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor  $J_A$  in CSA O86-14, section 12.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities:  $G = 0.42$ (SPF),  $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry ( < 19% moisture content ) at the time of nail installation.
8. Nail values in this table comply with CSA O86-14, section 12.9.5
9. This design is not valid after March 31, 2021.


**Toe-nailing on 2x6 Bearing Plate**



**Toe-nailing on 2x4 Bearing Plate**



PEO  
Certificate No. 10889486



**MiTek**® MiTek Canada Inc  
100 Industrial Rd.  
Bradford, Ontario L3Z 3G7


December 2, 2019

## Symbols

### PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths or mm. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- $\frac{1}{8}$ " from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

\*Plate location details available in MiTek software or upon request.

### PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

### LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

### BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.


### Industry Standards:

- TPIC: Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses  
 DSB-89: Design Standard for Bracing.  
 BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

## Numbering System



dimensions shown in ft-in-sixteenths or mm (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

### PRODUCT CODE APPROVALS

CCMC Reports:

11996-L, 10319-L, 13270-L, 12691-R

© 2007 MiTek® All Rights Reserved

**MI**  
**MiTek**

POWER TO PERFORM.™

MiTek Engineering Reference Sheet: MI-7473C rev. 10-08



## General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

- Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
- Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
- Never exceed the design loading shown and never stack materials on inadequately braced trusses.
- Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
- Cut members to bear tightly against each other.
- Place plates on each face of truss at each joint and embed fully. Knots and wane of joint locations are regulated by TPIC.
- Design assumes trusses will be suitably protected from the environment in accord with TPIC.
- Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
- Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
- Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
- Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
- Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
- Top chords must be sheathed or purlins provided at spacing indicated on design.
- Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
- Connections not shown are the responsibility of others.
- Do not cut or alter truss member or plate without prior approval of an engineer.
- Install and load vertically unless indicated otherwise.
- Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
- Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
- Design assumes manufacture in accordance with TPIC Quality Criteria.




Overview:

Where piggybacks are connected ovetop of base trusses, 2x4 purlins must be first added to the flat portion of the base truss at a spacing no more than 24" o/c. These purlins not only provide support for the piggyback trusses above, but are required to laterally support the top chord of the base truss which will not have the sheathing directly connected to the flat portion of the base truss. This ensures the top chord, most often in compression, will not buckle laterally.

Further, the purlins in the plane of the flat portion require diagonal bracing to prevent lateral displacement of the purlins themselves where under certain conditions, the trusses may in fact all buckle in the same direction if this additional bracing is not added in the plane of the purlins.

Detail:




NOTE: THE SLOPED PORTION OF THE TOP CHORD OF THE BASE TRUSS AND PIGGYBACK TRUSS IN THIS SKETCH IS ASSUMED TO BE SHEATHED IN ACCORDANCE WITH THE OBC.

SKETCH FROM BCSI-CANADA 2013

Disclaimer:

OWTFA Tech Notes are intended to provide guidance to the design community both within the membership as well as to third party designers who might benefit from the information. The details have been developed by the OWTFA technical committee and although there may be professional engineers involved in development, the information contained in the tech-note are not intended to be used without having a professional engineer review the information for a specific application. The OWTFA takes no responsibility with respect to the information provided but has developed this tech-note to offer guidance where it is not currently readily available.



## Alves Engineering Services Inc.

5208 Easton road  
Burlington, Ontario L7L 6N6  
(289) 259 5455

### RESPONSABILITIES

- 1-Alves Engineering Services Inc. is responsible for the design of trusses as individual components
- 2-It is the responsibility of others to ascertain that the design loads utilized on this drawing meet or exceed the actual dead load imposed by the structure and the live load imposed by the local building code or the authorities having jurisdictions.
- 3- All dimensions are to be verified by owner, contractor, architect or other authority before manufacture.
- 4- Alves Engineering Services Inc. bears no responsibility for the erection of the trusses. Persons erecting trusses are cautioned to seek professional advice regarding temporary and permanent bracing system. Bracing shown on Alves Engineering Services Inc. drawings is specified for the truss as a single component and forms an integral part of the truss design, but is not meant to represent the only required bracing for that truss when trusses are installed in a series of trusses forming a roof truss system.
- 5- It is the manufactures responsibility to ensure that the trusses are manufactured in conformance with Alves Engineering Services Inc. specifications outlined below.

### SPECIFICATIONS

- 1-Truss components sealed by Alves Engineering Services Inc. conform to the relevant sections of the current Building Code of Ontario and Canada (part 4 or part 9) or the current Canadian code for Farm Buildings in accordance with the application specified on the sealed truss component drawing. All truss component design procedures must conform to the current design standard issued by the truss plate institute of Canada (TPIC). All lumber and nailing stresses to conform to the current CSA wood design standard identified on the current Building Code and TPIC.
- 2- Lumber is to be the sizes and grade specified on the truss drawing.
- 3- Moist content of lumber is not to exceed 19% in service unless otherwise specified.
- 4- Plates shall be applied to both faces of the each truss joint and shall be positioned as shown on the truss drawings
- 5- Lumber used on manufacture of trusses is not to be treated with chemicals unless otherwise specified on the truss drawings.
- 6- The top chord is assumed to be continuously laterally braced by the roof sheathing or purlins at intervals specified on the truss drawing but not exceeding 24" c/c for (part 9) and not exceeding 48" for (part 4 or farm design)
- 7- When rigid ceiling is not attached directly to the bottom chord, lateral bracing is required and it should not exceed more than 3m or 10' intervals.
- 8-Refer to Mitek sheet M117473C REV.10-08 attached for information on symbols, numbering system and General Safety notes.

F-1800219

Feb 09, 2018