




Hanger Name	Symbol	QTY
LUS24	▲	8
	■	0
	●	0
LUS26-2	◆	3
	△	0
	□	0
	◡	0
	○	0

JOB INFORMATION

Customer	GREENPARK HOMES
Job #	22-00194R0
Address	ZADORRA PENROSE 1-2 OSHAWA, ON
Model	PENROSE 1-2
Sales Rep	RALPH MIRIGELLO
Designer	BB
Date	5/31/2022
Path	S:\DESIGN\KLU\CUSTOMERS\GREENPARK\ZADORRA ESTATES\MODELS\PENROSE 1\PENROSE 1-2\T

DESIGN INFORMATION

Code	NBCC 2015
Bldg	Residential - HSB (NBCC Part 9)
TC LL	34.8 lb/ft ²
TC DL	3.0 lb/ft ²
BC LL	0.0 lb/ft ²
BC DL	7.3 lb/ft ²
Deflection	LL=L/360 TL=L/360
Spacing	24" O/C unless otherwise noted
Complies With	OBC 2012 (2019 Amendment) CSA O86-14 and TPIC 2014

IMPORTANT INFORMATION

Hangers and Fasteners to be installed as per manufacturer

Refer to truss drawings in the Truss Engineering Package for ply-to-ply attachment notes

For site-framed valleys: top chords of all roof trusses must be laterally supported using 2x4 continuous bracing @24 O/C - all bracing must be anchored at ends as per TPIC Installation Guidelines

Read all notes on this page in addition to those shown on the KOTT Truss Engineering package

Field erection, handling and bracing are not the responsibility of KOTT, or KOTT Engineering

Unless noted otherwise, hurricane ties are to be installed at the bearings of all trusses > 40 ft clear span, and any girder or beam supporting trusses with a clear span >40 ft. See hanger legend for type.

Unless noted otherwise, for Part 9 bldgs, all trusses are to be anchored to the top of supporting walls as follows: trusses with a clear span <40 ft use 3-1/4" nails @ each bearing; trusses with a clear span >40 ft use 3-1/4" nails @ each bearing in addition to the appropriate hurricane tie.



CONVENTIONAL FRAMING BY OTHERS

ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 OF THE OBC. ROOF RAFTERS THAT CROSS OVER TRUSSES TO BE MIN. 2x4 SPF @ 24" C/C WITH A 2x4 VERTICAL POST TO THE TRUSS BELOW. VERTICAL POSTS TO BE Laterally BRACED SO THAT UNBRACED LENGTH DOES NOT EXCEED 6'. DESIGN OF CONVENTIONAL FRAMING IS THE RESPONSIBILITY OF THE PROJECT ENGINEER.

KOTT Inc.
14 Anderson Blvd.
Uxbridge, ON
905.642.4400



ENGINEERING NO. (NP-1)
PLEASE READ PRIOR TO INSTALLATION

TRUE COPY
OF PERMIT PLANS
Dec 06 2023

CHIEF BUILDING OFFICIAL

MHP 23018

RESPONSIBILITIES

THIS DESIGN IS FOR AN INDIVIDUAL BUILDING COMPONENT AND HAS BEEN BASED ON INFORMATION PROVIDED BY KOTT DESIGN. THE UNDERSIGNED ENGINEER DISCLAIMS ANY RESPONSIBILITY FOR DAMAGES AS A RESULT OF FAULTY OR INCORRECT INFORMATION, SPECIFICATION AND/OR DESIGNS FURNISHED TO THE ENGINEER. THE UNDERSIGNED ENGINEER IS ONLY RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THIS BUILDING COMPONENT FOR THE CONDITIONS AND LOADS SHOWN ON THIS DRAWING. THE STRUCTURAL INTEGRITY OF THE BUILDING AND THE VERIFICATION OF THE DIMENSIONS AND THE DESIGN LOADS USED ARE THE RESPONSIBILITY OF THE BUILDING DESIGNER.

TRUSSES ARE DESIGNED IN CONFORMANCE WITH THE RELEVANT SECTIONS OF THE NATIONAL BUILDING CODE OF CANADA OR THE CANADIAN CODE FOR FARM BUILDINGS, WHICHEVER APPLIES TO THE BUILDING TYPE INDICATED ON THE DRAWING

IT IS THE RESPONSIBILITY OF KOTT TO ENSURE THAT TRUSSES ARE MANUFACTURED IN CONFORMANCE WITH THESE DESIGNS AND WITH THE SPECIFICATIONS OUTLINED BELOW. THE UNDERSIGNED ENGINEER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

USE AND OCCUPANCY

- The building is of the type indicated on the drawing

LOADING

- The truss loading intensity and distribution as well as load transfer mechanism is that indicated on the drawing
- No buildings, trees, parapets or other projections higher than the roof for which the trusses are used are located within a distance less than ten (10) times the difference in height, or five metres (16 ft) whichever is greater, unless the drawing indicates that the snow drifting has been taken into account

HANDLING, INSTALLATION AND BRACING

- The trusses must be handled and installed by a qualified professional as per the supplied document titled *Information for Truss Installers* and the BCSI-B1 and BCSI-B3 Summary Sheets
- The compression chords are laterally braced by continuous rigid diaphragm sheathing or as specified on the drawing
- Temporary and permanent bracing must be installed as indicated on the truss drawing and according to the BCSI-B1 and BCSI-B3 Summary Sheets. Bracing for the lateral stability of the truss is to be provided by the building designer
- It is recommended that a Professional Engineer's advice be obtained for the bracing of trusses spanning more than 12.37m (40'-7")**


SUPPORTS

- The trusses are to be supported at the bearing points indicated and anchored to the supports where considered necessary by the designer of the overall structure
- Bearing sizes shown are the minimum required to prevent crushing of the truss members and do not necessarily take into account stability of the overall building structure
- Elevation of bearings must be carefully checked and shimmed to alignment for solid bearings
- Adequate wood truss bearing is the responsibility of the building designer.

DIMENSIONS

- Geometry of the truss and dimensions indicated on the drawing are identical to those of the installed truss.



**LUMBER****N. L. G. A. RULES**

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - G	2x4	DRY	2100F 1.8E
G - J	2x4	DRY	2100F 1.8E
J - M	2x4	DRY	No.2
X - B	2x6	DRY	No.2
N - L	2x6	DRY	No.2
X - S	2x6	DRY	2100F 1.8E
S - N	2x6	DRY	2100F 1.8E

ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
B - W	2x4	DRY	No.2	SPF
O - L	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWV-t	MT20	6.0	8.0	2.50	3.75
C	TMWV-t	MT20	4.0	4.0	1.75	1.75
D	TTWW-m	MT20	6.0	10.0	1.75	4.50
E	TMWV-t	MT20	4.0	4.0	1.50	1.75
F	TMWV-t	MT20	3.0	4.0		
G	TSW-I	MT20	5.0	10.0	Edge	5.00
H						
I	TMWV-t	MT20	4.0	4.0	1.50	2.00
J	TTWW-m	MT20	6.0	10.0	1.75	4.50
K	TMWV-t	MT20	4.0	4.0	1.75	1.75
L	TMWV-t	MT20	6.0	8.0	2.50	3.75
N	BMV1+p	MT20	3.0	5.0	2.75	1.50
O	BMWV-t	MT20	4.0	10.0	2.00	3.00
P	BMWV-t	MT20	4.0	4.0		
Q	BMWV-t	MT20	5.0	5.0	1.75	1.75
R	BMWV-t	MT20	5.0	6.0	2.50	1.50
S	BS-t	MT18HS	5.0	12.0		
T	BMWV-t	MT20	4.0	4.0	1.75	1.75
U	BMWV-t	MT20	5.0	5.0	1.75	1.75
V	BMWV-t	MT20	4.0	4.0		
W	BMWV-t	MT20	4.0	10.0	2.00	3.00
X	BMV1+p	MT20	3.0	5.0	2.75	1.50

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY**BUILDING DESIGNER****BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	UPLIFT
X	3823	0	3823	0
N	3823	0	3823	0

UNFACTORED REACTIONS

	1ST LCASE	MAX/MIN.	COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE
X	2648	2050 / 0	0 / 0
N	2648	2050 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) X, N.
BEARING SIZE FACTOR = 1.15 AT JNT(S) X, N (BASED ON SUPPORT DEPTH = 1-8)**BRACING**TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.40 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LBS)
FR-TO			FROM	TO		FR-TO			
A-B	0 / 34	-111.9	-111.9	0.16 (1)	10.00	W-C	-1202 / 0	0.21 (1)	
B-C	-5054 / 0	-111.9	-111.9	0.51 (1)	2.69	C-V	0 / 793	0.20 (1)	
C-D	-5784 / 0	-111.9	-111.9	0.58 (1)	2.40	V-D	-221 / 78	0.06 (1)	
D-E	-6988 / 0	-210.9	-210.9	0.55 (1)	2.89	D-U	0 / 2594	0.64 (1)	
E-F	-7851 / 0	-210.9	-210.9	0.61 (1)	2.65	U-E	-1751 / 0	0.45 (1)	
F-G	-7825 / 0	-210.9	-210.9	0.53 (1)	2.76	E-T	0 / 1238	0.31 (1)	
G-H	-7825 / 0	-210.9	-210.9	0.53 (1)	2.76	T-F	-738 / 0	0.19 (1)	
H-I	-7825 / 0	-210.9	-210.9	0.62 (1)	2.65	F-R	-38 / 0	0.02 (1)	
I-J	-6994 / 0	-210.9	-210.9	0.56 (1)	2.88	R-H	-747 / 0	0.19 (1)	
J-K	-5783 / 0	-111.9	-111.9	0.58 (1)	2.40	H-I	0 / 1191	0.29 (1)	
K-L	-5054 / 0	-111.9	-111.9	0.51 (1)	2.69	Q-I	-1726 / 0	0.45 (1)	
L-M	0 / 34	-111.9	-111.9	0.16 (1)	10.00	Q-J	0 / 2604	0.64 (1)	
X-B	-3696 / 0	0.0	0.0	0.26 (1)	5.51	P-K	-228 / 77	0.06 (1)	
N-L	-3696 / 0	0.0	0.0	0.26 (1)	5.51	P-K	0 / 791	0.20 (1)	
X-W	0 / 0	-34.4	-34.4	0.09 (1)	10.00	O-K	-1200 / 0	0.21 (1)	
W-V	0 / 4530	-34.4	-34.4	0.33 (1)	10.00	B-W	0 / 4669	0.83 (1)	
V-U	0 / 5151	-34.4	-34.4	0.31 (1)	10.00	O-L	0 / 4669	0.83 (1)	
U-T	0 / 6988	-34.4	-34.4	0.43 (1)	10.00				
T-S	0 / 7851	-34.4	-34.4	0.49 (1)	10.00				
S-R	0 / 7851	-34.4	-34.4	0.49 (1)	10.00				
R-Q	0 / 6994	-34.4	-34.4	0.44 (1)	10.00				
Q-P	0 / 5150	-34.4	-34.4	0.30 (1)	10.00				
P-O	0 / 4530	-34.4	-34.4	0.33 (1)	10.00				
O-N	0 / 0	-34.4	-34.4	0.09 (1)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR	TYPE	HEEL	CONN.
D	6-0-0	-503	-503	—	FRONT	VERT	TOTAL	—	C1
J	24-8-0	-503	-503	—	FRONT	VERT	TOTAL	—	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	34.8	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 6-0-0
END SETBACK = 6-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL. LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.02")
CALCULATED VERT. DEFL. (LL) = L/999 (0.35")
ALLOWABLE DEFL. (TL) = L/360 (1.02")
CALCULATED VERT. DEFL. (TL) = L/645 (0.57")CSI: TC=0.62/1.00 (H-I-1), BC=0.49/1.00 (R-T-1),
WB=0.83/1.00 (L-O-1), SSI=0.41/1.00 (I-J-1)DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE	GRIP (DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)	
	MAX	MIN	MAX	MIN
MT20	650	371	1747	788
MT18HS	586	403	2455	1382
			3163	3004

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (Q) (INPUT = 0.90)
JSI METAL= 0.99 (S) (INPUT = 1.00)

CONTINUED ON PAGE 2




July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	G01	TRUSS DESC.	

PER: 
CHIEF BUILDING OFFICIAL

Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:51:57 2022 Page 2
ID:OzM1q?scz2BChOKfHahjdLzPugE-hftwuGbikaa54ijYGQc8_EG5RsY8nSn2K37BHyySk0

MHP 23018

WB - INDICATES BLOCKING REQUIRED



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	G05	TRUSS DESC.	

TRUE COPY
OF QUANTITY PLANS
Dec 06 2023

PER: 
CHIEF BUILDING OFFICIAL

Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:51:58 2022 Page 2
ID:OzM1q?scz2BChOKfHahjdLzPugE-9sOF7EHDT2IRJEHv6zrgBnQ3qADtCcxH_ogikyysK?

MHP 23018

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN
THE TRUSS MANUFACTURING PLANT .

NAIL VALUES		PLATE GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
		MAX	MIN	MAX	MIN	MAX	MIN
MT20		650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (Y) (INPUT = 0.90)


JSI METAL= 1.00 (K) (INPUT = 1.00)



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 71 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
L - B	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	

ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					

ALL GABLE WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	5.0	1.25	2.00
C	TMVW-t	MT20	3.0	5.0	1.50	1.75
D	TTW+p	MT20	3.0	5.0	2.75	1.50
E	TMVW-t	MT20	3.0	5.0	1.50	1.75
F	TMVW+p	MT20	4.0	5.0	1.25	2.00
H	BMV1+p	MT20	2.0	4.0	0.25	1.00
I	BMVW-t	MT20	3.0	5.0		
J	BBWWW-p	MT20	5.0	6.0	2.75	3.00
K	BMVW-t	MT20	3.0	5.0		
L	BMV1+p	MT20	2.0	4.0	0.25	1.00
M, N, O, P, Q, R, S, T						
M	NP+w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED	MAXIMUM FACTORED	INPUT	REQRD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	UP
L	921	0	921	0
H	921	0	921	0

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN.	COMPONENT REACTIONS	
	COMBINED	SNOW	LIVE	PERM. LIVE
L	636	506 / 0	0 / 0	0 / 0
H	636	506 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX	MEMB.	WEBS	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX
		FORCE	(PLF)							FORCE	(PLF)				
FR-TO		(LBS)		FROM	TO	CS	CS	FR-TO		(LBS)		FROM	TO	CS	CS
A-B		0 / 60	-111.9	-111.9	0.16 (1)	10.00	10.00	J-D		0 / 925	0.21 (1)				
B-C		-827 / 0	-111.9	-111.9	0.12 (1)	6.25	6.25	J-E		-61 / 0	0.01 (1)				
C-D		-797 / 0	-111.9	-111.9	0.12 (1)	6.25	6.25	I-E		-313 / 0	0.07 (1)				
D-E		-797 / 0	-111.9	-111.9	0.12 (1)	6.25	6.25	C-J		-61 / 0	0.01 (1)				
E-F		-827 / 0	-111.9	-111.9	0.12 (1)	6.25	6.25	K-C		-313 / 0	0.07 (1)				
F-G		0 / 60	-111.9	-111.9	0.16 (1)	10.00	10.00	B-K		0 / 557	0.13 (1)				
L-B		-897 / 0	0.0	0.0	0.12 (1)	7.81	7.81	I-F		0 / 557	0.13 (1)				
H-F		-897 / 0	0.0	0.0	0.12 (1)	7.81	7.81								
L-K		0 / 4	-18.2	-18.2	0.04 (4)	10.00	10.00								
K-J		0 / 692	-18.2	-18.2	0.13 (1)	10.00	10.00								
J-I		0 / 692	-18.2	-18.2	0.13 (1)	10.00	10.00								
I-H		0 / 4	-18.2	-18.2	0.04 (4)	10.00	10.00								

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	34.8	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL)= L/360 (0.39")
CALCULATED VERT. DEFL. (LL) = L/999 (0.03")
ALLOWABLE DEFL. (TL)= L/360 (0.39")
CALCULATED VERT. DEFL. (TL) = L/999 (0.04")

CSI: TC=0.16/1.00 (F-G-1), BC=0.13/1.00 (J-K-1),
WB=0.21/1.00 (D-J-1), SSI=0.10/1.00 (E-F-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747
			788
			1987
			1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (D) (INPUT = 0.90)


JSI METAL= 0.48 (H) (INPUT = 1.00)



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = $2 \times 10 = 20$ lb

LUMBER

N. L. G. A. RULES		LUMBER		DESCR	
CHORDS	SIZE				
E - B	2x4	DRY	No.2		SPF
A - C	2x4	DRY	No.2		SPF
E - D	2x4	DRY	No.2		SPF

DRY-SEASONED LUMBER

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BUILDING BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	454	0	454	0	0	5-8	1-8
C	169	0	169	0	0	1-8	1-8
D	16	0	18	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX/MIN. COMPONENT REACTIONS					SOIL
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	
E	309	270 / 0	0 / 0	0 / 0	0 / 0	39 / 0	0 / 0
C	114	105 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY
APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LOAD (LC)	MAX. UNBRAC. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LOAD (LC)
FR-TO		FROM TO		LENGTH	FR-TO		
E-B	-434 / 0	0.0	0.0	0.01 (4)			
A-B	0 / 34	-111.9	-111.9	0.15 (1)			
B-C	-25 / 0	-111.9	-111.9	0.31 (1)			
E-D	0 / 0	-18.2	-18.2	0.02 (4)			

DESIGN CRITERIA

SPECIFIED LOADS:				
TOP	CH.	LL =	34.8	PSF
		DL =	3.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.3	PSF
TOTAL LOAD		=	45.1	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

DESIGN ASSUMPTIONS
-OVERHANG NOT TO BE ALTERED OR CUT
OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.31/1.00 (B-C:1) , BC=0.02/1.00 (D-E:4) ,
WB=0.00/1.00 (n/a:0) , SSI=0.20/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.24 (B) (INPUT = 0.90)
JSI METAL= 0.18 (B) (INPUT = 1.00)



July 14, 2022

**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	J02	TRUSS DESC.	


TRUE COPY

OF QUANTITY PLANS

Dec 06 2023

PER: *C. M. M.*
CHIEF BUILDING OFFICIALVersion 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:00 2022 Page 1
ID: OzM1q?scz2BChOKfHahjdLzPugE-5EW?YwIU_fy9yYRIEOzJlcsuie_eLK4EkIHnccysJz
Scale = 1:18.1

MHP 23018



TOTAL WEIGHT = 2 X 7 = 15 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0	
E	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNERBEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
E	314	0	314	0
C	86	0	86	0
D	16	0	16	0

SEE MITTEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN.	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	215	183 / 0	0 / 0	0 / 0	0 / 0	0 / 0	32 / 0	0 / 0
C	58	54 / 0	0 / 0	0 / 0	0 / 0	0 / 0	5 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACINGTOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS1 (LC)	MAX. UNBRACED LENGTH	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
FR-TO						FR-TO			
E-B	-294 / 0	0.0	0.0	0.01 (4)	7.81				
A-B	0 / 34	-111.9	-111.9	0.15 (1)	10.00				
B-C	-12 / 0	-111.9	-111.9	0.08 (1)	6.25				
E-D	0 / 0	-18.2	-18.2	0.02 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGNPATTERN-LOADING CHECK APPLIED TO THIS TRUSS.DESIGN CRITERIASPECIFIED LOADS:

TOP CH.	LL	=	34.8	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.00")CSI: TC=0.15/1.00 (A-B:1), BC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.11/1.00 (A-B:1)DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL= 0.12 (B) (INPUT = 1.00)


July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




CORPORATION OF THE CITY OF OSHAWA
TRUE COPY
OF QUANTITY PLANS
Dec 06 2023
PER: 
CHIEF BUILDING OFFICIAL

Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:01 2022 Page 1
ID:OzM1q?scz2BChOKfHahjdLzPugE-ZR4OmGJ6lz40ai?Un6VYlqP3S2l14nKNzy1KJ2yysJy
Scale = 1:18.1




TOTAL WEIGHT = $2 \times 12 = 24$ lb

JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL= 0.12 (B) (INPUT = 1.00)



**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**





TOTAL WEIGHT = 2 X 15 = 29 lb

LUMBER

N. L. G. A. RULES
CHORDS SIZE
E - B 2x4 DRY No.2
A - C 2x4 DRY No.2
E - D 2x4 DRY No.2

DRY: SEASONED LUMBER.

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG UPLIFT IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	498	0	498	0	5-8	1-8
C	169	0	169	0	1-8	1-8
D	45	0	51	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE		MAX / MIN		COMPONENT REACTIONS		DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	WIND		
E	345	270 / 0	0 / 0	0 / 0	0 / 0	75 / 0	0 / 0	0 / 0
C	114	105 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. CS1 (LC)	MAX. UNBRACED LENGTH FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)	MAX. UNBRACED LENGTH FR-TO
FR-TO								
E-B	-434 / 0	0.0	0.0 0.13 (4)	7.81				
A-B	0 / 34	-111.9	-111.9 0.15 (1)	10.00				
B-C	-25 / 0	-111.9	-111.9 0.31 (1)	6.25				
E-D	0 / 0	-18.2	-18.2 0.13 (4)	10.00				

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH. LL = 34.8 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 45.1 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.03")

CSI: $TC=0.31/1.00$ (B-C:1), $BC=0.13/1.00$ (D-E:4),
 $WB=0.00/1.00$ (n/a:0), $SSI=0.20/1.00$ (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.24 (B) (INPUT = 0.90)
JSI METAL= 0.18 (B) (INPUT = 1.00)



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	J05	TRUSS DESC.	

TRUE COPY
OF QUANTITY PLANS
Dec 06 2023
PER: *C. Mata*
CHIEF BUILDING OFFICIAL

Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:02 2022 Page 1
ID: OzM1q?scz2BChOKfHahjdLzPugE-1demzbbKkWHctBsagLp0nr1y6lSeGpEaWBcmurVyyJx
Scale = 1:32.8

MHP 23018



TOTAL WEIGHT = 11 X 17 = 188 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ
E	636	0	636	0
C	252	0	252	0
D	45	0	51	0

SEE MITTEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN.	COMPONENT REACTIONS	WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE		
E	437	355 / 0	0 / 0	0 / 0	82 / 0	0 / 0
C	170	157 / 0	0 / 0	0 / 0	14 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS1 (LC)	MAX. UNBRACED LENGTH	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
FR-TO						FR-TO			
E-B		-571 / 0	0.0	0.0	0.13 (4)	7.81			
A-B		0 / 34	-111.9	-111.9	0.15 (1)	10.00			
B-C		-38 / 0	-111.9	-111.9	0.69 (1)	6.25			
E-D		0 / 0	-18.2	-18.2	0.13 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	34.8	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.03")

CSI: TC=0.69/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.29/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.32 (B) (INPUT = 0.90)
JSI METAL= 0.24 (B) (INPUT = 1.00)



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 2 X 8 = 16 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.	SPF
E - B	2x4	DRY	No.2			
A - C	2x4	DRY	No.2			
E - D	2x4	DRY	No.2			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION VERT	HORZ	MAXIMUM FACTORED GROSS REACTION DOWN	HORZ	INPUT UPLIFT IN-SX	REQD BRG IN-SX
E	313	0	313	0	5-8	1-8
C	85	0	85	0	1-8	1-8
D	17	0	18	0	1-8	1-8

SEE MITTEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN.	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	214	182 / 0	0 / 0	0 / 0	0 / 0	0 / 0	32 / 0	0 / 0
C	57	53 / 0	0 / 0	0 / 0	0 / 0	0 / 0	5 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CS1 (LC)	MAX. UNBRAC LENGTH	MEMB.	WEBS MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
FR-TO						FR-TO		
E-B	-293 / 0	0.0	0.0	0.01 (4)	7.81			
A-B	0 / 43	-111.9	-111.9	0.15 (1)	10.00			
B-C	-15 / 0	-111.9	-111.9	0.07 (1)	6.25			
E-D	0 / 0	-18.2	-18.2	0.02 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGNPATTERN-LOADING CHECK APPLIED TO THIS TRUSS.**DESIGN CRITERIA****SPECIFIED LOADS:**

TOP CH.	LL =	34.8	PSF
DL =	3.0	PSF	
BOT CH.	LL =	0.0	PSF
DL =	7.3	PSF	
TOTAL LOAD	=	45.1	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.00")

CSI: TC=0.15/1.00 (A-B:1), BC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.10/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.18 (B) (INPUT = 0.90)
JSI METAL= 0.15 (B) (INPUT = 1.00)



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 5 X 10 = 52 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0	
E	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
E	315	0	315	0
C	85	0	85	0
D	17	0	17	0

SEE MITTEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX	MIN	COMPONENT REACTIONS
	COMBINED	SNOW	LIVE	PERM. LIVE
E	215	184 / 0	0 / 0	0 / 0
C	57	53 / 0	0 / 0	0 / 0
D	14	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED HORIZ. LOAD (LC1)	MAX. FACTORED UNBRACED LENGTH (LC)	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (LC)
FR-TO						FR-TO			
E-B		-296 / 0	0.0	0.0	0.01 (4)	7.81			
A-B		0 / 60	-111.9	-111.9	0.16 (1)	10.00			
B-C		-20 / 0	-111.9	-111.9	0.07 (1)	6.25			
E-D		0 / 0	-18.2	-18.2	0.02 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGNPATTERN-LOADING CHECK APPLIED TO THIS TRUSS.**DESIGN CRITERIA****SPECIFIED LOADS:**

TOP CH.	LL	=	34.8	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.19")

CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")

ALLOWABLE DEFL. (TL) = $L/360$ (0.19")

CALCULATED VERT. DEFL. (TL) = $L/999$ (0.00")

CSI: TC=0.16/1.00 (A-B:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.08/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.24 (B) (INPUT = 0.90)


JSI METAL= 0.15 (B) (INPUT = 1.00)



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 126 lb

LUMBER

N. L. G. A. RULES			LUMBER	DESCR
A	D	SIZE		
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
G - J	2x4	DRY	No.2	SPF
S - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
S - O	2x4	DRY	No.2	SPF
O - K	2x4	DRY	No.2	SPF

ALL WEBS EXCEPT	2x3	DRY
--------------------	-----	-----

DRY; SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWw-t	MT20	5.0	6.0	1.50	2.75
C	TMWw-t	MT20	3.0	4.0	1.50	1.75
D	TTWw+m	MT20	6.0	6.0	2.50	2.00
E	TMWw	MT20	2.0	4.0		
F	TMWw-t	MT20	3.0	4.0		
G	TTWw+m	MT20	6.0	6.0	2.50	2.00
H	TMWw-t	MT20	3.0	4.0	1.50	1.75
I	TMW-t	MT20	5.0	6.0	1.50	2.75
K	BMW1+p	MT20	3.0	4.0		
L	BMWw-t	MT20	4.0	6.0	1.50	2.00
M	BMWw-t	MT20	3.0	4.0		
N	BMWw-t	MT20	4.0	4.0	2.00	1.75
O	BS-t	MT20	3.0	8.0		
P	BMWwWw-t	MT20	4.0	6.0	1.75	2.00
Q	BMWw-t	MT20	3.0	4.0		
R	BMWw-t	MT20	4.0	6.0	1.50	2.00
S	BMW1+n	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
JT							
S	2147	0	2147	0	0	5-8	3-8
K	2147	0	2147	0	0	5-8	3-8

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
S	1485	1161/0	0/0	0/0	0/0	324/0	0/0
K	1485	1161/0	0/0	0/0	0/0	324/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.59 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY
APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED MAX CSI (LC)		
FR-TO		FROM TO			FR-TO				
A-B	0 / 34	-111.9	-111.9	0.15 (1)	10.00	R-C	-461 / 0	0.09 (1)	
B-C	-2775 / 0	-111.9	-111.9	0.30 (1)	3.92	C-Q	-88 / 0	0.04 (1)	
C-D	-2741 / 0	-111.9	-111.9	0.29 (1)	3.95	Q-D	0 / 146	0.03 (4)	
D-E	-3115 / 0	-111.9	-111.9	0.43 (1)	3.59	D-P	0 / 959	0.22 (1)	
E-F	-3115 / 0	-111.9	-111.9	0.40 (1)	3.63	P-E	-589 / 0	0.23 (1)	
F-G	-3117 / 0	-111.9	-111.9	0.43 (1)	3.59	P-F	-3 / 0	0.00 (1)	
G-H	-2740 / 0	-111.9	-111.9	0.29 (1)	3.95	N-F	-590 / 0	0.23 (1)	
H-I	-2775 / 0	-111.9	-111.9	0.30 (1)	3.92	N-G	0 / 962	0.22 (1)	
I-J	0 / 34	-111.9	-111.9	0.15 (1)	10.00	M-G	0 / 145	0.03 (4)	
S-B	-2108 / 0	0.0	0.0	0.21 (1)	5.84	M-H	-89 / 0	0.04 (1)	
K-I	-2108 / 0	0.0	0.0	0.21 (1)	5.84	L-H	-460 / 0	0.09 (1)	
						B-R	0 / 2555	0.57 (1)	
S-R	0 / 0	-18.2	-18.2	0.07 (4)	10.00	L-I	0 / 2555	0.57 (1)	
R-Q	0 / 2501	-18.2	-18.2	0.45 (1)	10.00				
Q-P	0 / 2433	-18.2	-18.2	0.44 (1)	10.00				
P-O	0 / 3117	-18.2	-18.2	0.55 (1)	10.00				
O-N	0 / 3117	-18.2	-18.2	0.55 (1)	10.00				
N-M	0 / 2432	-18.2	-18.2	0.44 (1)	10.00				
M-L	0 / 2501	-18.2	-18.2	0.45 (1)	10.00				
L-K	0 / 0	-18.2	-18.2	0.07 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:			
TOP	CH.	LL =	34.8 PSF
		DL =	3.0 PSF
BOT	CH.	LL =	0.0 PSF
		DL =	7.3 PSF
TOTAL LOAD		=	45.1 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A
SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= $L/360$ (1.02")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.18")
ALLOWABLE DEFL.(TL)= $L/360$ (1.02")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.29")

CSI: TC=0.43/1.00 (D-E:1), BC=0.55/1.00 (N-P:1),
WB=0.57/1.00 (I-L:1), SSI=0.25/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg

JSI GRIP= 0.85 (I) (INPUT = 0.90)
JSI METAL= 0.95 (O) (INPUT = 1.00)



July 14, 2022

**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T02	TRUSS DESC.	


TRUE COPY

OF QUANTITY PLANS

Dec 06 2023

PER: *C. Matuevic*
CHIEF BUILDING OFFICIALVersion 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:06 2022 Page 1
ID:OzM1q?scz2BChOKfHahjdLzPugE-wOtHpzNEaViJgTuSaf4j?6qd3wmluL66Ek5_GyysJt
Scale = 1:53.7

MHP 23018



TOTAL WEIGHT = 126 lb

LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - D 2x4 DRY No.2

D - F 2x4 DRY No.2

F - I 2x4 DRY No.2

P - B 2x4 DRY No.2

J - H 2x4 DRY No.2

P - M 2x4 DRY No.2

M - J 2x4 DRY No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

DRY: SEASONED LUMBER.

LUMBER

DESCR.

SPF

SPF

SPF

SPF

SPF

SPF

SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
P	2147	0	2147	0
J	2147	0	2147	0

UNFACTORED REACTIONS

	1ST LCASE	MAX. MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
P	1485	1161 / 0	0 / 0	0 / 0	0 / 0	324 / 0	0 / 0
J	1485	1161 / 0	0 / 0	0 / 0	0 / 0	324 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, J

BRACINGTOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.69 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 34	-111.9 -111.9	0.15 (1)	10.00	O-C	-347 / 14	0.08 (1)
B-C	-2864 / 0	-111.9 -111.9	0.47 (1)	3.69	C-N	-352 / 0	0.23 (1)
C-D	-2598 / 0	-111.9 -111.9	0.44 (1)	3.88	N-D	0 / 308	0.07 (1)
D-E	-2668 / 0	-111.9 -111.9	0.50 (1)	3.74	D-M	0 / 545	0.12 (1)
E-F	-2668 / 0	-111.9 -111.9	0.50 (1)	3.74	M-E	-730 / 0	0.44 (1)
F-G	-2598 / 0	-111.9 -111.9	0.44 (1)	3.88	M-F	0 / 545	0.12 (1)
G-H	-2864 / 0	-111.9 -111.9	0.47 (1)	3.69	L-F	0 / 308	0.07 (1)
H-I	0 / 34	-111.9 -111.9	0.15 (1)	10.00	L-G	-352 / 0	0.23 (1)
P-B	-2103 / 0	0.0 0.0	0.21 (1)	5.84	K-G	-347 / 14	0.08 (1)
J-H	-2103 / 0	0.0 0.0	0.21 (1)	5.84	B-O	0 / 2623	0.59 (1)
					K-H	0 / 2623	0.59 (1)
P-O	0 / 0	-18.2 -18.2	0.10 (4)	10.00			
O-N	0 / 2587	-18.2 -18.2	0.48 (1)	10.00			
N-M	0 / 2302	-18.2 -18.2	0.44 (1)	10.00			
M-L	0 / 2301	-18.2 -18.2	0.44 (1)	10.00			
L-K	0 / 2587	-18.2 -18.2	0.48 (1)	10.00			
K-J	0 / 0	-18.2 -18.2	0.10 (4)	10.00			

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH. LL = 34.8 PSF

DL = 3.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.3 PSF

TOTAL LOAD = 45.1 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (1.02")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.15")
ALLOWABLE DEFL. (TL) = $L/360$ (1.02")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.25")

CSI: TC=0.50/1.00 (D-E:1), BC=0.48/1.00 (N-O:1), WB=0.59/1.00 (B-O:1), SSI=0.29/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
		788	1987
		1873	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.84 (J) (INPUT = 0.90)
JSI METAL= 0.62 (K) (INPUT = 1.00)

July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T03	TRUSS DESC.	


TRUE COPY

OF QUANTITY PLANS

Dec 06 2023

PER: *C. Motta*
CHIEF BUILDING OFFICIALVersion 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:06 2022 Page 1
ID: OzM1q?scz2BChOKfHahjdLzPugE-wOtHpzNEaViJgTuSaf4j?7t6ni3wUluF66Ek5_GyysJt
Scale = 1:59.1

MHP 23018



TOTAL WEIGHT = 127 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - I	2x4	DRY	No.2	SPF
P - B	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
P - M	2x4	DRY	No.2	SPF
M - J	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW-t	MT20	4.0	8.0	1.50	3.00
C	TMW-t	MT20	3.0	4.0	1.50	1.75
D	TTW-m	MT20	4.0	5.0		
E	TMW-t	MT20	3.0	4.0		
F	TTW-m	MT20	4.0	5.0		
G	TMW-t	MT20	3.0	4.0	1.50	1.75
H	TMW-t	MT20	4.0	8.0	1.50	3.00
J	BMV1+p	MT20	3.0	4.0		
K	BMW-t	MT20	4.0	6.0	1.75	1.50
L	BMW-t	MT20	4.0	6.0		
M	BS-t	MT20	3.0	6.0		
N	BMW-t	MT20	4.0	6.0		
O	BMW-t	MT20	4.0	6.0	1.75	1.50
P	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	DOWN	IN-SX	IN-SX
P	2147	0	5-8	3-8
J	2147	0	5-8	3-8

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX. MIN. SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
P	1485	1161 / 0	0 / 0	0 / 0	0 / 0	324 / 0	0 / 0
J	1485	1161 / 0	0 / 0	0 / 0	0 / 0	324 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.39 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)		
FR-TO		FROM	TO		FR-TO				
A-B	0 / 34	-111.9	-111.9	0.15 (1)	10.00	O-C	-255 / 55	0.07 (1)	
B-C	-2902 / 0	-111.9	-111.9	0.69 (1)	3.39	C-N	-598 / 0	0.59 (1)	
C-D	-2413 / 0	-111.9	-111.9	0.62 (1)	3.76	N-D	0 / 664	0.15 (1)	
D-E	-2135 / 0	-111.9	-111.9	0.19 (1)	4.50	N-E	-243 / 0	0.28 (1)	
E-F	-2135 / 0	-111.9	-111.9	0.19 (1)	4.50	E-L	-243 / 0	0.28 (1)	
F-G	-2413 / 0	-111.9	-111.9	0.62 (1)	3.76	L-F	0 / 664	0.15 (1)	
G-H	-2902 / 0	-111.9	-111.9	0.69 (1)	3.39	L-G	-598 / 0	0.59 (1)	
H-I	0 / 34	-111.9	-111.9	0.15 (1)	10.00	K-G	-255 / 55	0.07 (1)	
P-B	-2098 / 0	0.0	0.0	0.21 (1)	5.84	B-O	0 / 2652	0.60 (1)	
J-H	-2098 / 0	0.0	0.0	0.21 (1)	5.84	K-H	0 / 2652	0.60 (1)	
P-O	0 / 0	-18.2	-18.2	0.15 (4)	10.00				
O-N	0 / 2626	-18.2	-18.2	0.50 (1)	10.00				
N-M	0 / 2239	-18.2	-18.2	0.44 (1)	10.00				
M-L	0 / 2239	-18.2	-18.2	0.44 (1)	10.00				
L-K	0 / 2626	-18.2	-18.2	0.50 (1)	10.00				
K-J	0 / 0	-18.2	-18.2	0.15 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	34.8	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD		=	45.1	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.02")
CALCULATED VERT. DEFL. (LL) = L/999 (0.14")
ALLOWABLE DEFL. (TL) = L/360 (1.02")
CALCULATED VERT. DEFL. (TL) = L/999 (0.25")

CSI: TC=0.69/1.00 (B-C:1), BC=0.50/1.00 (N-O:1), WB=0.60/1.00 (B-O:1), SSI=0.29/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.84 (J) (INPUT = 0.90)
JSI METAL= 0.72 (M) (INPUT = 1.00)

July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.



TOTAL WEIGHT = 138 lb

LUMBER

N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - G	2x4	DRY	No.2	SPF
G - J	2x4	DRY	No.2	SPF
J - L	2x4	DRY	No.2	SPF
U - B	2x4	DRY	No.2	SPF
M - K	2x4	DRY	No.2	SPF
U - Q	2x4	DRY	No.2	SPF
Q - M	2x4	DRY	No.2	SPF

ALL WEBS EXCEPT	2x3	DRY
--------------------	-----	-----

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW-t	MT20	4.0	8.0	1.50	3.00
C	TS-t	MT20	3.0	6.0		
D, E, H, I						
D	TMW-t	MT20	3.0	4.0	1.50	1.75
F	TTWW-m	MT20	4.0	6.0	1.75	2.25
G	TTW-m	MT20	4.0	4.0	2.25	1.75
J	TS-t	MT20	3.0	6.0		
K	TMW-t	MT20	4.0	8.0	1.50	3.00
M	BMV1+p	MT20	3.0	4.0		
N	BMW-t	MT20	4.0	6.0	1.75	1.50
O	BMW-t	MT20	3.0	4.0		
P	BMWVW-t	MT20	4.0	6.0		
Q	BS-t	MT20	3.0	6.0		
R	BMWVW+t	MT20	3.0	4.0	1.75	1.50
S	BMWV-t	MT20	3.0	4.0		
T	BMW-t	MT20	4.0	6.0	1.75	1.50
U	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQ'D BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
JT							
U	2147	0	2147	0	0	5-8	3-8
M	2147	0	2147	0	0	5-8	3-8

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
U	1485	1161 / 0	0 / 0	0 / 0	0 / 0	324 / 0	0 / 0
M	1485	1161 / 0	0 / 0	0 / 0	0 / 0	324 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.78 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY
APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED MAX. CSI (LC)	
FR-TO		FROM TO				FR-TO			
A-B	0 / 34	-111.9	-111.9	0.15 (1)	10.00	T-D	-371 / 4	0.08 (1)	
B-C	-2832 / 0	-111.9	-111.9	0.41 (1)	3.78	D-S	-204 / 0	0.11 (1)	
C-D	-2832 / 0	-111.9	-111.9	0.41 (1)	3.78	S-E	0 / 209	0.05 (1)	
D-E	-2667 / 0	-111.9	-111.9	0.34 (1)	3.96	E-R	-715 / 0	0.74 (1)	
E-F	-2174 / 0	-111.9	-111.9	0.33 (1)	4.32	R-F	0 / 599	0.13 (1)	
F-G	-1935 / 0	-111.9	-111.9	0.14 (1)	4.74	F-P	0 / 9	0.00 (1)	
G-H	-2177 / 0	-111.9	-111.9	0.33 (1)	4.32	P-G	0 / 609	0.14 (1)	
H-I	-2666 / 0	-111.9	-111.9	0.34 (1)	3.96	P-H	-709 / 0	0.73 (1)	
I-J	-2833 / 0	-111.9	-111.9	0.41 (1)	3.78	O-H	0 / 203	0.05 (1)	
J-K	-2833 / 0	-111.9	-111.9	0.41 (1)	3.78	O-I	-206 / 0	0.11 (1)	
K-L	0 / 34	-111.9	-111.9	0.15 (1)	10.00	N-I	-369 / 5	0.08 (1)	
U-B	-2105 / 0	0.0	0.0	0.21 (1)	5.84	B-T	0 / 2592	0.58 (1)	
M-K	-2106 / 0	0.0	0.0	0.21 (1)	5.84	N-K	0 / 2593	0.58 (1)	
U-T	0 / 0	-18.2	-18.2	0.09 (4)	10.00				
T-S	0 / 2552	-18.2	-18.2	0.45 (1)	10.00				
S-R	0 / 2385	-18.2	-18.2	0.43 (1)	10.00				
R-Q	0 / 1932	-18.2	-18.2	0.36 (1)	10.00				
Q-P	0 / 1932	-18.2	-18.2	0.36 (1)	10.00				
P-O	0 / 2384	-18.2	-18.2	0.43 (1)	10.00				
O-N	0 / 2552	-18.2	-18.2	0.45 (1)	10.00				
N-M	0 / 0	-18.2	-18.2	0.08 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL =	34.8	PSF
		DL =	3.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.3	PSF
TOTAL LOAD		=	45.1	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A
SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= $L/360$ (1.02")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.14")
ALLOWABLE DEFL.(TL)= $L/360$ (1.02")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.23")

CSI: TC=0.41/1.00 (I-K:1), BC=0.45/1.00 (N-O:1),
WB=0.74/1.00 (E-R:1), SSI=0.22/1.00 (I-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES						
PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.85 (G) (INPUT = 0.90)
JSI METAL= 0.61 (N) (INPUT = 1.00)



July 14, 2022

**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**





TOTAL WEIGHT = 7 X 119 = 836 lb

LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - C 2x4 DRY 2100F 1.8E

C - E 2x4 DRY 2100F 1.8E

E - G 2x4 DRY 2100F 1.8E

G - I 2x4 DRY 2100F 1.8E

N - B 2x4 DRY No.2

J - H 2x4 DRY No.2

N - L 2x4 DRY No.2

L - J 2x4 DRY No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER

BEARINGS

FACTORED

GROSS REACTION

DOWN HORZ

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

N 2147 0

J 2147 0

PLATES (table is in inches)

JT TYPE PLATES

B TMVW-t MT20

C TS-t MT20

D TMVW-t MT20

E TTW+p MT20

F TMVW-t MT20

G TS-t MT20

H TMVW-t MT20

J BMV1+p MT20

K BMVW-t MT20

L BSWWW-I MT20

M BMVW-t MT20

N BMV1+p MT20

W LEN Y X

4.0 8.0 1.50 3.00

3.0 6.0

3.0 4.0 1.50 1.75

4.0 5.0

3.0 4.0 1.50 1.75

3.0 6.0

4.0 8.0 1.50 3.00

3.0 4.0

4.0 6.0 1.75 1.75

6.0 6.0

4.0 6.0 1.75 1.75

3.0 4.0



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH. LL = 34.8 PSF

DL = 3.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.3 PSF

TOTAL LOAD = 45.1 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F.
RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED
ROOF LIVE LOAD

ALLOWABLE DEFL (LL)= L/360 (1.02")
CALCULATED VERT. DEFL (LL) = L/999 (0.14")
ALLOWABLE DEFL (TL)= L/360 (1.02")
CALCULATED VERT. DEFL (TL) = L/999 (0.29")

CSI: TC=0.70/1.00 (B-D:1) , BC=0.57/1.00 (L-M:1) ,
WB=0.60/1.00 (B-M:1) , SS=0.37/1.00 (B-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN
THE TRUSS MANUFACTURING PLANT .

NAIL VALUES


PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.83 (J) (INPUT = 0.90)
JSI METAL= 0.63 (K) (INPUT = 1.00)





TOTAL WEIGHT = 141 lb

LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - D 2x4 DRY No.2

D - F 2x4 DRY No.2

F - I 2x4 DRY No.2

P - B 2x4 DRY No.2

J - H 2x4 DRY No.2

P - M 2x4 DRY No.2

M - J 2x4 DRY No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

DRY: SEASONED LUMBER.

LUMBER

DESCR.

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER

BEARINGS

FACTORED

GROSS REACTION

DOWN

UP

VERT

HORZ

P 2149 0

J 2149 0

MAXIMUM FACTORED

GROSS REACTION

DOWN

UP

VERT

HORZ

P 2149 0

J 2149 0

INPUT

BRG

IN-SX

P 5-8

J 5-8

REQRD

BRG

IN-SX

P 3-8

J 3-8

UNFACTORED REACTIONS

1ST LCASE

COMBINED

SNOW

LIVE

PERM. LIVE

WIND

DEAD

SOIL

P 1487 1162 / 0

J 1487 1162 / 0

MAX./MIN. COMPONENT REACTIONS

DOWN

UP

VERT

HORZ

P 0 / 0

J 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.99 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY

APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

2x4 DRY SPF No.2 T-BRACE AT E-M

FASTEN T AND I-BRACES TO NARROW EDGE OF WEB WITH ONE ROW PER PLY OF 3"

COMMON WIRE NAILS @ 6" O.C. WITH 3" MINIMUM END DISTANCE. BRACE MUST COVER

90% OF WEB LENGTH.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN

THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.		MAX. FACTORED		MEMB.		MAX. FACTORED	
		FORCE (LBS)				FORCE (LBS)	
		VERT. LOAD LC1				MAX. FACTORED	
		PLF				FORCE (LBS)	
		CSI (LC)				MAX. FACTORED	
		UNBRACED				FORCE (LBS)	
		LENGTH				FORCE (LBS)	
		FR-TO				FORCE (LBS)	
A-B		0 / 43		O-C		-297 / 33	
B-C		-2345 / 0		C-N		-377 / 0	
C-D		-2087 / 0		N-D		0 / 352	
D-E		-1917 / 0		D-M		0 / 417	
E-F		-1917 / 0		M-E		-651 / 0	
F-G		-2087 / 0		M-F		0 / 417	
G-H		-2345 / 0		L-F		0 / 352	
H-I		0 / 43		L-G		-377 / 0	
P-B		-2106 / 0		K-G		-297 / 33	
J-H		-2106 / 0		B-O		0 / 2023	
P-O		0 / 0		K-H		0 / 2023	
O-N		0 / 1983					
N-M		0 / 1705					
M-L		0 / 1705					
L-K		0 / 1983					
K-J		0 / 0					

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH. LL = 34.8 PSF

DL = 3.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.3 PSF

TOTAL LOAD = 45.1 PSF

SPACING = 24.0 IN. C/CLOADING IN FLAT SECTION BASED ON A
SLOPE OF 2.00/12 MINIMUMTHIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F.
RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED
ROOF LIVE LOADALLOWABLE DEFL. (LL) = L/360 (1.02")
CALCULATED VERT. DEFL. (LL) = L/999 (0.10")
ALLOWABLE DEFL. (TL) = L/360 (1.02")
CALCULATED VERT. DEFL. (TL) = L/999 (0.16")CSI: TC=0.50/1.00 (B-C:1), BC=0.38/1.00 (N-O:1)
WB=0.46/1.00 (B-O:1), SSI=0.26/1.00 (E-F:1)DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN
THE TRUSS MANUFACTURING PLANT.**NAIL VALUES**

PLATE GRIP(DRY) SHEAR SECTION

(PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN

MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (B) (INPUT = 0.90)

JSI METAL= 0.62 (H) (INPUT = 1.00)




July 14, 2022


READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T07	TRUSS DESC.	

TRUE COPY
OF QUANTITY PLANS
Dec 06 2023PER: 
CHIEF BUILDING OFFICIALVersion 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:10 2022 Page 1
ID:OzM1q?scz2BChOKfHahjdLzPugE-o97neKQlekDk94CDpV9f9jHS1gJwhkRi1siJ81yysJp
Scale = 1:76.6

JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T08	TRUSS DESC.	

TRUE COPY
OF QUANTITY PLANS
Dec 06 2023PER: 
CHIEF BUILDING OFFICIALID: OzM1q?scz2BChOKfHahjdLzPugE-HMg9sgRNP2LbmEmPNCguixqfg4dRQAKrGWSSgTyysJo
Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:11 2022 Page 1
Scale = 1:99.1

TOTAL WEIGHT = 154 lb

LUMBER
N. L. G. A. RULES
CHORDS SIZE

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	2100F 1.8E
C - E	2x4	DRY	2100F 1.8E
E - F	2x4	DRY	No.2
F - H	2x4	DRY	2100F 1.8E
H - J	2x4	DRY	2100F 1.8E
Q - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
Q - N	2x4	DRY	No.2
N - K	2x4	DRY	No.2

ALL WEBS	EXCEPT	SIZE	LUMBER	DESCR.
O - E	2x4	DRY	No.2	SPF
E - M	2x4	DRY	No.2	SPF
M - F	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0	1.75	3.00
C	TS-t	MT20	3.0	6.0		
D	TMVW-t	MT20	3.0	4.0	1.50	1.50
E	TTWW-m	MT20	5.0	8.0	2.00	2.75
F	TTW-m	MT20	4.0	4.0		
G	TMVW-t	MT20	3.0	4.0	1.50	1.50
H	TS-t	MT20	3.0	6.0		
I	TMVW-t	MT20	5.0	6.0	1.75	3.00
K	BMV1-p	MT20	3.0	4.0		
L	BMVW-t	MT20	4.0	5.0	1.75	1.50
M	BMVWW-t	MT20	3.0	8.0		
N	BS-t	MT20	3.0	6.0		
O	BMVW-t	MT20	3.0	5.0		
P	BMVW-t	MT20	4.0	5.0	1.75	1.50
Q	BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY**BUILDING DESIGNER****BEARINGS**

	FACTORED	MAXIMUM FACTORED	INPUT	REQRD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
Q	2149	0	2149	0
K	2149	0	2149	0

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN	COMPONENT REACTIONS
	COMBINED	SNOW	LIVE
Q	1487	1162 / 0	0 / 0
K	1487	1162 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, K

BRACINGTOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.66 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

2x4 DRY SPF No.2 T-BRACE AT D-O, G-M

FASTEN T AND I-BRACES TO NARROW EDGE OF WEB WITH ONE ROW PER PLY OF 3" COMMON WIRE NAILS @ 6" O.C. WITH 3" MINIMUM END DISTANCE. BRACE MUST COVER 90% OF WEB LENGTH.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED	FACTORED	MAX	MEMB.	MAX. FACTORED	MAX	
	FORCE (LBS)	VERT. LOAD (PLF)	CSI (LC)		FORCE (LBS)	MAX	
FR-TO		FROM TO	LENGTH	FR-TO			
A-B	0 / 43	-111.9 -111.9	0.10 (1)	10.00	P-D	-139 / 110	0.09 (1)
B-C	-2349 / 0	-111.9 -111.9	0.61 (1)	4.66	D-O	-762 / 0	0.54 (1)
C-D	-2349 / 0	-111.9 -111.9	0.61 (1)	4.66	O-E	0 / 535	0.09 (1)
D-E	-1753 / 0	-111.9 -111.9	0.56 (1)	5.26	E-M	0 / 20	0.00 (1)
E-F	-1421 / 0	-111.9 -111.9	0.06 (1)	5.44	M-F	0 / 556	0.09 (1)
F-G	-1756 / 0	-111.9 -111.9	0.56 (1)	5.26	M-G	-757 / 0	0.54 (1)
G-H	-2348 / 0	-111.9 -111.9	0.61 (1)	4.66	L-G	-144 / 108	0.09 (1)
H-I	-2348 / 0	-111.9 -111.9	0.61 (1)	4.66	B-P	0 / 2021	0.45 (1)
I-J	0 / 43	-111.9 -111.9	0.10 (1)	10.00	L-I	0 / 2020	0.45 (1)
Q-B	-2094 / 0	0.0	0.0	2.22 (1)	5.85		
K-I	-2094 / 0	0.0	0.0	2.22 (1)	5.85		
Q-P	0 / 0	-18.2	-18.2	0.25 (4)	10.00		
P-O	0 / 2000	-18.2	-18.2	0.45 (1)	10.00		
O-N	0 / 1418	-18.2	-18.2	0.33 (1)	10.00		
N-M	0 / 1418	-18.2	-18.2	0.33 (1)	10.00		
M-L	0 / 1999	-18.2	-18.2	0.44 (1)	10.00		
L-K	0 / 0	-18.2	-18.2	0.25 (4)	10.00		

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	34.8	PSF
BOT CH.	LL	=	3.0	PSF
	DL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (1.02")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.09")
ALLOWABLE DEFL. (TL) = $L/360$ (1.02")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.18")CSI: TC=0.61/1.00 (B-D:1), BC=0.45/1.00 (O-P:1),
WB=0.54/1.00 (D-O:1), SSI=0.33/1.00 (B-D:1)DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.85 (B) (INPUT = 0.90)
JSI METAL= 0.63 (B) (INPUT = 1.00)

July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:12 2022 Page 1
ID:OzM1q?scz2BChOKfHahjdLzPugE-IY EY30S?ALTSOOLbxwB7F8MrDU_q9em?VABPCwysJn
5x8 = 1.905



[MIF]

CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED				
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX CSI (LC)	MAX UNBRAC	MEMB.	FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM	TO		LENGTH	FR-TO			
A-B	0 / 43	-111.9	-111.9	0.10 (1)	10.00	P-D	-156 / 102	0.09 (1)	
B-C	-2354 / 0	-111.9	-111.9	0.56 (1)	4.74	D-O	-713 / 0	0.47 (1)	
C-D	-2354 / 0	-111.9	-111.9	0.56 (1)	4.74	O-E	0 / 528	0.08 (1)	
D-E	-1801 / 0	-111.9	-111.9	0.51 (1)	5.29	E-M	0 / 6	0.00 (1)	
E-F	-1461 / 0	-111.9	-111.9	0.12 (1)	5.30	M-F	0 / 534	0.09 (1)	
F-G	-1803 / 0	-111.9	-111.9	0.51 (1)	5.29	M-G	-710 / 0	0.46 (1)	
G-H	-2354 / 0	-111.9	-111.9	0.56 (1)	4.74	L-G	-159 / 101	0.09 (1)	
H-I	-2354 / 0	-111.9	-111.9	0.56 (1)	4.74	B-P	0 / 2025	0.46 (1)	
I-J	0 / 43	-111.9	-111.9	0.10 (1)	10.00	L-I	0 / 2025	0.46 (1)	
Q-B	-2096 / 0	0.0	0.0	0.22 (1)	5.85				
K-I	-2096 / 0	0.0	0.0	0.22 (1)	5.85				
Q-P	0 / 0	-18.2	-18.2	0.23 (4)	10.00				
P-O	0 / 2002	-18.2	-18.2	0.44 (1)	10.00				
O-N	0 / 1460	-18.2	-18.2	0.31 (1)	10.00				
N-M	0 / 1460	-18.2	-18.2	0.31 (1)	10.00				
M-L	0 / 2002	-18.2	-18.2	0.44 (1)	10.00				
L-K	0 / 0	-18.2	-18.2	0.23 (4)	10.00				


PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMW-t	MT20	5.0	6.0	1.75 3.00
C	TS-t	MT20	3.0	6.0	
D	TMWW-t	MT20	3.0	4.0	1.50 1.50
E	TTWW-m	MT20	5.0	8.0	2.00 2.75
F	TTW-m	MT20	4.0	4.0	
G	TMWW-t	MT20	3.0	4.0	1.50 1.50
H	TS-t	MT20	3.0	6.0	
I	TMW-t	MT20	5.0	6.0	1.75 3.00
K	BMV1+p	MT20	3.0	4.0	
L	BMWW-t	MT20	4.0	5.0	1.75 1.50
M	BMWWWW-t	MT20	3.0	8.0	
N	BS-t	MT20	3.0	6.0	
O	BMWW-t	MT20	3.0	5.0	
P	BMWW-t	MT20	4.0	5.0	1.75 1.50
Q	BMV1+p	MT20	3.0	4.0	



**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**

JSI GRIP= 0.85 (B) (INPUT = 0.90)
JSI METAL= 0.63 (B) (INPUT = 1.00)





TRUE COPY

OF QUANTITY PLANS

Dec 06 2023

PER: *C. Matuevic*
CHIEF BUILDING OFFICIAL

JOB DESC.


DRWG NO.

TRUSS DESC.

Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:14 2022 Page 1

ID: OzM1q?scz2BChOkHahjdLzPugE-hxMIUIGhzAeiV_2KEbKZSCGHhBdRKlyUgWHoyysJl
Scale = 1:64.7

MHP 23018



TOTAL WEIGHT = 139 lb

[M/F]

LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - D 2x4 DRY No.2

D - F 2x4 DRY No.2

F - I 2x4 DRY No.2

P - B 2x4 DRY No.2

J - H 2x4 DRY No.2

P - M 2x4 DRY No.2

M - J 2x4 DRY No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

DRY: SEASONED LUMBER.

DESCR.

SPF

SPF

SPF

SPF

SPF

SPF

SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER

BEARINGS

FACTORED

GROSS REACTION

DOWN

UP

J 2149 0

J 2149 0

MAXIMUM FACTORED

GROSS REACTION

DOWN

UP

J 2149 0

J 2149 0

INPUT

BRG

IN-SX

5-8

5-8

REQD

BRG

IN-SX

3-8

3-8

UNFACTORED REACTIONS

1ST LCASE

COMBINED

SNOW

LIVE

PERM. LIVE

WIND

DEAD

SOIL

J 1487 1162 / 0

J 1487 1162 / 0

MAX/MIN. COMPONENT REACTIONS

VERT. LOAD

LC1

MAX

UNBRAC

LENGTH

FR-TO

A-B

B-C

C-D

D-E

E-F

F-G

G-H

H-I

I-J

J-K

K-L

L-M

M-N

N-O

O-P

P-Q

Q-R

R-S

S-T

T-U

U-V

V-W

W-X

X-Y

Y-Z

Z-AA

AA-BB

BB-CC

CC-DD

DD-EE

EE-FF

FF-GG

GG-HH

HH-II

II-JJ

JJ-KK

KK-LL

LL-MM

MM-NN

NN-OO

OO-PP

PP-QQ

QQ-RR

RR-SR

SR-TT

TT-UU

UU-VV

VV-WW

WW-XX

XX-YY

YY-ZZ

ZZ-AA

PLATES (table is in inches)

JT TYPE

PLATES

W

LEN

Y

X

B TMVW-t MT20 5.0 6.0 1.75 3.00

C TMVW-t MT20 3.0 4.0 1.50 1.50

D TTWW+m MT20 5.0 6.0 Edge 1.75

E TMVW-w MT20 2.0 4.0

F TTWW+m MT20 5.0 6.0 Edge 1.75

G TMVW-t MT20 3.0 4.0 1.50 1.50

H TMVW-t MT20 5.0 6.0 1.75 3.00

J BMV1+p MT20 3.0 4.0

K BMVW-t MT20 4.0 5.0 1.50 1.75

L BMVW-t MT20 3.0 4.0

M BSWWW-I MT20 5.0 6.0 3.00 3.00

N BMVW-t MT20 3.0 4.0

O BMVW-t MT20 4.0 5.0 1.50 1.75

P BMV1+p MT20 3.0 4.0

Edge - INDICATES REFERENCE CORNER OF PLATE

TOUCHES EDGE OF CHORD.



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.




JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T13	TRUSS DESC.	

TRUE COPY


OF QUANTITY PLANS

Dec 06 2023

 PER: 
 CHIEF BUILDING OFFICIAL

 ID: OzM1q?scz2BChOKfHahjdLzPugE-dJU2vOVVDazut?fNAIG3P_Xco5Se5WuaPn9dLhyysJj
 Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:16 2022 Page 1
 Scale = 1:87.7

MHP 23018



TOTAL WEIGHT = 81 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
K - B	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
K - G	2x4	DRY	No.2	SPF	

 ALL WEBS 2x3 DRY No.2 SPF
 EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	5.0	1.25	2.00
C	TMVW-t	MT20	3.0	5.0	1.50	1.75
D	TMVW+p	MT20	3.0	4.0		
E	TMVW-t	MT20	3.0	5.0	1.50	1.75
F	TMVW+p	MT20	4.0	5.0	1.25	2.00
G	BMV1+p	MT20	2.0	4.0		
H	BMVW-t	MT20	3.0	4.0		
I	BMVWW-t	MT20	3.0	6.0		
J	BMVW-t	MT20	3.0	4.0		
K	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
K	927 0	927 0	5-8	1-8
G	770 0	770 0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS
K	640	509 / 0	0 / 0
G	534	412 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-B	0 / 60	-111.9 -111.9	0.16 (1)	10.00	J-C	-239 / 2 0.20 (1)	
B-C	-392 / 0	-111.9 -111.9	0.12 (1)	6.25	C-I	-122 / 0 0.13 (1)	
C-D	-375 / 0	-111.9 -111.9	0.12 (1)	6.25	I-E	-123 / 0 0.13 (1)	
D-E	-375 / 0	-111.9 -111.9	0.12 (1)	6.25	H-E	-239 / 2 0.20 (1)	
E-F	-393 / 0	-111.9 -111.9	0.12 (1)	6.25	B-J	0 / 407 0.09 (1)	
K-B	-904 / 0	0.0 0.0	0.20 (1)	7.81	H-F	0 / 407 0.09 (1)	
G-F	-748 / 0	0.0 0.0	0.17 (1)	7.81	I-D	0 / 272 0.06 (1)	
K-J	0 / 0	-18.2 -18.2	0.04 (4)	10.00			
J-I	0 / 275	-18.2 -18.2	0.06 (1)	10.00			
I-H	0 / 275	-18.2 -18.2	0.06 (1)	10.00			
H-G	0 / 0	-18.2 -18.2	0.04 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	34.8	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

 ALLOWABLE DEFL. (LL) = $L/360$ (0.39")
 CALCULATED VERT. DEFL. (LL) = $L/999$ (0.01")
 ALLOWABLE DEFL. (TL) = $L/360$ (0.39")
 CALCULATED VERT. DEFL. (TL) = $L/999$ (0.02")

CSI: TC=0.20/1.00 (B-K-1), BC=0.06/1.00 (H-I-1), WB=0.20/1.00 (C-J-1), SSI=0.10/1.00 (D-E-1)

 DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

 JSI GRIP= 0.64 (H) (INPUT = 0.90)
 JSI METAL= 0.24 (F) (INPUT = 1.00)


July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T14	TRUSS DESC.	

TRUE COPY

OF QUANTITY PLANS


Dec 06 2023

PER: *C. Motta*
CHIEF BUILDING OFFICIAL

Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:17 2022 Page 1

ID: OzM1q?scz2BChOKfHahjdLzPugE-5W2R7kV8_u5IV9EZjTnlxB4n3Vndq_ZkeRvAt7yysJi

Scale: 3/16"=1'



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T16	TRUSS DESC.	

TRUE COPY

OF QUANTITY PLANS


Dec 06 2023

PER: *C. M. M.*

CHIEF BUILDING OFFICIAL

Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:18 2022 Page 1
ID: OzM1q?scz2BChOKfHahjdLzPugE-ZicpK4WmlBDc6JplHAIXUPczqu7CZS1tt5ekQZyysJh
Scale = 1:43.7

MHP 23018



TOTAL WEIGHT = 31 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
G - B	2x4	DRY	No.2	SPF	
A - D	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW-t	MT20	3.0	4.0	1.50	1.00
C	TMW-t	MT20	3.0	4.0	1.50	1.50
D	TMV+p	MT20	2.0	4.0		
E	BMWV-t	MT20	3.0	4.0		
F	BMWV-t	MT20	3.0	4.0		
G	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	DOWN	IN-SX	IN-SX
G	544	0	5-8	1-8
E	390	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
G	374	304 / 0	0 / 0	0 / 0	0 / 0	70 / 0	0 / 0
E	271	209 / 0	0 / 0	0 / 0	0 / 0	62 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO			FR-TO		
G-B	-521 / 0	0.0	0.0	0.05 (1)	7.81	B-F	0 / 248	0.06 (1)
A-B	0 / 43	-111.9	-111.9	0.15 (1)	10.00	F-C	-21 / 57	0.02 (4)
B-C	-259 / 0	-111.9	-111.9	0.17 (1)	6.25	C-E	-335 / 0	0.10 (1)
C-D	-22 / 0	-111.9	-111.9	0.17 (1)	6.25			
E-D	-127 / 0	0.0	0.0	0.06 (1)	7.81			
G-F	0 / 0	-18.2	-18.2	0.04 (4)	10.00			
F-E	0 / 234	-18.2	-18.2	0.06 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	34.8	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.00")

CSI: TC=0.17/1.00 (B-C:1), BC=0.06/1.00 (E-F:1), WB=0.10/1.00 (C-E:1), SS=0.14/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.77 (B) (INPUT = 0.90)

JSI METAL= 0.15 (B) (INPUT = 1.00)



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T17	TRUSS DESC.	

TRUE COPY
OF QUANTITY PLANS
Dec 06 2023

PER: *C. Matar*
CHIEF BUILDING OFFICIAL

ID: OzM1q?scz2BChOKfHahjdLzPugE-2u9BXPXOWVLTKTOxrupm1c92plMJlvn16lOHyoysJg
Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:19 2022 Page 1
Scale = 1:62.7

MHP 23018



TOTAL WEIGHT = 2 X 41 = 81 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - B	2x4	DRY	No.2	SPF	
B - C	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMBH1-I	MT20	3.0	4.0		
B	TTW+p	MT20	3.0	5.0	2.75	1.50
C	TMBH1-I	MT20	3.0	4.0		
D	BMW+w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG	HEEL WEDGE
A	764	0	764	0	0
C	764	0	764	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT A, C. MINIMUM BEARING LENGTH AT JOINT A = 1-12, JOINT C = 1-12.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS
A	530	409 / 0	0 / 0
C	530	409 / 0	0 / 0

BRACINGS

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED HORIZ. LOAD (LC1)	MAX. FACTORED UNBRACED LENGTH (LC)	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (LC)
FR-TO						FR-TO			
A-F		-157 / 0	-111.9	-111.9	0.25 (1)	D-B		0 / 287	0.06 (1)
F-B		-574 / 0	-111.9	-111.9	0.47 (1)	E-F		-929 / 11	0.00 (1)
B-H		-574 / 0	-111.9	-111.9	0.47 (1)	G-H		-929 / 11	0.00 (1)
H-C		-157 / 0	-111.9	-111.9	0.25 (1)				
A-E		0 / 353	-18.2	-18.2	0.45 (1)				
E-D		0 / 353	-18.2	-18.2	0.45 (1)				
D-G		0 / 353	-18.2	-18.2	0.45 (1)				
G-C		0 / 353	-18.2	-18.2	0.45 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	34.8	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.39")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.06")
ALLOWABLE DEFL. (TL) = $L/360$ (0.39")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.10")

CSI: TC=0.47/1.00 (B-H-1), BC=0.45/1.00 (D-G-1), WB=0.06/1.00 (B-D-1), SSI=0.70/1.00 (C-G-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987
			1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.58 (A) (INPUT = 0.90)
JSI METAL= 0.22 (C) (INPUT = 1.00)



July 14, 2022


READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T18	TRUSS DESC.	

TRUE COPY
OF QUANTITY PLANS
Dec 06 2023PER: 
CHIEF BUILDING OFFICIALVersion 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:20 2022 Page 1
ID:OzM1q?scz2BChOKfHahjdLzPugE-W5jZlY0HpTKMdy8PbK?ZqhGAioS1MjAKP7rUSyysJf
Scale: 1/2"=1'

MHP 23018



TOTAL WEIGHT = 26 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	
G - B	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	3.0	4.0	1.50	1.00
C	TTWW-m	MT20	4.0	5.0	1.75	1.50
D	TMV+p	MT20	2.0	4.0		
E	BMVW1-t	MT20	3.0	4.0		
F	BMVW-t	MT20	3.0	4.0		
G	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
E	390 0	390 0	MECHANICAL	
G	544 0	544 0	5-8	1-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS
E	271	209 / 0	0 / 0
G	374	304 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1	MAX. CS1 (LC)	MAX. UNBRAC LENGTH	MEMB.	WEBS MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
FR-TO						FR-TO		
A-B	0 / 43	-111.9	-111.9	0.15 (1)	10.00	F-C	-48 / 51	0.02 (4)
B-C	-272 / 0	-111.9	-111.9	0.08 (1)	6.25	C-E	-262 / 0	0.08 (1)
C-D	0 / 0	-111.9	-111.9	0.30 (1)	10.00	B-F	0 / 254	0.06 (1)
E-D	-224 / 0	0.0	0.0	0.03 (1)	7.81			
G-B	-534 / 0	0.0	0.0	0.05 (1)	7.81			
G-F	0 / 0	-18.2	-18.2	0.06 (4)	10.00			
F-E	0 / 224	-18.2	-18.2	0.07 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	34.8	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	45.1	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.01")CSI: TC=0.30/1.00 (C-D:1), BC=0.07/1.00 (E-F:1),
WB=0.08/1.00 (C-E:1), SSI=0.17/1.00 (C-D:1)DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
	MAX	MIN	MAX
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.79 (B) (INPUT = 0.90)
JSI METAL= 0.14 (B) (INPUT = 1.00)

July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	JOB DESC.	DRWG NO.
IM0722-052	T19	TRUSS DESC.	

TRUE COPY

OF QUANTITY PLANS


Dec 06 2023

PER: *C. M. M. M.*

CHIEF BUILDING OFFICIAL

Version 8.500 S Aug 16 2021 MiTek Industries, Inc. Tue Jul 12 09:52:20 2022 Page 1
 ID: OzM1q?scz2BChOKfHahjdLzPugE-W5jZIIY0HpTKMdy8PbK?ZqhJ1inZ1KnAKP7rUSyysJf
 Scale = 1:80.1

MHP 23018



TOTAL WEIGHT = 60 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
J - A	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	5.0	1.25	2.00
B	TMVW-t	MT20	3.0	5.0	1.50	1.75
C	TTW+p	MT20	3.0	5.0	2.75	1.50
D	TMVW-t	MT20	3.0	5.0	1.50	1.75
E	TMVW+p	MT20	4.0	5.0	1.25	2.00
F	BMV1+p	MT20	2.0	4.0	Edge	
G	BMVW-t	MT20	3.0	5.0		
H	BBVWV-p	MT20	5.0	6.0	2.75	3.00
I	BMVW-t	MT20	3.0	5.0		
J	BMV1+p	MT20	2.0	4.0	Edge	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
J	764	0	764	0	5-8	1-8
F	764	0	764	0	5-8	1-8

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX. MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM. LIVE	WIND			
J	530	409 / 0	0 / 0	0 / 0	0 / 0	121 / 0	0 / 0
F	530	409 / 0	0 / 0	0 / 0	0 / 0	121 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED CSI (LC)		
FR-TO		FROM	TO		FR-TO				
A-B	-827 / 0	-111.9	-111.9	0.12 (1)	6.25	H-C	0 / 925	0.21 (1)	
B-C	-797 / 0	-111.9	-111.9	0.12 (1)	6.25	H-D	-61 / 0	0.01 (1)	
C-D	-797 / 0	-111.9	-111.9	0.12 (1)	6.25	G-D	-313 / 0	0.07 (1)	
D-E	-827 / 0	-111.9	-111.9	0.12 (1)	6.25	B-H	-61 / 0	0.01 (1)	
J-A	-741 / 0	0.0	0.0	0.10 (1)	7.81	I-B	-313 / 0	0.07 (1)	
F-E	-741 / 0	0.0	0.0	0.10 (1)	7.81	A-I	0 / 558	0.13 (1)	
						G-E	0 / 558	0.13 (1)	
J-I	0 / 4	-18.3	-18.3	0.04 (4)	10.00				
I-H	0 / 692	-18.2	-18.2	0.13 (1)	10.00				
H-G	0 / 692	-18.2	-18.2	0.13 (1)	10.00				
G-F	0 / 4	-18.2	-18.2	0.04 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	34.8	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD		=	45.1	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.39")
 CALCULATED VERT. DEFL. (LL) = $L/999$ (0.03")
 ALLOWABLE DEFL. (TL) = $L/360$ (0.39")
 CALCULATED VERT. DEFL. (TL) = $L/999$ (0.04")

CSI: TC=0.12/1.00 (D-E:1), BC=0.13/1.00 (G-H:1), WB=0.21/1.00 (C-H:1), SS=0.10/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (C) (INPUT = 0.90)

JSI METAL= 0.37 (F) (INPUT = 1.00)



July 14, 2022

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



MiTek



STANDARD DETAIL MSD2015-H

MHP 23018

Issued: MARCH 1, 2022
Expiry: APRIL 30, 2024

TOE-NAIL CAPACITY DETAILS

LATERAL AND WITHDRAWAL RESISTANCE OF BEARING ANCHORAGE BY TOE-NAILS

NAIL TYPE	Length (in)	Diameter (in)	LATERAL Resistance per nail (Lbs.)		WITHDRAWAL Resistance per nail (Lbs.)	
			SPF	D. FIR	SPF	D. FIR
COMMON WIRE	3.00	0.144	122	139	30	42
	3.25	0.144	127	144	32	45
	3.50	0.160	152	173	38	52
COMMON SPIRAL	3.00	0.122	96	108	26	36
	3.25	0.122	97	108	28	40
	3.50	0.152	142	161	36	50
3.25" Gun nail	3.25	0.120	94	105	28	39

Note: If using truss with D. Fir lumber and SPF bearing plate, use tabulated SPF values in table.

Nail type:	Common wire	Common spiral	Common wire	Common spiral	Gun Nail
Diameter (in.)	0.160	0.152	0.144	0.122	0.120
Length (in.)	3.50	3.50	3.00	3.00	3.25
LUMBER	MAXIMUM NUMBER OF TOE-NAILS				
2x4 SPF	2	2	3	3	3
2x6 SPF	4	4	4	5	5
2x4 D. FIR	2	2	2	2	2
2x6 D. FIR	3	3	3	4	4




Figure 1: Toe-Nailing Rafter / Ceiling Member to Girder Truss



MiTek®




STANDARD DETAIL MSD2015-H

MHP 23018

Issued: MARCH 1, 2022
Expiry: APRIL 30, 2024

TOE-NAIL CAPACITY DETAILS

Figure 2: Toe-Nail Anchorage to Bearing Plate for Uplift



NOTES:

1. Rafter and ceiling members may be connected to top and bottom chords of girder truss by toe-nailing the members into the girder chords (see fig. 1), provided the factored vertical reactions of the supported members do not exceed the lateral resistance of the toe-nails. Mechanical connectors (hangers) are required if factored vertical reactions exceed the toe-nail capacity, or if the connection must resist horizontal loads (loads perpendicular to the face of girder or rafter).
2. Trusses, rafters or ceiling members may be anchored to the bearing plate with toe-nails (see fig. 2), provided that the factored uplift reactions due to **wind or earthquake loads** do not exceed the **withdrawal resistance of the toe-nails**. Mechanical anchors (tie-downs) are required for reactions that exceed the toe-nail withdrawal capacity. Toe-nail anchorage to bearing plates is **NOT** permitted if uplift reactions are generated from gravity loads (snow, floor live, dead).
3. Tabulated toe-nail resistances on page 1 are for **one** toe-nail. Multiply unit values by the number of nails used in the connection. Maximum number of nails in a connection shall not exceed the tabulated limits shown on page 1 for a given lumber size /species.
4. Nail values are based on specific gravity of $G = 0.42$ (SPF) and $G = 0.49$ (D. Fir).
5. Toe-nails shall be driven at approximately $1/3$ the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member.
6. For wind / earthquake loads, tabulated lateral resistances may be multiplied by 1.15 (K_D factor). No increases are permitted for tabulated withdrawal resistances.
7. Lumber must be dry ($< 19\%$ moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-19, Clause 12.9.

PEO
Certificate No. 10889485

MiTek



STANDARD DETAIL MSD2015-J




MHP 23018

Issued: MARCH 17, 2021

Expiry: APRIL 30, 2023




STANDARD HIP END FRAMING

PLAN VIEW



Specified Load Rating:


Top chord Live:	51.0 PSF or less
Top chord Dead:	6.0 PSF or less
Bottom chord Live:	0.0 PSF
Bottom chord Dead:	7.3 PSF or less



CANTILEVER DETAIL "C"

SLOPE	MAX CANT.	WEDGE PLATE	WEDGE SIZE
3/12	17"	3 X 5	2 X 3
4/12	14"	3 X 5	2 X 3
5/12	12"	3 X 5	2 X 4
6/12	10"	3 X 5	2 X 4
7/12	9"	3 X 5	2 X 6
8/12	8 5/8"	3 X 5	2 X 6
9/12	8"	3 X 5	2 X 6
10/12	7 5/8"	3 X 5	2 X 6

J Trusses



PEO

Certificate No. 10889485

NOTES:

1. This detail is valid only for projects conforming to **PART 9 NBCC 2015** that do not require a wind analysis to be incorporated into the design of the trusses.
2. Overhang length shall not exceed 24 inches.
3. All lumber shall be 2x4 SPF (or D-Fir) DRY No. 2 grade or better.
4. All plates specified are MITEK MT20, pressed into both faces of each truss. Heel plates of all trusses shall conform to heel details 'A', 'B' or 'C'.
5. Diagonal hip rafter design shall conform to section 9.23.14.6 of NBCC 2015.
6. For 6.0 ft. or less span, diagonal web on truss 'J' is optional. Girder design must reflect choice of partial jack ('J' with diagonal web) or open jack ('J' without diagonal web)
7. All truss-to-rafter and truss-to-truss connections shall be specified as per MITEK standard detail 'MSD2015-H: Toe-Nail Capacity Details'



MiTek®



STANDARD DETAIL MSD2015-K

MHP 23018

Issued: MARCH 1, 2022

Expiry: APRIL 30, 2024

STANDARD GABLE END DETAIL


Specified Load Rating:

Top chord Live:	51.0 PSF
Top chord Dead:	6.0 PSF
Bottom chord Live:	0.0 PSF
Bottom chord Dead:	7.3 PSF

See note 5 for bracing
all web members 6.0 ft.
in length or greater



Lumber Sizes:

Top chord:	2x4
Webs:	2x4 or 2x3
Bottom chord:	2x4 or 2x3

SCAB BRACE DETAIL
(Section B-B)

Gable Web

SPF No. 2 DRY Scab, same size as web. Scab brace must cover 90% of web length

2x4 SPF No. 2
DRY L-BraceL BRACE DETAIL
(Section A-A)

Fasten L-Brace to narrow edge of web with one row of 0.122" x 3.0" nails spaced at 6.0" c/c along entire length of web. Brace must cover 90% of the web length. Respect a 2.5" minimum end distance.

Notes:

1. This detail is only valid for projects conforming to **Part 9, NBCC 2015** that do not require a wind analysis to be incorporated into the design of the truss.
2. This detail is for vertical (gravity) load rating of the truss only. Truss must be continuously supported over the entire length of bottom chord.
3. Maximum web length not to exceed 12.0 ft. Spacing of gable stud webs in the truss not to exceed 24 inches cc.
4. Splice joints shall not be located in the first panel adjacent to the heel joint or peak joint.
5. Lateral restraint required at half-length of all webs over 6.0 ft. long. Alternatively install an L-Brace or scab brace as shown above. Scab braces shall be limited to 10 ft. long webs or less.
6. All plates are MITTEK MT20 pressed into both faces of truss.
7. All lumber to be SPF (or D-Fir) DRY and of No.2 grade or better.
8. Additional building bracing is typically installed to brace the face of the end wall assembly. See BCSI Canada 'Building Designer Responsibilities for Gable End Frame Bracing' for additional information on building bracing for gable-end assemblies.

PEO
Certificate No. 10889485

