


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0723-093	J02A	2	1	TRUSS DESC.	MHP 23030

PER: 
CHIEF BUILDING OFFICIAL



TOTAL WEIGHT = 2 X 6 = 12 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
D - A	2x4	DRY	No.2	SPF
A - B	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	2.0	4.0		
D	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
D	140	0	140	0	0	5-8	1-8
B	113	0	113	0	0	1-8	1-8
C	27	0	27	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) B , C

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
D	98	71 / 0	0 / 0	0 / 0	0 / 0	0 / 0	27 / 0	0 / 0
B	77	65 / 0	0 / 0	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0
C	21	6 / 0	0 / 0	0 / 0	0 / 0	0 / 0	15 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

C H O R D S				W E B S			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO		FROM	TO		FR-TO		
D- A	-130 / 0	0.0	0.0	0.02 (1)	7.81		
A- B	-4 / 0	-119.4	-119.4	0.06 (1)	10.00		
D- C	0 / 0	-18.2	-18.2	0.03 (1)	10.00		

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	34.8	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	48.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.00")

CSI: TC=0.06/0.97 (A-B:1) , BC=0.03/0.97 (C-D:1) ,
WB=0.00/0.97 (n/a:0) , SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
	MAX	MIN	MAX
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.07 (A) (INPUT = 0.90)
JSI METAL= 0.05 (A) (INPUT = 1.00)



JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0723-093	TRUSS NAME OF PERMIT PLANS Oct 30 2023	5	1	TRUSS DESC.	MHP 23030

PER: 
CHIEF BUILDING OFFICIAL

Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:36:00 2023 Page 1
ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-VGijt2nN2Jsf_Bon2kj?Vslee1LumrQoe?TV8qyyE7T

Scale = 1:25.3



TOTAL WEIGHT = 5 X 15 = 73 lb

LUMBER

N. L. G. A. RULES
CHORDS SIZE
E - B 2x4 DRY
A - C 2x4 DRY
E - D 2x4 DRY

LUMBER
No.2
No.2
No.2

DESCR.
SPF
SPF
SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	528	0	528	0	5-8	1-8
C	181	0	181	0	1-8	1-8
D	45	0	51	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	COMBINED	MAX./MIN. COMPONENT REACTIONS					
		1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD
E	368	270 / 0	0 / 0	0 / 0	0 / 0	98 / 0	0 / 0
C	124	105 / 0	0 / 0	0 / 0	0 / 0	18 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

C H O R D S				W E B S			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
FR-TO		FROM	TO		FR-TO		
E-B	-463 / 0	0.0	0.0	0.13 (4)	7.81		
A-B	0 / 36	-119.4	-119.4	0.16 (1)	10.00		
B-C	-27 / 0	-119.4	-119.4	0.33 (1)	6.25		
E-D	0 / 0	-18.2	-18.2	0.13 (4)	10.00		

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH. LL = 34.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 48.1 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.03")

CSI: TC=0.33/0.97 (B-C:1), BC=0.13/0.97 (D-E:4), WB=0.00/0.97 (n/a:0), SSI=0.21/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.26 (B) (INPUT = 0.90)
JSI METAL= 0.19 (B) (INPUT = 1.00)




JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0723-093	TRUSS NAME OF PERMIT PLANS Oct 30 2023	13	1	TRUSS DESC.	MHP 23030

PER: 
CHIEF BUILDING OFFICIAL



Scale = 1:34.0

TOTAL WEIGHT = 13 X 17 = 222 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
E	674	0	674	0
C	269	0	269	0
D	45	0	51	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	468	355 / 0	0 / 0	0 / 0	0 / 0	0 / 0	113 / 0	0 / 0
C	184	157 / 0	0 / 0	0 / 0	0 / 0	0 / 0	27 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

C H O R D S				W E B S			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO		FROM TO			FR-TO		
E-B	-610 / 0	0.0	0.0	0.13 (4)	7.81		
A-B	0 / 36	-119.4	-119.4	0.16 (1)	10.00		
B-C	-40 / 0	-119.4	-119.4	0.73 (1)	6.25		
E-D	0 / 0	-18.2	-18.2	0.13 (4)	10.00		

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	34.8	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	48.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.03")

CSI: TC=0.73/0.97 (B-C:1), BC=0.13/0.97 (D-E:4), WB=0.00/0.97 (n/a:0), SSI=0.31/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
	MAX	MIN	MAX
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.34 (B) (INPUT = 0.90)
JSI METAL= 0.25 (B) (INPUT = 1.00)




JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0723-093	TRUSS NAME	1	1	TRUSS DESC.	MHP 23030
Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:36:01 2023 Page 1					
ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-zTG55Oo?oc_WbLNzbSFE23InsQa1V93xtfC2hGyyE7S					
1-3-8	0-0	0-0	5-0-7	13-0-7	4-11-3
1-3-8	0-0	5-0-7	13-0-7	4-11-3	17-11-9
1-3-8	0-0	5-0-7	13-0-7	4-11-3	5-0-7
1-3-8	0-0	5-0-7	13-0-7	4-11-3	23-0-0
1-3-8	0-0	5-0-7	13-0-7	4-11-3	3-10-12
1-3-8	0-0	5-0-7	13-0-7	4-11-3	26-10-12
1-3-8	0-0	5-0-7	13-0-7	4-11-3	4-1-4
1-3-8	0-0	5-0-7	13-0-7	4-11-3	31-0-0
1-3-8	0-0	5-0-7	13-0-7	4-11-3	32-0-0

Oct 30 2023
CHIEF BUILDING OFFICIAL

**LUMBER**

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
G - J	2x4	DRY	No.2	SPF
S - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
S - O	2x4	DRY	No.2	SPF
O - K	2x4	DRY	No.2	SPF

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	8.0	1.50	3.00
C	TMWW-t	MT20	3.0	4.0	1.50	1.75
D	TTWW+m	MT20	6.0	6.0	2.50	2.00
E	TMW+w	MT20	2.0	4.0		
F	TMWW-t	MT20	3.0	4.0		
G	TTWW+m	MT20	6.0	6.0	2.50	2.00
H	TMWW-t	MT20	3.0	4.0	1.50	1.75
I	TMVW-t	MT20	4.0	8.0	1.50	3.00
K	BMV1+p	MT20	3.0	4.0		
L	BMWW-t	MT20	4.0	6.0	1.50	2.00
M	BMWW-t	MT20	3.0	4.0		
N	BMWW-t	MT20	4.0	4.0	2.00	1.75
O	BS-t	MT20	4.0	6.0		
P	BMWW-t	MT20	4.0	6.0	1.75	2.00
Q	BMWW-t	MT20	3.0	4.0		
R	BMWW-t	MT20	4.0	6.0	1.50	2.00
S	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY**BUILDING DESIGNER****BEARINGS**

	FACTORED	MAXIMUM FACTORED	INPUT	REQRD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	UPLIFT	IN-SX
S	2296	0	2296	0
K	2296	0	2296	0

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS
	COMBINED	SNOW	LIVE
S	1602	1174 / 0	0 / 0
K	1602	1174 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.35 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-B	0 / 36	-119.4 -119.4	0.16 (1)	10.00	R-C	-499 / 0	0.09 (1)
B-C	-2972 / 0	-119.4 -119.4	0.33 (1)	3.74	C-Q	-86 / 0	0.03 (1)
C-D	-2942 / 0	-119.4 -119.4	0.32 (1)	3.77	Q-D	0 / 148	0.04 (4)
D-E	-3367 / 0	-119.4 -119.4	0.49 (1)	3.35	D-P	0 / 1051	0.24 (1)
E-F	-3367 / 0	-119.4 -119.4	0.45 (1)	3.40	P-E	-643 / 0	0.25 (1)
F-G	-3369 / 0	-119.4 -119.4	0.49 (1)	3.35	P-F	-3 / 0	0.00 (1)
G-H	-2942 / 0	-119.4 -119.4	0.32 (1)	3.77	N-F	-644 / 0	0.25 (1)
H-I	-2972 / 0	-119.4 -119.4	0.33 (1)	3.74	N-G	0 / 1055	0.24 (1)
I-J	0 / 36	-119.4 -119.4	0.16 (1)	10.00	M-G	0 / 146	0.04 (4)
S-B	-2256 / 0	0.0 0.0	0.23 (1)	5.60	M-H	-87 / 0	0.03 (1)
K-I	-2256 / 0	0.0 0.0	0.23 (1)	5.60	L-H	-499 / 0	0.09 (1)
S-R	0 / 0	-18.2 -18.2	0.07 (4)	10.00	B-R	0 / 2736	0.62 (1)
R-Q	0 / 2678	-18.2 -18.2	0.48 (1)	10.00	L-I	0 / 2736	0.62 (1)
Q-P	0 / 2611	-18.2 -18.2	0.47 (1)	10.00			
P-O	0 / 3369	-18.2 -18.2	0.59 (1)	10.00			
O-N	0 / 3369	-18.2 -18.2	0.59 (1)	10.00			
N-M	0 / 2611	-18.2 -18.2	0.47 (1)	10.00			
M-L	0 / 2678	-18.2 -18.2	0.48 (1)	10.00			
L-K	0 / 0	-18.2 -18.2	0.07 (4)	10.00			

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	34.8	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	48.1	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.03")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.18")
ALLOWABLE DEFL.(TL)= L/360 (1.03")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.32")

CSI: TC=0.49/0.97 (D-E:1) , BC=0.59/0.97 (N-P:1) ,
WB=0.62/0.97 (I-L:1) , SSI=0.28/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.90 (K) (INPUT = 0.90)
JSI METAL= 0.76 (O) (INPUT = 1.00)




JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





**LUMBER**

N. L. G. A. RULES

CHORDS SIZE

A - D 2x4 DRY No.2

D - E 2x6 DRY No.2

E - H 2x4 DRY No.2

O - B 2x4 DRY No.2

I - G 2x4 DRY No.2

O - L 2x4 DRY No.2

L - I 2x4 DRY No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	8.0	1.50	3.00
C	TMWW-t	MT20	3.0	4.0	1.50	1.75
D	TTWW+m	MT20	4.0	6.0		
E	TTW-m	MT20	4.0	5.0		
F	TMVW-t	MT20	3.0	4.0	1.50	1.75
G	TMVW-t	MT20	4.0	8.0	1.50	3.00
I	BMV1+p	MT20	3.0	4.0		
J	BMVW-t	MT20	4.0	6.0	1.75	1.50
K	BMVWW-t	MT20	3.0	8.0		
L	BS-t	MT20	3.0	6.0		
M	BMVW-t	MT20	3.0	4.0		
N	BMVW-t	MT20	4.0	6.0	1.75	1.50
O	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
O	2296	0	2296	0
I	2296	0	2296	0

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
O	1602	1174 / 0	0 / 0	0 / 0	0 / 0	429 / 0	0 / 0
I	1602	1174 / 0	0 / 0	0 / 0	0 / 0	429 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.13 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-B	0 / 36	-119.4 -119.4	0.16 (1)	10.00	N-C	-287 / 24	0.08 (1)
B-C	-3109 / 0	-119.4 -119.4	0.75 (1)	3.13	C-M	-602 / 0	0.56 (1)
C-D	-2621 / 0	-119.4 -119.4	0.67 (1)	3.47	M-D	0 / 460	0.10 (1)
D-E	-2309 / 0	-119.4 -119.4	0.40 (1)	4.89	D-K	0 / 1	0.00 (1)
E-F	-2622 / 0	-119.4 -119.4	0.67 (1)	3.47	K-E	0 / 461	0.10 (1)
F-G	-3108 / 0	-119.4 -119.4	0.75 (1)	3.13	K-F	-600 / 0	0.56 (1)
G-H	0 / 36	-119.4 -119.4	0.16 (1)	10.00	J-F	-288 / 23	0.08 (1)
O-B	-2246 / 0	0.0	0.23 (1)	5.61	B-N	0 / 2841	0.64 (1)
I-G	-2245 / 0	0.0	0.23 (1)	5.61	J-G	0 / 2841	0.64 (1)
O-N	0 / 0	-18.2	-18.2	0.14 (4)	10.00		
N-M	0 / 2814	-18.2	-18.2	0.54 (1)	10.00		
M-L	0 / 2308	-18.2	-18.2	0.47 (1)	10.00		
L-K	0 / 2308	-18.2	-18.2	0.47 (1)	10.00		
K-J	0 / 2814	-18.2	-18.2	0.55 (1)	10.00		
J-I	0 / 0	-18.2	-18.2	0.14 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 34.8 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.3 PSF

TOTAL LOAD = 48.1 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE

- PART 9 OF OBC 2012 (2019 AMENDMENT)

- CSA 086-14

- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.03")
 CALCULATED VERT. DEFL.(LL) = L/ 999 (0.14")
 ALLOWABLE DEFL.(TL) = L/360 (1.03")
 CALCULATED VERT. DEFL.(TL) = L/ 999 (0.27")

CSI: TC=0.75/0.97 (B-C:1) , BC=0.55/0.97 (J-K:1) ,
 WB=0.64/0.97 (B-N:1) , SSI=0.31/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
	MAX	MIN	MAX
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (O) (INPUT = 0.90)
 JSI METAL= 0.78 (L) (INPUT = 1.00)




JULY 14, 2023


READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0723-093	TRUSS OF PERMIT PLANS Oct 30 2023	8	1	TRUSS DESC.	MHP 23030

PER: 
CHIEF BUILDING OFFICIAL

Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:36:04 2023 Page 1
ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-N2yEjPqt5XM5So6YHaoxgiwHFeeBiWaOZdRilbyyE7P



TOTAL WEIGHT = 8 X 132 = 1053 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - I	2x4	DRY	No.2	SPF
I - K	2x4	DRY	No.2	SPF
R - B	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
R - O	2x4	DRY	No.2	SPF
O - L	2x4	DRY	No.2	SPF

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	8.0	1.50	3.00
C	TS-t	MT20	3.0	6.0		
D	TMWW-t	MT20	3.0	4.0	1.50	1.75
E	TMWW-t	MT20	3.0	4.0	1.75	0.75
F	TTW+p	MT20	4.0	5.0		
G	TMWW-t	MT20	3.0	4.0	1.75	0.75
H	TMWW-t	MT20	3.0	4.0	1.50	1.75
I	TS-t	MT20	3.0	6.0		
J	TMVW-t	MT20	4.0	8.0	1.50	3.00
L	BMV1+p	MT20	3.0	4.0		
M	BMWW-t	MT20	4.0	6.0	1.75	1.50
N	BMWW-t	MT20	3.0	4.0		
O	BSWWW-t	MT20	6.0	6.0		
P	BMWW-t	MT20	3.0	4.0		
Q	BMWW-t	MT20	4.0	6.0	1.75	1.50
R	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED		MAXIMUM FACTORED			INPUT	REQRD
	GROSS REACTION		GROSS REACTION			BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
R	2296	0	2296	0	0	5-8	3-15
L	2296	0	2296	0	0	5-8	3-15

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
R	1602	1174 / 0	0 / 0	0 / 0	0 / 0	429 / 0	0 / 0
L	1602	1174 / 0	0 / 0	0 / 0	0 / 0	429 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.45 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 - 1x4 LATERAL BRACE(S) AT 1/2 LENGTH OF G-O, E-O. DBS = 20-0-0 . CBF = 110 LBS.

DBS = DIAGONAL BRACE SPACING (MAX). CBF = CUMULATIVE BRACING FORCE (PER BRACE). FASTEN LATERAL BRACE(S) USING (0.122"x3") SPIRAL NAILS : 1 NAIL FOR 2x3 BRACE(S), 2 FOR 1x4, 2x4, 2x5, 3 FOR 2x6, 4 FOR 2x8, 5 FOR 2x10, AND 6 FOR 2x12.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MAX. FACTORED		FACTORED		MAX. FACTORED		FACTORED		
MEMB.	FORCE	VERT. LOAD	LC1	MAX	MAX.	MEMB.	MAX. FORCE	MAX
	(LBS)	(PLF)		CSI (LC)	UNBRAC		(LBS)	CSI (LC)
FR-TO		FROM	TO		LENGTH	FR-TO		
A-B	0 / 36	-119.4	-119.4	0.16 (1)	10.00	O-F	0 / 1428	0.32 (1)
B-C	-3065 / 0	-119.4	-119.4	0.55 (1)	3.45	O-G	-882 / 0	0.37 (1)
C-D	-3065 / 0	-119.4	-119.4	0.55 (1)	3.45	N-G	0 / 294	0.07 (1)
D-E	-2784 / 0	-119.4	-119.4	0.45 (1)	3.74	N-H	-334 / 0	0.23 (1)
E-F	-2174 / 0	-119.4	-119.4	0.42 (1)	4.16	M-H	-352 / 0	0.08 (1)
F-G	-2174 / 0	-119.4	-119.4	0.42 (1)	4.16	E-O	-882 / 0	0.37 (1)
G-H	-2784 / 0	-119.4	-119.4	0.45 (1)	3.74	P-E	0 / 294	0.07 (1)
H-I	-3065 / 0	-119.4	-119.4	0.55 (1)	3.45	D-P	-334 / 0	0.23 (1)
I-J	-3065 / 0	-119.4	-119.4	0.55 (1)	3.45	Q-D	-352 / 0	0.08 (1)
J-K	0 / 36	-119.4	-119.4	0.16 (1)	10.00	B-Q	0 / 2800	0.63 (1)
R-B	-2251 / 0	0.0	0.0	0.23 (1)	5.60	M-J	0 / 2800	0.63 (1)
L-J	-2251 / 0	0.0	0.0	0.23 (1)	5.60			
R-Q	0 / 0	-18.2	-18.2	0.10 (4)	10.00			
Q-P	0 / 2764	-18.2	-18.2	0.50 (1)	10.00			
P-O	0 / 2489	-18.2	-18.2	0.46 (1)	10.00			
O-N	0 / 2489	-18.2	-18.2	0.46 (1)	10.00			
N-M	0 / 2764	-18.2	-18.2	0.50 (1)	10.00			
M-L	0 / 0	-18.2	-18.2	0.10 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	34.8	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	48.1	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.03")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (1.03")
CALCULATED VERT. DEFL.(TL) = L/999 (0.27")

CSI: TC=0.55/0.97 (B-D:1) , BC=0.50/0.97 (P-Q:1)
WB=0.63/0.97 (B-Q:1) , SSI=0.26/1.00 (B-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (L) (INPUT = 0.90)
JSI METAL= 0.66 (Q) (INPUT = 1.00)



JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0723-093	TRUSS NAME OF PERMIT PLANS Oct 30 2023 PER: <i>Charna</i> CHIEF BUILDING OFFICIAL	1	1	TRUSS DESC.	MHP 23030


Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:36:05 2023 Page 1
ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-rEVcwlRvsrUy4yhlgHJACvTWR21qR1GXoHAGq1yyE7O

Scale = 1:45.0

PER: _____
CHIEF BUILDING OFFICIAL

Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:36:06 2023 Page 1
ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-JQ3_85r8d9cpi6FxO?qPI7?gaRNrAUTg1xwpMUyyE7N

Scale = 1:49.8



TOTAL WEIGHT = 74 lb

LUMBER

N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
L - A	2x4	DRY	No.2	SPF
G - E	2x4	DRY	No.2	SPF
L - H	2x4	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

J	T	PLATES	W	LEN	Y	X
A	TMWV-t	MT20	4.0	6.0		Edge
B	MMWV-t	MT20	3.0	4.0	1.50	1.75
C	TTW+p	MT20	3.0	4.0		
D	TMWV-t	MT20	3.0	4.0	1.50	1.75
E	MMWV-t	MT20	4.0	6.0	2.00	3.00
G	BMV1+p	MT20	2.0	4.0		
H	BS-t	MT20	3.0	4.0		
I	BMWV-t	MT20	4.0	4.0	1.50	1.50
J	BMWVW-t	MT20	4.0	6.0		
K	BMWV-t	MT20	4.0	4.0	1.50	1.50
L	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
L	1296	0	1296	0	0	MECHANICAL	
G	1459	0	1459	0	0	5-8	1-9

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT L. MINIMUM BEARING LENGTH AT JOINT L = 1-8.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	906	656 / 0	0 / 0	0 / 0	0 / 0	250 / 0	0 / 0
G	1017	750 / 0	0 / 0	0 / 0	0 / 0	267 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.70 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY
APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

C H O R D S					W E B S			
MAX. FACTORED		FACTORED			MAX. FACTORED			
MEMB.	FORCE	VERT. LOAD	LC1	MAX	MAX.	MEMB.	FORCE	MAX
	(LBS)	(PLF)	CSI (LC)		UNBRAC		(LBS)	CSI (LC)
FR-TO		FROM	TO		LENGTH	FR-TO		
A-B	-1675 / 0	-119.4	-119.4	0.37 (1)	4.70	J-C	0 / 687	0.15 (1)
B-C	-1263 / 0	-119.4	-119.4	0.35 (1)	5.27	J-D	-516 / 0	0.28 (1)
C-D	-1263 / 0	-119.4	-119.4	0.35 (1)	5.27	I-D	-185 / 34	0.04 (1)
D-E	-1675 / 0	-119.4	-119.4	0.37 (1)	4.70	B-J	-516 / 0	0.28 (1)
E-F	0 / 36	-119.4	-119.4	0.16 (1)	10.00	K-B	-184 / 34	0.04 (1)
L-A	-1257 / 0	0.0	0.0	0.13 (1)	7.10	A-K	0 / 1548	0.35 (1)
G-E	-1419 / 0	0.0	0.0	0.14 (1)	6.77	I-E	0 / 1548	0.35 (1)
L-K	0 / 0	-18.2	-18.2	0.09 (4)	10.00			
K-J	0 / 1524	-18.2	-18.2	0.29 (1)	10.00			
J-I	0 / 1524	-18.2	-18.2	0.29 (1)	10.00			
I-H	0 / 0	-18.2	-18.2	0.09 (4)	10.00			
H-G	0 / 0	-18.2	-18.2	0.09 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL	=	34.8	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.3	PSF
TOTAL LOAD				=	48.1 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.63")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.63")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.09")

CSI: TC=0.37/0.97 (A-B:1), BC=0.29/0.97 (J-K:1),
WB=0.35/0.97 (A-K:1), SSI=0.25/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (I) (INPUT = 0.90)
JSI METAL= 0.52 (I) (INPUT = 1.00)



JULY 14, 2023

**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTES: TRUSSES. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**



CORPORATION OF THE CITY OF OSHAWA

TRUSS NAME
OF PERMIT PLANS
Oct 30 2023

PER: *[Signature]*
CHIEF BUILDING OFFICIAL

TRUSS NO.
IM0723-093

QUANTITY
1

PLY
1

JOB DESC.
TRUSS DESC.

DRWG NO.
MHP 23030

Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:36:07 2023 Page 1

ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-oddMLRsmOSkgJGq7yiMeIKYoeripvr2qFbfMuwyE7M

3-9-0

3-9-0

3-9-0

7-6-0

5-6-12

13-0-12

5-9-4

18-10-0

Scale = 1:53.9

TOTAL WEIGHT = 87 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
K - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
K - G	2x4	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	4.0	4.0	1.50	1.75
B	TMVW-w	MT20	2.0	4.0		
C	TTWW-m	MT20	4.0	5.0	1.75	1.25
D	TMVW-t	MT20	3.0	4.0	1.50	1.75
E	TMVW-p	MT20	4.0	5.0	1.50	2.25
F	BMV1+p	MT20	2.0	4.0		
G	BS-t	MT20	3.0	4.0		
H	BMVW-t	MT20	4.0	4.0	1.50	1.50
I	BMVW-t	MT20	3.0	5.0		
J	BMVWW-t	MT20	5.0	6.0	2.25	2.00
K	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
K	1296	0	1296	0
F	1296	0	1296	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT K. MINIMUM BEARING LENGTH AT JOINT K = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. SNOW	MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
K	906	656 / 0	0 / 0	0 / 0	0 / 0	250 / 0	0 / 0
F	906	656 / 0	0 / 0	0 / 0	0 / 0	250 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.43 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

2x4 DRY SPF No.2 T-BRACE AT A-K

FASTEN T AND I-BRACES TO NARROW EDGE OF WEB WITH ONE ROW PER PLY OF 3" COMMON WIRE NAILS @ 6" O.C. WITH 3" MINIMUM END DISTANCE. BRACE MUST COVER 90% OF WEB LENGTH.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

C H O R D S				W E B S			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
K-A	-1266 / 0	0.0	0.0 0.32 (1)	A-J	0 / 1260	0.28 (1)	
A-B	-627 / 0	-119.4	-119.4 0.21 (1)	J-B	-550 / 0	0.43 (1)	
B-C	-627 / 0	-119.4	-119.4 0.21 (1)	J-C	-551 / 0	0.61 (1)	
C-D	-1036 / 0	-119.4	-119.4 0.50 (1)	I-C	0 / 503	0.11 (1)	
D-E	-1665 / 0	-119.4	-119.4 0.54 (1)	I-D	-753 / 0	0.65 (1)	
F-E	-1252 / 0	0.0	0.0 0.13 (1)	H-D	-111 / 74	0.03 (1)	
K-J	0 / 0	-18.2	-18.2 0.05 (4)	H-E	0 / 1538	0.35 (1)	
J-I	0 / 901	-18.2	-18.2 0.19 (1)				
I-H	0 / 1522	-18.2	-18.2 0.31 (1)				
H-G	0 / 0	-18.2	-18.2 0.14 (4)				
G-F	0 / 0	-18.2	-18.2 0.14 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 34.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 48.1 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.63")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.63")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.10")

CSI: TC=0.54/0.97 (D-E:1) , BC=0.31/0.97 (H-I:1) , WB=0.65/0.97 (D-I:1) , SSI=0.30/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (A) (INPUT = 0.90)
JSI METAL= 0.52 (H) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

