

| SITE NAME: TRINIGROUP          |           | BUILDER: GREENPARK HOMES |         | TYPE: ROSE 2 |      | GFA: 3005 |       | DATE: Feb-24<br>LO# 102622 |       | WINTER NATURAL AIR CHANGE RATE 0.354 |      | HEAT LOSS ΔT °F. 78 |      | CSA-F280-12      |     |
|--------------------------------|-----------|--------------------------|---------|--------------|------|-----------|-------|----------------------------|-------|--------------------------------------|------|---------------------|------|------------------|-----|
|                                |           |                          |         |              |      |           |       |                            |       | SUMMER NATURAL AIR CHANGE RATE 0.110 |      | HEAT GAIN ΔT °F. 13 |      | SB-12 PACKAGE A1 |     |
| ROOM USE                       | EXP. WALL | CLG. HT.                 | FACTORS | MBR          | ENS  | WIC       | BED-2 | BED-3                      | BED-4 | S-BATH                               | FLEX | ENS-2               |      |                  |     |
|                                |           |                          |         | 34           | 24   | 0         | 27    | 36                         | 18    | 6                                    | 14   | 6                   |      |                  |     |
|                                |           |                          |         | 9            | 9    | 9         | 9     | 9                          | 9     | 9                                    | 9    | 9                   |      |                  |     |
| GRS.WALL AREA                  | LOSS      | GAIN                     |         | 309          | 218  | 0         | 246   | 328                        | 164   | 55                                   | 127  | 55                  |      |                  |     |
| GLAZING                        | LOSS      | GAIN                     |         | LOSS         | GAIN | LOSS      | LOSS  | LOSS                       | LOSS  | LOSS                                 | LOSS | LOSS                |      |                  |     |
| NORTH                          | 21.8      | 16.0                     | 0       | 0            | 0    | 0         | 0     | 0                          | 0     | 0                                    | 0    | 0                   | 0    | 0                | 0   |
| EAST                           | 21.8      | 41.6                     | 0       | 0            | 0    | 0         | 0     | 0                          | 0     | 0                                    | 0    | 0                   | 0    | 0                | 0   |
| SOUTH                          | 21.8      | 24.9                     | 0       | 0            | 0    | 7         | 152   | 174                        | 0     | 0                                    | 0    | 0                   | 0    | 0                | 0   |
| WEST                           | 21.8      | 41.6                     | 22      | 479          | 914  | 16        | 349   | 665                        | 0     | 0                                    | 0    | 0                   | 0    | 0                | 0   |
| SKYLT.                         | 38.1      | 101.5                    | 0       | 0            | 0    | 0         | 0     | 0                          | 0     | 0                                    | 0    | 0                   | 0    | 0                | 0   |
| DOORS                          | 20.5      | 3.4                      | 0       | 0            | 0    | 0         | 0     | 0                          | 0     | 0                                    | 0    | 0                   | 0    | 0                | 0   |
| NET EXPOSED WALL               | 4.6       | 0.8                      | 287     | 1313         | 216  | 195       | 893   | 147                        | 0     | 0                                    | 0    | 48                  | 217  | 36               | 112 |
| NET EXPOSED BSMT WALL ABOVE GR | 3.7       | 0.6                      | 0       | 0            | 0    | 0         | 0     | 0                          | 0     | 0                                    | 0    | 0                   | 0    | 0                | 0   |
| EXPOSED CLG                    | 1.3       | 0.6                      | 402     | 528          | 236  | 145       | 190   | 85                         | 29    | 38                                   | 17   | 181                 | 238  | 106              | 211 |
| NO ATTIC EXPOSED CLG           | 2.8       | 1.3                      | 0       | 0            | 0    | 0         | 0     | 0                          | 0     | 0                                    | 0    | 0                   | 0    | 0                | 0   |
| EXPOSED FLOOR                  | 2.6       | 0.4                      | 0       | 0            | 0    | 0         | 0     | 0                          | 0     | 0                                    | 0    | 0                   | 0    | 0                | 0   |
| BASEMENT/CRAWL HEAT LOSS       |           |                          | 0       |              |      | 0         |       |                            | 0     |                                      |      | 0                   |      |                  |     |
| SLAB ON GRADE HEAT LOSS        |           |                          | 0       |              |      | 0         |       |                            | 0     |                                      |      | 0                   |      |                  |     |
| SUBTOTAL HT LOSS               |           |                          | 2320    |              | 1584 | 114       | 2590  | 2668                       | 1280  | 468                                  | 1612 |                     |      |                  |     |
| SUB TOTAL HT GAIN              |           |                          |         | 1366         | 1071 | 29        | 2164  | 2392                       | 624   | 254                                  | 951  |                     |      |                  |     |
| LEVEL FACTOR / MULTIPLIER      | 0.20      | 0.29                     |         |              |      | 0.20      | 0.29  |                            | 0.20  | 0.29                                 |      | 0.20                | 0.29 |                  |     |
| AIR CHANGE HEAT LOSS           |           |                          | 673     |              | 460  | 33        | 751   | 774                        | 371   | 136                                  | 468  |                     |      |                  |     |
| AIR CHANGE HEAT GAIN           |           |                          |         | 104          | 81   | 2         | 164   | 182                        | 47    | 19                                   | 72   |                     |      |                  |     |
| DUCT LOSS                      |           |                          | 0       |              | 0    | 15        | 334   | 0                          | 0     | 0                                    | 208  |                     |      |                  |     |
| DUCT GAIN                      |           |                          | 0       |              | 0    | 3         | 341   | 0                          | 0     | 0                                    | 102  |                     |      |                  |     |
| HEAT GAIN PEOPLE               | 240       | 2                        | 480     | 0            | 0    | 0         | 1     | 240                        | 1     | 240                                  | 0    | 0                   | 0    | 0                | 0   |
| HEAT GAIN APPLIANCES/LIGHTS    |           |                          | 839     |              | 0    | 0         | 839   | 839                        | 839   | 839                                  | 0    |                     |      |                  |     |
| TOTAL HT LOSS BTU/H            |           |                          | 2993    |              | 2044 | 162       | 3676  | 3442                       | 1651  | 604                                  | 2287 |                     |      |                  |     |
| TOTAL HT GAIN x 1.3 BTU/H      |           |                          |         | 3626         | 1498 | 45        | 4873  | 4749                       | 2276  | 355                                  | 1463 |                     |      |                  |     |

| ROOM USE                       | EXP. WALL | CLG. HT. | FACTORS | H-OFF | DIN  | KT/BF | FAM  | LAUN | PWD  | FOY  | MUD  | WOD  | BAS  |
|--------------------------------|-----------|----------|---------|-------|------|-------|------|------|------|------|------|------|------|
|                                |           |          |         | 10    | 32   | 37    | 34   | 7    | 12   | 31   | 15   | 44   | 174  |
|                                |           |          |         | 10    | 10   | 10    | 10   | 9    | 10   | 10   | 10   | 9    | 9    |
| GRS.WALL AREA                  | LOSS      | GAIN     |         | 101   | 323  | 374   | 343  | 64   | 121  | 313  | 152  | 374  | 1089 |
| GLAZING                        | LOSS      | GAIN     |         | LOSS  | LOSS | LOSS  | LOSS | LOSS | LOSS | LOSS | LOSS | LOSS | LOSS |
| NORTH                          | 21.8      | 16.0     | 0       | 0     | 0    | 0     | 0    | 0    | 0    | 0    | 0    | 0    | 0    |
| EAST                           | 21.8      | 41.6     | 0       | 0     | 0    | 0     | 0    | 0    | 0    | 0    | 0    | 0    | 0    |
| SOUTH                          | 21.8      | 24.9     | 22      | 479   | 548  | 29    | 632  | 722  | 0    | 0    | 0    | 0    | 0    |
| WEST                           | 21.8      | 41.6     | 0       | 0     | 0    | 52    | 1133 | 2161 | 0    | 0    | 0    | 0    | 0    |
| SKYLT.                         | 38.1      | 101.5    | 0       | 0     | 0    | 0     | 0    | 0    | 0    | 0    | 0    | 0    | 0    |
| DOORS                          | 20.5      | 3.4      | 0       | 0     | 0    | 0     | 0    | 0    | 0    | 0    | 0    | 0    | 0    |
| NET EXPOSED WALL               | 4.6       | 0.8      | 79      | 361   | 59   | 294   | 1344 | 221  | 322  | 1470 | 242  | 321  | 1468 |
| NET EXPOSED BSMT WALL ABOVE GR | 3.7       | 0.6      | 0       | 0     | 0    | 0     | 0    | 0    | 0    | 0    | 0    | 0    | 0    |
| EXPOSED CLG                    | 1.3       | 0.6      | 0       | 0     | 0    | 0     | 0    | 0    | 0    | 0    | 0    | 0    | 0    |
| NO ATTIC EXPOSED CLG           | 2.8       | 1.3      | 0       | 0     | 0    | 0     | 0    | 0    | 0    | 0    | 0    | 0    | 0    |
| EXPOSED FLOOR                  | 2.6       | 0.4      | 0       | 0     | 0    | 0     | 0    | 0    | 0    | 0    | 0    | 0    | 0    |
| BASEMENT/CRAWL HEAT LOSS       |           |          | 0       |       |      | 0     |      |      | 0    |      |      | 0    |      |
| SLAB ON GRADE HEAT LOSS        |           |          | 0       |       |      | 0     |      |      | 0    |      |      | 0    |      |
| SUBTOTAL HT LOSS               |           |          | 840     |       | 1976 | 2602  | 1948 | 370  | 743  | 2064 | 1027 |      |      |
| SUB TOTAL HT GAIN              |           |          |         | 607   | 943  | 2402  | 1156 | 83   | 540  | 1175 | 169  |      |      |
| LEVEL FACTOR / MULTIPLIER      | 0.30      | 0.52     |         |       |      | 0.30  | 0.52 |      | 0.30 | 0.52 |      | 0.30 | 0.52 |
| AIR CHANGE HEAT LOSS           |           |          | 440     |       | 1034 | 1362  | 1019 | 107  | 389  | 1080 | 538  |      |      |
| AIR CHANGE HEAT GAIN           |           |          |         | 46    | 72   | 183   | 88   | 6    | 41   | 89   | 13   |      |      |
| DUCT LOSS                      |           |          | 0       |       | 0    | 0     | 0    | 0    | 0    | 0    | 0    |      |      |
| DUCT GAIN                      |           |          | 0       |       | 0    | 0     | 0    | 0    | 0    | 0    | 0    |      |      |
| HEAT GAIN PEOPLE               | 240       | 0        | 0       | 0     | 0    | 0     | 0    | 0    | 0    | 0    | 0    | 0    | 0    |
| HEAT GAIN APPLIANCES/LIGHTS    |           |          | 839     |       | 839  | 839   | 839  | 839  | 839  | 839  | 839  |      |      |
| TOTAL HT LOSS BTU/H            |           |          | 1280    |       | 3010 | 3964  | 2967 | 477  | 1132 | 3145 | 1565 |      |      |
| TOTAL HT GAIN x 1.3 BTU/H      |           |          |         | 1940  | 2410 | 4451  | 2707 | 1207 | 755  | 1644 | 236  |      |      |

TOTAL HEAT GAIN BTU/H:

36851

TONS: 3.07

LOSS DUE TO VENTILATION LOAD BTU/H: 1670

STRUCTURAL HEAT LOSS: 53787

TOTAL COMBINED HEAT LOSS BTU/H: 55457

SITE NAME: TRINIGROUP  
BUILDER: GREENPARK HOMES

TYPE: ROSE 2

DATE: Feb-24

GFA: 3005 LO# 102622

HEATING CFM 1083 COOLING CFM 1083  
TOTAL HEAT LOSS 53,787 TOTAL HEAT GAIN 36,577  
AIR FLOW RATE CFM 20.13 AIR FLOW RATE CFM 29.61furnace pressure 0.7  
furnace filter 0.14  
a/c coil pressure 0.26  
available pressure  
for s/a & r/a 0.30#GOODMAN  
GMEC960603BNA 60  
FAN SPEED LOWAFUE = 96 %  
INPUT (BTU/H) = 60,000  
OUTPUT (BTU/H) = 57,600

| RUN COUNT | 4th | 3rd | 2nd | 1st | Bas |
|-----------|-----|-----|-----|-----|-----|
| S/A       | 0   | 0   | 14  | 8   | 5   |
| R/A       | 0   | 0   | 5   | 2   | 1   |

plenium pressure s/a 0.16  
max s/a dif press. loss 0.01  
min adjusted pressure s/a 0.15  
r/a pressure 0.14  
r/a grille press. Loss 0.02  
adjusted pressure r/a 0.12MEDLOW 928  
MEDIUM 1083  
HIGH 1131DESIGN CFM = 1083  
CFM @ .7" E.S.P.

TEMPERATURE RISE 49 °F

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5"Ø unless noted otherwise on layout.

| RUN #                     | 1    | 2    | 3    | 4     | 5     | 6     | 7      | 8    | 9     | 10   | 11    | 12    | 13   | 14    | 15    | 16   | 17   | 18   | 19   | 20   | 21   | 22   | 23   | 24   |
|---------------------------|------|------|------|-------|-------|-------|--------|------|-------|------|-------|-------|------|-------|-------|------|------|------|------|------|------|------|------|------|
| ROOM NAME                 | MBR  | ENS  | WIC  | BED-2 | BED-3 | BED-4 | S-BATH | FLEX | BED-2 | MBR  | ENS-2 | H-OFF | DIN  | KT/BF | KT/BF | FAM  | LAUN | PWD  | FOY  | MUD  | BAS  | BAS  | BAS  | BAS  |
| RM LOSS MBH.              | 1.50 | 1.02 | 0.16 | 1.84  | 1.72  | 1.65  | 0.60   | 2.29 | 1.84  | 1.50 | 0.66  | 1.28  | 3.01 | 1.98  | 1.98  | 2.97 | 0.48 | 1.13 | 3.14 | 1.56 | 3.75 | 3.75 | 3.75 | 3.75 |
| CFM PER RUN HEAT          | 30   | 21   | 3    | 37    | 35    | 33    | 12     | 46   | 37    | 30   | 13    | 26    | 61   | 40    | 40    | 60   | 10   | 23   | 63   | 32   | 75   | 75   | 75   | 75   |
| RM GAIN MBH.              | 1.81 | 0.75 | 0.05 | 2.44  | 2.37  | 2.28  | 0.36   | 1.46 | 2.44  | 1.81 | 0.15  | 1.94  | 2.41 | 2.23  | 2.23  | 2.71 | 1.21 | 0.76 | 1.64 | 0.24 | 0.44 | 0.44 | 0.44 | 0.44 |
| CFM PER RUN COOLING       | 54   | 22   | 1    | 72    | 70    | 67    | 11     | 43   | 72    | 54   | 4     | 57    | 71   | 66    | 66    | 80   | 36   | 22   | 49   | 7    | 13   | 13   | 13   | 13   |
| ADJUSTED PRESSURE         | 0.15 | 0.15 | 0.15 | 0.15  | 0.15  | 0.15  | 0.15   | 0.15 | 0.15  | 0.15 | 0.15  | 0.15  | 0.15 | 0.15  | 0.15  | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 |
| ACTUAL DUCT LGH.          | 48   | 43   | 45   | 59    | 71    | 48    | 51     | 57   | 63    | 45   | 51    | 48    | 37   | 36    | 29    | 20   | 35   | 56   | 56   | 17   | 36   | 34   | 16   | 45   |
| EQUIVALENT LENGTH         | 180  | 190  | 140  | 170   | 190   | 160   | 170    | 140  | 190   | 180  | 130   | 120   | 120  | 140   | 90    | 130  | 190  | 170  | 140  | 160  | 130  | 120  | 100  | 150  |
| TOTAL EFFECTIVE LENGTH    | 228  | 233  | 185  | 229   | 261   | 208   | 221    | 197  | 253   | 225  | 181   | 168   | 157  | 176   | 119   | 150  | 225  | 226  | 196  | 177  | 166  | 154  | 116  | 195  |
| ADJUSTED PRESSURE         | 0.06 | 0.06 | 0.08 | 0.06  | 0.06  | 0.07  | 0.07   | 0.07 | 0.06  | 0.06 | 0.08  | 0.09  | 0.09 | 0.08  | 0.12  | 0.1  | 0.06 | 0.06 | 0.07 | 0.08 | 0.09 | 0.09 | 0.13 | 0.07 |
| ROUND DUCT SIZE           | 5    | 4    | 4    | 6     | 6     | 6     | 4      | 5    | 6     | 5    | 4     | 5     | 5    | 5     | 5     | 6    | 5    | 4    | 6    | 4    | 6    | 6    | 6    | 6    |
| HEATING VELOCITY (ft/min) | 220  | 241  | 34   | 189   | 178   | 168   | 138    | 338  | 189   | 220  | 149   | 191   | 448  | 294   | 294   | 306  | 73   | 264  | 321  | 367  | 382  | 382  | 382  | 382  |
| COOLING VELOCITY (ft/min) | 396  | 252  | 11   | 367   | 357   | 342   | 126    | 316  | 367   | 396  | 46    | 419   | 521  | 485   | 485   | 408  | 264  | 252  | 250  | 80   | 66   | 66   | 66   | 66   |
| OUTLET GRILL SIZE         | 3X10 | 3X10 | 3X10 | 4X10  | 4X10  | 4X10  | 3X10   | 3X10 | 4X10  | 3X10 | 3X10  | 3X10  | 3X10 | 3X10  | 3X10  | 4X10 | 3X10 | 3X10 | 4X10 | 3X10 | 4X10 | 4X10 | 4X10 | 4X10 |
| TRUNK                     | C    | D    | C    | B     | A     | D     | C      | B    | B     | D    | C     | B     | C    | D     | E     | E    | C    | A    | A    | C    | D    | D    | E    | B    |

| RUN #                     | 25   | 26    | 27   |
|---------------------------|------|-------|------|
| ROOM NAME                 | BAS  | BED-3 | ENS  |
| RM LOSS MBH.              | 3.75 | 1.72  | 1.02 |
| CFM PER RUN HEAT          | 75   | 35    | 21   |
| RM GAIN MBH.              | 0.44 | 2.37  | 0.75 |
| CFM PER RUN COOLING       | 13   | 70    | 22   |
| ADJUSTED PRESSURE         | 0.15 | 0.15  | 0.15 |
| ACTUAL DUCT LGH.          | 53   | 69    | 51   |
| EQUIVALENT LENGTH         | 160  | 200   | 130  |
| TOTAL EFFECTIVE LENGTH    | 213  | 269   | 181  |
| ADJUSTED PRESSURE         | 0.07 | 0.05  | 0.08 |
| ROUND DUCT SIZE           | 6    | 6     | 4    |
| HEATING VELOCITY (ft/min) | 382  | 178   | 241  |
| COOLING VELOCITY (ft/min) | 66   | 357   | 252  |
| OUTLET GRILL SIZE         | 4X10 | 4X10  | 3X10 |
| TRUNK                     | A    | A     | D    |

## SUPPLY AIR TRUNK SIZE

|         | TRUNK<br>CFM | STATIC<br>PRESS. | ROUND<br>DUCT | RECT<br>DUCT | VELOCITY<br>(ft/min) |     | TRUNK<br>CFM | STATIC<br>PRESS. | ROUND<br>DUCT | RECT<br>DUCT | VELOCITY<br>(ft/min) |
|---------|--------------|------------------|---------------|--------------|----------------------|-----|--------------|------------------|---------------|--------------|----------------------|
| TRUNK A | 231          | 0.05             | 9.1           | 10           | x 8                  | 416 | TRUNK G      | 0                | 0.00          | 0            | 0 x 8 0              |
| TRUNK B | 452          | 0.05             | 11.7          | 16           | x 8                  | 509 | TRUNK H      | 0                | 0.00          | 0            | 0 x 8 0              |
| TRUNK C | 613          | 0.05             | 13.1          | 22           | x 8                  | 502 | TRUNK I      | 0                | 0.00          | 0            | 0 x 8 0              |
| TRUNK D | 295          | 0.06             | 9.5           | 10           | x 8                  | 531 | TRUNK J      | 0                | 0.00          | 0            | 0 x 8 0              |
| TRUNK E | 470          | 0.06             | 11.4          | 16           | x 8                  | 529 | TRUNK K      | 0                | 0.00          | 0            | 0 x 8 0              |
| TRUNK F | 0            | 0.00             | 0             | 0            | x 8                  | 0   | TRUNK L      | 0                | 0.00          | 0            | 0 x 8 0              |

## RETURN AIR TRUNK SIZE

|         | TRUNK<br>CFM | STATIC<br>PRESS. | ROUND<br>DUCT | RECT<br>DUCT | VELOCITY<br>(ft/min) |
|---------|--------------|------------------|---------------|--------------|----------------------|
| TRUNK O | 0            | 0.05             | 0             | 0 x 8        | 0                    |
| TRUNK P | 0            | 0.05             | 0             | 0 x 8        | 0                    |
| TRUNK Q | 0            | 0.05             | 0             | 0 x 8        | 0                    |
| TRUNK R | 0            | 0.05             | 0             | 0 x 8        | 0                    |
| TRUNK S | 0            | 0.05             | 0             | 0 x 8        | 0                    |
| TRUNK T | 0            | 0.05             | 0             | 0 x 8        | 0                    |
| TRUNK U | 0            | 0.05             | 0             | 0 x 8        | 0                    |
| TRUNK V | 0            | 0.05             | 0             | 0 x 8        | 0                    |
| TRUNK W | 195          | 0.05             | 8.6           | 8 x 8        | 439                  |
| TRUNK X | 1083         | 0.05             | 16.3          | 30 x 8       | 650                  |
| TRUNK Y | 895          | 0.05             | 15.1          | 26 x 8       | 620                  |
| TRUNK Z | 375          | 0.05             | 10.9          | 14 x 8       | 482                  |
| DROP    | 1083         | 0.05             | 16.3          | 24 x 10      | 650                  |

| RETURN AIR #       | 1    | 2    | 3    | 4    | 5    | 6    | 7    | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    | 17    | 18    | 19    | 20    | 21    | 22    | 23    | 24    |
|--------------------|------|------|------|------|------|------|------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| AIR VOLUME         | 115  | 95   | 85   | 85   | 95   | 100  | 320  | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     |
| PLENUM PRESSURE    | 0.12 | 0.12 | 0.12 | 0.12 | 0.12 | 0.12 | 0.12 | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  | 0.12  |
| ACTUAL DUCT LGH.   | 43   | 66   | 66   | 48   | 73   | 46   | 37   | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     |
| EQUIVALENT LENGTH  | 175  | 195  | 200  | 190  | 200  | 205  | 230  | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     |
| TOTAL EFFECTIVE LH | 218  | 261  | 266  | 238  | 273  | 251  | 267  | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     | 1     |
| ADJUSTED PRESSURE  | 0.06 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 0.05 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 | 12.40 |
| ROUND DUCT SIZE    | 6.7  | 6.5  | 6    | 6    | 6.5  | 6.7  | 10.3 | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     |
| INLET GRILL SIZE   | 8    | 8    | 8    | 8    | 8    | 8    | 8    | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     |
| INLET GRILL SIZE   | X    | X    | X    | X    | X    | X    | X    | X     | X     | X     | X     | X     | X     | X     | X     | X     | X     | X     | X     | X     | X     | X     | X     | X     |
| INLET GRILL SIZE   | 14   | 14   | 14   | 14   | 14   | 14   | 30   | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     | 0     |

CITY OF RICHMOND HILL  
BUILDING DIVISION

05/01/2024

RECEIVED  
Per: joshua.nabua

TYPE: ROSE 2  
SITE NAME: TRINIGROUP

LO # 102622

**RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY**

| COMBUSTION APPLIANCES |                                                                               | 9.32.3.1(1) |
|-----------------------|-------------------------------------------------------------------------------|-------------|
| a)                    | <input checked="" type="checkbox"/> Direct vent (sealed combustion) only      |             |
| b)                    | <input type="checkbox"/> Positive venting induced draft (except fireplaces)   |             |
| c)                    | <input type="checkbox"/> Natural draft, B-vent or induced draft gas fireplace |             |
| d)                    | <input type="checkbox"/> Solid Fuel (including fireplaces)                    |             |
| e)                    | <input type="checkbox"/> No Combustion Appliances                             |             |

| HEATING SYSTEM                                 |                                         |
|------------------------------------------------|-----------------------------------------|
| <input checked="" type="checkbox"/> Forced Air | <input type="checkbox"/> Non Forced Air |
| <input type="checkbox"/> Electric Space Heat   |                                         |

| HOUSE TYPE                            |                                                      | 9.32.1(2) |
|---------------------------------------|------------------------------------------------------|-----------|
| <input checked="" type="checkbox"/> I | Type a) or b) appliance only, no solid fuel          |           |
| <input type="checkbox"/> II           | Type I except with solid fuel (including fireplaces) |           |
| <input type="checkbox"/> III          | Any Type c) appliance                                |           |
| <input type="checkbox"/> IV           | Type I, or II with electric space heat               |           |
| <input type="checkbox"/>              | Other: Type I, II or IV no forced air                |           |

| SYSTEM DESIGN OPTIONS                 |                                               | O.N.H.W.P. |
|---------------------------------------|-----------------------------------------------|------------|
| <input type="checkbox"/> 1            | Exhaust only/Forced Air System                |            |
| <input type="checkbox"/> 2            | HRV with Ducting/Forced Air System            |            |
| <input checked="" type="checkbox"/> 3 | HRV Simplified/connected to forced air system |            |
| <input type="checkbox"/> 4            | HRV with Ducting/non forced air system        |            |
| <input type="checkbox"/>              | Part 6 Design                                 |            |

| TOTAL VENTILATION CAPACITY |                                     | 9.32.3.3(1) |
|----------------------------|-------------------------------------|-------------|
| Basement + Master Bedroom  | <u>2</u> @ 21.2 cfm <u>42.4</u> cfm |             |
| Other Bedrooms             | <u>3</u> @ 10.6 cfm <u>31.8</u> cfm |             |
| Kitchen & Bathrooms        | <u>5</u> @ 10.6 cfm <u>53</u> cfm   |             |
| Other Rooms                | <u>5</u> @ 10.6 cfm <u>53.0</u> cfm |             |
| Table 9.32.3.A.            | TOTAL <u>180.2</u> cfm              |             |

| PRINCIPAL VENTILATION CAPACITY REQUIRED |          | 9.32.3.4.(1) |
|-----------------------------------------|----------|--------------|
| 1 Bedroom                               | 31.8 cfm |              |
| 2 Bedroom                               | 47.7 cfm |              |
| 3 Bedroom                               | 63.6 cfm |              |
| 4 Bedroom                               | 79.5 cfm |              |
| 5 Bedroom                               | 95.4 cfm |              |
| TOTAL                                   | 79.5 cfm |              |

| SUPPLEMENTAL VENTILATION CAPACITY |                  | 9.32.3.5. |
|-----------------------------------|------------------|-----------|
| Total Ventilation Capacity        | <u>180.2</u> cfm |           |
| Less Principal Ventil. Capacity   | <u>79.5</u> cfm  |           |
| Required Supplemental Capacity    | <u>100.7</u> cfm |           |

| PRINCIPAL EXHAUST FAN CAPACITY |                                                  |
|--------------------------------|--------------------------------------------------|
| Model: VANEE V150H             | Location: BSMT                                   |
| <u>79.5</u> cfm                | <input checked="" type="checkbox"/> HVI Approved |

| PRINCIPAL EXHAUST HEAT LOSS CALCULATION |        |        |        |      |
|-----------------------------------------|--------|--------|--------|------|
| CFM                                     | ΔT °F  | FACTOR | % LOSS |      |
| 79.5 CFM                                | X 78 F | X 1.08 | X      | 0.25 |

| SUPPLEMENTAL FANS |                          | BY INSTALLING CONTRACTOR |                                     |       |
|-------------------|--------------------------|--------------------------|-------------------------------------|-------|
| Location          | Model                    | cfm                      | HVI                                 | Sones |
| ENS               | BY INSTALLING CONTRACTOR | 50                       | <input checked="" type="checkbox"/> | 3.5   |
| S-BATH            | BY INSTALLING CONTRACTOR | 50                       | <input checked="" type="checkbox"/> | 3.5   |
| ENS-2             | BY INSTALLING CONTRACTOR | 50                       | <input checked="" type="checkbox"/> | 3.5   |
| PWD               | BY INSTALLING CONTRACTOR | 50                       | <input checked="" type="checkbox"/> | 3.5   |

| HEAT RECOVERY VENTILATOR                             |                                                  | 9.32.3.11. |
|------------------------------------------------------|--------------------------------------------------|------------|
| Model: VANEE V150H                                   |                                                  |            |
| <u>150</u> cfm high                                  | <u>35</u> cfm low                                |            |
| <u>75</u> % Sensible Efficiency @ 32 deg F (0 deg C) | <input checked="" type="checkbox"/> HVI Approved |            |

| LOCATION OF INSTALLATION |                 |
|--------------------------|-----------------|
| Lot:                     | Concession      |
| Township                 | Plan:           |
| Address                  |                 |
| Roll #                   |                 |
| BUILDER:                 | GREENPARK HOMES |
| Name:                    |                 |
| Address:                 |                 |
| City:                    |                 |
| Telephone #:             | Fax #:          |

| INSTALLING CONTRACTOR |        |
|-----------------------|--------|
| Name:                 |        |
| Address:              |        |
| City:                 |        |
| Telephone #:          | Fax #: |

| DESIGNER CERTIFICATION                                                                                        |                         |
|---------------------------------------------------------------------------------------------------------------|-------------------------|
| I hereby certify that this ventilation system has been designed in accordance with the Ontario Building Code. |                         |
| Name:                                                                                                         | HVAC Designs Ltd.       |
| Signature:                                                                                                    | <i>Michael O'Rourke</i> |
| HRAI #                                                                                                        | 001820                  |
| Date:                                                                                                         | February-24             |

I REVIEW AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED IN THE APPROPRIATE CATEGORY AS AN "OTHER DESIGNER" UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.

INDIVIDUAL BCIN: 19669

MICHAEL O'ROURKE

*Michael O'Rourke*

CITY OF RICHMOND HILL  
BUILDING DIVISION

05/01/2024

RECEIVED  
Per: joshua.nabua

## CSA F280-12 Residential Heat Loss and Heat Gain Calculations

## Formula Sheet (For Air Leakage / Ventilation Calculation)

LO#: 102622

Model: ROSE 2

Builder: GREENPARK HOMES

Date: 2/14/2024

## Volume Calculation

## Air Change &amp; Delta T Data

## House Volume

| Level  | Floor Area (ft <sup>2</sup> ) | Floor Height (ft) | Volume (ft <sup>3</sup> ) |
|--------|-------------------------------|-------------------|---------------------------|
| Bsmt   | 1308                          | 9                 | 11118                     |
| First  | 1308                          | 10                | 13210.8                   |
| Second | 1687                          | 9                 | 15351.7                   |
| Third  | 0                             | 9                 | 0                         |
| Fourth | 0                             | 9                 | 0                         |
| Total: |                               |                   | 39,680.5 ft <sup>3</sup>  |
| Total: |                               |                   | 1123.6 m <sup>3</sup>     |

|                                |       |
|--------------------------------|-------|
| WINTER NATURAL AIR CHANGE RATE | 0.354 |
| SUMMER NATURAL AIR CHANGE RATE | 0.110 |

| Design Temperature Difference |                    |                     |       |       |
|-------------------------------|--------------------|---------------------|-------|-------|
|                               | T <sub>in</sub> °C | T <sub>out</sub> °C | ΔT °C | ΔT °F |
| Winter DTD <sub>h</sub>       | 22                 | -21                 | 43    | 78    |
| Summer DTD <sub>c</sub>       | 24                 | 31                  | 7     | 13    |

## 5.2.3.1 Heat Loss due to Air Leakage

## 6.2.6 Sensible Gain due to Air Leakage

$$HL_{airb} = LR_{airh} \times \frac{V_b}{3.6} \times DTD_h \times 1.2$$

$$0.354 \times 312.12 \times 43^\circ\text{C} \times 1.2 = 5727 \text{ W}$$

$$= 19540 \text{ Btu/h}$$

$$HG_{salb} = LR_{airc} \times \frac{V_b}{3.6} \times DTD_c \times 1.2$$

$$0.110 \times 312.12 \times 7^\circ\text{C} \times 1.2 = 294 \text{ W}$$

$$= 1003 \text{ Btu/h}$$

## 5.2.3.2 Heat Loss due to Mechanical Ventilation

## 6.2.7 Sensible heat Gain due to Ventilation

$$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E)$$

$$80 \text{ CFM} \times 78^\circ\text{F} \times 1.08 \times 0.25 = 1670 \text{ Btu/h}$$

$$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E)$$

$$80 \text{ CFM} \times 13^\circ\text{F} \times 1.08 \times 0.25 = 275 \text{ Btu/h}$$

## 5.2.3.3 Calculation of Air Change Heat Loss for Each Room (Floor Multiplier Section)

$$HL_{airr} = \text{Level Factor} \times HL_{airbv} \times \{(HL_{agcr} + HL_{bgcr}) \div (HL_{agclevel} + HL_{bgclevel})\}$$

| Level | Level Factor (LF) | HL <sub>airve</sub> Air Leakage + Ventilation Heat Loss (Btu/h) | Level Conductive Heat Loss: (HL <sub>clevel</sub> ) | Air Leakage Heat Loss Multiplier (LF x HL <sub>airbv</sub> / HL <sub>level</sub> ) |
|-------|-------------------|-----------------------------------------------------------------|-----------------------------------------------------|------------------------------------------------------------------------------------|
| 1     | 0.5               | 19,540                                                          | 8,958                                               | 1.091                                                                              |
| 2     | 0.3               |                                                                 | 11,201                                              | 0.523                                                                              |
| 3     | 0.2               |                                                                 | 13,472                                              | 0.290                                                                              |
| 4     | 0                 |                                                                 | 0                                                   | 0.000                                                                              |
| 5     | 0                 |                                                                 | 0                                                   | 0.000                                                                              |

\*HL<sub>airbv</sub> = Air leakage heat loss + ventilation heat loss\*For a balanced or supply only ventilation system HL<sub>airve</sub> = 0Michael O'Rourke  
BCIN# 19669CITY OF RICHMOND HILL  
BUILDING DIVISION

05/01/2024

RECEIVED  
Per: joshua.nabua

## HEAT LOSS AND GAIN SUMMARY SHEET

|                      |                                           |
|----------------------|-------------------------------------------|
| <b>MODEL:</b> ROSE 2 | <b>BUILDER:</b> GREENPARK HOMES           |
| <b>SFQT:</b> 3005    | <b>LO#</b> 102622 <b>SITE:</b> TRINIGROUP |

### DESIGN ASSUMPTIONS

|                      |    |                                |      |
|----------------------|----|--------------------------------|------|
| HEATING              | °F | COOLING                        | °F   |
| OUTDOOR DESIGN TEMP. | -6 | OUTDOOR DESIGN TEMP.           | 88   |
| INDOOR DESIGN TEMP.  | 72 | INDOOR DESIGN TEMP. (MAX 75°F) | 75   |
|                      |    | WINDOW SHGC                    | 0.50 |

### BUILDING DATA

|                                     |                 |                           |          |
|-------------------------------------|-----------------|---------------------------|----------|
| ATTACHMENT:                         | DETACHED        | # OF STORIES (+BASEMENT): | 3        |
| FRONT FACES:                        | EAST            | ASSUMED (Y/N):            | Y        |
| AIR CHANGES PER HOUR:               | 3.57            | ASSUMED (Y/N):            | Y        |
| AIR TIGHTNESS CATEGORY:             | AVERAGE         | ASSUMED (Y/N):            | Y        |
| WIND EXPOSURE:                      | SHELTERED       | ASSUMED (Y/N):            | Y        |
| HOUSE VOLUME (ft³):                 | 39680.5         | ASSUMED (Y/N):            | Y        |
| INTERNAL SHADING:                   | BLINDS/CURTAINS | ASSUMED OCCUPANTS:        | 5        |
| INTERIOR LIGHTING LOAD (Btu/h/ft²): | 1.95            | DC BRUSHLESS MOTOR (Y/N): | Y        |
| FOUNDATION CONFIGURATION            | BCIN_1          | DEPTH BELOW GRADE:        | 5.5 ft   |
| LENGTH: 53.0 ft                     | WIDTH: 34.0 ft  | EXPOSED PERIMETER:        | 174.0 ft |

### 2012 OBC - COMPLIANCE PACKAGE

#### Component

#### Compliance Package A1

| Nominal | Min. Eff. |
|---------|-----------|
|---------|-----------|

|                                                                            |       |       |
|----------------------------------------------------------------------------|-------|-------|
| Ceiling with Attic Space Minimum RSI (R)-Value                             | 60    | 59.22 |
| Ceiling Without Attic Space Minimum RSI (R)-Value                          | 31    | 27.65 |
| Exposed Floor Minimum RSI (R)-Value                                        | 31    | 29.80 |
| Walls Above Grade Minimum RSI (R)-Value                                    | 22    | 17.03 |
| Basement Walls Minimum RSI (R)-Value                                       | 20 ci | 21.12 |
| Below Grade Slab Entire surface > 600 mm below grade Minimum RSI (R)-Value | -     | -     |
| Edge of Below Grade Slab ≤ 600 mm Below Grade Minimum RSI (R)-Value        | 10    | 10    |
| Heated Slab or Slab ≤ 600 mm below grade Minimum RSI (R)-Value             | 10    | 11.13 |
| Windows and Sliding Glass Doors Maximum U-Value                            | 0.28  | -     |
| Skylights Maximum U-Value                                                  | 0.49  | -     |
| Space Heating Equipment Minimum AFUE                                       | 96%   | -     |
| HRV/ERV Minimum Efficiency                                                 | 75%   | -     |
| Domestic Hot Water Heater Minimum EF                                       | 0.8   | -     |

INDIVIDUAL BCIN: 19669  
MICHAEL O'ROURKE




CITY OF RICHMOND HILL  
BUILDING DIVISION

05/01/2024

RECEIVED  
Per: joshua.nabua

# Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

| Weather Station Description    |                                           |                                                                                                                 |
|--------------------------------|-------------------------------------------|-----------------------------------------------------------------------------------------------------------------|
| Province:                      | Ontario                                   |                                                                                                                 |
| Region:                        | Richmond Hill                             |                                                                                                                 |
| Site Description               |                                           |                                                                                                                 |
| Soil Conductivity:             | Normal conductivity: dry sand, loam, clay |                                                                                                                 |
| Water Table:                   | Normal (7-10 m, 23-33 ft)                 |                                                                                                                 |
| Foundation Dimensions          |                                           |                                                                                                                 |
| Floor Length (m):              | 16.2                                      | <br>Insulation Configuration |
| Floor Width (m):               | 10.4                                      |                                                                                                                 |
| Exposed Perimeter (m):         | 0.0                                       |                                                                                                                 |
| Wall Height (m):               | 2.6                                       |                                                                                                                 |
| Depth Below Grade (m):         | 1.68                                      |                                                                                                                 |
| Window Area (m <sup>2</sup> ): | 0.8                                       |                                                                                                                 |
| Door Area (m <sup>2</sup> ):   | 2.0                                       |                                                                                                                 |
| Radiant Slab                   |                                           |                                                                                                                 |
| Heated Fraction of the Slab:   | 0                                         |                                                                                                                 |
| Fluid Temperature (°C):        | 33                                        |                                                                                                                 |
| Design Months                  |                                           |                                                                                                                 |
| Heating Month                  | 1                                         |                                                                                                                 |
| Foundation Loads               |                                           |                                                                                                                 |
| Heating Load (Watts):          |                                           | 1745                                                                                                            |

TYPE: ROSE 2  
LO# 102622

Michael O'Rourke BCIN #19669

CITY OF RICHMOND HILL  
BUILDING DIVISION


05/01/2024

  
**RECEIVED**  
Per: joshua.nabua

# Air Infiltration Residential Load Calculator

Supplemental tool for CAN/CSA-F280

| Weather Station Description       |                            |                        |    |    |
|-----------------------------------|----------------------------|------------------------|----|----|
| Province:                         | Ontario                    |                        |    |    |
| Region:                           | Richmond Hill              |                        |    |    |
| Weather Station Location:         | Open flat terrain, grass   |                        |    |    |
| Anemometer height (m):            | 10                         |                        |    |    |
| Local Shielding                   |                            |                        |    |    |
| Building Site:                    | Suburban, forest           |                        |    |    |
| Walls:                            | Heavy                      |                        |    |    |
| Flue:                             | Heavy                      |                        |    |    |
| Highest Ceiling Height (m):       | 7.68                       |                        |    |    |
| Building Configuration            |                            |                        |    |    |
| Type:                             | Detached                   |                        |    |    |
| Number of Stories:                | Two                        |                        |    |    |
| Foundation:                       | Full                       |                        |    |    |
| House Volume (m <sup>3</sup> ):   | 1123.6                     |                        |    |    |
| Air Leakage/Ventilation           |                            |                        |    |    |
| Air Tightness Type:               | Present (1961-) (3.57 ACH) |                        |    |    |
| Custom BDT Data:                  | ELA @ 10 Pa.               | 1497.8 cm <sup>2</sup> |    |    |
|                                   | 3.57                       | ACH @ 50 Pa            |    |    |
| Mechanical Ventilation (L/s):     | Total Supply               | Total Exhaust          |    |    |
|                                   | 37.5                       | 37.5                   |    |    |
| Flue Size                         |                            |                        |    |    |
| Flue #:                           | #1                         | #2                     | #3 | #4 |
| Diameter (mm):                    | 0                          | 0                      | 0  | 0  |
| Natural Infiltration Rates        |                            |                        |    |    |
| Heating Air Leakage Rate (ACH/H): | 0.354                      |                        |    |    |
| Cooling Air Leakage Rate (ACH/H): | 0.110                      |                        |    |    |

TYPE: ROSE 2  
LO# 102622

Michael O'Rourke BCIN# 19669




ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD. & MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

INSTALLATION TO COMPLY WITH THE LATEST ONTARIO BUILDING CODE. ALL SUPPLY BRANCH OUTLETS SHALL BE EQUIPPED WITH MANUAL BALANCING DAMPER. DUCTWORK WHICH PASSES THROUGH THE GARAGE OR UNHEATED SPACES SHALL BE ADEQUATELY INSULATED AND GAS-PROOFED


ALL S/A DIFFUSERS "4x10" UNLESS NOTED OTHERWISE ON LAYOUT. ALL S/A RUNS 5"ø UNLESS NOTED OTHERWISE ON LAYOUT. UNDERCUT DOORS 1" min. FOR R/A

SUPPLEMENTAL EXHAUST FAN (MINIMUM 100 CFM) DISCHARGING DIRECTLY TO THE EXTERIOR WILL BE PROVIDED IN THE KITCHEN. EXHAUST DUCTS SERVING THE KITCHEN SHALL BE SMALLER THAN RECOMMENDED BY THE MANUFACTURER OF THE FANS AND MUST AT LEAST MEET O.B.C. STATED MINIMUMS.


- 1.Laundry dryer exhaust duct shall be provided as per OBC 2012 Div.B 6.2.3.8(7).
- 2.Kitchen hood exhaust duct shall be provided as per OBC 2012, Div.B 9.32.3.10, 9.32.3.5(2).
- 3.Minimum R-12 Insulation Value required for ducts installed at unheated or exposed condition (OBC 2012 Div.B 6.2.4.3(10) and seal the ducts as per 6.2.4.3(11) & HRAI Digest 2005, Clause 4.5.
- 4.Penetration of Air Barrier System by ducts, wires, conduits or building materials shall be sealed as per OBC 2012, Div.B 9.25.3.3.(9) & (10).
- 5.Volume control dampers to all branches to be installed per OBC 2012, Div.B, 6.2.4.5.
- 6.Space between studs and joists used as return ducts shall be separated from unused portion as per OBC 2012 Div.B 6.2.4.7(6)




Partial Basement Plan For Deck Condition Elevation '1', '2' and '3'



Basement Plan '1'



Basement Plan '3'



Basement Plan '2'

**Richmond Hill** City of Richmond Hill Building Division

**REVIEWED**


By: **PV** Date: **May/14/2024**

Building Permit #: **RM#24-00017**


All construction shall comply with the Ontario Building Code and all other applicable statutory regulations. The reviewed documents must be kept on site at all times.

Building inspection line: 905-771-5465 (24 hr)  
buildinginspections@richmondhill.ca  
Building inquiry line 905-771-8810  
building@richmondhill.ca


Ensure that R-Values and U-Values used for heat loss and heat gain calculations are consistent with the values specified by SB-12 Prescriptive Package: **A1** and the values used for architectural design.



Ground Floor Plan '1'



Ground Floor Plan '3'



Ground Floor Plan '2'

- 13.Exterior insulation effective R-Value for wall, roof or exposed floor shall be maintained at the respective location where duct or sanitary pipes are routed inside exterior envelope.
14. Return air intake shall be provided as recommended in HRAI Digest 2005 Section 4.7 Return air inlet should be positioned so that short circuiting of supply air is avoided. A high and low wall return air combination shall be provided when a combined cooling & heating system is installed.
15. For simplified HRV/ERV installation, with stale air and fresh air connected to return air plenum, stale air intake and fresh air supply shall be separated minimum 3' or as recommended by HRV/ERV Manufacturer.

7. Combustion air supply shall be provided to the furnace and hot water tank.

- 8.HRV installation, testing, startup and commissioning shall be in compliance with OBC 2012, Div.B 9.32.3.11, 9.32.3.11(7)&(10)


9. HRV duct connection shall be in compliance with OBC 2012 Div.B 9.32.3.6(3) & 9.32.3.4(7).

10. Supply air grill at finished basement shall be at low level. Return air grill for finished or unfinished basement shall be at low level. HRAI digest 2005, clause 7.7(3).


**Richmond Hill** City of Richmond Hill Building Division

**HVAC REVIEWED**


Initials: **PXV**



Second Floor Plan '1'



Second Floor Plan '2'



Second Floor Plan '3'

| HEAT LOSS 52442 BTU/H |                      | # OF RUNS |    |   |   |
|-----------------------|----------------------|-----------|----|---|---|
| UNIT DATA             |                      | 3RD FLOOR |    |   |   |
| MAKE                  | GOODMAN              | 2ND FLOOR | 14 | 5 | 5 |
| MODEL                 | GMEC960603BNA        | 1ST FLOOR | 8  | 2 | 2 |
| INPUT                 | 60.0 MBTU/H          | BASEMENT  | 5  | 1 | 0 |
| OUTPUT                | 57.6 MBTU/H          |           |    |   |   |
| COOLING               | 3.0 TONS             |           |    |   |   |
| FAN SPEED             | 1083 cfm @ 0.6" w.c. |           |    |   |   |

| HVAC LEGEND                                                                           |                                    |
|---------------------------------------------------------------------------------------|------------------------------------|
|    | SUPPLY AIR GRILLE                  |
|    | SUPPLY AIR GRILLE 6" BOOT          |
|    | LINEAR BAR or LINEAR SLOT GRILLE   |
|    | SUPPLY AIR BOOT ABOVE              |
|    | 6" SUPPLY AIR BOOT ABOVE           |
|    | SUPPLY AIR STACK                   |
|    | 6" SUPPLY AIR STACK                |
|    | 14X8 RETURN AIR GRILLE             |
|    | 30X8 RETURN AIR GRILLE             |
|    | FLOOR RETURN AIR GRILLE            |
|    | RETURN STACK ABOVE                 |
|    | RETURN AIR STACK                   |
|    | REDUCER                            |
|    | SUPPLY DUCTWORK                    |
|    | RETURN DUCTWORK                    |
|    | FLEX DUCT                          |
|    | EXHAUST FAN                        |
|    | LINT TRAP by REVERSOMATIC          |
| DV                                                                                    | DIRECT VENT                        |
| LW                                                                                    | LOW WALL                           |
| HW                                                                                    | HIGH WALL                          |
| CLG.                                                                                  | CEILING                            |
| Z.D.                                                                                  | MOTORIZED ZONE DAMPER              |
| M.D.                                                                                  | MOTORIZED DAMPER                   |
|  | EXHAUST PIPE                       |
|  | CONCENTRIC VENT KIT                |
|  | CONCENTRIC HRV or ERV VENT KIT     |
|  | SINGLE WALL BOX<br>by REVERSOMATIC |
|  | DOUBLE WALL BOX<br>by REVERSOMATIC |
|  | TRIPLE WALL BOX<br>by REVERSOMATIC |
|  | DRYER BOOSTER FAN                  |

|     |                   |         |    |
|-----|-------------------|---------|----|
| 2   |                   |         |    |
| 1   | ISSUED FOR PERMIT | SEPT/23 | YV |
| Rev | Revision          | Date    | By |

SB-12 PACKAGE **A1**

Michael Offutt has reviewed and is responsible for the design work and is qualified under division C.2.2 of the building code.

Michael Offutt BCMA 1999 HVAC Design Ltd.

**HVACDESIGNS LTD.**

375 Finley Ave - Unit 202 - Ajax, Ontario L1S 2E2  
Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375  
Email: info@hvacdesigns.ca  
Web: www.hvacdesigns.ca

Specializing in Residential Mechanical Design Services

|              |                                   |
|--------------|-----------------------------------|
| Client       | GREENPARK HOMES                   |
| Project Name | TRINIGROUP RICHMOND HILL, ONTARIO |
|              | <b>ROSE 2</b>                     |
|              | 3005 SQFT                         |
| Sheet Title  | HVAC HEATING LAYOUT               |
| Drawn By     | YV                                |
| Scale        | 3/16"=1'-0"                       |
| Date         | SEPTEMBER 2023                    |
| LO #         | 102622                            |