


05/01/2024

RECEIVED

Per: Joshua Nabua



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC
2012(2019 AMENDMENT)
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 31.3 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

 **DENOTES:**
CONVENTIONAL
FRAMING

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)
H2.5T - (I)

DB - DROPPED BEAM BY OTHERS

M15637



Job Track: **53256**
Plan Log: **207462**
Layout ID: **434351**

Builder / Location:

GREENPARK HOMES / RICHMOND HILLProject: **TRINIGROUP DEVELOPMENTS**

Date: 2023-08-24

Sales:

Rick DiCiano

Designer: JC

Model / Elevation:

ROSE 3 / 1

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mitek ver 8.6.3.353

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua

ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.


DESIGN CONFORMS WITH OBC
2012(2019 AMENDMENT)
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 31.3 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

 **DENOTES:**
CONVENTIONAL
FRAMING

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)
H2.5T - (I)

DB - DROPPED BEAM BY OTHERS



M15637



Job Track: **53256**
Plan Log: **207462**
Layout ID: **434590**

Builder / Location:

GREENPARK HOMES / RICHMOND HILL

Project: **TRINIGROUP DEVELOPMENTS**

Date: 2023-08-24 Sales: Rick DiCiano Designer: JC

Model / Elevation:

ROSE 3 / 1-REAR UPG

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mitek ver 8.6.3.353

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua

ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC
2012(2019 AMENDMENT)
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 31.3 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

 DENOTES:
CONVENTIONAL
FRAMING

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)



M15637



Job Track: 53256

Plan Log: 207462

Layout ID: 434355

Builder / Location:

GREENPARK HOMES / RICHMOND HILL

Project: TRINIGROUP DEVELOPMENTS

Date: 2023-08-24

Sales: Rick DiCiano

Designer: JC

Model / Elevation:

ROSE 3 / 2


THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mitek ver 8.6.3.353

05/01/2024

RECEIVED

Per: joshua.nabua



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC
2012(2019 AMENDMENT)
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 31.3 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

 DENOTES:
CONVENTIONAL
FRAMING

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)

M15637



Job Track: **53256**
Plan Log: **207462**
Layout ID: **434591**

Builder / Location:

GREENPARK HOMES / RICHMOND HILLProject: **TRINIGROUP DEVELOPMENTS**

Date: 2023-08-24 Sales: Rick DiCiano Designer: JC

Model / Elevation:

ROSE 3 / 2-REAR UPG

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mitek ver 8.6.3.353

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua

ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC
2012(2019 AMENDMENT)
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 31.3 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

 DENOTES:
CONVENTIONAL
FRAMING

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)



M15637



Job Track: **53256**
Plan Log: **207462**
Layout ID: **434357**

Builder / Location:

GREENPARK HOMES / RICHMOND HILL

Model / Elevation:

ROSE 3 / 3

Project: **TRINIGROUP DEVELOPMENTS**

Date: 2023-08-24 Sales: Rick DiCiano Designer: JC

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mitek ver 8.6.3.353

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 1

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434351
 Ref #
 Page: 1 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Hip Girder	6 /12	31-00-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	336.84 206.67		
	1	T2 Hip	6 /12	31-00-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	126.87 80.17		
	1	T3 Hip	6 /12	31-00-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	126.51 80.00		
	1	T4 Hip	6 /12	31-00-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	127.93 80.00		
	1	T5 Hip	6 /12	31-00-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	128.89 81.83		
	11	T6 Common	6 /12	31-00-00	8-11-00	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1431.35 885.50		
	1	T7 Hip Girder	10 /12	31-00-00	4-10-07	2 x 4 2 x 6	1-03-08	1-07-11 3-03-11	154.03 97.50		
	1	T8 Hip	10 /12	31-00-00	4-10-07	2 x 4	1-03-08	1-07-11 3-03-11	127.21 81.17		
	3	T9 Hip	10 /12	31-00-00	6-06-07	2 x 4	1-03-08	1-07-11 3-03-11	417.81 259.50		
	1 2-ply	T10 Hip Girder	10 /12	25-06-00	4-06-11	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	251.01 156.00		
	1	T11 Hip	10 /12	25-06-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	113.9 73.33		
	1 2-ply	T14 Hip Girder	10 /12	14-06-00	3-01-03	2 x 6		1-07-11 1-07-11	179.34 116.00		
	1 2-ply	T15 Hip Girder	6 /12	17-00-00	4-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	130.66 84.67		
	2	T19 Common	10 /12	11-10-00	6-06-14	2 x 4		1-07-11 1-07-11	96.78 60.67		

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 1

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434351
 Ref #
 Page: 2 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	G19 GABLE	10 /12	11-10-00	6-06-14	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	57.55 37.00		
	1 2-ply	T20 Half Hip Girder	12 /12	18-05-00	2-00-15	2 x 4	1-03-08	1-03-04 1-07-12	132.71 89.33		
	1	T21 Half Hip	12 /12	7-01-00	3-00-15	2 x 4	1-03-08	1-03-04 2-07-12	30.88 21.50		
	1	T22 Half Hip	12 /12	7-01-00	3-09-03	2 x 4	1-03-08	1-03-04 3-04-00	32.77 22.17		
	1 2-ply	T23 Monopitch Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	1 2-ply	T24 Monopitch Girder	10 /12	3-10-08	4-10-07	2 x 4 2 x 6		1-07-11 4-10-07	44.83 30.67		
	1 2-ply	T25 Monopitch Girder	10 /12	3-06-00	4-06-11	2 x 4 2 x 6		1-07-11 4-06-11	41.09 27.00		
	1 2-ply	T26 Half Hip Girder	10 /12	3-06-00	3-04-08	2 x 4 2 x 6		1-07-11 3-04-08	44.84 31.67		
	8	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	134.36 85.33		
	2	J2 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	30.28 19.33		
	4	J3 Jack-Open	10 /12	3-06-00	4-06-11	2 x 4	1-03-08	1-07-11 4-06-11	56.62 38.67		
	7	J4 Jack-Open	10 /12	1-09-00	3-01-03	2 x 4	1-03-08	1-07-11 3-01-03	66.93 49.00		
	1	J5 Jack-Open	10 /12	2-01-00	3-04-08	2 x 4	1-03-08	1-07-11 3-04-08	10.51 7.67		
	6	J7W Jack-Open	4 /12	5-07-00	2-10-08	2 x 4	1-03-08	3-15 2-02-04	114.48 76.00		

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 1

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434351
 Ref #
 Page: 3 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	10	J8 Jack-Open	6 /12	2-02-00	2-00-11	2 x 4	1-03-08	6-12 1-07-12	77.11 60.00		
	3	C1 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	21.06 14.00		
	3	C2 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	28.71 18.00		
	3	C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	34.75 22.00		
	3	C4 Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	42.4 26.00		
	1	C5 Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 1-01	1-07-11 3-01-09	9.76 7.00		
	1	C6 Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 1-08-09	1-07-11 3-01-09	11.61 8.33		

TOTAL # TRUSS= 96

TOTAL BFT OF ALL TRUSSES= 3071.35

BFT.

TOTAL WEIGHT OF ALL TRSSES 4830.74 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
6	Hardware	H2.5T	
2	Hardware	HGUS26-2	
7	Hardware	LJS26DS	
6	Hardware	LUS24	
3	Hardware	LUS26-2	


TOTAL NUMBER OF ITEMS= 24

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 1-REAR UPG

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434590
 Ref #
 Page: 1 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Hip Girder	6 /12	31-00-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	336.84 206.67		
	1	T2 Hip	6 /12	31-00-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	126.87 80.17		
	1	T3 Hip	6 /12	31-00-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	126.51 80.00		
	1	T4 Hip	6 /12	31-00-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	127.93 80.00		
	1	T5 Hip	6 /12	31-00-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	128.89 81.83		
	11	T6 Common	6 /12	31-00-00	8-11-00	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1431.35 885.50		
	1	T7 Hip Girder	10 /12	31-00-00	4-10-07	2 x 4 2 x 6	1-03-08	1-07-11 3-03-11	154.03 97.50		
	1	T8 Hip	10 /12	31-00-00	4-10-07	2 x 4	1-03-08	1-07-11 3-03-11	127.21 81.17		
	3	T9 Hip	10 /12	31-00-00	6-06-07	2 x 4	1-03-08	1-07-11 3-03-11	417.81 259.50		
	1 2-ply	T10 Hip Girder	10 /12	25-06-00	4-06-11	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	251.01 156.00		
	1	T11 Hip	10 /12	25-06-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	113.9 73.33		
	1 2-ply	T14 Hip Girder	10 /12	14-06-00	3-01-03	2 x 6		1-07-11 1-07-11	179.34 116.00		
	3	T16 Common	6 /12	17-00-00	5-05-00	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	198.4 125.50		
	1	G16 GABLE	6 /12	17-00-00	5-05-00	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	67.72 43.83		

OFFICE OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 1-REAR UPG

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434590
 Ref #
 Page: 2 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	T19 Common	10 / 12	11-10-00	6-06-14	2 x 4		1-07-11 1-07-11	96.78 60.67		
	1	G19 GABLE	10 / 12	11-10-00	6-06-14	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	57.55 37.00		
	1 2-ply	T20 Half Hip Girder	12 / 12	18-05-00	2-00-15	2 x 4	1-03-08	1-03-04 1-07-12	132.71 89.33		
	1	T21 Half Hip	12 / 12	7-01-00	3-00-15	2 x 4	1-03-08	1-03-04 2-07-12	30.88 21.50		
	1	T22 Half Hip	12 / 12	7-01-00	3-09-03	2 x 4	1-03-08	1-03-04 3-04-00	32.77 22.17		
	1 2-ply	T23Z Monopitch Girder	6 / 12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	1 2-ply	T24 Monopitch Girder	10 / 12	3-10-08	4-10-07	2 x 4 2 x 6		1-07-11 4-10-07	44.83 30.67		
	1 2-ply	T25 Monopitch Girder	10 / 12	3-06-00	4-06-11	2 x 4		1-07-11 4-06-11	35.7 24.00		
	1 2-ply	T26 Half Hip Girder	10 / 12	3-06-00	3-04-08	2 x 4		1-07-11 3-04-08	39.95 27.67		
	4	J1 Jack-Open	6 / 12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	67.18 42.67		
	2	J2 Jack-Open	10 / 12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	30.28 19.33		
	4	J3 Jack-Open	10 / 12	3-06-00	4-06-11	2 x 4	1-03-08	1-07-11 4-06-11	56.62 38.67		
	7	J4 Jack-Open	10 / 12	1-09-00	3-01-03	2 x 4	1-03-08	1-07-11 3-01-03	66.93 49.00		
	1	J5 Jack-Open	10 / 12	2-01-00	3-04-08	2 x 4	1-03-08	1-07-11 3-04-08	10.51 7.67		

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 1-REAR UPG

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434590
 Ref #
 Page: 3 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	6	J7W Jack-Open	4 /12	5-07-00	2-10-08	2 x 4	1-03-08	3-15 2-02-04	114.48 76.00		
	10	J8 Jack-Open	6 /12	2-02-00	2-00-11	2 x 4	1-03-08	6-12 1-07-12	77.11 60.00		
	1	C1 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	7.02 4.67		
	1	C2 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	9.57 6.00		
	1	C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	11.58 7.33		
	1	C4 Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	14.13 8.67		
	1	C5 Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 1-01	1-07-11 3-01-09	9.76 7.00		
	1	C6 Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 1-08-09	1-07-11 3-01-09	11.61 8.33		

TOTAL # TRUSS= 86

TOTAL BFT OF ALL TRUSSES= 3053.02

BFT.

TOTAL WEIGHT OF ALL TRSSES 4804.13 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
6	Hardware	H2.5T	
1	Hardware	HGUS26-2	
10	Hardware	LJS26DS	
4	Hardware	LUS24	
3	Hardware	LUS26-2	


TOTAL NUMBER OF ITEMS= 24

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 2

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434355
 Ref #
 Page: 1 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses


PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Hip Girder	6 /12	31-00-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	336.84 206.67		
	1	T2 Hip	6 /12	31-00-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	126.87 80.17		
	1	T3 Hip	6 /12	31-00-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	126.51 80.00		
	1	T4 Hip	6 /12	31-00-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	127.93 80.00		
	1	T5 Hip	6 /12	31-00-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	128.89 81.83		
	11	T6 Common	6 /12	31-00-00	8-11-00	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1431.35 885.50		
	1	T7Z Hip Girder	10 /12	31-00-00	4-10-07	2 x 4 2 x 6	1-03-08	1-07-11 3-03-11	154.03 97.50		
	1	T8 Hip	10 /12	31-00-00	4-10-07	2 x 4	1-03-08	1-07-11 3-03-11	127.21 81.17		
	3	T9 Hip	10 /12	31-00-00	6-06-07	2 x 4	1-03-08	1-07-11 3-03-11	417.81 259.50		
	1 2-ply	T12 Roof Special Girder	10 /12	25-06-00	5-03-12	2 x 4 2 x 6	1-03-08	1-07-11 2-07-11	269.7 171.00		
	1	T13 Roof Special	10 /12	25-06-00	6-11-12	2 x 4	1-03-08	1-07-11 2-07-11	124.64 80.83		
	1 2-ply	T14Z Hip Girder	10 /12	14-06-00	3-01-03	2 x 6		1-07-11 1-07-11	179.34 116.00		
	1 2-ply	T15 Hip Girder	6 /12	17-00-00	4-01-04	2 x 4	1-03-08 1-00-06	1-02-00 1-02-00	130 83.33		
	2	T19 Common	10 /12	11-10-00	6-06-14	2 x 4		1-07-11 1-07-11	96.78 60.67		

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 2

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434355
 Ref #
 Page: 2 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses


PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	G19 GABLE	10 / 12	11-10-00	6-06-14	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	57.55 37.00		
	1 2-ply	T20 Half Hip Girder	12 / 12	18-05-00	2-00-15	2 x 4	1-03-08	1-03-04 1-07-12	132.71 89.33		
	1	T21 Half Hip	12 / 12	7-01-00	3-00-15	2 x 4	1-03-08	1-03-04 2-07-12	30.88 21.50		
	1	T22 Half Hip	12 / 12	7-01-00	3-09-03	2 x 4	1-03-08	1-03-04 3-04-00	32.77 22.17		
	1 2-ply	T23 Monopitch Girder	6 / 12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	1 2-ply	T24Z Monopitch Girder	10 / 12	3-10-08	4-10-07	2 x 4 2 x 6		1-07-11 4-10-07	44.83 30.67		
	1 2-ply	T27 Monopitch Girder	10 / 12	3-02-08	5-03-12	2 x 4		2-07-11 5-03-12	38.62 26.67		
	1 2-ply	T28 Half Hip Girder	10 / 12	3-02-08	3-04-08	2 x 4		1-07-11 3-04-08	38.48 27.67		
	8	J1 Jack-Open	6 / 12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	134.36 85.33		
	2	J2 Jack-Open	10 / 12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	30.28 19.33		
	7	J4 Jack-Open	10 / 12	1-09-00	3-01-03	2 x 4	1-03-08	1-07-11 3-01-03	66.93 49.00		
	1	J5 Jack-Open	10 / 12	2-01-00	3-04-08	2 x 4	1-03-08	1-07-11 3-04-08	10.44 7.67		
	4	J6 Jack-Open	10 / 12	3-02-08	5-03-12	2 x 4	1-03-08	2-07-11 5-03-12	60.84 43.33		
	10	J8 Jack-Open	6 / 12	2-02-00	2-00-11	2 x 4	1-03-08	6-12 1-07-12	77.11 60.00		

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 2

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434355
 Ref #
 Page: 3 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	3	C1 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	21.06 14.00		
	3	C2 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	28.71 18.00		
	3	C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	34.75 22.00		
	3	C4 Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	42.4 26.00		
	1	C7 Jack-Open	10 /12	1-09-07	4-01-09	2 x 4	1-03-08 1-01	2-07-11 4-01-09	11.58 8.17		
	1	C8 Jack-Open	10 /12	1-09-07	4-01-09	2 x 4	1-03-08 1-05-01	2-07-11 4-01-09	13.1 9.50		

TOTAL # TRUSS= 90

TOTAL BFT OF ALL TRUSSES= 3019.18

BFT.

TOTAL WEIGHT OF ALL TRSSES 4743.66 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	HGUS26-2	
7	Hardware	LJS26DS	
6	Hardware	LUS24	
3	Hardware	LUS26-2	


TOTAL NUMBER OF ITEMS= 18

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 2-REAR UPG

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434591
 Ref #
 Page: 1 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses


PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Hip Girder	6 /12	31-00-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	336.84 206.67		
	1	T2 Hip	6 /12	31-00-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	126.87 80.17		
	1	T3 Hip	6 /12	31-00-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	126.51 80.00		
	1	T4 Hip	6 /12	31-00-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	127.93 80.00		
	1	T5 Hip	6 /12	31-00-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	128.89 81.83		
	11	T6 Common	6 /12	31-00-00	8-11-00	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1431.35 885.50		
	1	T7Z Hip Girder	10 /12	31-00-00	4-10-07	2 x 4 2 x 6	1-03-08	1-07-11 3-03-11	154.03 97.50		
	1	T8 Hip	10 /12	31-00-00	4-10-07	2 x 4	1-03-08	1-07-11 3-03-11	127.21 81.17		
	3	T9 Hip	10 /12	31-00-00	6-06-07	2 x 4	1-03-08	1-07-11 3-03-11	417.81 259.50		
	1 2-ply	T12 Roof Special Girder	10 /12	25-06-00	5-03-12	2 x 4 2 x 6	1-03-08	1-07-11 2-07-11	269.7 171.00		
	1	T13 Roof Special	10 /12	25-06-00	6-11-12	2 x 4	1-03-08	1-07-11 2-07-11	124.64 80.83		
	1 2-ply	T14Z Hip Girder	10 /12	14-06-00	3-01-03	2 x 6		1-07-11 1-07-11	179.34 116.00		
	1	T17 Hip Girder	6 /12	17-00-00	4-10-07	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	73.49 48.37		
	1	T18 Common	6 /12	17-00-00	5-05-00	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	66.13 41.83		

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 2-REAR UPG

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434591
 Ref #
 Page: 2 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	T19 Common	10 /12	11-10-00	6-06-14	2 x 4		1-07-11 1-07-11	96.78 60.67		
	1	G19 GABLE	10 /12	11-10-00	6-06-14	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	57.55 37.00		
	1 2-ply	T20 Half Hip Girder	12 /12	18-05-00	2-00-15	2 x 4	1-03-08	1-03-04 1-07-12	132.71 89.33		
	1	T21 Half Hip	12 /12	7-01-00	3-00-15	2 x 4	1-03-08	1-03-04 2-07-12	30.88 21.50		
	1	T22 Half Hip	12 /12	7-01-00	3-09-03	2 x 4	1-03-08	1-03-04 3-04-00	32.77 22.17		
	1 2-ply	T23Z1 Monopitch Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	1 2-ply	T24Z Monopitch Girder	10 /12	3-10-08	4-10-07	2 x 4 2 x 6		1-07-11 4-10-07	44.83 30.67		
	1 2-ply	T27 Monopitch Girder	10 /12	3-02-08	5-03-12	2 x 4		2-07-11 5-03-12	38.62 26.67		
	1 2-ply	T28 Half Hip Girder	10 /12	3-02-08	3-04-08	2 x 4		1-07-11 3-04-08	38.48 27.67		
	4	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	67.18 42.67		
	10	J2 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	151.39 96.67		
	7	J4 Jack-Open	10 /12	1-09-00	3-01-03	2 x 4	1-03-08	1-07-11 3-01-03	66.93 49.00		
	1	J5 Jack-Open	10 /12	2-01-00	3-04-08	2 x 4	1-03-08	1-07-11 3-04-08	10.44 7.67		
	4	J6 Jack-Open	10 /12	3-02-08	5-03-12	2 x 4	1-03-08	2-07-11 5-03-12	60.84 43.33		

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 2-REAR UPG

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434591
 Ref #
 Page: 3 of 3
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	10	J8 Jack-Open	6 / 12	2-02-00	2-00-11	2 x 4	1-03-08	6-12 1-07-12	77.11 60.00		
	1	C1 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	7.02 4.67		
	1	C2 Jack-Open	6 / 12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	9.57 6.00		
	1	C3 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	11.58 7.33		
	1	C4 Jack-Open	6 / 12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	14.13 8.67		
	1	C7 Jack-Open	10 / 12	1-09-07	4-01-09	2 x 4	1-03-08 1-01	2-07-11 4-01-09	11.58 8.17		
	1	C8 Jack-Open	10 / 12	1-09-07	4-01-09	2 x 4	1-03-08 1-05-01	2-07-11 4-01-09	13.1 9.50		

TOTAL # TRUSS= 86

TOTAL BFT OF ALL TRUSSES= 3007.2

BFT.

TOTAL WEIGHT OF ALL TRSSES 4722.61 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
1	Hardware	HGUS26-2	
9	Hardware	LJS26DS	
4	Hardware	LUS24	
3	Hardware	LUS26-2	


TOTAL NUMBER OF ITEMS= 17

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 3

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434357
 Ref #
 Page: 1 of 2
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses


PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	T2 Hip	6 / 12	31-00-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	253.75 160.33		
	2	T3 Hip	6 / 12	31-00-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	253.01 160.00		
	2	T4 Hip	6 / 12	31-00-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	255.85 160.00		
	2	T5 Hip	6 / 12	31-00-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	273.85 173.67		
	10	T6 Common	6 / 12	31-00-00	8-11-00	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1299.65 805.00		
	1 2-ply	T15 Hip Girder	6 / 12	17-00-00	4-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	130.66 84.67		
	1 2-ply	T23 Monopitch Girder	6 / 12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	1 2-ply	T31 Hip Girder	6 / 12	25-06-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	237.72 148.67		
	1	T32 Hip	6 / 12	25-06-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	101.96 64.50		
	1 2-ply	T33 Hip Girder	6 / 12	14-06-00	2-00-08	2 x 4 2 x 6		1-02-00 1-02-00	154.08 110.67		
	1	T34 Half Hip	6 / 12	5-10-08	3-00-08	2 x 4	1-03-08	1-02-00 3-00-08	26.59 17.67		
	1	T35 Monopitch	6 / 12	5-10-08	4-00-08	2 x 4	1-03-08	1-02-00 4-01-04	25.08 16.33		
	1 2-ply	T36 Flat Girder	0 / 12	18-05-00	1-07-12	2 x 4		1-07-12 1-07-12	126.68 84.67		
	1	T37 Flat	0 / 12	7-01-00	2-07-12	2 x 4		2-07-12 2-07-12	29.62 20.83		

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREENPARK HOMES
 Project: TRINIGROUP DEVELOPMENTS
 Location: RICHMOND HILL
 Model: ROSE 3
 Lot #:
 Elevation: 3

Job Track: 53256
 PlanLog: 207462
 Layout ID: 434357
 Ref #
 Page: 2 of 2
 Date: 08-24-2023
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T38 Flat	0 /12	7-01-00	3-04-00	2 x 4		3-04-00 3-04-00	32.42 21.83		
	1 2-ply	T39 Monopitch Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	1 2-ply	T40 Hip Girder	6 /12	31-00-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	312.29 190.67		
	1 2-ply	T40Z Hip Girder	6 /12	31-00-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	312.29 190.67		
	16	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	268.71 170.67		
	10	J8 Jack-Open	6 /12	2-02-00	2-00-11	2 x 4	1-03-08	6-12 1-07-12	77.11 60.00		
	7	J30 Jack-Open	6 /12	1-09-00	2-00-08	2 x 4	1-03-08	1-02-00 2-00-08	47.82 32.67		
	5	C1 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	35.1 23.33		
	5	C2 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	47.85 30.00		
	5	C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	57.91 36.67		
	5	C4 Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	70.66 43.33		

TOTAL # TRUSS= 92

TOTAL BFT OF ALL TRUSSES= 2882.19

BFT.

TOTAL WEIGHT OF ALL TRSSES 4547.49 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
5	Hardware	LJS26DS	
11	Hardware	LUS24	
5	Hardware	HGUS26-2	

TOTAL NUMBER OF ITEMS= 21

CITY OF RICHMOND HILL
 BUILDING DIVISION

05/01/2024

RECEIVED
 Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	T1	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:43 2023 Page 2
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-vnDi7UkdhZ1TQpekBPdQWix98DOilp xGQg ZykHEU

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	2.00	3.00
C	TTWW+m	MT20	5.0	6.0	2.25	2.50
D, F, G						
D	TMVW+t	MT20	4.0	6.0		
E	TS-t	MT20	5.0	6.0		
H	TTWW+m	MT20	5.0	6.0	2.25	2.50
I	TMVW-p	MT20	5.0	6.0	2.00	3.00
K	BMV1+p	MT20	4.0	6.0		
L	BMVW-t	MT20	5.0	6.0	2.50	2.50
M, N, P, Q						
M	BMVW-t	MT20	5.0	6.0		
O	BS-t	MT20	5.0	6.0		
R	BMVW-t	MT20	5.0	6.0	2.50	2.50
S	BMV1+p	MT20	4.0	6.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY
DWG # TR23080825

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024


RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T2	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:44 2023 Page 1
ID:YfdYYpXmLXEEbZ5zh9C3ynKil-Nzn4KqkGRt9K1zDwl68f3wUNjdIDS7i7AwANW?ykhET



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2 SPF
D - G	2x4	DRY	No.2 SPF
G - J	2x4	DRY	No.2 SPF
Q - B	2x4	DRY	No.2 SPF
K - I	2x4	DRY	No.2 SPF
Q - N	2x4	DRY	No.2 SPF
N - K	2x4	DRY	No.2 SPF
ALL WEBS	2x3	DRY	No.2 SPF
EXCEPT			
Q - C	2x4	DRY	No.2 SPF
H - K	2x4	DRY	No.2 SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	5.0	6.0		
D	TTWW-m	MT20	5.0	6.0	2.00	2.00
E	TMWW-t	MT20	4.0	6.0		
F	TMWW-w	MT20	2.0	4.0		
G	TTWW-m	MT20	5.0	6.0	2.00	2.00
H	TMWW-t	MT20	5.0	6.0		
I	TMV+p	MT20	3.0	4.0		
K	BMVW-t	MT20	4.0	6.0	2.00	2.00
L, O, P						
L	BMWW-t	MT20	4.0	6.0		
M	BMWWW-t	MT20	5.0	6.0		
N	BS-t	MT20	3.0	8.0		
Q	BMVW-t	MT20	4.0	6.0	2.00	2.00

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

STRUCTURAL COMPONENT ONLY
DWG # TR23080826

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
BEARINGS									
	FACTORED		MAXIMUM FACTORED		INPUT		REQRD		
	GROSS REACTION		GROSS REACTION		BRG		BRG		
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
Q	1833	0	1833	0	0	5-8	2-0		
K	1833	0	1833	0	0	5-8	2-0		
UNFACTORED REACTIONS									
	1ST LCASE		MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
Q	1294	863 / 0	0 / 0	0 / 0	0 / 0	432 / 0	0 / 0		
K	1294	863 / 0	0 / 0	0 / 0	0 / 0	432 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.88 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING			
TOTAL LOAD CASES: (4)			
CHORDS			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)
FR-TO		FROM TO	
A-B	0 / 28	-91.8 -91.8 0.12 (1)	10.00
B-C	0 / 17	-91.8 -91.8 0.20 (1)	10.00
C-D	-2376 / 0	-91.8 -91.8 0.23 (1)	4.27
D-E	-2730 / 0	-91.8 -91.8 0.37 (1)	3.88
E-F	-2728 / 0	-91.8 -91.8 0.34 (1)	3.92
F-G	-2728 / 0	-91.8 -91.8 0.37 (1)	3.88
G-H	-2376 / 0	-91.8 -91.8 0.23 (1)	4.27
H-I	0 / 17	-91.8 -91.8 0.20 (1)	10.00
I-J	0 / 28	-91.8 -91.8 0.12 (1)	10.00
Q-B	-269 / 0	0.0 0.0 0.03 (1)	7.81
K-I	-269 / 0	0.0 0.0 0.03 (1)	7.81
Q-P	0 / 2097	-18.5 -18.5 0.48 (1)	10.00
P-O	0 / 2111	-18.5 -18.5 0.47 (1)	10.00
O-N	0 / 2730	-18.5 -18.5 0.50 (1)	10.00
N-M	0 / 2730	-18.5 -18.5 0.50 (1)	10.00
M-L	0 / 2111	-18.5 -18.5 0.47 (1)	10.00
L-K	0 / 2097	-18.5 -18.5 0.48 (1)	10.00
WEBS			
MEMB.	FORCE (LBS)	MAX. FACTORED CSI (LC)	UNBRACED LENGTH
C-P	0 / 89	0.02 (4)	
P-D	0 / 141	0.04 (4)	
D-O	0 / 848	0.19 (1)	
O-E	-503 / 0	0.19 (1)	
E-M	-2 / 0	0.00 (1)	
M-F	-502 / 0	0.19 (1)	
M-G	0 / 846	0.19 (1)	
L-G	0 / 142	0.04 (4)	
L-H	0 / 89	0.02 (4)	
Q-C	-2580 / 0	0.72 (1)	
H-K	-2580 / 0	0.72 (1)	

TOTAL WEIGHT = 127 lb [M][F]

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.03")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.13")
ALLOWABLE DEFL.(TL)= L/360 (1.03")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.26")

CSI: TC=0.37/1.00 (F-G:1) . BC=0.50/1.00 (M-O:1) . WB=0.72/1.00 (H-K:1) . SSI=0.22/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.88 (K) (INPUT = 0.90)
JSI METAL= 0.88 (N) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED

CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	T3	1	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MTEK Industries, Inc. Thu Aug 24 09:55:46 2023 Page 1
ID:YfdYYpXmLXEEbZ5zlh9C3ynKil-KMuqIWmWzUP2HGMJsXA78LZh?RS?w5XQdEfUbuykhER
1-3-8 9-10-8 11-3-0 9-10-8 1-3-8
-1-3-8 0-0 5-0-8 9-10-8 15-6-0 21-1-8 25-11-8 31-0-0 32-3-8
Scale = 1:52.6



LUMBER				TOTAL WEIGHT = 127 lb			
N. L. G. A. RULES				(M/F)			
CHORDS	SIZE	LUMBER	DESCR.				
A - D	2x4	DRY	No.2				
D - F	2x4	DRY	No.2				
F - I	2x4	DRY	No.2				
R - B	2x4	DRY	No.2				
J - H	2x4	DRY	No.2				
R - O	2x4	DRY	No.2				
O - M	2x4	DRY	No.2				
M - J	2x4	DRY	No.2				
ALL WEBS	2x3	DRY	No.2				
EXCEPT							
DRY: SEASONED LUMBER.							

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	5.0	6.0	2.50 2.75
C	TMVW-t	MT20	4.0	6.0	
D	TTVW-m	MT20	5.0	6.0	2.50 2.25
E	TMVW-w	MT20	2.0	4.0	
F	TTVW-m	MT20	5.0	6.0	2.50 2.25
G	TMVW-t	MT20	4.0	6.0	
H	TMVW-t	MT20	5.0	6.0	2.50 2.75
J	BMV1-p	MT20	3.0	4.0	
K	BMVW-t	MT20	4.0	6.0	2.00 1.50
L	BMVW-t	MT20	4.0	6.0	
M	BS-t	MT20	3.0	8.0	
N	BMVW-t	MT20	4.0	6.0	
O	BS-t	MT20	3.0	8.0	
P	BMVW-t	MT20	4.0	6.0	
Q	BMVW-t	MT20	4.0	6.0	2.00 1.50
R	BMV1-p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
R	1833	0	1833	0	5-8
J	1833	0	1833	0	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
R	1294	863 / 0	0 / 0	0 / 0	0 / 0	432 / 0	0 / 0
J	1294	863 / 0	0 / 0	0 / 0	0 / 0	432 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.03 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED				WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX	MAX. UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX	MAX. UNBRAC LENGTH
FR-TO		FROM	TO			FR-TO			
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	Q-C	-286 / 0	0.06 (1)	
B-C	-2455 / 0	-91.8	-91.8	0.36 (1)	4.08	C-P	-279 / 0	0.17 (1)	
C-D	-2245 / 0	-91.8	-91.8	0.34 (1)	4.25	P-D	0 / 261	0.06 (1)	
D-E	-2344 / 0	-91.8	-91.8	0.45 (1)	4.03	D-N	0 / 509	0.11 (1)	
E-F	-2344 / 0	-91.8	-91.8	0.45 (1)	4.03	N-E	-632 / 0	0.37 (1)	
F-G	-2245 / 0	-91.8	-91.8	0.34 (1)	4.25	N-F	0 / 509	0.11 (1)	
G-H	-2455 / 0	-91.8	-91.8	0.36 (1)	4.08	L-F	0 / 261	0.06 (1)	
H-I	0 / 28	-91.8	-91.8	0.12 (1)	10.00	L-G	-279 / 0	0.17 (1)	
R-B	-1790 / 0	0.0	0.0	0.18 (1)	6.24	K-G	-286 / 0	0.06 (1)	
J-H	-1790 / 0	0.0	0.0	0.18 (1)	6.24	B-Q	0 / 2248	0.51 (1)	
						K-H	0 / 2248	0.51 (1)	
R-Q	0 / 0	-18.5	-18.5	0.10 (4)	10.00				
Q-P	0 / 2216	-18.5	-18.5	0.42 (1)	10.00				
P-O	0 / 1990	-18.5	-18.5	0.38 (1)	10.00				
O-N	0 / 1990	-18.5	-18.5	0.38 (1)	10.00				
N-M	0 / 1990	-18.5	-18.5	0.38 (1)	10.00				
M-L	0 / 1990	-18.5	-18.5	0.38 (1)	10.00				
L-K	0 / 2216	-18.5	-18.5	0.42 (1)	10.00				
K-J	0 / 0	-18.5	-18.5	0.10 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC2018, NBC2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.03")
CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
ALLOWABLE DEFL.(TL) = L/360 (1.03")
CALCULATED VERT. DEFL.(TL) = L/999 (0.22")

CSI: TC=0.45/1.00 (D-E:1) , BC=0.42/1.00 (P-Q:1) , WB=0.51/1.00 (B-Q:1) , SSI=0.25/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(Psi) (Plf) (Plf)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (D) (INPUT = 0.90)
JSI METAL= 0.62 (O) (INPUT = 0.95)


CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080827



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - I	2x4	DRY No.2	SPF
P - B	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
P - M	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-t	MT20	5.0	6.0	2.50	2.75
C, E, G					
C TMVW-t	MT20	4.0	6.0		
D TTW-m	MT20	4.0	6.0		
F TTW-m	MT20	4.0	6.0		
H TMVW-t	MT20	5.0	6.0	2.50	2.75
J BMV1+p	MT20	3.0	4.0		
K BMVW-t	MT20	4.0	6.0	2.00	1.75
L BMVW-t	MT20	4.0	6.0		
M BS-t	MT20	3.0	8.0		
N BMVW-t	MT20	4.0	6.0		
O BMVW-t	MT20	4.0	6.0	2.00	1.75
P BMV1+p	MT20	3.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX
JT VERT	1833	1833	0	2-7
JT HORZ	1833	1833	0	2-7

UNFACTORED REACTIONS

	1ST CASE	MAX./MIN. SNOW	MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT COMBINED	1294	863 / 0	0 / 0	0 / 0	0 / 0	432 / 0	0 / 0
P	1294	863 / 0	0 / 0	0 / 0	0 / 0	432 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.86 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING									
TOTAL LOAD CASES: (4)									
CHORDS					WEBS				
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX. UNBRAC	LC1 MAX	MAX. UNBRAC
FR-TO		FROM TO	CSI (LC)		FR-TO		FROM TO	CSI (LC)	
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	O-C	-206 / 25	0.05 (1)	
B-C	-2489 / 0	-91.8	-91.8	0.54 (1)	3.86	C-N	-486 / 0	0.47 (1)	
C-D	-2093 / 0	-91.8	-91.8	0.48 (1)	4.20	N-D	0 / 588	0.13 (1)	
D-E	-1854 / 0	-91.8	-91.8	0.18 (1)	4.78	N-E	-223 / 0	0.27 (1)	
E-F	-1854 / 0	-91.8	-91.8	0.18 (1)	4.78	E-L	-223 / 0	0.27 (1)	
F-G	-2093 / 0	-91.8	-91.8	0.48 (1)	4.20	L-F	0 / 588	0.13 (1)	
G-H	-2489 / 0	-91.8	-91.8	0.54 (1)	3.86	L-G	-486 / 0	0.47 (1)	
H-I	0 / 28	-91.8	-91.8	0.12 (1)	10.00	K-G	-206 / 25	0.05 (1)	
P-B	-1784 / 0	0.0	0.0	0.18 (1)	6.26	B-O	0 / 2274	0.51 (1)	
J-H	-1784 / 0	0.0	0.0	0.18 (1)	6.26	K-H	0 / 2274	0.51 (1)	
P-O	0 / 0	-18.5	-18.5	0.14 (4)	10.00				
O-N	0 / 2251	-18.5	-18.5	0.45 (1)	10.00				
N-M	0 / 1956	-18.5	-18.5	0.40 (1)	10.00				
M-L	0 / 1956	-18.5	-18.5	0.40 (1)	10.00				
L-K	0 / 2251	-18.5	-18.5	0.45 (1)	10.00				
K-J	0 / 0	-18.5	-18.5	0.14 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.03")
CALCULATED VERT. DEFL.(LL)= L/999 (0.11")
ALLOWABLE DEFL.(TL)= L/360 (1.03")
CALCULATED VERT. DEFL.(TL)= L/999 (0.23")

CSI: TC=0.54/1.00 (B-C:1) , BC=0.45/1.00 (N-O:1) , WB=0.51/1.00 (B-O:1) , SS=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES


PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788
		1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (O) (INPUT = 0.90)
JSI METAL= 0.67 (M) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED
Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080828



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - G	2x4	DRY No.2	SPF
G - I	2x4	DRY No.2	SPF
I - L	2x4	DRY No.2	SPF
S - B	2x4	DRY No.2	SPF
M - K	2x4	DRY No.2	SPF
S - P	2x4	DRY No.2	SPF
P - M	2x4	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

S - C 2x4 DRY No.2 SPF

J - M 2x4 DRY No.2 SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVW-t	MT20	5.0	6.0	2.50	2.75
D	TS-t	MT20	3.0	8.0		
E	TMVW-t	MT20	4.0	6.0		
F	TTW-m	MT20	4.0	6.0		
G	TTWW-m	MT20	4.0	6.0	1.75	2.25
H	TMVW-t	MT20	4.0	6.0		
I	TS-t	MT20	3.0	8.0		
J	TMVW-t	MT20	5.0	6.0	2.50	2.75
K	TMV+p	MT20	3.0	4.0		
M	BMVW-t	MT20	4.0	6.0	2.00	2.00
N, O, R						
P	BMVW-t	MT20	4.0	6.0		
Q	BS-t	MT20	3.0	8.0		
S	BMVW-t	MT20	4.0	6.0	2.00	2.00

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
S	1833	0	1833	0
M	1833	0	1833	0

UNFACTORED REACTIONS

1ST CASE	MAX / MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW LIVE PERM. LIVE WIND DEAD SOIL
S	1294	863 / 0 0 / 0 0 / 0 0 / 0 432 / 0 0 / 0
M	1294	863 / 0 0 / 0 0 / 0 0 / 0 432 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.22 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-S, J-M.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	MEMB. MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1)	10.00	C-R	-51 / 46	0.02 (4)
B-C	0 / 16	-91.8 -91.8	0.24 (1)	10.00	R-E	0 / 201	0.05 (4)
C-D	-2380 / 0	-91.8 -91.8	0.28 (1)	4.22	E-Q	-572 / 0	0.59 (1)
D-E	-2380 / 0	-91.8 -91.8	0.28 (1)	4.22	Q-F	0 / 520	0.12 (1)
E-F	-1896 / 0	-91.8 -91.8	0.27 (1)	4.64	F-G	0 / 4	0.00 (1)
F-G	-1685 / 0	-91.8 -91.8	0.15 (1)	4.99	G-H	0 / 516	0.12 (1)
G-H	-1895 / 0	-91.8 -91.8	0.27 (1)	4.64	H-I	-574 / 0	0.59 (1)
H-I	-2381 / 0	-91.8 -91.8	0.28 (1)	4.22	I-J	0 / 204	0.05 (4)
I-J	-2381 / 0	-91.8 -91.8	0.28 (1)	4.22	J-K	-51 / 46	0.02 (4)
J-K	0 / 16	-91.8 -91.8	0.24 (1)	10.00	K-L	-2618 / 0	0.44 (1)
K-L	0 / 28	-91.8 -91.8	0.12 (1)	10.00	L-M	-2619 / 0	0.44 (1)
L-M	-302 / 0	0.0 0.0	0.03 (1)	7.81			
M-K	-302 / 0	0.0 0.0	0.03 (1)	7.81			
S-R	0 / 2161	-18.5 -18.5	0.46 (1)	10.00			
R-Q	0 / 2054	-18.5 -18.5	0.44 (1)	10.00			
Q-P	0 / 1684	-18.5 -18.5	0.34 (1)	10.00			
P-O	0 / 1684	-18.5 -18.5	0.34 (1)	10.00			
O-N	0 / 2054	-18.5 -18.5	0.44 (1)	10.00			
N-M	0 / 2161	-18.5 -18.5	0.46 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.03")

CALCULATED VERT. DEFL.(LL)= L/999 (0.10")

ALLOWABLE DEFL.(TL)= L/360 (1.03")

CALCULATED VERT. DEFL.(TL)= L/999 (0.21")

CSI: TC=0.28/1.00 (H-J:1), BC=0.46/1.00 (M-N:1), WB=0.59/0.90 (H-O:1), SSI=0.18/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
	788	1987	1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (M) (INPUT = 0.90)

JSI METAL= 0.59 (J) (INPUT = 0.95)


CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED
Per: joshua.nabua



Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:49 2023 Page 1

ID:YfxdYYPxmLXEEbZ5zh9C3ynKil-kxazNXoOGPoc8k5uYgkqm BEUeTa7MutKt8BCykhEO



TOTAL WEIGHT = 11 X 130 = 1430 lb

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - H	2x4	DRY No.2	SPF
H - K	2x4	DRY No.2	SPF
R - B	2x4	DRY No.2	SPF
L - J	2x4	DRY No.2	SPF
R - P	2x4	DRY No.2	SPF
P - N	2x4	DRY No.2	SPF
N - L	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF
R - C	2x4	DRY No.2	SPF
I - L	2x4	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	3.0	4.0	
C	TMVW-t	MT20	5.0	6.0	2.50 2.75
D	TS-t	MT20	3.0	8.0	
E	TMVW-t	MT20	4.0	6.0	
F	TTW+p	MT20	4.0	6.0	Edge
G	TMVW-t	MT20	4.0	6.0	
H	TS-t	MT20	3.0	8.0	
I	TMVW-t	MT20	5.0	6.0	2.50 2.75
J	TMV+p	MT20	3.0	4.0	
L	BMVW-t	MT20	4.0	6.0	2.00 2.00
M	BMVW-t	MT20	4.0	6.0	
N	BS-t	MT20	3.0	8.0	
O	BMVW-t	MT20	5.0	6.0	
P	BS-t	MT20	3.0	8.0	
Q	BMVW-t	MT20	4.0	6.0	
R	BMVW-t	MT20	4.0	6.0	2.00 2.00

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
R	1833	0	1833	0	0	5-8	2-0
L	1833	0	1833	0	0	5-8	2-0

UNFACTORED REACTIONS							
JT	1ST CASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
R	1294	863 / 0	0 / 0	0 / 0	0 / 0	0 / 0	432 / 0
L	1294	863 / 0	0 / 0	0 / 0	0 / 0	0 / 0	432 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.17 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.
1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-R, I-L.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1)	10.00	O-F	0 / 1216	0.27 (1)
B-C	0 / 22	-91.8 -91.8	0.35 (1)	10.00	O-G	-673 / 0	0.85 (1)
C-D	-2342 / 0	-91.8 -91.8	0.37 (1)	4.17	G-M	0 / 326	0.07 (1)
D-E	-2342 / 0	-91.8 -91.8	0.37 (1)	4.17	M-I	-169 / 18	0.05 (1)
E-F	-1753 / 0	-91.8 -91.8	0.29 (1)	4.77	E-O	-673 / 0	0.85 (1)
F-G	-1753 / 0	-91.8 -91.8	0.29 (1)	4.77	Q-E	0 / 326	0.07 (1)
G-H	-2342 / 0	-91.8 -91.8	0.37 (1)	4.17	C-Q	-169 / 18	0.05 (1)
H-I	-2342 / 0	-91.8 -91.8	0.37 (1)	4.17	R-C	-2636 / 0	0.51 (1)
I-J	0 / 22	-91.8 -91.8	0.35 (1)	10.00	I-L	-2636 / 0	0.51 (1)
J-K	0 / 28	-91.8 -91.8	0.12 (1)	10.00			
R-B	-314 / 0	0.0 0.0	0.03 (1)	7.81			
L-J	-314 / 0	0.0 0.0	0.03 (1)	7.81			
R-Q	0 / 2195	-18.5 -18.5	0.49 (1)	10.00			
Q-P	0 / 1951	-18.5 -18.5	0.45 (1)	10.00			
P-O	0 / 1951	-18.5 -18.5	0.45 (1)	10.00			
O-N	0 / 1951	-18.5 -18.5	0.45 (1)	10.00			
N-M	0 / 1951	-18.5 -18.5	0.45 (1)	10.00			
M-L	0 / 2195	-18.5 -18.5	0.49 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.03")
CALCULATED VERT. DEFL.(LL)= L/999 (0.11")
ALLOWABLE DEFL.(TL)= L/360 (1.03")
CALCULATED VERT. DEFL.(TL)= L/999 (0.22")

CSI: TC=0.37/1.00 (G-I:1), BC=0.49/1.00 (Q-R:1), WB=0.85/1.00 (E-O:1), SSI=0.20/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (R) (INPUT = 0.90)
JSI METAL= 0.67 (P) (INPUT = 0.95)



STRUCTURAL COMPONENT ONLY
DWG # TR23080830

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

Tamarack Roof Truss, Burlington


Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:51 2023 Page 1

ID:YfxdYYpXmLXEEbZ5zl9C3ynKil-qJioDqfo12KN2FGf5mlrPHUIS3fbJ99nWMFG5ykhEM

1-3-8 3-10-8 25-3-0 1-10-8 31-0-0

-1-3-8 0-0 3-10-8 8-11-14 13-11-15 19-0-1 24-0-2 29-1-8

Scale = 1:52.1



Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.




A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT K. MINIMUM BEARING LENGTH AT JOINT K = 3-8.

1) **C1:** A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

JSI GRIP= 0.90 (R) (INPUT = 0.90)
JSI METAL= 0.72 (M) (INPUT = 0.95)

Per: joshua.nabua



LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - C	2x4	DRY	No.2	SPF
C - G	2x4	DRY	No.2	SPF
G - I	2x4	DRY	No.2	SPF
I - J	2x4	DRY	No.2	SPF
S - B	2x6	DRY	No.2	SPF
K - J	2x6	DRY	No.2	SPF
S - O	2x6	DRY	No.2	SPF
O - K	2x6	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	Edge	
C	TTWW+m	MT20	6.0	7.0	2.00	1.75
D, E, H						
D	TMVW-t	MT20	4.0	6.0		
F	TMVW-w	MT20	2.0	4.0		
G	TS-t	MT20	3.0	8.0		
I	TTWW+m	MT20	8.0	9.0	Edge	2.75
J	TMVW+p	MT20	5.0	6.0	2.00	2.00
K	BMV1+t	MT20	6.0	10.0	Edge	0.50
L	BMVW+h	MT20	4.0	6.0	2.50	1.50
M	BMVW+h	MT20	5.0	6.0	2.75	1.50
N	BMVWVW-t	MT20	5.0	6.0		
O	BS-t	MT20	5.0	6.0		
P	BMVW+h	MT20	4.0	6.0		
Q	BMVW-t	MT20	5.0	6.0		
R	BMVW-t	MT20	5.0	6.0		
S	BMV1+p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
S	2010	0	2010	0
K	2637	0	2637	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT K. MINIMUM BEARING LENGTH AT JOINT K = 3-1.

UNFACTORED REACTIONS

1ST LCASE	SNOW	MAX/MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED					
S	1419	947 / 0	0 / 0	0 / 0	472 / 0	0 / 0
K	1864	1232 / 0	0 / 0	0 / 0	632 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.03 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 41	-91.8	-91.8	R-C	-342 / 0	0.12	(1)
B-C	-1915 / 0	-91.8	-91.8	C-Q	0 / 1813	0.45	(1)
C-D	-2823 / 0	-91.8	-91.8	Q-D	-1119 / 0	0.38	(1)
D-E	-3501 / 0	-91.8	-91.8	D-P	0 / 911	0.23	(1)
E-F	-3541 / 0	-91.8	-91.8	P-E	-486 / 0	0.16	(1)
F-G	-3541 / 0	-91.8	-91.8	E-N	0 / 53	0.01	(1)
G-H	-3541 / 0	-91.8	-91.8	N-F	-434 / 0	0.15	(1)
H-T	-3113 / 0	-91.8	-91.8	T-H	0 / 575	0.14	(1)
T-I	-3113 / 0	-91.8	-91.8	I-M	-944 / 0	0.32	(1)
I-J	-1562 / 0	-91.8	-91.8	M-I	0 / 2585	0.64	(1)
S-B	-1986 / 0	0.0	0.0	L-I	-1120 / 0	0.38	(1)
K-J	-2835 / 0	0.0	0.0	B-R	0 / 1534	0.38	(1)
				L-J	0 / 2111	0.52	(1)
S-R	0 / 0	-18.5	-18.5				
R-Q	0 / 1459	-18.5	-18.5				
Q-P	0 / 2823	-18.5	-18.5				
P-O	0 / 3501	-18.5	-18.5				
O-N	0 / 3501	-18.5	-18.5				
N-M	0 / 3113	-18.5	-18.5				
M-U	0 / 1167	-18.5	-18.5				
U-V	0 / 1167	-18.5	-18.5				
V-L	0 / 1167	-18.5	-18.5				
L-K	0 / 0	-18.5	-18.5				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
I	29-1-8	-65	-65	---	FRONT	VERT	TOTAL	---	C1
L	29-0-12	-14	-14	---	FRONT	VERT	TOTAL	---	C1
T	27-0-12	-59	-59	---	FRONT	VERT	TOTAL	---	C1
U	25-7-8	-626	-626	---	FRONT	VERT	TOTAL	---	C1
V	27-0-12	-14	-14	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.03")
CALCULATED VERT. DEFL.(LL)= L/999 (0.17")
ALLOWABLE DEFL.(TL)= L/360 (1.03")
CALCULATED VERT. DEFL.(TL)= L/999 (0.31")

CSI: TC=0.72/1.00 (F-H:1), BC=0.66/1.00 (L-M:1), WB=0.64/1.00 (I-M:1), SS=0.42/1.00 (L-M:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (R) (INPUT = 0.90)
JSI METAL= 0.68 (M) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080851

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T8	1	1	TRUSS DESC.		


Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:52 2023 Page 1

ID:YfxdYYPXmLXEEbZ5zh9C3ynKil-8WF6?ZrHZKAB?BqSDoHXNcpdRsUDKpfJ0A6ooXykhEL



Scale = 1:52.3



TOTAL WEIGHT = 127 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
H - I	2x4	DRY	No.2	SPF
I - B	2x4	DRY	No.2	SPF
J - I	2x4	DRY	No.2	SPF
Q - N	2x4	DRY	No.2	SPF
N - J	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWW+p	MT20	5.0	6.0	Edge	
C	TTWW+m	MT20	6.0	7.0	2.00	1.75
D	TMWW-t	MT20	4.0	6.0		
E	TMWW-w	MT20	2.0	4.0		
F	TS-t	MT20	3.0	8.0		
G	TMWW-t	MT20	4.0	6.0		
H	TTWW+m	MT20	6.0	7.0	2.00	1.50
I	TMWW+p	MT20	5.0	6.0	Edge	
J	BMV1+p	MT20	3.0	4.0		
K	BMWW-t	MT20	4.0	6.0		
L	BMWW-t	MT20	5.0	6.0	2.50	2.75
M	BMWW-t	MT20	4.0	6.0		
N	BS-t	MT20	3.0	8.0		
O	BMWW-t	MT20	5.0	6.0		
P	BMWW-t	MT20	4.0	6.0		
Q	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
Q	1836	0	1836	0
J	1709	0	1709	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT J. MINIMUM BEARING LENGTH AT JOINT J = 2-1.

UNFACTORED REACTIONS

	1ST CASE	MAX./MIN.	COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
Q	1296	864 / 0	0 / 0	0 / 0	0 / 0	432 / 0	0 / 0
J	1209	793 / 0	0 / 0	0 / 0	0 / 0	415 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.24 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 41	-91.8	-91.8 0.13 (1)	10.00	P-C	-315 / 0	0.11 (1)
B-C	-1687 / 0	-91.8	-91.8 0.29 (1)	4.81	C-O	0 / 1683	0.38 (1)
C-D	-2653 / 0	-91.8	-91.8 0.79 (1)	3.44	O-D	-864 / 0	0.30 (1)
D-E	-2943 / 0	-91.8	-91.8 0.84 (1)	3.24	D-M	0 / 359	0.08 (1)
E-F	-2943 / 0	-91.8	-91.8 0.84 (1)	3.24	M-E	-530 / 0	0.18 (1)
F-G	-2943 / 0	-91.8	-91.8 0.84 (1)	3.24	M-G	0 / 732	0.16 (1)
G-H	-2351 / 0	-91.8	-91.8 0.74 (1)	3.66	L-G	-1085 / 0	0.38 (1)
H-I	-911 / 0	-91.8	-91.8 0.06 (1)	6.25	L-H	0 / 2062	0.46 (1)
Q-B	-1813 / 0	0.0	0.0 0.19 (1)	6.21	K-H	-939 / 0	0.33 (1)
J-I	-1720 / 0	0.0	0.0 0.32 (1)	6.35	B-P	0 / 1360	0.31 (1)
					K-I	0 / 1256	0.28 (1)
Q-P	0 / 0	-18.5	-18.5 0.12 (4)	10.00			
P-O	0 / 1285	-18.5	-18.5 0.28 (1)	10.00			
O-N	0 / 2653	-18.5	-18.5 0.49 (1)	10.00			
N-M	0 / 2653	-18.5	-18.5 0.49 (1)	10.00			
M-L	0 / 2351	-18.5	-18.5 0.44 (1)	10.00			
L-K	0 / 675	-18.5	-18.5 0.20 (4)	10.00			
K-J	0 / 0	-18.5	-18.5 0.12 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 8.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.03")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (1.03")
CALCULATED VERT. DEFL.(TL) = L/999 (0.29")

CSI: TC=0.84/1.00 (E-G:1), BC=0.49/1.00 (M-O:1), WB=0.46/1.00 (H-L:1), SSI=0.27/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371 1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (M) (INPUT = 0.90)
JSI METAL= 0.80 (N) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080832

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T9	3	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:53 2023 Page 1
ID:YfxdYYpXmLXEEbZ5Zlh9C3ynKil-cipUDvrvKel2cLPfnVpmwqMqbFsN3C0SEqrMK ykhEK



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - C 2x4 DRY No.2 SPF C - F 2x4 DRY No.2 SPF F - H 2x4 DRY No.2 SPF H - I 2x4 DRY No.2 SPF Q - B 2x4 DRY No.2 SPF J - I 2x4 DRY No.2 SPF Q - N 2x4 DRY No.2 SPF N - J 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF EXCEPT DRY: SEASONED LUMBER.				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS FACTORED GROSS REACTION MAXIMUM FACTORED GROSS REACTION INPUT REQD BRG BRG JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX Q 1836 0 1836 0 0 5-8 2-8 J 1709 0 1709 0 0 MECHANICAL A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT J. MINIMUM BEARING LENGTH AT JOINT J = 2-1.				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 25.6 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 39.0 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC 2018, NBC-2019AE - PART 9 OF OBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPC 2014 (55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (1.03") CALCULATED VERT. DEFL.(LL) = L/ 999 (0.09") ALLOWABLE DEFL.(TL)= L/360 (1.03") CALCULATED VERT. DEFL.(TL) = L/ 999 (0.18") CSI: TC=0.75/1.00 (B-C:1) , BC=0.37/1.00 (M-O:1) , WB=0.65/1.00 (G-L:1) , SSI=0.23/1.00 (C-D:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10 COMPANION LIVE LOAD FACTOR = 1.00 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.89 (P) (INPUT = 0.90) JSI METAL= 0.82 (N) (INPUT = 0.95)			
PLATES (table is in inches) JT TYPE PLATES W LEN Y X B TMVW-t MT20 5.0 6.0 2.50 2.75 C TTWW+m MT20 5.0 6.0 2.25 1.50 D TMVW-t MT20 4.0 6.0 E TMVW-w MT20 2.0 4.0 F TS-t MT20 3.0 8.0 G TMVW-t MT20 4.0 6.0 H TTWW+m MT20 5.0 8.0 Edge 1.25 I TMVW+p MT20 5.0 6.0 Edge J BMV1+p MT20 3.0 4.0 K, O, P K BMVW-t MT20 4.0 6.0 L BMVW-t MT20 4.0 6.0 M BMVW-w MT20 4.0 6.0 N BS-t MT20 3.0 8.0 Q BMV1+p MT20 3.0 4.0 Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.				UNFACTORED REACTIONS 1ST LCASE MAX./MIN. COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL Q 1296 864 / 0 0 / 0 0 / 0 432 / 0 0 / 0 J 1209 793 / 0 0 / 0 0 / 0 415 / 0 0 / 0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.13 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (4) CHORDS WEBS MAX. FACTORED MAX. FACTORED MAX. FACTORED MEMB. FORCE VERT. LOAD LC1 MAX MAX. MEMB. FORCE MAX (LBS) (PLF) CSI (LC) UNBRAC LENGTH FR-TO (LBS) CSI (LC) FR-TO FROM TO A-B 0 / 41 -91.8 -91.8 0.13 (1) 10.00 P-C -168 / 35 0.12 (1) B-C -1723 / 0 -91.8 -91.8 0.75 (1) 4.21 C-O 0 / 1057 0.24 (1) C-D -2009 / 0 -91.8 -91.8 0.48 (1) 4.25 O-D -709 / 0 0.50 (1) D-E -2144 / 0 -91.8 -91.8 0.49 (1) 4.13 D-M 0 / 210 0.05 (1) E-F -2144 / 0 -91.8 -91.8 0.49 (1) 4.13 M-E -444 / 0 0.31 (1) F-G -2144 / 0 -91.8 -91.8 0.49 (1) 4.13 M-G 0 / 497 0.11 (1) G-H -1823 / 0 -91.8 -91.8 0.46 (1) 4.44 L-G -930 / 0 0.65 (1) H-I -1239 / 0 -91.8 -91.8 0.27 (1) 5.44 L-H 0 / 1355 0.30 (1) Q-B -1791 / 0 0.0 0.0 0.19 (1) 6.24 K-H -811 / 0 0.43 (1) J-I -1683 / 0 0.0 0.0 0.32 (1) 6.40 B-P 0 / 1352 0.30 (1) K-I 0 / 1185 0.27 (1) Q-P 0 / 0 -18.5 -18.5 0.15 (4) 10.00 P-O 0 / 1318 -18.5 -18.5 0.30 (1) 10.00 O-N 0 / 2009 -18.5 -18.5 0.37 (1) 10.00 N-M 0 / 2009 -18.5 -18.5 0.37 (1) 10.00 M-L 0 / 1824 -18.5 -18.5 0.34 (1) 10.00 L-K 0 / 939 -18.5 -18.5 0.21 (1) 10.00 K-J 0 / 0 -18.5 -18.5 0.10 (4) 10.00				NOTES: (1) 1) Lateral braces to be a minimum of 2X4 SPF #2.			



STRUCTURAL COMPONENT ONLY
DWG # TR23080833

CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED
Per: joshua.nabua

CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED
CONTINUED ON PAGE 2
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	T10	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:54 2023 Page 2
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-5uNsQFsX5yQvEV_rKDK?T1u6dfAhoI2cTUbvtQykhE

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	5.0	6.0	2.00	2.25
C	TTWW-m	MT20	5.0	6.0	1.75	1.75
D	TMVW-t	MT20	4.0	6.0		
E	TS-t	MT20	3.0	8.0		
F	TMVW+w	MT20	2.0	4.0		
G	TMVW-t	MT20	4.0	6.0		
H	TTWW-m	MT20	5.0	6.0	1.75	1.75
I	TMVW+p	MT20	5.0	6.0	2.00	2.25
K	BMV1+p	MT20	4.0	6.0		
L	BMVW-t	MT20	5.0	6.0		
M	BMVW+t	MT20	4.0	6.0		
N	BS-t	MT20	5.0	6.0		
O	BMVWW-t	MT20	5.0	6.0		
P	BMVW+t	MT20	4.0	6.0		
Q	BMVW-t	MT20	5.0	6.0		
R	BMV1+p	MT20	4.0	6.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




STRUCTURAL COMPONENT ONLY
DWG # TR23080834

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua



TOTAL WEIGHT = 114 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
O - B	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF
O - L	2x4	DRY	No.2	SPF
L - I	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW+p	MT20	5.0	6.0	Edge	
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TMW+t	MT20	4.0	6.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
G	TMW+p	MT20	5.0	6.0	Edge	
I	BMV1+p	MT20	3.0	4.0		
J, K, N						
J	BMWW-t	MT20	4.0	6.0		
L	BS-t	MT20	3.0	8.0		
M	BMWWW-t	MT20	4.0	6.0		
O	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
O	1533	0	1533	0	0
I	1533	0	1533	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 1-11.

UNFACTORED REACTIONS

JT	1ST CASE	MAX./MIN. COMPONENT REACTIONS	DEAD	SOIL
O	1082	723 / 0	0 / 0	0 / 0
I	1082	723 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.83 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FORCE (LBS)
FR-TO		FROM TO		FR-TO	
A-B	0 / 41	-91.8 -91.8	0.13 (1)	N-C	-129 / 41
B-C	-1354 / 0	-91.8 -91.8	0.59 (1)	C-M	0 / 722
C-D	-1495 / 0	-91.8 -91.8	0.32 (1)	M-D	-476 / 0
D-E	-1495 / 0	-91.8 -91.8	0.33 (1)	M-E	-3 / 0
E-F	-1497 / 0	-91.8 -91.8	0.33 (1)	K-E	-476 / 0
F-G	-1354 / 0	-91.8 -91.8	0.59 (1)	K-F	0 / 725
G-H	0 / 41	-91.8 -91.8	0.13 (1)	J-F	-131 / 41
O-B	-1491 / 0	0.0 0.0	0.16 (1)	B-N	0 / 1066
I-G	-1490 / 0	0.0 0.0	0.16 (1)	J-G	0 / 1066
O-N	0 / 0	-18.5 -18.5	0.13 (4)		
N-M	0 / 1036	-18.5 -18.5	0.24 (1)		
M-L	0 / 1497	-18.5 -18.5	0.28 (1)		
L-K	0 / 1497	-18.5 -18.5	0.28 (1)		
K-J	0 / 1036	-18.5 -18.5	0.24 (1)		
J-I	0 / 0	-18.5 -18.5	0.13 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.85")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.85")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.10")

CSI: TC=0.59/1.00 (B-C:1), BC=0.28/1.00 (K-M:1), WB=0.29/1.00 (E-K:1), SSI=0.21/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (M) (INPUT = 0.90)
JSI METAL= 0.53 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua





STRUCTURAL COMPONENT ONLY
DWG # TR23080835

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434355	T12	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 Mitek Industries, Inc. Thu Aug 24 09:41:30 2023 Page 1
ID:6Oq41CdGo289DtyFWSfoLuyinlg7-OqAE5pPaZUZVajwojmQsQ6SbNHKM?IRo3ICXVykRrP



TOTAL WEIGHT = 2 X 135 = 270 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
E - H	2x4	DRY	No.2	SPF
H - I	2x4	DRY	No.2	SPF
R - B	2x6	DRY	No.2	SPF
J - I	2x6	DRY	No.2	SPF
R - M	2x6	DRY	No.2	SPF
M - J	2x6	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C	12	TOP
C-D	12	TOP
D-E	12	TOP
E-H	12	SIDE(61.0)
H-I	12	SIDE(61.0)
R-B	12	TOP
J-I	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
R-M	12	SIDE(0.0)
M-J	12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	DOWN	IN-SX	IN-SX
R	2813	0	5-8	1-8
J	2328	0	5-8	1-8

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW
R	1982	1340 / 0
J	1643	1097 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.85 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MEMB.	FORCE (LBS)
FR-TO		FROM TO	FR-TO	
A-B	0 / 41	-91.8 -91.8 0.07 (1)	Q-C	0 / 257
B-C	-2495 / 0	-91.8 -91.8 0.11 (1)	C-P	0 / 1258
C-D	-2540 / 0	-91.8 -91.8 0.07 (1)	P-D	-1319 / 0
D-E	-3016 / 0	-91.8 -91.8 0.04 (1)	D-O	-816 / 0
E-F	-3276 / 0	-91.8 -91.8 0.22 (1)	O-E	0 / 776
F-S	-3276 / 0	-91.8 -91.8 0.29 (1)	K-H	-913 / 0
S-G	-3276 / 0	-91.8 -91.8 0.29 (1)	B-Q	0 / 2036
G-T	-2987 / 0	-91.8 -91.8 0.28 (1)	K-I	0 / 1707
T-U	-2987 / 0	-91.8 -91.8 0.28 (1)	L-H	0 / 2183
U-H	-2987 / 0	-91.8 -91.8 0.28 (1)	E-N	0 / 1295
H-I	-1852 / 0	-91.8 -91.8 0.10 (1)	L-G	-924 / 0
R-B	-2584 / 0	0.0 0.0 0.10 (1)	N-F	-496 / 0
J-I	-2289 / 0	0.0 0.0 0.11 (1)	N-G	0 / 402
R-V	0 / 0	-18.5 -18.5 0.17 (1)		
V-Q	0 / 0	-18.5 -18.5 0.17 (1)		
Q-P	0 / 1917	-18.5 -18.5 0.24 (1)		
P-O	0 / 2575	-18.5 -18.5 0.23 (1)		
O-N	0 / 2333	-18.5 -18.5 0.28 (1)		
N-W	0 / 2987	-18.5 -18.5 0.51 (1)		
W-M	0 / 2987	-18.5 -18.5 0.51 (1)		
M-L	0 / 2987	-18.5 -18.5 0.51 (1)		
L-X	0 / 1398	-18.5 -18.5 0.21 (1)		
X-Y	0 / 1398	-18.5 -18.5 0.21 (1)		
Y-K	0 / 1398	-18.5 -18.5 0.21 (1)		
K-Z	0 / 0	-18.5 -18.5 0.02 (4)		
Z-J	0 / 0	-18.5 -18.5 0.02 (4)		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
H	22-3-8	-152	-152	---	FRONT	VERT	TOTAL	---	C1
K	22-2-12	-9	-9	---	FRONT	VERT	TOTAL	---	C1
M	16-2-12	-9	-9	---	FRONT	VERT	TOTAL	---	C1
S	16-2-12	-38	-38	---	FRONT	VERT	TOTAL	---	C1
T	18-2-12	-38	-38	---	FRONT	VERT	TOTAL	---	C1
U	20-2-12	-38	-38	---	FRONT	VERT	TOTAL	---	C1
V	2-2-8	-622	-622	---	FRONT	VERT	TOTAL	---	C1
W	14-3-8	-617	-617	---	FRONT	VERT	TOTAL	---	C1
X	18-2-12	-9	-9	---	FRONT	VERT	TOTAL	---	C1
Y	20-2-12	-9	-9	---	FRONT	VERT	TOTAL	---	C1
Z	23-6-12	-9	-9	---	FRONT	VERT	TOTAL	---	C1

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
DL = 8.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 39.0	PSF	

SPACING = 24.0 IN. C/C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.85")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (0.85")
CALCULATED VERT. DEFL.(TL) = L/999 (0.13")

CSI: TC=0.29/1.00 (F-G:1), BC=0.51/1.00 (L-N:1), WB=0.27/1.00 (H-L:1), SSI=0.24/1.00 (Q-R:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788
		1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.86 (H) (INPUT = 0.90)
JSI METAL = 0.36 (L) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23080852

JOB NAME 434355	TRUSS NAME T12	QUANTITY 1	PLY 2	JOB DESC. GREENPARK HOMES	DRWG NO.
--------------------	-------------------	---------------	----------	------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:41:30 2023 Page 2
ID:6Oq41CdGo289DtyFWSfoLuyng7-OgAE5pPaZUZVaiwojmQOSq6SbNHKM?IRo3ICXVvkhRp


PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	5.0	6.0	2.00	2.25
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TTWW+m	MT20	5.0	6.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMVW+w	MT20	2.0	4.0		
G	TMVW-t	MT20	4.0	6.0		
H	TTWW-m	MT20	5.0	6.0	1.75	1.75
I	TMVW+p	MT20	5.0	6.0	2.00	2.25
J	BMV1+p	MT20	4.0	6.0		
K, L, O, P						
K	BMVW+t	MT20	4.0	6.0		
M	BS-t	MT20	5.0	6.0		
N	BMVWW-t	MT20	5.0	6.0		
Q	BMVW-t	MT20	5.0	6.0		
R	BMV1+p	MT20	4.0	6.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY
DWG # TR23080852

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434355	T13	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MTek Industries, Inc. Thu Aug 24 09:41:31 2023 Page 1
ID:6Oq41CdGo289DtyFWSfoLuyng7-stkcl9QCkHMcTV HTLD 2fYngR5OKa1j1l4xykhRo



TOTAL WEIGHT = 125 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
G - H	2x4	DRY	No.2	SPF
P - B	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
P - L	2x4	DRY	No.2	SPF
L - I	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	5.0	6.0	Edge	
C, E, G						
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TTWW-m	MT20	4.0	6.0		
F	TMVW+w	MT20	2.0	4.0		
H	TMVW+p	MT20	4.0	6.0	Edge	
I	BMV1+p	MT20	3.0	4.0		
J, M, O						
K	BMVW-t	MT20	4.0	6.0		
J	BMVWW-t	MT20	4.0	6.0		
L	BS-t	MT20	3.0	8.0		
N	BMVWW-t	MT20	4.0	6.0		
P	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED	MAXIMUM FACTORED	INPUT	REQRD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	HORZ	DOWN	HORZ
P 1533	0	1533	0
I 1406	0	1406	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 1-8.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN.	COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	SOIL
P	1082	723 / 0	0 / 0	0 / 0	0 / 0	358 / 0
I	994	652 / 0	0 / 0	0 / 0	0 / 0	342 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.73 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MEMB.	FORCE (LBS)
FR-TO		FROM TO	FR-TO	
A-B	0 / 41	-91.8 -91.8 0.13 (1)	O-C	-137 / 35
B-C	-1358 / 0	-91.8 -91.8 0.52 (1)	C-N	0 / 712
C-D	-1299 / 0	-91.8 -91.8 0.10 (1)	N-D	-718 / 0
D-E	-1573 / 0	-91.8 -91.8 0.05 (1)	D-M	-463 / 0
E-F	-1375 / 0	-91.8 -91.8 0.58 (1)	M-E	0 / 563
F-G	-1375 / 0	-91.8 -91.8 0.58 (1)	E-K	0 / 242
G-H	-1158 / 0	-91.8 -91.8 0.50 (1)	K-F	-647 / 0
P-B	-1494 / 0	0.0 0.0 0.16 (1)	K-G	0 / 752
I-H	-1367 / 0	0.0 0.0 0.19 (1)	J-G	-270 / 0
			B-O	0 / 1072
			J-H	0 / 967
P-O	0 / 0	-18.5 -18.5 0.12 (4)		
O-N	0 / 1038	-18.5 -18.5 0.24 (1)		
N-M	0 / 1312	-18.5 -18.5 0.26 (1)		
M-L	0 / 1217	-18.5 -18.5 0.25 (1)		
L-K	0 / 1217	-18.5 -18.5 0.25 (1)		
K-J	0 / 883	-18.5 -18.5 0.22 (1)		
J-I	0 / 0	-18.5 -18.5 0.13 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6 PSF
DL	= 8.0 PSF	
BOT CH.	LL	= 0.0 PSF
DL	= 7.4 PSF	
TOTAL LOAD	= 39.0 PSF	

SPACING = 24.0 IN./C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.85")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL) = L/360 (0.85")
CALCULATED VERT. DEFL.(TL) = L/999 (0.11")

CSI: TC=0.58/1.00 (E-F:1), BC=0.26/1.00 (M-N:1), WB=0.54/1.00 (F-K:1), SS=0.26/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371 1747 788 1987 1873	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (K) (INPUT = 0.90)
JSI METAL= 0.55 (H) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080853

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T14	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:57 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-VT3?3HvPOtoU5ziQ0Li4gWcoC7?1G29SpZUlykhEG



TOTAL WEIGHT = 2 X 90 = 179 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - B	2x6	DRY	No.2	SPF
B - F	2x6	DRY	No.2	SPF
F - G	2x6	DRY	No.2	SPF
N - A	2x6	DRY	No.2	SPF
N - G	2x6	DRY	No.2	SPF
H - H	2x6	DRY	2100F 1.8E	SPF

ALL WEBS 2x4 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-B 2 12	SIDE(122.0)	
B-F 2 12	SIDE(183.1)	
F-G 2 12	SIDE(122.0)	
N-A 2 12	TOP	
H-G 2 12	TOP	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
N-H 2 12	SIDE(197.8)	
WEBS : (0.122"x3") SPIRAL NAILS		
M-B 1 4	SIDE(275.7)	
C-L 1 2	SIDE(243.2)	
D-K 1 5	SIDE(243.2)	
E-J 1 2	SIDE(523.7)	
2x4 1 4		
L-B 1 6		
K-C 1 6		
K-E 1 6		
J-F 1 6		
M-A 1 6		
I-G 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX
JT VERT	6976	0	5-8	3-12
N	6976	0	5-8	3-12
H	6089	0	5-8	3-5

UNFACTORED REACTIONS

	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
N	4924	3286 / 0	0 / 0	0 / 0	1637 / 0	0 / 0	
H	4298	2866 / 0	0 / 0	0 / 0	1432 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.45 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1 MAX (PLF)	MEMB.	FORCE (LBS)
FR-TO		FROM TO	FR-TO	
A-B	-6279 / 0	-91.8 -91.8 0.06 (1)	M-B	-1026 / 0
B-C	-8755 / 0	-91.8 -91.8 0.15 (1)	B-L	0 / 6172
C-O	-11338 / 0	-91.8 -91.8 0.28 (1)	L-C	-2205 / 0
O-D	-11338 / 0	-91.8 -91.8 0.28 (1)	C-K	0 / 3330
D-P	-11338 / 0	-91.8 -91.8 0.29 (1)	K-D	-238 / 0
P-E	-11338 / 0	-91.8 -91.8 0.29 (1)	K-E	0 / 3286
E-F	-8790 / 0	-91.8 -91.8 0.16 (1)	J-E	-2154 / 0
F-G	-5569 / 0	-91.8 -91.8 0.05 (1)	J-F	0 / 7156
N-A	-6960 / 0	0.0 0.0 0.25 (1)	I-F	-2247 / 0
H-G	-6182 / 0	0.0 0.0 0.22 (1)	A-M	0 / 5539
			I-G	0 / 4913
N-M	0 / 0	-18.5 -18.5 0.00 (4)		
M-L	0 / 4719	-18.5 -18.5 0.15 (1)		
L-Q	0 / 8753	-18.5 -18.5 0.44 (1)		
Q-K	0 / 8753	-18.5 -18.5 0.44 (1)		
K-R	0 / 8788	-18.5 -18.5 0.44 (1)		
R-J	0 / 8788	-18.5 -18.5 0.44 (1)		
J-I	0 / 4111	-18.5 -18.5 0.15 (1)		
I-H	0 / 0	-18.5 -18.5 0.04 (1)		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
B	1-9-0	-43	-43	79	BACK	VERT	TOTAL	---	C1
C	3-9-12	1	1	79	BACK	VERT	TOTAL	---	C1
D	7-0-4	1	1	79	BACK	VERT	TOTAL	---	C1
E	10-8-4	1	1	79	BACK	VERT	TOTAL	---	C1
F	12-9-0	-43	-43	79	BACK	VERT	TOTAL	---	C1
I	12-8-4	1	1	---	BACK	VERT	TOTAL	---	C1
J	10-6-12	-1951	-1951	---	FRONT	VERT	TOTAL	---	C1
J	10-8-4	1	1	---	BACK	VERT	TOTAL	---	C1
K	7-0-4	1	1	---	BACK	VERT	TOTAL	---	C1
K	7-3-0	-1194	-1194	---	FRONT	VERT	TOTAL	---	C1
L	3-9-12	1	1	---	BACK	VERT	TOTAL	---	C1
L	3-11-4	-1194	-1194	---	FRONT	VERT	TOTAL	---	C1
M	1-9-12	1	1	---	BACK	VERT	TOTAL	---	C1
M	1-11-4	-1279	-1279	---	FRONT	VERT	TOTAL	---	C1
O	5-9-12	1	1	79	BACK	VERT	TOTAL	---	C1
O	8-8-4	1	1	79	BACK	VERT	TOTAL	---	C1
Q	5-9-12	1	1	---	BACK	VERT	TOTAL	---	C1
Q	5-11-4	-1194	-1194	---	FRONT	VERT	TOTAL	---	C1
R	8-6-12	-1194	-1194	---	FRONT	VERT	TOTAL	---	C1
R	8-8-4	1	1	---	BACK	VERT	TOTAL	---	C1

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
DL	= 6.0	PSF	
BOT CH.	LL	= 0.0	PSF
DL	= 7.4	PSF	
TOTAL LOAD	= 39.0	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.48")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (0.48")
CALCULATED VERT. DEFL.(TL) = L/999 (0.14")

CSI: TC=0.29/1.00 (D-E:1) . BC=0.44/1.00 (J-K:1) .
WB=0.63/1.00 (F-J:1) . SSI=0.39/1.00 (J-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (F) (INPUT = 0.90)
JSI METAL= 0.70 (L) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED CONTINUED ON PAGE 2

Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080836

JOB NAME 434351	TRUSS NAME T14	QUANTITY 1	PLY 2	JOB DESC. GREENPARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:57 2023 Page 2
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-VT3?3HvPOtoU5ziQ0Lti4gWcotC??1G29SpZUlykhEG

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	6.0	7.0	2.75	2.25
B	TTWW+m	MT20	6.0	12.0	4.00	1.25
C	TMWW-t	MT20	5.0	6.0		
D	TMW+w	MT20	4.0	6.0		
E	TMWW-t	MT20	5.0	6.0		
F	TTWW+m	MT20	6.0	12.0	4.00	1.25
G	TMVW-t	MT20	6.0	7.0	2.75	2.25
H	BMV1+p	MT20	4.0	6.0		
I	BMWW-t	MT20	5.0	6.0	2.50	2.25
J	BMWW+t	MT20	6.0	10.0		
K	BMWWW+t	MT20	8.0	9.0		
L	BMWW+t	MT20	6.0	10.0		
M	BMWW-t	MT20	5.0	6.0	2.50	2.25
N	BMV1+p	MT20	4.0	6.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




STRUCTURAL COMPONENT ONLY
DWG # TR23080836

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua



TOTAL WEIGHT = 2 X 90 = 179 lb

LUMBER

N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - B	2x6	DRY No.2	SPF
B - F	2x6	DRY No.2	SPF
F - G	2x6	DRY No.2	SPF
N - A	2x6	DRY No.2	SPF
H - G	2x6	DRY No.2	SPF
N - H	2x6	DRY 2100F 1.8E	SPF

ALL WEBS 2x4 DRY
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT
SEPARATELY THEN FASTENED TOGETHER AS
FOLLOWS:

CHORDS	#ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS			
A-B	2	12	SIDE (122.0)
B-F	2	12	SIDE (183.1)
F-G	2	12	SIDE (122.0)
N-A	2	12	TOP
H-G	2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS			
N-H	2	12	SIDE (197.8)
WEBS : (0.122"x3") SPIRAL NAILS			
M-B	1	4	SIDE (275.7)
C-L	1	2	SIDE (243.2)
D-K	1	5	SIDE (243.2)
E-J	1	2	SIDE (485.4)
2x4	1	4	
L-B	1	6	
K-C	1	6	
K-E	1	6	
J-F	1	6	
M-A	1	6	
I-G	1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.



STRUCTURAL COMPONENT ONLY
DWG # TR23080854

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
N	6936	0	6936	0	0	5-8	3-12
H	5982	0	5982	0	0	5-8	3-4

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
N	4895	3266 / 0	0 / 0	0 / 0	0 / 0	1629 / 0	0 / 0
H	4223	2812 / 0	0 / 0	0 / 0	0 / 0	1412 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.47 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS					WEBS				
MEMB.	MAX. FACTORED	FACTORED			MAX. UNBRAC	MEMB.	MAX. FACTORED	MAX	
	FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX CSI (LC)			FORCE (LBS)		MAX CSI (LC)
FR-TO		FROM	TO		LENGTH	FR-TO			
A-B	-6241/0	-91.8	-91.8	0.06 (1)	4.74	M-B	-1011/0	0.07 (1)	
B-C	-8694/0	-91.8	-91.8	0.14 (1)	4.04	B-L	0/6122	0.54 (1)	
C-O	-11226/0	-91.8	-91.8	0.28 (1)	3.47	L-C	-2166/0	0.14 (1)	
O-D	-11226/0	-91.8	-91.8	0.28 (1)	3.47	C-K	0/3265	0.29 (1)	
D-P	-11226/0	-91.8	-91.8	0.28 (1)	3.47	K-D	-236/0	0.02 (1)	
P-E	-11226/0	-91.8	-91.8	0.28 (1)	3.47	K-E	0/3340	0.30 (1)	
E-F	-8636/0	-91.8	-91.8	0.15 (1)	4.05	J-E	-2195/0	0.14 (1)	
F-G	-5469/0	-91.8	-91.8	0.05 (1)	5.00	J-F	0/7036	0.62 (1)	
N-A	-6918/0	0.0	0.0	0.25 (1)	5.68	I-F	-2215/0	0.14 (1)	
H-G	-6072/0	0.0	0.0	0.22 (1)	6.00	A-M	0/5506	0.49 (1)	
						I-G	0/4825	0.43 (1)	
N-M	0/0	-18.5	-18.5	0.00 (4)	10.00				
M-L	0/4691	-18.5	-18.5	0.15 (1)	10.00				
L-Q	0/8692	-18.5	-18.5	0.44 (1)	10.00				
Q-K	0/8692	-18.5	-18.5	0.44 (1)	10.00				
K-R	0/8634	-18.5	-18.5	0.44 (1)	10.00				
R-J	0/8634	-18.5	-18.5	0.44 (1)	10.00				
J-I	0/4037	-18.5	-18.5	0.15 (1)	10.00				
I-H	0/0	-18.5	-18.5	0.04 (1)	10.00				

SPECIFIED CONCENTRATED LOADS (LBS)

BT	LOC.	LC	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
B	1-9-12	-43	-43	79	BACK	VERT	TOTAL	---	C1
C	3-9-12	1	1	79	BACK	VERT	TOTAL	---	C1
D	7-0-4	1	1	79	BACK	VERT	TOTAL	---	C1
E	10-8-4	1	1	79	BACK	VERT	TOTAL	---	C1
F	12-9-0	-43	-43	79	BACK	VERT	TOTAL	---	C1
I	12-8-4	1	1	---	BACK	VERT	TOTAL	---	C1
J	10-6-12	-1849	-1849	---	FRONT	VERT	TOTAL	---	C1
K	10-8-4	1	1	---	BACK	VERT	TOTAL	---	C1
L	7-0-4	1	1	---	BACK	VERT	TOTAL	---	C1
K	7-3-0	-1194	-1194	---	FRONT	VERT	TOTAL	---	C1
L	3-9-12	1	1	---	BACK	VERT	TOTAL	---	C1
M	3-11-4	-1194	-1194	---	FRONT	VERT	TOTAL	---	C1
M	1-9-12	1	1	---	BACK	VERT	TOTAL	---	C1
M	1-11-4	-1279	-1279	---	FRONT	VERT	TOTAL	---	C1
O	5-9-12	1	1	79	BACK	VERT	TOTAL	---	C1
P	8-8-4	1	1	79	BACK	VERT	TOTAL	---	C1
Q	5-9-12	1	1	---	BACK	VERT	TOTAL	---	C1
Q	5-11-4	-1194	-1194	---	FRONT	VERT	TOTAL	---	C1
R	8-6-12	-1194	-1194	---	FRONT	VERT	TOTAL	---	C1
R	8-8-4	1	1	---	BACK	VERT	TOTAL	---	C1

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL =	25.6	PSF
		DL =	6.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.48")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.07")
ALLOWABLE DEFL.(TL)= L/360 (0.48")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.13")

CSI: TC=0.28/1.00 (D-E:1) , BC=0.44/1.00 (J-K:1) ,
WB=0.62/1.00 (F-J:1) , SSI=0.39/1.00 (J-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (F) (INPUT = 0.90)
JSI METAL= 0.69 (L) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED CONTINUED ON PAGE 2
Per: joshua.nabua



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
K - B	2x4	DRY	No.2	SPF
G - E	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	SIDE (61.0)
C - D	12	SIDE (61.0)
D - F	12	SIDE (61.0)
K - B	12	TOP
G - E	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
K - I	12	SIDE (61.0)
I - G	12	SIDE (61.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT	REQD
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
K	1736	0	1736	0	0
G	1736	0	1736	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

1ST CASE	MAX. MIN.	COMPONENT REACTIONS
JT	COMBINED	SNOW
K	1226	814 / 0
G	1226	814 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.55 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO		FR-TO	
A-B	0 / 28	-91.8 -91.8	0.07 (1)	J-C	-92 / 123
B-C	-2210 / 0	-91.8 -91.8	0.35 (1)	C-H	0 / 4
C-L	-1975 / 0	-91.8 -91.8	0.45 (1)	H-D	-88 / 125
L-M	-1975 / 0	-91.8 -91.8	0.45 (1)	B-J	0 / 1996
M-D	-1975 / 0	-91.8 -91.8	0.45 (1)	H-E	0 / 2000
D-E	-2215 / 0	-91.8 -91.8	0.35 (1)		
E-F	0 / 28	-91.8 -91.8	0.07 (1)		
K-B	-1668 / 0	0.0 0.0	0.09 (1)		
G-E	-1667 / 0	0.0 0.0	0.09 (1)		
K-N	0 / 0	-18.5 -18.5	0.13 (4)		
N-O	0 / 0	-18.5 -18.5	0.13 (4)		
O-J	0 / 0	-18.5 -18.5	0.13 (4)		
J-P	0 / 1973	-18.5 -18.5	0.24 (1)		
P-Q	0 / 1973	-18.5 -18.5	0.24 (1)		
Q-I	0 / 1973	-18.5 -18.5	0.24 (1)		
I-H	0 / 1973	-18.5 -18.5	0.24 (1)		
H-R	0 / 0	-18.5 -18.5	0.13 (4)		
R-S	0 / 0	-18.5 -18.5	0.13 (4)		
S-G	0 / 0	-18.5 -18.5	0.13 (4)		

SPECIFIED CONCENTRATED LOADS (LBS)	
JT	LOC.
C	5-10-8
D	11-1-8
H	11-0-12
J	5-11-4
L	7-11-4
M	9-0-12
N	1-11-4
O	3-11-4
P	7-11-4
Q	9-0-12
R	13-0-12
S	15-0-12

TOTAL WEIGHT = 2 X 65 = 131 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF

BOT CH. LL = 0.0 PSF
DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC 2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.57")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.57")
CALCULATED VERT. DEFL.(TL) = L/999 (0.06")

CSI: TC=0.45/1.00 (C-D:1), BC=0.24/1.00 (H-J:1), WB=0.25/1.00 (E-H:1), SSI=0.15/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.75 (H) (INPUT = 0.90)
JSI METAL= 0.30 (I) (INPUT = 0.95)

LICENSED PROFESSIONAL ENGINEER

8/24/23

C. M. HEYENS

100505065

PROVINCE OF ONTARIO

STRUCTURAL COMPONENT ONLY

DWG # TR23080837

CITY OF RICHMOND HILL

BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	T15	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:59 2023 Page 2
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-RsBITwgyU2CLGsp7mvAA5cwnqxrT1nLdmIqYdykhEE

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0		
C	TTWW-m	MT20	4.0	6.0	1.75	2.25
D	TTW-m	MT20	4.0	6.0		
E	TMVW-t	MT20	4.0	6.0		
G	BMV1+p	MT20	3.0	4.0		
H	BMWWW-t	MT20	5.0	6.0	2.50	1.50
I	BS-t	MT20	3.0	8.0		
J	BMWW-t	MT20	4.0	6.0		
K	BMV1+p	MT20	3.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




STRUCTURAL COMPONENT ONLY
DWG # TR23080837

CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434590	G16	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:53:04 2023 Page 1
ID:YfxdYYpXmLXEEbZ5Zlh9C3ynKil-3B6bl7pu7i?1rN ANWG8aBs527GDzw6aN1PvuHykhGz



TOTAL WEIGHT = 64 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES	U - B	2x4	DRY	No.2
	A - F	2x4	DRY	No.2
	F - K	2x4	DRY	No.2
	L - J	2x4	DRY	No.2
	U - P	2x4	DRY	No.2
	P - L	2x4	DRY	No.2

ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)	W	LEN	Y	X
JT TYPE	MT20	3.0	4.0	
B TMV+p	MT20	2.0	4.0	
C, D, E, G, H, I	MT20	4.0	6.0	
C TMW+w	MT20	3.0	4.0	
F TTW-p	MT20	3.0	4.0	
J TMV+p	MT20	3.0	4.0	
L BMV1+p	MT20	2.0	4.0	
M, N, O, Q, R, S, T	MT20	3.0	4.0	
M BMW1+w	MT20	3.0	8.0	
P BS-1	MT20	3.0	8.0	
U BMV1+p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

C H O R D S				W E B S			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO	CSI (LC)	UNBRAC LENGTH	FR-TO		CSI (LC)
U-B	-253 / 0	0.0	0.0	0.02 (4)	7.81	Q-F	-179 / 0
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	R-E	-187 / 0
B-C	-29 / 0	-91.8	-91.8	0.07 (1)	6.25	S-D	-176 / 0
C-D	-22 / 0	-91.8	-91.8	0.05 (1)	6.25	T-C	-199 / 0
D-E	-15 / 0	-91.8	-91.8	0.04 (1)	6.25	O-G	-187 / 0
E-F	-12 / 0	-91.8	-91.8	0.04 (1)	6.25	N-H	-176 / 0
F-G	-12 / 0	-91.8	-91.8	0.04 (1)	6.25	M-I	-199 / 0
G-H	-15 / 0	-91.8	-91.8	0.04 (1)	6.25		
H-I	-22 / 0	-91.8	-91.8	0.05 (1)	6.25		
I-J	-29 / 0	-91.8	-91.8	0.07 (1)	6.25		
J-K	0 / 28	-91.8	-91.8	0.12 (1)	10.00		
L-J	-253 / 0	0.0	0.0	0.02 (4)	7.81		
U-T	0 / 24	-18.5	-18.5	0.02 (4)	10.00		
T-S	0 / 18	-18.5	-18.5	0.02 (4)	10.00		
S-R	0 / 14	-18.5	-18.5	0.02 (4)	10.00		
R-Q	0 / 11	-18.5	-18.5	0.02 (4)	10.00		
Q-P	0 / 11	-18.5	-18.5	0.02 (4)	10.00		
P-O	0 / 11	-18.5	-18.5	0.02 (4)	10.00		
O-N	0 / 14	-18.5	-18.5	0.02 (4)	10.00		
N-M	0 / 18	-18.5	-18.5	0.02 (4)	10.00		
M-L	0 / 24	-18.5	-18.5	0.02 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (T-U:4), WB=0.08/1.00 (F-Q:1), SS=0.09/1.00 (J-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.38 (E) (INPUT = 0.90)
JSI METAL= 0.08 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080846

STRUCTURAL COMPONENT ONLY
DWG # TR23080858

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434591	T17	1	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:48:15 2023 Page 2

ID:YfdYYpXmLXEEbZ5zlh9C3ynKil-1b8L5UjcBwb1gzOdyJbMMEOgqYQl8t2wZv8GXyknLU

SPECIFIED CONCENTRATED LOADS (LBS)									
JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
U	9-0-12	-14	-14	---	FRONT	VERT	TOTAL	---	C1
V	15-0-12	-14	-14	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




STRUCTURAL COMPONENT ONLY
DWG # TR23080858

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434591	T18	1	1	TRUSS DESC.		



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - G	2x4	DRY No.2	SPF
K - B	2x4	DRY No.2	SPF
H - F	2x4	DRY No.2	SPF
K - I	2x4	DRY No.2	SPF
I - H	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVW-t	MT20	4.0	6.0		
D	TTW-p	MT20	4.0	6.0		
E	TMVW-t	MT20	4.0	6.0		
F	TMV+p	MT20	3.0	4.0		
H	BMVW1-t	MT20	4.0	6.0		
I	BS-t	MT20	3.0	8.0		
J	BMVWV-t	MT20	4.0	6.0		
K	BMVW1-t	MT20	4.0	6.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
K	1062	0	1062	0
H	1062	0	1062	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. SNOW	MAX./MIN. LIVE	MAX./MIN. PERM. LIVE	WIND	DEAD	SOIL
K	748	504 / 0	0 / 0	0 / 0	0 / 0	244 / 0	0 / 0
H	748	504 / 0	0 / 0	0 / 0	0 / 0	244 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.18 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1)	J-D	0 / 510	0.11 (1)	
B-C	0 / 20	-91.8 -91.8	0.26 (1)	J-E	-274 / 0	0.13 (1)	
C-D	-926 / 0	-91.8 -91.8	0.21 (1)	C-J	-274 / 0	0.13 (1)	
D-E	-926 / 0	-91.8 -91.8	0.21 (1)	K-C	-1263 / 0	0.56 (1)	
E-F	0 / 20	-91.8 -91.8	0.26 (1)	E-H	-1263 / 0	0.56 (1)	
F-G	0 / 28	-91.8 -91.8	0.12 (1)				
K-B	-276 / 0	0.0 0.0	0.03 (1)				
H-F	-276 / 0	0.0 0.0	0.03 (1)				
K-J	0 / 1034	-18.5 -18.5	0.46 (4)				
J-I	0 / 1034	-18.5 -18.5	0.46 (4)				
I-H	0 / 1034	-18.5 -18.5	0.46 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	PSF
LL	25.6	PSF
DL	6.0	PSF
BOT CH. <th>LL</th> <th>PSF</th>	LL	PSF
LL	0.0	PSF
DL	7.4	PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.57")

CALCULATED VERT. DEFL.(LL) = L/ 999 (0.03")

ALLOWABLE DEFL.(TL) = L/360 (0.57")

CALCULATED VERT. DEFL.(TL) = L/ 999 (0.13")

CSI: TC=0.26/1.00 (B-C:1), BC=0.46/1.00 (J-K:4), WB=0.56/1.00 (C-K:1), SSI=0.17/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.64 (J) (INPUT = 0.90)

JSI METAL= 0.36 (I) (INPUT = 0.95)

8/24/23

C. M. HEYENS

100505065

PROVINCE OF ONTARIO

STRUCTURAL COMPONENT ONLY

DWG # TR23080859


CITY OF RICHMOND HILL

BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - B 2x4 DRY No.2 SPF B - C 2x4 DRY No.2 SPF D - A 2x4 DRY No.2 SPF F - C 2x4 DRY No.2 SPF F - D 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF EXCEPT DRY: SEASONED LUMBER.				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 25.6 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 39.0 PSF SPACING = 24.0 IN. C/C THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015 THIS DESIGN COMPLIES WITH: - PART 9 OF BCBC 2018, NBC-2019AE - PART 9 OF OBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (0.39") CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00") ALLOWABLE DEFL.(TL)= L/360 (0.39") CALCULATED VERT. DEFL.(TL) = L/ 999 (0.03") CSI: TC=0.41/1.00 (B-C:1) , BC=0.19/1.00 (E-F:4) , WB=0.07/1.00 (A-E:1) , SSI=0.16/1.00 (B-C:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10 COMPANION LIVE LOAD FACTOR = 1.00 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.44 (E) (INPUT = 0.90) JSI METAL= 0.25 (A) (INPUT = 0.95)				UNFACTORED REACTIONS 1ST LCASE MAX /MIN. COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL F 461 303 / 0 0 / 0 0 / 0 0 / 0 159 / 0 0 / 0 D 461 303 / 0 0 / 0 0 / 0 0 / 0 159 / 0 0 / 0 BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (4) C H O R D S MAX. FACTORED FACTORED W E B S MEMB. FORCE VERT. LOAD LC1 MAX MAX. MEMB. FORCE MAX (LBS) (PLF) CSI (LC) UNBRAC LENGTH FR-TO (LBS) CSI (LC) FR-TO FROM TO A-B -419 / 0 -91.8 -91.8 0.41 (1) 6.25 E-B -7 / 100 0.03 (4) B-C -419 / 0 -91.8 -91.8 0.41 (1) 6.25 A-E 0 / 329 0.07 (1) F-A -611 / 0 0.0 0.0 0.06 (1) 7.81 E-C 0 / 329 0.07 (1) D-C -611 / 0 0.0 0.0 0.06 (1) 7.81 F-E 0 / 0 -18.5 -18.5 0.19 (4) 10.00 E-D 0 / 0 -18.5 -18.5 0.19 (4) 10.00				PLATES (table is in inches) JT TYPE PLATES W LEN Y X A TMVW+p MT20 4.0 6.0 Edge B TTW+p MT20 4.0 6.0 Edge C TMVW+p MT20 4.0 6.0 Edge D BMV1+p MT20 3.0 4.0 E BMVWW-t MT20 4.0 6.0 F BMV1+p MT20 3.0 4.0 Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD. NOTES- (1) 1) Lateral braces to be a minimum of 2X4 SPF #2.				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS FACTORED MAXIMUM FACTORED INPUT REQD GROSS REACTION GROSS REACTION BRG BRG JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX F 652 0 652 0 0 MECHANICAL D 652 0 652 0 0 MECHANICAL A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 1-8, JOINT D = 1-8.				TOTAL WEIGHT = 2 X 48 = 97 lb [M][F]			
---	--	--	--	---	--	--	--	--	--	--	--	---	--	--	--	---	--	--	--	---	--	--	--

STRUCTURAL COMPONENT ONLY
DWG # TR23080838

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024


RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	G19	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:33 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-Cscw03cM1VnuDHtpcJS46cXZKB69NjnVej?Id8ykhEe



LUMBER				DESIGN CRITERIA			
N. L. G. A. RULES				SPECIFIED LOADS:			
CHORDS	SIZE	LUMBER	DESCR.	TOP CH. LL = 25.6 PSF			
P - B	2x4	DRY	No.2	DL = 6.0 PSF			
A - E	2x4	DRY	No.2	BOT CH. LL = 0.0 PSF			
E - I	2x4	DRY	No.2	DL = 7.4 PSF			
J - H	2x4	DRY	No.2	TOTAL LOAD = 39.0 PSF			
P - J	2x4	DRY	No.2	SPACING = 24.0 IN. C/C			
ALL WEBS	2x3	DRY	No.2	THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015			
ALL GABLE WEBS	2x3	DRY	No.2	THIS DESIGN COMPLIES WITH:			
DRY: SEASONED LUMBER.				- PART 9 OF BCBC 2018, NBC-2019AE			
				- PART 9 OF OBC 2012 (2019 AMENDMENT)			
				- CSA 086-14			
				- TPIC 2014			
				DESIGN ASSUMPTIONS			
				- OVERHANG NOT TO BE ALTERED OR CUT OFF.			
				(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD			
				CS1: TC=0.13/1.00 (A-B:1), BC=0.02/1.00 (K-L:4), WB=0.09/1.00 (E-M:1), SSI=0.08/1.00 (A-B:1)			
				DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10			
				COMPANION LIVE LOAD FACTOR = 1.00			
				TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.			
				NAIL VALUES			
				PLATE GRIP(DRY) SHEAR SECTION			
				(PSI) (PLI) (PLI)			
				MAX MIN MAX MIN MAX MIN			
				MT20 650 371 1747 788 1987 1873			
				PLATE PLACEMENT TOL. = 0.250 inches			
				PLATE ROTATION TOL. = 5.0 Deg.			
				JSI GRIP= 0.18 (B) (INPUT = 0.90)			
				JSI METAL= 0.12 (D) (INPUT = 0.95)			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	6.0	Edge
C, D, F, G					
E	TTW+w	MT20	2.0	4.0	
E	TTW+p	MT20	4.0	6.0	Edge
H	TMVW+p	MT20	4.0	6.0	Edge
J	BMV1+p	MT20	3.0	4.0	
K	BMVW1-l	MT20	4.0	6.0	
L, M, N					
L	BMV1+w	MT20	2.0	4.0	
O	BMVW1-l	MT20	4.0	6.0	
P	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
BEARINGS									
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.									
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.									
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)									
BRACING									
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.									
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.									
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.									
LOADING									
TOTAL LOAD CASES: (4)									
CHORDS									
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	LC1	MAX. UNBRACED LENGTH	MEMB.
FR-TO		FROM TO			FR-TO				
P-B	-281 / 0	0.0	0.0	0.03 (1)	7.81	M-E	-134 / 0	0.09 (1)	
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	N-D	-220 / 0	0.08 (1)	
B-C	-51 / 0	-91.8	-91.8	0.12 (1)	6.25	O-C	-115 / 0	0.02 (1)	
C-D	-9 / 0	-91.8	-91.8	0.06 (1)	10.00	L-F	-220 / 0	0.08 (1)	
D-E	-26 / 0	-91.8	-91.8	0.06 (1)	6.25	K-G	-115 / 0	0.02 (1)	
E-F	-26 / 0	-91.8	-91.8	0.06 (1)	6.25	B-O	0 / 22	0.01 (1)	
F-G	-9 / 0	-91.8	-91.8	0.06 (1)	10.00	K-H	0 / 22	0.01 (1)	
G-H	-51 / 0	-91.8	-91.8	0.12 (1)	6.25				
H-I	0 / 41	-91.8	-91.8	0.13 (1)	10.00				
J-H	-281 / 0	0.0	0.0	0.03 (1)	7.81				
P-O	0 / 0	-18.5	-18.5	0.02 (4)	10.00				
O-N	0 / 15	-18.5	-18.5	0.02 (4)	10.00				
N-M	0 / 10	-18.5	-18.5	0.02 (4)	10.00				
M-L	0 / 10	-18.5	-18.5	0.02 (4)	10.00				
L-K	0 / 15	-18.5	-18.5	0.02 (4)	10.00				
K-J	0 / 0	-18.5	-18.5	0.02 (4)	10.00				



STRUCTURAL COMPONENT ONLY
DWG # TR23080817

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T20	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc.
Thu Aug 24 09:56:02 2023
Page 1
ID:YfxdYYpXmLXEEbZ5Zlh9C3ynKil-sRst6 yYCPQmCkbOouTtnjEULusagKAnJjXK9yykhEE



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - C 2x4 DRY No.2 SPF C - E 2x4 DRY No.2 SPF E - H 2x4 DRY No.2 SPF J - H 2x4 DRY No.2 SPF O - B 2x4 DRY No.2 SPF O - L 2x4 DRY No.2 SPF L - I 2x4 DRY No.2 SPF J - I 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF EXCEPT DRY: SEASONED LUMBER. DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS: CHORDS #ROWS SURFACE SPACING (IN) LOAD(PLF) TOP CHORDS : (0.122"x3") SPIRAL NAILS A-C 1 12 SIDE(61.0) C-E 1 12 SIDE(61.0) E-H 1 12 SIDE(61.0) H-J 1 6 SIDE(11.0) O-B 1 12 TOP BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS O-L 1 12 SIDE(61.0) L-I 1 12 SIDE(61.0) WEBS : (0.122"x3") SPIRAL NAILS O-C 1 6 SIDE(11.2) 2x3 1 6 2x4 1 6 NAILS TO BE DRIVEN FROM ONE SIDE ONLY. GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS. TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS FACTORED GROSS REACTION MAXIMUM FACTORED GROSS REACTION INPUT REQD BRG JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX O 1317 0 1317 0 0 3-8 1-8 I 1101 0 1101 0 0 5-8 1-8 UNFACTORED REACTIONS 1ST LCASE MAX./MIN. COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL O 927 631 / 0 0 / 0 0 / 0 0 / 0 297 / 0 0 / 0 I 778 515 / 0 0 / 0 0 / 0 0 / 0 263 / 0 0 / 0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, I BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.58 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (4) C H O R D S W E B S MEMB. MAX. FACTORED FORCE VERT. LOAD LC1 MAX. MAX. MEMB. MAX. FACTORED FORCE MAX. MAX. (LBS) (PLF) CSI (LC) UNBRAC LENGTH FR-TO (LBS) CSI (LC) FR-TO FROM TO A-B 0 / 45 -91.8 -91.8 0.07 (1) 10.00 N-D -727 / 0 0.06 (1) B-C -145 / 0 -91.8 -91.8 0.07 (1) 6.25 O-C -938 / 0 0.07 (1) C-P -3157 / 0 -91.8 -91.8 0.17 (1) 5.07 C-N 0 / 3004 0.37 (1) P-Q -3157 / 0 -91.8 -91.8 0.17 (1) 5.07 K-H 0 / 3730 0.46 (1) Q-D -3157 / 0 -91.8 -91.8 0.17 (1) 5.07 D-M 0 / 954 0.12 (1) D-R -4070 / 0 -91.8 -91.8 0.17 (1) 4.58 K-G -606 / 0 0.05 (1) R-E -4070 / 0 -91.8 -91.8 0.17 (1) 4.58 M-F -393 / 0 0.03 (1) E-F -4070 / 0 -91.8 -91.8 0.17 (1) 4.58 M-G 0 / 511 0.06 (1) F-S -4070 / 0 -91.8 -91.8 0.17 (1) 4.58 S-T -4070 / 0 -91.8 -91.8 0.17 (1) 4.58 T-G -4070 / 0 -91.8 -91.8 0.17 (1) 4.58 G-U -3581 / 0 -91.8 -91.8 0.21 (1) 4.78 U-V -3581 / 0 -91.8 -91.8 0.21 (1) 4.78 V-H -3581 / 0 -91.8 -91.8 0.21 (1) 4.78 J-H -1256 / 0 0.0 0.0 0.07 (1) 7.81 O-B -353 / 0 0.0 0.0 0.02 (1) 7.81 O-W 0 / 287 -18.5 -18.5 0.08 (1) 10.00 W-X 0 / 287 -18.5 -18.5 0.08 (1) 10.00 X-Y 0 / 287 -18.5 -18.5 0.08 (1) 10.00 Y-N 0 / 287 -18.5 -18.5 0.08 (1) 10.00 N-Z 0 / 3157 -18.5 -18.5 0.36 (1) 10.00 Z-AA 0 / 3157 -18.5 -18.5 0.36 (1) 10.00 AA-M 0 / 3157 -18.5 -18.5 0.36 (1) 10.00 M-AB 0 / 3581 -18.5 -18.5 0.49 (1) 10.00 AB-L 0 / 3581 -18.5 -18.5 0.49 (1) 10.00 L-AC 0 / 3581 -18.5 -18.5 0.49 (1) 10.00 AC-K 0 / 3581 -18.5 -18.5 0.49 (1) 10.00 K-AD 0 / 0 -18.5 -18.5 0.68 (1) 10.00 AD-AE 0 / 0 -18.5 -18.5 0.68 (1) 10.00 AE-J 0 / 0 -18.5 -18.5 0.68 (1) 10.00 J-I 0 / 0 -18.5 -18.5 0.28 (1) 10.00 SPECIFIED CONCENTRATED LOADS (LBS) JT LOC. LC1 MAX- MAX+ FACE DIR. TYPE HEEL CONN. C 5-4 -14 -1 --- BACK VERT TOTAL --- C1 E 8-5-4 -1 -1 --- BACK VERT TOTAL --- C1 H 18-5-0 -17 -17 --- BACK VERT TOTAL --- C1 J 18-1-12 -12 -12 --- BACK VERT TOTAL --- C1 P 2-5-4 -1 -1 --- BACK VERT TOTAL --- C1 Q 4-5-4 -1 -1 --- BACK VERT TOTAL --- C1 R 6-5-4 -1 -1 --- BACK VERT TOTAL --- C1										DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 25.6 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 39.0 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015 THIS DESIGN COMPLIES WITH: - PART 9 OF BCBC 2018 , NBC-2019AE - PART 9 OF OBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 DESIGN ASSUMPTIONS -OVERHANG NOT TO BE ALTERED OR CUT OFF. (55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (0.64") CALCULATED VERT. DEFL.(LL) = L/ 999 (0.18") ALLOWABLE DEFL.(TL)= L/360 (0.64") CALCULATED VERT. DEFL.(TL) = L/ 699 (0.33") CSI: TC=0.21/1.00 (G-H:1) , BC=0.68/1.00 (J-K:1) , WB=0.46/1.00 (H-K:1) , SS=0.24/1.00 (I-J:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS= 1.00 COMPANION LIVE LOAD FACTOR = 1.00 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL = 5.0 Deg. JSI GRIP= 0.87 (H) (INPUT = 0.90) JSI METAL= 0.55 (L) (INPUT = 0.95)	
---	--	--	--	--	--	--	--	--	--	--	--	--	--	---	--



STRUCTURAL COMPONENT ONLY
DWG # TR23080839

CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T20	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:56:02 2023 Page 2

ID:YfxdYYpXmLXEEbZ5zh9C3ynKil-sRst6_yYCPQmCkbOouTtnjEULusagKAnJjXK9yykhEB

PLATES (table is in inches)						SPECIFIED CONCENTRATED LOADS (LBS)										
JT	TYPE	PLATES	W	LEN	Y	X	JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
B	TMV+p	MT20	3.0	4.0			S	10-5-4	-1	-1	---	BACK	VERT	TOTAL	---	C1
C	TTWW+m	MT20	5.0	6.0	2.50	2.00	T	12-5-4	-1	-1	---	BACK	VERT	TOTAL	---	C1
D	TMVW-t	MT20	4.0	6.0			U	14-5-4	-1	-1	---	BACK	VERT	TOTAL	---	C1
E	TS-t	MT20	3.0	8.0			V	16-5-4	-1	-1	---	BACK	VERT	TOTAL	---	C1
F	TMVW+w	MT20	2.0	4.0			W	5-4	-17	-17	---	BACK	VERT	TOTAL	---	C1
G	TMVW-t	MT20	4.0	6.0			X	2-5-4	-12	-12	---	BACK	VERT	TOTAL	---	C1
H	TMVW-t	MT20	5.0	6.0			Y	4-5-4	-12	-12	---	BACK	VERT	TOTAL	---	C1
J	BMVW-t	MT20	6.0	16.0	3.00	Edge	Z	6-5-4	-12	-12	---	BACK	VERT	TOTAL	---	C1
K	BMVW-t	MT20	5.0	6.0			AA	8-5-4	-12	-12	---	BACK	VERT	TOTAL	---	C1
L	BS-t	MT20	3.0	8.0			AB	10-5-4	-12	-12	---	BACK	VERT	TOTAL	---	C1
M	BMVWW-t	MT20	4.0	6.0			AC	12-5-4	-12	-12	---	BACK	VERT	TOTAL	---	C1
N	BMVW-t	MT20	5.0	6.0			AD	14-5-4	-12	-12	---	BACK	VERT	TOTAL	---	C1
O	BMVW-t	MT20	4.0	6.0			AE	16-5-4	-12	-12	---	BACK	VERT	TOTAL	---	C1
Edge - INDICATES REFERENCE CORNER OF PLATE																

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS
1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY
DWG # TR23080839

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024


RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T21	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:56:03 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zh9C3ynKil-KdQGGJKzAzjYdpuAaMc 6KXmboHIYPsNwYNGuhOYkhEA



TOTAL WEIGHT = 31 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
H - B	2x4	DRY	No.2	SPF
H - E	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	5.0	6.0	Edge	2.50
C	TTWW+m	MT20	5.0	6.0	2.00	1.50
D	TMV+p	MT20	3.0	4.0		
F	BMVWW-t	MT20	6.0	12.0	3.00	3.50
G	BMVWW-t	MT20	4.0	6.0		
H	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
H	553	0	553	0
E	402	0	402	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	DEAD	SOIL
H	COMBINED	SNOW	LIVE	PERM. LIVE
H	389	270 / 0	0 / 0	0 / 0
E	284	185 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)
FR-TO									
A-B		0 / 45	-91.8	-91.8	0.13 (1)	10.00	G-C	0 / 94	0.03 (4)
B-C		-359 / 0	-91.8	-91.8	0.12 (1)	6.25	C-F	-239 / 0	0.14 (1)
C-D		0 / 0	-91.8	-91.8	0.51 (1)	10.00	B-G	0 / 258	0.06 (1)
F-D		-262 / 0	0.0	0.0	0.03 (1)	7.81			
H-B		-616 / 0	0.0	0.0	0.06 (1)	7.81			
H-G		0 / 0	-18.5	-18.5	0.17 (4)	10.00			
G-F		0 / 221	-18.5	-18.5	0.25 (1)	10.00			
F-E		0 / 0	-110.3	-110.3	0.09 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
DL	= 6.0	PSF	
BOT CH.	LL	= 0.0	PSF
DL	= 7.4	PSF	
TOTAL LOAD	= 39.0	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.25")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.03")
ALLOWABLE DEFL.(TL) = $L/360$ (0.25")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.09")

CSI: TC=0.51/1.00 (C-D:1), BC=0.25/1.00 (F-G:1), WB=0.14/1.00 (C-F:1), SSI=0.20/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.31 (B) (INPUT = 0.90)
JSI METAL = 0.15 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080840

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T22	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:56:04 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-op eXg ok0hUR2kmwJVLt8JnKhde8JZ4m10RDrykhE9



Scale = 1:20.1

TOTAL WEIGHT = 33 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
H - B	2x4	DRY	No.2	SPF
H - E	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWW+p	MT20	5.0	6.0	Edge	2.50
C	TTWW+m	MT20	5.0	6.0	2.00	1.50
D	TMV+p	MT20	3.0	4.0		
F	BMWW-t	MT20	6.0	12.0	3.00	Edge
G	BMWW-t	MT20	4.0	6.0		
H	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ
H	541	0	541	0
E	413	0	413	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX /MIN	COMPONENT REACTIONS	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND
H	380	263 / 0	0 / 0	0 / 0	0 / 0
E	292	192 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 45	-91.8 -91.8	0.13 (1)	G-C	0 / 88	0.03 (4)	
B-C	-337 / 0	-91.8 -91.8	0.07 (1)	C-F	-279 / 0	0.15 (1)	
C-D	0 / 0	-91.8 -91.8	0.39 (1)	B-G	0 / 257	0.06 (1)	
F-D	-230 / 0	0.0 0.0	0.04 (1)				
H-B	-564 / 0	0.0 0.0	0.06 (1)				
H-G	0 / 0	-18.5 -18.5	0.13 (4)				
G-F	0 / 239	-18.5 -18.5	0.26 (1)				
F-E	0 / 0	-110.3 -110.3	0.09 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.25")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL) = L/360 (0.25")
CALCULATED VERT. DEFL.(TL) = L/999 (0.07")

CSI: TC=0.39/1.00 (C-D:1), BC=0.26/1.00 (F-G:1), WB=0.15/1.00 (C-F:1), SSI=0.18/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371
	1747	788
	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.29 (B) (INPUT = 0.90)
JSI METAL= 0.15 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080841

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T23	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MTek Industries, Inc. Thu Aug 24 09:56:05 2023 Page 1

ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-G0Y0k0?RVKpL3BJyU10aPMs2H5wZtmXD?hl mHykhE8



Scale = 1:23.5

TOTAL WEIGHT = 2 X 29 = 58 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
D - C	2x4	DRY	No.2	SPF	
F - A	2x6	DRY	No.2	SPF	
F - D	2x6	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C 1 12		TOP
C-D 1 12		TOP
F-A 2 12		TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2 12		SIDE (183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	4.0	6.0	1.00	3.00
B	TMVW-t	MT20	4.0	6.0		
C	TMV+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
D	1868	0	1868	0
F	1102	0	1102	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

	1ST CASE	MAX/MIN	COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
D	1315	896 / 0	0 / 0	0 / 0	0 / 0	420 / 0	0 / 0
F	771	550 / 0	0 / 0	0 / 0	0 / 0	221 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED			
MEMB.	FORCE	VERT. LOAD	LC1	MAX	MEMB.	FORCE	MAX
	(LBS)	(PLF)	CSI (LC)	UNBRAC		(LBS)	CSI (LC)
FR-TO		FROM	TO	LENGTH	FR-TO		
A-B	-1231 / 0	-91.8	-91.8	0.06 (1)	6.25	E-B	0 / 1085
B-C	-11 / 0	-91.8	-91.8	0.05 (1)	6.25	B-D	-1398 / 0
D-C	-110 / 0	0.0	0.0	0.01 (1)	7.81	A-E	0 / 1149
F-A	-958 / 0	0.0	0.0	0.03 (1)	7.81		
F-G	0 / 0	-18.5	-18.5	0.14 (1)	10.00		
G-H	0 / 0	-18.5	-18.5	0.14 (1)	10.00		
H-E	0 / 0	-18.5	-18.5	0.14 (1)	10.00		
E-I	0 / 1111	-18.5	-18.5	0.47 (1)	10.00		
I-D	0 / 1111	-18.5	-18.5	0.47 (1)	10.00		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	7-4	-179	-179	---	BACK	VERT	TOTAL	---	C1
H	2-7.4	-239	-239	---	BACK	VERT	TOTAL	---	C1
I	4-8.0	-1211	-1211	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC 2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.06/1.00 (A-B:1), BC=0.47/1.00 (D-E:1), WB=0.17/1.00 (B-D:1), SSI=0.30/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.53 (D) (INPUT = 0.90)
JSI METAL= 0.25 (D) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23080842

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	T23	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:56:05 2023 Page 2

ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-G0Y0k0?RVKpL3BJyU10aPMs2H5wZtmXD?hl mHykhE8

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
D	BMW1+p	MT20	4.0	6.0		
E	BMW1+t	MT20	4.0	10.0		
F	BMW1+p	MT20	4.0	6.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY

DWG # TR23080842

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024


RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434590	T23Z	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:53:06 2023 Page 1
ID: YfxdYYPxMlXEEbZ5zlh9C3ynKil-7aELAoa9fKFI4h8ZVxJcfcxSRxsoRoNtrLu0z9ykhGx



Scale = 1:23.5

TOTAL WEIGHT = 2 X 29 = 58 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - A	2x6	DRY	No.2	SPF
F - D	2x6	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C 1	12	TOP
C - D 1	12	TOP
F - A 2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F - D 2	12	SIDE (183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
B - E 1	6	SIDE (89.0)
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	4.0	6.0	1.00	3.00
B	TMVW-t	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX
D	1815	0	1815	0	0	MECHANICAL
F	1965	0	1965	0	0	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE COMBINED		MAX./MIN. COMPONENT REACTIONS		DEAD	SOIL
	SNOW	LIVE	PERM. LIVE	WIND		
D	1278	871 / 0	0 / 0	0 / 0	407 / 0	0 / 0
F	1383	943 / 0	0 / 0	0 / 0	441 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO		FR-TO			
A-B	-1630 / 0	-91.8	-91.8	0.06 (1)	6.25	E-B	0 / 1540	0.19 (1)
B-C	-10 / 0	-91.8	-91.8	0.05 (1)	10.00	B-D	-1846 / 0	0.22 (1)
D-C	-113 / 0	0.0	0.0	0.01 (1)	7.81	A-E	0 / 1517	0.19 (1)
F-A	-1233 / 0	0.0	0.0	0.04 (1)	7.81			
F-G	0 / 0	-18.5	-18.5	0.19 (1)	10.00			
G-E	0 / 0	-18.5	-18.5	0.19 (1)	10.00			
E-H	0 / 1467	-18.5	-18.5	0.34 (1)	10.00			
H-D	0 / 1467	-18.5	-18.5	0.34 (1)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	2-8-12	-734	-734	---	BACK	VERT	TOTAL	---	C1
G	8-12	-736	-736	---	BACK	VERT	TOTAL	---	C1
H	4-8-12	-734	-734	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.06/1.00 (A-B:1), BC=0.34/1.00 (D-E:1), WB=0.22/1.00 (B-D:1), SSI=0.24/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
MT20	650	371	1747
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.70 (D) (INPUT = 0.90)
JSI METAL= 0.33 (D) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23080848

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434590	T23Z	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:53:06 2023 Page 2

ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-2aELAog9fKFI4h8ZVxJcfcxSRxsoRoNtrLu0z9yknGx

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
C	TMV+p	MT20	3.0	4.0		
D	BMVW1+p	MT20	4.0	6.0		
E	BMWW+t	MT20	4.0	10.0		
F	BMV1+p	MT20	4.0	6.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23080848

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024


RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434591	T23Z1	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:48:17 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zh9C3ynKil-zzG5W KtiXrlvGY03kdqRfT3LRE7D4dLoiOEKPykhLS



Scale = 1:23.5

TOTAL WEIGHT = 2 X 29 = 58 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
D - C	2x4	DRY	No.2	SPF	
F - A	2x6	DRY	No.2	SPF	
F - D	2x6	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C 1 12	TOP	
C-D 1 12	TOP	
F-A 2 12	TOP	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2 12	SIDE(183.1)	
WEBS : (0.122"x3") SPIRAL NAILS		
B-E 1 3	SIDE(220.4)	
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	4.0	6.0	1.00	3.00
B	TMVW-t	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
D	1827	0	1827	0
F	1411	0	1411	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN	COMPONENT REACTIONS	DEAD	SOIL
D	1286	876 / 0	0 / 0	410 / 0	0 / 0
F	994	675 / 0	0 / 0	319 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)
FR-TO									
A-B	-1732 / 0	-91.8	-91.8	0.06 (1)	6.25	E-B	0 / 1656	0.20 (1)	
B-C	-9 / 0	-91.8	-91.8	0.05 (1)	10.00	B-D	-1959 / 0	0.23 (1)	
D-C	-114 / 0	0.0	0.0	0.01 (1)	7.81	A-E	0 / 1610	0.20 (1)	
F-A	-1303 / 0	0.0	0.0	0.05 (1)	7.81				
F-G	0 / 0	-18.5	-18.5	0.10 (1)	10.00				
G-E	0 / 0	-18.5	-18.5	0.10 (1)	10.00				
E-H	0 / 1557	-18.5	-18.5	0.34 (1)	10.00				
H-D	0 / 1557	-18.5	-18.5	0.34 (1)	10.00				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	2-7-4	-1088	-1088	---	BACK	VERT	TOTAL	---	C1
H	4-7-4	-734	-734	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.02")

CSI: TC=0.06/1.00 (A-B:1), BC=0.34/1.00 (D-E:1), WB=0.23/1.00 (B-D:1), SSI=0.50/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.74 (D) (INPUT = 0.90)
JSI METAL= 0.35 (D) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23080860

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434591	T23Z1	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:48:17 2023 Page 2

ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-zzG5W_KtiXrlvGY03kdqRfT3LRE7D4dLOtOEKPykhlS

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
C	TMV+p	MT20	3.0	4.0		
D	BMVW1+p	MT20	4.0	6.0		
E	BMWW+t	MT20	4.0	10.0		
F	BMV1+p	MT20	4.0	6.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY

DWG # TR23080860

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	T24	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:56:06 2023 Page 2

ID:YfdYYpXmLXEEbZ5zlh9C3ynKil-kC6OxL03GexCgLu91kXpyZOBzVFjcFNNELVYIjykhE7

NOTES- (1)
 1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
 DWG # TR23080843

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434355	T24Z	1	2	GREENPARK HOMES TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 5 Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:41:34 2023 Page 2
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-GRPlxBs4dj3x3LEZybuKcgHA1 fEltV0jhGPhGykhR

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23080855

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T25	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:56:08 2023 Page 1
ID:YfxdYYpXmLXEEbZ5Zlh9C3ynKil-gbD9M11JoFBwrf2X99aH1 UYqlyP49sqhf fMcvkhE5



Scale = 1:25.8

TOTAL WEIGHT = 2 X 18 = 36 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - B	2x4	DRY	No.2	SPF
C - B	2x4	DRY	No.2	SPF
D - A	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-B 1 12	TOP	
B-C 1 12	TOP	
D-A 1 12	TOP	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D-C 1 12	SIDE (0.0)	
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	6.0	Edge	
B	TMV+p	MT20	3.0	4.0		
C	BMVW1+t	MT20	4.0	6.0		
D	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
C	905	0	905	0
D	752	0	752	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 1-8.

UNFACTORED REACTIONS

	1ST CASE	MAX/MIN.	COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
C	638	428 / 0	0 / 0	0 / 0	0 / 0	210 / 0	0 / 0
D	530	356 / 0	0 / 0	0 / 0	0 / 0	174 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CS (LC)	MEMB. FORCE (LBS)
FR-TO		FROM TO	UNBRAC LENGTH	FR-TO
A-B	0 / 0	-91.8 -91.8	0.11 (1)	10.00
C-B	-161 / 0	0.0 0.0	0.03 (1)	7.81
D-A	-161 / 0	0.0 0.0	0.01 (1)	7.81
D-E	0 / 0	-18.5 -18.5	0.46 (1)	10.00
E-F	0 / 0	-18.5 -18.5	0.46 (1)	10.00
F-C	0 / 0	-18.5 -18.5	0.46 (1)	10.00

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	1-0-12	-447	-447	—	BACK	VERT	TOTAL	—	C1
F	2-10-4	-449	-449	—	BACK	VERT	TOTAL	—	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN.C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/528 (0.08")

CSI: TC=0.11/1.00 (A-B:1), BC=0.46/1.00 (C-D:1), WB=0.00/1.00 (A-C:1), SSI=0.32/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.05 (A) (INPUT = 0.90)
JSI METAL= 0.03 (B) (INPUT = 0.95)



STRUCTURAL COMPONENT ONLY
DWG # TR23080844

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	T25	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:56:08 2023 Page 2

ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-gbD9M11JoFBwwf2X99aH1 UYqlyP49sqhf fMcykhE5

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23080844


CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	T26	1	2	TRUSS DESC.		



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - B 2x4 DRY No.2 SPF B - C 2x4 DRY No.2 SPF D - C 2x4 DRY No.2 SPF F - A 2x4 DRY No.2 SPF F - D 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF EXCEPT DRY: SEASONED LUMBER. DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS: CHORDS #ROWS SURFACE SPACING (IN) LOAD(PLF) TOP CHORDS : (0.122"x3") SPIRAL NAILS A-B 1 12 SIDE(61.0) B-C 1 12 SIDE(61.0) C-D 1 12 TOP F-A 1 12 TOP BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS F-D 1 12 SIDE(61.0) WEBS : (0.122"x3") SPIRAL NAILS 2x3 1 6 NAILS TO BE DRIVEN FROM ONE SIDE ONLY. GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS. TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY. SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP. PLATES (table is in inches) JT TYPE PLATES W LEN Y X A TMVW+p MT20 4.0 6.0 Edge				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS FACTORED GROSS REACTION MAXIMUM FACTORED GROSS REACTION INPUT REQORD JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX D 911 0 911 0 0 5-8 MECHANICAL F 756 0 756 0 0 5-8 1-8 A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8. UNFACTORED REACTIONS 1ST LCASE MAX./MIN. COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL D 643 430 / 0 0 / 0 0 / 0 214 / 0 0 / 0 F 534 357 / 0 0 / 0 0 / 0 177 / 0 0 / 0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (4) CHORDS WEBS MAX. FACTORED MAX. FACTORED MAX. FACTORED MEMB. FORCE VERT. LOAD LC1 MAX MAX. MEMB. MAX. FORCE MAX (LBS) (PLF) CSI (LC) UNBRAC LENGTH FR-TO (LBS) CSI (LC) FR-TO FROM TO A-B -366 / 0 -91.8 -91.8 0.04 (1) 6.25 E-B 0 / 61 0.01 (4) B-C -281 / 0 -91.8 -91.8 0.02 (1) 6.25 E-C 0 / 719 0.09 (1) D-C -722 / 0 0.0 0.0 0.07 (1) 7.81 A-E 0 / 325 0.04 (1) F-A -498 / 0 0.0 0.0 0.03 (1) 7.81 F-G 0 / 0 -18.5 -18.5 0.20 (1) 10.00 G-E 0 / 0 -18.5 -18.5 0.20 (1) 10.00 E-H 0 / 0 -18.5 -18.5 0.14 (1) 10.00 H-D 0 / 0 -18.5 -18.5 0.14 (1) 10.00 SPECIFIED CONCENTRATED LOADS (LBS) JT LOC. LC1 MAX- MAX+ FACE DIR. TYPE HEEL CONN. B 2-1-0 -8 -8 --- BACK VERT TOTAL --- C1 E 1-11-4 -1 -1 --- BACK VERT TOTAL --- C1 G 1-0-12 -447 -447 --- FRONT VERT TOTAL --- C1 H 2-10-4 -449 -449 --- FRONT VERT TOTAL --- C1 CONNECTION REQUIREMENTS 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 25.6 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 39.0 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC 2018 , NBC-2019AE - PART 9 OF OBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (0.19") CALCULATED VERT. DEFL.(LL) = L/ 999 (0.01") ALLOWABLE DEFL.(TL)= L/360 (0.19") CALCULATED VERT. DEFL.(TL) = L/ 999 (0.01") CSI: TC=0.07/1.00 (C-D:1) , BC=0.20/1.00 (E-F:1) , WB=0.09/1.00 (C-E:1) , SSI=0.20/1.00 (D-E:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS= 1.00 COMPANION LIVE LOAD FACTOR = 1.00 AUTOSOLVE RIGHT HEEL ONLY TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.49 (C) (INPUT = 0.90) JSI METAL= 0.11 (E) (INPUT = 0.95)			
--	--	--	--	--	--	--	--	--	--	--	--



STRUCTURAL COMPONENT ONLY
DWG # TR23080845

CITY OF RICHMOND HILL

BUILDING DIVISION

05/01/2024

RECEIVED

CONTINUED ON PAGE 2

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	T26	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:56:09 2023 Page 2
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-8nnXaN2xZZJnXpdqjs5WaB0j9lMnbpkpwJlCv2ykhE4

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TTW+h	MT20	3.0	4.0	2.00	1.25
C	TMVW-t	MT20	4.0	8.0		
D	BMV1+p	MT20	3.0	4.0		
E	BMVWW-t	MT20	4.0	8.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23080845

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434355	T27	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:41:35 2023 Page 1
ID:6Oq41CdGo289DtyFWSfoLuyInq7-kez78XTiO0CohVpIWPJZ8uqMPO?11JIAxL0zDiykhRk



Scale = 1:29.7

TOTAL WEIGHT = 2 X 19 = 39 lb [M]

LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - B 2x4 DRY No.2 SPF C - B 2x4 DRY No.2 SPF D - A 2x4 DRY No.2 SPF D - C 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF DRY: SEASONED LUMBER. DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS: CHORDS #ROWS SURFACE SPACING (IN) LOAD (PLF) TOP CHORDS : (0.122"x3") SPIRAL NAILS A-B 1 12 TOP B-C 1 12 TOP D-A 1 12 TOP BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS D-C 1 12 SIDE(0.0) WEBS : (0.122"x3") SPIRAL NAILS 2x3 1 6 NAILS TO BE DRIVEN FROM ONE SIDE ONLY. GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS. TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY. SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP. PLATES (table is in inches) JT TYPE PLATES W LEN Y X A TMVW+p MT20 4.0 6.0 Edge B TMV+p MT20 3.0 4.0 C BMVW1-t MT20 4.0 6.0 D BMV1+p MT20 3.0 4.0				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS FACTORED GROSS REACTION MAXIMUM FACTORED GROSS REACTION INPUT REQD BRG BRG JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX C 896 0 896 0 0 5-8 MECHANICAL 1-8 D 729 0 729 0 0 5-8 MECHANICAL 1-8 A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 1-8. UNFACTORED REACTIONS 1ST LCASE MAX/MIN COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL C 632 424 / 0 0 / 0 0 / 0 208 / 0 0 / 0 D 514 345 / 0 0 / 0 0 / 0 169 / 0 0 / 0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (4) CHORDS WEBS MAX. FACTORED MAX. FACTORED MEMB. FORCE VERT. LOAD LC1 MAX MAX. MEMB. FORCE MAX (LBS) (PLF) CSI (LC) UNBRAC LENGTH FR-TO (LBS) CSI (LC) FR-TO FROM TO A-B 0 / 0 -91.8 -91.8 0.09 (1) 10.00 A-C 0 / 0 0.00 (1) C-B -147 / 0 0.0 0.0 0.04 (1) 7.81 D-A -147 / 0 0.0 0.0 0.01 (1) 7.81 D-E 0 / 0 -18.5 -18.5 0.45 (1) 10.00 E-F 0 / 0 -18.5 -18.5 0.45 (1) 10.00 F-C 0 / 0 -18.5 -18.5 0.45 (1) 10.00 SPECIFIED CONCENTRATED LOADS (LBS) JT LOC. LC1 MAX- MAX+ FACE DIR. TYPE HEEL CONN. E 1-0-12 -447 -447 --- BACK VERT TOTAL --- C1 F 2-6-12 -449 -449 --- BACK VERT TOTAL --- C1 CONNECTION REQUIREMENTS 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 25.6 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 39.0 PSF SPACING = 24.0 IN. C/C THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC 2018 , NBC-2019AE - PART 9 OF OBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (0.19") CALCULATED VERT. DEFL.(LL) = L/ 999 (0.03") ALLOWABLE DEFL.(TL)= L/360 (0.19") CALCULATED VERT. DEFL.(TL) = L/ 592 (0.07") CSI: TC=0.09/1.00 (A-B:1) , BC=0.45/1.00 (C-D:1) , WB=0.00/1.00 (A-C:1) , SSI=0.32/1.00 (C-D:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS= 1.00 COMPANION LIVE LOAD FACTOR = 1.00 AUTOSOLVE RIGHT HEEL ONLY TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (Psi) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.05 (A) (INPUT = 0.90) JSI METAL= 0.03 (B) (INPUT = 0.95)			
---	--	--	--	---	--	--	--	--	--	--	--



STRUCTURAL COMPONENT ONLY
DWG # TR23080856

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

CONTINUED ON PAGE 2

JOB NAME 434355	TRUSS NAME T27	QUANTITY 1	PLY 2	JOB DESC. GREENPARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:41:35 2023 Page 2
ID:6Oq41CdGo289DtyFWSfoLuyng7-kez78XTiO0CohVplWJPZ8ugMPO?11JlAxL0zDlykhRk

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23080856

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434355	T28	1	2	TRUSS DESC.		



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - B 2x4 DRY No.2 SPF B - C 2x4 DRY No.2 SPF D - C 2x4 DRY No.2 SPF F - A 2x4 DRY No.2 SPF F - D 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF EXCEPT DRY: SEASONED LUMBER. DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS: CHORDS #ROWS SURFACE SPACING (IN) LOAD(PLF) TOP CHORDS : (0.122"x3") SPIRAL NAILS A-B 1 12 SIDE(61.0) B-C 1 12 SIDE(61.0) C-D 1 12 TOP F-A 1 12 TOP BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS F-D 1 12 SIDE(61.0) WEBS : (0.122"x3") SPIRAL NAILS E-C 1 6 SIDE(105.2) 2x3 1 6 NAILS TO BE DRIVEN FROM ONE SIDE ONLY. GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS. TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY. SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS FACTORED GROSS REACTION MAXIMUM FACTORED GROSS REACTION INPUT REQD JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX D 903 0 903 0 0 MECHANICAL F 733 0 733 0 0 5-8 1-8 A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8. UNFACTORED REACTIONS 1ST LCASE MAX./MIN. COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL D 637 425 / 0 0 / 0 0 / 0 212 / 0 0 / 0 F 517 346 / 0 0 / 0 0 / 0 0 / 0 171 / 0 0 / 0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. LOADING TOTAL LOAD CASES: (4) CHORDS WEBS MAX. FACTORED MAX. FACTORED MEMB. FORCE VERT. LOAD LC1 MAX MAX. MEMB. MAX. FORCE MAX (LBS) (PLF) CSI (LC) UNBRAC LENGTH FR-TO (LBS) CSI (LC) FR-TO FROM TO A-B -336 / 0 -91.8 -91.8 0.04 (1) 6.25 E-B 0 / 54 0.01 (4) B-C -259 / 0 -91.8 -91.8 0.01 (1) 6.25 E-C 0 / 824 0.10 (1) D-C -828 / 0 0.0 0.0 0.08 (1) 7.81 A-E 0 / 299 0.04 (1) F-A -466 / 0 0.0 0.0 0.03 (1) 7.81 F-G 0 / 0 -18.5 -18.5 0.20 (1) 10.00 G-E 0 / 0 -18.5 -18.5 0.20 (1) 10.00 E-H 0 / 0 -18.5 -18.5 0.13 (1) 10.00 H-D 0 / 0 -18.5 -18.5 0.13 (1) 10.00 SPECIFIED CONCENTRATED LOADS (LBS) JT LOC. LC1 MAX- MAX+ FACE DIR. TYPE HEEL CONN. B 2-1-0 -8 -8 --- BACK VERT TOTAL --- C1 E 1-11-4 -1 -1 --- BACK VERT TOTAL --- C1 G 1-0-12 -447 -447 --- FRONT VERT TOTAL --- C1 H 2-6-12 -449 -449 --- FRONT VERT TOTAL --- C1 CONNECTION REQUIREMENTS 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 25.6 PSF DL = 8.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 39.0 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC2018, NBC-2019AE - PART 9 OF OBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (0.19") CALCULATED VERT. DEFL.(LL) = L/ 999 (0.01") ALLOWABLE DEFL.(TL)= L/360 (0.19") CALCULATED VERT. DEFL.(TL) = L/ 999 (0.01") CSI: TC=0.08/1.00 (C-D:1) , BC=0.20/1.00 (E-F:1) , WB=0.10/1.00 (C-E:1) , SSI=0.25/1.00 (D-E:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00 COMPANION LIVE LOAD FACTOR = 1.00 AUTOSOLVE RIGHT HEEL ONLY TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.63 (E) (INPUT = 0.90) JSI METAL= 0.13 (E) (INPUT = 0.95)			
---	--	--	--	--	--	--	--	---	--	--	--



STRUCTURAL COMPONENT ONLY
DWG # TR23080857

CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434355	T28	1	2	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:41:36 2023 Page 2

ID:6Oq41CdGo289DtyFWSfoLuyng7-CqXVLtUL9KKeleOx40xoh5MXJoPRmiQJA?IWl9ykhRj

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	6.0	Edge	
B	TTW+h	MT20	3.0	4.0	2.00	1.25
C	TMVW-t	MT20	4.0	6.0		
D	BMV1+p	MT20	3.0	4.0		
E	BMWWV-t	MT20	4.0	6.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.




STRUCTURAL COMPONENT ONLY
DWG # TR23080857

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua



DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
 DL = 6.0 PSF

BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF PART
9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.85")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.08")
ALLOWABLE DEFL.(TL)= L/360 (0.85")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.15")


CSI: TC=0.42/1.00 (B-C:1) , BC=0.32/1.00 (K-M:1) ,
WB=0.28/1.00 (B-N:1) , SSI=0.18/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN THE
TRUSS MANUFACTURING PLANT .



SPECIFIED CONCENTRATED LOADS (LBS)									
JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-318	-318	---	FRONT	VERT	TOTAL	---	C1
F	19-7-8	-318	-318	---	FRONT	VERT	TOTAL	---	C1
J	19-6-12	-21	-21	---	FRONT	VERT	TOTAL	---	C1

CITY OF RICHMOND HILL
BUILDING DIVISION
05/01/2024
RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T31	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:09 2023 Page 2
ID:pYk_ur5hyVX0CBYnrb33OynG4G-y_1eAqNlwzP5_3c7iEUFTbkjwivRlMa5Ehh6sgykpg

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	6.0	1.00	3.25
C	TTWW-m	MT20	5.0	6.0	2.50	1.75
D	TMW+w	MT20	2.0	4.0		
E	TMWW-l	MT20	4.0	6.0		
F	TTWW-m	MT20	5.0	6.0	2.50	1.75
G	TMVW-p	MT20	4.0	6.0	1.00	3.25
I	BMV1+p	MT20	4.0	6.0		
J	BMWW-l	MT20	5.0	6.0		
K	BMWW-t	MT20	4.0	6.0		
L	BS-l	MT20	5.0	6.0		
M	BMWWW-l	MT20	5.0	6.0		
N	BMWW-l	MT20	5.0	6.0		
O	BMV1+p	MT20	4.0	6.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

SPECIFIED CONCENTRATED LOADS (LBS)									
JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
N	5-11-4	-21	-21	--	FRONT	VERT	TOTAL	--	C1
P	7-11-4	-76	-76	--	FRONT	VERT	TOTAL	--	C1
Q	9-11-4	-76	-76	--	FRONT	VERT	TOTAL	--	C1
R	11-6-12	-76	-76	--	FRONT	VERT	TOTAL	--	C1
S	13-6-12	-76	-76	--	FRONT	VERT	TOTAL	--	C1
T	15-6-12	-76	-76	--	FRONT	VERT	TOTAL	--	C1
U	17-6-12	-76	-76	--	FRONT	VERT	TOTAL	--	C1
V	1-11-4	-20	-20	--	FRONT	VERT	TOTAL	--	C1
W	3-11-4	-21	-21	--	FRONT	VERT	TOTAL	--	C1
X	7-11-4	-21	-21	--	FRONT	VERT	TOTAL	--	C1
Y	9-11-4	-21	-21	--	FRONT	VERT	TOTAL	--	C1
Z	11-6-12	-21	-21	--	FRONT	VERT	TOTAL	--	C1
AA	13-6-12	-21	-21	--	FRONT	VERT	TOTAL	--	C1
AB	15-6-12	-21	-21	--	FRONT	VERT	TOTAL	--	C1
AC	17-6-12	-21	-21	--	FRONT	VERT	TOTAL	--	C1
AD	21-6-12	-21	-21	--	FRONT	VERT	TOTAL	--	C1
AE	23-6-12	-20	-20	--	FRONT	VERT	TOTAL	--	C1

CONNECTION REQUIREMENTS
1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

8/24/23

C. M. HEYENS

100505065

Cheng

LICENSED PROFESSIONAL ENGINEER

PROVINCE OF ONTARIO

STRUCTURAL COMPONENT ONLY
DWG # TR23080862

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED



STRUCTURAL COMPONENT ONLY
DWG # TR23080862

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED


Per: joshua.nabua

STRUCTURAL COMPONENT ONLY
DWG # TR23080863

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T33	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:12 2023 Page 1
ID:pYk ur5hyVX0CBYnRlb33OynG4G-NZ mosPdCfL ySnBpqnBH6DBV8evebOXwfvms?yqkpn



TOTAL WEIGHT = 2 X 77 = 154 lb

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - B	2x4	DRY	No.2	SPF
B - H	2x6	DRY	No.2	SPF
H - I	2x4	DRY	No.2	SPF
Q - A	2x6	DRY	No.2	SPF
J - I	2x6	DRY	No.2	SPF
Q - J	2x6	DRY	2100F 1.8E	SPF

ALL WEBS EXCEPT 2x4 DRY No.2 SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-B 1 12		SIDE(61.0)
B-H 1 12		SIDE(61.0)
H-I 1 12		SIDE(183.1)
Q-A 3 2		TOP
J-I 3 2		TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
Q-J 3 2		SIDE(2241.9)
WEBS : (0.122"x3") SPIRAL NAILS		
2x4 2 2		
P-B 1 6		
K-H 1 6		
C-O 1 6		
G-L 1 6		
P-A 1 6		
K-I 1 6		
N-E 1 6		
E-M 1 6		
N-C 1 6		
O-B 1 6		
M-G 1 6		
L-H 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	8238	0	5-8	5-7
Q VERT	5343	0	5-8	2-14

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
Q	5809	3909 / 0	0 / 0	0 / 0	1899 / 0	0 / 0
J	3767	2537 / 0	0 / 0	0 / 0	1229 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.20 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1	MAX. UNBRACED LENGTH	MEMB. FORCE (LBS)
FR-TO		FROM TO		FR-TO
A-B	-8231 / 0	-91.8 -91.8 0.24 (1)	3.28	P-B -1593 / 0
B-C	-13842 / 0	-91.8 -91.8 0.40 (1)	3.00	N-D 0 / 198
C-D	-17574 / 0	-91.8 -91.8 0.61 (1)	2.37	M-F 0 / 538
D-E	-17574 / 0	-91.8 -91.8 0.61 (1)	2.37	K-H -2522 / 0
E-F	-17854 / 0	-91.8 -91.8 0.70 (1)	2.20	A-P 0 / 8236
F-G	-17854 / 0	-91.8 -91.8 0.70 (1)	2.20	K-I 0 / 6040
G-H	-11890 / 0	-91.8 -91.8 0.27 (1)	3.38	N-E -761 / 0
H-I	-6036 / 0	-91.8 -91.8 0.14 (1)	3.89	E-M -309 / 0
Q-A	-7229 / 0	0.0 0.0 0.25 (1)	5.57	C-N 0 / 4598
J-I	-5323 / 0	0.0 0.0 0.19 (1)	6.34	O-C -2988 / 0
Q-R	0 / 0	-18.5 -18.5 0.11 (1)	10.00	B-O 0 / 7998
R-P	0 / 0	-18.5 -18.5 0.11 (1)	10.00	M-G 0 / 7227
P-S	0 / 7560	-18.5 -18.5 0.36 (1)	10.00	L-G -4760 / 0
S-O	0 / 7560	-18.5 -18.5 0.36 (1)	10.00	L-H 0 / 8050
O-T	0 / 13843	-18.5 -18.5 0.55 (1)	10.00	
T-N	0 / 13843	-18.5 -18.5 0.55 (1)	10.00	
N-U	0 / 18045	-18.5 -18.5 0.69 (1)	10.00	
U-V	0 / 18045	-18.5 -18.5 0.69 (1)	10.00	
V-M	0 / 18045	-18.5 -18.5 0.69 (1)	10.00	
M-L	0 / 11990	-18.5 -18.5 0.48 (1)	10.00	
L-K	0 / 5666	-18.5 -18.5 0.19 (1)	10.00	
K-J	0 / 0	-18.5 -18.5 0.00 (1)	10.00	

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
B	1-9-0	-43	-43	70	BACK	VERT	TOTAL	---	C1
C	3-9-12	1	1	70	BACK	VERT	TOTAL	---	C1
D	5-9-12	1	1	70	BACK	VERT	TOTAL	---	C1
E	7-3-0	1	1	70	BACK	VERT	TOTAL	---	C1
F	8-8-4	1	1	70	BACK	VERT	TOTAL	---	C1
G	10-8-4	1	1	70	BACK	VERT	TOTAL	---	C1
H	12-9-0	-43	-43	70	BACK	VERT	TOTAL	---	C1
K	12-8-4	5	1	8	BACK	VERT	TOTAL	---	C1
L	10-8-4	5	1	8	BACK	VERT	TOTAL	---	C1
M	8-6-0	-3274	-3274	---	FRONT	VERT	TOTAL	---	C1
N	8-8-4	5	1	8	BACK	VERT	TOTAL	---	C1
O	5-9-12	5	1	8	BACK	VERT	TOTAL	---	C1
P	3-9-12	5	1	8	BACK	VERT	TOTAL	---	C1
Q	1-9-12	5	1	8	BACK	VERT	TOTAL	---	C1
R	6-12	-1283	-1283	---	FRONT	VERT	TOTAL	---	C1
S	2-6-12	-1279	-1279	---	FRONT	VERT	TOTAL	---	C1

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
DL	= 8.0	PSF	
BOT CH.	LL	= 0.0	PSF
DL	= 7.4	PSF	
TOTAL LOAD	= 39.0	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.48")
CALCULATED VERT. DEFL.(LL) = L/999 (0.16")
ALLOWABLE DEFL.(TL) = L/360 (0.48")
CALCULATED VERT. DEFL.(TL) = L/615 (0.28")

CSI: TC=0.70/1.00 (F-G:1), BC=0.69/1.00 (M-N:1), WB=0.73/1.00 (A-P:1), SSI=0.57/1.00 (M-N:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (O) (INPUT = 0.90)
JSI METAL= 0.66 (A) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

CONTINUED ON PAGE 2



STRUCTURAL COMPONENT ONLY
DWG # TR23080864

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T33	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:12 2023 Page 2
ID:pYk ur5hyVX0CBYnrlb33OynG4G-NZ mosPdCfL ySnBpqnBH6DBV8evebOXwfvms?ykgpn

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	6.0	7.0	Edge	
B	TTWW+m	MT20	6.0	10.0	Edge	2.50
C	TMVW-t	MT20	5.0	8.0	2.50	3.25
D	TMVW+w	MT20	4.0	6.0		
E	TMVW+t	MT20	4.0	6.0		
F	TMVW+w	MT20	4.0	6.0		
G	TMVW-t	MT20	5.0	8.0	2.50	3.25
H	TTWW+m	MT20	6.0	10.0	Edge	2.50
I	TMVW-p	MT20	6.0	7.0	Edge	
J	BMV1+p	MT20	4.0	6.0		
K	BMVW-t	MT20	6.0	10.0	3.50	4.25
L	BMVW-t	MT20	5.0	8.0	2.50	2.75
M	BMVW-t	MT20	7.0	12.0	4.25	6.00
N	BMVW-t	MT20	7.0	12.0	4.25	6.00
O	BMVW-t	MT20	5.0	8.0	2.50	2.75
P	BMVW-t	MT20	6.0	10.0	3.50	4.25
Q	BMV1+p	MT20	4.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
T	4-6-12	-1279	-1279	---	FRONT	VERT	TOTAL	---	C1
U	6-6-12	-1279	-1279	---	FRONT	VERT	TOTAL	---	C1
V	7-3-0	5	1	8	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY
DWG # TR23080864

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T34	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:13 2023 Page 1
ID:pYk ur5hyVX0CBYnrb33OynG4G-rfX90BQFzzUrZcMNMXIQQJmTnX8yND3h9JfJ?Rykqpm



Scale = 1:19.6

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF
G - B	2x4	DRY	No.2	SPF
G - E	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B	TMW-t	MT20	4.0	6.0
C	TTW-m	MT20	4.0	6.0
D	TMW-t	MT20	4.0	6.0
E	BMV1+p	MT20	3.0	4.0
F	BMVWW-t	MT20	4.0	6.0
G	BMV1+p	MT20	3.0	4.0

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	BRG	BRG
E	324	0	324	0	0
G	448	0	448	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	DEAD	SOIL
E	229	150 / 0	0 / 0	0 / 0
G	315	220 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	FORCE (LBS)	VERT. LOAD	MAX. (PLF)	MEMB.	FORCE (LBS)
FR-TO		FROM	TO	FR-TO	
A-B	0 / 28	-91.8	-91.8	F-C	-187 / 0
B-C	-187 / 0	-91.8	-91.8	F-D	0 / 269
C-D	-156 / 0	-91.8	-91.8	B-F	0 / 171
E-D	-316 / 0	0.0	0.0		
G-B	-417 / 0	0.0	0.0		
G-F	0 / 0	-18.5	-18.5		
F-E	0 / 0	-18.5	-18.5		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.22/1.00 (B-C:1), BC=0.06/1.00 (F-G:4), WB=0.06/1.00 (D-F:1), SSI=0.12/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.32 (F) (INPUT = 0.90)
JSI METAL= 0.08 (F) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080865

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T35	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:14 2023 Page 1
ID:pYk ur5hyVX0CByNrlb33OynG4G-Jy5XDXRtkGciBixawFqfMXJZaxS96qFqOzOtXuykqp



Scale = 1:23.5

TOTAL WEIGHT = 25 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	No.2	DESCR.	SPF
A - C	2x4	DRY	No.2	SPF				
D - C	2x4	DRY	No.2	SPF				
E - B	2x4	DRY	No.2	SPF				
E - D	2x4	DRY	No.2	SPF				
ALL WEBS	2x3	DRY	No.2	SPF				
DRY: SEASONED LUMBER.								

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0			
C	TMV+p	MT20	3.0	4.0			
D	BMVW1-t	MT20	4.0	6.0			
E	BMV1+p	MT20	3.0	4.0			

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQRD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
D	324	0	324	0
E	448	0	448	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

1ST CASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
D	229	150 / 0	0 / 0	0 / 0	0 / 0	79 / 0	0 / 0
E	315	220 / 0	0 / 0	0 / 0	0 / 0	95 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED				
MEMB.	FORCE	VERT. LOAD	LC1	MAX	MAX.	MEMB.	FORCE	MAX	
	(LBS)	(PLF)		CSI (LC)	UNBRAC		(LBS)	CSI (LC)	
FR-TO		FROM	TO		LENGTH	FR-TO			
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	B-D	0 / 0	0.00 (1)	
B-C	0 / 0	-91.8	-91.8	0.54 (1)	10.00				
D-C	-270 / 0	0.0	0.0	0.07 (1)	7.81				
E-B	-394 / 0	0.0	0.0	0.04 (1)	7.81				
E-D	0 / 0	-18.5	-18.5	0.19 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.54/1.00 (B-C:1), BC=0.19/1.00 (D-E:4),
WB=0.00/1.00 (B-D:1), SSI=0.19/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987
			1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.20 (B) (INPUT = 0.90)
JSI METAL= 0.07 (C) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024


RECEIVED

Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080866

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T36	1	2	TRUSS DESC.		



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T36	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:16 2023 Page 2

ID:pYk ur5hyVX0CByNrIb33OynG4G-FKDHeDS8GusPQ35y2qs7RyQ 6l0xaTT7rHt cmykgpi

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMWW-t	MT20	5.0	6.0		
B	TMWW-t	MT20	4.0	6.0		
C	TS-t	MT20	3.0	8.0		
D	TMWW-w	MT20	2.0	4.0		
E	TMWW-t	MT20	4.0	6.0		
F	TMWW-t	MT20	5.0	6.0		
H	BMWW-t	MT20	6.0	16.0	3.00	Edge
I	BMWW-t	MT20	5.0	6.0		
J	BS-t	MT20	3.0	8.0		
K	BMWW-t	MT20	4.0	6.0		
L	BMWW-t	MT20	5.0	6.0		
M	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
T	14-0-12	-1	-1	--	BACK	VERT	TOTAL	--	C1
U	16-0-12	-1	-1	--	BACK	VERT	TOTAL	--	C1
V	18-0-12	-14	-14	--	BACK	VERT	TOTAL	--	C1
W	2-0-12	-12	-12	--	BACK	VERT	TOTAL	--	C1
X	4-0-12	-12	-12	--	BACK	VERT	TOTAL	--	C1
Y	6-0-12	-12	-12	--	BACK	VERT	TOTAL	--	C1
Z	8-0-12	-12	-12	--	BACK	VERT	TOTAL	--	C1
AA	10-0-12	-12	-12	--	BACK	VERT	TOTAL	--	C1
AB	14-0-12	-12	-12	--	BACK	VERT	TOTAL	--	C1
AC	16-0-12	-12	-12	--	BACK	VERT	TOTAL	--	C1
AD	18-0-12	-12	-12	--	BACK	VERT	TOTAL	--	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY
DWG # TR23080867

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T37	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:17 2023 Page 1
ID:pYk ur5hyVX0CBYnrib33OynG4G-jXnfrZTm1B G2Dq8bNNM 9xAQ9TKJ0IG4xdX8Dykqp



TOTAL WEIGHT = 30 lb [M]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
G - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - C	2x4	DRY	No.2	SPF
G - D	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	4.0	6.0		
B	TMVW-w	MT20	2.0	4.0		
C	TMVW-t	MT20	4.0	6.0		
E	BMVW-t	MT20	6.0	10.0	3.00	Edge
F	BMVWVW-t	MT20	4.0	6.0		
G	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-

- (1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	DOWN	IN-SX	IN-SX
G	413	0	3-8	1-8
D	413	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	292	192 / 0	0 / 0	0 / 0	0 / 0	100 / 0	0 / 0
D	292	192 / 0	0 / 0	0 / 0	0 / 0	100 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
G-A	-396 / 0	0.0	0.0 0.05 (1)	F-B	-398 / 0	0.06 (1)	
A-B	-407 / 0	-91.8	-91.8 0.18 (1)	F-C	0 / 488	0.11 (1)	
B-C	-407 / 0	-91.8	-91.8 0.18 (1)	A-F	0 / 488	0.11 (1)	
E-C	-396 / 0	0.0	0.0 0.05 (1)				
G-F	0 / 0	-18.5	-18.5 0.09 (4)				
F-E	0 / 0	-18.5	-18.5 0.22 (1)				
E-D	0 / 0	-110.3	-110.3 0.09 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
DL =	6.0	PSF	
BOT CH.	LL =	0.0	PSF
DL =	7.4	PSF	
TOTAL LOAD =	39.0	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.25")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.25")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.04")

CSI: TC=0.18/1.00 (B-C:1), BC=0.22/1.00 (E-F:1),
WB=0.11/1.00 (C-F:1), SSI=0.16/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.59 (F) (INPUT = 0.90)
JSI METAL= 0.14 (F) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080868

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T38	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:18 2023 Page 1
ID:pYk ur5hyVX0CBYnrlb33OynG4G-BjL23vUOoV67qNfL95ubXNTK8YpY2ToQlbM4gfvkqph



TOTAL WEIGHT = 32 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER
G - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - C	2x4	DRY	No.2	SPF
G - D	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-t	MT20	4.0	6.0	
B	TMVW-w	MT20	2.0	4.0	
C	TMVW-t	MT20	4.0	6.0	
E	BMVW-t	MT20	6.0	10.0	
F	BMVW-w	MT20	4.0	6.0	
G	BMV1+p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
G	413	0	413	0	0
D	413	0	413	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	292	192 / 0	0 / 0	0 / 0	0 / 0	100 / 0	0 / 0
D	292	192 / 0	0 / 0	0 / 0	0 / 0	100 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO		FR-TO	
G-A	-397 / 0	0.0 0.0 0.07 (1)	7.81	F-B	-399 / 0
A-B	-317 / 0	-91.8 -91.8 0.18 (1)	6.25	F-C	0 / 417
B-C	-317 / 0	-91.8 -91.8 0.18 (1)	6.25	A-F	0 / 417
E-C	-397 / 0	0.0 0.0 0.07 (1)	7.81		
G-F	0 / 0	-18.5 -18.5 0.09 (4)	10.00		
F-E	0 / 0	-18.5 -18.5 0.22 (1)	10.00		
E-D	0 / 0	-110.3 -110.3 0.09 (1)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL		
DL	=	25.6	PSF
DL	=	6.0	PSF
BOT CH.	LL		
DL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.25")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.25")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.04")

CSI: TC=0.18/1.00 (B-C:1) , BC=0.22/1.00 (E-F:1) , WB=0.09/1.00 (C-F:1) , SSI=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371 1747 788 1987 1873	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.49 (F) (INPUT = 0.90)
JSI METAL= 0.12 (F) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080869

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T39	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:19 2023 Page 1
ID:YfxdYypXmLXEEbZ5zlh9C3vnrKil-gvvQGfV0ZpE HXqXioPq3a0VQy3knsyZXF6eC5ykqpc



Scale = 1:23.5

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - A	2x6	DRY	No.2
F - D	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C 1	12	TOP
C-D 1	12	TOP
F-A 2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2	11	SIDE(244.1)
WEBS : (0.122"x3") SPIRAL NAILS		
B-E 1	2	SIDE(397.0)
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMWV-p	MT20	4.0	6.0	1.00	3.00
B	TMWW-t	MT20	5.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
D	2773	0	2773	0	0
F	2193	0	2193	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
D	1956	1312 / 0	0 / 0	0 / 0	0 / 0	644 / 0	0 / 0
F	1543	1054 / 0	0 / 0	0 / 0	0 / 0	489 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.53 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX.	MEMB.	MAX. FACTORED	MAX.
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	CSI (LC)	UNBRAC	LENGTH	FR-TO	MEMB.	FORCE (LBS)	CSI (LC)	
FR-TO										
A-B	-2638 / 0	-91.8	-91.8	0.08 (1)	5.53	E-B	0 / 2691	0.33 (1)		
B-C	-7 / 0	-91.8	-91.8	0.06 (1)	10.00	B-D	-2977 / 0	0.35 (1)		
D-C	-120 / 0	0.0	0.0	0.01 (1)	7.81	A-E	0 / 2447	0.30 (1)		
F-A	-1927 / 0	0.0	0.0	0.07 (1)	7.81					
F-G	0 / 0	-18.5	-18.5	0.06 (1)	10.00					
G-E	0 / 0	-18.5	-18.5	0.06 (1)	10.00					
E-H	0 / 2366	-18.5	-18.5	0.54 (1)	10.00					
H-D	0 / 2366	-18.5	-18.5	0.54 (1)	10.00					

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	2-8-0	-1735	-1735	---	BACK	VERT	TOTAL	---	C1
G	7-4	-241	-241	---	BACK	VERT	TOTAL	---	C1
H	4-7-4	-1065	-1065	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 29 = 58 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.08/1.00 (A-B:1), BC=0.54/1.00 (D-E:1), WB=0.35/1.00 (B-D:1), SSI=0.28/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.83 (B) (INPUT = 0.90)
JSI METAL = 0.56 (E) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080870

CONTINUED ON PAGE 2

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	T40	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:20 2023 Page 2

ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-85ToUjWbWeK6MrvgOjHVx3coZZ?MTSWl0jmvRBlXykgpf

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	2.00	3.00
C	TTWW-m	MT20	5.0	6.0	2.00	2.25
D, F, G						
D	TMWW-t	MT20	4.0	6.0		
E	TS-t	MT20	3.0	8.0		
H	TTWW-m	MT20	5.0	6.0	2.25	2.00
I	TMVW-t	MT20	5.0	8.0		
K	BMV1+p	MT20	4.0	6.0		
L	BMWW+t	MT20	6.0	10.0		
M	BMWW+t	MT20	4.0	6.0		
N	BMWW-t	MT20	5.0	6.0		
O	BS-t	MT20	5.0	6.0		
P	BMWW-t	MT20	5.0	6.0		
Q	BMWW+t	MT20	4.0	6.0		
R	BMWW-t	MT20	5.0	6.0	2.50	2.75
S	BMV1+p	MT20	4.0	6.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY

DWG # TR23080871


CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:22 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-4UaYvGXvskcZ8 Y6OwzXhDeuGAB4 Aj?DDKlpQvkkpp



RECEIVED CONTINUED ON PAGE 2
Per: joshua.nabua



JOB NAME 434357	TRUSS NAME T40Z	QUANTITY 1	PLY 2	JOB DESC. GREENPARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:22 2023 Page 2
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-4UaYvGXvskcZ8 Y6QwzXhDeuGAB4 Ai?DDKlpQykqgc

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	6.0	1.00	3.25
C	TTWW+m	MT20	5.0	6.0	2.75	2.00
D, F, G						
D	TMWW-t	MT20	4.0	6.0		
E	TS-t	MT20	3.0	8.0		
H	TTWW-m	MT20	5.0	6.0	2.50	2.75
I	TMVW-t	MT20	5.0	8.0		
K	BMV1+p	MT20	4.0	6.0		
L	BMWW+t	MT20	6.0	10.0		
M	BMWW+t	MT20	4.0	6.0		
N, P, R						
N	BMWW-t	MT20	5.0	6.0		
O	BS-t	MT20	5.0	6.0		
Q	BMWW+t	MT20	4.0	6.0		
S	BMV1+p	MT20	4.0	6.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.



STRUCTURAL COMPONENT ONLY
DWG # TR23080872

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	J1	8	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 Mitek Industries, Inc. Thu Aug 24 09:55:34 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zh9C3ynKil-g2AIEpd oovlrQS?90zJfp3ddbQe6mSftNlrAaykhEc



Scale = 1:23.1

TOTAL WEIGHT = 8 X 17 = 134 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4 DRY	No.2	SPF
A - C	2x4 DRY	No.2	SPF
E - D	2x4 DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

NOTES-

(1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
VERT	HORZ	DOWN	HORZ	UPLIFT
E	525	0	525	0
C	202	0	202	0
D	45	0	50	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	369	257 / 0	0 / 0	0 / 0	0 / 0	111 / 0	0 / 0
C	139	113 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MEMB. FORCE (LBS)
FR-TO		FROM TO		FR-TO
E-B	-461 / 0	0.0 0.0	0.13 (4)	7.81
A-B	0 / 28	-91.8 -91.8	0.12 (1)	10.00
B-C	-30 / 0	-91.8 -91.8	0.54 (1)	6.25
E-D	0 / 0	-18.5 -18.5	0.13 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/999 (0.03")

CSI: TC=0.54/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (E) (INPUT = 0.90)
JSI METAL= 0.13 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080818


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	J2	2	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:35 2023 Page 1

ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-8EkqRlecZ61cSa1BijUYB1ct8?nerDip51UPi0vkhEc



Scale = 1:27.3



TOTAL WEIGHT = 2 X 15 = 30 lb [M]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED		MAXIMUM FACTORED		INPUT	REQRD
	GROSS REACTION		GROSS REACTION		BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX
F	341	0	341	0	0	5-8
C	178	0	178	0	0	1-8
D	36	0	40	0	0	1-8

SEE MITTEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	COMBINED					
F	239	170 / 0	0 / 0	0 / 0	69 / 0	0 / 0
C	122	99 / 0	0 / 0	0 / 0	23 / 0	0 / 0
D	29	0 / 0	0 / 0	0 / 0	29 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX.	MEMB.	MAX. FACTORED	MAX
MEMB.	FORCE (LBS)	VERT. (PLF)	CSI (LC)	UNBRAC	LENGTH	FR-TO	MEMB.	FORCE (LBS)	MAX
FR-TO		FROM	TO				FR-TO		
F-B	-305 / 0	0.0	0.0	0.03 (1)	7.81	B-E	0 / 0	0.00 (1)	
A-B	0 / 41	-91.8	-91.8	0.14 (5)	10.00				
B-C	0 / 0	-91.8	-91.8	0.23 (1)	10.00				
F-E	0 / 0	-18.5	-18.5	0.07 (4)	10.00				
E-D	0 / 0	-18.5	-18.5	0.08 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.23/1.00 (B-C:1), BC=0.08/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.19 (B) (INPUT = 0.90)
JSI METAL= 0.08 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024


RECEIVED
Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080819

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	J3	4	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:37 2023 Page 1
ID:YfxdYYpXmLXEebZ5Zlh9C3ynKil-4drRsRft5IHJiuAar8W0HShEJpTLJ7B6ZKzVwmykhEa



Scale = 1:25.8

TOTAL WEIGHT = 4 X 14 = 57 lb [M]

LUMBER				
N. L. G. A. RULES	SIZE	LUMBER	DESCR.	
CHORDS				
F - B	2x4 DRY	No.2	SPF	
A - C	2x4 DRY	No.2	SPF	
F - D	2x4 DRY	No.2	SPF	
ALL WEBS	2x3 DRY	No.2	SPF	
DRY: SEASONED LUMBER.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	6.0	Edge
E	BMV+w	MT20	2.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
F	320	0	320	0	0
C	161	0	161	0	0
D	32	0	36	0	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	224	160 / 0	0 / 0	0 / 0	0 / 0	64 / 0	0 / 0
C	111	90 / 0	0 / 0	0 / 0	0 / 0	21 / 0	0 / 0
D	26	0 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
F-B	-288 / 0	B-E	0 / 0
A-B	0 / 41		
B-C	0 / 0		
F-E	0 / 0		
E-D	0 / 0		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.19/1.00 (B-C:1), BC=0.07/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.10/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)
JSI METAL= 0.08 (B) (INPUT = 0.95)



STRUCTURAL COMPONENT ONLY
DWG # TR23080820

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	J4	7	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:38 2023 Page 1

ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-ZpPp3ngVs1PAJ2lmOs1FpfEQ3CpM2aRfo j3JLykhEZ



Scale = 1:18.5



TOTAL WEIGHT = 7 X 10 = 67 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	6.0	Edge
E	BMW+w	MT20	2.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
F	274	0	274	0	0	5-8	1-8
C	30	0	30	0	-41	1-8	1-8
D	16	0	18	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	190	144 / 0	0 / 0	0 / 0	0 / 0	47 / 0	0 / 0
C	21	17 / -28	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO	FR-TO			
F-B	-258 / 0	0.0	0.0 0.03 (1)	B-E	0 / 0	0.00 (1)	
A-B	0 / 41	-91.8	-91.8 0.13 (1)				
B-C	-32 / 0	-91.8	-91.8 0.12 (1)				
			6.25				
F-E	0 / 0	-18.5	-18.5 0.02 (4)				
E-D	0 / 0	-18.5	-18.5 0.01 (4)				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.13/1.00 (A-B:1), BC=0.02/1.00 (E-F:4), WB=0.00/1.00 (B-E:1), SSI=0.08/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL = 0.07 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080821


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	J5	1	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:39 2023 Page 1

ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-10zBH7h7dLx1xCKzyZYUMnbpc9Un1hO0eScroykhEY



Scale = 1:19.9



TOTAL WEIGHT = 11 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMV+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
F	242	0	242	0	5-8	1-8
C	96	0	96	0	1-8	1-8
D	19	0	22	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	169	124 / 0	0 / 0	0 / 0	0 / 0	45 / 0	0 / 0
C	66	53 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0
D	15	0 / 0	0 / 0	0 / 0	0 / 0	15 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED			
MEMB.	FORCE	VERT. LOAD	LC1	MAX	MEMB.	FORCE	MAX
	(LBS)	(PLF)		CSI (LC)		(LBS)	CSI (LC)
FR-TO		FROM	TO	UNBRAC	FR-TO		
				LENGTH			
F-B	-223 / 0	0.0	0.0	0.02 (1)	7.81	0 / 0	0.00 (1)
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00		
B-C	0 / 0	-91.8	-91.8	0.07 (1)	10.00		
F-E	0 / 0	-18.5	-18.5	0.02 (4)	10.00		
E-D	0 / 0	-18.5	-18.5	0.02 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.13/1.00 (A-B:1), BC=0.02/1.00 (E-F:4), WB=0.00/1.00 (B-E:1), SSI=0.08/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (B) (INPUT = 0.90)
JSI METAL= 0.06 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080822


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	J7W	6	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:41 2023 Page 1
ID:YfxdYYpXmLXEebZ5Zlh9C3ynKil-zO5xioiN9ynIAVUL4 byRlsvDQlqFwVhUyxivgykhEW



Scale = 1:14.9



TOTAL WEIGHT = 6 X 19 = 114 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	SPF
A - D	2x4	DRY	No.2	SPF
B - E	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB1-I	MT20	3.0	4.0	0.25 2.00
C	TMBW-t	MT20	4.0	6.0	
F	BMW+w	MT20	2.0	4.0	
G	BMW+w	MT20	2.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
D	87	0	87	0	-56	1-8	1-8
B	476	0	476	151	-292	3-0	1-8
E	267	0	267	0	-233	5-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) D

PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT B FOR 292 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT E FOR 233 LBS FACTORED UPLIFT

PROVIDE FOR 151 LBS FACTORED HORIZONTAL REACTION AT JOINT B

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
D	80	47 / 0	0 / 0	0 / 0	0 / -48	13 / 0	0 / 0
B	335	233 / 0	0 / 0	0 / 0	0 / -274	102 / 0	0 / 0
E	190	117 / 0	0 / 0	0 / 0	0 / -214	73 / 0	0 / 0

HORIZONTAL REACTIONS

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
B	---	0 / 0	0 / 0	0 / 0	108 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D, B, E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (12)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FORCE (LBS)	MAX. UNBRACED LENGTH	MAX. CSI (LC)
FR-TO		FROM TO		FR-TO			
A-B	0 / 18	-91.8 -91.8	0.11 (1)	10.00	G-C	-331 / 331	0.07 (1)
B-I	-511 / 295	-91.8 -91.8	0.05 (5)	6.25	C-F	-675 / 553	0.11 (5)
I-C	-505 / 326	-91.8 -91.8	0.13 (5)	6.25	H-I	-168 / 75	0.00 (1)
C-D	-22 / 0	-91.8 -91.8	0.06 (1)	6.25			
B-H	-395 / 483	-18.5 -18.5	0.20 (1)	6.25			
H-G	-395 / 483	-18.5 -18.5	0.20 (1)	6.25			
G-F	-395 / 483	-18.5 -18.5	0.43 (1)	6.25			
F-E	0 / 0	-18.5 -18.5	0.35 (1)	10.00			

WIND LOAD APPLIED IS DERIVED FROM REFERENCE VELOCITY PRESSURE OF { 9.2 } PSF AT (20-0-0) FT-IN-SX REFERENCE HEIGHT ABOVE GRADE AND USING EXTERNAL PEAK COEFFICIENTS, CpCg, BASED ON THE (MAIN WIND FORCE RESISTING SYSTEM). INTERNAL WIND PRESSURE IS BASED ON DESIGN (CATEGORY 2). BUILDING MAY BE LOCATED ON (OPEN TERRAIN), AND TRUSS IS DESIGNED TO BE LOCATED AT LEAST (0-0) FT-IN-SX AWAY FROM EAVE. TRUSS UPLIFT IS BASED ON TOP AND BOTTOM CHORD DEAD LOADS OF 6.0 PSF AND 7.4 PSF RESPECTIVELY.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.21")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.21")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.04")

CSI: TC=0.13/1.00 (C-I:5) , BC=0.43/1.00 (F-G:1) , WB=0.11/1.00 (C-F:5) , SSI=0.21/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.55 (F) (INPUT = 0.90)
JSI METAL= 0.34 (F) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED


Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080823

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	J8	10	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:42 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zh9C3ynKil-RbfkV8j?wGvc0f3Xdi6B VP5AqBo ORichHS6ykhEV



Scale = 1:11.0

TOTAL WEIGHT = 10 X 8 = 77 lb

LUMBER

N. L. G. A. RULES					
CHORDS	SIZE	LUMBER	DESCR.	SPF	SPF
A - C	2x4	DRY	No.2		
B - D	2x4	DRY	No.2		

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMBH1-I	MT20	4.0	6.0	Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES - (1)

1) Lateral braces to be a minimum of 2x4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG	HEEL WEDGE
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
C	83	0	83	0	0
B	244	0	244	0	0
D	37	0	37	0	0

SEE MITTEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
C	57	44 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0
B	170	125 / 0	0 / 0	0 / 0	0 / 0	45 / 0	0 / 0
D	27	11 / 0	0 / 0	0 / 0	0 / 0	16 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 19	-91.8 -91.8	0.12 (5)	E-F	-70 / 0	0.00 (1)	
B-F	-16 / 0	-91.8 -91.8	0.02 (4)				
F-C	0 / 3	-91.8 -91.8	0.05 (1)				
B-E	0 / 0	-18.5 -18.5	0.05 (1)				
E-D	0 / 0	-18.5 -18.5	0.05 (1)				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:5), BC=0.05/1.00 (B-E:1), WB=0.00/1.00 (E-F:1), SSI=0.09/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.25 (B) (INPUT = 0.90)
JSI METAL= 0.03 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080824

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434357	J30	7	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 10:24:07 2023 Page 1
ID:pYk ur5hyVX0CBYnrlb33OynG4G-0bAti8LU07jhrhvD0HC0a2WTu75tzWWonNC?noykqps



Scale = 1:13.1

TOTAL WEIGHT = 7 X 7 = 48 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	No.2	DESCR.	SPF
E - B	2x4	DRY	No.2	SPF			
A - C	2x4	DRY	No.2	SPF			
E - D	2x4	DRY	No.2	SPF			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

NOTES-

(1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
E	289	0	289	0
C	42	0	42	0
D	6	0	15	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	187	141/0	0/0	0/0	0/0	46/0	0/0
C	29	23/-18	0/0	0/0	0/0	6/0	0/0
D	6	0/-3	0/0	0/0	0/0	11/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED HORIZ. LOAD (LC)	MAX. FACTORED UPLIFT (LBS)	MAX. FACTORED UPLIFT (LC)
FR-TO		FROM	TO	LENGTH	FR-TO	
E-B	-243/0	0.0	0.0	0.04 (5)	7.81	
A-B	0/28	-91.8	-91.8	0.12 (1)	10.00	
B-C	-17/0	-91.8	-91.8	0.09 (1)	6.25	
E-D	0/0	-18.5	-18.5	0.04 (5)	10.00	

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.04/1.00 (D-E:5),
WB=0.00/1.00 (n/a:0), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747	788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (E) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED


Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080861

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	C1	3	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:26 2023 Page 1
ID:YfdYYpXmLXEEbZ5zh9C3ynKil-vWhGYqXzhLuttCrThLqRK7kMCNjEE9TU17pQt2ykhE



Scale = 1:13.2

TOTAL WEIGHT = 3 X 7 = 21 lb

LUMBER

N. L. G. A. RULES

CHORDS SIZE

E - B 2x4 DRY

A - C 2x4 DRY

E - D 2x4 DRY

DRY: SEASONED LUMBER.

LUMBER

No.2

No.2

No.2

DESCR.

SPF

SPF

SPF

PLATES (table is in inches)

JT

TYPE

PLATES

W

LEN

Y

X

B

TMV+p

MT20

3.0

4.0

E

BMV1+p

MT20

3.0

4.0

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG			
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	271	0	271	0	0	5-8	1-8
C	45	0	45	0	-23	1-8	1-8
D	8	0	17	0	-2	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C , D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	188	141 / 0	0 / 0	0 / 0	0 / 0	47 / 0	0 / 0
C	31	24 / -18	0 / 0	0 / 0	0 / 0	7 / 0	0 / 0
D	7	0 / -8	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS			WEBS		
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO	CS1 (LC)	UNBRAC LENGTH	CS1 (LC)
E-B	-244 / 0	0.0	0.0	0.04 (5)	7.81
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00
B-C	-17 / 0	-91.8	-91.8	0.09 (1)	6.25
E-D	0 / 0	-18.5	-18.5	0.04 (5)	10.00

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , NBC-2019AE

- PART 9 OF OBC 2012 (2019 AMENDMENT)

- CSA 086-14

- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")

CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")

ALLOWABLE DEFL.(TL)= L/360 (0.19")

CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")


CSI: TC=0.12/1.00 (A-B:1) , BC=0.04/1.00 (D-E:5) , WB=0.00/1.00 (n/a:0) , SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10

COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.



STRUCTURAL COMPONENT ONLY
DWG # TR23080811

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	C2	3	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 Mitek Industries, Inc. Thu Aug 24 09:55:27 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-NiFfm0XbSf0kVMPf2LgtLHVKn3ozcjdGnY QUykhEk



Scale = 1:18.3



TOTAL WEIGHT = 3 X 10 = 29 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

NOTES-

(1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
E	361	361	0	5-8
C	130	130	0	1-8
D	16	17	0	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	250	190/0	0/0	0/0	0/0	60/0	0/0
C	90	73/0	0/0	0/0	0/0	17/0	0/0
D	12	0/0	0/0	0/0	0/0	12/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		WEBS	
	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)
FR-TO						
E-B	-342/0	0.0	0.0	0.01 (4)	7.81	
A-B	0/28	-91.8	-91.8	0.13 (5)	10.00	
B-C	-19/0	-91.8	-91.8	0.22 (1)	6.25	
E-D	0/0	-18.5	-18.5	0.02 (4)	10.00	

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
DL = 6.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD = 39.0 PSF	

SPACING = 24.0 IN.C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.22/1.00 (B-C:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080812

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	C3	3	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:28 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zh9C3ynKil-rup1zMYDDY8b7V rplsvPYqihAN8i3znURIYwykhE



TOTAL WEIGHT = 3 X 12 = 35 lb

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				DESIGN CRITERIA			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.	FACTORED	GROSS REACTION	MAXIMUM FACTORED	INPUT	REQD	SPECIFIED LOADS:	
E - B	2x4	DRY	No.2	SPF	VERT	HORZ	DOWN	HORZ	UPLIFT	TOP CH. LL = 25.6 PSF	
A - C	2x4	DRY	No.2	SPF	E	284	0	284	0	DL = 6.0 PSF	
E - D	2x4	DRY	No.2	SPF	C	63	0	63	0	BOT CH. LL = 0.0 PSF	
					D	44	0	52	0	DL = 7.4 PSF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	200	137 / 0	0 / 0	0 / 0	0 / 0	62 / 0	0 / 0
C	48	21 / 0	0 / 0	0 / 0	0 / 0	25 / 0	0 / 0
D	35	0 / -3	0 / 0	0 / 0	0 / 0	37 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS				WEBS			
MEMB.	MAX. FACTORED	FACTORED	MAX	MEMB.	MAX. FACTORED	FACTORED	MAX
	FORCE	VERT. LOAD	LC1 MAX		FORCE	UNBRAC	MAX
	(LBS)	(PLF)	CSI (LC)		(LBS)	LENGTH	CSI (LC)
FR-TO		FROM	TO	FR-TO			
E-B	-227 / 0	0.0	0.0 0.11 (4)	7.81			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00			
B-C	-9 / 9	-91.8	-91.8 0.08 (4)	10.00			
E-F	0 / 0	-18.5	-18.5 0.14 (4)	10.00			
F-G	0 / 0	-18.5	-18.5 0.14 (4)	10.00			
G-D	0 / 0	-18.5	-18.5 0.14 (4)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	1-11-4	5	1	8	BACK	VERT	TOTAL	--	C1
G	3-11-4	1	1	--	BACK	VERT	TOTAL	--	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



STRUCTURAL COMPONENT ONLY
DWG # TR23080813

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	C4	3	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:29 2023 Page 1
ID:YfxdYYpXmLXEEbZ5zlh9C3ynKil-J4NPBiZr GGSkfZ2NTN8ymMrqajTRWDWj515UNykhE



Scale = 1:18.1

TOTAL WEIGHT = 3 X 14 = 42 lb [M]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

NOTES-

(1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQRD BRG IN-SX
E	405	405	0	0
C	130	130	0	0
D	45	50	0	0

SEE MITTEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	286	190 / 0	0 / 0	0 / 0	0 / 0	96 / 0	0 / 0
C	90	73 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	CSF (LC)	MEMB. FORCE (LBS)
FR-TO		FROM	TO	LENGTH FR-TO
E-B	-342 / 0	0.0	0.0	0.13 (4)
A-B	0 / 28	-91.8	-91.8	0.12 (1)
B-C	-19 / 0	-91.8	-91.8	0.22 (1)
E-D	0 / 0	-18.5	-18.5	0.13 (4)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
DL =	6.0	PSF	
BOT CH.	LL =	0.0	PSF
DL =	7.4	PSF	
TOTAL LOAD =	39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSF: TC=0.22/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SS=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX	MIN	MAX
MT20	650	371

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080814

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434351	C5	1	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:30 2023 Page 1
ID:YfdYpXmLXEebZ5zh9C3ynKil-oHwnO2aUkaOJMp8EwAuNUzv25 5RAzS4ylne0pykhEh

1-3-8 1-9-7
-1-3-8 0-0 1-9-7 1-10-8

Scale = 1:18.7



TOTAL WEIGHT = 10 lb

LUMBER

N. L. G. A. RULES					
CHORDS	SIZE	LUMBER	DESCR.	SPF	
F - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
F - D	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMV+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES-

- (1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED			MAXIMUM FACTORED			INPUT	REQRD
	GROSS REACTION		GROSS REACTION			BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
F	276	0	276	0	0	5-8	1-8
C	33	0	33	0	-40	1-8	1-8
D	17	0	19	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	COMBINED					
F	192	144 / 0	0 / 0	0 / 0	48 / 0	0 / 0
C	23	18 / -27	0 / 0	0 / 0	4 / 0	0 / 0
D	14	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO		FR-TO		
F-B	-258 / 0	0.0	0.0	0.03 (1)	7.81	0 / 0	0.00 (1)
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00		
B-C	-32 / 0	-91.8	-91.8	0.12 (1)	6.25		
F-E	0 / 0	-18.5	-18.5	0.02 (4)	10.00		
E-D	0 / 0	-18.5	-18.5	0.02 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, NBC-2019AE
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.13/1.00 (A-B:1), BC=0.02/1.00 (E-F:4), WB=0.00/1.00 (B-E:1), SSI=0.08/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080815

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
434351	C6	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:55:31 2023 Page 1
ID:YfdYYpXmLXEebZ5zh9C3ynKil-GTU9bOa6VtWA zQUuPc1BSCbOPxvQiDBPWBZFykHq



Scale = 1:18.7

TOTAL WEIGHT = 12 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMVW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
F	291	291	0	0
C	33	33	0	0
D	32	36	0	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LOASE	MAX./MIN. COMPONENT REACTIONS	DEAD	SOIL
F	204	144 / 0	0 / 0	0 / 0
C	23	18 / -27	0 / 0	0 / 0
D	26	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)
FR-TO									
F-B		-258 / 0	0.0	0.0	0.03 (1)	7.81	0 / 0	0.00 (1)	
A-B		0 / 41	-91.8	-91.8	0.14 (5)	10.00			
B-C		-32 / 0	-91.8	-91.8	0.13 (5)	6.25			
F-E		0 / 0	-18.5	-18.5	0.06 (4)	10.00			
E-G		0 / 0	-18.5	-18.5	0.07 (4)	10.00			
G-D		0 / 0	-18.5	-18.5	0.07 (4)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-11-4	1	1	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
DL =	6.0	PSF	
BOT CH.	LL =	0.0	PSF
DL =	7.4	PSF	
TOTAL LOAD =	39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.14/1.00 (A-B:5), BC=0.07/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.09/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX MIN	MAX MIN	MAX MIN	
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL = 0.07 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua




STRUCTURAL COMPONENT ONLY
DWG # TR23080816

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434355	C7	1	1	GREENPARK HOMES	
				TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:41:26 2023 Page 1
ID:6Oq41CdGo289DtyFWSfoLuyng7-VvxjFSM3VF3366d0UwISH yp4m1 QFWrtRK OkykhRt



Scale: 1/2"=1'

TOTAL WEIGHT = 12 lb


TOTAL WEIGHT = 12 LB									
[M]									
DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
BEARINGS									
FACTORED GROSS REACTION									
MAXIMUM FACTORED GROSS REACTION									
INPUT BRG									
REQRD BRG									
JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX									
F 276 0 276 0 0 5-8 1-8									
C 33 0 33 0 -40 1-8 1-8									
D 17 0 19 0 0 1-8 1-8									
SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C , D									
PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT									
UNFACTORED REACTIONS									
1ST LCASE MAX./MIN. COMPONENT REACTIONS									
JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL									
F 192 144 / 0 0 / 0 0 / 0 48 / 0 0 / 0									
C 23 18 / -27 0 / 0 0 / 0 4 / 0 0 / 0									
D 14 0 / 0 0 / 0 0 / 0 14 / 0 0 / 0									
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C									
BRACING									
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.									
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.									
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.									
LOADING									
TOTAL LOAD CASES: (5)									
CHORDS WEBS									
MAX. FACTORED FORCE (LBS) VERT. LOAD LC1 MAX. FACTORED FORCE (LBS) UNBRACED LENGTH FR-TO									
MEMB. (PLF) CSI (LC) UNBRAC LENGTH FR-TO									
F-B -258 / 0 0.0 0.0 0.04 (1) 7.81 B-E 0 / 0 0.00 (1)									
A-B 0 / 41 -91.8 -91.8 0.13 (1) 10.00									
B-C -32 / 0 -91.8 -91.8 0.12 (1) 6.25									
F-E 0 / 0 -18.5 -18.5 0.02 (4) 10.00									
E-D 0 / 0 -18.5 -18.5 0.01 (4) 10.00									
CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN									
DESIGN CRITERIA									
SPECIFIED LOADS:									
TOP CH. LL = 25.6 PSF									
DL = 6.0 PSF									
BOT CH. LL = 0.0 PSF									
DL = 7.4 PSF									
TOTAL LOAD = 39.0 PSF									
SPACING = 24.0 IN. C/C									
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015									
THIS DESIGN COMPLIES WITH:									
- PART 9 OF CBC 2018 , NBC-2019AE									
- PART 9 OF OBC 2012 (2019 AMENDMENT)									
- CSA 086-14									
- TPIC 2014									
DESIGN ASSUMPTIONS									
-OVERHANG NOT TO BE ALTERED OR CUT OFF.									
(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD									
ALLOWABLE DEFL.(LL)= L/360 (0.19")									
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")									
ALLOWABLE DEFL.(TL)= L/360 (0.19")									
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")									
CSI: TC=0.13/1.00 (A-B:1) , BC=0.02/1.00 (E-F:4) , WB=0.00/1.00 (B-E:1) , SSI=0.08/1.00 (B-C:1)									
DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10									
COMP=1.10 SHEAR=1.10 TENS= 1.10									
COMPANION LIVE LOAD FACTOR = 1.00									
TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .									
NAIL VALUES									
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PSI) (PLI)									
MAX MIN MAX MIN MAX MIN									
MT20 650 371 1747 788 1987 1873									
PLATE PLACEMENT TOL. = 0.250 inches									
PLATE ROTATION TOL. = 5.0 Deg.									
JSI GRIP= 0.16 (B) (INPUT = 0.90)									
JSI METAL= 0.07 (B) (INPUT = 0.95)									
CITY OF RICHMOND HILL BUILDING DIVISION									
05/01/2024									
RECEIVED									
Per: joshua.nabua									

LUMBER									
N. L. G. A. RULES									
CHORDS SIZE LUMBER DESCR.									
F - B 2x4 DRY No.2 SPF									
A - C 2x4 DRY No.2 SPF									
F - D 2x4 DRY No.2 SPF									
ALL WEBS 2x3 DRY No.2 SPF									
DRY: SEASONED LUMBER.									
PLATES (table is in inches)									
JT TYPE PLATES W LEN Y X									
B TMVW+p MT20 4.0 6.0 Edge									
E BMV+w MT20 2.0 4.0									
F BMV1+p MT20 3.0 4.0									
Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.									
NOTES- (1)									
1) Lateral braces to be a minimum of 2X4 SPF #2.									

8/24/23

C. M. HEYENS

100505065



LICENSED PROFESSIONAL ENGINEER

PROVINCE OF ONTARIO


STRUCTURAL COMPONENT ONLY

DWG # TR23080849

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
434355	C8	1	1	GREENPARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.630 S Jul 5 2023 MiTek Industries, Inc. Thu Aug 24 09:41:27 2023 Page 1
ID:6Oq41CdGo289DtyFWSfoLuyng7-z5U5ToNhGZBwjGCD2dGhqCUzcANf9im 653YxAykhRhs



Scale: 1/2"=1'

TOTAL WEIGHT = 13 lb

LUMBER					
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.	SPF
F - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
F - D	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	6.0	Edge
E	BMW+w	MT20	2.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
F	288	0	288	0	0	1-8	1-8
C	33	0	33	0	-40	1-8	1-8
D	30	0	33	0	0	1-8	1-8

SEE MITTEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS		DEAD		SOIL	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND		
F	202	144 / 0	0 / 0	0 / 0	0 / 0	58 / 0	0 / 0
C	23	18 / -27	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
D	24	0 / 0	0 / 0	0 / 0	0 / 0	24 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		FACTORED		WEBS		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH	MEMB.	FORCE (LBS)	MAX. CS1 (LC)
FR-TO		FROM	TO		FR-TO		
F-B	-258 / 0	0.0	0.0	0.04 (1)	7.81	0 / 0	0.00 (1)
A-B	0 / 41	-91.8	-91.8	0.14 (5)	10.00		
B-C	-32 / 0	-91.8	-91.8	0.13 (5)	6.25		
F-E	0 / 0	-18.5	-18.5	0.05 (4)	10.00		
E-G	0 / 0	-18.5	-18.5	0.06 (4)	10.00		
G-D	0 / 0	-18.5	-18.5	0.06 (4)	10.00		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-11.4	1	1	1	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.14/1.00 (A-B:5), BC=0.06/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.08/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.16 (B) (INPUT = 0.90)
JSI METAL = 0.07 (B) (INPUT = 0.95)

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED

Per: joshua.nabua



STRUCTURAL COMPONENT ONLY
DWG # TR23080850

EWP DESIGN INC.

(905) 832-2250

FAX (905) 832-0286

RESPONSIBILITIES AND SPECIFICATIONS

RESPONSIBILITIES

1. EWP DESIGN INC. is responsible for the design of trusses as individual components.
2. It is the responsibility of others to ascertain that the design loads utilized on each drawing meet or exceed the actual dead load imposed by the structure, the live load imposed by the intended use and the snow load imposed by local building code or authorities with jurisdictions.
3. All dimensions are to be verified by the owner, contractor, architect or other authorities with jurisdictions before truss fabrication.
4. EWP DESIGN INC. bears no responsibility for the erection of trusses. Persons erecting trusses are cautioned to seek professional advice regarding the temporary and permanent bracing for the system. Bracing shown on EWP DESIGN INC. drawing is specified for the truss as a component only and forms an integral part of the truss design.
5. It is the truss manufacturer's responsibility to ensure that trusses are manufactured in conformance with specifications of EWP DESIGN INC. as outlined below.

SPECIFICATIONS

1. Trusses designed by EWP DESIGN INC. conform to the relevant section of the Ontario Building Code of Canada (Part 9 or Part 4) or to the Canadian code for farm buildings, whichever applies to the building type, as indicated on the EWP DESIGN INC. drawings, and conform to the design procedures established by the Truss Plate Institute of Canada. Unit stresses used for truss designs are as per the edition of CSA-O86 shown on EWP DESIGN INC. drawings.
2. Lumber is to be the size, species and grade as specified on EWP DESIGN INC. drawings.
3. Moisture content of lumber shall not exceed 19% in service unless specified otherwise.
4. Metal connector plates shall be applied to both faces of truss at each joint and shall be positioned as specified.
5. Top chords of trusses are assumed to be continuously braced laterally by roof sheathing or by purlins at intervals not exceeding 12.5 times the thickness of top chord member.
6. Bottom chords shall be laterally braced at intervals not exceeding 3M (10') o.c., where rigid ceiling is not applied directly to the underside of chords.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF EWP DESIGN INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY THE ALPA LUMBER GROUP, AND WILL BE RETRACTED BY EWP DESIGN INC. IF UTILIZED FOR ANY OTHER PURPOSE.

February 1, 2019

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

TOE-NAIL CAPACITY DETAILS

LATERAL AND WITHDRAWAL RESISTANCE OF BEARING ANCHORAGE BY TOE-NAILS

Nail type	Diameter (in.)	Length (in.)	SPF	D. FIR	SPF	D. FIR
COMMON WIRE	3.00	0.144	122	139	30	42
	3.25	0.144	127	144	32	45
	3.50	0.160	152	173	38	52
COMMON SPIRAL	3.00	0.122	96	108	26	36
	3.25	0.122	97	108	28	40
	3.50	0.152	142	161	36	50
3.25" Gun nail	3.25	0.120	94	105	28	39

Note: If using truss with D. Fir lumber and SPF bearing plate, use tabulated SPF values in table.

Nail type:	Common wire	Common spiral	Common wire	Common spiral	Gun Nail
Diameter (in.)	0.160	0.152	0.144	0.122	0.120
Length (in.)	3.50	3.50	3.00	3.00	3.25
MEMBER	MAXIMUM NUMBER OF TOE NAILS				
2x4 SPF	2	2	3	3	3
2x6 SPF	4	4	4	5	5
2x4 D. FIR	2	2	2	2	2
2x6 D. FIR	3	3	3	4	4





Figure 1: Toe-Nailing Rafter / Ceiling Member to Girder Truss

PEO
Certificate No. 10889485



TOE-NAIL CAPACITY DETAILS

Figure 2: Toe-Nail Anchorage to Bearing Plate for Uplift



NOTES:

1. Rafter and ceiling members may be connected to top and bottom chords of girder truss by toe-nailing the members into the girder chords (see fig. 1), provided the factored vertical reactions of the supported members do not exceed the lateral resistance of the toe-nails. Mechanical connectors (hangers) are required if factored vertical reactions exceed the toe-nail capacity, or if the connection must resist horizontal loads (loads perpendicular to the face of girder or rafter).
2. Trusses, rafters or ceiling members may be anchored to the bearing plate with toe-nails (see fig. 2), provided that the factored uplift reactions due to **wind or earthquake loads** do not exceed the **withdrawal resistance of the toe-nails**. Mechanical anchors (tie-downs) are required for reactions that exceed the toe-nail withdrawal capacity. Toe-nail anchorage to bearing plates is **NOT** permitted if uplift reactions are generated from gravity loads (snow, floor live, dead).
3. Tabulated toe-nail resistances on page 1 are for **one** toe-nail. Multiply unit values by the number of nails used in the connection. Maximum number of nails in a connection shall not exceed the tabulated limits shown on page 1 for a given lumber size /species.
4. Nail values are based on specific gravity of $G = 0.42$ (SPF) and $G = 0.49$ (D. Fir).
5. Toe-nails shall be driven at approximately $1/3$ the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member.
6. For wind / earthquake loads, tabulated lateral resistances may be multiplied by 1.15 (K_D factor). No increases are permitted for tabulated withdrawal resistances.
7. Lumber must be dry ($< 19\%$ moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-19, Clause 12.9.

PEO
Certificate No. 10889485



LUL/LUS/LJS/HUS/HHUS/HGUS

SIMPSON
Strong-Tie

Standard and Double-Shear Joist Hangers



This product is preferable to similar connectors because of a) easier installation, b) higher capacities, c) lower installed cost, or a combination of these features.

Most hangers in this series have double-shear nailing — an innovation that distributes the load through two points on each joist nail for greater strength. This allows for fewer nails, faster installation, and the use of all common nails for the same connection. (Do not bend or remove tabs)

Double-shear hangers range from the light capacity LUS hangers to the highest capacity HGUS hangers. For medium load truss applications, the HUS offers a lower cost alternative and easier installation than the HGUS hangers, while providing greater load capacity and bearing than the LUS.

Material: See table on pp. 217–218.


Finish: Galvanized. Some products available in stainless steel or ZMAX® coating; see Corrosion Information, pp. 18–20.

Installation:


- Use all specified fasteners; see General Notes.
- Nails must be driven at an angle through the joist or truss into the header to achieve the tabulated resistances (except LUL).
- Where 16d commons are specified, 10d commons may be used at 0.83 of the tabulated factored resistance.
- Not designed for welded or nailer applications.
- With single ply 2x carrying members, use 10d x 1 1/2" nails into the header and 10d commons into the joist, and reduce the resistance to 0.64 of the table value where 16d nails are specified and 0.77 where 10d nails are specified.

Options:


- LUS, LJS, LUL and HUS hangers cannot be modified.
- Other sizes available; consult your Simpson Strong-Tie representative.
- See Hanger Options information on pp. 105–107.



Double-Shear Nailing Top View






Double-Shear Nailing Side View; Do not bend tab




Dome Double-Shear Nailing Side View (available on some models)


Typical HUS26 Installation with Reduced Heel Height
(Truss Designer to provide fastener quantity for connecting multiple members together)




LUS28




LU26L




HUS210
(HUS26, HUS28, and HHUS similar)



HGUS28-2



HHUS210-2



LJS26DS

C-C-CAN2020 © 2020 SIMPSON STRONG-TIE COMPANY INC.

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

TECHNICAL BULLETIN

LUS - Double Shear Joist Hangers

SIMPSON
Strong-Tie

All LUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections.

Material: 18 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA 086-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header are capable of withstanding these loads.

Installation:


- Use all specified fasteners.
- Nails: 16d = 0.162" dia. x 3 1/2" long common wire, 10d = 0.148" x 3" long common wire.
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads.
- Not designed for welded or nailer applications.

Options:

- These hangers cannot be modified




Typical LUS Installation



LUS28


Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _o ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K _p =1.15)	(K _p =1.00)	(K _p =1.15)	(K _p =1.00)
LUS24	18	1 1/16	3 1/8	1 3/4	1 15/16	(4) 10d	(2) 10d	710	1630	645	1155
LUS24-2	18	3 1/8	3 1/8	2	1 15/16	(4) 16d	(2) 16d	835	2020	590	1435
LUS26	18	1 1/16	4 1/8	1 3/4	3 3/8	(4) 10d	(4) 10d	1420	2170	1290	1630
LUS26-2	18	3 1/8	4 1/8	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920
LUS26-3	18	4 1/8	4 1/8	2	3 1/4	(4) 16d	(4) 16d	1720	2595	1545	2340
LUS28	18	1 1/16	6 1/8	1 3/4	3 3/4	(6) 10d	(6) 10d	1420	2520	1290	1790
LUS28-2	18	3 1/8	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575
LUS28-3	18	4 1/8	6 1/8	2	3 1/4	(6) 16d	(4) 16d	1720	3325	1545	2375
LUS210	18	1 1/16	7 13/16	1 3/4	3 3/8	(8) 10d	(4) 10d	1420	2785	1290	2210
LUS210-2	18	3 1/8	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195
LUS210-3	18	4 1/8	8 3/16	2	5 1/4	(8) 16d	(6) 16d	2580	3345	2320	2375

1. d_o is the distance from the seat of the hanger to the highest joist nail.




Dome Double Shear Nailing prevents tabs breaking off (available on some models).

U.S. Patent
5,603,580



Double Shear Nailing Top View.



LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2022, and reflects information available as of April 1, 2020. This information is updated periodically and should not be relied upon after June 30, 2022. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2020 Simpson Strong-Tie Company Inc.

T-SPEC LUS20 3/20 exp. 6/22

CITY OF RICHMOND HILL
BUILDING DIVISION

(800) 999-5099
strongtie.com

05/01/2024

RECEIVED
Per: joshua.nabua

TECHNICAL BULLETIN

HUS/LJS - Double Shear Joist Hangers

SIMPSON
Strong-Tie

All hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: See table

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia. x 3½" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:


- See current catalogue for options




LJS26DS




HUS210
(HUS26, HUS28, similar)



Typical LJS26DS
Installation




Typical HUS
Installation



Typical HUS Installation
(Truss Designer to provide fastener quantity for connecting multiple members together)


Model No.	Ga.	Dimensions (in.)					Fasteners		Factored Resistance (lb.)			
		W	H	B	d _e ¹	Face	Joist		D.Fir-L		S-P-F	
									Uplift (K _u =1.15) lb.	Normal (K _p =1.00) lb.	Uplift (K _u =1.15) lb.	Normal (K _p =1.00) lb.
LJS26DS	18	1⅞	5	3½	4⅞	(16) 16d	(6) 16d		2055	4265	1460	4115
HUS26	16	1⅞	5⅞	3	3⅞⅞	(14) 16d	(6) 16d		2705	4940	2065	3875
HUS28	16	1⅞	7⅞	3	6⅞	(22) 16d	(8) 16d		3605	5365	2675	4345
HUS210	16	1⅞	9⅞	3	7⅞	(30) 16d	(10) 16d		4505	5795	4010	4740
HUS1.81/10	16	1⅞	9	3	8	(30) 16d	(10) 16d		4505	6450	4010	5200

1. d_e is the distance from the seat of the hanger to the highest joist nail.




Dome Double Shear Nailing prevents tabs breaking off (available on some models).


U.S. Patent
5,603,580



Double Shear Nailing Side View. Do not bend tab back.



Double Shear Nailing Top View.



CITY OF RICHMOND HILL
BUILDING DIVISION

(800) 999-5099
strongtie.com

RECEIVED
Per: joshua.nabua



LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2022, and reflects information available as of April 1, 2020. This information is updated periodically and should not be relied upon after June 30, 2022. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2020 Simpson Strong-Tie Company Inc.

T-SPECHUS20 3/20 exp. 6/22

TECHNICAL BULLETIN

HGUS – Double Shear Joist Hangers

SIMPSON
Strong-Tie

All HGUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: 12 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%.
No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia x 3½" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:


- See current catalogue for options



HGUS28-2




Typical HGUS
Installation



Typical HGUS Installation
(Truss Designer to
provide fastener quantity
for connecting multiple
members together)


Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _o ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _o =1.15)	Normal (K _o =1.00)	Uplift (K _o =1.15)	Normal (K _o =1.00)
HGUS26	12	1½	5½	5	4½	(20) 16d	(8) 16d	2685	6625	2685	5700
HGUS26-2	12	3½	5½	4	4½	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-3	12	4½	5½	4	4½	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-4	12	6½	5½	4	4½	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS28	12	1½	7½	5	6½	(36) 16d	(12) 16d	3310	7675	3100	6900
HGUS28-2	12	3½	7½	4	6½	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-3	12	4½	7½	4	6½	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-4	12	6½	7½	4	6½	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS210	12	1½	9½	5	7½	(46) 16d	(16) 16d	3535	11070	2510	8090
HGUS210-2	12	3½	9½	4	8½	(46) 16d	(16) 16d	6840	14015	4855	10270
HGUS210-3	12	4½	9½	4	8½	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS210-4	12	6½	9½	4	8½	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS212-4	12	6½	10½	4	10½	(56) 16d	(20) 16d	7640	14995	5425	10645
HGUS214-4	12	6½	12½	4	11½	(66) 16d	(22) 16d	10130	16400	7195	11645

1. d_o is the distance from the seat of the hanger to the highest joist nail.




Dome Double
Shear Nailing
prevents tabs
breaking off
(available on
some models).


U.S. Patent
5,603,580



Double
Shear
Nailing
Side View.
Do not
bend tab
back.



Double
Shear
Nailing
Top View.



CITY OF RICHMOND HILL
BUILDING DIVISION

(800) 999-5099
strongtie.com

RECEIVED
Per: joshua.nabua



LIMIT
STATES
DESIGN


This technical bulletin is effective until June 30, 2022, and reflects information available as of April 1, 2020. This information is updated periodically and should not be relied upon after June 30, 2022. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2020 Simpson Strong-Tie Company Inc.


T-SPECHGUS20 3/20 exp. 6/22

H/TSP


Seismic and Hurricane Ties (cont.)




1 H1 Installation




2 H2A Installation




3 TSP Installation




4 H2.5A Installation
(Nails into both top plates)




5 H2.5T Installation
(Nails into both top plates)




6 H2.5T Installation




7 H3 Installation
(Nails into upper top plate)




8 H6 Stud
to Top Plate
Installation




9 H6 Stud to
Band Joist
Installation




10 H7Z Installation




11 H8 Attaching
Rafter to Double
Top Plates




12 H8 attaching Stud to Sill
((4) 8d into plate, (5) 8d into stud)




13 H8 attaching
I-Joist to Double
Top Plates




14 H10A Field-Bent
Installation



15 H10S Installation




16 H10S Installation
with Stud Offset




17 H10A
Installation

H10A optional positive angle nailing connects shear blocking to rafter. Use 8d common nails. Slot allows maximum field-bending up to a pitch of 6/12, use 75% of the table uplift value; bend one time only.




18 H14 Installation to
Double Top Plates



19 H14 Installation
to Double 2x Header

Avoid a Misinstallation



Do not make new holes or overdrive nails.

05/01/2024

RECEIVED
Per: joshua.nabua

Straps and Ties

H/TSP

Seismic and Hurricane Ties

Simpson Strong-Tie® hurricane ties provide a positive connection between truss/rafter and the wall of the structure to resist wind and seismic forces. New additions to the line provide even more options.


- H10AR — The heavy-duty design of the H10A available with a 2" wide throat to accommodate rough lumber
- H10A-2 — The H10A design with a 3" throat for double 2x members
- H2ASS, H2.5ASS and H10ASS — Popular ties now available in stainless steel

Material: See table

Finish: Galvanized. H7Z and H11Z — ZMAX® coating. Some models available in stainless steel or ZMAX; see Corrosion Information, pp. 20–24 or visit strongtie.com.

Installation:

- Use all specified fasteners; see General Notes.
- H1 can be installed with flanges facing inward (reverse of H1 installation drawing; number 1).
- H2.5T, H3 and H6 ties are shipped in equal quantities of right and left versions (right versions shown).
- Hurricane ties do not replace solid blocking.
- When installing ties on plated trusses (on the side opposite the truss plate) do not fasten through the truss plate from behind. This can force the truss plate off of the truss and compromise truss performance.
- H10A optional nailing to connect shear blocking, use 8d nails. Slots allow maximum field bending up to a pitch of 6:12; use H10A sloped loads for field bent installation.



Straps and Ties

TECHNICAL BULLETIN

H – Seismic and Hurricane Ties

SIMPSON
Strong-Tie

The H connector series provides wind and seismic ties for trusses and rafters.

Material: 18 gauge **Finish:** G90 galvanized


Design: • Factored resistances are in accordance with CSA O86-14
• Factored resistances have been increased 15%. No further increase is permitted.

Installation: • Use all specified fasteners

- Nails: 8d = 0.131" dia. x 2½" long common wire, 8d x 1½" = 0.131" x 1½" long, 10d x 1½" = 0.146" x 1½" long
- H1 can be installed with flanges facing outwards
- Hurricane ties do not replace solid blocking


Factored resistances for more than one direction for a single connection cannot be added together. A factored load which can be divided into components in the directions given must be evaluated as follows: Factored Shear/Resisting Shear + Factored Tension/Resisting Tension ≤ 1.0.

Hurricane Tie Installations to Achieve Twice the Load (Top View)




Install diagonally across from each other for minimum 2x truss.


Nailing into both sides of a single ply 2x truss may cause the wood to split.




H1




H1 Installation




H2A




H2A Installation




H2.5A




H2.5A Installation




H2.5T




H2.5T Installation
(Nails into both top plates)




H3



H3 Installation



H10A




H10A Installation

Model No.	Ga.	Fasteners			Factored Resistance (lb.)					
		To Rafter	To Plates	To Studs	D.Fir-L			S-P-F		
					Uplift	Normal		Uplift	Normal	
						F ₁	F ₂		F ₁	F ₂
H1	18	(6) 8d x 1½"	(4) 8d	—	740	685	300	680	485	215
H2A	18	(5) 8d x 1½"	(2) 8d x 1½"	(5) 8d x 1½"	830	220	75	590	155	55
H2.5A	18	(5) 8d	(5) 8d	—	805	160	160	755	160	160
H2.5T	18	(5) 8d	(5) 8d	—	835	175	240	740	160	210
H3	18	(4) 8d	(4) 8d	—	740	180	265	615	125	190
H10A	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1735	795	410	1505	565	290

- Factored resistances have been increased 15% for earthquake or wind loading with no further increase allowed.
- Factored resistances are for one anchor. A minimum after thickness of 2½" must be used when framing anchors are installed on each side of the joist and on the same side of the plate.

- When cross-grain bending or cross-grain tension cannot be avoided, mechanical reinforcement to resist such forces should be considered.
- Hurricane ties are shown installed on the outside of the wall for clarity. Installation on the inside of the wall is acceptable. For a Continuous Load Path, connections must be on same side of the wall.



CITY OF RICHMOND HILL
BUILDING DIVISION

(800) 999-5099
strongtie.com

RECEIVED
Per: joshua.nabua



LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2022, and reflects information available as of April 1, 2020. This information is updated periodically and should not be relied upon after June 30, 2022. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2020 Simpson Strong-Tie Company Inc.

T-SPECH20 3/20 exp. 6/22


TN 15-001
Piggyback Bracing

Overview:

Where piggybacks are connected ovetop of base trusses, 2x4 purlins must be first added to the flat portion of the base truss at a spacing no more than 24" o/c. These purlins not only provide support for the piggyback trusses above, but are required to laterally support the top chord of the base truss which will not have the sheathing directly connected to the flat portion of the base truss. This ensures the top chord, most often in compression, will not buckle laterally.

Further, the purlins in the plane of the flat portion require diagonal bracing to prevent lateral displacement of the purlins themselves where under certain conditions, the trusses may in fact all buckle in the same direction if this additional bracing is not added in the plane of the purlins.

Detail:



Disclaimer:

OWTFA Tech Notes are intended to provide guidance to the design community both within the membership as well as to third party designers who might benefit from the information. The details have been developed by the OWTFA technical committee and although there may be professional engineers involved in development, the information contained in the tech-note are not intended to be used without having a professional engineer review the information for a specific application. The OWTFA takes no responsibility with respect to the information provided but has developed this tech-note to offer guidance where it is not currently readily available.


CITY OF RICHMOND HILL
BUILDING DIVISION

05/02/2024


RECEIVED
Per: joshua.nabua

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths or mm. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0-1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

*Plate location details available in MiTek software or upon request.

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.

Industry Standards:

TPIC
OF SHIMMOND HILL
BUILDING DIVISION
Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths or mm (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

CCMC Reports:

11996-L, 10319-L, 13270-L, 12691-R

© 2007 MiTek® All Rights Reserved

MiTek
POWER TO PERFORM.™

MiTek Engineering Reference Sheet: Mil-7473C rev. 10-08

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by TPIC.
7. Design assumes trusses will be suitably protected from the environment in accord with TPIC.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with TPIC Quality Criteria.

RECEIVED
Per: joshua.nabua

05/01/2024

SHIMMOND HILL
BUILDING DIVISION