

SITE NAME: TRINIGROUP

BUILDER: GREENPARK HOMES

TYPE: ROSE 3

DATE: Sep-23

GFA: 2596

LO# 102624

HEATING CFM 1083 COOLING CFM 1083
TOTAL HEAT LOSS 53,704 TOTAL HEAT GAIN 36,142
AIR FLOW RATE CFM 20.17 AIR FLOW RATE CFM 29.97

furnace pressure 0.7
furnace filter 0.14
a/c coil pressure 0.26
available pressure
for s/a & r/a 0.30

#GOODMAN
GMEC960603BNA 60

AFUE = 96 %
INPUT (BTU/H) = 60,000
OUTPUT (BTU/H) = 57,600

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	15	9	4
R/A	0	0	5	2	1

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5"Ø unless noted otherwise on layout.

plenium pressure s/a 0.16
max s/a dif press. loss 0.02
min adjusted pressure s/a 0.14

r/a pressure 0.14
r/a grille press. Loss 0.02
adjusted pressure r/a 0.12


MEDLOW
MEDIUM 928
MEDIUM HIGH 1083
HIGH 1131

DESIGN CFM = 1083
CFM @ .7" E.S.P.

TEMPERATURE RISE 49 °F

RUN #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
ROOM NAME	MBR	ENS	WIC	BED-2	BED-3	BED-4	S-BATH	FLEX	BED-3	MBR	ENS-4	H-OFF	DIN	KT/BF	KT/BF	FAM	LAUN	PWD	FOY	MUD	BAS	BAS	BAS	BAS
RM LOSS MBH.	1.47	1.15	0.50	1.39	1.04	1.19	0.82	1.90	1.04	1.47	0.35	2.10	3.40	2.17	2.17	1.57	0.69	0.59	4.28	0.93	4.51	4.51	4.51	4.51
CFM PER RUN HEAT	30	23	10	28	21	24	16	38	21	30	7	42	69	44	44	32	14	12	86	19	91	91	91	91
RM GAIN MBH.	1.75	1.06	0.13	1.97	2.06	2.11	0.41	1.87	2.06	1.75	0.09	1.73	1.94	2.68	2.68	1.55	1.40	0.09	1.85	0.15	0.48	0.48	0.48	0.48
CFM PER RUN COOLING	52	32	4	59	62	63	12	56	62	52	3	52	58	80	80	47	42	3	56	5	14	14	14	14
ADJUSTED PRESSURE	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.14	0.15	0.14	0.14	0.14	0.14
ACTUAL DUCT LGH.	37	53	35	34	41	35	41	50	42	48	35	20	21	37	30	30	34	19	29	20	34	26	18	25
EQUIVALENT LENGTH	140	190	200	180	130	180	150	160	140	170	120	180	120	160	150	120	200	120	140	130	80	90	120	140
TOTAL EFFECTIVE LENGTH	177	243	235	214	171	215	191	210	182	218	155	200	141	197	180	150	234	139	169	150	114	116	138	165
ADJUSTED PRESSURE	0.08	0.06	0.06	0.07	0.09	0.07	0.08	0.07	0.08	0.07	0.09	0.07	0.1	0.07	0.08	0.1	0.06	0.11	0.08	0.1	0.12	0.12	0.1	0.08
ROUND DUCT SIZE	5	5	4	6	5	6	4	6	5	5	4	5	5	6	6	4	5	4	6	4	6	6	6	6
HEATING VELOCITY (ft/min)	220	169	115	143	154	122	184	194	154	220	80	308	507	224	224	367	103	138	438	218	464	464	464	464
COOLING VELOCITY (ft/min)	382	235	46	301	455	321	138	286	455	382	34	382	426	408	408	539	308	34	286	57	71	71	71	71
OUTLET GRILL SIZE	3X10	3X10	3X10	4X10	3X10	4X10	3X10	4X10	3X10	3X10	3X10	3X10	3X10	4X10	4X10	3X10	3X10	3X10	4X10	3X10	4X10	4X10	4X10	4X10
TRUNK	C	C	D	D	B	B	B	A	B	C	D	B	D	C	C	C	B	B	A	B	D	D	D	A

RUN #	25	26	27	28
ROOM NAME	FLEX	ENS	FAM	S-BATH
RM LOSS MBH.	1.90	1.15	1.57	0.82
CFM PER RUN HEAT	38	23	32	16
RM GAIN MBH.	1.87	1.06	1.55	0.41
CFM PER RUN COOLING	56	32	47	12
ADJUSTED PRESSURE	0.15	0.15	0.15	0.15
ACTUAL DUCT LGH.	54	39	40	35
EQUIVALENT LENGTH	200	170	140	160
TOTAL EFFECTIVE LENGTH	254	209	180	195
ADJUSTED PRESSURE	0.06	0.07	0.08	0.07
ROUND DUCT SIZE	6	4	5	4
HEATING VELOCITY (ft/min)	194	264	235	184
COOLING VELOCITY (ft/min)	286	367	345	138
OUTLET GRILL SIZE	4X10	3X10	3X10	3X10
TRUNK	A	C	C	B



SUPPLY AIR TRUNK SIZE

	TRUNK CFM	STATIC PRESS.	ROUND DUCT	RECT DUCT	VELOCITY (ft/min)		TRUNK CFM	STATIC PRESS.	ROUND DUCT	RECT DUCT	VELOCITY (ft/min)
TRUNK A	253	0.06	9	10	x 8	455	TRUNK G	0	0.00	0	0 x 8 0
TRUNK B	438	0.06	11.1	16	x 8	493	TRUNK H	0	0.00	0	0 x 8 0
TRUNK C	258	0.06	9.1	14	x 8	332	TRUNK I	0	0.00	0	0 x 8 0
TRUNK D	645	0.06	12.8	20	x 8	581	TRUNK J	0	0.00	0	0 x 8 0
TRUNK E	0	0.00	0	0	x 8	0	TRUNK K	0	0.00	0	0 x 8 0
TRUNK F	0	0.00	0	0	x 8	0	TRUNK L	0	0.00	0	0 x 8 0

RETURN AIR TRUNK SIZE

	TRUNK CFM	STATIC PRESS.	ROUND DUCT	RECT DUCT	VELOCITY (ft/min)
TRUNK O	0	0.05	0	0	x 8 0
TRUNK P	0	0.05	0	0	x 8 0
TRUNK Q	0	0.05	0	0	x 8 0
TRUNK R	0	0.05	0	0	x 8 0
TRUNK S	0	0.05	0	0	x 8 0
TRUNK T	0	0.05	0	0	x 8 0
TRUNK U	0	0.05	0	0	x 8 0
TRUNK V	0	0.05	0	0	x 8 0
TRUNK W	0	0.05	0	0	x 8 0
TRUNK X	1083	0.05	16.3	32	x 8 609
TRUNK Y	265	0.05	9.6	10	x 8 477
TRUNK Z	267	0.05	9.6	10	x 8 481
DROP	1083	0.05	16.3	32	x 8 650

RETURN AIR #	1	2	3	4	5	6	7																		BR
AIR VOLUME	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	182
PLENUM PRESSURE	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12	0.12
ACTUAL DUCT LGH.	56	48	49	47	46	18	17	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	141
EQUIVALENT LENGTH	150	185	190	145	145	135	175	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	150
TOTAL EFFECTIVE LH	206	233	239	192	191	153	192	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	164
ADJUSTED PRESSURE	0.06	0.05	0.05	0.06	0.06	0.08	0.06	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	12.40	0.08
ROUND DUCT SIZE	6.7	6	6.5	6	6	6	9.8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	7.4
INLET GRILL SIZE	8	8	8	8	8	8	8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	8
	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
INLET GRILL SIZE	14	14	14	14	14	14	30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	14

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

TYPE: ROSE 3
SITE NAME: TRINIGROUP

LO # 102624

RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY

COMBUSTION APPLIANCES		9.32.3.1(1)
a)	☒ Direct vent (sealed combustion) only	
b)	☐ Positive venting induced draft (except fireplaces)	
c)	☐ Natural draft, B-vent or induced draft gas fireplace	
d)	☐ Solid Fuel (including fireplaces)	
e)	☐ No Combustion Appliances	

HEATING SYSTEM	
☒ Forced Air	☐ Non Forced Air
☐ Electric Space Heat	

HOUSE TYPE		9.32.1(2)
☒ I	Type a) or b) appliance only, no solid fuel	
☐ II	Type I except with solid fuel (including fireplaces)	
☐ III	Any Type c) appliance	
☐ IV	Type I, or II with electric space heat	
☐	Other: Type I, II or IV no forced air	

SYSTEM DESIGN OPTIONS		O.N.H.W.P.
☐ 1	Exhaust only/Forced Air System	
☐ 2	HRV with Ducting/Forced Air System	
☒ 3	HRV Simplified/connected to forced air system	
☐ 4	HRV with Ducting/non forced air system	
☐	Part 6 Design	

TOTAL VENTILATION CAPACITY		9.32.3.3(1)
Basement + Master Bedroom	<u>2</u> @ 21.2 cfm <u>42.4</u> cfm	
Other Bedrooms	<u>3</u> @ 10.6 cfm <u>31.8</u> cfm	
Kitchen & Bathrooms	<u>5</u> @ 10.6 cfm <u>53</u> cfm	
Other Rooms	<u>5</u> @ 10.6 cfm <u>53.0</u> cfm	
Table 9.32.3.A.	TOTAL <u>180.2</u> cfm	

PRINCIPAL VENTILATION CAPACITY REQUIRED		9.32.3.4.(1)
1 Bedroom	31.8 cfm	
2 Bedroom	47.7 cfm	
3 Bedroom	63.6 cfm	
4 Bedroom	79.5 cfm	
5 Bedroom	95.4 cfm	
TOTAL	79.5 cfm	

SUPPLEMENTAL VENTILATION CAPACITY		9.32.3.5.
Total Ventilation Capacity	<u>180.2</u> cfm	
Less Principal Ventil. Capacity	<u>79.5</u> cfm	
Required Supplemental Capacity	<u>100.7</u> cfm	

PRINCIPAL EXHAUST FAN CAPACITY	
Model: VANEE V150H	Location: BSMT
<u>79.5</u> cfm	☒ HVI Approved

PRINCIPAL EXHAUST HEAT LOSS CALCULATION			
CFM	ΔT °F	FACTOR	% LOSS
79.5 CFM	X 78 F	X 1.08	X 0.25

SUPPLEMENTAL FANS		BY INSTALLING CONTRACTOR		
Location	Model	cfm	HVI	Sones
ENS	BY INSTALLING CONTRACTOR	50	☒	3.5
S-BATH	BY INSTALLING CONTRACTOR	50	☒	3.5
ENS-4	BY INSTALLING CONTRACTOR	50	☒	3.5
PWD	BY INSTALLING CONTRACTOR	50	☒	3.5

HEAT RECOVERY VENTILATOR		9.32.3.11.
Model: VANEE V150H		
<u>150</u> cfm high	<u>35</u> cfm low	
<u>75</u> % Sensible Efficiency @ 32 deg F (0 deg C)	☒ HVI Approved	

LOCATION OF INSTALLATION	
Lot:	Concession
Township	Plan:
Address	
Roll #	Building Permit #

BUILDER:	
GREENPARK HOMES	
Name:	
Address:	Richmond Hill City of Richmond Hill
City:	Building Division
Telephone #:	

INSTALLING CONTRACTOR	
Initials:	PXV
Name:	
Address:	
City:	
Telephone #:	Fax #:

DESIGNER CERTIFICATION	
I hereby certify that this ventilation system has been designed in accordance with the Ontario Building Code.	
Name:	HVAC Designs Ltd.
Signature:	<i>Michael O'Rourke</i>
HRAI #	001820
Date:	September-23

I REVIEW AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED IN THE APPROPRIATE CATEGORY AS AN "OTHER DESIGNER" UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.
INDIVIDUAL BCIN: 19669 *Michael O'Rourke* MICHAEL O'ROURKE

05/01/2024

RECEIVED
Per: joshua.nabua

CSA F280-12 Residential Heat Loss and Heat Gain Calculations																																																												
Formula Sheet (For Air Leakage / Ventilation Calculation)																																																												
LO#: 102624		Model: ROSE 3		Builder: GREENPARK HOMES																																																								
				Date: 9/25/2023																																																								
Volume Calculation			Air Change & Delta T Data																																																									
House Volume <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Level</th> <th>Floor Area (ft²)</th> <th>Floor Height (ft)</th> <th>Volume (ft³)</th> </tr> </thead> <tbody> <tr><td>Bsmt</td><td>1388</td><td>9</td><td>11798</td></tr> <tr><td>First</td><td>1388</td><td>10</td><td>14018.8</td></tr> <tr><td>Second</td><td>1225</td><td>9</td><td>11147.5</td></tr> <tr><td>Third</td><td>0</td><td>9</td><td>0</td></tr> <tr><td>Fourth</td><td>0</td><td>9</td><td>0</td></tr> <tr><td colspan="3" style="text-align: right;">Total:</td><td>36,964.3 ft³</td></tr> <tr><td colspan="3" style="text-align: right;">Total:</td><td>1046.7 m³</td></tr> </tbody> </table>			Level	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)	Bsmt	1388	9	11798	First	1388	10	14018.8	Second	1225	9	11147.5	Third	0	9	0	Fourth	0	9	0	Total:			36,964.3 ft³	Total:			1046.7 m³	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width: 80%;">WINTER NATURAL AIR CHANGE RATE</td> <td style="width: 20%;">0.354</td> </tr> <tr> <td>SUMMER NATURAL AIR CHANGE RATE</td> <td>0.110</td> </tr> </table> <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th colspan="5" style="text-align: center;">Design Temperature Difference</th> </tr> <tr> <th></th> <th>Tin °C</th> <th>Tout °C</th> <th>ΔT °C</th> <th>ΔT °F</th> </tr> <tr> <td>Winter DTDh</td> <td>22</td> <td>-21</td> <td>43</td> <td>78</td> </tr> <tr> <td>Summer DTDc</td> <td>24</td> <td>31</td> <td>7</td> <td>13</td> </tr> </table>		WINTER NATURAL AIR CHANGE RATE	0.354	SUMMER NATURAL AIR CHANGE RATE	0.110	Design Temperature Difference						Tin °C	Tout °C	ΔT °C	ΔT °F	Winter DTDh	22	-21	43	78	Summer DTDc	24	31	7	13
Level	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)																																																									
Bsmt	1388	9	11798																																																									
First	1388	10	14018.8																																																									
Second	1225	9	11147.5																																																									
Third	0	9	0																																																									
Fourth	0	9	0																																																									
Total:			36,964.3 ft³																																																									
Total:			1046.7 m³																																																									
WINTER NATURAL AIR CHANGE RATE	0.354																																																											
SUMMER NATURAL AIR CHANGE RATE	0.110																																																											
Design Temperature Difference																																																												
	Tin °C	Tout °C	ΔT °C	ΔT °F																																																								
Winter DTDh	22	-21	43	78																																																								
Summer DTDc	24	31	7	13																																																								
5.2.3.1 Heat Loss due to Air Leakage			6.2.6 Sensible Gain due to Air Leakage																																																									
$HL_{airb} = LR_{airh} \times \frac{V_b}{3.6} \times DTD_h \times 1.2$ 0.354 x 290.75 x 43 °C x 1.2 = 5335 W = 18203 Btu/h			$HG_{salb} = LR_{airc} \times \frac{V_b}{3.6} \times DTD_c \times 1.2$ = 0.110 x 290.75 x 7 °C x 1.2 = 274 W = 934 Btu/h																																																									
5.2.3.2 Heat Loss due to Mechanical Ventilation			6.2.7 Sensible heat Gain due to Ventilation																																																									
$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E)$ 80 CFM x 78 °F x 1.08 x 0.25 = 1670 Btu/h			$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E)$ 80 CFM x 13 °F x 1.08 x 0.25 = 275 Btu/h																																																									
5.2.3.3 Calculation of Air Change Heat Loss for Each Room (Floor Multiplier Section)																																																												
$HL_{airr} = Level\ Factor \times HL_{airbv} \times \{(HL_{agcr} + HL_{bgcr}) \div (HL_{agclevel} + HL_{bgclevel})\}$ <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Level</th> <th>Level Factor (LF)</th> <th>HLairve Air Leakage + Ventilation Heat Loss (Btu/h)</th> <th>Level Conductive Heat Loss: (HL_{clevel})</th> <th>Air Leakage Heat Loss Multiplier (LF x HLairbv / HL_{clevel})</th> </tr> </thead> <tbody> <tr><td>1</td><td>0.5</td><td rowspan="5" style="text-align: center; vertical-align: middle;">18,203</td><td>8,948</td><td>1.017</td></tr> <tr><td>2</td><td>0.3</td><td>13,309</td><td>0.410</td></tr> <tr><td>3</td><td>0.2</td><td>13,245</td><td>0.275</td></tr> <tr><td>4</td><td>0</td><td>0</td><td>0.000</td></tr> <tr><td>5</td><td>0</td><td>0</td><td>0.000</td></tr> </tbody> </table>					Level	Level Factor (LF)	HLairve Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{clevel})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HL _{clevel})	1	0.5	18,203	8,948	1.017	2	0.3	13,309	0.410	3	0.2	13,245	0.275	4	0	0	0.000	5	0	0	0.000																														
Level	Level Factor (LF)	HLairve Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{clevel})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HL _{clevel})																																																								
1	0.5	18,203	8,948	1.017																																																								
2	0.3		13,309	0.410																																																								
3	0.2		13,245	0.275																																																								
4	0		0	0.000																																																								
5	0		0	0.000																																																								
*HLairbv = Air leakage heat loss + ventilation heat loss *For a balanced or supply only ventilation system HLairve = 0																																																												

Michael O'Rourke
BCIN# 19669

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

HEAT LOSS AND GAIN SUMMARY SHEET

MODEL: ROSE 3	BUILDER: GREENPARK HOMES
SFQT: 2596	LO# 102624 SITE: TRINIGROUP

DESIGN ASSUMPTIONS

HEATING	°F	COOLING	°F
OUTDOOR DESIGN TEMP.	-6	OUTDOOR DESIGN TEMP.	88
INDOOR DESIGN TEMP.	72	INDOOR DESIGN TEMP. (MAX 75°F)	75
		WINDOW SHGC	0.50

BUILDING DATA

ATTACHMENT:	DETACHED	# OF STORIES (+BASEMENT):	3
FRONT FACES:	EAST	ASSUMED (Y/N):	Y
AIR CHANGES PER HOUR:	3.57	ASSUMED (Y/N):	Y
AIR TIGHTNESS CATEGORY:	AVERAGE	ASSUMED (Y/N):	Y
WIND EXPOSURE:	SHELTERED	ASSUMED (Y/N):	Y
HOUSE VOLUME (ft³):	36964.3	ASSUMED (Y/N):	Y
INTERNAL SHADING:	BLINDS/CURTAINS	ASSUMED OCCUPANTS:	5
INTERIOR LIGHTING LOAD (Btu/h/ft²):	1.95	DC BRUSHLESS MOTOR (Y/N):	Y
FOUNDATION CONFIGURATION	BCIN_1	DEPTH BELOW GRADE:	5.5 ft
LENGTH: 56.0 ft	WIDTH: 31.0 ft	EXPOSED PERIMETER:	174.0 ft

2012 OBC - COMPLIANCE PACKAGE

Component

Compliance Package A1

Nominal	Min. Eff.
---------	-----------

Ceiling with Attic Space Minimum RSI (R)-Value	60	59.22
Ceiling Without Attic Space Minimum RSI (R)-Value	31	27.65
Exposed Floor Minimum RSI (R)-Value	31	29.80
Walls Above Grade Minimum RSI (R)-Value	22	17.03
Basement Walls Minimum RSI (R)-Value	20 ci	21.12
Below Grade Slab Entire surface > 600 mm below grade Minimum RSI (R)-Value	-	-
Edge of Below Grade Slab ≤ 600 mm Below Grade Minimum RSI (R)-Value	10	10
Heated Slab or Slab ≤ 600 mm below grade Minimum RSI (R)-Value	10	11.13
Windows and Sliding Glass Doors Maximum U-Value	0.28	-
Skylights Maximum U-Value	0.49	-
Space Heating Equipment Minimum AFUE	96%	-
HRV/ERV Minimum Efficiency	75%	-
Domestic Hot Water Heater Minimum EF	0.8	-

INDIVIDUAL BCIN: 19669
MICHAEL O'ROURKE




CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024

RECEIVED
Per: joshua.nabua

Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description		
Province:	Ontario	
Region:	Richmond Hill	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Floor Length (m):	17.1	 Insulation Configuration
Floor Width (m):	9.4	
Exposed Perimeter (m):	0.0	
Wall Height (m):	2.6	
Depth Below Grade (m):	1.68	
Window Area (m ²):	0.8	
Door Area (m ²):	2.0	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Foundation Loads		
Heating Load (Watts):		1742

TYPE: ROSE 3
LO# 102624

Michael O'Rourke BCIN #19669

CITY OF RICHMOND HILL
BUILDING DIVISION

05/01/2024


RECEIVED
Per: joshua.nabua

Air Infiltration Residential Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description				
Province:	Ontario			
Region:	Richmond Hill			
Weather Station Location:	Open flat terrain, grass			
Anemometer height (m):	10			
Local Shielding				
Building Site:	Suburban, forest			
Walls:	Heavy			
Flue:	Heavy			
Highest Ceiling Height (m):	7.68			
Building Configuration				
Type:	Detached			
Number of Stories:	Two			
Foundation:	Full			
House Volume (m ³):	1046.7			
Air Leakage/Ventilation				
Air Tightness Type:	Present (1961-) (3.57 ACH)			
Custom BDT Data:	ELA @ 10 Pa.	1395.3 cm ²		
	3.57	ACH @ 50 Pa		
Mechanical Ventilation (L/s):	Total Supply	Total Exhaust		
	37.5	37.5		
Flue Size				
Flue #:	#1	#2	#3	#4
Diameter (mm):	0	0	0	0
Natural Infiltration Rates				
Heating Air Leakage Rate (ACH/H):	0.354			
Cooling Air Leakage Rate (ACH/H):	0.110			

TYPE: ROSE 3
LO# 102624


Michael O'Rourke BCIN# 19669

CITY OF RICHMOND HILL
BUILDING DIVISION


05/01/2024

RECEIVED
Per: joshua.nabua


SUPPLEMENTAL EXHAUST FAN (MINIMUM 100 CFM) DISCHARGING DIRECTLY TO THE EXTERIOR WILL BE PROVIDED IN THE KITCHEN. EXHAUST DUCTS SERVING THE KITCHEN SHALL NOT BE SMALLER THAN RECOMMENDED BY THE MANUFACTURER OF THE FANS AND MUST AT LEAST MEET O.B.C. STATED MINIMUMS.




Partial Basement Plan For Deck Condition
Elevation '1', '2' and '3'



Basement Plan '1'




Basement Plan '3




Basement Plan '2'




Ensure that R-Values and U-Values used for heat loss and heat gain calculations are consistent with the values specified by SB-12 Prescriptive Package: A1 and the values used for architectural design.



Ground Floor Plan '1'



Ground Floor Plan '3'



Ground Floor Plan '2

13. Exterior insulation effective R-Value for wall, roof or exposed floor shall be maintained at the respective location where duct or sanitary pipes are routed inside exterior envelope.

14. Return air intake shall be provided as recommended in HRAI Digest 2005 Section 4.7. Return air inlet should be positioned so that short circuiting of supply air is avoided. A high and low wall return air combination shall be provided when a combined cooling & heating system is installed.


15. For simplified HRV/ERV installation, with stale air and fresh air connected to return air plenum, stale air intake and fresh air supply shall be separated minimum 3' or as recommended by HRV/ERV Manufacturer.

7. Combustion air supply shall be provided to the furnace and hot water tank.


8.HRV installation, testing, startup and commissioning shall be in compliance with OBC 2012, Div.B 9.32.3.11, 9.32.3.11(7)&(10)

9. HRV duct connection shall be in compliance with OBC 2012 Div.B 9.32.3.6(3) & 9.32.3.4(7).


10. Supply air grill at finished basement shall be at low level. Return air grill for finished or unfinished basement shall be at low level. HRAI digest 2005, clause 7.7(3).



Second Floor Plan '1'



Second Floor Plan '2'



Second Floor Plan '3'

HEAT LOSS 55374 BTU/H UNIT DATA		# OF RUNS	S/A	R/A	FANS
MAKE	GOODMAN	3RD FLOOR			
MODEL	GMCE960603BNA	2ND FLOOR	15	5	4
INPUT	60.0 MBTU/H	1ST FLOOR	9	2	2
OUTPUT	57.6 MBTU/H	BASEMENT	4	1	0
COOLING	3.0 TONS	ALL S/A DIFFUSERS 4 "x10" UNLESS NOTED OTHERWISE ON LAYOUT. ALL R/A UNLESS NOTED OTHERWISE			
FAN SPEED	1083 cfm @ 0.8" w.c.	ON LAYOUT. UNDERCUT DOORS 1" min. FOR R/A			

HVAC LEGEND	
	SUPPLY AIR GRILLE
	SUPPLY AIR GRILLE 6' BOOT
	LINEAR BAR or LINEAR SLOT GRILLE
	SUPPLY AIR BOOT ABOVE
	6" SUPPLY AIR BOOT ABOVE
	SUPPLY AIR STACK
	6" SUPPLY AIR STACK
	143R RETURN AIR GRILLE
	304R RETURN AIR GRILLE
	603R RETURN AIR GRILLE
	RETURN AIR STACK ABOVE
	RETURN AIR STACK
	PVX
	R
	SUPPLY DUCTWORK
	RETURN DUCTWORK
	FLEX DUCT
	EXHAUST FAN
	LINT TRAP by REVERSOMATIC
	DIRECT VENT
	LOW WALL
	HIGH WALL
	CEILING
	MOTORIZED ZONE DAMPER
	MOTORIZED DAMPER
	EXHAUST PIPE
	CONCENTRIC VENT KIT
	CONCENTRIC HRV or ERV VENT KIT
	SINGLE WALL BOX by REVERSOMATIC
	DOUBLE WALL BOX by REVERSOMATIC
	TRIPLE WALL BOX by REVERSOMATIC
	DRYER BOOSTER FAN

2			
1	ISSUED FOR PERMIT	SEPT/23	YV
No.	Revision	Date	By

SB-12 PACKAGE

Michael O'Rourke has reviewed and taken responsibility for the design work and am qualified under division C.3.2.5 of the building code.

Michael O'Rourke
Michael O'Rourke BCIN # 19669
HMC Designs Ltd.

HVA DESIGNS LTD.

375 Finley Ave - Unit 202 - Ajax, Ontario L1S 2E2
Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375
Email: info@hvacdesigns.ca
Web: www.hvacdesigns.ca

Specializing in Residential Mechanical Design Services

Client GREENPARK HOMES

Project TRINIGROUP

RICHMOND HILL, ONTARIO
B2B5 2

ROSE 3
2596 SQFT

Copyright © 2023 HVAC Desk

Sheet Title	HVAC	CITY
Drawn by		BL

Scale $3/16"=1'-0"$

Date SEPTEMBER 2023 05

102624

[illegible]

100