

CONSTRUCTION SUMMARY

The Enclave at Castlemore Village - Baltro Construction Inc.

PURCHASERS: JOHN PERMAUL and DIANA DEVI PERMAUL

TEL:

LOT / PHASE	REG. PLAN #	HOUSE TYPE	
28 / 1	43M-2013	York 3 Elev B	

CABINETRY

1 - KITCHEN- ISLAND DIFFERENT COLOUR FEE 07Mar18 Note:	
---	--

CABINETRY ACCESSORIES

1 - CABINETRY FEE FOR FLUSH CUTOUT ON WALL OVEN/MICROWAVE COMBO CABINET ONLY 07Mar18 Note:	
1 - KITCHEN CABINETS - DECOR WOOD HOOD (DHB) 800-1000 WIDE - PRICE IS EACH - STANDARD 07Mar18 Note: GREY COLOUR	
1 - KITCHEN CABINETRY BASE - BANK OF DRAWERS - UPGRADE 3 07Mar18 Note: ADD BANK OF DRAWERS IN SERVERY -	
1 - KITCHEN- CROWN MOULDING CM3 07Mar18 Note: IN LIEU OF STANDARD CROWN MOULDING	
1 - KITCHEN CABINETRY UPPER - FULL DEPTH ABOVE FRIDGE - WITH GABLES - 600MM - PRICE IS EACH - UPGRADE 3 07Mar18 Note:	
1 - KITCHEN CABINETRY BASE - POT/PAN DRAWERS (CABINET) - UPGRADE 3 07Mar18 Note: UNDER COOKTOP	
1 - OVEN CABINET - BUILT-IN - MICROWAVE COMBO - PRICE IS EACH - UPGRADE 3 07Mar18 Note:	
1 - KITCHEN CABINETRY BASE - COOKTOP CABINET FULL HEIGHT DOORS - UPGRADE 3 07Mar18 Note: GREY COLOUR SAME AS ISLAND wood hood and cooktop	

CERAMIC TILE

1 - MASTER ENSUITE SHOWER- INSTALL TILES STAGGERED- 08Mar18 Note: NEW	RECEIVED MAR 13 2018
1 - MASTER ENSUITE UPGRADED 5 TILES 24X24 OF FLOOR AND 12X24 IN SHOWER 07Mar18 Note:	
1 - UPGRADED 5 TILES IN FOYER, KITCHEN, POWDER, SERVERY AND WALKIN PANTRY 07Mar18 Note:	

CONSTRUCTION

1 - FAMILY ROOM- WAFFLE CEILING 07Mar18 Note:	
--	--

COUNTER TOP

1 - POWDER ROOM- UPGRADED COUNTERTOP 07Mar18 Note:	
1 - MASTER ENSUITE - UPGRADE COUNTERTOP TO QUARTZ IN LIEU OF VENDOR STANDARD GRANITE 07Mar18 Note: CAESARSTONE NOT INCLUDED	
1 - KITCHEN INCLUDING SERVERY - UPGRADE COUNTERTOP TO QUARTZ IN LIEU OF VENDOR STANDARD GRANITE 07Mar18 Note:	

DOORS AND TRIM


1 - UPGRADED TRIM PACKAGE-3"BB WITH 7 1/4 BASEBOARDS 07Mar18 Note:	
---	--

ELECTRICAL

CONSTRUCTION SUMMARY**The Enclave at Castlemore Village - Baltrio Construction Inc.****PURCHASERS:** JOHN PERMAUL and DIANA DEVI PERMAUL**TEL:**

LOT / PHASE	REG. PLAN #	HOUSE TYPE	
28 / 1	43M-2013	York 3 Elev B	

1 - KITCHEN - FAN INSERT FOR UPGRADE 36" HOOD - CYCLONE BX21534*07Mar18* Note:**1 - BUILT IN OVEN AND COOKTOP PROVISION - PROVISION ONLY - ELECTRICAL ONLY***07Mar18* Note:**FIREPLACE AND ACCESSORIES****1 - GAS LINE ROUGH-IN FOR STOVE (INCLUDES ELECTRICAL OUTLET) - FIRST FLOOR***07Mar18* Note:**HARDWOOD FLOORING****1 - FIRST FLOOR & UPPER HALL - 5" GROUP B MIRAGE HOPSCOTCH HARDWOOD FLOORING IN LIEU OF VENDOR STANDARD HARDWOOD***07Mar18* Note:**PLUMBING****1 - SINK - UNDERMOUNT SINK - CONTRAC EMERY #4220CGY***07Mar18* Note: undermount sink of other bath vanities**PROMOTIONAL****1 - LESS CREDIT FROM PURCHASER EXTRA SHEET IN OFFER***07Mar18* Note:**EXTRAS AS PER OFFER****RELOCATE POWDER ROOM AND INCREASE BY 1 FOOT IN SIZE. REMOVE FRONT HALL CLOSET (PER ENGINEERING SKETCH DATED FEBRUARY 22, 2018).***Upgrade* Note:**SHIFT DOWN DINING ROOM AND INCREASE BY 10 INCHES. CENTER WINDOW IN DINING ROOM (PER ENGINEERING SKETCH DATED FEBRUARY 22, 2018).***Upgrade* Note:**INCREASE SERVERY BY 3 FEET 10 INCHES AND INCREASE WALK-IN PANTRY BY 1 FOOT 8 INCHES (PER ENGINEERING SKETCH DATED FEBRUARY 22, 2018).***Upgrade* Note:**REMOVE FRENCH DOORS AND ADD ARCHWAYS TO OFFICE (PER ENGINEERING SKETCH DATED FEBRUARY 22, 2018).***Upgrade* Note:**The Vendor agrees that notwithstanding any other term or provision in this Agreement included in the Purchase Price and in addition to those items detailed in Schedule GP to the Agreement of Purchase and Sale, the Purchaser is entitled to a credit of This***Worksheet* Note:**THE PURCHASERS ACKNOWLEDGE AND ACCEPT THAT THE PURCHASE PRICE IS INCLUSIVE OF ALL CREDITS AND PROMOTIONS AVAILABLE AT THE TIME OF SALE.***Worksheet* Note:**THE PURCHASERS ACKNOWLEDGE AND ACCEPT EXTERIOR COLOUR SELECTIONS AS CHOSEN BY THE VENDOR.***Worksheet* Note:**This Document is Extremely Time Sensitive - Printed 8 Mar 18 at 12:54**



INTERIOR COLOUR SCHEME

Purchasers: JOHN PERMAUL & DIANA DEVI PERMAUL Property: 28
Telephone Res. / Bus: / Project: Baltro Construction Inc.
Decor Advisor: Natalie Mancuso Model and Elevation: York 3 Elev B
Lock Date: 7-Mar-18 Plan #: 43M-2013

Layout Changes: ☐ Yes ☐ No Sketch Attached: ☐ Yes ☐ No Exterior Colour Scheme:

1. Cabinetry

	Style and Colour	Hardware
Kitchen / Breakfast	LEGACY 614XZ4 - ISLAND/ COOKTOP AND WOOD HOOD- 701XZ4	1001
Laundry Room	ELISSE	
Powder Room	AMALFI WHITE	2004
Master Ensuite Bathroom	HAMPTON W823XZ4	2004
Ensuite Bath - Bedroom 2/3	HAMPTON W350XZ4	2004
Ensuite Bath - Bedroom 4/5	HAMPTON W350XZ4	2004

Appliances:

Built In Appliances ☒ Yes ☐ No Slide In Stove ☐ Yes ☒ No
Dishwasher Cabinet ☐ Closed ☒ Open 41" Upper Cabinets ☒ Yes ☐ No Please NOTE: Standard Cabinet Height is 30"

NOTE: If not specified, opening will be set to builder's standard opening of approximately 30" width

Stove Opening 36"

NOTE: If not specified, opening will be set to builder's standard opening of approximately 37" width x 74" height

Fridge Opening

** Refer to Construction Summary

2. Counters

	Counter	Edge
Kitchen / Breakfast	QUARTZ - ISTRIA	320
Laundry Room		
Powder Room	QUARTZ-BIANCO STARDUST	320
Master Ensuite Bathroom	QUARTZ-BIANCO STARDUST	320
Ensuite Bath - Bedroom 2/3	LAMINATE-WHITE CARRARA 4924-38	320
Ensuite Bath - Bedroom 4/5	LAMINATE-WHITE CARRARA 4924-38	320

** Refer to Construction Summary



INTERIOR COLOUR SCHEME

Purchasers:

JOHN PERMAUL & DIANA DEVI PERMAUL

Property: 28

Telephone Res. / Bus:

/

Project: Baltrio Construction Inc.

Decor Advisor:

Natalie Mancuso

Model and Elevation: York 3 Elev B

Lock Date:

7-Mar-18

Plan #: 43M-2013

3. Ceramic Flooring

		At a 45 Threshold-If App.
Entrance Vestibule	TILE-GOTHA DIAMOND LUX 24X24	☐
Main Hall	→	389
Kitchen / Breakfast	TILE-GOTHA DIAMOND LUX 24X24	☐
Laundry Room	TILE- ESSENZE BIANCO 13X13	☐
Powder Room	TILE-GOTHA DIAMOND LUX 24X24	☐
Master Ensuite Bathroom	TILE-GOTHA DIAMOND LUX 24X24	389
Ensuite Bath - Bedroom 2/3	TILE-ESSENZE BIANCO 13X13	☐
Ensuite Bath - Bedroom 4/5	TILE-ESSENZE BIANCO 13X13	☐
		☐
		☐
		☐

** Refer to Construction Summary

4. Ceramic Wall Tile

	Selection	Describe
Master Ensuite Bathroom		
Tub Deck Wall		
Tub Deck		
Tub Deck Skirt		
Shower Stall	TILE-GOTHA DIAMOND LUX12X24	389 Staggered
Bathtub Enclosure Walls		
Ensuite Bath - Bedroom 2/3	TILE-BIANCO LUCIDO 8X16	
Ensuite Bath - Bedroom 4/5	TILE- BIANCO LUCIDO 8X16	
Kitchen Backsplash		

** Refer to Construction Summary - STANDARD GROUT THROUGHOUT UNLESS SPECIFIED

5. Plumbing Fixtures

All Bathrooms	White		Whirlpool	☐	☐ Yes ☒ No

Dishwasher Rough-In

☒ Yes ☐ No

Waterline for Fridge

☐ Yes ☒ No

** Refer to Construction Summary

6. Trim Carpentry

Interior Doors	CARRARA SMOOTH
Interior Trim	3" BB CASING WITH 7 1/4" BASEBOARD - COLONIAL
Door Handles	As Per Construction Specifications
Exterior Front Door Handle	As Per Construction Specifications

** Refer to Construction Summary



INTERIOR COLOUR SCHEME

Purchasers: JOHN PERMAUL & DIANA DEVI PERMAUL Property: 28
Telephone Res. / Bus: / Project: Baltro Construction Inc.
Decor Advisor: Natalie Mancuso Model and Elevation: York 3 Elev B
Lock Date: 7-Mar-18 7-Mar-18 Plan #: 43M-2013

7. Outer Flooring

Main Hall	VINTAGE NSS RED OAK 5" TITAN WIRE BRUSHED CHARACTER UV OIL
Living Room	
Dining Room	VINTAGE NSS RED OAK 5" TITAN WIRE BRUSHED CHARACTER UV OIL
Family Room	VINTAGE NSS RED OAK 5" TITAN WIRE BRUSHED CHARACTER UV OIL
Den / Library / Study	VINTAGE NSS RED OAK 5" TITAN WIRE BRUSHED CHARACTER UV OIL
Basement Landing(If Applies)	LAMINATE-LEXINGTON - HAZELWOOD OAK TL21016 - M
Lower Landing (If Applies)	VINTAGE NSS RED OAK 5" TITAN WIRE BRUSHED CHARACTER UV OIL
Upper Landing	VINTAGE NSS RED OAK 5" TITAN WIRE BRUSHED CHARACTER UV OIL
Upper Hall	VINTAGE NSS RED OAK 5" TITAN WIRE BRUSHED CHARACTER UV OIL
Master Bedroom	CARPET-SHAW - E0949 NEWBERN CLASSIC - FOSSIL 00761
Bedroom #2	CARPET-SHAW - E0949 NEWBERN CLASSIC - FOSSIL 00761
Bedroom #3	CARPET-SHAW - E0949 NEWBERN CLASSIC - FOSSIL 00761
Bedroom #4	CARPET-SHAW - E0949 NEWBERN CLASSIC - FOSSIL 00761
Bedroom #5	CARPET-SHAW - E0949 NEWBERN CLASSIC - FOSSIL 00761

Underpad	Type	Area

** Refer to Construction Summary

8. Railings and Pickets

Railing Type	V-GROOVE	Colour	V INTAGE-TITAN
Picket Type	EUROLINE 1	Colour	BLACK
Stringer / Riser	As Per Construction Specifications	Colour	V INTAGE-TITAN
Treads	Standard	Colour	V INTAGE-TITAN

Red Oak Stairs with Semi Gloss Finish

☒ Yes ☐ No

** Refer to Construction Summary

9. Wall Paint Flat Finish

Main & Upper Hall	22 WARM GREY	Master Bedroom	22 WARM GREY
Living Room	22 WARM GREY	Bedroom #2	22 WARM GREY
Dining Room	22 WARM GREY	Bedroom #3	22 WARM GREY
Kitchen / Breakfast	22 WARM GREY	Bedroom #4	22 WARM GREY
Family Room	22 WARM GREY	Bedroom #5	22 WARM GREY
Powder Room	22 WARM GREY	Master Ensuite	22 WARM GREY
Laundry Room	22 WARM GREY	Ensuite Bath - Bedroom 2/3	22 WARM GREY
Den/Library	22 WARM GREY	Ensuite Bath - Bedroom 4/5	22 WARM GREY
Trim Paint-Semi Gloss	BIRCH WHITE		

Smooth Ceilings First Floor ☒ Yes ☐ No

** Refer to Construction Summary



INTERIOR COLOUR SCHEME

Purchasers: JOHN PERMAUL & DIANA DEVI PERMAUL Property: 28
Telephone Res. / Bus: / Project: Baltro Construction Inc.
Decor Advisor: Natalie Mancuso Model and Elevation: York 3 Elev B
Lock Date: 7-Mar-18 Plan #: 43M-2013

10. Plaster Mouldings and Medallions

Entrance Vestibule		Kitchen/Breakfast	
Main Hall		Den/Library	
Living Room		Lower Landing	
Dining Room			
Family Room			

** Refer to Construction Summary

11. Fireplace

Living Room		Family Room		Other Room - Specify	
Purchased	As Per Plan	Purchased	As Per Plan	Purchased	As Per Plan
☐	☐	☐	☒	☐	☐
Fireplace Type		STANDARD			
Mantle Type		MANTLE M2-STANDARD			
Colour / Stain		AS PER CONSTRUCTION SPECIFICATIONS			
Surround		BIANCO			
Hearth					

** Refer to Construction Summary

12. Heating and Air Conditioning

Air Conditioning	NO	Gas Provisions Stove	YES
Gas Provisions Dryer	NO	Gas Provisions Barbecue	NO

Comment

** Refer to Construction Summary

13. Electrical

Plugs and Switches	☒ White	DECOR	Above Kitchen Cabinet Light	☐ Yes	☒ No
Hood Fan	Cyclone Insert # BX21534		Below Kitchen Cabinet Light	☐ Yes	☒ No
Appliances	Built in Cooktop	Built in Oven	Gas Stove	Microwave	
	☒ Yes ☐ No	☒ Yes ☐ No		☒ Yes ☐ No	☐ Yes ☒ No

Dishwasher Rough-in

Yes


** Refer to Construction Summary

14. General Comments

** Refer to Construction Summary




Disclaimers and Notes

- Colours of all materials are as close as possible to builder's selection, but not necessarily identical due to variances in manufacturing.
- Any extras listed above are null and void unless accompanied by a separate invoice/amendment. Said invoice must be paid in full.
- The Purchaser agrees that this colour selection is final and that no changes will be permitted, unless required by the Vendor.
- The Purchaser acknowledges reading and accepting document which contains other miscellaneous disclaimers.

Signature:  Date: 07-03-18 Signature: Date:

BALTRIO 28

X-TEND
POWDER
BR 1' \$
HOD
BANK
CF DRAWS
\$



THIS LAYOUT CONTAINS EXTRAS
THAT ARE NOT PART OF CONTRACT
PROVIDE GABLE
WITH CUT-OUT
FOR ELECT. PLUG

WINDOW SEAT
BUILD TOE KICK UNDER
UPPER CABINETS
SUPPLY 19MM THICK PANEL AS TOP

CUSTOM-H-CUSTOM-H
W310CG B800 W310CG B800

ASK FRIDA FOR DETAILS

3534 4293 5334


X-TEND
SEAT
HOD APPROX 4' BASE \$
" 4' UPPER \$

HOD 4' CLEAN
HOD 4' L.V.H

(IF AVAILABLE)

Selba Industries

W DTH	W HGT	W CNT	FL HGT	DWY H	ST CENT	2X4	VENT BOX COVER
1040MM HIGH UPERS LIGHT VAANCE DISHWASHER SPACE GRANITE KITCHEN & ENSUITE COUNTERTOPS BY OTHERS CLEAN CUT LAMINATE VANITY COUNTERTOPS							
SELBA INDUSTRIES INC. and is an original design while it has been paid or job order placed.							
JOB NUMBER: BUILDER: GREENWORK SITE NAME: BALTRIO CONST. MODEL: YORK 3X ELEV B LOT #: 28 DESIGNER: KS DATE: APR 26 17/REV D NOV 15 17							



VALANCE INCLUDED
CROWN MLD EXTRA

All dimensions size designations given are
subject to verification on job site and
adjustment to fit job conditions.



Kitchen + Bath Design

FLAT FRONT WOOD HOOD

CLASS
RICHM
NOTT
BANC
LEGA
LEXI
TRAF
BRAD
ST M

LOT 28


BALTRO

YORK 3

ELEV. B


REVISION:

1. RELOCATE POWDER ROOM AND INCREASED BY 1'-0" IN SIZE. REMOVE FRONT HALL CLOSET.
2. SHIFT DOWN DINING ROOM AND INCREASED BY 10". CENTER WINDOW IN DINING ROOM.
3. INCREASE SERVERY BY 3'-10" AND INCREASE WALK-IN PANTRY BY 1'-8". REMOVE FRENCH DOORS AND ADD ARCHWAYS TO OFFICE.
- 4.




York 3


4024 sq. ft. Elev. A
 With 95 sq. ft. of basement area
 4010 sq. ft. Elev. B
 With 95 sq. ft. of basement area



York 3 Elev. A



York 3 Elev. B





72" COUNTER-DEPTH FREESTANDING REFRIGERATOR

Signature Features

OBSIDIAN INTERIOR

Showcases food items throughout the refrigerator, and provides a sharper contrast than white interiors. Includes coordinating crisper drawers and freezer.

WIFI CONNECTIVITY

Allows monitoring and adjustment of basic refrigerator functions such as refrigerator and freezer temperatures through an app for iOS or Android devices. Requires WiFi and account creation. Subject to terms of service available at: jennair.com/connect. Data rates may apply.

TWIN FRESH™ CLIMATE CONTROL SYSTEM

Features separate evaporators in the refrigerator and freezer compartments that maintain independent temperature control, and maintain humidity two times that of our refrigerators with shared cooling.

Feature Listing

PERFORMANCE FEATURES

Twin Fresh™ Climate Control System

Integrated Electronic Controls with LED Display

Measured Fill

Max Cool Option

Max Ice Option

Removable EveryDrop™ Filter by Whirlpool Water

Favorite Fill

WiFi Connectivity

REFRIGERATOR FEATURES

Electronic Temperature-Controlled Pantry Drawer

Humidiseal™ Crisper Drawers

Herb Tender™ Container

Fold-Away Glass Shelf

Adjustable, Clear Glass Shelves

Adjustable Door Bins with Metal Accents

Gallon Door Storage Bins

Pull-Out Platter

Undershelf Wine Bottle Rack

In-Door-Ice Storage Bin

Interior LED Theater Lighting

FREEZER FEATURES

Slide-Out Freezer Drawer with Premium Glide System

Pure Freeze™ Mode

Automatic Ice Maker

DESIGN FEATURES

Obsidian Interior

Counter-Depth Design

72-Inch Height

Soft, Auto-Close Technology

Integrated Cubed/Crushed Ice and Water Dispenser


OPTIONAL ACCESSORIES

EveryDrop™ Ice/Water Filter – EDR2RXD1

Herb Tender Container – W10882409

Produce Preserver Starter Kit – P1KL6S1CS

Produce Preserver Keep Fresh Packet Refill – P1KO6R1



Style Options

EURO-STYLE STAINLESS DESIGN JFFCC72EFS

A refined design that satisfies contemporary and traditional tastes and blends in with other Jenn-Air® Euro-Style Stainless appliances.

PRO-STYLE® STAINLESS DESIGN JFFCC72EFP

Express commercial styling and gourmet sensibilities with diamond-etched handles, stainless steel finish and an oversized badge, matching other Jenn-Air® Pro-Style® Stainless appliances.



LIMITED
WARRANTY

Bold = Top Features




©/™ © 2017 Jenn-Air. All rights reserved. Specifications subject to change without notice. dZw0317


72" COUNTER-DEPTH FRENCH DOOR REFRIGERATORS WITH EXTERNAL DISPENSER

JFFCC72EF – 35³/₄" x 71¹⁵/₁₆" x 31¹/₄" (with handles)

PRODUCT DIMENSIONS



FRONT VIEW



TOP VIEW


MODEL #		JFFCC72EF	
		in	cm
A	Width of each door	17 ¹¹ / ₁₆	45.0
B	Space between doors	³ / ₈	0.9
C	Overall width	35 ³ / ₄	90.5
D	Height of door handles Pro-Style [®] Stainless	33 ³ / ₁₆	84.3
	Euro-Style Stainless	37 ³ / ₄	95.6
E	Height to top of door handles Pro-Style [®] Stainless	38 ¹⁵ / ₁₆	99.0
	Euro-Style Stainless	41 ³ / ₁₆	104.6
F	Height of doors	46 ¹ / ₂	118.2
G	Space between doors and drawer	¹ / ₂	1.2
H	Height to top of drawer handle Pro-Style [®] Stainless	21 ³ / ₄	55.3
	Euro-Style Stainless	21 ⁹ / ₁₆	54.8
I	Height of drawer	23	58.4
J	Height of grille	1 ¹ / ₂	3.9
K	Width from side of refrigerator to handle – door fully open 135° Pro-Style [®] Stainless	13 ⁷ / ₈	35.2
	Euro-Style Stainless	13 ¹ / ₂	34.3
L	Width from side of refrigerator to handle – door open 90° Pro-Style [®] Stainless	3 ¹ / ₁₆	10.0
	Euro-Style Stainless	3 ⁵ / ₈	8.4
M	Depth without doors	24 ⁵ / ₈	62.6
N	Depth with doors	29 ⁵ / ₁₆	74.4
O	Depth with handles Pro-Style [®] Stainless	31 ¹⁵ / ₁₆	81.1
	Euro-Style Stainless	31 ¹ / ₄	79.4
P	Depth with doors open 90°	44	111.7

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

72" COUNTER-DEPTH FRENCH DOOR REFRIGERATORS WITH EXTERNAL DISPENSER

JFFCC72EF – 35¾" x 71¹⁵/₁₆" x 31¹/₄" (with handles)

DIMENSIONS AS INSTALLED



SIDE VIEW

MODEL #		JFFCC72EF
		in cm
A*	Height to top of drawer (min.)	24 ¹⁵ / ₁₆ 63.3
B*	Height to top of drawer handle (min.)	
	Pro-Style® Stainless	23 ¹ / ₁₆ 60.2
	Euro-Style Stainless	23 ³ / ₁₆ 59.8
C*	Height of recessed refrigerator (min.)	70 ¹⁵ / ₁₆ 180.1
D*	Height to top of hinges (min.)	71 ¹⁵ / ₁₆ 182.7
E	Depth with drawer fully open including drawer handle (min.)	
	Pro-Style® Stainless	46 ⁷ / ₁₆ 117.9
	Euro-Style Stainless	45 ¹⁵ / ₁₆ 116.7
F	Depth with handles (min.)	
	Pro-Style® Stainless	31 ¹⁵ / ₁₆ 81.1
	Euro-Style Stainless	31 ¹ / ₄ 79.4
G	Depth with doors (min.)	29 ⁵ / ₁₆ 74.4
H	Depth without doors (min.)	24 ⁵ / ₈ 62.6
I	Depth to back of hinges (min.)	16 ³ / ₄ 42.6


*Add ¾" (1.9 cm) to the height dimension when leveling legs are fully extended.

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.


72" COUNTER-DEPTH FRENCH DOOR REFRIGERATORS WITH EXTERNAL DISPENSER

JFFCC72EF – 35³/₄" x 71¹⁵/₁₆" x 31¹/₄" (with handles)

OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



BACK VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

MODEL #	JFFCC72EF
A	Width (min.) in cm 36 ³ / ₄ 93.3
B	Minimum width from side of refrigerator to fixed wall – door open 90° (full access to remove bins) 3 ³ / ₄ 9.5
C	Minimum width from side of refrigerator to fixed wall – door open approx. 135° 12 30.5
D	Width of recommended electrical/ water installation area 35 ¹ / ₂ 90.2
E	Height (min.) 72 ⁷ / ₁₆ 184.0
F	Height of recommended electrical installation area (min.-max.) 24-36 61.0-91.4
G	Height of recommended water installation area 12 30.5
H	Depth of recommended water installation area 1 2.5
I	Water line location – distance from side 2 ¹ / ₂ 6.4
J	Water line location – distance from bottom 7 17.8
K	Recommended electrical connection location
L	Recommended water connection location

ELECTRICAL REQUIREMENTS

115 volt, 60 Hz, AC only, 15- or 20-amp fused, grounded circuit is required. A dedicated circuit is recommended. Use an outlet that cannot be turned off by a switch.
Minimum length of power cord is 60" (152.0 cm). Do not use an extension cord.

WATER PRESSURE REQUIREMENTS

A cold water supply with water pressure between 30 and 120 psi (207 and 827 kPa) is required to operate the water dispenser and ice maker. Call a licensed, qualified plumber with any questions about the water pressure.
Reverse Osmosis Water Supply

IMPORTANT: The pressure of the water coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 30 and 120 psi (207 and 827 kPa).
If a reverse osmosis water filtration system is connected to the cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).



30" MICROWAVE/WALL OVEN WITH V2™ VERTICAL DUAL-FAN CONVECTION SYSTEM

Signature Features

V2™ VERTICAL DUAL-FAN CONVECTION SYSTEM

The V2™ Vertical Dual-Fan Convection System uses innovative cooking features and technology that combine to help you achieve consistently ideal results.

7-INCH FULL COLOR TOUCH-ANYWHERE LCD DISPLAY

This stylish LCD control panel features dynamic touch-screen technology, which allows you to navigate effortlessly through settings and the Jenn-Air® Culinary Center.

JENN-AIR® CULINARY CENTER

The Jenn-Air® Culinary Center customizes each cooking cycle based on a variety of your preferences to create your perfect meal. Providing full-color pictures of foods, doneness levels and pan types, the Culinary Center also offers menu-specific cooking tips for optimal results.

Feature Listing

PERFORMANCE FEATURES (UPPER OVEN)

- 1.4 Cubic Foot Capacity
- Convection & Microwave Combination Cooking
- 1,200-Watt Convection Element
- 900-Watt Microwave Element
- 1,600-Watt Grill Element
- Crisp Pan

PERFORMANCE FEATURES (LOWER OVEN)

- 5.0 Cubic Foot Oven Capacity
- V2™ Vertical Dual-Fan Convection System
- 6,800-Watt Combined Convection Capacity
- 2,800-Watt Bake Element
- 4,000-Watt Broil Element
- Hidden Bake Element
- 8-Pass Reflective Broil Element
- Closed-Door Broiling
- Temperature Probe
- Telescoping Glide Rack

Jenn-Air® Culinary Center

- Auto Convection Conversion
- Auto Convection Modes
- Manual Convection Modes
- My Creations
- No Preheat Baking
- Proofing Option
- Keep Warm™ Option
- Sabbath Mode
- Control Lock

DESIGN FEATURES

- Stainless Steel Convection Tower
- DuraFinish® Protection
- Halogen Theater Lighting
- Chef's Light
- Soft, Auto-Close Door
- Stainless Steel Microwave Interior
- Flush-to-Cabinet Design

CONTROL FEATURES

7-Inch Full Color Touch-Anywhere LCD Display

Glass-Touch Electronic Controls

WiFi Connectivity

Works With Nest

Speed-Cook

Sensor Cooking

Soften/Melt Cycle

Keep Warm™ Option

Style Options

EURO-STYLE STAINLESS DESIGN JMW3430DS

A refined design that satisfies contemporary and traditional tastes and blends in with other Jenn-Air® Euro-Style Stainless appliances.

BLACK FLOATING GLASS DESIGN JMW3430DB

Convey the elegance of classic black with a design that features a premium, contemporary look.

PRO-STYLE® STAINLESS DESIGN JMW3430DP

Express commercial styling and gourmet sensibilities with diamond-etched handles, stainless steel finish and an oversized badge, matching other Jenn-Air® Pro-Style® Stainless appliances.



LIMITED
WARRANTY



Bold = Top Features



30" COMBINATION MICROWAVE/WALL OVENS

JMW3430D, JMW2430D – 30" x 43³/₄" x 25⁵/₁₆"

PRODUCT DIMENSIONS




MODEL #	JMW3430D JMW2430D	
	in	cm
A	Overall width	
	Pro-Style® Stainless or Euro-Style Stainless	30 76.2
B	Floating Glass	29 ¹⁵ / ₁₆ 76.1
	Height of control panel	5 ¹ / ₂ 14
C	Space between control panel and door	1 ¹ / ₂ 1.2
	Height to top of microwave oven handle	
D	Pro-Style® Stainless	12 ³ / ₁₆ 31.0
	Euro-Style (color-coordinating)	12 ³ / ₁₆ 31.0
E	Height of microwave oven door	12 ¹ / ₁₆ 32.3
F	Space between doors	1 ¹ / ₈ 2.9
G	Height to top of oven handle	
	Pro-Style® Stainless	21 ⁵ / ₈ 55.0
H	Euro-Style (color-coordinating)	21 ¹ / ₁₆ 54.4
	Height of oven door	22 ¹ / ₈ 56.2
I	Height of trim	1 ¹ / ₁₆ 4.3
J	Overall height	43 ³ / ₄ 111.1
K	Width of recessed oven	28 ⁷ / ₁₆ 72.2
L	Width of conduit channel	4 ¹ / ₁₆ 12.5
M	Depth of recessed oven	23 ¹ / ₄ 59.0
N	Depth with doors	24 ³ / ₈ 61.9
O	Depth with handles	
	Pro-Style® Stainless	26 ³ / ₈ 67.0
P	Euro-Style (color-coordinating)	25 ⁵ / ₁₆ 64.3
	Depth with door fully open	45 ³ / ₈ 115.3

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

30" COMBINATION MICROWAVE/WALL OVENS

JMW3430D, JMW2430D – 30" x 43³/₄" x 25⁵/₁₆"

DIMENSIONS AS INSTALLED




MODEL #	JMW3430D JMW2430D	
	in	cm
A	Height to top of upper handle Pro-Style® Stainless	36½ 92.7
	Euro-Style (color-coordinating)	36½ 92.7
B	Height to top of lower handle Pro-Style® Stainless	23¾ 59.3
	Euro-Style (color-coordinating)	23¾ 58.7
C	Height of trim extending below cutout	1 11/16 4.3
D	Height from top of recessed oven to top of control panel JMW3430D	2½ 6.3
	JMW2430D	2 15/16 7.4
E	Height from bottom of recessed oven foot to bottom of oven vent	¾ 0.5
F	Height of recessed oven	41 104.2
G	Height to top of control panel	43¾ 111.1
H	Depth with door fully open	45¾ 115.3
I	Depth with handles Pro-Style® Stainless	26¾ 67.0
	Euro-Style (color-coordinating)	25 5/16 64.3
J	Depth with doors	24¾ 61.9
K	Depth of recessed oven	23¼ 59.0

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

30" COMBINATION MICROWAVE/WALL OVENS

JMW3430D; JMW2430D – 30" x 43^{3⁄4}" x 25^{5⁄8}"

OPENING/CLEARANCE DIMENSIONS




MODEL #		JMW3430D	JMW2430D
		in	cm
A	Width of cabinet (min.)	30	76.2
B	Width of cutout	28½	72.4
C*	Height of cutout (recommended)	41⅝	104.9
D	Top of cutout to bottom of upper cabinet door (min.)	2¼	5.7
E	Bottom of cutout to top of lower cabinet door (min.)	1½	3.8
F	Bottom of cutout to floor	4-19¼	10.2-48.9
G	Depth of cutout (min.)	24	61.0
e	Recommended junction box location		

* Will fit cutout height from 41" (104.1 cm) to 41½" (105.4 cm).

ELECTRICAL REQUIREMENTS

240 volt, 40-amp fused, grounded circuit is required. A dedicated circuit is required.

The length of conduit provided is for serviceability. Do not cut the conduit. The junction box should be located 3" (7.6 cm) maximum below the support surface. Drill a 1" (2.5 cm) minimum diameter hole in the right rear or left rear corner of the support surface for access to the junction box.



BACK VIEW


IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

JENN-AIR® DETAILED PLANNING DIMENSIONS

30" COMBINATION MICROWAVE/WALL OVENS – FLUSH INSTALLATION

JMW3430D; JMW2430D – 30" x 43³/₄" x 24³/₈" (depth without handles)

OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



SIDE VIEW

MODEL #		JMW3430D	JMW2430D
		in	cm
A	Width of flush inset cutout (min.)	30 1/4	76.8
B	Width of opening (min.)	28 7/8	73.3
C	Height of flush inset cutout (min.)	44 5/16	112.5
D	Height of opening (min.)	43 11/16	110.9
E	Bottom of cutout to floor	4 7/8-19 1/4	11.7-48.9
F	Depth of cutout (min.)	25	63.5
e	Recommended junction box location		

ELECTRICAL REQUIREMENTS

240 volt, 40-amp fused, grounded circuit is required. A dedicated circuit is required.


The length of conduit provided is for serviceability. Do not cut the conduit. The junction box should be located 3" (7.6 cm) maximum below the support surface. Drill a 1" (2.5 cm) minimum diameter hole in the right rear or left rear corner of the support surface for access to the junction box.

FLUSH INSTALLATION REQUIREMENTS *


A 25" (63.5 cm) minimum cutout depth is required.

These dimensions will result in a 1/4" (0.6 cm) reveal on the top, a 1/4" (0.6 cm) reveal on the sides and a 1/8" (0.3 cm) reveal on the bottom of the wall oven.

The front face of the cleats and spacers will be visible and should be treated as a finished surface.



TOP VIEW



BACK VIEW

* Cleats and spacers must be recessed 1 3/8" (3.5 cm) from the front of the cabinet.

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.



36" PRO-STYLE® GAS RANGETOP

Signature Features

20,000 BTU DUAL-STACKED POWERBURNER


This dual-stacked burner helps you achieve exceptional results with high-heat cooking techniques like searing or wok cooking while also giving you the control for delicate simmering.

ELECTRONIC IGNITION AND FLAME-SENSING™ RE-IGNITION

Electronic ignition and Flame-Sensing™ re-ignition ensures a continuous flame that re-ignites automatically when a burner's flame is blown out by a sudden draft. It allows meal preparation to continue uninterrupted and prevents delays in timed recipes.

5,000 BTU SIMMER BURNER

With a power output ranging from 5,000 BTUs to a gentle 700 BTUs, this simmer burner gives you maximum control while simmering sauces and melting delicate ingredients like chocolate and butter.



Feature Listing

PERFORMANCE FEATURES

20,000 BTU Dual-Stacked PowerBurner

15,000 BTU Burner

5,000 BTU Simmer Burner

Convertible to LP

CONTROL FEATURES

Infinite Burner Control Settings

Electronic Ignition and Flame-Sensing™ Re-ignition

DESIGN FEATURES

Heavy-Duty, Cast Iron Grates

Sealed Burners

OPTIONAL ACCESSORIES

Gas Connector Kit (Required) – 30-48KITRC

High Altitude Kit (Natural Gas) – W10160841

High Altitude Kit (LP Gas) – W10237848

9" Stainless Steel Backsplash – W10115776

Stainless Steel Backsplash with Two Shelves (36") – W10285448

Wok Ring – W10216179

Affresh™ Kitchen & Appliance Cleaner, 16 oz. – W10355010

Style Options

PRO-STYLE® STAINLESS DESIGN JGCP436WP

Express commercial styling and gourmet sensibilities with diamond-etched handles, stainless steel finish and an oversized badge, matching other Jenn-Air® Pro-Style® Stainless appliances.



Bold = Top Features




®/™ © 2017 Jenn-Air. All rights reserved. Specifications subject to change without notice. d2w0317


36" PRO-STYLE® RANGETOP

JGCP436WP-- 35¾" x 14⅝" x 28⅜"


PRODUCT DIMENSIONS




TOP VIEW



FRONT VIEW



BACK VIEW



SIDE VIEW

MODEL #		JGCP436WP
		in cm
A	Overall width	35¾ 90.7
B	Depth of grates	21¾ 55.2
C	Depth without control panel	23¼ 59.0
D	Depth with control panel overhang	27⅞ 68.9
E	Depth with knobs	28⅞ 72.0
F	Width of grates	33 83.8
G	Center of rangetop to center of gas inlet	14⅞ 35.9
H	Height from gas inlet to cooking surface	14⅞ 37.1
I	Width of recessed rangetop	35 89.0
J	Height including grates	8½ 21.7
K	Height of control panel	7½ 19.0
L	Height to bullnose	5⅝ 13.5
M	Height of recessed rangetop	7 17.7
N	Height to cooking surface	7⅝ 18.8
O	Height of recessed rangetop with grates	8½ 21.6
P	Depth of recessed rangetop	22⅞ 56.3
Q	Depth with control panel	26⅞ 67.3

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.




8631BdZw915


36" PRO-STYLE® RANGETOP

JGCP436WP – 35³/₄" x 14⁵/₈" x 28³/₈"


OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



SIDE VIEW



TOP VIEW – CUTOUT
(solid platform not shown)

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.



8631BdZw915

MODEL #		JGCP436WP	
		in	cm
A	Width of combustible area above cooking surface (min.)	36	91.4
B	Width from rangetop to fixed wall or other combustible material (min.)	6	15.2
C	Width to inner edge of outlet (max.)	16	40.6
D*	Height to bottom of uncovered wood or metal cabinet above cooking surface (min.)	42	106.7
E	Height to bottom of uncovered wood or metal cabinet (min.)	18	45.7
F	Height to top edge of outlet (min.)	10	25.4
G	Height to gas supply line area	14	35.6
H	Depth of upper cabinet (recommended)	13	33.0
I**	Depth from cutout to wall	1 ³ / ₄	4.4
J	Depth of cabinet	24	61.0
K	Height from cabinet to countertop	7 ¹ / ₄	18.4
L	Width of cutout (countertop and cabinet)	35 ³ / ₄	89.5
M	Width of gas opening	12 ¹ / ₂	31.7
N	Width from cutout to gas opening	2	5.1
O	Width of notch	³ / ₈	1.0
	Zero clearance	⁵ / ₁₆	0.8
P	Width of cutout (countertop only)	36	91.4
	Zero clearance	35 ³ / ₄	90.8
Q	Depth of gas opening	6 ⁷ / ₈	17.5
R	Depth from cutout to gas opening	³ / ₄	1.9
S	Depth of cutout (countertop and cabinet)	22 ¹ / ₄	56.5
e	Recommended electrical outlet location		
g	Recommended gas supply line location		

*Dimension can be reduced by 6" (15.2 cm) when bottom of wood or metal cabinet is covered by not less than 1/4" (0.6 cm) flame retardant millboard covered with not less than No. 28 MSG sheet metal, 0.015" (0.4 mm) stainless steel, 0.024" (0.6 mm) aluminum or 0.020" (0.5 mm) copper.

If installing a hood above the rangetop, follow the hood instructions for dimensional clearances above the cooking surface.

**If back wall is constructed of a combustible material and a backsplash is not installed, a 4³/₄" (12.1 cm) minimum clearance is required.

GAS REQUIREMENTS

Natural Gas

This rangetop is factory-set for use with natural gas.

LP Gas Conversion

Conversion must be done by a qualified service technician. To convert to LP gas, use the LP gas conversion kit provided with the rangetop.


ELECTRICAL REQUIREMENTS

120 volt, 60 Hz, AC only, 15-amp fused, electrical circuit is required. A time-delay fuse or dedicated circuit is recommended.


DISHWASHERS

JDTS246G, JDTS244G – 23⁷/₈" x 33¹/₂" x 28⁹/₃₂" (including handle)
JDTS245G, JDTS243G – 23⁷/₈" x 33¹/₂" x 24" (not including handle)


PRODUCT DIMENSIONS



FRONT VIEW



ADJUSTABLE TOE KICK



TOP VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.


MODEL #	JDTS246G JDTS244G		JDTS245G JDTS243G	
	in	cm	in	cm
A Width of door	23 ⁷ / ₈	60.6	23 ⁷ / ₈	60.6
B Width of toe kick	23 ¹ / ₂	59.7	23 ¹ / ₂	59.7
C Height of door				
	Pro-Style® Stainless			
	30	76.2	—	—
Euro-Style Stainless	30	76.2	—	—
	—	—	30	76.2
	Custom panel (¾"/1.9 cm)			
Height to top of handle				
	Pro-Style® Stainless			
	31 ¹⁷ / ₃₂	80.1	—	—
Euro-Style Stainless	31 ¹⁷ / ₃₂	80.1	—	—
	—	—	*	*
	Custom panel (¾"/1.9 cm)			
E Height of adjustable toe kick (min.-max.)	3 ¹ / ₂ -4 ¹ / ₄	8.8-10.6	3 ¹ / ₂ -4 ¹ / ₄	8.8-10.6
	23 ⁷ / ₈	60.6	23 ⁷ / ₈	60.6
F Width of recessed dishwasher	21	53.3	21	53.3
G Depth with tub flange	24 ¹ / ₂	62.2	—	—
Depth with door	24 ¹ / ₂	62.2	—	—
	—	—	24	60.0
Depth with handle	29 ³ / ₃₂	73.9	—	—
	28 ¹⁹ / ₃₂	72.6	—	—
Euro-Style Stainless	—	—	*	*
	49 ¹ / ₂	125.7	49 ¹ / ₂	125.7

*For custom panel models, this depends on handle chosen.

DISHWASHERS

JDTSS246G, JDTSS244G – 23⁷/₈" x 33¹/₂" x 28¹⁹/₃₂" (including handle)
JDTSS245G, JDTSS243G – 23⁷/₈" x 33¹/₂" x 24" (not including handle)

DIMENSIONS AS INSTALLED



SIDE VIEW

MODEL #		JDTSS246G	JDTSS245G	JDTSS244G	JDTSS243G
		in	cm		
A*	Height to top of tub flange (min.)	33½	85.1		
B*	Height to top of door (min.)	33¾	85.7		
C*	Height to top of handle (min.)				
	Pro-Style® Stainless	31 ¹⁷ / ₃₂	80.1		
	Euro-Style Stainless	31 ¹⁷ / ₃₂	80.1		
	Custom panel (¾"/1.9 cm)	†	†		
D*	Height to bottom of door	3 ⁵ / ₈	9.4		
E*	Height of recessed dishwasher (min.)	33¾	85.5		
F	Depth with door fully open (min.)	49½	125.7		
G	Depth with handle (min.)				
	Pro-Style® Stainless	29 ³ / ₃₂	73.9		
	Euro-Style Stainless	28 ¹⁹ / ₃₂	72.6		
	Custom panel (¾"/1.9 cm)	†	†		
H	Depth with door (min.)				
	Pro-Style® Stainless	26½	67.3		
	Euro-Style Stainless	26½	67.3		
	Custom panel (¾"/1.9 cm)	24½	62.2		
I	Depth with tub flange (min.)	22 ⁵ / ₈	57.4		
J	Depth with toe kick (min.)	20 ⁷ / ₈	52.9		

*With wheels removed. Add up to 1" (2.5 cm) to height with wheels and leg levelers fully extended.




†For custom panel models, this depends on handle chosen.

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

DISHWASHERS

JDTS246G, JDTS244G – 23⁷/₈" x 33¹/₂" x 28¹⁹/₃₂" (including handle)
JDTS245G, JDTS243G – 23⁷/₈" x 33¹/₂" x 24¹/₂" (not including handle)

OPENING/CLEARANCE DIMENSIONS



MODEL #	JDTS246G JDTS245G JDTS244G JDTS243G	
	in	cm
A	Width (min.)	24 61.0
B	Width of possible utility installation area (back wall)	6 ³ / ₄ 17.2
C	Width of clear area (back wall)	10 ¹ / ₂ 26.7
D*	Height with wheels removed (min.)	34 86.4
E	Height of possible utility installation area (back wall)	2 ¹ / ₄ 6.4
F	Height of possible utility installation area (back/side wall)	6 ¹ / ₄ 15.9
G	Height of clear area (side wall)	3 7.6
H	Depth (min.)	24 61.0
I	Depth of utility location (side wall)	4 10.2
Electrical, water and drain connections may be installed in shaded areas		
Recommended drain connection location – closest to sink		1 ¹ / ₂ dia. 3.8 dia.
Recommended electrical connection location – right-hand side or back wall		1 ¹ / ₂ dia. 3.8 dia.
Recommended water connection location – left-hand side or back wall		1/2 dia. 1.3 dia.
*Measured from the lowest point on the underside of countertop.		

ELECTRICAL REQUIREMENTS

20-volt, 60 Hz, AC-only, 15- or 20-amp. fused electrical supply. Copper wire only. A time delay fuse or circuit breaker and separate circuit is recommended.

WATER SUPPLY REQUIREMENTS

120°F (49°C) hot water supply with water pressure between 20 and 120 psi (138 and 862 kPa) is required. If you have questions about your water pressure, call a licensed, qualified plumber.

DRAIN REQUIREMENTS

Connect drain hose to waste tee or disposer inlet above drain trap. Maximum drain hose length 12' (3.7 m).

LOCATION REQUIREMENTS

Corner locations require a 2" (5.1 cm) minimum clearance between the side of the dishwasher door and the wall or cabinet.

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

Spec Sheets

Powered by SteelCod



SPECIFICATIONS INCLUDED IN THIS PACKAGE:

JFFCC72EFS.pdf JFFCC72EFS (Jenn-Air - Refrigeration)
JFFCC72EFS_Dimension_Sheet.pdf JFFCC72EFS (Jenn-Air - Refrigeration)
JMW3430DS.pdf JMW3430DS (Jenn-Air - Wall Oven)
JMW3430DS_Dimension_Sheet.pdf JMW3430DS (Jenn-Air - Wall Oven)
JGCP436WP.pdf JGCP436WP (Jenn-Air - Rangetop)
JGCP436WP_Dimension_Sheet.pdf JGCP436WP (Jenn-Air - Rangetop)
JDTSS246G_DIMENSION_SHEET.PDF JDTSS246GS (Jenn-Air - Dishwasher)
WFW90HEFC.pdf WFW90HEFC (Whirlpool - Washer)
WFW90HEFC_Dimension Guide_EN.pdf WFW90HEFC (Whirlpool - Washer)
YWED90HEFC.pdf YWED90HEFC (Whirlpool - Dryer)

YWED90HEFC_Installation Instruction_EN.pdf
YWED90HEFC (Whirlpool - Dryer)