

LOT 2-65

HOME APPLIANCES

LG COOKING

LMC2075

NeoChef Countertop Microwave Oven



2.0 cu.ft. Oven Capacity

Smart Inverter

EasyClean® Interior


SmoothTouch™ Glass Touch

Hexagonal Stable Ring

LED Interior Light

10 Year Warranty on Magnetron

Available in Black Stainless Steel, Stainless Steel,
Smooth White and Smooth Black



CAPACITY

Cavity Size 2.0 cu. ft.

FEATURES

Watts 1,200 Output / 1,350 Microwave

Turntable Diameter 16"

Display SmoothTouch™ Glass Touch

Lighting White LED

COOKING FEATURES

Power Levels 10

Sensor Cooking Options 7 (Potato, Fresh Vegetable, Frozen Vegetable, Frozen Entrée, Bacon, Rice, Soften Butter)

Sensor Reheat Options 5 (Beverage, Casserole, Pizza, Dinner Plate, Pie)

Defrost Options 4 (Meat, Poultry, Fish, Bread)

Quick Start Yes

CONVENIENCE FEATURES

EasyClean® Interior Yes

Clock Yes

Completion Beeper Yes

Energy Saving Button Yes (turns off LED display)

SAFETY FEATURES

Child Lock Yes

MATERIALS/FINISHES

Available Colors

Black Stainless Steel (BD), Stainless Steel (ST),

Smooth White (SW), Smooth Black (SB)

Metal

EasyClean® Enamel (Gray/Interior)

POWER/RATINGS

Input Volt/Hertz 120/60

Input Amps/Watts (Microwave) 14A/1600W

DIMENSIONS

Cavity (WxHxD) 16 11/16" x 11 1/4" x 18 1/16"

Exterior (WxHxD) 23 7/8" x 13 9/16" x 19 5/16"

Net Weight 36.4 lbs.

Shipping Weight 40.7 lbs.

Shipping Dimensions (WxHxD) 27 3/4" x 15 2/5" x 21 1/4"

LIMITED WARRANTY

1 Year Parts and Labor (In Home Service)

10 Years Limited on Magnetron (In Home Service)

UPC CODES

LMC2075BD (Black Stainless Steel)

LMC2075ST (Stainless Steel)

LMC2075SW (Smooth White)

LMC2075SB (Smooth Black)



LMC2075SB



LMC2075SW



LMC2075ST



LMC2075BD

LOT 2-05

HOME APPLIANCES

LG LAUNDRY

WM4100HBA

5.2 cu. ft. Capacity Front Load Washer

TurboWash™ 360 Technology

AI DD™

Steam Technology

ENERGY STAR® Qualified

SmartDiagnosis™

Touch Control Panel


ThinQ™ Technology (Wi-Fi Enabled)

SMART APPLIANCE


Enjoy new ways to control your home with LG smart appliances

LG ThinQ™

- Start the laundry while you're out shopping
- Get alerts when the cycle is finished
- Works with the LG ThinQ app



CAPACITY	5.2
APPEARANCE	Front Control
Design Look	
Intelligent Electronic Controls with LED Display	
Touch Buttons	
Dial-A-Cycle™	
ENERGY	
ENERGY STAR® Qualified	
CEE Tier	2
DRYING PROGRAMS	
No. of Programs - 14	Normal, Perm. Press, Heavy Duty, Delicates, Towels, Speed Wash, Drain-Spin, Bedding, Tub Clean, Bright, Whites™, Sanitary Allergene™, Sportswear, Downloaded
No. of Options - 14	TurboWash™, Steam, Fresh Care, Pre-wash, Remote Start, Delay Wash, Wi-Fi, Add Item, Cold Wash, Extra Rinse, Rinse-Spin, Control Lock, Spin Only, Signal
Temperature Settings	5 Extra Hot, Hot, Warm, Cold, Tap Cold
Spin Speeds	5 Extra High, High, Medium, Low, No Spin
Water Levels	Load Sensing
Soil Levels	5
FABRIC CARE FEATURES	
AI DD™	
TurboWash™ 360 Technology	
Steam Technology	
Allergiene™ Cycle	
Sanitary Cycle	
ColdWash™ Option	
CONVENIENCE FEATURES	
TrueBalance™ Anti-Vibration System	Prewash, Main Wash (with liquid detergent cup), Bleach, Fabric Softener
Load Sense	
Control Lock	
Auto Suds Removal	
Leveling Legs	4 Adjustable Legs
ThinQ™ TECHNOLOGY	
SmartDiagnosis™ (v3.0)	
Wi-Fi	
Remote Start and Cycle Monitor	
Energy Monitoring	



Tub Clean Coach	
MOTOR	
Motor Type	Inverter Direct Drive Motor
Motor Speed	Variable
Max RPM	1,300
Axis	Horizontal
MATERIALS AND FINISHES	
NeverRust™	Stainless Steel Drum
Cabinet	
Control Panel	PCM
Top Plate	Plastic
Door Cover	Painted
Door / Rim	Tempered Glass Door
All Available Colours	Glass/Chrome
POWER SOURCE	Black Steel (B)
Ratings	
Electrical Requirements	UL Listed
Type	120V, 10 Amps
OPTIONS	Electric
Pedestal	WD94B 27" x 14 1/8" x 30 3/4"
SideKick™ Pedestal Washer	WD100CB 27" x 14 1/8" x 30 3/4"
Stacking Kit	KSTK
DIMENSIONS	
Product (WxHxD)	27" x 29" x 30 1/4"
Carton (WxHxD)	55" (With door open) 29 23/32" x 42 27/32" x 31 17/32"
Weight (Product/Carton)	199.4 lbs / 212.1 lbs
LIMITED WARRANTY	

UPC CODES	
WM4100HBA	772454073250
DLEX4200B	772454073257
DLGX4201B	772454073356
WD100CB	772454071805
WD94B	048231028451
KSTK1	772454059896

1 Year Parts and Labour, 3 Years on Drum, 10 Years on Direct Drive Motor

LOT 2-05

HOME APPLIANCES

LG LAUNDRY

DLEX4200B/DLGX4201B

7.4 cu.ft. Capacity Electric/Gas Dryer

TurboSteam™ Technology

AI Sensor Dry™

Aluminized Alloy Steel Drum

Touch Control Panel

ENERGY STAR® Qualified

ThinQ™ Technology (Wi-Fi Enabled)


FlowSense™ Duct Clogging Indicator

SMART APPLIANCE


Enjoy new ways to control your home with LG smart appliances

LG ThinQ™

- Start the laundry while you're out shopping
- Get alerts when the cycle is finished
- Works with the LG ThinQ® app



CAPACITY		7.4
APPEARANCE		Front Control
Design Look		
Intelligent Electronic Controls with LED Display		
Touch Buttons		
Dial-A-Cycle™		
ENERGY		
ENERGY STAR® Qualified		
DRYING PROGRAMS		
No. of Programs - 14	Normal, Heavy Duty, Bedding, Small Load, Anti Bacterial, SteamSanitary™, SteamRefresh™, Fern Press, Delicates, Dry, Air Dry (Manual Dry), Downloaded Dry, Air Dry (Manual Dry), Downloaded	
No. of Options - 12	More Time, Less Time, Damp Dry Signal, Wrinkle Care, Control Lock, Wi-Fi, Energy Saver, TurboSteam™, Reduce Static, Remote Start, Drum Light, Signal	
Temperature Settings	High, Mid, High, Medium, Low, Ultra Low	
Drying Levels	Very, More, Normal, Less, Damp	
Manual Dry Times	60 min, 50 min, 40 min, 30 min, 20 min, More Time/Less Time	
FABRIC CARE FEATURES		
AI Sensor Dry™		
TurboSteam™		
Precise Temperature Control and Variable Heater		
CONVENIENCE FEATURES		
3 Minute Installation Check		
LoDecibel™ Quiet Operation		
End of Cycle Signal		
Drum Light		
Reversible Door		
FlowSense™ Duct Clogging Indicator		
Wrinkle Care Option		
Control Lock		
Venting Option		
Leveling Legs	Electric 4 Way Venting Gas 3 Way Venting	
Remaining Time Display/Status Indicator(s)	4 Adjustable Legs	



ThinQ® TECHNOLOGY

SmartDiagnosis™ (v3.0)

Wi-Fi

Remote Start and Cycle Monitor

Energy Monitoring

MATERIALS AND FINISHES

Aluminized Alloy Steel Drum

Cabinet

Control Panel

Door

All Available Colours

POWER SOURCE

Ratings

Electrical Requirements

Type

BTU Rating

OPTIONS

Pedestal

Stacking Kit

DIMENSIONS

Product (WxHxD)

Carton (WxHxD)

Weight (Product/Carton)

LIMITED WARRANTY

1 Year Parts and Labour, 3 Years on Drum

UPC CODES

WM4100HBA

DLEX4200B

DLGX4201B

WDP4B

KSTK1

772454073250

772454073257

772454073355

048231025451

772454059896



Life's Good

LOT 2-65

HOME APPLIANCES

LG REFRIGERATION

LMWS27626S

4-Door French Door Refrigerator

KEY FEATURES

- Sleek Design
- Double Freezer
- Internal Water Dispenser
- Door Cooling+
- Smart Cooling System
- Smart Diagnosis™
- ENERGY STAR® Qualified


AVAILABLE COLORS



Smudge Resistant Stainless Steel

PRODUCT FEATURES

CAPACITY	
Refrigerator (cu.ft.)	18.20
Freezer (cu.ft.)	8.70
Total Capacity (cu.ft.)	26.90
ENERGY	
Energy Consumption (kWh/Year)	636
ENERGY STAR® Qualified	Yes
WATER & ICE SYSTEM	
Ice & Water Dispenser	Water Only
Dispenser Type	Internal Water Dispenser
Daily Ice Production (lbs)	2.5 lbs
IcePlus™ Production (lbs)	2.7 lbs
Ice Storage Capacity (lbs)	3.5 lbs
Ice System	Factory Installed
Water Filter	LT1000P
COOLING	
Linear Compressor	Yes
Smart Cooling™ System	Yes
Door Cooling+	Yes
Multi-Air Flow™ System	Yes
Temperature Sensors	5
Evaporator	1
CONVENIENCE	
Display Type	Membrane / White LED
Temperature Controls	Electronic/Digital
Auto Closing Door Hinge	Yes
Sabbath Mode	Yes
LoDecibel™ Quiet Operation	Yes
REFRIGERATOR	
No. of Shelves	4 Split
Hybrid Shelves	Yes
Shelf Construction	Spill Protector™ Tempered Glass
Crisper Bins	2 Humidity Crisper
Glide N' Sense™ Drawer	Yes
Refrigerator Light	Ceiling LED (Frameless)
REFRIGERATOR DOOR	
No. of Bins	6 Total (2 Adjustable Gallon Sized)
Door Bin Construction	1 Piece (Clear)



FREEZER	
Door Type	Pull Drawer
Drawers	2-Tier Organization
DuraBase™ Solid Drawer Base	Yes
Drawer Divider	Yes
Freezer Light	Premium LED
Freezer Handle	Yes
Smart Features	
SmartDiagnosis™	Yes
MATERIALS AND FINISHES	
Contour Door	Yes
Hidden Hinges	Yes
Surface	Smooth
Smudge Resistant Exterior	Yes
Handles	Matching Commercial Handles
All Available Colors	Smudge Resistant Stainless Steel
DIMENSIONS/CLEARANCES/WEIGHTS	
Depth with Handles	34 1/4"
Depth without Handles	31 3/4"
Depth without Door	27 7/8"
Depth (Total with Door Open)	46 1/2"
Height to Top of Case	68 3/8"
Height to Top of Door Hinge	69 3/4"
Width	35 3/4"
Width (Door Open 90° with Handle)	44 1/4"
Width (Door Open 90° without Handle)	39 1/4"
Door Edge Clearance with Handle	4 1/2"
Door Edge Clearance without Handle	1 3/4"
Installation Clearance	Sides 1/8", Top 1", Back 2"
Weight (Unit/ Carton)	287lbs / 311lbs.
Carton Dimensions (WxHxD)	38" x 73" x 36"
LIMITED WARRANTY	
Parts & Labor	1 Year
Sealed System	7 Years
Inverter Linear Compressor	10 Years

UPC CODES
LMWS27626S (Smudge Resistant Stainless Steel) 048231806442


LOT 2-65

VISSANI

Under Cabinet Range Hood

**Hotte de cuisinière
pour dessous d'armoire**

U5H300A15 / QR052



Owner's Manual
Manuel de l'utilisateur

LOT 2-65

Pre-Installation (continued)

FOLLOW THESE GUIDELINES WHEN INSTALLING DUCT WORK:

- Your venting system must vent to the outdoors either horizontally through the back wall (13) or vertically through the roof (14) (refer to Fig. 5/ Fig. 6/ Fig. 7).
- Use round metal duct work with a uniform diameter of 152 mm (6 in). The total duct run in the venting system should be not more than 10.7 m (35 ft).
- Calculate the total effective length of the duct work by adding the equivalent lengths in the table shown (Fig. 9). For each fitting used add the length of the equivalent straight duct used in the system.
- Fasten all connections between pieces of duct with sheet metal screws and tape all joints with certified duct tape.
- If you must turn the path of the duct work using elbows, keep the number of elbows to a minimum for effective performance and use no more than three 90° elbows. Ensure that there is a minimum of 457 mm (18 in) of straight vent between each elbow. Elbow as far away from the range hood's exhaust opening as possible.
- Cap the exterior of the duct with a wall cap (15) or roof cap (16). Never use 102 mm (4 in) laundry-type wall caps. Use caulking to seal exterior wall or roof opening around the cap.
- The venting system must have an exterior damper (not supplied). Check that your roof or wall cap has a damper and install one if needed.

Horizontal Wall Venting




Fig. 5

Horizontal Wall Venting




Fig. 6

Vertical Roof Venting




Fig. 7

For inside venting system (air does not exhaust to outdoors) see Fig. 8. Please refer to the installation section. The cover on the top plate will be removed and air will be exhausted through the charcoal filter and out from 17.




Fig. 8

Equivalent Length Chart

Type of duct	Length added
45° Elbow	0.91 m (3 ft)
90° Elbow	1.52 m (5 ft)
90° Flat elbow	3.66 m (12 ft)
2.74 m (9 ft) Straight duct	2.74 m (9 ft)
Wall cap	0 m (0 ft)

Fig. 9

Installation

WARNING: FUEL (GAS) BURNING RANGES MUST BE VENTED OUTDOORS USING, AT MINIMUM, METAL DUCTWORK AND RANGE HOODS OF SUFFICIENT CAPACITY. Follow your fuel burning equipment manufacturer's guidelines, as well as, all applicable safety standards published by the National Fire Protection Association (NFPA), and the American Society for Heating, Refrigeration and Air Conditioning Engineers (ASHRAE), and your local code authorities.

REMOVING THE ELECTRICAL KNOCK-OUT HOLE



WARNING: Always wear safety goggles and gloves during installation.

- Choose the appropriate electrical knock-out hole to remove for your installation type. Use the top hole (1) if your electrical supply is in the cabinet and the back hole (2) if your electrical supply is on the wall below the cabinet (refer to Fig. 10).
- Use a hammer and a flathead screwdriver to gently punch out the electrical knock-out hole.




Fig. 10




Fig. 11




Fig. 12

- Choose the venting hole to remove for your installation type. Use the top hole (3) for a top venting installation and the back hole (4) for a back venting installation.
- Carefully remove the cover (3 or 4) of the appropriate venting hole using a flat head screwdriver or needle nose pliers (refer Fig. 11). Be careful not to leave any debris inside the range hood (A).
- If you are venting indoors, unscrew the 2 screws holding cover (5) in place and remove the cover as per Fig. 12. **DO NOT REMOVE ANY OTHER VENTING HOLE COVER.**

INSTALLATION THE TRANSITION (SKIP THIS STEP IF YOU ARE USING INTERIOR VENTING)

NOTE:

If this hood replaces an existing unit, the location of the air exhaust can vary from one manufacturer to another. Ensure that the transition fits in the existing opening before installing.

- Choose to install the transition (C) either in the top position (3) for top venting or in the back position (4) for back venting.
- Insert the transition (C) into the chosen hole in the range hood (A), ensuring that the central flap (6) goes into the hole while the two side flaps (7) remain above it.
- Screw the transition (C) to the range hood (A) with the two short tapping screws (BB).
- Seal the transition (C) to the range hood (A) on all four sides with duct tape.




Fig. 13

