

REFRIGERATOR

LFX28978

CAPACITY

Refrigerator	18.8 cuft.
Freezer	8.8 cuft.
Total	27.6 cuft.

FEATURES

Energy Rating	Energy Star
Freezer Door Type	Drawer
External Ice & Water Dispenser	
Water Filtration System	Compact Filter LT700P
Multi-Air Flow Cooling Display	

LED (Temperature R/F, Ice & Water, Child Lock, IcePlus™, Water Filter Status)

Temperature Controls	Electronic
Temperature Sensors	6
LoDecibel™ Operation	
Door Alarm	

REFRIGERATOR



No. of Shelves	4 Split
Slide-Out Shelves	3
Folding Shelf	1
Canilivered Shelves	
Shelf Construction	Spill Protector™ Tempered Glass
Crisper Bins	2 Humidity Crispers/1 Bonus Drawer
Glide N' Serve™ Drawer	
Slim SpacePlus™ Ice Maker	
Refrigerator Light	Premium LED

REFRIGERATOR DOOR

No. of Shelves/Bin	6 (2 Adjustable Gallon Size)
Dairy Corner	

FREEZER

Drawers	2
DuraBase™ Solid Drawer Base	
Divider	
IcePlus™	
Ice Bin	
Freezer Light	60W



MATERIALS AND FINISHES

Foam Door Insulation	
Contour Door	
Hidden Hinges	
Toe Grille	
Surface	Coated Metal, Stainless Steel
Back	Flush & Metal cover over mechanical parts
Available Colors	Smooth White (SW), Smooth Black (SB), Stainless Steel (ST)

HANDLES

Matching Commercial Handles

DIMENSIONS/CLEARANCES/WEIGHT

Depth with Handles	35 3/8"
Depth without Handles	32 7/8"
Depth without Door	29"
Depth (Total with Door Open)	47 5/8"
Height to Top of Case	68 3/8"
Height to Top of Door Hinge	69 3/4"
Width	35 3/4"
Width (Door Open 90° with Handle)	44 1/4"
Width (Door Open 90° without Handle)	39 1/4"
Door Edge Clearance with Handle	4 1/2"
Door Edge Clearance without Handle	1 3/4"
Installation Clearance	Sides 1/8", Top 1", Back 1"
Weight (Unit/Carton)	324 lbs./377 lbs.
Carton Dimensions (WxHxD)	38" x 73" x 38"

WARRANTY

1 Year Parts and Labor,
7 Years on the Sealed System,
10 Years on Linear Compressor

UPC CODES

LFX28978SW	Smooth White	048231 783217
LFX28978SB	Smooth Black	048231 783194
LFX28978ST	Stainless Steel	048231 783200

www.LG.com

LG Electronics U.S.A., Inc.
1000 Sylvan Avenue Englewood Cliffs, NJ 07632
Customer Service and Technical Support: (800) 243-0000


Dimensions and weights are approximate. Design, features and specifications subject to change without notice.

© 2010 LG Electronics USA, Inc. All rights reserved. "LG Life's Good" is a registered trademark of LG Corp. All other product and brand names are trademarks or registered trademarks of their respective companies.

HARF-LFX28978-S5 07/01/10

ZVC36LSS GE Monogram® 36" Custom Hood Insert

Custom Insert Liner




The custom canopy must be sized to fit the insert sleeve. Construct the canopy with an opening that is:

26"W x 13-3/16"D

The opening must be constructed of 3/4" thick material to allow the sleeve locking clips to engage.

The Supplied Liner




A stainless steel liner is shipped with each hood insert. This non-combustible liner protects the underside of the canopy.

Custom Liner


If you are not using the supplied liner, you may construct a custom non-combustible liner. Use the supplied liner as a template. The opening must be 26"W x 13-3/16"D. 3/4" thick material must surround the opening to allow the sleeve locking clips to engage. The insert sleeve inside the cabinet should be positioned 1/2" from the rear wall so that the center of the 8" duct is 5-1/2" from the rear wall.

Dimensions and Specifications (in inches)

Outside Dimensions




The Insert Sleeve



The bottom edge of the insert sleeve has a 7/8" wide flange on the sides and a 1/2" wide flange on the front and back.

Remote Location for the Control

The control may be removed from the hood and installed into a wall or countertop. A 30-ft length of wire is supplied to accommodate most installations. A blanking plate covers the opening when the controls are removed. The overall size of the control is 4-1/4" wide and 2-1/4" deep.



We recommend that the cutout in granite or other hard surfaces be made before the countertop is installed.



imagination at work

For answers to your Monogram®, GE Profile™ or GE® appliance questions, visit our website at geappliances.com or call GE Answer Center® service, 800.626.2000.

JGP975SEK

GE Profile™ 36" Built-In Gas Cooktop

Dimensions and Installation Information

AGA Requirement: All gas cooktop models require 7/16" free area below cooktop height to combustible material. Requires 18" minimum from countertop to adjacent overhead cabinets.



Note: If installing with a GE Profile™ Telescopic Downdraft System, consult both cooktop and downdraft installation instructions packed with product before installing. Cooktop gas/electric supply may need to be re-routed to install downdraft.

Electrical Rating: 120V, 60Hz, 5A



Installation With Single Wall Oven Information:

30" Gas Cooktops are approved for use over select GE 27" and 30" Wall Ovens and Warming Drawers. 30" and 36" Gas cooktops are approved for use over 30" Wall Ovens and Warming Drawers. Refer to cooktop and wall oven/warming drawer installation instructions packed with product for current dimensional data.

Installation Information: Before installing, consult installation instructions, packed with product, for current dimensional data.



Gas Connection



Electrical junction box 12" MIN. below countertop

Cut should not interfere with cabinet structure at front

For answers to your Monogram®, GE Profile™ or GE® appliance questions, visit our website at ge.com or call GE Answer Center® service, 800.626.2000.

Dimension and installation information are shown in inches.
*Allow 5-3/4" depth at rear for electrical and gas connections



imagination at work



Specification Revised 10/05

230276

PT925SN

GE Profile™ 30" Built-In Single/Double Convection Wall Oven

Dimensions and Installation Information (in inches)

KW Rating	
240V	3.9
208V	2.9
Breaker Size	
240V	20 Amps
208V	20 Amps

Most 30" Wall Cabinets can be used with this unit.

Note: These ovens are not approved for stackable installations. Cabinets installed adjacent to wall ovens must have an adhesion spec of at least a 194°F temperature rating.


Door handle protrudes 3" from door face. Cabinets and drawers on adjacent 45° and 90° walls should be placed to avoid interference with the handle.

Electric wall ovens are not approved for installation with a plug and receptacle. They must be hard wired in accordance with installation instructions.

Installation Information: Before installing, consult installation instructions packed with product for current dimensional data.

Side-by-side installations require at least 2" between cutouts.

For answers to your Monogram,® GE Profile™ or GE® appliance questions, visit our website at ge.com or call GE Answer Center® service, 800.626.2000.



Dimension and installation information are shown in inches.



imagination at work



Listed by
Underwriters
Laboratories



Specification Revised 4/09

220245

PEB2060SM

GE Profile™ 2.0 Cu. Ft. Countertop Microwave Oven

Dimensions and Installation Information (in inches)

Exterior Dimensions (in inches)	
W x H x D	24 x 13-3/4 x 19-3/8


Accessory trim kits	"Z"	Trim Kits	Max Height
30" Deluxe	29-3/4"	JX2030SMSS	19-1/16"
27" Deluxe	26-15/16"	JX2027SMSS	19-1/16"

Optional Accessory Trim Kits for 2.0 GE Microwave Ovens (Available at additional cost)

For a custom built-in appearance, these kits allow built-in installation of the countertop microwave oven into a wall or cabinet alone and are U.L. approved for installation over a GE single electric wall oven. These kits should not be installed over a gas wall oven.

Note: 120V, 60-cycle, grounded power receptacle location optional on back within cabinet opening.

Installation Information: This information is not intended to be used for installing unit described. Before installing, consult installation instructions packed with product/kit for current dimensional data.



For answers to your Monogram®, GE Profile™ or GE® appliance questions, visit our website at geappliances.com or call GE Answer Center® service, 800.626.2000.



PDWF600/680R

GE Profile™ Stainless Built-In Dishwasher with SmartDispense™ Technology


Dimensions and Installation Information (in inches)

Electrical Rating

Voltage AC.....	120
Hertz.....	60
Total connected load amperage.....	9.9
Calrod® heater watts max.....	875

For use on adequately wired 120-volt, 15-amp circuit having 2-wire service with a separate ground wire. This appliance must be grounded for safe operation.

Installation Information: Before installing, consult installation instructions packed with product for current dimensional data.



For answers to your Monogram®, GE Profile™ or GE® appliance questions, visit our website at ge.com or call GE Answer Center® service, 800.626.2000.



imagination at work



Listed by
Underwriters
Laboratories




As an ENERGY STAR® partner, GE has determined that this product meets the ENERGY STAR guidelines for energy efficiency.

Installation Instructions

THE INSTALLATION SPACE

The beverage center and wine chiller can be a free-standing model or it can be built in using the cut-out dimensions below.



The cutout depth should be 24"

The cutout dimensions shown allow for a full door swing and access to the pull-out racks when installed as a built-in in standard 24" deep cabinets.

- The door should protrude 2-1/4" beyond the surrounding cabinets. For easy reference, the back edge of the pocket handle should protrude a minimum of 5/8" beyond the front edge of the countertop.
- If installing between frameless cabinets, a 1/2" wide filler strip or side panel may be needed on hinge side. The filler strip will act as a spacer between the case and adjacent cabinet door swing. The width of the opening must include the filler panels. **NOTE:** The door should protrude 2-1/4" beyond the surrounding cabinets.
- The beverage center and wine chiller can be installed freestanding.

Additional Specifications

- A 120 volt 60Hz, 15 or 20 amp power supply is required. An individual properly grounded branch circuit or circuit breaker is recommended. Install a properly grounded 3-prong electrical receptacle recessed into the back wall as shown. Electrical must be located on rear wall as shown. **NOTE: GFI (ground fault interrupter) is not recommended.**

SIDE-BY-SIDE INSTALLATIONS

Increase storage capacity by installing two beverage centers or wine chillers together. Or, for a complete refreshment center, install any two of these units together.

- A side-by-side installation requires at least a 47-1/2" wide opening. No trim kits required.
- Products must operate from separate, properly grounded receptacles.

