

PRODUCT MODEL NUMBERS

KBFS22EW
KBFS25EW


Electrical: A 115 Volt, 60 Hz., AC only 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

Water: Connect the ice maker to a cold water supply with water pressure between 35 and 120 psi (241 and 827 kPa).

If a reverse osmosis water filtration system is connected to your cold water supply, the water pressure to the system needs to be a minimum of approximately 40 to 60 psi (276 to 414 kPa).


IMPORTANT: The pressure of the water coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 35 and 120 psi (241 and 827 kPa).

OVERALL DIMENSIONS



Model #	Depth with Handles "A"	Cab. Width "B"	Cab. Height "C"	Overall Height "D"
KBFS22EW	34 1/2"	32 5/8"	68 7/8"	70 1/8"
KBFS25EW	35 1/2"	35 5/8"	68 7/8"	70 1/8"

LOCATION REQUIREMENTS



To ensure proper ventilation for your refrigerator, allow for 1/2" (1.25 cm) space at the top and behind the refrigerator. If your refrigerator has an ice maker, allow extra space at the back for the water connections. When installing your refrigerator next to a fixed wall, leave 2 1/2" (6.3 cm) minimum on each side (some models require more) to allow for the door to swing open.

NOTE: It is recommended that you do not install the refrigerator near an oven, radiator, or other heat source. Do not install the refrigerator in a location where the temperature will fall below 55°F (13°C).

LOT 11 SR2



FOR THE WAY IT'S MADE®

30-In. Width | Freestanding | Electric | 5 Elements | Even-Heat™ True Convection System | Architect® Series II

Base model: YKER507XSS | MSRP: See Dealer*



With two ovens that combine for the industry's largest capacity,* this double oven range allows you to cook several dishes simultaneously, even at different temperatures. The cooking surface offers flexibility with five elements and controls that respond to the touch. *Among electric double oven ranges.

PRODUCT FEATURES


- 10" 3200-watt element accommodates high-temperature cooking methods like rapid boiling and searing
- 6.7 cu. ft. combined upper and lower oven capacities provide more room to cook multiple dishes simultaneously
- EasyConvect™ Time and Temperature Conversion System takes the guesswork out of convection cooking
- Even-Heat™ True Convection System provides consistent heating and even cooking on both lower oven racks
- The oven's slow cook function provides superb slow cooking without taking up valuable counter space

AVAILABLE COLOURS

■ STAINLESS STEEL | YKER507XSS
MSRP*: SEE DEALER

For questions regarding major appliances, call 1-800-422-1230, Monday - Friday 8 a.m. - 6 p.m. local time

Product Dimensions



- A. $35\frac{3}{4} \pm \frac{1}{8}$ (90.8 cm \pm 0.3 cm) cooktop height (minimum) with leveling legs screwed all the way in*
- B. Model/serial/rating plates (located behind the control panel)**
- C. $47\frac{1}{8} \pm \frac{1}{8}$ (119.7 cm \pm 0.3 cm) overall height (minimum) with leveling legs screwed all the way in*
- D. $28\frac{1}{2} \pm \frac{1}{4}$ (72.4 cm \pm 0.6 cm) depth with handle
- E. $26\frac{1}{8} \pm \frac{1}{8}$ (66.4 cm \pm 0.3 cm)***
- F. $29\frac{5}{16} \pm \frac{1}{16}$ (76.0 cm \pm 0.2 cm) width

*Range can be raised approximately 1" (2.5 cm) by adjusting the leveling legs.

**Model/serial/rating plates may be rotated up from behind the control panel for viewing from the front of the range.


***Excludes handle. Dimension given is from wall to front of oven door and will vary based on electric outlet receptacle installation.

Cabinet Dimensions

Cabinet opening dimensions shown are for 25" (63.5 cm) countertop depth, 24" (61.0 cm) base cabinet depth and 36" (91.4 cm) countertop height.

IMPORTANT: If installing a range hood or microwave hood combination above the range, follow the range hood or microwave hood combination installation instructions for dimensional clearances above the cooktop surface.

A freestanding range may be installed next to combustible walls with zero clearance.



- A. 18" (45.7 cm) upper cabinet to countertop
- B. 13" (33.0 cm) upper cabinet depth
- C. 30" (76.2 cm) min. opening width.
- D. For minimum clearance to the top of the cooktop, see NOTE.
- E. 30" (76.2 cm) min. opening width
- F. Cabinet door or hinge should not extend into cutout*
- G. 1½" (3.8 cm) min. from right side cabinet
- H. 2" (5.1 cm) min. from floor
- I. 7" (17.8 cm) min. from floor
- J. 8" (20.3 cm) width
- K. 3½" (8.91 cm) min. from floor

Proper positioning of outlet shown above.


*Nothing located in shaded areas can extend more than 1½" (3.8 cm) from wall or range will not slide all the way back.

NOTE: 24" (61.0 cm) minimum when bottom of wood or metal cabinet is covered by not less than ¼" (0.64 cm) flame retardant millboard covered with not less than No. 28 MSG sheet steel, 0.015" (0.4 mm) stainless steel, 0.024" (0.6 mm) aluminum or 0.020" (0.5 mm) copper.

30" (76.2 cm) minimum clearance between the top of the cooking platform and the bottom of an unprotected wood or metal cabinet.

Lot 11 SR2

KitchenAid®



KitchenAid® 24-Inch 5-Cycle/6-Option Dishwasher, Architect® Series II

★★★★☆ 4.4 / 5

[Read all 22 reviews](#) [Write a review](#)

This high performance dishwasher has an energy-efficient, filter-based wash system that helps make it the industry's best performing dishwasher^{1*}. And features like the ProWash™ Cycle and ProScrub® Option virtually remove the guesswork from getting a variety of dishes clean.

AVAILABLE COLOR OPTIONS

■ □ □
Stainless Steel - KUDE48FXSS

SPECIFICATIONS

Performance

Optimum Wash Sensor	Optimum Wash Sensor
Hi Temp Wash Option	Yes
Quick Clean Up Cycle	Yes
Light/China Cycle	Yes
One Hour Wash Cycle	One Hour Wash
Number of Options	6
Sani Rinse Option	Yes
Normal Cycle	Yes
Heated Dry Option	Yes
Number of Cycles	5
4 Stainless Steel Wash Arms	S-Shape 2 Arm

Quality Construction

Rack Glides	Satin Glide Max
Durakote™ Rack Material	Nylon
Commercial Grade Stainless Steel Tub	Stainless
Sound Tested DBA	46
Tub Design	Tall Tub

Loading Features

LOT 11SR2

Place Settings	15 Place Settings
Lower Rack	2 Fold-Down Tines
Premium Easy Lift Upper Rack Adjuster	Premium - 2 Position
Upper Rack	2 Fold-Down Tines
Silverware Basket	Large In-the-Rack Basket

General

ENERGY STAR® Qualified	Yes
------------------------	-----

Dimensions

Maximum Height	34 1/2
Product Width	23 7/8
Product Depth	27 1/2
Minimum Height	33 3/4
Product Height	34 1/2

(1) Combined wash and dry results of leading premium brands' highest MSRP models; dry testing conducted without rinse aid.