

13R SL Semi's

American Standard

Style That Works Better



CADET® 3 RIGHT HEIGHT™ 14" ROUGH-IN ELONGATED TOILET

VITREOUS CHINA

CADET® 3 RIGHT HEIGHT™ 14" ROUGH-IN ELONGATED TOILET

☐ 2386.014

- Vitreous china
- Low-consumption (6.0 Lpf/1.6 gpf)
- EverClean® surface inhibits the growth of stain- and odor-causing bacteria, mold, and mildew on the surface
- Features the **Cadet® 3 Flushing System**
- 16-1/2" rim height for accessible application
- Elongated siphon action jetted bowl
- Fully-glazed 2-1/8" trapway with 2" ball pass
- Generous 9" x 8" water surface area
- Close-coupled tank with flat tank cover for superior storage
- Oversized 3" flush valve with chemical resistant flapper
- Chrome trip lever
- Speed Connect® tank-to-bowl coupling system
- Sanitary dam on bowl with four point tank stabilization
- 2 color-matched bolt caps
- 100% factory flush tested
- 5 year warranty

☐ 3016.016 Right Height™ Elongated Bowl

☐ 3016.001 Right Height™ Elongated Universal Bowl

☐ 4027.016 Tank

Nominal Dimensions:

819 x 445 x 775mm (32-1/4" x 17-1/2" x 30-1/2")

Fixture only, seat and supply by others

Alternative Tank Configurations Available:

- ☐ **4027.600** Tank complete with tank cover locking device
- ☐ **4027.800** Tank complete with trip lever on right side
- ☐ **4027.900** Tank complete with tank cover locking device and trip lever on right side



Compliance Certifications -

Meets or Exceeds the Following Specifications:

- ASME A112.19.2-2008/CSA B45.1-08 for Vitreous China Fixtures

To Be Specified:

- ☐ Color: ☐ White ☐ Bone ☐ Linen ☐ Black
- ☐ Seat: #5325.010 Elongated Champion® Slow Close solid plastic seat and cover with easy lift off feature
- ☐ Seat: #5284.016 Elongated EverClean® solid plastic seat and cover
- ☐ Seat: #5321.110 EverClean® Elongated Seat with Slow Close Snap-Off Hinges
- ☐ Supply with stop:



NOTES:

THIS TOILET IS DESIGNED TO ROUGH-IN AT A MINIMUM DIMENSION OF 356MM (14") FROM FINISHED WALL TO C/L OF OUTLET. SUPPLY NOT INCLUDED WITH FIXTURE AND MUST BE ORDERED SEPARATELY.

* DIMENSION SHOWN FOR LOCATION OF SUPPLY IS SUGGESTED.

IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.



MEETS THE AMERICANS WITH DISABILITIES ACT GUIDELINES AND ANSI A117.1 REQUIREMENTS FOR ACCESSIBLE AND USABLE BUILDING FACILITIES-CHECK LOCAL CODES.

CADET® 3

Flushing System



see what Delta can do[®]

Leland Single Handle Pull-Down Kitchen Faucet

Model Number: 9178-AR-DST



Features & Benefits

- A charming teapot-inspired series of faucets for the entire home.
- Timeless design is a perfect marriage of both form and function.
- High-arc spout swivels 360° for complete sink access
- The pull-down spray wand features a 59 inch hose providing a 20 inch reach
- Single Handle control provides ease of operation with one hand
- Optional escutcheon for three hole mounting included

Smart Features

- ADA Compliant
- DIAMOND™ Seal Technology
- MagnaTite® Docking
- Water-Efficient
- Touch Clean
- Legislation Compliant



13R SR SEMI'S
ENSUITE

MAAX SUBMITTAL SPECIFICATIONS

60NHS - 1-piece

MODEL NUMBER 105083

DIMENSIONS: 66" x 37" x 84" Acrylic



Vivez l'expérience
MAAX®
Enjoy the experience

STANDARD FEATURES

- 1-piece shower with roof cap
- Integrated soap dishes, grab bars and curtain rod
- Unique features: reinforced walls and easy access design
- Optional seat (specify left or right)

OPTIONS

- 12 in. straight grab bar
- 16 in. straight grab bar
- 24 in. straight grab bar
- 30 in. straight grab bar
- 36 in. straight grab bar
- 18 x 32 in. horizontal L-shaped grab bar

UNIQUE FEATURES

- None

SYSTEMS

- None

DOOR SELECTION

Combine with MAAX's complete shower door offering visit www.maax.com

Project :

Contractor :

MAAX Representative :

Date :

Tel :

www.maax.com

CERTIFICATIONS

Maax products adhere to one or more of the following certifications:




2014-05-29

MAAX SUBMITTAL SPECIFICATIONS

60NHS - 1-piece

MODEL NUMBER 105083

TECHNICAL DRAWINGS



All dimensions are approximate. Structure measurements must be verified against the unit to ensure proper fit.

13R SR SEMI'S

ENSUITE



see what Delta can do™

Delta Shower Arm Mount Hand Shower

Model Number: 54613



Features & Benefits

- Timeless design for today's homes
- Simple, elegant lines complement traditional decor
- Three function spray for personal comfort
- Complete with 69 hose and shower mount bracket
- 69 long hose for a long reach within the shower.
- Dual check valves

Product Specifications

FLOW RATE: 2.5 gpm @ 80 psi, 9.5 L/min @ 550 kPa

SPRAY SETTINGS:  Full Body Spray
 Massaging Spray
 Soft Drench Spray

13R SR-SERIES
ENSUITE



see what Delta can do™

Delta 3 Setting Diverter Trim

Model Number: T11800



Features & Benefits

- For use with R11000 diverter rough-in
- Includes valve cartridge
- Available in five finishes

Smart Features

- ADA Compliant

Product Specifications