

Lot 49 DV

SUMMARY **FRIDGE**

CAPACITY	MEASUREMENTS (WXHxD)
29.50 cu.ft.	35 3/4" x 68 7/8" x 36 5/8"

INSTAVIEW™ DOOR-IN-DOOR®	THINQ®
Yes	Yes

SUMMARY

Series	LG
Type	French Door
Door Type	4-Door
InstaView™ Door-in-Door®	Yes
Total Capacity (cu.ft.)	29.50
Colour	Smudge Resistant Stainless Steel

CAPACITY

Refrigerator (cu.ft.)	17.00
Full-Convert™ Drawer	3.60
Freezer (cu.ft.)	8.90
Total Capacity (cu.ft.)	29.50

Energy Consumption (kWh/Year)	799
-------------------------------	-----

ENERGY STAR® Qualified	Yes
------------------------	-----

## WATER & ICE SYSTEM

Ice & Water Dispenser	Yes
-----------------------	-----

Dispenser Type	Integrated Ice & Water Dispenser
----------------	----------------------------------

Measured Fill	Yes
---------------	-----

Daily Ice Production (lbs)	3.5 lbs
----------------------------	---------

IcePlus™ Production (lbs)	3.8 lbs
---------------------------	---------

Craft Ice™ Daily Ice Production	0.4 lbs
---------------------------------	---------

Ice Storage Capacity (lbs)	3.0 + 3.3 lbs
----------------------------	---------------

Ice System	Slim SpacePlus®
------------	-----------------

Dual Ice with Craft Ice™	Yes
--------------------------	-----

Dispenser Light	Yes
-----------------	-----

Water Filter	LT1000P
--------------	---------

## COOLING

Linear Compressor	Yes
-------------------	-----

Smart Cooling Plus™ System	Yes
----------------------------	-----

Door Cooling+	Yes
---------------	-----

Multi-Air Flow™ System	Yes
------------------------	-----

Temperature Sensors	9
---------------------	---

Fresh Air Filter	Yes
------------------	-----

Evaporator	2
------------	---

## CONVENIENCE

Display Type	Smooth Touch Control/White LED
--------------	--------------------------------

Temperature Controls	Electronic/Digital
----------------------	--------------------

Door Alarm	Yes
------------	-----

Child Lock	Yes
------------	-----

Auto Closing Door Hinge	Yes
-------------------------	-----

Sabbath Mode	Yes
--------------	-----

LoDecibel™ Quiet Operation	Yes
----------------------------	-----

## REFRIGERATOR

No. of Shelves	4 Split (3 Fixed+1 Folding)
----------------	-----------------------------

Folding Shelf	1
---------------	---

Cantilevered Shelves	Yes
----------------------	-----

Shelf Construction	Spill Protector™ Tempered Glass
--------------------	---------------------------------

Crisper Bins	2 Humidity Crisper
--------------	--------------------

CoolGuard™	Yes
------------	-----

Refrigerator Light	Micro Surface LED
--------------------	-------------------

## FULL-CONVERT™ DRAWER

Dividers	Yes
Temperature Range (°C)	-23, -1, 1, 3, 5
Handle Type	SmartPull™

## REFRIGERATOR DOOR

InstaView™ Door-in-Door®	Yes
Adjustable Door-in-Door® Bin	Yes
No. of Bins	6
Door Bin Construction	1 Piece (Clear)

## FREEZER

Door Type	Pull Drawer
Drawers	2-Tier Organization
DuraBase™ Solid Drawer Base	Yes
Drawer Divider	Yes
Ice Bin / In-Door Ice	Icemaker & Ice bin in the freezer
Freezer Light	Premium LED
Freezer Handle	SmartPull™ Handle

## THINQ® SMART FEATURES

Wi-Fi Enabled	Yes
---------------	-----

**ThinQ® Technology with Proactive Customer Care**

Yes

**Works with**

Google Assistant, Amazon Alexa

**Smart Diagnosis™**

Yes

## **MATERIALS AND FINISHES**

**Contour Door**

Yes

**Hidden Hinges**

Yes

**Surface**

Smooth

**Fingerprint & Smudge Resistant Exterior**

Yes

**Handles**

Matching Commercial Handles

**All Available Colours**

Smudge Resistant Stainless Steel

## **DIMENSIONS/CLEARANCES/WEIGHTS**

**Depth with Handles**

39 1/8"

**Depth without Handles**

36 5/8"

**Depth without Door**

31 3/4"

**Depth (Total with Door Open)**

51"

**Height to Top of Case**

68 7/8"

**Height to Top of Door Hinge**

70 1/4"

**Width**

35 3/4"

**Width (Door Open 90° with Handle)**

45"

Width (Door Open 90° without Handle)	40"
Door Edge Clearance with Handle	4 5/8"
Door Edge Clearance without Handle	2 1/4"
Installation Clearance	Sides 1/8", Top 1", Back 2"
Weight (Unit/Carton)	404 lbs./437 lbs.
Carton Dimensions (WxHxD)	38" x 73" x 33"

## LIMITED WARRANTY

Parts & Labour	1 Year
Sealed System	7 Years
Linear Compressor (Parts Only)	6-10 Years

## UPC CODE

LRMVS3006S (Smudge Resistant Stainless Steel)	048231806145
---	--------------

# Gas Slide-in Range












Installation manual


NX60\*8\*\*\*\*

SAMSUNG

# Gas range components

## Tools needed

			
Flat-blade screwdriver	Phillips screwdriver	Open-end or adjustable wrench	Pipe wrench (2)
			
1/4" Nut driver	Pencil and ruler	Level	Pipe joint compound
			
Utility knife	Soapy water solution	Pliers	





# Installation requirements

## Location requirements



### Clearances and dimensions

BEFORE YOU BEGIN to install this appliance, refer to the following information, dimensions, and clearances. Do not locate the range where it may be subject to strong drafts. Provide adequate clearances between the range and adjacent combustible surfaces. These dimensions must be met for safe use of the range. The location of the electrical outlet and gas piping may be adjusted to meet the following dimensions and clearances.

For installation in Canada, a free-standing range is not to be installed closer than 4.7 in (12 cm) from any adjacent surface.


### CAUTION

This range has been designed to comply with the maximum allowable wood cabinet temperature of 194 °F (90 °C). Make sure the wall covering, countertops, and cabinets around the range can withstand the heat (up to 194 °F [90 °C]) generated by the range. If not, discoloration, delamination, or melting may occur.



### CAUTION

Do not grasp the knob, handle and push when you install.



### CAUTION

DO NOT install the oven so that the door is flush with the cabinet. For OTR over Gas Stove, please follow local GAS CODE.

## LG DISHWASHERS

## LDP6809

Top Control Dishwasher with TrueSteam®

KEY FEATURES

QuadWash® with TrueSteam®

Smudge Resistant Finish

SmartThinQ® WiFi Connectivity

3rd Rack

EasyRack™ Plus System

Inverter Direct Drive Motor with 10-Year Warranty

LoDecibel™ Quiet Operation (44 dBA)

NeverRust™ Stainless Steel Tub

Steam &amp; Refresh options

Dual Zone Wash

Energy Star®

SMART APPLIANCE



SmartThinQ®


Enjoy new ways to control your home with LG smart appliances

- Get notifications when dishes are clean
- Monitor the cycle time from your smartphone
- Works with the LG SmartThinQ® app

works with the Google Assistant

PRODUCT FEATURES

CAPACITY	
Total Place Settings	15
Upper Rack Dish Height Limit	7.1"
Lower Rack Dish Height Limit	12.5"
RACKS AND BASKETS	
Cutlery Baskets	Yes
Cup Rack	Yes
Stemware Holder	Yes
Fold Down Tines	Yes (Half, Upper/ Lower)
BPA-Free Nylon Coated Racks and Tines	Yes
Rack Handle	Yes (Upper/Lower)
Glide Rail	No
Wheel Bearing	No
EasyRack™ Plus System	Yes
Height Adjustable Upper Rack	Yes (One Touch, 3 Level)
3rd Rack	Yes
STYLE AND DESIGN	
Control Panel Location	Top
Electronic Controls	Hidden SmoothTouch™ Controls with LED Display
Signalight™ Cycle Indicator Lights	3
Time Remaining Indicator	Yes (LED)
Tub Material	NeverRust™ Stainless Steel
Tub Light	No
Handle	Matching Commercial Handle
All Available Colours	Matte Black Stainless Steel, Smudge Resistant Stainless Steel
FEATURES	
TrueSteam®	Yes
QuadWash®	Yes
Inverter Direct Drive Motor	Yes
LoDecibel™ Quiet Operation	44 dB
Number of Wash Cycles	10 (Auto, Heavy, Delicate, Refresh, Normal, Turbo, Download Cycle, Machine Clean, Rinse, Express)
Number of Options	9 (Dual Zone, Half Load, Energy Saver, Steam, High Temp, Extra Dry, Delay Start, Control Lock, Night Dry)
Number of Spray Arms	3 (Top, Upper, Lower)
SenseClean™ Wash System	Yes
Vario Wash	Yes
Detergent and Rinse-Aid Dispenser	Yes
Hybrid Condensing Drying System	Yes
End of Cycle Indicator	Yes (Beeper + END indication on display)



Hidden Water Heater	Yes
Safety Float Switch (Leaks)	Yes
Soil (Turbidity) Sensor	Yes
Tub Insulation	Yes
Sound Absorbing Material	Yes
Anti-Bacterial Treatment (Sump, Inner / Outer filter, Drain pump case, Drain hose)	Yes
Balanced Door	Yes
Multi-Level (5) Water Direction	Yes (Top Nozzle (Down), Upper Nozzle (Up/Down), Lower Nozzle (Up/Down))
Wi-Fi Enabled	Yes
Voice Activation	Yes
Works with	Google Assistant
SmartDiagnosis™	Yes
POWER RATINGS	
ENERGY STAR® Qualified	Yes
CEE Tier	1
Energy Use (kWh/Year)	258 kWh
Water Factor (WF)	2.8
DIMENSIONS / CLEARANCES / WEIGHT	
Product Dimensions (in) (W x H x D)	23.75" x 33.6" x 24.6"
Product Weight (lbs)	82 lbs. / 34.3 kg
Depth with Door Closed with Handle (in)	24 3/5"
Depth with Door Open (in)	50.5"
Clearances (W x H x D)	24" x 33.5" x 24"
Carton Dimensions (in) (W x H x D)	28" x 34.7" x 29.6"
Shipping Weight with Carton (lbs)	94.1 lbs. / 42.7 kg
LIMITED WARRANTY	
Labour	1 Year
Parts	1 Year
Control Board, Rack Parts, Tub/Door Liner	5 Years
Inverter Direct Drive Motor	10 Years
UPC CODES	
LDP6809BM (Matte Black Stainless Steel)	772454071577
LDP6809SS (Smudge Resistant Stainless Steel)	048231341141



# LDP7708\_

Top Control wi-fi Enabled Dishwasher  
with QuadWash™

## QUICK INSTALL & CLEARANCES

For full installation directions/clearances please refer to the corresponding User Manual and Installation Guide.

### DIMENSIONS / CLEARANCES / WEIGHT

Product Dimensions (in) (W x H x D)	23.75" x 33.6" x 24.6"
Depth with Door Closed with Handle (in)	24 3/5"
Depth with Door Open (in)	50 1/2"
Carton Dimensions (in) (W x H x D)	28" x 34 3/4" x 29 5/8"


### POWER RATINGS

ENERGY STAR® Qualified	Yes
CEE Tier	1
Energy Use (kWh/Year)	258 kWh/Year
Water Factor (WF)	2.8



### PREPARING ELECTRICAL WIRING

- Operate this appliance with the correct voltage as shown in your User Manual and on the rating plate. Connect it to a dedicated, properly grounded branch circuit which is protected by a time delay fuse. Connect the appliance using 3-wires, including a ground wire.
- If an outlet and other power connector are used, it should be in an accessible location adjacent to and not behind the dishwasher and within 4 ft. of the dishwasher's side.
- The wiring must be grounded properly. If in doubt, have it checked by a qualified electrician. Do not connect any other appliance to the same outlet.
- Route the wiring.
- Make sure the electrical cable is oriented in the right side channel.




### WARNING

- For personal safety, remove house fuse or open circuit breaker before installation.
- Do not use an extension cable or adapter with this dishwasher.
- If you find any damage to the dishwasher, contact your retailer or contractor.

### PREPARING CABINET OPENING

- This dishwasher is designed to fit a standard dishwasher opening. An opening may be needed on both sides to route plumbing and electrical connections.
- Select a location as close to the sink as possible for easy connections to water and drain lines.
- To ensure proper drainage, install the dishwasher no more than 12 ft. from the sink.
- If installing the dishwasher in a corner, leave a minimum of 2" between the dishwasher and the adjacent wall.
- To allow for proper clearance of plumbing and electrical, use the template included with the literature to determine the clearance on the side of the cabinet where the cabinet meets the back wall. Using a 2 1/2" diameter hole saw, drill a hole in the target area as shown on the template.



### WARNING


Don't use existing holes unless they are in the target area. Otherwise, the water supply and drain hose may be damaged by being crushed or kinked.

### CAUTION

Failure to properly locate the hole for the water and drain lines may prevent the dishwasher from installing flush with the cabinets and could result in kinked or damaged lines. Installation damage is not covered by the warranty, and leaks caused by improper installation may result in property damage.

### PREPARING WATER SUPPLY CONNECTION

- Make sure the house water supply is turned off before connecting the dishwasher water lines.
- Connect the dishwasher to a hot water supply with a temperature range between 120 °F (49 °C) and 149 °F (65 °C). This temperature range provides the best washing results and shortest cycle time. To prevent damage to dishes, the temperature should not exceed 149 °F (65 °C).
- When connecting the dishwasher water line, sealing tape or compound should be used on pipe threads to avoid leaks. Tape or compound should not be used on compression fittings.
- The water supply tube must be located in the left side channel.



### NOTE

Use new hoses when connecting to the water supply. Do not reuse old hoses.