

INT2-LOT 23 - MASTER

Reveal Sleek 71 Pivot Shower Door 32 1/2-35 1/2 x 71 1/2 in. 8 mm

Model number: 139575

Dimensions: 32 1/2-35 1/2" x 71 1/2" Installation: Alcove Door type: Pivot



Standard Features:

- Wide opening to ease the access in and out of the shower
- Strongly built sill, permanently fixed on the base, better water barrier
- Hinge with patent mechanism that offers 3 in. of lateral adjustment
- Additional 3/4 in. of out-of-plumb adjustment
- Header-less door, no height restriction
- New design, 1 7/8 in. deep, makes it compatible with many bases and tile

Product characteristics:

- 8mm Tempered Glass
- Available in Multiple Finishes
- Wide Opening

Warranty:

10 Years

Certifications

MAAX products adhere to one or more of the following certifications:



Frame Finish(es):

 Chrome (084)

 Dark Bronze (173)

 Brushed Nickel (305)

 Matte Black (340)

Glass Pattern(s):

 Clear (900)

Recommended products (Visit our website for a complete list of our recommended products)

No	Description
145024	KDS 3636
145025	KDS 3636 AFR
101430	Square Base 36 - 3 in.




Reveal Sleek 71 Pivot Shower Door 32 1/2-35 1/2 x 71 1/2 in. 8 mm

Model number: 139575

Dimensions: 32 1/2-35 1/2" x 71 1/2" Installation: Alcove Door type: Pivot

STANDARD



Code	Description	L	F	O
139575	Reveal Sleek 71 1/2" x 32 1/2" - 35 1/2"	32 1/2" - 35 1/2"	5 3/8"	23 3/4" - 26 3/4"
139576	Reveal Sleek 71 1/2" x 38" - 41"	38" - 41"	10 7/8"	23 3/4" - 26 3/4"
139577	Reveal Sleek 71 1/2" x 41 1/2" - 44 1/2"	41 1/2" - 44 1/2"	14 3/8"	23 3/4" - 26 3/4"
139578	Reveal Sleek 71 1/2" x 44" - 47"	44" - 47"	16 7/8"	23 3/4" - 26 3/4"
139579	Reveal Sleek 71 1/2" x 51 1/2" - 54 1/2"	51 1/2" - 54 1/2"	24 3/8"	23 3/4" - 26 3/4"
139580	Reveal Sleek 71 1/2" x 56" - 59"	56" - 59"	28 7/8"	23 3/4" - 26 3/4"

- Wall adjustment = 3/4"

All dimensions are approximate. Structure measurements must be verified against the unit to ensure proper fit.

Dimensions:

32 1/2-35 1/2 x 71 1/2 in.  
(826-902 x 1816 mm)

Glass Thickness:

5/16 in. (8 mm)

Weight:

100 lbs (45.5 kg)

Frame type:

Frameless

Opening:

Reversible

Door adjustment:

3 in.

Minimum access:

23 3/4 (603 mm)

Maximum access:

26 3/4 (603 mm)

Project:

WT2-LOT 23


Contractor:

Representative:

Date:

Tel:

Notes:





Lounge

Model number: 105798

Dimensions: 64" x 34" x 22"      Installation: Freestanding      Material: Acrylic



Standard Features:

- 2-piece – Transports and installs easily
- Bathtub apron available in 3 colors: Aqua, Platinum Grey, and Ruby
- MAAX innovative leveling legs for easy installation
- Faucet installation can be deck-mounted or floor-mounted
- Unique feature: maximized bathing well with comfortable backrest

Product characteristics:

- Made in North America
- Deck Space for Faucet
- Maximized Bathing Well

Warranty:

25 Years

Standard colors:

White (001)

Certifications

MAAX products adhere to one or more of the following certifications:


UL

ICC  
ES  
PMG

Options (Visit our website for a complete list of our options)

No	Description
<input type="checkbox"/> OPT 20137	Cable-operated waste and overflow


WT2-LOT 23



Lounge

Model number: 105798

Dimensions: 64" x 34" x 22" Installation: Freestanding Material: Acrylic



Dimensions:

64 x 34 x 22 1/4 in.  
(1626 x 864 x 565 mm)

Water capacity:

68 gallons - 259 liters

Weight:

160 lbs - 72.56 kg

Bathing well:

57 3/8 X 32 1/4 in.  
(1457 X 819 mm)

Deep sump height:


18 1/4 in. - 464 mm

Deck width:

5 1/4 in. - 133 mm

Drain location:

End

() : Recommended faucet area 2 sections of 12" (L) x 3 1/2" (W).  
All dimensions are approximate. Structure measurements must be verified against the unit to ensure proper fit.

Project: WT2-LOT 23

Contractor:

Representative:

Date:

Tel:

Notes:

