

WT 33

Halo Sliding Shower Door 56 1/2-59 x 78 3/4 in. 8 mm

Model number: 138997

Dimensions: 56 1/2-59" x 78 3/4" Installation: Alcove Door type: Slider



Standard Features:

- Glass panels 5/16 in. (8 mm) with a height of 78 3/4 in.
- Lotus easy clean protection for effortless maintenance
- Ball bearing roller technology for smooth and quiet opening
- 48 in. and 60 in. reversible showers door allowing left or right opening
- Also available in a corner configuration
- Available in 4 finishes: Chrome, Brushed

Product characteristics:

- Ball Bearing Roller System
- Bestseller
- Utile Compatible

Warranty:

10 Years

Certifications

MAAX products adhere to one or more of the following certifications:



Frame Finish(es):

 Chrome (084)

 Dark Bronze (173)

 Brushed Nickel (305)

 Matte Black (340)


Glass Pattern(s):

 Clear (900)

Recommended products (Visit our website for a complete list of our recommended products)

No	Description
410011	ModulR 6032 Corner left (without armrests)
102003	Rectangular Base 6034 - 3 in.
105055	Rectangular Base 6030 - 5 in.

Handwritten signature and initials in red circles.




WT 33

Halo Sliding Shower Door 56 1/2-59 x 78 3/4 in. 8 mm

Model number: 138997

Dimensions: 56 1/2-59" x 78 3/4" Installation: Alcove Door type: Slider

STANDARD



Code	Description	H	L Adjustable	F	P Adjustable	Door Opening	Wall Adjustment
138996	Halo 78 3/4" x 47"	78 3/4"	44 1/2" - 47"	22 1/2"	-	16 1/4" - 18 3/4"	1"
138997	Halo 78 3/4" x 59"	78 3/4"	56 1/2" - 59"	28 5/8"	-	22 1/8" - 24 5/8"	1"
139393	Return Panel 30"	78 3/4"	-	-	27 7/8"	-	1"
138998	Return Panel 32"	78 3/4"	-	-	29 7/8"	-	1"
139395	Return Panel 34"	78 3/4"	-	-	31 7/8"	-	1"
139396	Return Panel 36"	78 3/4"	-	-	33 7/8"	-	1"
139394	Return Panel 42"	78 3/4"	-	-	39 7/8"	-	1"

All dimensions are approximate. Structure measurements must be verified against the unit to ensure proper fit.

Dimensions:

56 1/2-59 x 78 3/4 in.
(1435-1499 x 2000 mm)

Glass Thickness:

5/16 in. (8 mm)

Weight:

162 lbs (73.47 kg)

Frame type:

Frameless

Opening:

Reversible

Door adjustment:

For out of plumb walls

Minimum access:

22 1/2 (572 mm)

Maximum access:

24 1/2 (572 mm)

Project: _____

Contractor: _____

Representative: _____

Date: _____

Tel: _____

Notes: _____

jm mm

WT 33

Exhibit 6032 IFS

Model number: 105520

Dimensions: 60" x 32" x 18" Installation: Alcove Material: Acrylic



Standard Features:

- Rectangular shape bathtub in alcove installation
- Available in Above-the-Floor Rough (AFR) or not
- Minimalist look with discreet armrests and textured floor
- Integrated tiling flange
- Integrated skirt with access panel when equipped with a system

Product characteristics:

- Made in North America
- Elegant design
- Integrated Tiling Flange and Skirt

Systems:

- Whirlpool
- Combined Whirlpool/Aeroeffect
- Aeroeffect

Warranty:

25 Years

Standard colors:

White (001)

Bone (004)

Biscuit (007)

Certifications

MAAX products adhere to one or more of the following certifications:

UL

ICC

ES

PHS

Recommended products (Visit our website for a complete list of our recommended doors)

No	Description
139398	Halo Sliding Tub Door 56 ½-59 x 59 in. 8 mm
135330	Incognito 57 Shaker Sliding Tub Door 56-59 x 56 ¾ in. 8 mm
139351	Incognito 57 Sliding Tub Door 56-59 x 56 ¾ in. 6 mm

Options (Visit our website for a complete list of our options)

No	Description
☐ OPT 10019	Removable access panel
☐ OPT 10053	Chromatherapy
☐ OPT 10095	Water heater assembly
☐ OPT 10106	Metal trim kit for whirlpool and combined systems
☐ OPT 20029	Metal trim kit for Air Push Control


mm

WT 33


Exhibit 6032 IFS

Model number: 105520


Dimensions: 60" x 32" x 18" Installation: Alcove Material: Acrylic



1" Single Integrated tiling flange (shown)
2" Double Integrated tiling flange (not shown)
Drop-in model (Shown)



Wood support design may vary.
Single Integrated tiling flange: 1" height x 1/4" thickness (shown)
Double Integrated tiling flange: 2" height (not shown)
All dimensions are approximate.
Structure measurement must be verified against the unit to ensure proper fit.



Dimensions:

59 3/4 x 32 x 17 3/4 in.
(1518 x 813 x 451 mm)

Water capacity:

46 gallons - 173 liters

Weight:

78 lbs - 35.37 kg

Bathing well:

53 1/4 X 25 7/8 in.
(1353 X 657 mm)

Deep sump height:

16 1/4 in. - 413 mm

Deck width:

4 1/8 in. - 105 mm

Drain location:

Left

Right

Project:

Contractor:

Representative:

Date:

Tel:

Notes:

[Handwritten signatures]