

CUSTOMER'S OWN APPLIANCE



HOME APPLIANCES

LG LAUNDRY

WM3998HBA

4.5 cu.ft. Front Load Washer & Dryer Combo

KEY FEATURES

- 4.5 cu. ft. Ultra Large Capacity
- TurboWash® Technology
- 6Motion™ Technology
- Steam Technology & Allergiene™ Cycle / AAFA Certified
- LG ThinQ® Technology
- Ventless Condensing Drying
- ColdWash™ Technology
- Direct Drive Motor 10-Year Limited Warranty
- LG SideKick™ Compatible
- NeveRust™ Stainless Steel Tub

AVAILABLE COLORS



BLACK STEEL





SMART APPLIANCE

LG ThinQ™

Enjoy new ways to control your home with LG smart appliances

- Start the laundry while you're out shopping
- Get alerts when the cycle is finished
- Works with the LG ThinQ® app



PRODUCT FEATURES

SUMMARY

Series	LG
Type	Front Load Washer & Dryer Combo
Capacity (cu.ft.)	4.5
Internal Heater	Yes
Steam	Yes
Width	27"
Color	Black Steel (B)
APPEARANCE	
Hard Buttons	Yes
Touch Buttons	Yes
Dial-A-Cycle™	Yes
WASH PROGRAMS	
No. of Programs	14 Normal, Heavy Duty, Bedding, Bright Whites, Sanitary, Allergiene, Tub Clean, Towels, Perm. Press, Sportswear, Delicates, Speed Wash, Drain+Spin, Down-loaded
No. of Options	12 Steam, Fresh Care, Cold Wash, Delay Wash, Remote Start, Wi-Fi, TurboWash®, Rinse+Spin, Extra Rinse, Add Garments, Pre Wash, Control Lock
WASH DETAILS	
No. of Wash/Rinse Temps	5 Extra Hot, Hot, Warm, Cold, Tap Cold
Wash/Rinse Temps	
No. of Spin Speeds	5 Extra High, High, Medium, Low, No Spin
Spin Speeds	
Max RPM	1300
Water Levels	Load Sensing
No. of Soil Levels	5

FABRIC CARE FEATURES

TurboWash® 2.0 Technology	Yes
Steam Technology	Yes
Allergiene™ Cycle	Yes
Sanitary Cycle	Yes
ColdWash™ Option	Yes
SenseClean™ System	Yes
CONVENIENCE FEATURES	
TrueBalance™ Anti-Vibration System	Yes
4 Tray Dispenser	Yes
End of Cycle Signal	Yes
LoadSense	Yes
Child Lock	Yes
Auto Suds Removal	Yes
Leveling Legs	Yes
Easy Loading TiltTub™	Yes
ThinQ® TECHNOLOGY	
SmartDiagnosis™	Yes
Wi-Fi	Yes
Cycle Monitoring and Notification	Yes
Energy Monitoring	Yes
Tub Clean Coach	Yes
ENERGY	
IMEF	2.4
IWF	3.7
MOTOR	
Motor Type	Inverter Direct Drive Motor
Axis	Horizontal

MATERIALS AND FINISHES

NeveRust™ Stainless Steel Drum	Yes
Cabinet	PCM
Control Panel	Plastic
Top Plate	Painted
Door / Rim	Glass/Chrome
Door Cover	Dark Blue Tinted Round Cover
All Available Colors	Black Steel (B)
POWER SOURCE	
Ratings	UL Listed
Electrical Requirements	120V, 10 Amps
Type	Electric
OPTIONS/ACCESSORIES	
Pedestal	WDP4B
Pedestal (WxHxD)	27 x 14 1/8 x 30 3/4 (50 9/16 D with door open)
LG Sidekick™ Pedestal Washer	WD100CB
LG Sidekick™ Pedestal Washer (WxHxD)	27 x 14 1/8 x 30 3/4 (50 9/16 D with door open)
DIMENSIONS	
Product (WxHxD)	27" x 39" x 30 1/4"
Depth with Door Open	55"
Carton (WxHxD)	29 23/32" x 41 27/32" x 31 17/32"
Weight (Product)	213.8 lbs.
Weight (Carton)	235.9 lbs.
LIMITED WARRANTY	
Parts and Labor	1 Year
Direct Drive Motor	10 Years
Drum	3 Years
UPC CODES	
WM3998HBA (Black Steel)	048231027946



Freestyle 40 Neo-Round (1-Piece)

Model number: 102998

Dimensions: 40" x 40" x 78"      Installation: Corner      Material: Acrylic



Standard Features:

- 1 or 2-piece shower
- 2 large shelves and integrated soap dish
- Customize the shower: specify seat or footrest
- Optional roof cap
- Optional roof cap light
- Integrated shelves, specify Chrome or Brushed Nickel guard rail

Product characteristics:

- Made in Canada
- One-Piece Unit
- Integrated Shelving




Warranty:

25 Years

Standard colors:

 White (001)

**Certifications**  
MAAX products adhere to one or more of the following certifications:



Recommended doors (Visit our website for a complete list of our recommended doors)

No	Description
137445	Radia Neo-round Sliding Shower Door 40 x 40 x 71 1/2 in. 6 mm







Freestyle 40 Neo-Round (1-Piece)

Model number: 102998

Dimensions: 40" x 40" x 78"

Installation: Corner

Material: Acrylic



All dimensions are approximate. Structure measurements must be verified against the unit to ensure proper fit.


Dimensions:  
39 1/2 x 39 1/2 x 77 1/2 in.  
(1003 x 1003 x 1969 mm)

Weight:  
107 lbs - 48.5 kg

Shape:  
NeoRound

Pieces:  
1

Drain location:  
With center footrest  
With center seat



Project: \_\_\_\_\_

Contractor: \_\_\_\_\_

Representative: \_\_\_\_\_

Date: \_\_\_\_\_

Tel: \_\_\_\_\_

Notes: \_\_\_\_\_

\_\_\_\_\_


\_\_\_\_\_





## CHARGING INSTALLATION: 240 VOLT NEMA 14-50 OUTLET

The Mobile Connector is included as standard equipment with all new vehicles. This is a 20-foot-long cable with interchangeable adapters which can be used to plug in to different outlets. This guide provides detail on installing a NEMA 14-50 outlet for home charging with the Mobile Connector. Adapter purchased separately.



### NEMA 14-50 OUTLET DETAILS

- **Circuit Breaker:** 50 amps
- **Voltage:** Single phase, 208-250 volt AC supply, 60 hertz
- **Four Wire Configuration:** Line 1 - Line 2 - Ground - Neutral
- **Conductors:** 6 AWG copper wire for circuits up to 150 feet
- **Outlet:** Use a high quality, industrial grade outlet
- **Ground Pin Orientation:** Top position of outlet
- **Ventilation:** Not required




### USING THE MOBILE CONNECTOR

Attach adapter to Mobile Connector, plug into outlet and then into vehicle to begin charging. The NEMA 14-50 adapter will allow a Tesla to draw up to 32 amps (7.6 kW at 240 volts). Recharge speeds will vary between different models.

#### MILES OF RANGE PER HOUR OF CHARGE

MODEL S	MODEL S	MODEL X
80	25	20

## INSTALL LOCATIONS



- 1. CHARGE PORT
- 2. RECOMMENDED INSTALLATION AREA

## ADDITIONAL SUPPORT

EMAIL  
[CHARGINGINSTALLATION@TESLA.COM](mailto:CHARGINGINSTALLATION@TESLA.COM)

PHONE  
800.688.6133 (M-F 8:30 AM - 5:00 PM PST)

24/7 TECH SUPPORT  
877.796.3752

WEB  
[TESLA.COM/SUPPORT](https://tesla.com/support)

ONLINE STORE  
[SHOP.TESLA.COM](https://shop.tesla.com)






Radia Neo-round Sliding Shower Door 40 x 40 x 71 1/2 in. 6 mm

Model number: 137445

Dimensions: 40-40" x 71 1/2" Installation: Corner Door type: Slider



Standard Features:

- 6 mm tempered glass with Lotus glass protection
- Magnetic and PVC extrusion for a better watertight closure
- Easy to detach the bottom wheels to clean the track (Clip and Push)
- Panels are pre-assembled with hardware and side jambs
- 3/4 in. of out of plumb adjustment for those not so perfect walls

Product characteristics:


- Hardware Pre-installed
- Lotus Easy Clean Glass Protection
- Available in Multiple Finishes

Warranty:

10 Years

Certifications

MAAX products adhere to one or more of the following certifications:



Frame Finish(es):

 Chrome (084)

 Brushed Nickel (305)

Glass Pattern(s):

Clear (900)

 Mistelite (981)

Recommended products (Visit our website for a complete list of our recommended products)

No	Description
107224	Denso 42 in. Wall Kit - Modern Subway
107228	Denso 42 in. Wall Kit - Traditional Subway
102998	Freestyle 40 Neo-Round (1-Piece)




Radia Neo-round Sliding Shower Door 40 x 40 x 71 1/2 in. 6 mm

Model number: 137445

Dimensions: 40-40" x 71 1/2" Installation: Corner Door type: Slider

STANDARD



Code Código	Description Descripción	H	M	L	P Adjustable	R	Door opening Ouverture de la porte Apertura de la puerta	Wall adjustment Ajustement du mur Ajuste de la pared
137443	RADIA N-R 32" X 32" X 71.5"	71 1/2"	37 7/8"	29 7/8"	14 7/8" - 15 5/8"	14 9/16"	17 1/2"	3/4"
137444	RADIA N-R 36" X 36" X 71.5"	71 1/2"	39 5/8"	34 1/8"	13" - 13 3/4"	20 5/8"	20 1/2"	3/4"
137449	RADIA N-R 38" X 38" X 71.5"	71 1/2"	42 3/8"	36 1/8"	15" - 15 3/4"	20 5/8"	21 1/4"	3/4"
137445	RADIA N-R 40" X 40" X 71.5"	71 1/2"	44 5/8"	37 5/8"	16 1/2" - 17 1/4"	20 11/16"	22 5/8"	3/4"

All dimensions are approximate. Structure measurements must be verified against the unit to ensure proper fit.  
Toutes ces dimensions sont approximatives. Afin d'assurer une installation parfaite, les dimensions de la structure doivent être vérifiées à partir de l'unité.  
Todas las dimensiones son aproximadas. Las medidas de la estructura deben ser verificadas contra la unidad para asegurar el ajuste apropiado.

Dimensions:

40-40 x 71 1/2 in.  
(1016-1016 x 1816 mm)

Glass Thickness:

1/4 in. (6 mm)

Weight:

112 lbs (50.79 kg)

Frame type:

Semi-frameless

Opening:

Central

Door adjustment:

1 in.

Minimum access:

23 1/8 (587 mm)

Maximum access:

23 1/8 (587 mm)

Project: \_\_\_\_\_

Contractor: \_\_\_\_\_

Representative: \_\_\_\_\_

Date: \_\_\_\_\_

Tel: \_\_\_\_\_

Notes: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

