


Product Specification Sheet



B1615 Stainless Steel Single Bowl 16 Gauge



Colour Finish
Stainless Steel

Model No.
B1615

- Description
- Double Bowl Stainless Steel Sink 16 Gauge
 - Outside dimensions: 15 3/8" x 18 5/16" x 9"
 - Minimum Cabinet Size: 20"
 - Stainless Steel Single Bowl Sink
 - 16 Gauge Type 304 Stainless Steel
 - Stone Guard undercoating over rubber pad
 - 3 1/2" drain opening
 - Supplied with installation clip, template and strainer
 - CUPC certified

Available accessories

- BG1615 - Stainless Steel Grid
- Colander Strainer - Stainless Steel
- Drying Rack



MAIN LOCATION

BRISTOL SINKS
56 Firestone Blvd
London, Ontario
N5W 6E6

WESTERN LOCATION

BRISTOL SINKS
964 72nd Avenue NE
Calgary, Alberta
T2E 8V9


CONTACT

Tel: 1(800) 930-0214
Fax: 1(866) 310-7580
Email: sales@bristolsinks.com



Product Specification Sheet

B1608 Undermount Sink w/ 20mil Radius Corners



Colour Finish
Stainless Steel

Model No.
B1608

- Description
- Double Bowl Undermount Sink with 20mil radius corners
 - Outside dimensions: 31" x 18" x 9"
 - Minimum Cabinet Size: 33"
 - Stainless Steel Double Bowl Sink
 - 16 Gauge Type 304 Stainless Steel
 - Stone Guard undercoating over rubber pad
 - 3 1/2" drain opening
 - Supplied with installation clip, template and strainer
 - cUPC certified

Available accessories

- BG1608LG - Stainless Steel Grid Large
- BG1608SM - Stainless Steel Grid Small
- Colander Strainer - Stainless Steel
- Drying Rack



MAIN LOCATION


BRISTOL SINKS
56 Firestone Blvd
London, Ontario
N5W 6E6

WESTERN LOCATION

BRISTOL SINKS
764 72nd Avenue NE
Calgary, Alberta
T2E 8V9

CONTACT

Tel: 1(800) 930-0214
Fax: 1(866) 310-7580
Email: sales@bristolsinks.com





My Store: **Nepean** | **Open** • Closes 9 p.m. ▾

Rental Credit Services For the Pro
Order Status Customer Support
Gift Cards Français

Account / Sign In ▾ | Cart

- Shop by Department ▾
- Shop by Room
- Ideas & How-to
- Home Services
- Warehouse Value & Specials
- Weekly Flyer

Maintaining clean, safe stores is one of our top priorities. [Learn More](#)



GE Profile 30-inch W Gas Cooktop with 5 Burners with Rapid Burner Technology in Stainless Steel

Model # PGP9030SLSS | Store SKU # 1001090082

★★★★★ (167)

[Write a Review](#)

[Q&A \(12\)](#)

\$1,595.00 / each

Delivery Charges Apply

Appliance Delivery

Enter your postal code for availability and earliest delivery date:

[Submit](#)

[Add To Cart](#)

Price and availability may vary by store, and between online and in-store. [Click here for details.](#)



Customers Also Viewed



GE 30-inch W Gas Cooktop with 5 Burners
Including Power Burners in Stainless Steel

★★★★★ (578)
\$1,145.00 / each

[View Details](#)

Café 30-inch Gas Cooktop in Stainless
Steel with 5 Burners including 20,000 BTU
Triple Burner

★★★★★ (191)
\$2,095.00 / each

[View Details](#)



Overview

Model # PGP9030SLSS Store SKU # 1001090082

Create a feast with this GE 30-inch gas cooktop. Bring foods to a boil quickly via the unit's 18,000 BTU tri-ring burner and use the 5,000 BTU simmer burner to keep dishes hot until you're ready to eat. Heavy-duty cast iron grates, which sit alongside each other on this GE 30-inch gas cooktop, make it easy to move pans around.

- 18,000 BTU tri-ring burner - 3-in-1 burner is designed for accelerated boiling and gentle simmering
- Control lock capability - protects against unintended activation
- Sealed cooktop burners - contains spills and make cleaning quick and easy
- Heavy-duty, dishwasher safe grates - easily and safely clean grates in the dishwasher
- Optional extra-large, integrated cooktop griddle - eliminate the need for extra cookware and enjoy an optional built-in cooking surface for pancakes, grilled cheeses and other favorites
- 30" cooktop with 5 burners - Enjoy ultimate cooktop flexibility and more cooking space with 5 sealed burners
- MAX burner system - delivers the same maximum BTU power to propane and natural gas cooktops
- LP conversion kit included
- Heavy-cast, edge-to-edge grates - Durable cast iron offers lasting performance and allows easy movement of pans between burners
- White LED backlit heavy-duty knobs - Durable knobs are back-lit with white LED lighting that lend a sleek appearance and let you know if burners are on
- Precise Simmer burner Delicate foods don't burn with low, even heat

Read more about [Delivery & Installation](#) | Download the [Appliance Delivery Checklist](#)

Specifications

Dimensions

Assembled Depth (in inches)	21	Assembled Height (in inches)	5.5
Assembled Weight (in lbs)	44	Assembled Width (in inches)	30
Packaged Depth (in inches)	35	Packaged Height (in inches)	11
Packaged Weight (In lbs)	50	Packaged Width (in inches)	26

Details

JTS5000DN/BN/EN/FN/SN

GE® 30" Built-In Single Electric Convection Wall Oven

DIMENSIONS AND INSTALLATION INFORMATION

NOTE: Single wall ovens are NOT approved for stacking above or below another single wall oven.

NOTE: Wall coverings, countertops and cabinets surrounding the wall oven must be able to withstand a temperature of up to 200°F (94°C).

NOTE: If the cabinet in which the wall oven is installed does not have a solid bottom, two braces or runners must be installed to support the weight of the oven. The runners and braces must support up to 220 lbs (99 kg).

NOTE: Door handle protrudes 3" from door face. Cabinets and drawers on adjacent 45° and 90° walls should be placed to avoid interference with the handle.


ATTENTION INSTALLER: Electric wall ovens are NOT approved for installation with a plug and receptacle. They must be hard wired into an approved junction box.

IMPORTANT: Before installing, consult installation instructions packed with product for current dimensional data.

KW RATING	
240V	3.6
208V	2.7
BREAKER SIZE	
240V	20 Amps
208V	20 Amps




For answers to your GE Profile® Series or GE Appliances product questions, visit our website at geappliances.com or call GE Answer Center® Service, 800.626.2000.



Dimension and installation information are shown in inches.

JTS5000	
Cabinet	30"
A - Overlap of oven at top of cutout	1"
B - Overlap of oven other side of edge of cutout	3/4"
C - Overlap of oven at bottom of cutout	1-1/4"
Oven	
D - Install depth	23-1/2"
E - Overall height with trim	28-5/8"
F - Overall width	29-3/4"



Specification Revised 1/19

JTS5000DN/BN/EN/FN/SN

GE® 30" Built-In Single Electric Convection Wall Oven

FEATURES AND BENEFITS

- True European Convection – Achieve faster and more even results with a convection fan and third heating element that circulates air for more efficient cooking
- Hidden backlit LCD control – Easily read and operate a bright display that shows the clock when not in use and illuminates controls when you're ready to cook
- Never scrub, heavy-duty smooth glide racks – Easily remove even the heaviest dishes with a roller rack that's engineered to glide seamlessly out of the oven
- Precision temperature probe – Internal probe allows monitoring of roasts and meats to assure they are thoroughly and accurately cooked without opening the oven door
- Never scrub, heavy-duty racks – Say goodbye to scrubbing thanks to never scrub heavy-duty racks, engineered to withstand a self clean cycle
- Self-Clean with optional Steam Clean – Cleaning the oven interior has never been easier, with two cleaning options to fit your lifestyle
- Anywhere control with remote notifications – Save time by conveniently preheating and monitoring your oven from anywhere using the GE Appliances Kitchen app
- Scan-to-cook – Prepare your favorite packaged foods to perfection simply by scanning the barcode on the package with your smartphone and letting your oven adjust settings automatically
- 10-pass hidden bake element – Even baking and quick cleanup are assured, with 10-pass element that heats a large cooking area and is hidden for an easy-to-wipe surface
- 8-pass broil element – Get full broil coverage and even browning from edge to edge


- Model JTS5000DNBB – Black
- Model JTS5000DNWW – White
- Model JTS5000ENES – Slate
- Model JTS5000FNDS – Black Slate
- Model JTS5000BNTS – Black Stainless
- Model JTS5000SNSS – Stainless Steel



FIT GUARANTEE

Replacing a similar wall oven from GE Appliances or another brand? GE wall ovens are guaranteed for an exact fit or GE Appliances will pay up to \$300 toward modifications.

Visit geappliances.com for more info





 My Store: **Nepean** | **Open** • Closes 9 p.m. 

Rental

Credit Services

For the Pro

Order Status

Customer Support

Gift Cards

Français



 Account / Sign In 

 Cart

Shop by Department 

Shop by Room

Ideas & How-to

Home Services

Warehouse Value & Specials

Weekly Flyer

Maintaining clean, safe stores is one of our top priorities. [Learn More](#)



Broan-NuTone 30-inch Under Cabinet Range Hood, 450 CFM with Ductless Option (Charcoal Filter Sold Separately) in Stainless Steel

Model # AVDN130SS | Store SKU # 1001029366

★★★★★ (48)

[Write a Review](#)

[Q&A \(4\)](#)

\$559.99 / each

Choose Your Options

Colour/Finish: **Stainless Steel**















 **Not Sold In-Store**

Qty

[Add To Cart](#)

DS



DS



Delivery options for [K2C 0C6](#)

 **STANDARD SHIPPING**

Estimated Arrival **Aug 19–28**

FREE

Price and availability may vary by store, and between online and in-store. [Click here for details.](#)





Customers Who Viewed this Item Bought







Chat

search

Search

[My Account \(https://mcappliance.com/customer/account/\)](https://mcappliance.com/customer/account/) | [Log In \(https://mcappliance.com/customer/account/login/\)](https://mcappliance.com/customer/account/login/)

[View Cart \(/checkout/cart/\)](/checkout/cart/)

[Home \(https://mcappliance.com/\)](https://mcappliance.com/) / [Brands \(https://mcappliance.com/brands.html\)](https://mcappliance.com/brands.html) / [Magic Chef \(https://mcappliance.com/brands/magic-chef.html\)](https://mcappliance.com/brands/magic-chef.html) / 5.8 cu ft Beverage Cooler

5.8 cu ft Beverage Cooler

DS


km

DS

SM



Description	Warranty	Manuals	Images
-------------	----------	---------	--------



Features:

- Easy-to-maintain stainless steel door frame with tempered, smoked glass
- Easy-touch electronic temperature control panel with digital display
- Convenient "Normal" or "Manual" temperature modes and display settings
- Wire shelves allow you to easily organize your beverages
- Sturdy stainless steel door handle complements the luxurious design
- LED stage lighting at the push of a button for interior visibility
- Versatile built-in or freestanding installation solutions
- Temperature range: 37°F to 54°F
- Capacity: up to 178 12-oz cans/ 5.8 cu. ft.

Specifications:

Brand	Magic Chef
Type	Built-In or Freestanding
Model	HMBC58ST
UPC Code	665679006175
Weight (lbs)	101.4
Capacity (cu. ft.)	5.8
Width (in)	23.4
Height (in)	34.4
Depth (in)	24.4

Where to buy:



[http://www.homedepot.com/p/Magic-Chef-Reverage-23-4-in-154-12-](http://www.homedepot.com/p/Magic-Chef-Reverage-23-4-in-154-12-oz-Can-Cooler-Stainless-Steel-HMBC58ST/300509606/)

[oz-Can-Cooler-Stainless-Steel-HMBC58ST/300509606/](http://www.homedepot.com/p/Magic-Chef-Reverage-23-4-in-154-12-oz-Can-Cooler-Stainless-Steel-HMBC58ST/300509606/)


KitchenAid®

24" Dishwasher

DETAILED PLANNING DIMENSIONS GUIDE

Applies to all model numbers starting with;
KDFE104K, KDFE204K, KDTE204K, KDTE204LPA, KDFM404K,
KDTM404K, KDPM604K, KDTM604K, KDPM704K, KDTM704K,
KDTM704LPA, KDPM804K, KDTM804K

PRODUCT DIMENSIONS



*Dishwasher can be raised 1 1/4" (3.7 cm) with feet fully extended.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.


KitchenAid

24"

Dishwasher

DETAILED PLANNING DIMENSIONS GUIDE

PRODUCT DIMENSIONS (CONTD.)



	DESCRIPTION	DIMENSIONS
A	Width of door	23½" (59.7 cm)
B*	Height to top of handle	30 ^{13⁄16} " (78.3 cm)
C	Height of adjustable toe kick	3 ^{3⁄16} " (8.4 cm) - min. 4 ^{1⁄16} " (11.8 cm) - max.
D	Width of recessed dishwasher	22 ^{5⁄8} " (57.4 cm)
E†	Depth without door	22 ^{1⁄2} " (57.5 cm)
F***	Depth with Towel Bar Handle	26 ^{1⁄4} " (68.3 cm)
	Depth with Pocket Handle	24 ^{1⁄2} " (62.6 cm)
	Depth of Panel-Ready Models	24" (61.0 cm)
G*	Height to bottom of door (min.)	3 ^{3⁄16} " (8.4 cm)
H*	Height to top of door (min.)	33 ^{3⁄16} " (84.9 cm)
I*	Height of recessed dishwasher (min.)	33 ^{3⁄8} " (85.4 cm)
J†	Depth with door fully open (min.)	50 ^{3⁄16} " (127.4 cm)
K†	Depth with toe kick (min.)	20 ^{3⁄16} " (52.9 cm)

†Insulation blanket thickness adds up to 11/16" (1.8 cm) but can crush up to 1/8" (0.3 cm).

*Dishwasher can be raised 1¼" (3.7 cm) with feet fully extended.

***For panel-ready models, dishwasher depth is 24" (61.0 cm), not including the 3/4" (1.9 cm) custom door panel.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.


Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

KitchenAid®

24" Dishwasher
DETAILED PLANNING DIMENSIONS GUIDE

OPENING/CLEARANCE DIMENSIONS

IMPORTANT: Check that all surfaces have no protrusions that would prohibit dishwasher installation.



- A. Measured from the lowest point on the underside of the countertop. May be reduced to 33 1/2" (85.1 cm) by removing the wheels and perforated area of insulation (blanket) on dishwasher.
- B. Minimum, measured from narrowest point of opening.
- NOTE:** Corner locations require a 2" (5.1 cm) minimum clearance between the side of the dishwasher door and the wall or cabinet.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.


Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

DRAIN REQUIREMENTS

- A new drain hose is supplied with your dishwasher. If drain hose is not long enough, use a new drain hose with a maximum length of 12 ft (3.7 m) that meets all current AHAM/ IAPMO test standards, is resistant to heat and detergent, and fits the 1" (2.5 cm) drain connector of the dishwasher.

NOTE: Do not connect multiple drain hoses together.

- Make sure to connect drain hose to waste tee or disposer inlet above drain trap in house plumbing and 20" (50.8 cm) minimum above the floor. It is recommended that the drain hose either be looped up and securely fastened to the underside of the counter or be connected to an air gap.
- Make sure to use an air gap if the drain hose is connected to house plumbing lower than 20" (50.8 cm) above subfloor or floor.



- If required, the air gap should be installed in accordance with the air gap installation instructions. When you are connecting the air gap, a rubber hose (not provided) will be needed to connect to the waste tee or disposer inlet.
- Use 1/2" (1.3 cm) minimum I.D. drain line fittings.

WATER SUPPLY REQUIREMENTS

- This dishwasher has a water heating feature and also requires a connection to a hot water supply line.
 - A hot water line with 20 psi to 120 psi (138 kPa to 862 kPa) water pressure can be verified by a licensed plumber.
 - 120°F (49°C) water at dishwasher.
 - 3/8" (0.95 cm) O.D. copper tubing with compression fitting or flexible braided water supply line.
- NOTE:** 1/2" (1.3 cm) minimum plastic tubing is not recommended.
- A 90° elbow with 3/4" (0.95 cm) hose connection with rubber washer.
 - Do not solder within 6" (15.2 cm) of the water inlet valve.
 - If installed in new construction, make sure the house water supply lines have been flushed prior to connecting the dishwasher to remove any debris that may exist in the supply line.

NOTE: If replacing an existing dishwasher, it is recommended to install a new water line and drain hose (supplied) with the new dishwasher.

ELECTRICAL REQUIREMENTS

⚠ WARNING



Electrical Shock Hazard

Plug into a grounded 3 prong outlet.

Do not remove ground prong.

Do not use an adapter.

Do not use an extension cord.

Failure to follow these instructions can result in death, fire, or electrical shock.

Be sure that the electrical connection and wire size are adequate and in conformance with the National Electrical Code, ANSI/NFPA 70 - latest edition, and all local codes and ordinances.

A copy of the above code standards can be obtained from:

National Fire Protection Association
1 Batterymarch Park
Quincy, MA 02169-7471

You Must Have:

- 120 V, 60 Hz, AC only, 15 A or 20 A, fused electrical supply
- Copper wire only
- A maximum of 2 field wiring supply conductors (12 AWG largest size) plus 1 grounding conductor are permitted in the terminal box.

We Recommend:

- A time-delay fuse or circuit breaker.

Circuit Requirements:

- The dishwasher may be installed on the same circuit as a garbage disposal providing that the branch circuit cannot exceed rated circuit load and must comply with all governing codes and regulations such as but not limited to National Electrical Code, ANSI/NFPA 70 - latest edition.
- No electrical connections other than the dishwasher power and ground connections can be made inside of the dishwasher terminal box.

If connecting dishwasher with a power supply cord:

- Use UL Listed power cord kit marked for use with dishwasher.
- Plug into a grounded 3 prong outlet. Outlet must meet all local codes and ordinances.



If connecting dishwasher with direct wiring:

- Use flexible, armored, or nonmetallic sheathed copper wire with grounding wire that meets the wiring requirements for your home and local codes and ordinances.
- Use a UL Listed/CSA Approved metallic strain relief.






Lave-vaisselle de 24 po

GUIDE SUR LES DIMENSIONS DE PLANIFICATION DÉTAILLÉES

Pertinent pour tous les modèles, notamment :
KDFE104K, KDFE204K, KDTE204K, KDTE204LPA, KDFM404K,
KDTM404K, KDPM604K, KDTM604K, KDPM704K, KDTM704K,
KDTM704LPA, KDPM804K, KDTM804K

DIMENSIONS DU PRODUIT




*Le lave-vaisselle peut être relevé de 1 3/16 po (3,7 cm) avec les pieds complètement déployés.

La politique de Whirlpool Corporation, c'est aussi notre engagement à travailler sans relâche à l'amélioration de nos produits; aussi nous nous réservons le droit de modifier les matériaux et spécifications sans préavis.

Les dimensions sont indiquées à des fins de planification uniquement. Pour des détails complets, voir les Instructions d'installation fournies avec le produit. Spécifications indiquées sous réserve de modifications.

KitchenAid® Lave-vaisselle de 24 po
GUIDE SUR LES DIMENSIONS DE PLANIFICATION DÉTAILLÉES

DIMENSIONS DU PRODUIT (SUITE)



	DESCRIPTION	DIMENSIONS
A	Largeur de la porte	23 ½ po (59,7 cm)
B*	Hauteur jusqu'au sommet de la poignée	30 13⁄16 po (78,3 cm)
C	Hauteur de la plinthe réglable	3 3⁄8 po (8,4 cm) - min. 4 13⁄16 po (11,8 cm) - max.
D	Largeur du lave-vaisselle encastré	22 ¾ po (57,4 cm)
E†	Profondeur sans porte	22 ¾ po (57,5 cm)
F**	Profondeur avec poignée porte-serviettes	26 7⁄8 po (68,3 cm)
	Profondeur avec poignée en creux	24 ½ po (62,6 cm)
	Profondeur des modèles avec panneaux prêts à installer	24 po (61,0 cm)
G*	Hauteur au bas de la porte (min.)	3 5⁄8 po (8,4 cm)
H*	Hauteur jusqu'au haut de la porte (min.)	33 7⁄8 po (84,9 cm)
I*	Hauteur du lave-vaisselle encastré (min.)	33 ¾ po (85,4 cm)
J†	Profondeur avec porte entièrement ouverte (min.)	50 3⁄8 po (127,4 cm)
K†	Profondeur avec plinthe (min.)	20 13⁄16 po (52,9 cm)

†L'épaisseur de la couverture isolante ajoute jusqu'à 11/16 po (1,8 cm) mais peut s'aplatir jusqu'à 1/8 po (0,3 cm).

*Le lave-vaisselle peut être relevé de 1 3/8 po (3,7 cm) avec les pieds complètement déployés.

****Pour les modèles avec panneaux prêts à installer, la profondeur du lave-vaisselle est de 24 po (61,0 cm) – sans le panneau de porte personnalisé de 3/4 po (1,9 cm).**

La politique de Whirlpool Corporation, c'est aussi notre engagement à travailler sans relâche à l'amélioration de nos produits; aussi nous nous réservons le droit de modifier les matériaux et spécifications sans préavis.


Les dimensions sont indiquées à des fins de planification uniquement.
Pour des détails complets, voir les instructions d'installation fournies
avec le produit. Spécifications indiquées sous réserve de modifications.

KitchenAid®

Lave-vaisselle de 24 po
GUIDE SUR LES DIMENSIONS DE PLANIFICATION DÉTAILLÉES

DIMENSIONS D'OUVERTURE ET DE DÉGAGEMENT

IMPORTANT : Vérifier que toutes les surfaces n'ont aucune aspérité qui empêcherait l'installation du lave-vaisselle.



- A. Mesure depuis le point le plus bas de la face inférieure du comptoir. Cette dimension peut être réduite à 33 1/4 po (85,1 cm) en retirant les roulettes du lave-vaisselle et en perforant l'isolant (la plaque d'insonorisation) de l'appareil.
- B. Dimension minimale mesurée au point le plus étroit de l'ouverture.
- REMARQUE :** Dans le cas de l'installation dans un angle, on doit pouvoir établir un dégagement de 2 po (5,1 cm) ou plus entre le côté de la porte du lave-vaisselle et le mur ou l'armoire.

La politique de Whirlpool Corporation, c'est aussi notre engagement à travailler sans relâche à l'amélioration de nos produits; aussi nous nous réservons le droit de modifier les matériaux et spécifications sans préavis.

Les dimensions sont indiquées à des fins de planification uniquement. Pour des détails complets, voir les Instructions d'installation fournies avec le produit. Spécifications indiquées sous réserve de modifications.

EXIGENCES D'ÉVACUATION

- Un tuyau d'évacuation neuf est fourni avec le lave-vaisselle. Si le tuyau d'évacuation n'est pas suffisamment long, utiliser un tuyau d'évacuation neuf d'une longueur maximale de 12 pi (3,7 m) satisfaisant à toutes les normes de test AHAM/IAPMO en vigueur, qui soit résistant à la chaleur et au détergent et qui convienne au raccord d'évacuation de 1 po (2,5 cm) du lave-vaisselle.

REMARQUE : Ne pas raccorder plusieurs tuyaux de vidange.

- Veiller à raccorder le tuyau d'évacuation à la canalisation d'égout en T ou au raccord de broyeur à déchets en amont du siphon du circuit de plomberie du domicile, et à au moins 20 po (50,8 cm) au-dessus du sol. On recommande de lover le tuyau d'évacuation et de le fixer solidement sur la face inférieure du comptoir ou de le raccorder à un dispositif de brise-siphon.
- Utiliser un dispositif de brise-siphon si le tuyau d'évacuation est raccordé au circuit de plomberie du domicile à moins de 20 po (50,8 cm) au-dessus du sous-plancher ou du plancher.



- Si nécessaire, le dispositif de brise-siphon doit être installé conformément aux instructions d'installation de ce dernier. Lors du raccordement du dispositif de brise-siphon à la canalisation d'égout en T ou au raccord de broyeur à déchets, un tuyau en caoutchouc (non fourni) sera nécessaire.
- Utiliser des raccords de canalisation d'évacuation de diamètre intérieur de 1/2 po (1,3 cm) minimum.

SPÉCIFICATIONS DE L'ALIMENTATION EN EAU

- Ce lave-vaisselle est doté d'une fonction de chauffage de l'eau et doit être raccordé à la canalisation d'alimentation en eau chaude.
- Une canalisation d'eau chaude, sous pression de 20 à 120 lb/po² (138 à 862 kPa), peut être inspectée par un plombier certifié.
- Température de 120 °F (49 °C) à l'entrée du lave-vaisselle.
- Tube de cuivre de 3/8 po (0,95 cm) de diamètre externe avec raccord de compression ou canalisation d'alimentation en eau flexible à tresse d'acier.

REMARQUE : L'emploi d'un tuyau de plastique d'un minimum de 1/2 po (1,3 cm) n'est pas recommandé.

- Raccord coudé à 90° avec raccord de tuyau de 3/4 po (0,95 cm) et rondelle de caoutchouc.
- Ne pas souder à moins de 6 po (15,2 cm) de l'électrovanne d'admission d'eau.
- S'il est installé dans une nouvelle construction, vous assurer que l'entrée d'eau de la maison a été nettoyée avant d'effectuer le branchement au lave-vaisselle pour en enlever les débris possibles.

REMARQUE : S'il remplace un lave-vaisselle existant, il est recommandé d'installer une nouvelle entrée d'eau et vider le tuyau de vidange (fourni) avec le nouveau lave-vaisselle.

SPÉCIFICATIONS ÉLECTRIQUES

⚠ AVERTISSEMENT

Risque de choc électrique

Brancher sur une prise à 3 alvéoles reliée à la terre.

Ne pas enlever la broche de liaison à la terre.

Ne pas utiliser un adaptateur.

Ne pas utiliser un câble de rallonge.

Le non-respect de ces instructions peut causer un décès, un incendie ou un choc électrique.

S'assurer que le raccordement électrique est adéquat et conforme au code national de l'électricité, ANSI/NFPA 70 – dernière édition, et à tous les codes et règlements locaux en vigueur.

Pour obtenir un exemplaire des normes des codes ci-dessus, contacter :

National Fire Protection Association
1 Batterymarch Park
Quincy, MA 02169-7471

Il vous faut :

- Alimentation de 120 V CA à 60 Hz et protégée par un fusible de 15 ou 20 A
- Conducteurs de cuivre uniquement
- Un maximum de deux conducteurs d'alimentation (calibre 12 AWG maximum) plus un conducteur de mise à la terre est autorisé dans le boîtier de connexion.

Nous recommandons :

- L'utilisation d'un fusible ou disjoncteur temporisé.

Spécifications du circuit :

- Le lave-vaisselle peut être installé sur le même circuit que le broyeur à déchets en s'assurant que ce circuit ne dépasse pas la charge nominale et qu'il respecte les normes et codes dont, mais ne se limitant pas, au code national de l'électricité, ANSI/NFPA 70 – dernière édition.
- Aucun autre raccordement électrique que ceux des conducteurs d'alimentation et de mise à la terre du lave-vaisselle ne peuvent être effectués à l'intérieur du boîtier de connexion du lave-vaisselle.

Pour le raccordement du lave-vaisselle avec un cordon d'alimentation électrique :

- Utiliser un cordon d'alimentation (homologation UL) conçu pour utilisation avec un lave-vaisselle.
- Brancher l'appareil sur une prise à 3 alvéoles reliée à la terre. La prise doit être conforme à tous les codes et règlements locaux.

Pour le raccordement direct du lave-vaisselle :

- Utiliser des conducteurs de cuivre gainés non métalliques ou blindés souples avec conducteur de liaison à la terre qui satisfassent aux exigences de l'installation électrique du domicile, et qui soient conformes aux prescriptions des codes et règlements locaux.
- Utiliser un serre-câbles homologué UL ou CSA.






Lavavajillas de 24"

GUÍA DE DIMENSIONES DE PLANIFICACIÓN EN DETALLE

Aplicable para todos los números de modelos que comiencen con:
KDFE104K, KDFE204K, KDTE204K, KDTE204LPA, KDFM404K,
KDTM404K, KDPM604K, KDTM604K, KDPM704K, KDTM704K,
KDTM704LPA, KDPM804K, KDTM804K

DIMENSIONES DEL PRODUCTO



*La lavavajillas se puede elevar 1 1/8" (3,7 cm) con las patas completamente extendidas.


Debido a que la política de Whirlpool Corporation incluye un compromiso continuo para mejorar nuestros productos, nos reservamos el derecho de cambiar materiales y especificaciones sin previo aviso.

Las dimensiones son solo para fines de planificación. Para obtener los detalles completos, vea las Instrucciones de instalación incluidas con el producto. Las especificaciones están sujetas a cambio sin previo aviso.

KitchenAid®

Lavavajillas de 24"
GUÍA DE DIMENSIONES DE PLANIFICACIÓN EN DETALLE

DIMENSIONES DEL PRODUCTO (CONT.)



	DESCRIPCIÓN	DIMENSIONES
A	Ancho de la puerta	23½" (59,7 cm)
B*	Altura de la parte superior de la manija	30⅜" (78,3 cm)
C	Altura del zócalo ajustable	3⅝" (8,4 cm) - mín. 4⅞" (11,8 cm) - máx.
D	Ancho de la lavavajillas empotrada	22¾" (57,4 cm)
E†	Profundidad sin puerta	22¾" (57,5 cm)
F**	Profundidad con manija tipo toallero	26¾" (68,3 cm)
	Profundidad con manija empotrada	24½" (62,6 cm)
	Profundidad de los modelos adaptados a la instalación de panel	24" (61 cm)
G*	Altura hasta la parte inferior de la puerta (mín.)	3⅝" (8,4 cm)
H*	Altura hasta la parte superior de la puerta (mín.)	33⅞" (84,9 cm)
I*	Altura de la lavavajillas empotrada (mín.)	33⅝" (85,4 cm)
J†	Profundidad con la puerta totalmente abierta (mín.)	50⅝" (127,4 cm)
K†	Profundidad con zócalo (mín.)	20⅜" (52,9 cm)

†El espesor de la manta aislante agrega hasta 11/16" (1,8 cm) pero se puede aplastar hasta 1/8" (0,3 cm).

*La lavavajillas se puede elevar 1⅞" (3,7 cm) con las patas completamente extendidas.

**Para los modelos adaptables para la instalación de paneles, la profundidad de la lavavajillas es de 24" (61,0 cm) sin incluir el panel de la puerta a la medida de 3/4" (1,9 cm).

Debido a que la política de Whirlpool Corporation incluye un compromiso continuo para mejorar nuestros productos, nos reservamos el derecho de cambiar materiales y especificaciones sin previo aviso.


Las dimensiones son solo para fines de planificación. Para obtener los detalles completos, vea las Instrucciones de instalación incluidas con el producto. Las especificaciones están sujetas a cambio sin previo aviso.

KitchenAid®

Lavavajillas de 24"
GUÍA DE DIMENSIONES DE PLANIFICACIÓN EN DETALLE

MEDIDAS DE ABERTURA/ESPACIO

IMPORTANTE: Revise todas las superficies para asegurarse de que no hayan protuberancias que pudieran impedir la instalación de la lavavajillas.



- A. Medido desde el punto más bajo del lado inferior del mostrador. Se puede reducir a 33 1/2" (85,1 cm) retirando las ruedas y el área perforada del aislante (manta) en la lavavajillas.
- B. Mínimo, medido desde el punto más angosto de la abertura.
- NOTA:** Las ubicaciones en esquinas requieren de un espacio libre mínimo de 2" (5,1 cm) entre el lado de la puerta de la lavavajillas y la pared o el gabinete.

Debido a que la política de Whirlpool Corporation incluye un compromiso continuo para mejorar nuestros productos, nos reservamos el derecho de cambiar materiales y especificaciones sin previo aviso.

Las dimensiones son solo para fines de planificación. Para obtener los detalles completos, vea las Instrucciones de instalación incluidas con el producto. Las especificaciones están sujetas a cambio sin previo aviso.

REQUISITOS DE DESAGÜE

- Se provee una manguera nueva de desagüe con su lavavajillas. Si la manguera de desagüe no es lo suficientemente larga, utilice una manguera de desagüe nueva con una longitud máxima de 12 pies (3,7 m) que cumpla con todos los estándares de comprobación actuales de AHAM/IAPMO, que sea resistente al calor y al detergente, y que encaje en el conector de desagüe de 1" (2,5 mm) de la lavavajillas.

NOTA: No conecte múltiples mangueras de desagüe juntas.

- Asegúrese de conectar la manguera de desagüe al colector de residuos en "T" o a la entrada del colector de residuos sobre el sifón de desagüe en la plomería de la casa, y a un mínimo de 20" (50,8 cm) por encima del piso. Se recomienda que la manguera de desagüe se enrolle y fije con firmeza a la parte inferior del mostrador o que se conecte a una purga de aire.
- Asegúrese de utilizar una purga de aire si la manguera de desagüe está conectada a la plomería de la casa a una altura menor de 20" (50,8 cm) sobre el contrapiso o el piso.



- Si se requiere, la purga de aire se debe instalar siguiendo las instrucciones de instalación de la misma. Al conectar la purga de aire, se requiere una manguera de goma (no proporcionada) para conectarla al tubo de residuos en "T" o la entrada del colector de residuos.
- Use accesorios para líneas de desagüe con un diámetro interior de 1,3 cm (1/2") mínimo.

REQUISITOS DE SUMINISTRO DE AGUA

- Esta lavavajilla tiene una función de calentamiento de agua y también requiere una conexión a una línea de suministro de agua caliente.
- Una tubería de agua caliente con presión de agua de 20 psi a 120 psi (de 138 kPa a 862 kPa), que pueda ser verificada por un plomero autorizado.
- Agua a 120 °F (49 °C) en la lavavajillas
- Tubería de cobre con un diámetro externo de 3/8" (0,95 cm) con racor con conexión de compresión o tubería de suministro de agua trenzada flexible.

NOTA: No se recomienda usar tubería de plástico de 1/2" (1,3 cm) mínimo.

- Un codo de 90° con una conexión de manguera de 3/4" (0,95 cm) con una arandela de goma.
- No suelde a una distancia menor de 6" (15,2 cm) de la válvula de entrada del agua.
- Si la instalación se realiza en una construcción nueva, asegúrese de enjuagar las tuberías de suministro de agua domésticas antes de conectar la lavavajillas para eliminar cualquier residuo presente en la tubería de suministro.

NOTA: Si se va a reemplazar una lavavajillas existente, se recomienda instalar una nueva tubería de agua y manguera de desagüe (suministradas) con la nueva lavavajillas.

W11409323A

®/™ ©2020 KitchenAid. All rights reserved.
Tous droits réservés.
Todos los derechos reservados.

REQUISITOS ELÉCTRICOS

⚠ ADVERTENCIA

Peligro de Choque Eléctrico

Conecte a un contacto de pared de conexión a tierra de 3 terminales.

No quite la terminal de conexión a tierra.

No use un adaptador.

No use un cable eléctrico de extensión.

No seguir estas instrucciones puede ocasionar la muerte, incendio o choque eléctrico.

Asegúrese de que la conexión eléctrica y el tamaño del cable sean adecuados y cumplan con el Código nacional eléctrico, ANSI/NFPA 70, su edición más reciente, y con todos los códigos y las ordenanzas locales.

Puede obtener una copia de las normas de los códigos antes indicados en:

National Fire Protection Association
1 Batterymarch Park
Quincy, MA 02169-7471

Usted debe tener:

- Un suministro eléctrico de 120 V, 60 Hz., CA solamente, con fusibles de 15 A o 20 A
- Solamente cable de cobre
- Se permite un máximo de 2 conductores de suministro de cable en sitio (tamaño máximo: 12 AWG) y 1 conductor de conexión a tierra en la caja de terminales.

Se recomienda:

- Un fusible retardador o un disyuntor.

Requisitos del circuito:

- La lavavajillas se puede instalar en el mismo circuito que el triturador de basura siempre y cuando el circuito derivado no exceda la carga calculada del circuito y cumpla con todos los códigos y regulaciones vigentes, como, por ejemplo, la edición más reciente del Código nacional eléctrico, ANSI/NFPA 70.
- No se puede realizar ninguna otra conexión eléctrica dentro de la caja de terminales de la lavavajillas más que la conexión a tierra y la de suministro eléctrico de esta.

Si va a conectar la lavavajillas con un cable de suministro eléctrico:

- Use un cable de suministro de energía con certificación UL para uso con lavavajillas.
- Conecte el producto a un tomacorriente de 3 terminales con conexión a tierra. El tomacorriente debe cumplir con todos los códigos y ordenanzas locales.



Si va a conectar la lavavajillas con cableado directo:

- Utilice un cable de cobre flexible, blindado o con una funda no metálica con un cable de conexión a tierra que cumpla con los requisitos de cableado para su hogar y con los códigos y ordenanzas locales.
- Utilice un protector de cables con certificación UL/homologación CSA.





MOBILE

KITCHEN

LAUNDRY

AIR SOLUTIONS

TV/AUDIO/VIDEO

COMPUTER PRODUCTS

[SUPPORT HOME](#)

ome / KITCHEN / Refrigerators / LRMV53006S



LRIIVS30065

30 cu.ft. InstaView ThinQ® Door-in-Door® Refrigerator with Craft Ice™

★★★★★ 4.4 (152) [Write a review](#)

- InstaView™ Door-in-Door® with adjustable bin
- Slim SpacePlus® Ice System
- Inverter Linear Compressor
- Door Cooling+
- Smudge Resistant Stainless Steel
- LG ThinQ® App Compatible



SMUDGE RESISTANT STAINLESS STEEL

\$4799.99

WHERE TO BUY

ADD TO COMPARE

OVERVIEW

SPECS

REVIEWS

SUPPORT

WHERE TO BUY

DS
LM

SUMMARY

CAPACITY		MEASUREMENTS (WXHxD)	
29.50 cu.ft.		35 3/4" x 70 1/4" x 39 1/8"	
INSTAVIEW™ DOOR-IN-DOOR®		THINQ®	
Yes		Yes	

SUMMARY

Series	LG
Type	French Door
Door Type	4-Door
InstaView™ Door-in-Door®	Yes
Total Capacity (cu.ft.)	29.50
Colour	Smudge Resistant Stainless Steel

CAPACITY

Refrigerator (cu.ft.)	17.00
Full-Convert™ Drawer	3.60
Freezer (cu.ft.)	8.90
Total Capacity (cu.ft.)	29.50
Energy Consumption (kWh/Year)	799
ENERGY STAR® Qualified	Yes

WATER & ICE SYSTEM

Ice & Water Dispenser	Yes
Dispenser Type	Integrated Ice & Water Dispenser

Measured Fill	Yes
Daily Ice Production (lbs)	3.5 lbs
IcePlus™ Production (lbs)	3.8 lbs
Craft Ice™ Daily Ice Production	0.4 lbs
Ice Storage Capacity (lbs)	3.0 + 3.3 lbs
Ice System	Slim SpacePlus®
Dual Ice with Craft Ice™	Yes
Dispenser Light	Yes
Water Filter	LT1000P

COOLING

Linear Compressor	Yes
Smart Cooling Plus™ System	Yes
Door Cooling+	Yes
Multi-Air Flow™ System	Yes
Temperature Sensors	9
Fresh Air Filter	Yes
Evaporator	2

CONVENIENCE

Display Type	Smooth Touch Control/White LED
Temperature Controls	Electronic/Digital
Door Alarm	Yes
Child Lock	Yes
Auto Closing Door Hinge	Yes
Sabbath Mode	Yes
LoDecibel™ Quiet Operation	Yes

REFRIGERATOR

No. of Shelves	4 Split (3 Fixed+1 Folding)
Folding Shelf	1
Cantilevered Shelves	Yes
Shelf Construction	Spill Protector™ Tempered Glass
Crisper Bins	2 Humidity Crisper
CoolGuard™	Yes
Refrigerator Light	Micro Surface LED

FULL-CONVERT™ DRAWER

Dividers	Yes
Temperature Range (°C)	-23, -1, 1, 3, 5
Handle Type	SmartPull™

REFRIGERATOR DOOR

InstaView™ Door-in-Door®	Yes
Adjustable Door-in-Door® Bin	Yes
No. of Bins	6
Door Bin Construction	1 Piece (Clear)

FREEZER

Door Type	Pull Drawer
Drawers	2-Tier Organization
DuraBase™ Solid Drawer Base	Yes
Drawer Divider	Yes
Ice Bin / In-Door Ice	Icemaker & Ice bin in the freezer
Freezer Light	Premium LED
Freezer Handle	SmartPull™ Handle

THINQ® SMART FEATURES

Wi-Fi Enabled	Yes
ThinQ® Technology with Proactive Customer Care	Yes
Works with	Google Assistant, Amazon Alexa
Smart Diagnosis™	Yes

MATERIALS AND FINISHES

Contour Door	Yes
Hidden Hinges	Yes
Surface	Smooth
Fingerprint & Smudge Resistant Exterior	Yes
Handles	Matching Commercial Handles
All Available Colours	Smudge Resistant Stainless Steel

DIMENSIONS/CLEARANCES/WEIGHTS

Depth with Handles	39 1/8"
Depth without Handles	36 5/8"
Depth without Door	31 3/4"
Depth (Total with Door Open)	51"
Height to Top of Case	68 7/8"
Height to Top of Door Hinge	70 1/4"
Width	35 3/4"
Width (Door Open 90° with Handle)	45"
Width (Door Open 90° without Handle)	40"
Door Edge Clearance with Handle	4 5/8"
Door Edge Clearance without Handle	2 1/4"

Installation Clearance	Sides 1/8", Top 1", Back 2"
Weight (Unit/Carton)	404 lbs./437 lbs.
Carton Dimensions (WxHxD)	38" x 73" x 33"

LIMITED WARRANTY

Parts & Labour	1 Year
Sealed System	7 Years
Linear Compressor (Parts Only)	6-10 Years

BRAND

LG Brand	Yes
----------	-----

WIDTH

36"	Yes
-----	-----

DEPTH

Standard Depth	Yes
----------------	-----

UPC CODE

LRMVS3006S (Smudge Resistant Stainless Steel)	048231806145
---	--------------