



APPLIANCE CHECKLIST

It may seem early to be thinking about appliances, but they are an important part of your kitchen design and may require upgrades to your HVAC, plumbing and electrical plans. It’s important that we are provided with your appliance information during the structural and foundation part of the Design Process, so that these upgrades can be included on your invoice, if required.

| ITEM | BRAND | MODEL NUMBER |
|--|---------|--------------|
| FRIDGE | LG | LRFCC23D6S |
| DISHWASHER | LG | LDPS6762S |
| RANGE | LG | LSEL6335F |
| Type: Gas <input type="checkbox"/> Electric <input checked="" type="checkbox"/> Induction <input type="checkbox"/> Waterline Required <input type="checkbox"/> Electrical: 15 Amp <input type="checkbox"/> 40 Amp <input type="checkbox"/> 50 Amp <input checked="" type="checkbox"/> | | |
| WALL OVEN | NA | |
| Type: Gas <input type="checkbox"/> Electric <input type="checkbox"/> Waterline Required <input type="checkbox"/> Electrical: 30 Amp <input type="checkbox"/> 40 Amp <input type="checkbox"/> | | |
| WARMING DRAWER | NA | |
| Electrical: 15 Amp <input type="checkbox"/> Other: Specify | | |
| COOKTOP | NA | |
| Type: Gas <input type="checkbox"/> Electric <input type="checkbox"/> Induction <input type="checkbox"/> Electrical: 15 Amp <input type="checkbox"/> 40 Amp <input type="checkbox"/> 50 Amp <input type="checkbox"/> | | |
| BUILT IN MICROWAVE | NA | |
| Electrical: 15 Amp <input type="checkbox"/> 30Amp <input type="checkbox"/> 240 Volt <input type="checkbox"/> 120 Volt <input type="checkbox"/> | | |
| MICROWAVE TRIM KIT | NA | |
| OTR MICROWAVE | NA | |
| WASHING MACHINE | GE | GFW650SPNSN |
| DRYER | GE | GFD65ESMNSN |
| Type: Gas <input type="checkbox"/> Electric <input checked="" type="checkbox"/> Stacked <input type="checkbox"/> | | |
| OTHER: HOODFAN | CYCLONE | SCB31930 |
| OTHER: | | |
| OTHER: | | |

Hood Fans must be purchased through Phoenix Homes, and will require an upgrade to a make up air system for any hood fans above 300CFM. Standard hood fan vent pipe is 6”.

A make up air system is a required upgraded for all gas stoves/cooktops.

Any changes from the standard kitchen plan and/or standard electrical, plumbing and electrical specifications/plans may be subject to additional fees.

Community: WHITETAIL RIDGE (4)

Lot #: 141

Purchaser Signature:

DocuSigned by:
Cathy Dyotte
37567FC3CF9E4BA...

Purchaser Signature:

DocuSigned by:
Don Dyotte
036448CCDC164CD...

HOME APPLIANCES

LG DISHWASHERS

LDPS6762_

Top Control Wi-Fi Enabled Dishwasher
with QuadWash™ Pro

QuadWash® Pro

Dynamic Dry® Enhanced with TrueSteam®

Remote Start

Height Adjustable 3rd Rack

EasyRack® Plus

ThinQ® Technology with ThinQ Care

AVAILABLE COLORS



PRINTPROOF™ STAINLESS STEEL



PRINTPROOF™ BLACK STAINLESS STEEL

Proactive Smart Alerts to Keep
Your Appliances Running Smoothly

- Preventative Alerts help you stay a step ahead of potential issues to find proactive solutions before problems arise.
- Avoid preventable repairs and service calls with real-time diagnostics for a hassle-free experience.
- Integrated within LG's ThinQ app—a smart home hub for managing your smart devices and appliances.

ThinQ Care

CAPACITY

| | |
|------------------------------|-------|
| Total Place Settings | 15 |
| Upper Rack Dish Height Limit | 7.1" |
| Lower Rack Dish Height Limit | 12.5" |

RACKS AND BASKETS

| | |
|---------------------------------------|---|
| Cutlery Baskets | Yes |
| Cup Rack | Yes |
| Stemware Holder | Yes |
| Fold Down Times | Yes (Half Fold on Upper & Half (Smart), Half (Normal) on Lower) |
| BPA-Free Nylon Coated Racks and Tines | Yes |
| Rack Handle | Yes (Upper & Lower) |
| EasyRack™ Plus System | Yes |
| Height Adjustable 3rd Rack | Yes (Easy One Touch (3 Level)) |

STYLE AND DESIGN

| | |
|--------------------------|--|
| Control Panel Location | Top Control |
| Electronic Controls | Fully Integrated Control Panel |
| Time Remaining Indicator | LED |
| Tub Material | NeveRust™ Stainless Steel |
| Handle | Pocket Handle |
| All Available Colors | PrintProof™ Stainless Steel, PrintProof™ Black Stainless Steel |
| Fingerprint Resistant | Yes |

FEATURES

| | |
|-----------------------------------|---|
| TrueSteam® | Yes |
| QuadWash® Pro | Yes |
| SenseClean™ Wash System | Yes |
| Vario Wash | Yes |
| Number of Spray Arms | 3 (Top, Upper, Lower) |
| Detergent and Rinse-Aid Dispenser | Yes |
| Number of Wash Cycles | 10 (Auto, Heavy, Delicate, Refresh, Normal, Turbo, Download Cycle, Machine Clean, Rinse, Express) |
| Number of Options | 8 (Flex Zone, Steam, High Temp, Extra Dry, Delay Start, Control Lock, Night Dry, Remote Start) |
| Drying System | Dynamic Dry |
| End of Cycle Indicator | Yes (Beeper + END indication on display) |
| Hidden Water Heater | Yes |
| Safety Float Switch (Leaks) | Yes |
| Soil (Turbidity) Sensor | Yes |
| DirectDrive Motor™ | Yes |
| LoDecibel™ Quiet Operation | 44 dBA |
| Tub Insulation | Yes (Damping Sheet, Sound Absorbing Material (felt), Base) |

WTR4 LOT 141



| | |
|---------------------------------------|-----|
| BPA-Free Nylon Coated Racks and Tines | Yes |
| Anti-Bacterial Treatment (Drain hose) | Yes |
| Balanced Door | Yes |

ThinQ® SMART FEATURES

| | |
|-----------------|-----|
| Wi-Fi Enabled | Yes |
| ThinQ Care | Yes |
| SmartDiagnosis™ | Yes |

POWER RATINGS

| | |
|------------------------|--------------|
| ENERGY STAR® Qualified | Yes |
| CEE Tier | 1 |
| Energy Use (kWh/Year) | 238 kWh/Year |
| Water Factor (WF) | 2.9 |

DIMENSIONS / CLEARANCES / WEIGHT

| | |
|---|---|
| Product Dimensions (in) (W x H x D) | 23 3/4" x 24 5/8" x 33 5/8" |
| Min Height (Unit Dimensions) | 33 5/8" |
| Min Height (Unit Dimensions) | 36" |
| Product Weight (lbs) | 87.3 |
| Depth with Door Closed with Handle (in) | 24 5/8" |
| Depth with Door Open (in) | 49 1/4" |
| Water Connection (in) | 90° 3/8" Compression Installed at Factory |
| Drain Hose End Sizes (in) | 5/8" or 3/4" or 1" |
| Carton Dimensions (in) (W x H x D) | 28 1/32" x 29 5/8" x 34 7/8" |
| Shipping Weight with Carton (lbs) | 99.43 |


LIMITED WARRANTY

| | |
|-----------------------------------|----------|
| Labor | 1 Year |
| Parts | 1 Year |
| Control Board and Rack Parts | 5 Years |
| Direct Drive Motor | 10 Years |
| Stainless Steel Door Liner or Tub | Lifetime |

UPC CODES

| | |
|---|-------------|
| LDPS6762S (PrintProof™ Stainless Steel) | 48231342667 |
| LDPS6762D (PrintProof™ Black Stainless Steel) | 48231344197 |

WTR4 LOT 141




Installation Instructions



UNPACKING YOUR DRYER

Tilt the dryer sideways and remove the foam shipping pads by pulling at the sides and breaking them away from the dryer legs. Be sure to remove all of the foam pieces around the legs.

Remove the bag containing the literature.



DRYER DIMENSIONS



***NOTE:**
With leveling legs retracted: 39-3/4 (101 cm).
With leveling legs fully extended: 40-5/8 (103.1 cm).
With Optional Pedestal: 55-1/2" (141 cm) Min. - 56-5/8" (143.8 cm) Max.
Stacked: 79-1/8" (201 cm).

STEAM WATER HOSES (for steam dryer models only):

GE Appliances strongly recommends the use of factory specified parts. These hoses are manufactured and tested to meet GE Appliances specifications.

GE Appliances strongly recommends the use of new water supply hoses. Hoses degrade over time and need to be replaced every 5 years to reduce the risk of hose failures and water damage.

Parts and Accessories

Order on-line at GEApplianceparts.com, 24 hours a day or by phone at 877.959.8688 during normal business hours.

| Part Number | Accessory |
|---------------|--|
| WE25X20060 | Complete Kit (hoses, Y-adapter, washers) or |
| WE49X25794 | Kit (Short hose, Y-adapter, washers) and |
| WE1M847 | Long Hose |
| OR SEPARATELY | |
| WE1M847 | Long Hose and |
| WE1M848 | Short Hose |


ACCESSORIES:


Order on-line at GEApplianceparts.com, 24 hours a day or by phone at 877.959.8688 during normal business hours.

| Part Number | Accessory |
|-------------|--------------------------------------|
| GFP1528SNWW | White Pedestal |
| GFP1528PNSN | Satin Nickel Pedestal |
| GFP1528PNRS | Royal Sapphire Pedestal |
| GFP1528PNDG | Diamond Gray Pedestal |
| GFA28KITN | Stacking Kit for Dryer over Washer |
| PM08X10085 | Flexible Metal Dryer Transition Duct |
| WE02X29449 | Clothes Dryer Drying Rack |

Installation Instructions

REQUIREMENTS FOR ALCOVE OR CLOSET INSTALLATION

**WARNING**

 - **Explosion Hazard**

Keep flammable materials and vapors, such as gasoline, away from dryer.

Place dryer at least 18" (46 cm) above the floor for a garage installation.

Failure to do so can result in death, explosion, or fire.

- The dryer **MUST** be vented to the outdoors.
 - Minimum clearance between dryer cabinet and adjacent walls or other surfaces is:
 - 0" either side*
 - 0" front
 - 0" rear
 - 0" top
- *For improved performance, a 1/2" clearance is suggested on each side.
- The rear of the dryer should face a wall.
 - Consideration must be given to provide adequate clearance for installation and service.
 - Closet doors must be louvered or otherwise ventilated and have at least 60 square inches of open area. If the closet contains both a washer and a dryer, doors must contain a minimum of 120 square inches of open area.
- NOTE:** WHEN THE EXHAUST DUCT IS LOCATED AT THE REAR OF THE DRYER, THE CONFIGURATION OF THE DUCTING MAY REQUIRE GREATER CLEARANCE.
- Gas Dryers Only:**
- No other fuel burning appliance shall be installed in the same closet as a gas dryer.
 - The dryer must be disconnected from the gas supply piping during pressure testing at pressures greater than 1/2 psi (3.5 kPa).
 - A 1/8 inch NPT minimum plugged tapping, accessible for test gauge connection, must be installed immediately upstream of the gas supply connection to the dryer.

MINIMUM CLEARANCE OTHER THAN ALCOVE OR CLOSET INSTALLATION

Minimum clearance to combustibile surfaces and for air opening are: 0" both sides*, 0" rear and 0" top.

*For improved performance, a 1/2" clearance is suggested on each side.

The rear of the dryer should face a wall.

Consideration must be given to provide adequate clearance for installation and service.


MOBILE OR MANUFACTURED HOME INSTALLATION

- Installation **MUST** conform to the MANUFACTURED HOME CONSTRUCTION AND SAFETY STANDARD, TITLE 24, PART 3280 or STANDARD FOR MOBILE HOMES CAN/CSA-Z240 MH, or, when such standards are not applicable, with AMERICAN NATIONAL STANDARD FOR MOBILE HOME, ANSI/NFPA NO. 501B.
- The dryer **MUST** be vented to the outdoors.
- The exhaust vent **MUST** be securely fastened to a non-combustible portion of the mobile home.
- The vent **MUST NOT** be terminated beneath a mobile or manufactured home.
- The vent duct material **MUST BE METAL**.
- KIT 14-D346-33 **MUST** be used to attach the dryer securely to the structure.
- The vent **MUST NOT** be connected to any other duct, vent or chimney.
- **DO NOT** use sheet metal screws or other fastening devices which extend into the interior of the exhaust vent.
- Provide an opening with a free area of at least 25 square inches for introduction of outside air into the dryer room.
- See the sections for electrical connection information.

Installation Instructions

ELECTRICAL CONNECTION INFORMATION FOR ELECTRIC DRYERS

For electrical connections using a power cord:



⚠ WARNING - Fire Hazard

Use a new UL-listed 240V 30 amp dryer power supply cord with closed ring terminals or spade terminals with upturned ends.

Use a UL-listed strain relief.

Disconnect power before making electrical connections.

Connect neutral wire (white or center wire) to center terminal.

Ground wire (green or bare wire) must be connected to green ground connector.

Connect remaining two supply wires to remaining two terminals.


Securely tighten all electrical connections.

Replace the terminal block cover.

Failure to do so can result in death, fire or electrical shock.


GROUNDING INSTRUCTIONS

For a grounded, cord-connected dryer: This dryer must be grounded. In the event of a malfunction or breakdown, grounding will reduce the risk of electric shock by providing a path of least resistance for electric current. This dryer uses a cord having an equipment-grounding conductor and a grounding plug. The plug must be plugged into an appropriate outlet that is properly installed and grounded in accordance with all local codes and ordinances.



⚠ WARNING Improper connection of the equipment-grounding conductor can result in a risk of electric shock. Check with a qualified electrician, or service representative or personnel, if you are in doubt as to whether the appliance is properly grounded. **DO NOT** modify the plug on the power supply cord. If it will not fit the outlet, have a proper outlet installed by a qualified electrician.

SAVE THESE INSTRUCTIONS



⚠ WARNING - Electrical Shock Hazard


TO PREVENT ELECTRIC SHOCK, DISCONNECT POWER BEFORE SERVICING.

This dryer should be connected to an individual branch circuit with 10 gauge copper wire minimum through a 30 amp fuse or circuit breaker. **DO NOT** fuse neutral.

Use copper conductors only.

ELECTRICAL CONNECTION INFORMATION FOR ELECTRIC DRYERS

For direct wire connections:



⚠ WARNING - Fire Hazard

Use 10 gauge copper wire.

Use a UL-listed strain relief.

Disconnect power before making electrical connections.

Connect neutral wire (white or center wire) to center terminal.

Ground wire (green or bare wire) must be connected to green ground connector.

Connect remaining two supply wires to remaining two terminals.


Securely tighten all electrical connections.

Replace the terminal block cover.

Failure to do so can result in death, fire or electrical shock.


GROUNDING INSTRUCTIONS

For a permanently connected dryer: This dryer must be connected to a grounded metal, permanent wiring system, or an equipment-grounding conductor must be run with the circuit conductors and connected to the equipment-grounding terminal on the appliance.



⚠ WARNING Improper connection of the equipment-grounding conductor can result in a risk of electric shock. Check with a qualified electrician, or service representative or personnel, if you are in doubt as to whether the appliance is properly grounded.

SAVE THESE INSTRUCTIONS



⚠ WARNING - Electrical Shock Hazard

TO PREVENT ELECTRIC SHOCK, DISCONNECT POWER BEFORE SERVICING.

This dryer should be connected to an individual branch circuit with 10 gauge copper wire minimum through a 30 amp fuse or circuit breaker. **DO NOT** fuse neutral.

Use copper conductors only.

HOME APPLIANCES

LG COOKING

LSEL6335_

6.3 cu ft. Smart Wi-Fi Enabled ProBake Convection® InstaView™ Electric Slide-in Range with Air Fry

WTR4 LOT 141



KEY FEATURES

- 6.3 cu ft. Large Capacity
- InstaView™ Window – Knock Twice to see what’s cooking
- Built-In Air Fry with ProBake Convection®
- EasyClean® + Self Clean
- 3-in-1 Element for cooking flexibility
- ThinQ® app with Proactive Customer Care

AVAILABLE COLORS

- PRINTPROOF™ STAINLESS STEEL
- PRINTPROOF™ BLACK STAINLESS STEEL

SMART APPLIANCE



Enjoy new ways to control your home with LG smart appliances

- Install Setup Quick Check
- Preventative Alerts & Guidance
- Performance & Usage Reports




PRODUCT FEATURES

| SUMMARY | | OVEN | | SMART FEATURES | |
|--|--|-----------------------------------|--|---|-------------------------|
| Cooktop Type | Radiant, Ceramic Glass | Oven Type | Single Oven | Wi-Fi Connect | Yes |
| Number of Cooktop Burners | 5 | Oven Cooking System | ProBake Convection® | Proactive Customer Care | Yes |
| Oven Type | Single Oven | Convection Conversion Auto-Adjust | Yes | Smart Diagnosis™ | Yes |
| Oven Cooking System | ProBake Convection® | Oven Cleaning Type | EasyClean® + Self Clean | Works with | LG ThinQ® |
| Oven Capacity (cu. ft.) | 6.3 | Self-Clean Oven Door Lock | Automatic | | Amazon Alexa |
| Oven Cleaning Type | EasyClean® + Self Clean | Oven Capacity (cu. ft.) | 6.3 | | Google Assistant |
| Drawer Type | Storage | Broiler Element Power | 4200W | | SIDECHEF |
| Size in Width (in.) | 30 | Number of Rack Positions | 7 | | Innit (*) |
| APPEARANCE | | | | | Nestle (*) |
| Color | PrintProof™ Stainless Steel, PrintProof™ Black Stainless Steel | Number of Oven Racks | 2 | INCLUDED ACCESSORIES | |
| Control Type | SmoothTouch™ Glass | Oven Rack Type | 2 Heavy Duty | Air Fry Tray | Yes |
| Knobs | Stainless Steel Appearance, Weighted | Drawer Type | Storage | POWER/RATINGS | |
| Oven Door Feature | InstaView & WideView™ Window | Oven Modes | Bake, Conv. Bake, Conv. Roast, Broil High, Broil Low, Warm, Proof, Frozen Meal, Air Fry, Slow Cook, EasyClean, SelfClean | Amp Rating at 208V | 46.9A |
| Cooktop Finish | Ceramic Glass, Stainless Steel, Porcelain Enamel | Oven Light Type | Halogen | Amp Rating at 240V | 54.2A |
| COOKTOP | | CONTROL FEATURES | | KW Rating at 208V | 9.8kW |
| Cooktop Type | Radiant, Ceramic Glass | Kitchen Timer | Yes | KW Rating at 240V | 13.0kW |
| Number of Cooktop Burners | 5 | Timed Cook | Yes | Required Power Supply Amp | 40A |
| Element/Burner - Left Front | 9" / 6" Dual, 3200W UltraHeat™ | Oven Control Lock | Yes (Cooktop, Key) | DIMENSIONS & WEIGHT | |
| Element/Burner - Left Rear | 6" Single, 1200W | Sabbath Mode | Yes | Cabinet Width (in.) | 30 |
| Element/Burner - Right Front | 12" / 9" 6" Triple, 3000W | | | Overall Depth (in.) - including handle | 29 9/32 (743.9mm) |
| Element/Burner - Right Rear | 6" Single, 1200W | | | Overall Height (in.) | 36 1/2 (927.9mm) |
| Element/Burner - Center | 7" Single, 100W Warming Zone | | | Overall Width (in.) | 30 (761.8mm) |
| Hot Surface Indicator Light | Yes | | | Product Weight (lb) | 161.7 |
| | | | | Shipping Weight (lb) | 221 |
| | | | | Shipping Dimensions (W x H x D) (in.) | 32 1/2" x 44" x 30 1/2" |
| | | | | UPC CODES | |
| | | | | LSEL6335F (PrintProof™ Stainless Steel) | 048231341844 |
| | | | | LSEL6335D (PrintProof™ Black Stainless Steel) | 048231341851 |
| *These partners may not yet be available at the time of purchase of this product, please continue to check for app updates | | | | | |



LG REFRIGERATION

WTR4 LOT 141



LRFCC23D6S

23.0 cu. ft. French Door Refrigerator

23.0 cu. ft. Capacity

4 Refrigerator Shelves and Glide N' Serve Pantry

Smart Inverter

Smart Diagnosis

KEY FEATURES

AVAILABLE COLORS



PRINTPROOF™ STAINLESS STEEL



SMART APPLIANCE

Proactive Smart Alerts to Keep Your Appliances Running Smoothly




- Preventative Alerts help you stay a step ahead of potential issues to find proactive solutions before problems arise.
- Avoid preventable repairs and service calls with real-time diagnostics for a hassle-free experience.
- Integrated within LG's ThinQ app--a smart home hub for managing your smart devices and appliances.



PRODUCT FEATURES

| CAPACITY | | REFRIGERATOR | | DIMENSIONS/CLEARANCES/WEIGHTS | |
|---|--|-------------------------|------------------------------------|--|-----------------------------|
| Refrigerator (cu. ft.) | 15.8 cu. ft. | No. of Shelves | 4 split (4 Fixed) | Product (W x H x D) | 35 3/4" x 69 3/4" x 31 1/4" |
| Freezer (cu. ft.) | 7.2 cu. ft. | Shelf Construction | Spill protector/Tempered glass | Width | 35 3/4" |
| Total Capacity (cu. ft.) | 23.0 cu. ft. | Shelf Trim | White décor | Height (to Top of Hinge) | 69 3/4" |
| ENERGY | | No. of Crisper Bins | 2 | Depth (with Handles) | 31 1/4" |
| ENERGY STAR® Qualified | Yes | Pantry (Glide N' Serve) | Yes (Normal) | Width (Door Open 90° without Handle) | 39 1/4" |
| Energy Consumption (kWh/Year) | TBD | Light | Yes | Width (Door Open 90° with Handle) | 44 1/4" |
| WATER & ICE SYSTEM | | REFRIGERATOR DOOR | | Width (Door Fully Open without Handle) | 63 1/2" |
| No. Freezer Ice maker | 1 | No. of Door Bins | 3 (left door) / 3 (right door) | Height (to Top of Case) | 68 1/2" |
| Freezer Ice maker Ice type | Cubed | Door Shape | Contour | Depth without Door | 24 3/4" |
| Freezer Ice maker Daily production (lbs.) | 2.5 / 2.7 lbs. | Handle Type | Bar | Depth without Handles | 28 3/4" |
| Freezer Ice maker storage capacity | 4.0 lbs. | FREEZER | | Depth (to Hinge Cover) | 20 3/8" |
| Ice Plus | Yes | Door Type | Pull Drawer | Depth (Total with Door Open) | 43 1/2" |
| Filteration system | 1 stage | Handle Type | Smart Pull™ Handle | Installation Clearance | Sides 1/8", Top 1", Back 2" |
| Filter | LT1000P | Drawers / Shelves | 2-Tier Organization | Carton Dimensions (WxHxD) | 38" x 73" x 37" |
| COOLING | | Freezer Light | Upper Yes Lower No | Weight (Unit/Carton) | 251 lbs. / 276 lbs. |
| Compressor Type | Smart Inverter | SMART TECHNOLOGY | | LIMITED WARRANTY | |
| Evaporator | Yes (1) | Smart Diagnosis | Yes | Parts & Labor | 1 year |
| Multi Air Flow Cooling | Yes | Wi-Fi Enabled | Yes | Sealed System (Parts & Labor) | 5 years |
| Temperature Sensors | 2 | ThinQ® | Yes | Compressor (Parts & Labor) | 5 years |
| Refrigerant | Low GWP, Zero ODP and More Energy Efficient Refrigerant (R600a / 60g / 2.12oz) | ThinQ® Care | Yes | Inverter Compressor (Parts Only) | 6-10 years |
| | | MATERIALS AND FINISHES | | UPC CODES | |
| CONVENIENCE | | Hidden Hinges | Yes | LRFCC23D6S (PrintProof™ Stainless Steel) | 195174058909 |
| Display Type | Membrane / White LED | All Available Colors | PrintProof™ Stainless Steel | | |
| Temperature Controls | Electronic/Digital | PrintProof™ | Yes | | |
| Door Alarm | Yes | Insulation | Low GWP and Zero ODP Blowing Agent | | |
| Child Lock | Yes | | | | |
| Auto Closing Door Hinge | Yes | | | | |
| Sabbath Mode | Yes | | | | |
| ADA Compliant | Yes | | | | |

WIR4 LOT 141




SC(B)319 | ALITO Collection




Wall Mount

Our most popular and best-selling model has been redesigned to have the bright dual-setting LED lights on the front of the range hood to better illuminate your cooking surface where you need it most. The relocation of the lights will not only improve illumination over your cooktop it also helps hide any imperfections in your backsplash finish. The lighting being in the front of the hood will help the tortured perfectionists out there to avoid any reminders that even the most skilled tilers cannot always avoid having slight imperfections. This small change may seem superficial but will make a huge difference for all involved and can help keep your project under budget. As they say in business...."it is all in the finishing".


Green Features




3 Speed Push Button Control Panel



Long-Lasting LED Lights



Time-Delay OFF Feature



Grease Cup



| Model | Colour | Ducting | Filters | Size | CFM |
|----------|-----------------|---------|---------|------|-----|
| SC31924 | Stainless Steel | 6" | Mesh | 24" | 300 |
| SC31930 | Stainless Steel | 6" | Mesh | 30" | 300 |
| SC31936 | Stainless Steel | 6" | Mesh | 36" | 300 |
| SCB31924 | Stainless Steel | 6" | Baffle | 24" | 300 |
| SCB31930 | Stainless Steel | 6" | Baffle | 30" | 300 |
| SCB31936 | Stainless Steel | 6" | Baffle | 36" | 300 |

Cyclone Range Hoods Inc.



1361 Huntingwood Drive, Unit 16. Toronto, ON. M1S 3J1. Canada.
Toll Free: 1-888-293-5662 Tel: (416) 293-0933 Fax: (416) 293-4793 Website: www.CycloneRangeHoods.com

SC(B)319 | ALITO Collection



Features

- Wall mount range hood
- 6” round duct adapter
- Non-stick aluminum fan blades
- 3 speed push button control
- 2 LED lights (2 x 1.4W, 4000K)
- Quick release filters
- Standard chimney fits up to 9 ft. ceiling
- Up to 9 minutes time-delay OFF feature
- Plug-in connection



Options

- Filters:
 - SC319 - Quick Release Aluminum Mesh Filters
 - SCB319 - Quick Release Stainless Steel Baffle Filters
- Chimney Flues:
 - A1.CH10 - short (7'-8' ceilings)
 - A1.CH18 - standard (8'-9' ceilings)
 - A1.CH30 - extended (9'-11' ceilings)
- Widths: 24", 30", 36"

Specifications

- | | | |
|--------------------------------------|--------------------------------|---|
| ▪ Air Flow Volume: 300 CFM | ▪ Current: 2.5 Amps | ▪ Finishes: Stainless Steel |
| ▪ Electrical Connection: 120 V/60 Hz | ▪ Fan Speed: 1350 RPM | ▪ Ducting: 6" Round |
| ▪ Power Consumption: 300 Watts | ▪ Fan Type: Centrifugal Blower | ▪ Noise Level: Min. 2 Sones Max. 4 Sones |



WTR4 LOT 141

GEFW650SSN/SPN


GE® 4.8 cu. ft. Capacity Front Load ENERGY STAR® Steam Washer with SmartDispense™ and UltraFresh Vent System with OdorBlock™



DIMENSIONS AND INSTALLATION INFORMATION (IN INCHES)

| ELECTRIC RATING | |
|-----------------|-------------|
| 120V | 11.0A, 60Hz |

INSTALLATION INFORMATION: For complete information, see installation instructions packed with your washer.



*With leveling leg adjust.



For answers to your Monogram, GE Café™ Series, GE Profile™ Series or GE Appliances product questions, visit our website at geappliances.com or call GE Answer Center® Service, 800.626.2000.



Specification Revised 11/19

GFW650SSN/SPN

GE® 4.8 cu. ft. Capacity Front Load ENERGY STAR® Steam Washer with SmartDispense™ and UltraFresh Vent System with OdorBlock™

SPECIAL INSTALLATION REQUIREMENTS:

STACKED INSTALLATION:

- Brackets for stacking dryer over washer are not included with the washer. Order part no. GFA28KITN.
- ALCOVE OR CLOSET INSTALLATION:**
 - If your dryer is approved for installation in an alcove or closet, it will be stated on a label on the dryer back.
 - The dryer MUST be exhausted to the outside.
 - Minimum clearances between dryer cabinet and adjacent walls or other surfaces are: 0" all sides and top.*
 - Closet doors must be louvered or otherwise ventilated and must contain a minimum of 60 sq. in. of open area equally distributed. If this closet contains both a washer and a dryer, doors must contain a minimum of 120 sq. in. of open area equally distributed.
 - No other fuel-burning appliance shall be installed in the same closet with a gas dryer.

BATHROOM OR BEDROOM INSTALLATION:

- The dryer MUST be exhausted to the outdoors.
- The installation must conform with the local codes, or in the absence of local codes, with the National Electric Code and National Fuel Gas Code, ANSI Z223.

MINIMUM CLEARANCE OTHER THAN ALCOVE OR CLOSET INSTALLATIONS:


- Minimum clearances to combustible surfaces 0" all sides and top.*

FOR MORE INFORMATION ON VENTING KITS AND ACCESSORIES, PLEASE CALL 1-800-GE-CARES.

*For improved performance, a 1/2" clearance is suggested on each side.



For answers to your Monogram, GE Café™ Series, GE Profile™ Series or GE Appliances product questions, visit our website at geappliances.com or call GE Answer Center® Service, 800.626.2000.



STACKED DIMENSIONS (IN INCHES)

PEDESTAL DIMENSIONS (IN INCHES)


GFP1528PNDG - DIAMOND GRAY

GFP1528PNRS - SAPPHIRE BLUE

GFP1528PNSN - SATIN NICKEL

GFP1528SNWW - WHITE

This optional 16" pedestal raises the door opening and height of the washer or dryer.



GE® 4.8 cu. ft. Capacity Front Load ENERGY STAR® Steam Washer with SmartDispense™ and UltraFresh Vent System with OdorBlock™

FEATURES AND BENEFITS

UltraFresh Vent System With OdorBlock™ – The first and only UltraFresh Vent System with OdorBlock™ eliminates excess moisture to help prevent odors ensuring your washer stays fresh and clean.

Microban® antimicrobial technology – Built into components including the gasket, dispenser and draining system delivers protection that lives on load after load.

SmartDispense™ Technology – Save time and make laundry effortless with an intelligent dispenser that holds up to 32 loads of detergent and automatically dispenses the right amount each time.

Built-in WiFi – Start, stop and monitor your laundry from anywhere while receiving real-time notifications and updates.

Dynamic Balancing Technology (dBt™) – Our patented, time saving technology senses and re-balances uneven loads during the spin cycle, providing a quiet wash.

Reversible door – Easily reverse your washer and dryer door for superior installation flexibility.

PowerSteam – Safely penetrates deep into fabric fibers, loosening stains to deliver enhanced cleaning performance.

Quick Wash Cycle – Provides a fast 20 minute wash for lightly soiled items.

Sanitize + Allergen – Industry-first cycle sanitizes fabrics to kill 99% of common bacteria and allergens such as dust mites.

Model GFW650SSNWW – White

Model GFW650SPNSN – Satin Nickel



For answers to your Monogram, GE Café™ Series, GE Profile™ Series or GE Appliances product questions, visit our website at geappliances.com or call GE Answer Center® Service, 800.626.2000.

