

# **Scope of Work for Excavation and Backfill**

## **Project: Low-Rise Residential Development**

### **1. Introduction:**

This document outlines the scope of work for the excavation and backfill activities required for the low-rise residential development project. The work includes excavation for the basement foundation, backfilling, cutting of the driveway, spreading stone, and rough grading. All activities will be executed in accordance with the project drawings and specifications.

### **2. Scope of Work:**

2.1 Excavation of Basement foundation as per drawing up to 6' and cast fill once.

2.2 Backfill basement foundation

2.3 Cut driveway

2.4 Spread stone once and backfill

2.5 Rough grade up

### **3. General Requirements:**

All work shall be performed in compliance with local building codes, regulations, and industry standards.

The contractor shall ensure the safety of workers and the public during all phases of the work.

Proper erosion and sediment control measures shall be implemented throughout the project.

The contractor shall maintain clear communication with the project manager and other relevant parties to ensure the smooth execution of the work.

All necessary permits and inspections shall be obtained and coordinated by the contractor.

### **4. Completion and Cleanup:**

Upon completion of the excavation and backfill activities, the contractor shall ensure the site is left in a clean and orderly condition.

Any damage to existing structures, utilities, or landscaping shall be repaired to the satisfaction of the project manager.

### **5. Documentation:**

The contractor shall provide detailed documentation of all work performed, including test results, inspection reports, and any other relevant records.