



ADDENDUM TO CONSTRUCTION CONTRACT

SCHEDULE "A "

(revised: Aug. 16, 2018)

Forestside Towns VI

The materials and labour to be furnished and the work to be performed by the contractor under the terms of this agreement are as set out below:

BRICKLAYERS:

- Ø Bricks completed.
- Ø Bricklayers responsible for the following;
 - Bricks to be cleaned
 - Gas proofing in garage and parging
 - Plastering on gable roofs & behind lower roofs
 - Clean up excess materials and bricks
- Ø Supply: colour, masonry, sand, brick ties, stone, window sills, key stones where required, and bricks.
- Ø Contractor is responsible for laying of bricks in accordance to the plan and elevation supplied by the builder's brochure.
- Ø Soldier courses, detailing and quoining are all included in quoted costs.
- Ø Any brick veneer to be estimated by site superintendent and or construction manager with a foreman of the sub-contractors.
- Ø Brick flashing/steel lintels to be supplied and installed by the bricklayer.
- Ø Any stone or precast to be supplied and installed as per architectural drawings/brochure.
- Ø Builder responsible to place order of the radius size for arched angle-line and bricklayer will be responsible to supply and install. Bricklayer to pay steel manufacturer directly.
- Ø **17' & 18' towns: 8ft on lower level, 8ft ground, 9ft main & 8ft on upper level (as per plan).**
- Ø **22' Semi-towns & Semi-Detached: 8ft on lower level, 9ft on main, 8ft on upper level**
- Ø **HANSEN Brick**
- Ø **Aristcraft Stone**

EXPIRY DATE: DECEMBER 31, 2019