



ADDENDUM TO CONSTRUCTION CONTRACT

SCHEDULE "A"

(revised: Aub. 16, 2018)
Forestside Towns VI

The materials and labour to be furnished and the work to be performed by the contractor under the terms of this agreement are as set out below:

EXTERIOR TRIM & DETAILING:

- Ø Supply & install all necessary materials including exterior columns & exterior railings to complete trim according to architectural drawings. Vinyl siding supplied & installed by others.
- Ø **All wood trim including dentils must be primed by contractor prior to installation.**
- Ø Quote supplied by contractor must specify material being supplied as required by each individual architectural drawing. Example: vinyl railings, vinyl columns(specifications), wood trim on porch etc...
- Ø All vinyl colours must match exterior colour schemes as approved by architectural control.
- Ø Supply all necessary supplies for installation of trim including poly, vapour barriers, glue etc...
- Ø All wood joints must be properly glued, caulked and sealed to prevent leakage.

EXPIRY DATE: DECEMBER 31, 2019