




ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
(2019 AMENDMENT)
Ss = 27.2 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 23.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)

DENOTES:

*: 12" RAISED CEILING
#: 20" RAISED CEILING

DENOTES:
CONVENTIONAL FRAMING

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DWG NO. TAM **T-2127208**
 STRUCTURAL
 COMPONENT ONLY

TRUSS PLACEMENT PLAN.

This is a truss placement plan only, NOT a final roof framing plan. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss drawings for each component identified on this placement plan.

Please verify that all dimensions match the dimensions found on the job. The Building designer is responsible for the temporary/permanent bracing of the roof and floor system and its integration into the bracing of the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer unless otherwise noted in this plan. Building designer to review and approve this plan to ascertain conformity to his overall structural plan.


DWG# T-2126452 to T-2126480, T1800218

Job Track: **52430**
 Layout ID: **420375**
 Plan Log: **205032**

Builder / Location: **ROYAL PINE HOMES / BRAMPTON**
 Project: **VALES OF CASTLEMORE NORTH**
 Date: 2021-08-05 Designer: **ND**

Model / Elevation: **UNIT 4505 / A STD (4 OR 5 BED)**
 Mitek ver 8.4.2.286
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

M14217



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
(2019 AMENDMENT)
Ss = 27.2 psf | Sr = 8.4 psf


DESIGN LOADS:
TCSL = 23.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)

DENOTES:
*: 12" RAISED CEILING
#: 20" RAISED CEILING

DENOTES:
CONVENTIONAL
FRAMING

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.




DWG NO. TAM T-2127209
STRUCTURAL
COMPONENT ONLY

TRUSS PLACEMENT PLAN.

This is a truss placement plan only, NOT a final roof framing plan. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss drawings for each component identified on this placement plan.


Please verify that all dimensions match the dimensions found on the job. The Building designer is responsible for the temporary/permanent bracing of the roof and floor system and its integration into the bracing of the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer unless otherwise noted in this plan. Building designer to review and approve this plan to ascertain conformity to his overall structural plan.

DWG# T-2126452 to T-2126460, T-2126467, T-2126469 to T-2126492, T1800218



Job Track:	52430	Builder / Location:	ROYAL PINE HOMES / BRAMPTON
Layout ID:	420376	Project:	VALES OF CASTLEMORE NORTH
Plan Log:	205032	Date:	2021-08-05
		Designer:	ND

Model / Elevation:	UNIT 4505 / A OPT. COFF (4 BED)	Mitek ver 8.4.2.286
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.		



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
(2019 AMENDMENT)
Ss = 27.2 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 23.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf


HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)

DENOTES:

*: 12" RAISED CEILING
#: 20" RAISED CEILING

 DENOTES:
CONVENTIONAL
FRAMING

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.



DWG NO. TAM **T-2127210**
STRUCTURAL
COMPONENT ONLY

TRUSS PLACEMENT PLAN.

This is a truss placement plan only, NOT a final roof framing plan. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss drawings for each component identified on this placement plan.


Please verify that all dimensions match the dimensions found on the job. The Building designer is responsible for the temporary/permanent bracing of the roof and floor system and its integration into the bracing of the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer unless otherwise noted in this plan. Building designer to review and approve this plan to ascertain conformity to his overall structural plan.

DWG# T-2126452 to T-2126460, T-2126467, T-2126469 to T-2126482, T-2126492 to T-2126502, T1800218



Job Track: **52430**
Layout ID: **420377**
Plan Log: **205032**
Builder / Location: **ROYAL PINE HOMES / BRAMPTON**
Project: **VALES OF CASTLEMORE NORTH**
Date: 2021-08-05 Designer: **ND**

Model / Elevation: **UNIT 4505 / A OPT. COFF (5 BED)**
Mitek ver 8.4.2.286
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
(2019 AMENDMENT)
Ss = 27.2 psf | Sr = 8.4 psf


DESIGN LOADS:
TCSL = 23.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)


DENOTES:

#: 20" RAISED CEILING

X: DROPPED BEAM BY OTHERS

 DENOTES:
CONVENTIONAL
FRAMING

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.




DWG NO. TAM T-2127211
STRUCTURAL
COMPONENT ONLY

TRUSS PLACEMENT PLAN.

This is a truss placement plan only, NOT a final roof framing plan. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss drawings for each component identified on this placement plan.

Please verify that all dimensions match the dimensions found on the job. The Building designer is responsible for the temporary/permanent bracing of the roof and floor system and its integration into the bracing of the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer unless otherwise noted in this plan. Building designer to review and approve this plan to ascertain conformity to his overall structural plan.


DWG# T-2126452 to T-2126457, T-2126461 to
T-2126471, T-2126473, T-2126503 to T-
2126519, T1800218



Job Track: 52430
Layout ID: 420378
Plan Log: 205032

Builder / Location: ROYAL PINE HOMES / BRAMPTON
Project: VALES OF CASTLEMORE NORTH
Date: 2021-08-05 Designer: ND

Model / Elevation: UNIT 4505 / B STD (4 OR 5 BED)
Mitek ver 8.4.2.286
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
(2019 AMENDMENT)
Ss = 27.2 psf | Sr = 8.4 psf


DESIGN LOADS:
TCSL = 23.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)


DENOTES:

#: 20" RAISED CEILING

X: DROPPED BEAM BY OTHERS

 DENOTES:
CONVENTIONAL
FRAMING

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.



DWG NO. TAM **T-2127212**
STRUCTURAL
COMPONENT ONLY

DWG# T-2126452 to T-2126457, T-2126467, T-2126469 to T-2126471, T-2126473, T-2126481 to T-2126492, T-2126503 to T-2126519, T1800218

TRUSS PLACEMENT PLAN.

This is a truss placement plan only, NOT a final roof framing plan. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss drawings for each component identified on this placement plan.


Please verify that all dimensions match the dimensions found on the job. The Building designer is responsible for the temporary/permanent bracing of the roof and floor system and its integration into the bracing of the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer unless otherwise noted in this plan. Building designer to review and approve this plan to ascertain conformity to his overall structural plan.



Job Track: **52430**
Layout ID: **420379**
Plan Log: **205032**

Builder / Location: **ROYAL PINE HOMES / BRAMPTON**
Project: **VALES OF CASTLEMORE NORTH**
Date: 2021-08-05 Designer: **ND**

Model / Elevation: **UNIT 4505 / B OPT. COFF (4 BED)**
Mitek ver 8.4.2.286
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
(2019 AMENDMENT)
Ss = 27.2 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 23.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)


DENOTES:

#: 20" RAISED CEILING

X: DROPPED BEAM BY OTHERS

 DENOTES:
CONVENTIONAL
FRAMING

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.



DWG NO. TAM T-2127213
STRUCTURAL
COMPONENT ONLY

TRUSS PLACEMENT PLAN.

This is a truss placement plan only, NOT a final roof framing plan. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss drawings for each component identified on this placement plan.

Please verify that all dimensions match the dimensions found on the job. The Building designer is responsible for the temporary/permanent bracing of the roof and floor system and its integration into the bracing of the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer unless otherwise noted in this plan. Building designer to review and approve this plan to ascertain conformity to his overall structural plan.


DWG# T-2126452 to T-2126457, T-2126467, T-2126469 to T-2126471, T-2126473, T-2126481 to T-2126482, T-2126492 to T-2126519, T1800218



Job Track: 52430
Layout ID: 420380
Plan Log: 205032

Builder / Location: ROYAL PINE HOMES / BRAMPTON
Project: VALES OF CASTLEMORE NORTH
Date: 2021-08-05
Designer: ND

Model / Elevation: UNIT 4505 / B OPT. COFF (5 BED)
Mitek ver 8.4.2.286
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.



ALL ROOF SLOPES ARE 8/12 UNLESS NOTED OTHERWISE

ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
(2019 AMENDMENT)
Ss = 27.2 psf | Sr = 8.4 psf


DESIGN LOADS:
TCSL = 23.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
HGUS26 - (X)
LJS26DS - (V)
LUS26-2 - (VV)
HGUS26-2 - (XX)

DENOTES:
#: 24" RAISED CEILING
X: DROPPED BEAM BY OTHERS

DENOTES:
CONVENTIONAL
FRAMING

All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.



DWG NO. TAM T-2127214
STRUCTURAL
COMPONENT ONLY

TRUSS PLACEMENT PLAN.


This is a truss placement plan only, NOT a final roof framing plan. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss drawings for each component identified on this placement plan.

Please verify that all dimensions match the dimensions found on the job. The Building designer is responsible for the temporary/permanent bracing of the roof and floor system and its integration into the bracing of the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer unless otherwise noted in this plan. Building designer to review and approve this plan to ascertain conformity to his overall structural plan.

DWG# T-2126452 to T-2126456, T-2126461 to T-2126468, T-2126520 to T-2126537, T1800218



Job Track: 52430	Builder / Location: ROYAL PINE HOMES / BRAMPTON	Model / Elevation: UNIT 4505 / C STD (4 OR 5 BED)
Layout ID: 420381	Project: VALES OF CASTLEMORE NORTH	MITAK ver 8.4.2.286
Plan Log: 205032	Date: 2021-08-05 Designer: ND	THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
(2019 AMENDMENT)
Ss = 27.2 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 23.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
HGUS26 - (X)
LUS26-2 - (VV)
HGUS26-2 - (XX)

DENOTES:
#: 24" RAISED CEILING
X: DROPPED BEAM BY OTHERS

DENOTES:
CONVENTIONAL FRAMING



All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.


TRUSS PLACEMENT PLAN.


This is a truss placement plan only, NOT a final roof framing plan. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss drawings for each component identified on this placement plan.

Please verify that all dimensions match the dimensions found on the job. The Building designer is responsible for the temporary/permanent bracing of the roof and floor system and its integration into the bracing of the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer unless otherwise noted in this plan. Building designer to review and approve this plan to ascertain conformity to his overall structural plan.

DWG# T-2126452 to T-2126456, T-2126467, T-2126481 to T-2126492, T-2126520 to T-2126537, T1800218

Job Track: 52430	Builder / Location: ROYAL PINE HOMES / BRAMPTON	Model / Elevation: UNIT 4505 / C OPT. COFF (4 BED)
Layout ID: 420382	Project: VALES OF CASTLEMORE NORTH	THese DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.
Plan Log: 205032	Date: 2021-08-05	Designer: ND





ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
(2019 AMENDMENT)
Ss = 27.2 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 23.3 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
HGUS26 - (X)
LUS26-2 - (VV)
HGUS26-2 - (XX)

DENOTES:
#: 24" RAISED CEILING
X: DROPPED BEAM BY OTHERS

DENOTES:
CONVENTIONAL
FRAMING



All conventional framing to conform with Part 9 of O.B.C. 2012. Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

TRUSS PLACEMENT PLAN.


This is a truss placement plan only, NOT a final roof framing plan. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss drawings for each component identified on this placement plan.

Please verify that all dimensions match the dimensions found on the job. The Building designer is responsible for the temporary/permanent bracing of the roof and floor system and its integration into the bracing of the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer unless otherwise noted in this plan. Building designer to review and approve this plan to ascertain conformity to his overall structural plan.

DWG# T-2126452 to T-2126456, T-2126467, T-2126481 to T-2126482, T-2126492 to T-2126502, T-2126520 to T-2126537, T1800218

 TAMARACK ROOF TRUSSES INC. ALPHA-LUMBER GROUP	Job Track: 52430	Builder / Location: ROYAL PINE HOMES / BRAMPTON			Model / Elevation: UNIT 4505 / C OPT. COFF (5 BED) Mitek ver 8.4.2.286	
	Layout ID: 420383	Project: VALES OF CASTLEMORE NORTH			THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.	
	Plan Log: 205032	Date: 2021-08-05	Designer: ND			

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: A STD (4 OR 5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420375
 Ref #
 Page: 1 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Hip Girder	6 /12	35-11-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	333.31 207.33		
	1	T2 Hip	6 /12	35-11-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	143.28 90.50		
	1	T3 Hip	6 /12	35-11-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	148.12 93.00		
	1	T4 Hip	6 /12	35-11-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	146.64 90.50		
	1	T5 Hip	6 /12	35-11-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	163.39 103.33		
	1	T6 Hip	6 /12	35-11-00	9-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	158.74 100.33		
	9	T7 Common	6 /12	35-11-00	10-01-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1388 849.00		
	1	T7CP Hip	6 /12	35-11-00	10-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	154.04 94.33		
	2	T8 Hip	10 /12	35-11-00	7-10-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	317.07 197.33		
	2	T9 Hip	10 /12	35-11-00	9-06-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	374.82 232.00		
	2	T10 Hip	10 /12	35-11-00	11-02-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	386.25 236.67		
	1 2-ply	T11 Hip Girder	10 /12	35-11-00	6-02-08	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	379.01 234.00		
	3	T12 Common	10 /12	11-00-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	147.28 97.00		
	4	T12S Roof Special	10 /12	11-00-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	227.43 154.00		

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: A STD (4 OR 5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420375
 Ref #
 Page: 2 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T13 Jack-Closed Girder	10 / 12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	59.24 39.33		
	1 2-ply	T13Z Jack-Closed Girder	10 / 12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	59.24 39.33		
	1	T14 Hip	10 / 12	17-03-00	9-00-07	2 x 4	1-03-08	1-07-11 3-03-11	97.41 62.67		
	1	T15 Hip	10 / 12	17-03-00	7-04-07	2 x 4	1-03-08	1-07-11 3-03-11	81.15 51.33		
	1	T16S Hip Girder	10 / 12	17-03-00	5-08-07	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	100.31 63.67		
	1 2-ply	T17 Jack-Closed Girder	10 / 12	2-10-08	5-08-07	2 x 4 2 x 6		3-03-11 5-08-07	42.46 26.00		
	13	J1 Jack-Open	6 / 12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	234.21 151.67		
	2	J1C Jack-Open	6 / 12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	30.71 19.33		
	2	J1C2 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	25.61 16.67		
	2	J1C3 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	16.85 11.33		
	2	J1C4 Jack-Open	6 / 12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	21.95 14.00		
	3	J2 Jack-Open	10 / 12	5-05-12	6-02-08	2 x 4	1-03-08	1-07-11 6-02-08	58.27 39.00		
	2	J3 Jack-Open	10 / 12	2-10-08	4-00-07	2 x 4	1-03-08	1-07-11 4-00-07	25.18 16.67		
	1	J3C Jack-Open	10 / 12	1-10-15	3-02-13	2 x 4	1-03-08 11-09	1-07-11 3-02-13	11.16 7.67		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: A STD (4 OR 5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420375
 Ref #
 Page: 3 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	J3C1 Jack-Open	10 /12	1-10-15	3-02-13	2 x 4	1-03-08 1-01	1-07-11 3-02-13	10.4 7.50		


TOTAL # TRUSS= 69 TOTAL BFT OF ALL TRUSSES= 3345.49 BFT. TOTAL WEIGHT OF ALL TRSSES 5341.52 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	LJS26DS	
4	Hardware	LUS24	
1	Hardware	LUS26-2	
2	Hardware	HGUS26-2	

TOTAL NUMBER OF ITEMS= 9

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: A OPT. COFF (4 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420376
 Ref #
 Page: 1 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	10	T7 Common	6 /12	35-11-00	10-01-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1511.62 926.67		
	2	T8 Hip	10 /12	35-11-00	7-10-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	317.07 197.33		
	2	T9 Hip	10 /12	35-11-00	9-06-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	374.82 232.00		
	2	T10 Hip	10 /12	35-11-00	11-02-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	386.25 236.67		
	1 2-ply	T11 Hip Girder	10 /12	35-11-00	6-02-08	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	369.01 227.33		
	3	T12 Common	10 /12	11-00-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	147.28 97.00		
	4	T12S Roof Special	10 /12	11-00-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	227.43 154.00		
	1 2-ply	T13 Jack-Closed Girder	10 /12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	59.24 39.33		
	1 2-ply	T13Z Jack-Closed Girder	10 /12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	59.24 39.33		
	1	T14 Hip	10 /12	17-03-00	9-00-07	2 x 4	1-03-08	1-07-11 3-03-11	97.41 62.67		
	1	T15 Hip	10 /12	17-03-00	7-04-07	2 x 4	1-03-08	1-07-11 3-03-11	81.15 51.33		
	1	T16S Hip Girder	10 /12	17-03-00	5-08-07	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	100.31 63.67		
	1 2-ply	T17 Jack-Closed Girder	10 /12	2-10-08	5-08-07	2 x 4 2 x 6		3-03-11 5-08-07	42.46 26.00		
	1 3-ply	T18S Hip Girder	6 /12	35-11-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	513.74 329.00		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: A OPT. COFF (4 BED)





Job Track: 52430
 PlanLog: 205032
 Layout ID: 420376
 Ref #
 Page: 2 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T19S Hip	6 /12	35-11-00	4-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	147.17 94.67		
	1	T20S Hip	6 /12	35-11-00	5-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	153.43 96.67		
	1	T21S Hip	6 /12	35-11-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	160.79 101.67		
	1	T22S Hip	6 /12	35-11-00	6-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	154.36 99.00		
	1	T23S Hip	6 /12	35-11-00	7-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	157.09 99.17		
	1	T24S Hip	6 /12	35-11-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	160.27 102.00		
	1	T25 Hip	6 /12	35-11-00	8-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	145.69 90.67		
	1	T26 Hip	6 /12	35-11-00	9-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	163.77 102.67		
	1	T27 Half Hip Girder	6 /12	5-10-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	23.14 16.50		
	7	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	126.11 81.67		
	1	J1C Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	15.35 9.67		
	1	J1C2 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	12.8 8.33		
	1	J1C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	8.43 5.67		
	1	J1C4 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	10.98 7.00		

DELIVERY SHIPLIST				
 TAMARACK ROOF TRUSSES INC. ALPHA LUMBER GROUP	Lumber Yard:	TAMARACK LUMBER	Job Track:	52430
	Builder:	ROYAL PINE HOMES	PlanLog:	205032
	Project:	VALES OF CASTLEMORE NORTH	Layout ID:	420376
	Location:	BRAMPTON	Ref #	
	Model:	UNIT 4505	Page:	3 of 3
	Lot #:		Date:	08-05-2021
	Elevation:	A OPT. COFF (4 BED)	Designer:	
		Sales Rep:	Rick DiCiano	

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	8	J1S Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 3-01-04	165.75 117.33		
	3	J2 Jack-Open	10 /12	5-05-12	6-02-08	2 x 4	1-03-08	1-07-11 6-02-08	58.27 39.00		
	2	J3 Jack-Open	10 /12	2-10-08	4-00-07	2 x 4	1-03-08	1-07-11 4-00-07	25.18 16.67		
	1	J3C Jack-Open	10 /12	1-10-15	3-02-13	2 x 4	1-03-08 11-09	1-07-11 3-02-13	11.16 7.67		
	1	J3C1 Jack-Open	10 /12	1-10-15	3-02-13	2 x 4	1-03-08 1-01	1-07-11 3-02-13	10.4 7.50		
	3	J4 Jack-Open	6 /12	1-04-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	17.78 14.00		

TOTAL # TRUSS= 75

TOTAL BFT OF ALL TRUSSES= 3799.86 BFT.


TOTAL WEIGHT OF ALL TRSSES 6014.94 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	LJS26DS	
5	Hardware	LUS24	
1	Hardware	LUS26-2	
2	Hardware	HGUS26-2	

TOTAL NUMBER OF ITEMS= 10

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: A OPT. COFF (5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420377
 Ref #
 Page: 1 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	10	T7 Common	6 /12	35-11-00	10-01-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1511.62 926.67		
	1	T7SCP Hip	6 /12	35-11-00	10-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	168.94 106.00		
	2	T8 Hip	10 /12	35-11-00	7-10-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	317.07 197.33		
	2	T9 Hip	10 /12	35-11-00	9-06-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	374.82 232.00		
	2	T10 Hip	10 /12	35-11-00	11-02-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	386.25 236.67		
	1 2-ply	T11 Hip Girder	10 /12	35-11-00	6-02-08	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	369.01 227.33		
	3	T12 Common	10 /12	11-00-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	147.28 97.00		
	4	T12S Roof Special	10 /12	11-00-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	227.43 154.00		
	1 2-ply	T13 Jack-Closed Girder	10 /12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	59.24 39.33		
	1 2-ply	T13Z Jack-Closed Girder	10 /12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	59.24 39.33		
	1	T14 Hip	10 /12	17-03-00	9-00-07	2 x 4	1-03-08	1-07-11 3-03-11	97.41 62.67		
	1	T15 Hip	10 /12	17-03-00	7-04-07	2 x 4	1-03-08	1-07-11 3-03-11	81.15 51.33		
	1	T16S Hip Girder	10 /12	17-03-00	5-08-07	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	100.31 63.67		
	1 2-ply	T17 Jack-Closed Girder	10 /12	2-10-08	5-08-07	2 x 4 2 x 6		3-03-11 5-08-07	42.46 26.00		

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: A OPT. COFF (5 BED)








Job Track: 52430
 PlanLog: 205032
 Layout ID: 420377
 Ref #
 Page: 2 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T27 Half Hip Girder	6 /12	5-10-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	23.14 16.50		
	1 3-ply	T28S Hip Girder	6 /12	35-11-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	508.39 326.00		
	1	T29S Hip	6 /12	35-11-00	4-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	148.03 96.50		
	1	T30S Hip	6 /12	35-11-00	5-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	154.69 98.83		
	1	T31S Hip	6 /12	35-11-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	155.39 98.83		
	1	T32S Hip	6 /12	35-11-00	6-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	159.96 103.67		
	1	T33S Hip	6 /12	35-11-00	7-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	164.97 104.33		
	1	T34S Hip	6 /12	35-11-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	162.18 102.67		
	1	T35S Hip	6 /12	35-11-00	8-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	166.93 107.00		
	1	T36S Hip	6 /12	35-11-00	9-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	167.6 106.83		
	8	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	144.13 93.33		
	1	J1C Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	15.35 9.67		
	1	J1C2 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	12.8 8.33		
	1	J1C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	8.43 5.67		

 TAMARACK ROOF TRUSSES INC. — ALPA LUMBER GROUP —	DELIVERY SHIPLIST					
	Lumber Yard: TAMARACK LUMBER				Job Track: 52430	
	Builder: ROYAL PINE HOMES				PlanLog: 205032	
	Project: VALES OF CASTLEMORE NORTH				Layout ID: 420377	
	Location: BRAMPTON				Ref #	
	Model: UNIT 4505				Page: 3 of 3	
Lot #:				Date: 08-05-2021		
Elevation: A OPT. COFF (5 BED)				Designer:		
				Sales Rep: Rick DiCiano		

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	J1C4 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	10.98 7.00		
	7	J1S Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 3-01-04	142.15 100.33		
	3	J2 Jack-Open	10 /12	5-05-12	6-02-08	2 x 4	1-03-08	1-07-11 6-02-08	58.27 39.00		
	2	J3 Jack-Open	10 /12	2-10-08	4-00-07	2 x 4	1-03-08	1-07-11 4-00-07	25.18 16.67		
	1	J3C Jack-Open	10 /12	1-10-15	3-02-13	2 x 4	1-03-08 11-09	1-07-11 3-02-13	11.16 7.67		
	1	J3C1 Jack-Open	10 /12	1-10-15	3-02-13	2 x 4	1-03-08 1-01	1-07-11 3-02-13	10.4 7.50		
	3	J4 Jack-Open	6 /12	1-04-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	20.92 17.00		

TOTAL # TRUSS= 76

TOTAL BFT OF ALL TRUSSES= 3932.66 BFT.

TOTAL WEIGHT OF ALL TRSSES 6213.28 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	LJS26DS	
5	Hardware	LUS24	
1	Hardware	LUS26-2	
2	Hardware	HGUS26-2	

TOTAL NUMBER OF ITEMS= 10

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: B STD (4 OR 5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420378
 Ref #
 Page: 1 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Hip Girder	6 /12	35-11-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	326.21 203.33		
	1	T2 Hip	6 /12	35-11-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	143.28 90.50		
	1	T3 Hip	6 /12	35-11-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	148.12 93.00		
	1	T4 Hip	6 /12	35-11-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	146.64 90.50		
	1	T5 Hip	6 /12	35-11-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	163.39 103.33		
	1	T6 Hip	6 /12	35-11-00	9-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	158.74 100.33		
	9	T7 Common	6 /12	35-11-00	10-01-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1360.46 834.00		
	1	T7CP Hip	6 /12	35-11-00	10-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	150.98 92.67		
	2	T8 Hip	10 /12	35-11-00	7-10-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	317.07 197.33		
	2	T9 Hip	10 /12	35-11-00	9-06-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	374.82 232.00		
	2	T10 Hip	10 /12	35-11-00	11-02-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	386.25 236.67		
	1	T12 Common	10 /12	11-00-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	49.09 32.33		
	1	T38 Hip Girder	10 /12	11-00-00	4-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	52.24 34.00		
	1 2-ply	T39 Jack-Closed Girder	10 /12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	68.59 45.67		

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: B STD (4 OR 5 BED)




Job Track: 52430
 PlanLog: 205032
 Layout ID: 420378
 Ref #
 Page: 2 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T39Z Jack-Closed Girder	10 / 12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	68.59 45.67		
	1	T40 Hip	10 / 12	17-03-00	8-01-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	88.63 57.33		
	1	T41 Hip	10 / 12	17-03-00	6-05-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	75.53 48.00		
	1	T42 Hip Girder	10 / 12	17-03-00	4-10-07	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	86.03 55.17		
	1	T43 Hip	10 / 12	11-00-00	7-04-07	2 x 4	1-03-08 1-03-08	3-03-11 3-03-11	64.83 41.17		
	1	T44 Hip Girder	10 / 12	11-00-00	5-08-07	2 x 4	1-03-08 1-03-08	3-03-11 3-03-11	67.75 45.67		
	1 2-ply	T45 Jack-Closed Girder	10 / 12	3-10-08	4-10-07	2 x 4 2 x 6		1-07-11 4-10-07	43.15 29.33		
	2	T46 Half Hip Girder	10 / 12	2-10-08	4-05-07	2 x 4	1-03-08	3-03-11 4-05-07	51.72 33.33		
	2	T47 Monopitch	10 / 12	1-04-08	4-05-07	2 x 4	1-03-08	3-03-11 4-05-07	31.83 21.33		
	1 2-ply	T48 Hip Girder	10 / 12	35-11-00	6-02-08	2 x 4 2 x 6	1-03-08 1-05-00	1-07-11 1-07-11	394.14 242.00		
	13	J1 Jack-Open	6 / 12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	234.21 151.67		
	2	J1C Jack-Open	6 / 12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	30.71 19.33		
	2	J1C2 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	25.61 16.67		
	2	J1C3 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	16.86 11.33		

DELIVERY SHIPLIST			
 TAMARACK ROOF TRUSSES INC. ALPA LUMBER GROUP	Lumber Yard:	TAMARACK LUMBER	Job Track: 52430
	Builder:	ROYAL PINE HOMES	PlanLog: 205032
	Project:	VALES OF CASTLEMORE NORTH	Layout ID: 420378
	Location:	BRAMPTON	Ref #
	Model:	UNIT 4505	Page: 3 of 3
	Lot #:		Date: 08-05-2021
	Elevation:	B STD (4 OR 5 BED)	Designer:
			Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	J1C4 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	21.96 14.00		
	3	J2 Jack-Open	10 /12	5-05-12	6-02-08	2 x 4	1-03-08	1-07-11 6-02-08	58.27 39.00		
	5	J5 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	76.06 48.33		
	3	J5C Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 2-01-01	1-07-11 3-01-09	36.34 25.00		
	3	J5C1 Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 1-01	1-07-11 3-01-09	29.97 21.00		
	4	J6 Jack-Open	10 /12	2-10-08	4-00-07	2 x 4	1-03-08	1-07-11 4-00-07	50.35 33.33		
	4	J7 Jack-Open	4 /12	6-11-00	3-00-08	2 x 4	1-03-08	3-15 2-04-04	82.23 50.67		


TOTAL # TRUSS= 85 TOTAL BFT OF ALL TRUSSES= 3434.99 BFT. TOTAL WEIGHT OF ALL TRSSES 5480.65 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
4	Hardware	LJS26DS	
6	Hardware	LUS24	
1	Hardware	LUS26-2	
2	Hardware	HGUS26-2	

TOTAL NUMBER OF ITEMS= 13

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: B OPT. COFF (4 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420379
 Ref #
 Page: 1 of 4
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	10	T7 Common	6 /12	35-11-00	10-01-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1511.62 926.67		
	2	T8 Hip	10 /12	35-11-00	7-10-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	317.07 197.33		
	2	T9 Hip	10 /12	35-11-00	9-06-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	374.82 232.00		
	2	T10 Hip	10 /12	35-11-00	11-02-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	386.25 236.67		
	1	T12 Common	10 /12	11-00-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	49.09 32.33		
	1 3-ply	T18S Hip Girder	6 /12	35-11-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	513.74 329.00		
	1	T19S Hip	6 /12	35-11-00	4-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	147.17 94.67		
	1	T20S Hip	6 /12	35-11-00	5-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	152.3 95.67		
	1	T21S Hip	6 /12	35-11-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	159.46 100.67		
	1	T22S Hip	6 /12	35-11-00	6-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	154.36 99.00		
	1	T23S Hip	6 /12	35-11-00	7-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	157.09 99.17		
	1	T24S Hip	6 /12	35-11-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	160.27 102.00		
	1	T25 Hip	6 /12	35-11-00	8-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	145.69 90.67		
	1	T26 Hip	6 /12	35-11-00	9-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	163.77 102.67		

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: B OPT. COFF (4 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420379
 Ref #
 Page: 2 of 4
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T27 Half Hip Girder	6 /12	5-10-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	23.14 16.50		
	1	T38 Hip Girder	10 /12	11-00-00	4-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	52.24 34.00		
	1 2-ply	T39 Jack-Closed Girder	10 /12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	68.59 45.67		
	1 2-ply	T39Z Jack-Closed Girder	10 /12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	68.59 45.67		
	1	T40 Hip	10 /12	17-03-00	8-01-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	88.63 57.33		
	1	T41 Hip	10 /12	17-03-00	6-05-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	75.53 48.00		
	1	T42 Hip Girder	10 /12	17-03-00	4-10-07	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	86.03 55.17		
	1	T43 Hip	10 /12	11-00-00	7-04-07	2 x 4	1-03-08 1-03-08	3-03-11 3-03-11	64.83 41.17		
	1	T44 Hip Girder	10 /12	11-00-00	5-08-07	2 x 4	1-03-08 1-03-08	3-03-11 3-03-11	67.75 45.67		
	1 2-ply	T45 Jack-Closed Girder	10 /12	3-10-08	4-10-07	2 x 4 2 x 6		1-07-11 4-10-07	43.15 29.33		
	2	T46 Half Hip Girder	10 /12	2-10-08	4-05-07	2 x 4	1-03-08	3-03-11 4-05-07	51.72 33.33		
	2	T47 Monopitch	10 /12	1-04-08	4-05-07	2 x 4	1-03-08	3-03-11 4-05-07	31.83 21.33		
	1 2-ply	T48 Hip Girder	10 /12	35-11-00	6-02-08	2 x 4 2 x 6	1-03-08 1-05-00	1-07-11 1-07-11	387.69 238.67		
	7	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	126.11 81.67		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: B OPT. COFF (4 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420379
 Ref #
 Page: 3 of 4
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	J1C Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	15.35 9.67		
	1	J1C2 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	12.8 8.33		
	1	J1C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	8.43 5.67		
	1	J1C4 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	10.98 7.00		
	8	J1S Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 3-01-04	162.46 114.67		
	3	J2 Jack-Open	10 /12	5-05-12	6-02-08	2 x 4	1-03-08	1-07-11 6-02-08	58.27 39.00		
	3	J4 Jack-Open	6 /12	1-04-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	20.92 17.00		
	5	J5 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	76.06 48.33		
	3	J5C Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 2-01-01	1-07-11 3-01-09	36.34 25.00		
	3	J5C1 Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 1-01	1-07-11 3-01-09	29.97 21.00		
	4	J6 Jack-Open	10 /12	2-10-08	4-00-07	2 x 4	1-03-08	1-07-11 4-00-07	50.35 33.33		
	4	J7 Jack-Open	4 /12	6-11-00	3-00-08	2 x 4	1-03-08	3-15 2-04-04	82.23 50.67		

TOTAL # TRUSS= 91


TOTAL BFT OF ALL TRUSSES= 3911.7

BFT.

TOTAL WEIGHT OF ALL TRSSES 6192.72 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
4	Hardware	LJS26DS	
7	Hardware	LUS24	


DELIVERY SHIPLIST			
	Lumber Yard:	TAMARACK LUMBER	Job Track: 52430
	Builder:	ROYAL PINE HOMES	PlanLog: 205032
	Project:	VALES OF CASTLEMORE NORTH	Layout ID: 420379
	Location:	BRAMPTON	Ref #
	Model:	UNIT 4505	Page: 4 of 4
	Lot #:		Date: 08-05-2021
	Elevation:	B OPT. COFF (4 BED)	Designer:
			Sales Rep: Rick DiCiano

HARDWARE

QTY	TYPE	MODEL	LENGTH
1	Hardware	LUS26-2	
2	Hardware	HGUS26-2	

TOTAL NUMBER OF ITEMS= **14**

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: B OPT. COFF (5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420380
 Ref #
 Page: 1 of 4
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	10	T7 Common	6 /12	35-11-00	10-01-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1511.62 926.67		
	1	T7SCP Hip	6 /12	35-11-00	10-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	168.94 106.00		
	2	T8 Hip	10 /12	35-11-00	7-10-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	317.07 197.33		
	2	T9 Hip	10 /12	35-11-00	9-06-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	374.82 232.00		
	2	T10 Hip	10 /12	35-11-00	11-02-08	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	386.25 236.67		
	1	T12 Common	10 /12	11-00-00	6-02-11	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	49.09 32.33		
	1	T27 Half Hip Girder	6 /12	5-10-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	23.14 16.50		
	1 3-ply	T28S Hip Girder	6 /12	35-11-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	508.39 326.00		
	1	T29S Hip	6 /12	35-11-00	4-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	148.03 95.83		
	1	T30S Hip	6 /12	35-11-00	5-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	153.56 97.83		
	1	T31S Hip	6 /12	35-11-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	154.07 97.83		
	1	T32S Hip	6 /12	35-11-00	6-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	159.96 103.67		
	1	T33S Hip	6 /12	35-11-00	7-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	164.97 104.33		
	1	T34S Hip	6 /12	35-11-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	162.18 102.67		

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: B OPT. COFF (5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420380
 Ref #
 Page: 2 of 4
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T35S Hip	6 /12	35-11-00	8-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	164.55 105.50		
	1	T36S Hip	6 /12	35-11-00	9-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	167.6 106.83		
	1	T38 Hip Girder	10 /12	11-00-00	4-10-07	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	52.24 34.00		
	1 2-ply	T39 Jack-Closed Girder	10 /12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	68.59 45.67		
	1 2-ply	T39Z Jack-Closed Girder	10 /12	5-05-12	6-02-08	2 x 4 2 x 6		1-07-11 6-02-08	68.59 45.67		
	1	T40 Hip	10 /12	17-03-00	8-01-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	88.63 57.33		
	1	T41 Hip	10 /12	17-03-00	6-05-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	75.53 48.00		
	1	T42 Hip Girder	10 /12	17-03-00	4-10-07	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	86.03 55.17		
	1	T43 Hip	10 /12	11-00-00	7-04-07	2 x 4	1-03-08 1-03-08	3-03-11 3-03-11	64.83 41.17		
	1	T44 Hip Girder	10 /12	11-00-00	5-08-07	2 x 4	1-03-08 1-03-08	3-03-11 3-03-11	67.75 45.67		
	1 2-ply	T45 Jack-Closed Girder	10 /12	3-10-08	4-10-07	2 x 4 2 x 6		1-07-11 4-10-07	43.15 29.33		
	2	T46 Half Hip Girder	10 /12	2-10-08	4-05-07	2 x 4	1-03-08	3-03-11 4-05-07	51.72 33.33		
	2	T47 Monopitch	10 /12	1-04-08	4-05-07	2 x 4	1-03-08	3-03-11 4-05-07	31.83 21.33		
	1 2-ply	T48 Hip Girder	10 /12	35-11-00	6-02-08	2 x 4 2 x 6	1-03-08 1-05-00	1-07-11 1-07-11	387.69 238.67		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: B OPT. COFF (5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420380
 Ref #
 Page: 3 of 4
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses


PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	8	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	144.13 93.33		
	1	J1C Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	15.35 9.67		
	1	J1C2 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	12.8 8.33		
	1	J1C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	8.43 5.67		
	1	J1C4 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	10.98 7.00		
	7	J1S Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 3-01-04	142.15 100.33		
	3	J2 Jack-Open	10 /12	5-05-12	6-02-08	2 x 4	1-03-08	1-07-11 6-02-08	58.27 39.00		
	3	J4 Jack-Open	6 /12	1-04-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	20.92 17.00		
	5	J5 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	76.06 48.33		
	3	J5C Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 2-01-01	1-07-11 3-01-09	36.34 25.00		
	3	J5C1 Jack-Open	10 /12	1-09-07	3-01-09	2 x 4	1-03-08 1-01	1-07-11 3-01-09	29.97 21.00		
	4	J6 Jack-Open	10 /12	2-10-08	4-00-07	2 x 4	1-03-08	1-07-11 4-00-07	50.35 33.33		
	4	J7 Jack-Open	4 /12	6-11-00	3-00-08	2 x 4	1-03-08	3-15 2-04-04	82.23 50.67		

TOTAL # TRUSS= 92

TOTAL BFT OF ALL TRUSSES= 4041.99

BFT.

TOTAL WEIGHT OF ALL TRSSES 6388.82 LBS


DELIVERY SHIPLIST			
	Lumber Yard:	TAMARACK LUMBER	Job Track: 52430
	Builder:	ROYAL PINE HOMES	PlanLog: 205032
	Project:	VALES OF CASTLEMORE NORTH	Layout ID: 420380
	Location:	BRAMPTON	Ref #
	Model:	UNIT 4505	Page: 4 of 4
	Lot #:		Date: 08-05-2021
	Elevation:	B OPT. COFF (5 BED)	Designer:
			Sales Rep: Rick DiCiano

HARDWARE

QTY	TYPE	MODEL	LENGTH
4	Hardware	LJS26DS	
7	Hardware	LUS24	
1	Hardware	LUS26-2	
2	Hardware	HGUS26-2	

TOTAL NUMBER OF ITEMS= **14**

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: C STD (4 OR 5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420381
 Ref #
 Page: 1 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Hip Girder	6 /12	35-11-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	333.31 207.33		
	1	T2 Hip	6 /12	35-11-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	143.28 90.50		
	1	T3 Hip	6 /12	35-11-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	148.12 93.00		
	1	T4 Hip	6 /12	35-11-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	146.64 90.50		
	1	T5 Hip	6 /12	35-11-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	163.39 103.33		
	1	T6 Hip	6 /12	35-11-00	9-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	158.74 100.33		
	8	T7 Common	6 /12	35-11-00	10-01-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1209.3 741.33		
	1	T7CP Hip	6 /12	35-11-00	10-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	150.98 92.67		
	2	T49 Hip	8 /12	35-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	343.98 216.67		
	2	T50 Hip	8 /12	35-11-00	11-06-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	359.47 222.67		
	2	T51 Hip	8 /12	35-11-00	8-02-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	322.55 199.33		
	1	T52 Hip	8 /12	35-11-00	6-06-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	147.86 90.83		
	1 2-ply	T53 Hip Girder	8 /12	35-11-00	4-10-07	2 x 4 2 x 6	1-03-08 1-03-08	1-04-13 1-04-13	343.42 210.00		
	1 2-ply	T54 Flat Girder	0 /12	3-10-08	2-00-00	2 x 4 2 x 6		2-00-00 2-00-00	36.93 24.67		

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: C STD (4 OR 5 BED)


Job Track: 52430
 PlanLog: 205032
 Layout ID: 420381
 Ref #
 Page: 2 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T55 Hip	8 /12	30-04-00	6-08-07	2 x 4	1-03-08 1-03-08	3-02-13 3-04-13	132.8 82.83		
	1 2-ply	T56S Hip Girder	8 /12	30-07-00	5-02-07	2 x 4 2 x 6	1-03-08	3-04-13 1-04-13	311.48 199.33		
	1 2-ply	T57 Jack-Closed Girder	10 /12	1-10-08	5-02-07	2 x 4 2 x 6		3-07-11 5-02-07	35.18 24.00		
	1	T58 Hip	8 /12	17-03-00	5-11-13	2 x 4	1-03-08 1-03-08	2-04-13 3-04-13	83.12 52.83		
	1	T59S Hip Girder	8 /12	17-03-00	5-07-13	2 x 4 2 x 6	1-03-08 1-03-08	3-04-13 2-04-13	101.7 63.33		
	1	T60 Hip	8 /12	11-00-00	6-10-07	2 x 4	1-03-08	3-04-13 1-04-13	63.11 41.50		
	1	T61 Hip Girder	8 /12	11-00-00	3-02-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	49 30.83		
	1 2-ply	T62 Jack-Closed Girder	8 /12	1-10-08	3-07-13	2 x 4 2 x 6		2-04-13 3-07-13	26.45 17.67		
	13	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	234.21 151.67		
	2	J1C Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	30.71 19.33		
	2	J1C2 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	25.61 16.67		
	2	J1C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	16.85 11.33		
	2	J1C4 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	21.95 14.00		
	3	J8 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	45.64 29.00		

 TAMARACK ROOF TRUSSES INC. ALPA LUMBER GROUP	DELIVERY SHIPLIST	
	Lumber Yard: TAMARACK LUMBER Builder: ROYAL PINE HOMES Project: VALES OF CASTLEMORE NORTH Location: BRAMPTON Model: UNIT 4505 Lot #: Elevation: C STD (4 OR 5 BED)	Job Track: 52430 PlanLog: 205032 Layout ID: 420381 Ref # Page: 3 of 3 Date: 08-05-2021 Designer: Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	11	J9 Jack-Open	10 /12	1-10-08	3-02-07	2 x 4	1-03-08	1-07-11 3-02-07	111.32 77.00		
	2	J9C Jack-Open	10 /12	1-01-09	2-07-00	2 x 4	1-03-08 8-15	1-07-11 2-07-00	18.04 12.67		
	3	J10 Jack-Open	8 /12	1-10-08	3-07-13	2 x 4	1-03-08	2-04-13 3-07-13	32.92 20.50		


TOTAL # TRUSS= 78 TOTAL BFT OF ALL TRUSSES= 3347.65 BFT. TOTAL WEIGHT OF ALL TRSSES 5348.05 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	LJS26DS	
3	Hardware	LUS26-2	
1	Hardware	HGUS26-2	
1	Hardware	HGUS26	

TOTAL NUMBER OF ITEMS= 7

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: C OPT. COFF (4 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420382
 Ref #
 Page: 1 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	9	T7 Common	6 /12	35-11-00	10-01-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1360.46 834.00		
	1 3-ply	T18S Hip Girder	6 /12	35-11-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	513.74 329.00		
	1	T19S Hip	6 /12	35-11-00	4-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	147.17 94.67		
	1	T20S Hip	6 /12	35-11-00	5-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	152.3 95.67		
	1	T21S Hip	6 /12	35-11-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	159.46 100.67		
	1	T22S Hip	6 /12	35-11-00	6-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	154.36 99.00		
	1	T23S Hip	6 /12	35-11-00	7-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	157.09 99.17		
	1	T24S Hip	6 /12	35-11-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	160.27 102.00		
	1	T25 Hip	6 /12	35-11-00	8-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	145.69 90.67		
	1	T26 Hip	6 /12	35-11-00	9-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	163.77 102.67		
	1	T27 Half Hip Girder	6 /12	5-10-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	23.14 16.50		
	2	T49 Hip	8 /12	35-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	343.98 216.67		
	2	T50 Hip	8 /12	35-11-00	11-06-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	353.78 219.33		
	2	T51 Hip	8 /12	35-11-00	8-02-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	322.55 199.33		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: C OPT. COFF (4 BED)







Job Track: 52430
 PlanLog: 205032
 Layout ID: 420382
 Ref #
 Page: 2 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T52 Hip	8 /12	35-11-00	6-06-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	147.86 90.83		
	1 2-ply	T53 Hip Girder	8 /12	35-11-00	4-10-07	2 x 4 2 x 6	1-03-08 1-03-08	1-04-13 1-04-13	341.05 210.67		
	1 2-ply	T54 Flat Girder	0 /12	3-10-08	2-00-00	2 x 4 2 x 6		2-00-00 2-00-00	36.93 24.67		
	1	T55 Hip	8 /12	30-04-00	6-08-07	2 x 4	1-03-08 1-03-08	3-02-13 3-04-13	132.8 82.83		
	1 2-ply	T56S Hip Girder	8 /12	30-07-00	5-02-07	2 x 4 2 x 6	1-03-08	3-04-13 1-04-13	311.48 199.33		
	1 2-ply	T57 Jack-Closed Girder	10 /12	1-10-08	5-02-07	2 x 4		3-07-11 5-02-07	33.75 22.67		
	1	T58 Hip	8 /12	17-03-00	5-11-13	2 x 4	1-03-08 1-03-08	2-04-13 3-04-13	83.12 52.83		
	1	T59S Hip Girder	8 /12	17-03-00	5-07-13	2 x 4 2 x 6	1-03-08 1-03-08	3-04-13 2-04-13	100.28 62.50		
	1	T60 Hip	8 /12	11-00-00	6-10-07	2 x 4	1-03-08	3-04-13 1-04-13	63.11 41.50		
	1	T61 Hip Girder	8 /12	11-00-00	3-02-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	49 30.83		
	1 2-ply	T62 Jack-Closed Girder	8 /12	1-10-08	3-07-13	2 x 4		2-04-13 3-07-13	24.99 17.67		
	7	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	126.11 81.67		
	1	J1C Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	15.35 9.67		
	1	J1C2 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	12.8 8.33		

DELIVERY SHIPLIST			
 TAMARACK ROOF TRUSSES INC. ALPHA LUMBER GROUP	Lumber Yard:	TAMARACK LUMBER	Job Track: 52430
	Builder:	ROYAL PINE HOMES	PlanLog: 205032
	Project:	VALES OF CASTLEMORE NORTH	Layout ID: 420382
	Location:	BRAMPTON	Ref #
	Model:	UNIT 4505	Page: 3 of 3
	Lot #:		Date: 08-05-2021
	Elevation:	C OPT. COFF (4 BED)	Designer:
			Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	J1C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	8.43 5.67		
	1	J1C4 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	10.98 7.00		
	8	J1S Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 3-01-04	162.46 114.67		
	3	J4 Jack-Open	6 /12	1-04-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	20.92 17.00		
	3	J8 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	45.64 29.00		
	11	J9 Jack-Open	10 /12	1-10-08	3-02-07	2 x 4	1-03-08	1-07-11 3-02-07	111.35 77.00		
	2	J9C Jack-Open	10 /12	1-01-09	2-07-00	2 x 4	1-03-08 8-15	1-07-11 2-07-00	18.04 12.67		
	3	J10 Jack-Open	8 /12	1-10-08	3-07-13	2 x 4	1-03-08	2-04-13 3-07-13	32.92 20.50		

TOTAL # TRUSS= 84 TOTAL BFT OF ALL TRUSSES= 3818.86 BFT. TOTAL WEIGHT OF ALL TRSSES 6047.14 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	LJS26DS	
1	Hardware	LUS24	
3	Hardware	LUS26-2	
1	Hardware	HGUS26-2	
1	Hardware	HGUS26	

TOTAL NUMBER OF ITEMS= 8

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: C OPT. COFF (5 BED)

Job Track: 52430
 PlanLog: 205032
 Layout ID: 420383
 Ref #
 Page: 1 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	9	T7 Common	6 /12	35-11-00	10-01-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	1360.46 834.00		
	1	T7SCP Hip	6 /12	35-11-00	10-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	168.94 106.00		
	1	T27 Half Hip Girder	6 /12	5-10-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	23.14 16.50		
	1 3-ply	T28S Hip Girder	6 /12	35-11-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	508.39 326.00		
	1	T29S Hip	6 /12	35-11-00	4-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	148.03 95.83		
	1	T30S Hip	6 /12	35-11-00	5-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	153.56 97.83		
	1	T31S Hip	6 /12	35-11-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	154.07 97.83		
	1	T32S Hip	6 /12	35-11-00	6-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	159.96 103.67		
	1	T33S Hip	6 /12	35-11-00	7-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	164.97 104.33		
	1	T34S Hip	6 /12	35-11-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	162.18 102.67		
	1	T35S Hip	6 /12	35-11-00	8-09-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	164.55 105.50		
	1	T36S Hip	6 /12	35-11-00	9-05-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	167.6 106.83		
	2	T49 Hip	8 /12	35-11-00	9-10-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	343.98 216.67		
	2	T50 Hip	8 /12	35-11-00	11-06-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	353.78 219.33		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: VALES OF CASTLEMORE NORTH
 Location: BRAMPTON
 Model: UNIT 4505
 Lot #:
 Elevation: C OPT. COFF (5 BED)








Job Track: 52430
 PlanLog: 205032
 Layout ID: 420383
 Ref #
 Page: 2 of 3
 Date: 08-05-2021
 Designer:
 Sales Rep: Rick DiCiano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	T51 Hip	8 /12	35-11-00	8-02-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	322.55 199.33		
	1	T52 Hip	8 /12	35-11-00	6-06-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	147.86 90.83		
	1 2-ply	T53 Hip Girder	8 /12	35-11-00	4-10-07	2 x 4 2 x 6	1-03-08 1-03-08	1-04-13 1-04-13	341.05 210.67		
	1 2-ply	T54 Flat Girder	0 /12	3-10-08	2-00-00	2 x 4 2 x 6		2-00-00 2-00-00	36.93 24.67		
	1	T55 Hip	8 /12	30-04-00	6-08-07	2 x 4	1-03-08 1-03-08	3-02-13 3-04-13	132.8 82.83		
	1 2-ply	T56S Hip Girder	8 /12	30-07-00	5-02-07	2 x 4 2 x 6	1-03-08	3-04-13 1-04-13	311.48 199.33		
	1 2-ply	T57 Jack-Closed Girder	10 /12	1-10-08	5-02-07	2 x 4		3-07-11 5-02-07	33.75 22.67		
	1	T58 Hip	8 /12	17-03-00	5-11-13	2 x 4	1-03-08 1-03-08	2-04-13 3-04-13	83.12 52.83		
	1	T59S Hip Girder	8 /12	17-03-00	5-07-13	2 x 4 2 x 6	1-03-08 1-03-08	3-04-13 2-04-13	100.28 62.50		
	1	T60 Hip	8 /12	11-00-00	6-10-07	2 x 4	1-03-08	3-04-13 1-04-13	63.11 41.50		
	1	T61 Hip Girder	8 /12	11-00-00	3-02-07	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	49 30.83		
	1 2-ply	T62 Jack-Closed Girder	8 /12	1-10-08	3-07-13	2 x 4		2-04-13 3-07-13	24.99 17.67		
	8	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	144.13 93.33		
	1	J1C Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	15.35 9.67		

 TAMARACK ROOF TRUSSES INC. ALPA LUMBER GROUP	DELIVERY SHIPLIST										
	Lumber Yard: TAMARACK LUMBER Builder: ROYAL PINE HOMES Project: VALES OF CASTLEMORE NORTH Location: BRAMPTON Model: UNIT 4505 Lot #: Elevation: C OPT. COFF (5 BED)						Job Track: 52430 PlanLog: 205032 Layout ID: 420383 Ref # Page: 3 of 3 Date: 08-05-2021 Designer: Sales Rep: Rick DiCiano				

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	J1C2 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	12.8 8.33		
	1	J1C3 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	8.43 5.67		
	1	J1C4 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	10.98 7.00		
	7	J1S Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 3-01-04	142.15 100.33		
	3	J4 Jack-Open	6 /12	1-04-08	1-10-04	2 x 4	1-03-08	1-02-00 1-10-04	20.92 17.00		
	3	J8 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	45.64 29.00		
	11	J9 Jack-Open	10 /12	1-10-08	3-02-07	2 x 4	1-03-08	1-07-11 3-02-07	111.35 77.00		
	2	J9C Jack-Open	10 /12	1-01-09	2-07-00	2 x 4	1-03-08 8-15	1-07-11 2-07-00	18.04 12.67		
	3	J10 Jack-Open	8 /12	1-10-08	3-07-13	2 x 4	1-03-08	2-04-13 3-07-13	32.92 20.50		

TOTAL # TRUSS= 85 TOTAL BFT OF ALL TRUSSES= 3949.15 BFT. TOTAL WEIGHT OF ALL TRSSES 6243.25 LBS

HARDWARE


QTY	TYPE	MODEL	LENGTH
2	Hardware	LJS26DS	
1	Hardware	LUS24	
3	Hardware	LUS26-2	
1	Hardware	HGUS26-2	
1	Hardware	HGUS26	

TOTAL NUMBER OF ITEMS= 8

JOB NAME 420375	TRUSS NAME T1	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:49 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N160ZyxnM3-1X4cAFY84ZlupYuEOvue4KAKoHqVSKHPd77dOQyrEgm



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - G	2x4	DRY	No.2	SPF
G - J	2x4	DRY	No.2	SPF
J - L	2x4	DRY	No.2	SPF
V - B	2x6	DRY	No.2	SPF
M - K	2x6	DRY	No.2	SPF
V - S	2x6	DRY	No.2	SPF
S - P	2x6	DRY	No.2	SPF
P - M	2x6	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				
B - U	2x4	DRY	No.2	SPF
N - K	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C	12	SIDE(61.0)
C-G	12	SIDE(61.0)
G-J	12	SIDE(61.0)
J-L	12	SIDE(61.0)
V-B	2	TOP
M-K	2	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
V-S	2	SIDE(183.1)
S-P	2	SIDE(183.1)
P-M	2	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
U-C	6	SIDE(19.2)
N-J	6	SIDE(19.2)
2x3	6	
2x4	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	VERT	GROSS REACTION	HORZ	DOWN	HORZ	BRG	IN-SX	IN-SX	
V	3722	0	3722	0	0	5-8	5-8	5-8	
M	3721	0	3721	0	0	5-8	5-8	5-8	

UNFACTORED REACTIONS

JT	1ST CASE	MAX./MIN.	COMPONENT REACTIONS						
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
V	2540	1689 / 0	0 / 0	0 / 0	0 / 0	950 / 0	0 / 0		
M	2639	1689 / 0	0 / 0	0 / 0	0 / 0	950 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) V, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.70 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		MAX. FACTORED		W E B S		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX	CS1 (LC)	UNBRAC	MEMB.	FORCE (LBS)	MAX	CS1 (LC)
FR-TO		FROM	TO		LENGTH	FR-TO			
A-B	0 / 26	-84.9	-84.9	0.06 (1)	10.00	U-C	-448 / 13	0.06 (1)	
B-C	-5801 / 0	-84.9	-84.9	0.55 (1)	3.64	C-T	0 / 3299	0.41 (1)	
C-W	-7799 / 0	-84.9	-84.9	0.65 (1)	3.00	T-D	-1836 / 0	0.23 (1)	
W-X	-7799 / 0	-84.9	-84.9	0.65 (1)	3.00	D-R	0 / 1494	0.18 (1)	
X-D	-7799 / 0	-84.9	-84.9	0.65 (1)	3.00	R-E	-609 / 0	0.08 (1)	
D-Y	-8979 / 0	-84.9	-84.9	0.74 (1)	2.70	Q-H	-603 / 0	0.08 (1)	
Y-Z	-8979 / 0	-84.9	-84.9	0.74 (1)	2.70	Q-I	0 / 1494	0.18 (1)	
Z-E	-8979 / 0	-84.9	-84.9	0.74 (1)	2.70	O-I	-1834 / 0	0.23 (1)	
E-AA	-8979 / 0	-84.9	-84.9	0.41 (1)	2.99	O-J	0 / 3296	0.41 (1)	
AA-F	-8979 / 0	-84.9	-84.9	0.41 (1)	2.99	N-J	-448 / 13	0.06 (1)	
F-G	-8975 / 0	-84.9	-84.9	0.42 (1)	2.98	B-U	0 / 5229	0.46 (1)	
G-H	-8975 / 0	-84.9	-84.9	0.42 (1)	2.98	N-K	0 / 5227	0.46 (1)	
H-AB	-8975 / 0	-84.9	-84.9	0.74 (1)	2.70	R-F	-169 / 0	0.03 (1)	
AB-AC	-8975 / 0	-84.9	-84.9	0.74 (1)	2.70	F-Q	-175 / 0	0.03 (1)	
AC-I	-8975 / 0	-84.9	-84.9	0.74 (1)	2.70				
I-AD	-7796 / 0	-84.9	-84.9	0.64 (1)	3.00				
AD-AE	-7796 / 0	-84.9	-84.9	0.64 (1)	3.00				
AE-J	-7796 / 0	-84.9	-84.9	0.64 (1)	3.00				
J-K	-5799 / 0	-84.9	-84.9	0.55 (1)	3.64				
K-L	0 / 26	-84.9	-84.9	0.08 (1)	10.00				
V-B	-3637 / 0	0.0	0.0	0.13 (1)	7.37				
M-K	-3635 / 0	0.0	0.0	0.13 (1)	7.37				

V-AF	0 / 0	-18.5	-18.5	0.07 (4)	10.00
AF-AG	0 / 0	-18.5	-18.5	0.07 (4)	10.00
AG-U	0 / 0	-18.5	-18.5	0.07 (4)	10.00
U-AH	0 / 5173	-18.5	-18.5	0.38 (1)	10.00
AH-AI	0 / 5173	-18.5	-18.5	0.38 (1)	10.00
AI-T	0 / 5173	-18.5	-18.5	0.38 (1)	10.00
T-S	0 / 7800	-18.5	-18.5	0.57 (1)	10.00
S-AJ	0 / 7800	-18.5	-18.5	0.57 (1)	10.00
AJ-R	0 / 7800	-18.5	-18.5	0.57 (1)	10.00
R-AK	0 / 9070	-18.5	-18.5	0.68 (1)	10.00
AK-AL	0 / 9070	-18.5	-18.5	0.68 (1)	10.00
AL-AM	0 / 9070	-18.5	-18.5	0.68 (1)	10.00
AM-Q	0 / 9070	-18.5	-18.5	0.68 (1)	10.00
Q-AN	0 / 7796	-18.5	-18.5	0.57 (1)	10.00
AN-P	0 / 7796	-18.5	-18.5	0.57 (1)	10.00
P-O	0 / 7796	-18.5	-18.5	0.57 (1)	10.00
O-AO	0 / 5171	-18.5	-18.5	0.38 (1)	10.00
AO-AP	0 / 5171	-18.5	-18.5	0.38 (1)	10.00
AP-N	0 / 5171	-18.5	-18.5	0.38 (1)	10.00
N-AQ	0 / 0	-18.5	-18.5	0.07 (4)	10.00

TOTAL WEIGHT = 2 X 167 = 333 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (1.20")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.28")
ALLOWABLE DEFL.(TL) = $L/360$ (1.20")
CALCULATED VERT. DEFL.(TL) = $L/809$ (0.53")

CSI: $TC=0.74/1.00$ (D-E:1), $BC=0.66/1.00$ (Q-R:1),
 $WB=0.46/1.00$ (B-U:1), $SS=0.21/1.00$ (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (U) (INPUT = 0.90)
JSI METAL= 0.73 (S) (INPUT = 1.00)



Structural component only
DWG# T-2126461

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ROYAL PINE HOMES	DRWG NO.
420375	T1	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:49 2021 Page 2
ID:rhtOOT9Mf?GOVQD N160ZyxmN3-1X4cAFY84ZlupYuEOvue4KAKoHqVSKHPd77dOQyrEgm

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	2.00	2.75
C	TTWW-m	MT20	5.0	8.0	2.00	2.50
D, F, I						
D	TMWW-t	MT20	4.0	4.0		
E	TMW+w	MT20	2.0	4.0		
G	TS-t	MT20	3.0	6.0		
H	TMW+w	MT20	2.0	4.0		
J	TTWW-m	MT20	5.0	8.0	2.00	2.50
K	TMVW-p	MT20	5.0	6.0	2.00	2.75
M	BMV1+p	MT20	3.0	6.0		
N	BMWW-t	MT20	5.0	6.0	2.50	2.50
O	BMWW-t	MT20	5.0	6.0		
P	BS-t	MT20	5.0	6.0		
Q	BMWWWW-t	MT20	5.0	8.0		
R	BMWWWW-t	MT20	5.0	8.0		
S	BS-t	MT20	5.0	6.0		
T	BMWW-t	MT20	5.0	6.0		
U	BMWW-t	MT20	5.0	6.0	2.50	2.50
V	BMV1+p	MT20	3.0	6.0		

NOTES: (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. CSI (LC)
FR-TO		FROM TO	LENGTH FR-TO				
AQ-AR	0/0	-18.5	-18.5 0.07 (4)	10.00			
AR-M	0/0	-18.5	-18.5 0.07 (4)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-374	-374	---	FRONT	VERT	TOTAL	---	C1
F	17-11-8	-113	-113	---	FRONT	VERT	TOTAL	---	C1
G	19-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
J	30-0-8	-374	-374	---	FRONT	VERT	TOTAL	---	C1
N	29-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
P	23-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
S	11-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
U	5-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
W	7-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
X	9-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
Y	11-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
Z	13-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AA	15-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AB	21-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AC	23-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AD	25-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AE	27-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AF	1-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AG	3-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AH	7-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AI	9-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AJ	13-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AK	15-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AL	17-11-8	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AM	19-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AN	21-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AO	25-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AP	27-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AQ	31-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AR	33-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.





Structural component only
DWG# T-2126461 *mm*

JOB NAME 420375	TRUSS NAME T2	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:50 2021 Page 1
ID:rhT0OT9Mf?GOVQD_N1160ZyxmN3-Vje_NbZmrTQkRiSQydPtdXjXhhC7B9yZsnsAxsyrEgI



TOTAL WEIGHT = 143 lb

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
I - L	2x4	DRY	No.2
U - B	2x4	DRY	No.2
M - K	2x4	DRY	No.2
U - S	2x4	DRY	No.2
S - O	2x4	DRY	No.2
O - M	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	5.0	6.0		
D	TTWW-m	MT20	5.0	8.0	2.25	3.00
E	TMWW-t	MT20	4.0	4.0		
F	TMW+w	MT20	2.0	4.0		
G	TS-t	MT20	3.0	6.0		
H	TMWW-t	MT20	4.0	4.0		
I	TTWW-m	MT20	5.0	8.0	2.25	3.00
J	TMWW-t	MT20	5.0	6.0		
K	TMV+p	MT20	3.0	4.0		
M	BMVW1-t	MT20	5.0	6.0	2.50	2.25
N	BMVW-t	MT20	4.0	4.0		
O	BS-t	MT20	3.0	6.0		
P	BMVW-t	MT20	4.0	6.0		
Q	BMVW-t	MT20	4.0	6.0		
R	BMVW-t	MT20	4.0	6.0		
S	BS-t	MT20	3.0	6.0		
T	BMVW-t	MT20	4.0	4.0		
U	BMVW1-t	MT20	5.0	6.0	2.50	2.25

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	BRG	BRG
U	VERT	HORZ	HORZ	UPLIFT	IN-SX
U	1971	0	0	5-8	5-8
M	1971	0	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
U	COMBINED	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0
M	1397	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.32 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 / 26	C-T	0 / 275
B-C	0 / 28	D-R	0 / 103
C-D	-2696 / 0	E-Q	0 / 1162
D-E	-3243 / 0	F-H	-727 / 0
E-F	-3497 / 0	G-I	0 / 353
F-G	-3497 / 0	H-J	-390 / 0
G-H	-3497 / 0	I-K	0 / 353
H-I	-3243 / 0	J-L	-727 / 0
I-J	-2696 / 0	K-M	0 / 1162
J-K	0 / 28	L-N	0 / 103
K-L	0 / 26	M-O	0 / 275
U-B	-170 / 0	N-J	0 / 103
M-K	-170 / 0	U-C	-2761 / 0
		J-M	-2761 / 0
U-T	0 / 2144		
T-S	0 / 2397		
S-R	0 / 2397		
R-Q	0 / 3243		
Q-P	0 / 3243		
P-O	0 / 2397		
O-N	0 / 2397		
N-M	0 / 2144		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.20")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.39")

CSI: TC=0.54/1.00 (E-F:1), BC=0.57/1.00 (P-Q:1),
WB=0.63/1.00 (J-M:1), SSI=0.20/1.00 (H-I:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987
		1873	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (M) (INPUT = 0.90)

JSI METAL= 0.70 (S) (INPUT = 1.00)




Structural component only
DWG# T-2126462

JOB NAME 420375	TRUSS NAME T3	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:51 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-wCMaxaObAYb3s1cVKx69IFkY5ZRwdFI5RcTlyrEgk



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - H	2x4	DRY	No.2	SPF	
H - K	2x4	DRY	No.2	SPF	
U - B	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
R - O	2x4	DRY	No.2	SPF	
O - L	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0	2.00	2.75
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TTWW-m	MT20	5.0	8.0	2.25	3.75
E	TMVW-t	MT20	4.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMVW-w	MT20	2.0	4.0		
H	TTWW-m	MT20	5.0	8.0	2.25	3.75
I	TMVW-t	MT20	4.0	4.0	2.00	1.75
J	TMVW-t	MT20	5.0	6.0	2.00	2.75
L	BMV1+p	MT20	3.0	4.0		
M	BMVW-t	MT20	5.0	6.0	2.50	2.50
N, Q, S	BMVW-t	MT20	4.0	4.0		
O	BS-t	MT20	3.0	6.0		
P	BMVW-t	MT20	4.0	9.0		
R	BS-t	MT20	3.0	6.0		
T	BMVW-t	MT20	5.0	6.0	2.50	2.50
U	BMV1+p	MT20	3.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	HORZ	GROSS REACTION	DOWN	HORZ	UPLIFT	BRG	IN-SX	IN-SX
U	1971	0		1971	0	0	5-8	5-8	
L	1971	0		1971	0	0	5-8	5-8	

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
U	1397	900 / 0	0 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0
L	1397	900 / 0	0 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.78 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				W E B S			
MAX. FACTORED		FACTORED		MAX. FACTORED		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 26	-84.9	-84.9 0.11 (1)	10.00	T-C	-327 / 0	0.07 (1)
B-C	-2723 / 0	-84.9	-84.9 0.36 (1)	3.91	C-S	-194 / 0	0.12 (1)
C-D	-2588 / 0	-84.9	-84.9 0.34 (1)	4.01	S-D	0 / 211	0.05 (4)
D-E	-2851 / 0	-84.9	-84.9 0.40 (1)	3.78	D-Q	0 / 810	0.18 (1)
E-F	-2849 / 0	-84.9	-84.9 0.37 (1)	3.82	Q-E	-494 / 0	0.29 (1)
F-G	-2849 / 0	-84.9	-84.9 0.37 (1)	3.82	E-P	-2 / 0	0.00 (1)
G-H	-2849 / 0	-84.9	-84.9 0.40 (1)	3.78	P-G	-493 / 0	0.29 (1)
H-I	-2588 / 0	-84.9	-84.9 0.34 (1)	4.01	P-H	0 / 807	0.18 (1)
I-J	-2723 / 0	-84.9	-84.9 0.36 (1)	3.91	N-H	0 / 212	0.05 (4)
J-K	0 / 26	-84.9	-84.9 0.11 (1)	10.00	N-I	-193 / 0	0.12 (1)
U-B	-1928 / 0	0.0	0.0 0.19 (1)	6.06	M-I	-327 / 0	0.07 (1)
L-J	-1928 / 0	0.0	0.0 0.19 (1)	6.06	B-T	0 / 2489	0.56 (1)
					M-J	0 / 2489	0.56 (1)
U-T	0 / 0	-18.5	-18.5 0.10 (4)	10.00			
T-S	0 / 2454	-18.5	-18.5 0.45 (1)	10.00			
S-R	0 / 2298	-18.5	-18.5 0.43 (1)	10.00			
R-Q	0 / 2298	-18.5	-18.5 0.43 (1)	10.00			
Q-P	0 / 2851	-18.5	-18.5 0.51 (1)	10.00			
P-O	0 / 2298	-18.5	-18.5 0.43 (1)	10.00			
O-N	0 / 2298	-18.5	-18.5 0.43 (1)	10.00			
N-M	0 / 2454	-18.5	-18.5 0.45 (1)	10.00			
M-L	0 / 0	-18.5	-18.5 0.10 (4)	10.00			

TOTAL WEIGHT = 148 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL)= L/999 (0.16")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL)= L/999 (0.32")

CSI: TC=0.40/1.00 (G-H:1), BC=0.51/1.00 (P-Q:1),
WB=0.56/1.00 (B-T:1), SSI=0.21/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (T) (INPUT = 0.90)
JSI METAL= 0.70 (O) (INPUT = 1.00)




Structural component only
DWG# T-2126463

JOB NAME 420375	TRUSS NAME T4	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Wed Aug 4 12:41:52 2021 Page 1
ID:rhT0OT9Mf?GOVQD_N1160ZyxmN3-S6lloHb0MUGSg?cp32SLiyotCUv7f4LsJ5LH?kyrEgJ



LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - D 2x4 DRY

D - F 2x4 DRY

F - I 2x4 DRY

R - B 2x4 DRY

J - H 2x4 DRY

R - O 2x4 DRY

O - M 2x4 DRY

M - J 2x4 DRY

ALL WEBS 2x3 DRY

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0	2.00	2.75
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMVW-w	MT20	2.0	4.0		
F	TTWW-m	MT20	5.0	6.0	2.25	2.00
G	TMVW-t	MT20	4.0	4.0	2.00	1.75
H	TMVW-t	MT20	5.0	6.0	2.00	2.75
J	BMV1+p	MT20	3.0	4.0		
K	BMVW-t	MT20	5.0	6.0	2.50	2.50
L	BMVW-t	MT20	4.0	4.0		
M	BS-t	MT20	3.0	6.0		
N	BMVW-t	MT20	4.0	9.0		
O	BS-t	MT20	3.0	6.0		
P	BMVW-t	MT20	4.0	4.0		
Q	BMVW-t	MT20	5.0	6.0	2.50	2.50
R	BMV1+p	MT20	3.0	4.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
R	VERT	DOWN	IN-SX	IN-SX
R	1971	0	5-8	5-8
J	1971	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LOASE	MAX./MIN. COMPONENT REACTIONS	WIND	DEAD	SOIL
R	COMBINED	SNOW	LIVE	PERM.LIVE	
R	1397	900 / 0	0 / 0	0 / 0	498 / 0
J	1397	900 / 0	0 / 0	0 / 0	498 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.70 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	CS1 (LC)	UNBRAC LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CS1 (LC)
FR-TO							FR-TO			
A-B	0 / 26	-84.9	-84.9	0.11 (1)	10.00	Q-C	-240 / 8	0.06 (1)		
B-C	-2775 / 0	-84.9	-84.9	0.54 (1)	3.70	C-P	-398 / 0	0.38 (1)		
C-D	-2457 / 0	-84.9	-84.9	0.48 (1)	3.94	P-D	0 / 332	0.07 (1)		
D-E	-2508 / 0	-84.9	-84.9	0.51 (1)	3.86	D-N	0 / 496	0.11 (1)		
E-F	-2508 / 0	-84.9	-84.9	0.51 (1)	3.86	N-E	-633 / 0	0.55 (1)		
F-G	-2457 / 0	-84.9	-84.9	0.48 (1)	3.94	N-F	0 / 496	0.11 (1)		
G-H	-2775 / 0	-84.9	-84.9	0.54 (1)	3.70	L-F	0 / 332	0.07 (1)		
H-I	0 / 26	-84.9	-84.9	0.11 (1)	10.00	L-G	-398 / 0	0.38 (1)		
R-B	-1922 / 0	0.0	0.0	0.19 (1)	6.07	K-G	-240 / 8	0.06 (1)		
J-H	-1922 / 0	0.0	0.0	0.19 (1)	6.07	B-Q	0 / 2530	0.57 (1)		
						K-H	0 / 2530	0.57 (1)		
R-Q	0 / 0	-18.5	-18.5	0.14 (4)	10.00					
Q-P	0 / 2505	-18.5	-18.5	0.48 (1)	10.00					
P-O	0 / 2177	-18.5	-18.5	0.42 (1)	10.00					
O-N	0 / 2177	-18.5	-18.5	0.42 (1)	10.00					
N-M	0 / 2177	-18.5	-18.5	0.42 (1)	10.00					
M-L	0 / 2177	-18.5	-18.5	0.42 (1)	10.00					
L-K	0 / 2505	-18.5	-18.5	0.48 (1)	10.00					
K-J	0 / 0	-18.5	-18.5	0.14 (4)	10.00					

TOTAL WEIGHT = 147 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.28")

CSI: TC=0.54/1.00 (G-H:1), BC=0.48/1.00 (K-L:1), WB=0.57/1.00 (H-K:1), SSI=0.25/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (B) (INPUT = 0.90)
JSI METAL= 0.67 (B) (INPUT = 1.00)




Structural component only
DWG# T-2126464

JOB NAME 420375	TRUSS NAME T5	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:53 2021 Page 1

ID:rh1OOT9Mf?GOVQD_N1160ZyxmN3-wlj7?dbe7ooJl9B?dlzaEAL58uG5OXr?Y15qXByrEg



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - E	2x4	DRY	No.2
E - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - I	2x4	DRY	No.2
I - M	2x4	DRY	No.2
X - B	2x4	DRY	No.2
N - L	2x4	DRY	No.2
X - U	2x4	DRY	No.2
U - Q	2x4	DRY	No.2
Q - N	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	5.0	6.0	2.00 2.75
C, D, J, K					
C	TMVW-t	MT20	4.0	4.0	2.00 1.75
E	TS-t	MT20	3.0	6.0	
F	TTWW-m	MT20	5.0	6.0	2.25 2.00
G	TMVW-t	MT20	2.0	4.0	
H	TTWW-m	MT20	5.0	6.0	2.25 2.00
I	TS-t	MT20	3.0	6.0	
L	TMVW-t	MT20	5.0	6.0	2.00 2.75
N	BMV1-p	MT20	3.0	4.0	
O	BMVW-t	MT20	5.0	6.0	2.50 2.50
P, R, T, V					
P	BMVW-t	MT20	4.0	4.0	
Q	BS-t	MT20	3.0	6.0	
S	BMVW-t	MT20	4.0	9.0	
U	BS-t	MT20	3.0	6.0	
W	BMVW-t	MT20	5.0	6.0	2.50 2.50
X	BMV1-p	MT20	3.0	4.0	

NOTES: (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	IN-SX	BRG
X	1971	0	1971	0	0	5-8	5-8		
N	1971	0	1971	0	0	5-8	5-8		

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS							
X	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
N	1397	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0		
N	1397	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) X, N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.96 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		W E B S		FACTORED	
MEMB.	FORCE	VERT. LOAD	LC1 MAX	MEMB.	FORCE	MAX	CSI (LC)
FR-TO				FR-TO			
A-B	0 / 26	-84.9	-84.9 0.11 (1)	10.00	W-C	-349 / 0	0.07 (1)
B-C	-2692 / 0	-84.9	-84.9 0.33 (1)	3.96	C-V	-80 / 0	0.04 (1)
C-D	-2634 / 0	-84.9	-84.9 0.28 (1)	4.05	V-D	0 / 133	0.04 (4)
D-E	-2280 / 0	-84.9	-84.9 0.27 (1)	4.31	D-T	-516 / 0	0.52 (1)
E-F	-2280 / 0	-84.9	-84.9 0.27 (1)	4.31	T-F	0 / 478	0.11 (1)
F-G	-2156 / 0	-84.9	-84.9 0.22 (1)	4.45	F-S	0 / 274	0.06 (1)
G-H	-2156 / 0	-84.9	-84.9 0.22 (1)	4.45	S-G	-416 / 0	0.53 (1)
H-I	-2280 / 0	-84.9	-84.9 0.27 (1)	4.31	S-H	0 / 274	0.06 (1)
I-J	-2280 / 0	-84.9	-84.9 0.27 (1)	4.31	R-H	0 / 478	0.11 (1)
J-K	-2634 / 0	-84.9	-84.9 0.28 (1)	4.05	R-J	-516 / 0	0.52 (1)
K-L	-2692 / 0	-84.9	-84.9 0.33 (1)	3.96	P-J	0 / 133	0.04 (4)
L-M	0 / 26	-84.9	-84.9 0.11 (1)	10.00	P-K	-80 / 0	0.04 (1)
X-B	-1930 / 0	0.0	0.0 0.20 (1)	6.06	O-K	-349 / 0	0.07 (1)
N-L	-1930 / 0	0.0	0.0 0.20 (1)	6.06	B-W	0 / 2460	0.55 (1)
					O-L	0 / 2460	0.55 (1)
X-W	0 / 0	-18.5	-18.5 0.09 (4)	10.00			
W-V	0 / 2421	-18.5	-18.5 0.43 (1)	10.00			
V-U	0 / 2356	-18.5	-18.5 0.42 (1)	10.00			
U-T	0 / 2356	-18.5	-18.5 0.42 (1)	10.00			
T-S	0 / 2029	-18.5	-18.5 0.36 (1)	10.00			
S-R	0 / 2029	-18.5	-18.5 0.36 (1)	10.00			
R-Q	0 / 2356	-18.5	-18.5 0.42 (1)	10.00			
Q-P	0 / 2356	-18.5	-18.5 0.42 (1)	10.00			
P-O	0 / 2421	-18.5	-18.5 0.43 (1)	10.00			
O-N	0 / 0	-18.5	-18.5 0.09 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.13")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.24")

CSI: TC=0.33/1.00 (K-L:1), BC=0.43/1.00 (O-P:1),
WB=0.55/1.00 (L-O:1), SS=0.17/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (O) (INPUT = 0.90)
JSI METAL= 0.72 (U) (INPUT = 1.00)




Structural component only
DWG# T-2126465

JOB NAME 420375	TRUSS NAME T6	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:54 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-OVtVDzGu5wAwJmBBTUpnNtFSib47_z9nPqO4dyrEgh



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - G	2x4	DRY	No.2	SPF	
G - I	2x4	DRY	No.2	SPF	
I - L	2x4	DRY	No.2	SPF	
V - B	2x4	DRY	No.2	SPF	
M - K	2x4	DRY	No.2	SPF	
V - S	2x4	DRY	No.2	SPF	
S - P	2x4	DRY	No.2	SPF	
P - M	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
DRY: SEASONED LUMBER.					

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0	2.00	2.75	
C, E, H, J							
C	TMVW-t	MT20	4.0	4.0	2.00	1.75	
D	TS-t	MT20	3.0	6.0			
F	TTWW-m	MT20	5.0	6.0	2.25	2.00	
G	TTW-m	MT20	4.0	4.0	2.00	1.75	
I	TS-t	MT20	3.0	6.0			
K	TMVW-t	MT20	5.0	6.0	2.00	2.75	
M	BMV1+p	MT20	3.0	4.0			
N	BMVW-t	MT20	5.0	6.0	2.50	2.50	
O, R, T							
O	BMVW-t	MT20	4.0	4.0			
P	BS-t	MT20	3.0	6.0			
Q	BMVW-t	MT20	4.0	9.0			
S	BS-t	MT20	3.0	6.0			
U	BMVW-t	MT20	5.0	6.0	2.50	2.50	
V	BMV1+p	MT20	3.0	4.0			

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
V	1971	0	1971	0
M	1971	0	1971	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED						
V	1397	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0
M	1397	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) V, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.85 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-R, H-Q.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE	FACTORED VERT. LOAD	LC1	MAX. FACTORED VERT. LOAD	LC1	MAX. FACTORED VERT. LOAD	LC1	MAX. FACTORED VERT. LOAD	LC1
MEMB.	FORCE (LBS)	FROM	TO	MEMB.	FORCE (LBS)	FROM	TO	MEMB.	FORCE (LBS)
FR-TO				FR-TO				FR-TO	
A-B	0 / 26	-84.9	-84.9	0.11 (1)	10.00	U-C	-287 / 0	0.07 (1)	
B-C	-2736 / 0	-84.9	-84.9	0.42 (1)	3.85	C-T	-210 / 0	0.15 (1)	
C-D	-2561 / 0	-84.9	-84.9	0.35 (1)	4.04	T-E	0 / 219	0.05 (4)	
D-E	-2561 / 0	-84.9	-84.9	0.35 (1)	4.04	E-R	-653 / 0	0.29 (1)	
E-F	-2105 / 0	-84.9	-84.9	0.34 (1)	4.38	R-F	0 / 576	0.13 (1)	
F-G	-1873 / 0	-84.9	-84.9	0.23 (1)	4.70	F-Q	0 / 3	0.00 (1)	
G-H	-2106 / 0	-84.9	-84.9	0.34 (1)	4.38	Q-G	0 / 580	0.13 (1)	
H-I	-2561 / 0	-84.9	-84.9	0.35 (1)	4.04	H-J	-651 / 0	0.29 (1)	
I-J	-2561 / 0	-84.9	-84.9	0.35 (1)	4.04	O-H	0 / 216	0.05 (4)	
J-K	-2737 / 0	-84.9	-84.9	0.42 (1)	3.85	O-J	-210 / 0	0.15 (1)	
K-L	0 / 26	-84.9	-84.9	0.11 (1)	10.00	N-J	-287 / 0	0.07 (1)	
V-B	-1926 / 0	0.0	0.0	0.19 (1)	6.06	B-U	0 / 2494	0.56 (1)	
M-K	-1926 / 0	0.0	0.0	0.19 (1)	6.06	N-K	0 / 2495	0.56 (1)	
V-U	0 / 0	-18.5	-18.5	0.11 (4)	10.00				
U-T	0 / 2464	-18.5	-18.5	0.45 (1)	10.00				
T-S	0 / 2291	-18.5	-18.5	0.42 (1)	10.00				
S-R	0 / 2291	-18.5	-18.5	0.42 (1)	10.00				
R-Q	0 / 1871	-18.5	-18.5	0.35 (1)	10.00				
Q-P	0 / 2290	-18.5	-18.5	0.42 (1)	10.00				
P-O	0 / 2290	-18.5	-18.5	0.42 (1)	10.00				
O-N	0 / 2464	-18.5	-18.5	0.44 (1)	10.00				
N-M	0 / 0	-18.5	-18.5	0.11 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019

- PART 9 OF OBC 2012 (2019 AMENDMENT)

- CSA 086-14

- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")

CALCULATED VERT. DEFL.(LL) = L/999 (0.13")

ALLOWABLE DEFL.(TL) = L/360 (1.20")

CALCULATED VERT. DEFL.(TL) = L/999 (0.26")

CSI: TO=0.42/1.00 (J-K:1), BC=0.45/1.00 (T-U:1), WB=0.56/1.00 (K-N:1), SS=0.19/1.00 (J-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (N) (INPUT = 0.90)

JSI METAL= 0.68 (S) (INPUT = 1.00)




Structural component only
DWG# T-2126466

JOB NAME 420375	TRUSS NAME T7	QUANTITY 9	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:55 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1I60ZyxmN3-shRtQJdvP21XTLOkA?2KbQOLiw2sR8I03axc3yrEgg



TOTAL WEIGHT = 9 X 154 = 1388 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - K	2x4	DRY	No.2
T - B	2x4	DRY	No.2
T - J	2x4	DRY	No.2
O - O	2x4	DRY	No.2
O - L	2x4	DRY	No.2
ALL WEBS EXCEPT P - F	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0	2.00	2.75
C, E, G, I						
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TS-t	MT20	3.0	6.0		
F	TTW+p	MT20	4.0	4.0		
H	TS-t	MT20	3.0	6.0		
J	TMVW-t	MT20	5.0	6.0	2.00	2.75
L	BMV1+p	MT20	3.0	4.0		
M	BMVW-t	MT20	5.0	6.0	2.50	2.50
N	BMVW-t	MT20	4.0	4.0		
O	BS-t	MT20	3.0	6.0		
P	BMVW-t	MT20	4.0	9.0		
Q	BS-t	MT20	3.0	6.0		
R	BMVW-t	MT20	4.0	4.0		
S	BMVW-t	MT20	5.0	6.0	2.50	2.50
T	BMV1+p	MT20	3.0	4.0		

NOTES-

(1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
T	1971	0	0	5-8
L	1971	0	0	5-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	WIND	DEAD	SOIL
T	1397	900 / 0	0 / 0	0 / 0	498 / 0
L	1397	900 / 0	0 / 0	0 / 0	498 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.72 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-P, E-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)
FR-TO		FROM	TO	FR-TO		FROM	TO
A-B	0 / 26	-84.9	-84.9 0.11 (1)	10.00	P-F	0 / 1295	0.21 (1)
B-C	-2764 / 0	-84.9	-84.9 0.54 (1)	3.72	P-G	-778 / 0	0.44 (1)
C-D	-2469 / 0	-84.9	-84.9 0.44 (1)	4.02	N-G	0 / 293	0.07 (1)
D-E	-2469 / 0	-84.9	-84.9 0.44 (1)	4.02	N-I	-340 / 0	0.33 (1)
E-F	-1923 / 0	-84.9	-84.9 0.42 (1)	4.45	M-I	-229 / 13	0.06 (1)
F-G	-1923 / 0	-84.9	-84.9 0.42 (1)	4.45	E-P	-778 / 0	0.44 (1)
G-H	-2469 / 0	-84.9	-84.9 0.44 (1)	4.02	R-E	0 / 293	0.07 (1)
H-I	-2469 / 0	-84.9	-84.9 0.44 (1)	4.02	C-R	-340 / 0	0.33 (1)
I-J	-2764 / 0	-84.9	-84.9 0.54 (1)	3.72	S-C	-229 / 13	0.06 (1)
J-K	0 / 26	-84.9	-84.9 0.11 (1)	10.00	B-S	0 / 2515	0.57 (1)
T-B	-1922 / 0	0.0	0.0 0.19 (1)	6.07	M-J	0 / 2515	0.57 (1)
L-J	-1922 / 0	0.0	0.0 0.19 (1)	6.07			

T-S	0 / 0	-18.5	-18.5 0.15 (4)	10.00
S-R	0 / 2491	-18.5	-18.5 0.46 (1)	10.00
R-Q	0 / 2208	-18.5	-18.5 0.44 (1)	10.00
Q-P	0 / 2208	-18.5	-18.5 0.44 (1)	10.00
P-O	0 / 2208	-18.5	-18.5 0.44 (1)	10.00
O-N	0 / 2208	-18.5	-18.5 0.44 (1)	10.00
N-M	0 / 2491	-18.5	-18.5 0.46 (1)	10.00
M-L	0 / 0	-18.5	-18.5 0.15 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (1.20")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.14")
ALLOWABLE DEFL.(TL) = $L/360$ (1.20")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.27")

CSI: TC=0.54/1.00 (I-J:1), BC=0.46/1.00 (R-S:1), WB=0.57/1.00 (B-S:1), SS=0.21/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (J) (INPUT = 0.90)

JSI METAL = 0.68 (Q) (INPUT = 1.00)



Structural component only
DWG# T-2126467

amarack floor truss, Burlington


Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Wed Aug 4 14:46:57 2021 Page 1

ID.rhtOOT9Mf?GOVQD_N1I60ZyxmN3-CykxwVPewODbZmsCDkbHnC7UZOzKzblPx5DnwEyrCrS

1-3-8 0-0 1-9-8 4-9-5 6-6-13 4-9-5 11-4-3 4-9-5 16-1-8 17-10-8 17-11-8 18-0-8 23-11-3 5-10-11 29-9-13 6-1-3 35-11-0 37-2-8

1-3-8 1-9-8 1-9-0 1-0-1 5-10-11 1-3-8

Scale = 1/8"=1'

[illegible]

<u>DESIGN CRITERIA</u>	(M)
SPECIFIED LOADS:	
TOP CH.	LL = 23.3 PSF DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF DL = 7.4 PSF
TOTAL LOAD	= 36.7 PSF
<u>SPACING = 16.0 IN. C/C</u>	
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCO 2015	
THIS DESIGN COMPLIES WITH:	
- PART 9 OF CBCO 2018 , ABC 2019	
- PART 9 OF OBC 2012 (2019 AMENDMENT)	
- CSA 086-14	

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-T, I-R, H-R.

END LATERAL BRACE(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

C H O R D S					W E B S				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO				FR-TO			
A-B	0 / 17	-56.6	-56.6	0.07 (1)	10.00	C-V	-957 / 0	0.40 (1)	
B-C	-2993 / 0	-56.6	-56.6	0.21 (1)	3.89	V-D	0 / 128	0.03 (4)	
C-D	-2384 / 0	-56.6	-56.6	0.32 (1)	4.19	D-U	-479 / 0	0.27 (1)	
D-E	-1964 / 0	-56.6	-56.6	0.22 (1)	4.64	U-F	0 / 329	0.07 (1)	
E-F	-1964 / 0	-56.6	-56.6	0.22 (1)	4.64	F-T	-558 / 0	0.60 (1)	
F-G	-1550 / 0	-56.6	-56.6	0.16 (1)	5.16	T-R	0 / 1269	0.20 (1)	
G-H	-1552 / 0	-56.6	-56.6	0.08 (1)	5.22	R-I	-515 / 0	0.30 (1)	
H-I	-1284 / 0	-56.6	-56.6	0.27 (1)	5.41	Q-I	0 / 188	0.04 (4)	
I-J	-1645 / 0	-56.6	-56.6	0.26 (1)	4.94	Q-K	-223 / 0	0.21 (1)	
J-K	-1645 / 0	-56.6	-56.6	0.26 (1)	4.94	O-K	-153 / 8	0.04 (1)	
K-L	-1840 / 0	-56.6	-56.6	0.32 (1)	4.67	O-L	0 / 1674	0.38 (1)	
L-M	0 / 17	-56.6	-56.6	0.07 (1)	10.00	R-H	-152 / 0	0.11 (1)	
Y-B	-1144 / 0	0.0	0.0	0.12 (1)	7.43	Y-W	-291 / 0	0.04 (1)	
N-L	-1280 / 0	0.0	0.0	0.13 (1)	7.13	B-W	0 / 2669	0.60 (1)	
						T-H	0 / 1276	0.29 (1)	
Y-X	0 / 242	-12.3	-12.3	0.04 (1)	10.00				
X-W	0 / 11	0.0	0.0	0.36 (1)	10.00				
W-C	0 / 334	0.0	0.0	0.42 (1)	10.00				
W-V	0 / 3102	-12.3	-12.3	0.54 (1)	10.00				
V-U	0 / 2153	-12.3	-12.3	0.38 (1)	10.00				
U-T	0 / 1753	-12.3	-12.3	0.32 (1)	10.00				
S-T	-24 / 0	0.0	0.0	0.04 (1)	7.81				
T-G	-205 / 0	0.0	0.0	0.05 (1)	6.25				
S-R	0 / 36	-12.3	-12.3	0.09 (4)	10.00				
R-Q	0 / 1472	-12.3	-12.3	0.32 (1)	10.00				
Q-P	0 / 1658	-12.3	-12.3	0.31 (1)	10.00				
P-O	0 / 1658	-12.3	-12.3	0.31 (1)	10.00				
O-N	0 / 0	-12.3	-12.3	0.10 (4)	10.00				

DESIGN ASSUMPTIONS
-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.29")

CSI: TC=0.32/1.00 (C-D:1) , BC=0.54/1.00 (V-W:1) ,
WB=0.60/1.00 (B-W:1) , SSI=0.36/1.00 (C-W:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN THE
TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 173

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (R) (INPUT = 0.90)
JSI METAL= 0.65 (W) (INPUT = 1.00)



Tamarack Roof Truss, Burlington


Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:57 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-o4Zer_e9B0llnnVmsb1WP0VglVdyKH7bTN32gyyrEge

Diagram showing dimensions and member labels for the Tamarack Roof Truss, Burlington. The diagram includes a horizontal line with various dimensions and member labels.

Dimensions (from left to right):

- 1-3-8
- 0-0
- 3-10-2
- 3-10-2
- 3-7-10
- 7-5-12
- 7-0-4
- 14-6-0
- 6-11-0
- 21-5-0
- 7-0-4
- 28-5-4
- 3-7-10
- 32-0-14
- 3-10-2
- 35-11-0
- 37-2-8
- 1-3-8

Scale = 1/60.7



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - H	2x4	DRY No.2	SPF
H - K	2x4	DRY No.2	SPF
S - B	2x4	DRY No.2	SPF
L - J	2x4	DRY No.2	SPF
S - Q	2x4	DRY No.2	SPF
Q - N	2x4	DRY No.2	SPF
N - L	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV-w	MT20	3.0	4.0	
C	TMV-W	MT20	5.0	6.0	
D	TTWW-w	MT20	5.0	6.0	1.75 1.75
E	TMW-W-t	MT20	4.0	4.0	
F	TS-t	MT20	3.0	6.0	
G	TMW-w	MT20	2.0	4.0	
H	TTWW-W	MT20	5.0	6.0	1.75 1.75
I	TMW-W-t	MT20	5.0	6.0	
J	TMV-w	MT20	3.0	4.0	
L	BMWV-1-t	MT20	5.0	6.0	
M	BMWV-t	MT20	4.0	4.0	
N	BS-t	MT20	3.0	6.0	
O	BMWVW-t	MT20	4.0	9.0	
P	BMWV-t	MT20	4.0	6.0	
Q	BS-t	MT20	3.0	6.0	
R	BMWV-t	MT20	4.0	4.0	
S	BMWV-1-t	MT20	5.0	6.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
FACTORED			MAXIMUM FACTORED			INPUT	REQD
GROSS REACTION			GROSS REACTION			BRG	BRG
ST	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
J	1974	0	1974	0	0	5-8	5-8
S	1974	0	1974	0	0	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
S	1399	901 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0
L	1399	901 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S. L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.73 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-O.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM TO			FR-TO		
A-B		-84.9	-84.9 0.12 (1)	10.00	C-R	0 / 152	0.03 (4)
B-C	0 / 32	-84.9	-84.9 0.20 (1)	10.00	R-D	0 / 109	0.04 (4)
C-D	-1936 / 0	-84.9	-84.9 0.30 (1)	4.58	D-P	0 / 1043	0.23 (1)
D-E	-2178 / 0	-84.9	-84.9 0.80 (1)	3.73	P-E	-642 / 0	0.75 (1)
E-F	-2177 / 0	-84.9	-84.9 0.80 (1)	3.73	E-O	-2 / 0	0.00 (1)
F-G	-2177 / 0	-84.9	-84.9 0.80 (1)	3.73	O-G	-641 / 0	0.75 (1)
G-H	-2177 / 0	-84.9	-84.9 0.80 (1)	3.74	O-H	0 / 1041	0.23 (1)
H-I	-1936 / 0	-84.9	-84.9 0.30 (1)	4.58	M-H	0 / 110	0.04 (4)
I-J	0 / 32	-84.9	-84.9 0.20 (2)	10.00	M-I	0 / 152	0.03 (4)
J-K	0 / 38	-84.9	-84.9 0.12 (1)	10.00	S-C	-2190 / 0	0.79 (1)
S-B	-192 / 0	0.0	0.0 0.02 (1)	7.81	I-L	-2190 / 0	0.79 (1)
L-J	-192 / 0	0.0	0.0 0.02 (1)	7.81			
S-R	0 / 1350	-18.5	-18.5 0.36 (4)	10.00			
R-Q	0 / 1468	-18.5	-18.5 0.38 (4)	10.00			
Q-P	0 / 1468	-18.5	-18.5 0.38 (4)	10.00			
P-O	0 / 2178	-18.5	-18.5 0.43 (1)	10.00			
O-N	0 / 1469	-18.5	-18.5 0.38 (4)	10.00			
N-M	0 / 1469	-18.5	-18.5 0.38 (4)	10.00			
M-L	0 / 1350	-18.5	-18.5 0.36 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL =	23.3	PSF
		DL =	6.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.4	PSF

TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIQ 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL(LL)= L/360 (1.20")
CALCULATED VERT. DEFL(LL) = L/ 999 (0.10")
ALLOWABLE DEFL(TL)= L/360 (1.20")
CALCULATED VERT. DEFL(TL) = L/ 999 (0.22")

CSI: TC=0.80/1.00 (D-E:1), BC=0.43/1.00 (O-P:1),
WB=0.79/1.00 (I-L:1), SSI=0.28/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (I) (INPUT = 0.90)
JSI METAL= 0.49 (I) (INPUT = 1.00)



Structural component only
DWG# T-2126469

JOB NAME 420375	TRUSS NAME T9	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					


Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:58 2021 Page 1

ID:rhT0OT9Mf?GOVQD_N1l60ZyxmN3-GG702KfnyKQcOw4yQlZlxD2yTv_S3rFki1obDOyrEgd

1-3-8 0-0 4-10-2 4-10-2 4-7-10 9-5-12 5-8-4 15-2-0 5-7-0 20-9-0 5-8-4 26-5-4 4-7-10 31-0-14 4-10-2 35-11-0 37-2-8 1-3-8

Scale = 1:60.5



LUMBER				DESIGN CRITERIA			
N. L. G. A. RULES				TOTAL WEIGHT = 2 X 187 = 375 lb			
CHORDS				BEARINGS			
A - D	2x4	DRY	No.2	FACTORED	MAXIMUM FACTORED	INPUT	REQD
D - F	2x4	DRY	No.2	GROSS REACTION	GROSS REACTION	BRG	BRG
F - H	2x4	DRY	No.2	JT VERT	DOWN	UPLIFT	IN-SX
H - K	2x4	DRY	No.2	U 1974	0	5-8	5-8
U - B	2x4	DRY	No.2	L 1974	0	5-8	5-8
L - J	2x4	DRY	No.2	UNFACTORED REACTIONS			
U - R	2x4	DRY	No.2	1ST LOASE	MAX./MIN.	COMPONENT REACTIONS	
R - O	2x4	DRY	No.2	JT COMBINED	SNOW	LIVE	PERM.LIVE
O - L	2x4	DRY	No.2	U 1399	901 / 0	0 / 0	0 / 0
				L 1399	901 / 0	0 / 0	0 / 0
ALL WEBS				BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, L			
EXCEPT				BRACING			
D - Q	2x4	DRY	No.2	TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.58 FT.			
E - P	2x4	DRY	No.2	MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.			
P - H	2x4	DRY	No.2	ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.			
DRY: SEASONED LUMBER.				1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, E-P, G-P.			
				END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW			

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMVW-t	MT20	5.0	6.0	2.50 2.50
C TMVW-t	MT20	4.0	4.0	2.00 1.25
D TTWW+m	MT20	5.0	6.0	2.25 1.50
E TMVW-t	MT20	4.0	4.0	
F TS-t	MT20	3.0	6.0	
G TMVW+w	MT20	2.0	4.0	
H TTWW+m	MT20	5.0	6.0	2.25 1.50
I TMVW-t	MT20	4.0	4.0	2.00 1.25
J TMVW-t	MT20	5.0	6.0	2.50 2.50
L BMV1+p	MT20	3.0	4.0	
M BMVW-t	MT20	5.0	6.0	
N, Q, S				
N BMVW-t	MT20	4.0	4.0	
O BS-t	MT20	3.0	6.0	
P BMVWW-t	MT20	4.0	9.0	
R BS-t	MT20	3.0	6.0	
T BMVW-t	MT20	5.0	6.0	
U BMV1+p	MT20	3.0	4.0	


NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.



Structural component only
DWG# T-2126470

JOB NAME 420375	TRUSS NAME T10	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:59 2021 Page 1
ID:rhTOOT9Mf?GOVQD_N1I60ZyxmN3-ISgOGggPjeYT04f9z04_URb5xJLD0G5uwhY8lqyrEgc



LUMBER				N. L. G. A. RULES	
CHORDS	SIZE	LUMBER	DESCR.	SPF	NO.2
A - D	2x4	DRY	No.2	SPF	
D - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
G - H	2x4	DRY	No.2	SPF	
H - K	2x4	DRY	No.2	SPF	
T - B	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
T - Q	2x4	DRY	No.2	SPF	
Q - O	2x4	DRY	No.2	SPF	
O - L	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x4	DRY	No.2	SPF	
S - C	2x3	DRY	No.2	SPF	
C - R	2x3	DRY	No.2	SPF	
N - I	2x3	DRY	No.2	SPF	
M - J	2x3	DRY	No.2	SPF	
B - S	2x3	DRY	No.2	SPF	
M - J	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-t	MT20	5.0	6.0	2.50	2.50
C TMVW-t	MT20	4.0	4.0	2.00	1.25
D TS-t	MT20	3.0	6.0		
E TTWW-m	MT20	5.0	8.0	Edge 3.00	
F TMW+w	MT20	2.0	4.0		
G TTWW-m	MT20	5.0	8.0	Edge 3.00	
H TS-t	MT20	3.0	6.0		
I TMVW-t	MT20	4.0	4.0	2.00	1.25
J TMVW-t	MT20	5.0	6.0	2.50	2.50
L BMV1+p	MT20	3.0	4.0		
M BMWW-t	MT20	5.0	6.0		
N BMWW-t	MT20	4.0	4.0		
O BS-t	MT20	3.0	6.0		
P BMWW-t	MT20	4.0	9.0		
Q BS-t	MT20	3.0	6.0		
R BMWW-t	MT20	4.0	4.0		
S BMWW-t	MT20	5.0	6.0		
T BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	VERT	HORZ	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
T	1974	0	1974	0	5-8	5-8
L	1974	0	1974	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
T	1399	901 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0
L	1399	901 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.37 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-R, F-P, I-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC) MAX	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC) MAX	MAX. FACTORED VERT. LOAD (LC) MAX
FR-TO		FROM TO	CSI (LC)	FR-TO		FROM TO	CSI (LC)
A-B	0 / 38	-84.9	-84.9 0.12 (1)	10.00	S-C	-227 / 9	0.16 (1)
B-C	-1960 / 0	-84.9	-84.9 0.47 (1)	4.37	C-R	-296 / 0	0.14 (1)
C-D	-1776 / 0	-84.9	-84.9 0.44 (1)	4.57	R-E	0 / 327	0.05 (1)
D-E	-1776 / 0	-84.9	-84.9 0.44 (1)	4.57	E-P	0 / 461	0.07 (1)
E-F	-1572 / 0	-84.9	-84.9 0.50 (1)	4.65	P-F	-673 / 0	0.44 (1)
F-G	-1572 / 0	-84.9	-84.9 0.50 (1)	4.65	P-G	0 / 461	0.07 (1)
G-H	-1776 / 0	-84.9	-84.9 0.44 (1)	4.57	N-G	0 / 328	0.05 (1)
H-I	-1776 / 0	-84.9	-84.9 0.44 (1)	4.57	N-I	-296 / 0	0.14 (1)
I-J	-1960 / 0	-84.9	-84.9 0.47 (1)	4.37	M-I	-227 / 9	0.16 (1)
J-K	0 / 38	-84.9	-84.9 0.12 (1)	10.00	B-S	0 / 1572	0.35 (1)
T-B	-1928 / 0	0.0	0.0 0.21 (1)	6.06	M-J	0 / 1572	0.35 (1)
L-J	-1928 / 0	0.0	0.0 0.21 (1)	6.06			

T-S	0 / 0	-18.5	-18.5 0.14 (4)	10.00
S-R	0 / 1535	-18.5	-18.5 0.32 (1)	10.00
R-Q	0 / 1337	-18.5	-18.5 0.30 (1)	10.00
Q-P	0 / 1337	-18.5	-18.5 0.30 (1)	10.00
P-O	0 / 1337	-18.5	-18.5 0.30 (1)	10.00
O-N	0 / 1337	-18.5	-18.5 0.30 (1)	10.00
N-M	0 / 1535	-18.5	-18.5 0.32 (1)	10.00
M-L	0 / 0	-18.5	-18.5 0.14 (4)	10.00

TOTAL WEIGHT = 2 X 193 = 386 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 23.3	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.14")

CSI: TC=0.50/1.00 (E-F:1), BC=0.32/1.00 (M-N:1), WB=0.44/1.00 (F-P:1), SS=0.27/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.83 (J) (INPUT = 0.90)
JSI METAL= 0.50 (J) (INPUT = 1.00)




Structural component only
DWG# T-2126471

JOB NAME 420375	TRUSS NAME T11	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:42:00 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-DfEmT0h1UxgKeEDLXjbD1e7GXjZZXfx19LHhHyrEgb



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - G	2x4	DRY	No.2	SPF	
G - J	2x4	DRY	No.2	SPF	
J - L	2x4	DRY	No.2	SPF	
V - B	2x6	DRY	No.2	SPF	
M - K	2x6	DRY	No.2	SPF	
V - S	2x6	DRY	No.2	SPF	
S - P	2x6	DRY	No.2	SPF	
P - M	2x6	DRY	No.2	SPF	
ALL WEBS EXCEPT B - U	2x3	DRY	No.2	SPF	
N - K	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C	12	TOP
C-G	12	TOP
G-J	12	TOP
J-L	12	TOP
V-B	12	TOP
M-K	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
V-S	12	SIDE(183.1)
S-P	12	SIDE(0.1)
P-M	12	TOP
WEBS : (0.122"x3") SPIRAL NAILS		
T-D	6	SIDE(179.4)
2x3	6	
2x4	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT 3790	DOWN 3790	0	5-8
V	HORZ 0	HORZ 0	0	5-8
M	0	0	0	5-8

UNFACTORED REACTIONS

1ST LOASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	2681	1755 / 0	0 / 0	0 / 0	0 / 0	927 / 0	0 / 0
V	2270	1477 / 0	0 / 0	0 / 0	0 / 0	793 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) V, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.47 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	MAX. FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX. (PLF)	MEMB.	FORCE (LBS)
FR-TO		FROM TO		FR-TO	
A-B	0 / 38	-84.9	-84.9 0.06 (1)	U-C	-540 / 0
B-C	-4209 / 0	-84.9	-84.9 0.42 (1)	N-J	-433 / 0
C-D	-5936 / 0	-84.9	-84.9 0.45 (1)	B-U	0 / 3303
D-W	-6589 / 0	-84.9	-84.9 0.44 (1)	N-K	0 / 2735
W-X	-6589 / 0	-84.9	-84.9 0.44 (1)	T-D	-1429 / 0
X-E	-6589 / 0	-84.9	-84.9 0.44 (1)	O-I	-2256 / 0
E-Y	-6589 / 0	-84.9	-84.9 0.28 (1)	C-T	0 / 3902
Y-F	-6589 / 0	-84.9	-84.9 0.28 (1)	O-J	0 / 3100
F-G	-6192 / 0	-84.9	-84.9 0.17 (1)	Q-I	0 / 2222
G-H	-6192 / 0	-84.9	-84.9 0.17 (1)	D-R	0 / 1060
H-I	-6192 / 0	-84.9	-84.9 0.38 (1)	Q-H	-247 / 0
I-J	-4824 / 0	-84.9	-84.9 0.34 (1)	R-E	-599 / 0
J-K	-3484 / 0	-84.9	-84.9 0.37 (1)	R-F	0 / 443
K-L	0 / 38	-84.9	-84.9 0.06 (1)	F-Q	-647 / 0
V-B	-3758 / 0	0.0	0.0 0.14 (1)		
M-K	-3172 / 0	0.0	0.0 0.12 (1)		

V-U	0 / 0	-18.5	-18.5 0.05 (4)	10.00
U-T	0 / 3217	-18.5	-18.5 0.26 (1)	10.00
T-S	0 / 5936	-18.5	-18.5 0.49 (1)	10.00
S-Z	0 / 5936	-18.5	-18.5 0.49 (1)	10.00
Z-AA	0 / 5936	-18.5	-18.5 0.49 (1)	10.00
AA-R	0 / 5936	-18.5	-18.5 0.49 (1)	10.00
R-AB	0 / 6427	-18.5	-18.5 0.76 (1)	10.00
AB-AC	0 / 6427	-18.5	-18.5 0.76 (1)	10.00
AC-Q	0 / 6427	-18.5	-18.5 0.76 (1)	10.00
Q-P	0 / 4824	-18.5	-18.5 0.44 (1)	10.00
P-O	0 / 4824	-18.5	-18.5 0.44 (1)	10.00
O-N	0 / 2664	-18.5	-18.5 0.21 (1)	10.00
N-M	0 / 0	-18.5	-18.5 0.04 (4)	10.00

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
T	11-1-8	-978	-978	---	BACK	VERT	TOTAL	---	C1
W	13-0-12	-102	-102	---	BACK	VERT	TOTAL	---	C1
X	15-0-12	-102	-102	---	BACK	VERT	TOTAL	---	C1
Y	16-7-4	-102	-102	---	BACK	VERT	TOTAL	---	C1
Z	13-0-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
AA	15-0-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
AB	16-7-4	-26	-26	---	BACK	VERT	TOTAL	---	C1
AC	18-6-8	-793	-793	---	BACK	VERT	TOTAL	---	C1

TOTAL WEIGHT = 2 X 190 = 379 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.17")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.31")

CSI: TC=0.45/1.00 (C-D:1), BC=0.76/1.00 (Q-R:1),
WB=0.66/1.00 (I-O:1), SSI=0.25/1.00 (Q-R:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (T) (INPUT = 0.90)
JSI METAL= 0.55 (S) (INPUT = 1.00)



Structural component only
DWG# T-2126472

CONTINUED ON PAGE 2

JOB NAME 420375	TRUSS NAME T11	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:42:00 2021 Page 2
ID:rhOOT9Mf?GOVQD N160ZyxmN3-DfEmT0h1UxgKeEDLXjbD1e7GXjZZXfx19LHihHyrEgb

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	Edge	
C	TTWW+m	MT20	6.0	9.0	Edge	1.75
D	TMWW-t	MT20	4.0	6.0		
E	TMW+w	MT20	2.0	4.0		
F	TMWW-t	MT20	4.0	4.0		
G	TS-t	MT20	3.0	6.0		
H	TMW+w	MT20	2.0	4.0		
I	TMWW-t	MT20	4.0	6.0		
J	TTWW+m	MT20	6.0	9.0	Edge	1.75
K	TMVW-p	MT20	5.0	8.0	Edge	
M	BMV1+p	MT20	3.0	6.0		
N	BMWW-t	MT20	5.0	6.0		
O	BMWW-t	MT20	5.0	6.0	2.50	2.50
P	BS-t	MT20	5.0	6.0		
Q	BMWWW-t	MT20	5.0	8.0		
R	BMWWWW-t	MT20	5.0	8.0		
S	BS-t	MT20	5.0	6.0		
T	BMWW-t	MT20	5.0	6.0	2.50	2.50
U	BMWW-t	MT20	5.0	6.0		
V	BMV1+p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES: (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS


1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2126472 *mn*

JOB NAME 420375	TRUSS NAME T12	QUANTITY 3	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:42:01 2021 Page 1
ID:rhtOOT9Mf?GOVQD_N1i60ZyrmN3-hro8hMiffFoBFOoX5R6SZsgT872BGGUAO?1FqjyrEga



Scale = 1:36.2

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - C	2x4 DRY	No.2	SPF
C - E	2x4 DRY	No.2	SPF
H - B	2x4 DRY	No.2	SPF
F - D	2x4 DRY	No.2	SPF
H - F	2x4 DRY	No.2	SPF
ALL WEBS EXCEPT	2x3 DRY	No.2	SPF

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
C	TTW+p	MT20	4.0	6.0	Edge
D	TMVW+p	MT20	4.0	4.0	1.00 2.00
F	BMV1+p	MT20	3.0	4.0	
G	BMVWW-t	MT20	4.0	9.0	
H	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

- NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX
H	686	0	686	0	5-8	5-8
F	686	0	686	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	485	321 / 0	0 / 0	0 / 0	0 / 0	164 / 0	0 / 0
F	485	321 / 0	0 / 0	0 / 0	0 / 0	164 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)
FR-TO				FR-TO			
A-B	0 / 38	-84.9	-84.9 0.12 (1)	G-C	-6 / 90	10.00	0.03 (4)
B-C	-360 / 0	-84.9	-84.9 0.33 (1)	B-G	0 / 284	6.25	0.06 (1)
C-D	-360 / 0	-84.9	-84.9 0.33 (1)	G-D	0 / 284	6.25	0.06 (1)
D-E	0 / 38	-84.9	-84.9 0.12 (1)				
H-B	-647 / 0	0.0	0.0 0.07 (1)				
F-D	-647 / 0	0.0	0.0 0.07 (1)				
H-G	0 / 0	-18.5	-18.5 0.16 (4)				
G-F	0 / 0	-18.5	-18.5 0.16 (4)				

TOTAL WEIGHT = 3 X 49 = 147 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.37")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.37")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.33/1.00 (C-D:1), BC=0.16/1.00 (G-H:4), WB=0.06/1.00 (D-G:1), SSI=0.14/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.54 (D) (INPUT = 0.90)
JSI METAL = 0.15 (D) (INPUT = 1.00)



Structural component only
DWG# T-2126473

JOB NAME 420375	TRUSS NAME T12S	QUANTITY 4	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:42:02 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1i60ZyxnM3-91MWuill0Zx2tYnkf8dh63DhtWP3?i_KdfmpM9yrEgZ



TOTAL WEIGHT = 4 X 57 = 227 lb

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - D	2x4 DRY	No.2	SPF
D - G	2x4 DRY	No.2	SPF
N - B	2x4 DRY	No.2	SPF
H - F	2x4 DRY	No.2	SPF
N - M	2x4 DRY	No.2	SPF
M - C	2x4 DRY	No.2	SPF
L - J	2x4 DRY	No.2	SPF
I - E	2x4 DRY	No.2	SPF
I - H	2x4 DRY	No.2	SPF
ALL WEBS	2x3 DRY	No.2	SPF
EXCEPT			
DRY: SEASONED LUMBER.			

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B, C, E, F				
B	TMVW+p	MT20	4.0	4.0 1.00 2.00
D	TTW+p	MT20	4.0	6.0 Edge
H	BMVW1-t	MT20	4.0	4.0
I	BMV+p	MT20	3.0	4.0
J	BVMWW-t	MT20	5.0	12.0 Edge 7.00
K	BMVWW-t	MT20	4.0	9.0
L	BVMWW-t	MT20	5.0	12.0 Edge 7.00
M	BMV+p	MT20	3.0	4.0
N	BMVW1-t	MT20	4.0	4.0

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION		DOWN	HORIZ	UPLIFT	IN-SX
JT	VERT	0	0	0	0
N	VERT	686	0	0	0
H	VERT	686	0	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN.	COMPONENT REACTIONS				
N	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
N	485	321 / 0	0 / 0	0 / 0	0 / 0	164 / 0	0 / 0
H	485	321 / 0	0 / 0	0 / 0	0 / 0	164 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MEMB.	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX
MEMB.		FORCE	(LBS)	(PLF)	CSI	(LC)	UNBRAC	FORCE	(LBS)	(PLF)	CSI	(LC)
FR-TO							LENGTH	FR-TO				
A-B	0 / 38	-84.9	-84.9	0.12	(1)	10.00	K-D	0 / 247	0.06	(1)		
B-C	-637 / 0	-84.9	-84.9	0.09	(1)	6.25	K-E	-213 / 0	0.06	(1)		
C-D	-417 / 0	-84.9	-84.9	0.14	(1)	6.25	C-K	-213 / 0	0.06	(1)		
D-E	-417 / 0	-84.9	-84.9	0.14	(1)	6.25	N-L	-18 / 0	0.00	(1)		
E-F	-637 / 0	-84.9	-84.9	0.09	(1)	6.25	B-L	0 / 493	0.11	(1)		
F-G	0 / 38	-84.9	-84.9	0.12	(1)	10.00	J-H	-18 / 0	0.00	(1)		
N-B	-660 / 0	0.0	0.0	0.07	(1)	7.81	J-F	0 / 493	0.11	(1)		
H-F	-660 / 0	0.0	0.0	0.07	(1)	7.81						
N-M	0 / 16	-18.5	-18.5	0.02	(4)	10.00						
M-L	0 / 19	0.0	0.0	0.03	(1)	10.00						
L-C	-12 / 28	0.0	0.0	0.02	(4)	7.81						
L-K	0 / 500	-18.5	-18.5	0.12	(1)	10.00						
K-J	0 / 500	-18.5	-18.5	0.12	(1)	10.00						
I-J	0 / 19	0.0	0.0	0.03	(1)	10.00						
J-E	-12 / 28	0.0	0.0	0.02	(4)	7.81						
I-H	0 / 16	-18.5	-18.5	0.02	(4)	10.00						

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.37")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.37")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TO=0.14/1.00 (C-D:1), BC=0.12/1.00 (K-L:1), WB=0.11/1.00 (B-L:1), SSI=0.11/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.69 (F) (INPUT = 0.90)
JSI METAL= 0.19 (F) (INPUT = 1.00)



Structural component only
DWG# T-2126474

JOB NAME 420375	TRUSS NAME T13	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:42:03 2021 Page 1
ID:rhT9Mf?GOVQD_N1160ZyxnN3-dEwv62jwns3uViywCs8weHlr4wetkAzTrJWMucyrEgY



Scale = 1:34.7

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
D - A	2x4	DRY	No.2	SPF
A - B	2x4	DRY	No.2	SPF
C - B	2x4	DRY	No.2	SPF
D - C	2x6	DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF				
DRY: SEASONED LUMBER.				

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
D - A 1	12	TOP
A - B 1	12	TOP
B - C 1	12	SIDE(53.5)
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D - C 2	12	SIDE(122.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TMV+p	MT20	3.0	4.0		
C	BMVW1+p	MT20	4.0	6.0		
D	BMV1+p	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
D	1167	0	1167	0	5-8	5-8		
C	1408	0	1408	0	5-8	5-8		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 4-0.

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
D	823	552 / 0	0 / 0	0 / 0	0 / 0	271 / 0	0 / 0
C	993	665 / 0	0 / 0	0 / 0	0 / 0	328 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		MAX. FACTORED		WEBS		MAX. FACTORED	
	FR-TO	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	CS1 (LC)	UNBRAC LENGTH	FR-TO	MEMB.	FORCE (LBS)	MAX CS1 (LC)
D-A	-232 / 0	0.0	0.0	0.01 (1)	7.81		A-C	0 / 0	0.00 (1)	
A-B	0 / 0	-84.9	-84.9	0.24 (1)	10.00					
C-B	-232 / 0	0.0	0.0	0.08 (1)	7.81					
D-E	0 / 0	-18.5	-18.5	0.53 (1)	10.00					
E-F	0 / 0	-18.5	-18.5	0.53 (1)	10.00					
F-G	0 / 0	-18.5	-18.5	0.53 (1)	10.00					
G-C	0 / 0	-18.5	-18.5	0.53 (1)	10.00					

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	1-0-12	-470	-470	---	FRONT	VERT	TOTAL	---	C1
F	3-0-12	-470	-470	---	FRONT	VERT	TOTAL	---	C1
G	5-0-12	-474	-474	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 30 = 59 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/597 (0.11")

CSI: TC=0.24/1.00 (A-B:1), BC=0.53/1.00 (C-D:1),
WB=0.00/1.00 (A-C:1), SS=0.39/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.09 (A) (INPUT = 0.90)


JSI METAL = 0.04 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126475

JOB NAME 420375	TRUSS NAME T13Z	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:42:04 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-5QUHJOKYYABl6rX6mZg9BUl0qKzDTdDd4zFvQ2yrEgX



Scale = 1:34.7

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
D - A	2x4 DRY	No.2	SPF
A - B	2x4 DRY	No.2	SPF
C - B	2x4 DRY	No.2	SPF
D - C	2x6 DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF			
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
D-A 1	12	TOP
A-B 1	12	TOP
B-C 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D-C 2	12	SIDE (0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
D	1173	0	1173	0	5-8	5-8		
C	1140	0	1140	0	MECHANICAL			

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 4-0.

UNFACTORED REACTIONS

JT	1ST CASE		MAX/MIN. COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
D	831	537 / 0	0 / 0	0 / 0	0 / 0	294 / 0	0 / 0
C	807	522 / 0	0 / 0	0 / 0	0 / 0	286 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRACED LENGTH	MEMB. FR-TO	MAX. FORCE (LBS)	MAX. CSI (LC)
D-A	-232 / 0	0.0	0.0	0.01 (1)	7.81	A-C	0 / 0	0.00 (1)
A-B	0 / 0	-84.9	-84.9	0.24 (1)	10.00			
C-B	-232 / 0	0.0	0.0	0.08 (1)	7.81			
D-E	0 / 0	-18.5	-18.5	0.59 (1)	10.00			
E-F	0 / 0	-18.5	-18.5	0.59 (1)	10.00			
F-C	0 / 0	-18.5	-18.5	0.59 (1)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	1-8-4	-618	-618	---	BACK	VERT	TOTAL	---	C1
F	3-8-4	-618	-618	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 30 = 59 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL (LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL (LL) = $L/961$ (0.07")
ALLOWABLE DEFL (TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL (TL) = $L/493$ (0.13")

CSI: TC=0.24/1.00 (A-B:1), BC=0.59/1.00 (C-D:1),
WB=0.00/1.00 (A-C:1), SSI=0.31/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.09 (A) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126476

JOB NAME 420375	TRUSS NAME T14	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:42:05 2021 Page 1
ID:rhT00T9Mf?GOVQD_N1i60ZyxmN3-Zc2FWjA1UJck?6JKHB0kirBrkQEC1YmJd?TzUyrEgW



TOTAL WEIGHT = 97 lb
(M/F)

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - G	2x4	DRY	No.2
N - B	2x4	DRY	No.2
H - G	2x4	DRY	No.2
N - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00	2.00
C	TMVW-t	MT20	4.0	4.0	2.00	1.25
D	TTWW+m	MT20	5.0	6.0	2.25	1.50
E	TTW-m	MT20	4.0	4.0		
F	TMVW-t	MT20	4.0	4.0	2.00	1.25
G	TMVW+p	MT20	4.0	4.0	1.00	2.00
H	BMV1+p	MT20	3.0	4.0		
I	BMVW-t	MT20	4.0	4.0		
J	BS-t	MT20	3.0	6.0		
K	BMVWW-t	MT20	4.0	6.0	2.00	1.50
L	BMVW-t	MT20	4.0	4.0		
M	BMVW-t	MT20	4.0	6.0		
N	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
H	891	0	891	0	0	231	0	0	0
N	1009	0	1009	0	0	248	0	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 3-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS
H	833	402 / 0	0 / 0
N	714	466 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF D-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 38	-84.9 -84.9	0.12 (1)	M-C	-83 / 44	0.04 (1)	
B-C	-796 / 0	-84.9 -84.9	0.22 (1)	C-L	-297 / 0	0.25 (1)	
C-D	-601 / 0	-84.9 -84.9	0.22 (1)	D-K	0 / 246	0.06 (1)	
D-E	-428 / 0	-84.9 -84.9	0.03 (1)	E-K	-81 / 0	0.04 (1)	
E-F	-578 / 0	-84.9 -84.9	0.18 (1)	K-E	0 / 143	0.03 (1)	
F-G	-499 / 0	-84.9 -84.9	0.15 (1)	K-F	0 / 22	0.01 (1)	
N-B	-975 / 0	0.0 0.0	0.10 (1)	I-F	-413 / 0	0.18 (1)	
H-G	-875 / 0	0.0 0.0	0.16 (1)	B-M	0 / 659	0.15 (1)	
				I-G	0 / 633	0.14 (1)	
N-M	0 / 0	-18.5 -18.5	0.09 (4)				
M-L	0 / 633	-18.5 -18.5	0.15 (1)				
L-K	0 / 441	-18.5 -18.5	0.12 (1)				
K-J	0 / 412	-18.5 -18.5	0.11 (1)				
J-I	0 / 412	-18.5 -18.5	0.11 (1)				
I-H	0 / 0	-18.5 -18.5	0.05 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.58")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/380 (0.58")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.22/1.00 (B-C:1), BC=0.15/1.00 (L-M:1), WB=0.25/1.00 (C-L:1), SSI=0.14/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.89 (B) (INPUT = 0.90)
JSI METAL= 0.25 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126477

JOB NAME 420375	TRUSS NAME T15	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:42:05 2021 Page 1
ID:rhOOT9Mf?GOVQD_N1I60ZyxmN3-Zc2FWjAIUJck?6JKHBOKir97kPsC_amJd?TzUyrEgW



TOTAL WEIGHT = 81 lb
(M/F)

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - F	2x4	DRY	No.2
K - B	2x4	DRY	No.2
G - F	2x4	DRY	No.2
K - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVW-t	MT20	4.0	6.0		
D	TTW-m	MT20	4.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMVW+p	MT20	4.0	4.0	1.00	2.00
G	BMV1+p	MT20	3.0	4.0		
H	BMVW-t	MT20	4.0	4.0		
I	BS-t	MT20	3.0	6.0		
J	BMVWW-t	MT20	4.0	9.0		
K	BMVW1-t	MT20	4.0	4.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
K	1009	0	1009	0
G	891	0	891	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
K	714	466 / 0	0 / 0	0 / 0	0 / 0	248 / 0	0 / 0	
G	633	402 / 0	0 / 0	0 / 0	0 / 0	231 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH FR-TO	MAX. FACTORED CSI (LC)
FR-TO		FROM	TO	FR-TO			
A-B	0 / 38	-84.9	-84.9 0.12 (1)	10.00	C-J	-102 / 4	0.05 (1)
B-C	0 / 21	-84.9	-84.9 0.16 (1)	10.00	J-D	0 / 100	0.03 (4)
C-D	-715 / 0	-84.9	-84.9 0.13 (1)	6.25	J-E	0 / 139	0.03 (1)
D-E	-533 / 0	-84.9	-84.9 0.33 (1)	6.25	H-E	-173 / 6	0.17 (1)
E-F	-588 / 0	-84.9	-84.9 0.26 (1)	6.25	K-C	-941 / 0	0.44 (1)
K-B	-229 / 0	0.0	0.0 0.02 (1)	7.81	H-F	0 / 525	0.12 (1)
G-F	-853 / 0	0.0	0.0 0.16 (1)	7.81			
K-J	0 / 598	-18.5	-18.5 0.24 (4)	10.00			
J-I	0 / 448	-18.5	-18.5 0.23 (4)	10.00			
I-H	0 / 448	-18.5	-18.5 0.23 (4)	10.00			
H-G	0 / 0	-18.5	-18.5 0.09 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.58")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.58")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.08")

CSI: TC=0.33/1.00 (D-E:1), BC=0.24/1.00 (J-K:4), WB=0.44/1.00 (C-K:1), SSI=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.71 (K) (INPUT = 0.90)
JSI METAL= 0.21 (C) (INPUT = 1.00)



Structural component only
DWG# T-2126478




JSI GRIP= 0.89 (G) (INPUT = 0.90)
JSI METAL= 0.58 (G) (INPUT = 1.00)



JOB NAME 420375	TRUSS NAME T17	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
---------------------------	--------------------------	----------------------	-----------------	--------------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:42:08 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1I60ZyxmN3-_Bjo9ln2bPhBbTrt?Pk5LKSjWxRePRCC?ad7ZpyrEgT



Scale: 3/8"=1'

TOTAL WEIGHT = 2 X 21 = 42 lb

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
D - A	2x4	DRY	No.2 SPF
A - B	2x4	DRY	No.2 SPF
C - B	2x4	DRY	No.2 SPF
D - C	2x6	DRY	No.2 SPF
ALL WEBS	2x3	DRY	No.2 SPF
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
D-A 1	12	TOP
A-B 1	12	TOP
B-C 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D-C 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TMV+p	MT20	3.0	4.0		
C	BMVW1+p	MT20	4.0	6.0		
D	BMV1+p	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ
JT				
D	569	0	569	0
C	395	0	395	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 2'-0."

UNFACTORED REACTIONS

	1ST LOASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
D	402	269 / 0	0 / 0	0 / 0	0 / 0	133 / 0	0 / 0
C	279	186 / 0	0 / 0	0 / 0	0 / 0	94 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO	FR-TO			
D-A	-122 / 0	0.0	0.0 0.01 (1)	7.81	A-C	0 / 0	0.00 (1)
A-B	0 / 0	-84.9	-84.9 0.07 (1)	10.00			
C-B	-122 / 0	0.0	0.0 0.03 (1)	7.81			
D-E	0 / 0	-18.5	-18.5 0.17 (1)	10.00			
E-C	0 / 0	-18.5	-18.5 0.17 (1)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	1-0-12	-470	-470	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.07/1.00 (A-B:1), BC=0.17/1.00 (C-D:1), WB=0.00/1.00 (A-C:1), SS=0.15/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.05 (A) (INPUT = 0.90)
JSI METAL= 0.02 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126480

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	2.00	3.00
C	TTWW-m	MT20	5.0	6.0	2.00	1.75
D, H, I						
D	TMVW-t	MT20	4.0	4.0		
E	TMVW-t	MT20	4.0	6.0		
F	TMV-p	MT20	3.0	4.0		
G	TS-t	MT20	3.0	6.0		
J	TTWW-m	MT20	5.0	8.0	2.25	3.00
K	TMVW-p	MT20	4.0	4.0	1.50	2.00
L	TMVW-p	MT20	5.0	8.0	2.00	3.50
N	BMVW-t	MT20	5.0	6.0		
O	BMV-p	MT20	3.0	6.0		
P	BVMWW-I	MT20	5.0	16.0	2.25	9.50
Q, R, S, X, Y						
Q	BMVW-t	MT20	5.0	6.0		
T	BVMWWW-I	MT20	8.0	12.0	4.50	4.50
U	BMV-p	MT20	3.0	6.0		
V	BMVWW-t	MT20	6.0	10.0		
W	BS-t	MT20	5.0	6.0		
Z	BMV1+p	MT20	3.0	6.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

LOADING

TOTAL LOAD CASES: (4)

C H O R D S				W E B S			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO			FR-TO		
AS-AT	0 / 7259	-18.5	-18.5 0.32 (1)	10.00			
AT-Q	0 / 7259	-18.5	-18.5 0.32 (1)	10.00			
Q-AU	0 / 10112	-18.5	-18.5 0.42 (1)	10.00			
AU-AV	0 / 10112	-18.5	-18.5 0.42 (1)	10.00			
AV-P	0 / 10112	-18.5	-18.5 0.42 (1)	10.00			
O-P	0 / 17	0.0	0.0 0.39 (1)	10.00			
P-K	0 / 1164	0.0	0.0 0.45 (1)	10.00			
O-N	0 / 869	-18.5	-18.5 0.04 (1)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-374	-374	---	FRONT	VERT	TOTAL	---	C1
D	9-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
E	13-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
F	17-11-8	-113	-113	---	FRONT	VERT	TOTAL	---	C1
J	30-0-8	-30	-30	---	FRONT	VERT	DEAD	---	C1
J	30-0-8	-134	-134	---	FRONT	VERT	SNOW	---	C1
P	34-3-4	-345	-345	---	FRONT	VERT	TOTAL	---	C1
U	18-1-12	-35	-35	---	FRONT	VERT	TOTAL	---	C1
V	13-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
W	11-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
X	9-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
Y	5-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AA	7-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AB	11-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AC	15-11-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AD	18-5-12	-69	-69	---	FRONT	VERT	TOTAL	---	C1
AE	20-5-12	-69	-69	---	FRONT	VERT	TOTAL	---	C1
AF	22-5-12	-69	-69	---	FRONT	VERT	TOTAL	---	C1
AG	24-5-12	-69	-69	---	FRONT	VERT	TOTAL	---	C1
AH	26-5-12	-69	-69	---	FRONT	VERT	TOTAL	---	C1
AI	28-5-12	-69	-69	---	FRONT	VERT	TOTAL	---	C1
AJ	30-5-12	-86	-86	---	FRONT	VERT	TOTAL	---	C1
AK	1-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AL	3-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AM	7-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AN	15-11-4	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AO	18-5-12	-69	-69	---	FRONT	VERT	TOTAL	---	C1
AP	20-5-12	-64	-64	---	FRONT	VERT	TOTAL	---	C1
AQ	22-5-12	-64	-64	---	FRONT	VERT	TOTAL	---	C1
AR	24-5-12	-64	-64	---	FRONT	VERT	TOTAL	---	C1
AS	26-5-12	-64	-64	---	FRONT	VERT	TOTAL	---	C1
AT	28-5-12	-64	-64	---	FRONT	VERT	TOTAL	---	C1
AU	30-5-12	-64	-64	---	FRONT	VERT	TOTAL	---	C1
AV	32-5-12	-64	-64	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.


JSI GRIP= 0.90 (L) (INPUT = 0.90)
JSI METAL= 0.57 (P) (INPUT = 1.00)



Structural component only
DWG# T-2126483

Version 8.420 5 Jan 21 2021 MTEK Industries, Inc. Thu Aug 5 07:24:51 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1I60ZyxmN3-6jZnAV0VWhj9ij5WiLmz1qxUONGIASKSSRcBosyr_Dw

Scale = 1:61.0



<

TOTAL WEIGHT = 147 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 16.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCO 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBCO 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")

CALCULATED VERT. DEFL.(LL) = L/999 (0.23")

ALLOWABLE DEFL.(TL)= L/360 (1.20")

CALCULATED VERT. DEFL.(TL) = L/966 (0.45")

CSI: TC=0.46/1.00 (E-F:1) , BC=0.44/1.00 (J-O:1) , WB=0.70/1.00 (J-P:1) , SS=0.38/1.00 (J-Q:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (K) (INPUT = 0.90)
JSI METAL= 0.69 (O) (INPUT = 1.00)




Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 13:00:40 2021 Page 1

ID:rhtOOT9Mf?GOVQD_N1I60ZyxmN3-Q7wAX_Eaj3nP?Mrb8xhsQqWiyBIOyDLuibbzcmYrEPs

-1-3-8 0-0 4-4-8 4-4-8 4-2-0 8-6-8 4-10-8 13-5-0 4-10-8 18-3-8 4-5-4 22-8-12 27-4-8 3-4-8 30-9-0 3-4-8 34-1-8 35-7-8 35-11-0 37-2-8 1-6-0 3-8 1-3-8

Scale = 1/61.0



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
<u>BEARINGS</u>									
	FACTORED		MAXIMUM FACTORED		INPUT	REQ'D			
	GROSS REACTION		GROSS REACTION		BRG	BRG			
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
X	1313	0	1313	0	0	5-8	5-8		
M	1316	0	1316	0	0	5-8	5-8		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS TRUSS COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.19")
ALLOWABLE DEFL. (TL)= L/360 (1.20")
CALCULATED VERT. DEFL. (TL) = L/ 999 (0.36")

CSI: TC=0.32/1.00 (G+H:1), BC=0.52/1.00 (O-P:1),
WB=0.59/1.00 (K-O:1), SS=0.35/1.00 (J-O:1)

DOL LUMBER=1.00 NAIL=1.00 L5 BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION
	(PSI)	(PLI)	(PLI)	(PLI)	
	MAX	MIN	MAX	MIN	MAX MIN
MT20	650	371	1747	788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.88 (K) (INPUT = 0.90)


JSI METAL = 0.68 (K) (INPUT = 1.00)



Structural component only
DWG# T-2126485

JOB NAME 420376	TRUSS NAME T21S	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 13:00:41 2021 Page 1
ID:rh1OOT9Mf?GOVQD_N160ZymN3-wTYIKFCUNvGdWQoifC5y13tEbDVhgW1xFKX8oyrEP4



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
I - M	2x4	DRY	No.2
Z - B	2x4	DRY	No.2
N - L	2x4	DRY	No.2
Z - W	2x4	DRY	No.2
W - U	2x4	DRY	No.2
U - F	2x4	DRY	No.2
T - P	2x4	DRY	No.2
O - K	2x4	DRY	No.2
O - N	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
V - T	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0		
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMVW-t	MT20	4.0	4.0		
F	TMVW-p	MT20	3.0	4.0		
G	TS-t	MT20	3.0	6.0		
H	TMVW-t	MT20	4.0	4.0		
I	TTWW-m	MT20	5.0	6.0	2.25	2.00
J	TMVW-t	MT20	4.0	4.0	2.00	1.75
K	TMVW-p	MT20	4.0	6.0	Edge	
L	TMVW-t	MT20	5.0	6.0		
N	BMVW1-t	MT20	4.0	4.0		
O	BMVW-p	MT20	3.0	4.0		
P	BVMWV-t	MT20	5.0	12.0	Edge	6.75
Q, R, S, X						
Q	BMVW-t	MT20	4.0	4.0		
T	BVMWVW-t	MT20	6.0	12.0	3.00	4.50
U	BMVW-p	MT20	3.0	4.0		
V	BMVWVW-t	MT20	6.0	10.0	3.00	3.50
W	BS-t	MT20	3.0	6.0		
Y	BMVW-t	MT20	5.0	6.0		
Z	BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	HORZ	GROSS REACTION	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	BRG
Z	1313	0	1313	0	0	5-8	5-8		
N	1316	0	1316	0	0	5-8	5-8		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Z, N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.88 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		MAX. FACTORED		WEBS		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MAX. UNBRAC	LENGTH	MEMB.	FORCE (LBS)	MAX. CSI (LC)	MAX. UNBRAC
FR-TO						FR-TO			
A-B	0 / 17	-56.6	-56.6 0.07 (1)	10.00	Y-C	-216 / 0	0.05 (1)		
B-C	-1814 / 0	-56.6	-56.6 0.22 (1)	4.79	X-D	-132 / 0	0.08 (1)		
C-D	-1721 / 0	-56.6	-56.6 0.21 (1)	4.90	X-D	0 / 132	0.03 (1)		
D-E	-1835 / 0	-56.6	-56.6 0.15 (1)	4.83	D-V	0 / 528	0.12 (1)		
E-F	-2303 / 0	-56.6	-56.6 0.17 (1)	4.39	V-E	-810 / 0	0.47 (1)		
F-G	-2313 / 0	-56.6	-56.6 0.15 (1)	4.40	V-T	0 / 1846	0.30 (1)		
G-H	-2313 / 0	-56.6	-56.6 0.15 (1)	4.40	E-T	0 / 712	0.16 (1)		
H-I	-2201 / 0	-56.6	-56.6 0.15 (1)	4.49	R-I	0 / 309	0.07 (1)		
I-J	-2067 / 0	-56.6	-56.6 0.20 (1)	4.56	B-Y	0 / 1658	0.37 (1)		
J-K	-2446 / 0	-56.6	-56.6 0.28 (1)	4.16	S-I	0 / 565	0.13 (1)		
K-L	-2952 / 0	-56.6	-56.6 0.23 (1)	3.88	T-H	0 / 178	0.04 (1)		
L-M	0 / 17	-56.6	-56.6 0.07 (1)	10.00	S-H	-387 / 0	0.15 (1)		
Z-B	-1284 / 0	0.0	0.0 0.13 (1)	7.11	P-N	-287 / 0	0.04 (1)		
N-L	-1146 / 0	0.0	0.0 0.12 (1)	7.43	P-L	0 / 2625	0.59 (1)		
Z-Y	0 / 0	-12.3	-12.3 0.06 (4)	10.00	R-J	-457 / 0	0.19 (1)		
Y-X	0 / 1634	-12.3	-12.3 0.29 (1)	10.00	Q-J	0 / 110	0.03 (4)		
X-W	0 / 1528	-12.3	-12.3 0.27 (1)	10.00	Q-K	-848 / 0	0.26 (1)		
W-V	0 / 1528	-12.3	-12.3 0.27 (1)	10.00					
V-U	0 / 49	-12.3	-12.3 0.05 (4)	10.00					
U-T	0 / 23	0.0	0.0 0.07 (1)	10.00					
T-F	-204 / 0	0.0	0.0 0.07 (1)	7.81					
T-S	0 / 2201	-12.3	-12.3 0.38 (1)	10.00					
S-R	0 / 1841	-12.3	-12.3 0.32 (1)	10.00					
R-Q	0 / 2214	-12.3	-12.3 0.38 (1)	10.00					
Q-P	0 / 3052	-12.3	-12.3 0.53 (1)	10.00					
O-P	0 / 11	0.0	0.0 0.36 (1)	10.00					
P-K	0 / 338	0.0	0.0 0.41 (1)	10.00					
O-N	0 / 238	-12.3	-12.3 0.04 (1)	10.00					

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.
(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD
ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.16")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.31")
CSI: TC=0.28/1.00 (J-K:1), BC=0.53/1.00 (P-Q:1),
WB=0.59/1.00 (L-P:1), SSI=0.35/1.00 (K-P:1)
DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10
COMPANION LIVE LOAD FACTOR = 1.00
AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.89 (L) (INPUT = 0.90)
JSI METAL = 0.68 (L) (INPUT = 1.00)



Structural component only
DWG# T-2126486

JOB NAME 420376	TRUSS NAME T22S	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 13:00:42 2021 Page 1
ID:rhTOOT9Mf?GOVQD_N160ZyxmN3-MV1wygGqFg17Ff?_GMjKVfB0I?YVQ7gB9v44gFyrEP3



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - J	2x4	DRY No.2	SPF
U - B	2x4	DRY No.2	SPF
K - I	2x4	DRY No.2	SPF
U - S	2x4	DRY No.2	SPF
S - Q	2x4	DRY No.2	SPF
Q - E	2x4	DRY No.2	SPF
P - M	2x4	DRY No.2	SPF
L - H	2x4	DRY No.2	SPF
L - K	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			
R - P	2x4	DRY No.2	SPF

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMVW-t	MT20	4.0	6.0
C	TMVW-t	MT20	4.0	4.0 2.00 1.75
D	TTWW-m	MT20	5.0	6.0 2.25 2.00
E	TMV+p	MT20	3.0	4.0
F	TTWW-m	MT20	5.0	6.0 2.25 2.00
G	TMVW-t	MT20	4.0	4.0 2.00 1.75
H	TMVW+p	MT20	4.0	4.0 1.50 2.00
I	TMVW-t	MT20	4.0	9.0 2.00 4.00
K	BMVW1-t	MT20	4.0	4.0
L	BMV+p	MT20	3.0	4.0
M	BVMWV-t	MT20	5.0	12.0 Edge 6.75
N	BMVW-t	MT20	4.0	6.0
O	BMVW-t	MT20	4.0	4.0
P	BVMWVW-t	MT20	6.0	12.0 Edge 4.50
Q	BMV+p	MT20	3.0	4.0
R	BMVWVW-t	MT20	6.0	12.0
S	BS-t	MT20	3.0	6.0
T	BMVW-t	MT20	5.0	6.0
U	BMV1+p	MT20	3.0	4.0

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	GROSS REACTION	VERT	HORZ	DOWN	HORZ	BRG	IN-SX	BRG	IN-SX
U	1313	0	1313	0	0	5-8	5-8	5-8	5-8
K	1316	0	1316	0	0	5-8	5-8	5-8	5-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
U	930	599 / 0	0 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0
K	932	601 / 0	0 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.88 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		MAX. FACTORED		WEBS		FACTORED		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH	FR-TO	MEMB.	FORCE (LBS)	MAX. UNBRACED LENGTH	FR-TO	MEMB.	FORCE (LBS)
A-B	0 / 17	-56.6	-56.6 0.07 (1)	10.00	T-C	-185 / 0	0.05 (1)				
B-C	-1837 / 0	-56.6	-56.6 0.28 (1)	4.70	C-R	-213 / 0	0.18 (1)				
C-D	-1673 / 0	-56.6	-56.6 0.27 (1)	4.89	R-D	0 / 61	0.02 (4)				
D-E	-2070 / 0	-56.6	-56.6 0.43 (1)	4.32	R-P	0 / 1447	0.23 (1)				
E-F	-2079 / 0	-56.6	-56.6 0.41 (1)	4.32	D-P	0 / 751	0.17 (1)				
F-G	-1963 / 0	-56.6	-56.6 0.24 (1)	4.61	P-F	0 / 433	0.10 (1)				
G-H	-2394 / 0	-56.6	-56.6 0.31 (1)	4.19	O-F	0 / 359	0.08 (1)				
H-I	-2978 / 0	-56.6	-56.6 0.21 (1)	3.88	O-G	-506 / 0	0.28 (1)				
I-J	0 / 17	-56.6	-56.6 0.07 (1)	10.00	N-G	0 / 117	0.03 (4)				
U-B	-1280 / 0	0.0	0.0 0.13 (1)	7.13	N-H	-926 / 0	0.37 (1)				
K-I	-1144 / 0	0.0	0.0 0.12 (1)	7.43	B-T	0 / 1676	0.38 (1)				
					M-K	-289 / 0	0.04 (1)				
U-T	0 / 0	-12.3	-12.3 0.09 (4)	10.00	M-I	0 / 2652	0.60 (1)				
T-S	0 / 1658	-12.3	-12.3 0.34 (1)	10.00							
S-R	0 / 1658	-12.3	-12.3 0.34 (1)	10.00							
R-Q	0 / 48	-12.3	-12.3 0.13 (4)	10.00							
Q-P	0 / 39	0.0	0.0 0.07 (1)	10.00							
P-E	-468 / 0	0.0	0.0 0.17 (1)	7.81							
P-O	0 / 1747	-12.3	-12.3 0.34 (1)	10.00							
O-N	0 / 2165	-12.3	-12.3 0.41 (1)	10.00							
N-M	0 / 3083	-12.3	-12.3 0.54 (1)	10.00							
L-M	0 / 11	0.0	0.0 0.36 (1)	10.00							
M-H	0 / 334	0.0	0.0 0.41 (1)	10.00							
L-K	0 / 240	-12.3	-12.3 0.04 (1)	10.00							

TOTAL WEIGHT = 154 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.31")

CSI: TC=0.43/1.00 (D-E:1), BC=0.54/1.00 (M-N:1), WB=0.60/1.00 (H-M:1), SSI=0.36/1.00 (H-M:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.87 (D) (INPUT = 0.90)

JSI METAL = 0.52 (M) (INPUT = 1.00)




Structural component only
DWG# T-2126487

JOB NAME 420376	TRUSS NAME T23S	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 13:00:43 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxnM3-qibJA0HS0_A_spaAq4EZ2S8CVPua9apKOZpdChyrEP2



TOTAL WEIGHT = 157 lb
[M][F]

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - J	2x4	DRY	No.2
U - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
U - S	2x4	DRY	No.2
S - Q	2x4	DRY	No.2
Q - E	2x4	DRY	No.2
P - M	2x4	DRY	No.2
L - H	2x4	DRY	No.2
L - K	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
R - P	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0		
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMV+p	MT20	3.0	4.0		
F	TTWW-m	MT20	5.0	6.0	2.25	2.00
G	TMVW-t	MT20	4.0	4.0	2.00	1.75
H	TMVW+p	MT20	4.0	4.0	1.50	2.00
I	TMVW-t	MT20	4.0	9.0	2.00	4.00
K	BMVW1-t	MT20	4.0	4.0		
L	BMV+p	MT20	3.0	4.0		
M	BMVWW-t	MT20	5.0	12.0	Edge	6.75
N	BMVW-t	MT20	4.0	6.0		
O	BMVW-t	MT20	4.0	4.0		
P	BMVWW-t	MT20	6.0	12.0	Edge	4.50
Q	BMV+p	MT20	3.0	4.0		
R	BMVWW-t	MT20	6.0	10.0	3.00	4.00
S	BS-t	MT20	3.0	6.0		
T	BMVW-t	MT20	5.0	6.0		
U	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
U	930	0	1313	0	0	5-8	5-8
K	1316	0	1316	0	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
U	930	599 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0
K	932	601 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.89 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO				FR-TO			
A-B	0 / 17	-56.6	-56.6 0.07 (1)	10.00	T-C	-145 / 13	0.04 (1)
B-C	-1853 / 0	-56.6	-56.6 0.36 (1)	4.60	C-R	-306 / 0	0.34 (1)
C-D	-1606 / 0	-56.6	-56.6 0.33 (1)	4.90	R-D	0 / 55	0.02 (4)
D-E	-1830 / 0	-56.6	-56.6 0.26 (1)	4.72	R-P	0 / 1407	0.23 (1)
E-F	-1835 / 0	-56.6	-56.6 0.25 (1)	4.72	D-P	0 / 610	0.14 (1)
F-G	-1853 / 0	-56.6	-56.6 0.29 (1)	4.67	P-F	0 / 291	0.07 (1)
G-H	-2347 / 0	-56.6	-56.6 0.35 (1)	4.18	O-F	0 / 376	0.08 (1)
H-I	-3007 / 0	-56.6	-56.6 0.19 (1)	3.89	O-G	-569 / 0	0.43 (1)
I-J	0 / 17	-56.6	-56.6 0.07 (1)	10.00	N-G	0 / 135	0.04 (4)
U-B	-1278 / 0	0.0	0.0 0.13 (1)	7.13	N-H	-1004 / 0	0.53 (1)
K-I	-1143 / 0	0.0	0.0 0.12 (1)	7.43	B-T	0 / 1689	0.38 (1)
					M-K	-292 / 0	0.04 (1)
U-T	0 / 0	-12.3	-12.3 0.10 (4)	10.00	M-I	0 / 2684	0.60 (1)
T-S	0 / 1674	-12.3	-12.3 0.33 (1)	10.00			
S-R	0 / 1674	-12.3	-12.3 0.33 (1)	10.00			
R-Q	0 / 34	-12.3	-12.3 0.10 (4)	10.00			
Q-P	0 / 30	0.0	0.0 0.05 (1)	10.00			
P-E	-373 / 0	0.0	0.0 0.17 (1)	7.81			
P-O	0 / 1646	-12.3	-12.3 0.31 (1)	10.00			
O-N	0 / 2122	-12.3	-12.3 0.39 (1)	10.00			
N-M	0 / 3119	-12.3	-12.3 0.55 (1)	10.00			
L-M	0 / 11	0.0	0.0 0.37 (1)	10.00			
M-H	0 / 331	0.0	0.0 0.42 (1)	10.00			
L-K	0 / 243	-12.3	-12.3 0.04 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF	

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.28")

CSI: TC=0.36/1.00 (B-C:1), BC=0.55/1.00 (M-N:1), WB=0.60/1.00 (I-M:1), SSI=0.36/1.00 (H-M:1)

DOL LUMBER=1.00 NAIL=1.00 L/S BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
(PS)	(PL)	(PL)	(PL)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (B) (INPUT = 0.90)
JSI METAL= 0.52 (M) (INPUT = 1.00)




Structural component only
DWG# T-2126488

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ROYAL PINE HOMES	DRWG NO.
420376	T24S	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Wed Aug 4 13:00:45 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxnN3-n4j3bhiYbQ167KZxVH17tDWUCaqdSvdstikHayrEP0



TOTAL WEIGHT = 160 lb
[M][F]

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - G	2x4	DRY	No.2
G - H	2x4	DRY	No.2
H - L	2x4	DRY	No.2
W - B	2x4	DRY	No.2
M - K	2x4	DRY	No.2
W - U	2x4	DRY	No.2
U - S	2x4	DRY	No.2
S - F	2x4	DRY	No.2
R - O	2x4	DRY	No.2
N - J	2x4	DRY	No.2
N - M	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
T - R	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0		
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TS-t	MT20	3.0	6.0		
E	TTWW-m	MT20	5.0	6.0	2.25	2.00
F	TMV+p	MT20	3.0	4.0		
G	TTWW-m	MT20	5.0	6.0	2.25	2.00
H	TS-t	MT20	3.0	6.0		
I	TMVW-t	MT20	4.0	4.0	2.00	1.75
J	TMVW-p	MT20	4.0	4.0	1.50	2.00
K	TMVW-t	MT20	4.0	9.0	2.00	4.00
M	BMVW1-t	MT20	4.0	4.0		
N	BMV+p	MT20	3.0	4.0		
O	BVMWW-t	MT20	5.0	12.0	Edge	6.75
P	BMVW-t	MT20	4.0	6.0		
Q	BMVW-t	MT20	4.0	4.0		
R	BVMWW-t	MT20	6.0	12.0	Edge	4.50
S	BMV+p	MT20	3.0	4.0		
T	BMVWW-t	MT20	6.0	12.0		
U	BS-t	MT20	3.0	6.0		
V	BMVW-t	MT20	5.0	6.0		
W	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

DESIGN									
BEARINGS			FACTORED			MAXIMUM FACTORED		INPUT	REQRD
	GROSS REACTION		GROSS REACTION			BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
W	1313	0	1313	0	0	5-8	5-8		
M	1316	0	1316	0	0	5-8	5-8		

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
W	930	599 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0
M	932	601 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) W, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.89 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF F-R, C-T.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)	MAX. CSI (LC)	MAX. CSI (LC)
FR-TO		FROM TO		FR-TO			
A-B	0 / 17	-56.6	-56.6 0.07 (1)	10.00	V-C	-112 / 35	0.04 (1)
B-C	-1861 / 0	-56.6	-56.6 0.46 (1)	4.49	C-T	-392 / 0	0.18 (1)
C-D	-1534 / 0	-56.6	-56.6 0.41 (1)	4.88	T-E	-23 / 42	0.03 (1)
D-E	-1534 / 0	-56.6	-56.6 0.41 (1)	4.88	T-R	0 / 1365	0.22 (1)
E-F	-1639 / 0	-56.6	-56.6 0.14 (1)	5.06	E-R	0 / 539	0.12 (1)
F-G	-1642 / 0	-56.6	-56.6 0.14 (1)	5.05	R-G	0 / 189	0.04 (1)
G-H	-1746 / 0	-56.6	-56.6 0.35 (1)	4.71	Q-G	0 / 397	0.09 (1)
H-I	-1746 / 0	-56.6	-56.6 0.35 (1)	4.71	Q-I	-630 / 0	0.64 (1)
I-J	-2300 / 0	-56.6	-56.6 0.42 (1)	4.16	P-I	0 / 150	0.04 (4)
J-K	-3039 / 0	-56.6	-56.6 0.17 (1)	3.89	P-J	-1085 / 0	0.76 (1)
K-L	0 / 17	-56.6	-56.6 0.07 (1)	10.00	B-V	0 / 1695	0.38 (1)
W-B	-1276 / 0	0.0	0.0 0.13 (1)	7.13	O-M	-296 / 0	0.04 (1)
M-K	-1141 / 0	0.0	0.0 0.12 (1)	7.44	O-K	0 / 2718	0.81 (1)

W-V	0 / 0	-12.3	-12.3 0.14 (4)	10.00
V-U	0 / 1683	-12.3	-12.3 0.33 (1)	10.00
U-T	0 / 1683	-12.3	-12.3 0.33 (1)	10.00
T-S	0 / 24	-12.3	-12.3 0.09 (4)	10.00
S-R	0 / 20	0.0	0.0 0.04 (1)	10.00
R-F	-276 / 0	0.0	0.0 0.03 (1)	6.25
R-Q	0 / 1549	-12.3	-12.3 0.29 (1)	10.00
Q-P	0 / 2079	-12.3	-12.3 0.39 (1)	10.00
P-O	0 / 3158	-12.3	-12.3 0.56 (1)	10.00
N-O	0 / 11	0.0	0.0 0.37 (1)	10.00
O-J	0 / 331	0.0	0.0 0.42 (1)	10.00
N-M	0 / 246	-12.3	-12.3 0.05 (1)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 36.7	PSF	

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.28")

CSI: TC=0.46/1.00 (B-C:1), BC=0.56/1.00 (O-P:1), WB=0.76/1.00 (J-P:1), SSI=0.37/1.00 (J-O:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (B) (INPUT = 0.90)
JSI METAL= 0.53 (O) (INPUT = 1.00)




Structural component only
DWG# T-2126489

JOB NAME 420376	TRUSS NAME T25	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	TRUSS DESC.	DRWG NO.
---------------------------	--------------------------	----------------------	-----------------	--------------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 13:00:46 2021 Page 1

ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-FHHRo1JLJYVZJHJVCoGf5mgVczGM??m4W2Hp0yrEP?



TOTAL WEIGHT = 146 lb [M/F]

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2 SPF
D - E	2x4	DRY	No.2 SPF
E - F	2x4	DRY	No.2 SPF
F - G	2x4	DRY	No.2 SPF
G - J	2x4	DRY	No.2 SPF
R - B	2x4	DRY	No.2 SPF
K - I	2x4	DRY	No.2 SPF
R - P	2x4	DRY	No.2 SPF
P - M	2x4	DRY	No.2 SPF
M - K	2x4	DRY	No.2 SPF
ALL WEBS EXCEPT	2x3	DRY	No.2 SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMVW-t	MT20	4.0	6.0
C	TMVW-t	MT20	4.0	4.0
D	TS-t	MT20	3.0	6.0
E	TTWW-m	MT20	5.0	6.0
F	TTW-m	MT20	4.0	4.0
G	TS-t	MT20	3.0	6.0
H	TMVW-t	MT20	4.0	4.0
I	TMVW-t	MT20	4.0	6.0
K	BMV1+p	MT20	3.0	4.0
L	BMVW-t	MT20	5.0	6.0
M	BS-t	MT20	3.0	6.0
N	BMVW-t	MT20	4.0	9.0
O	BMVW-t	MT20	4.0	4.0
P	BS-t	MT20	3.0	6.0
Q	BMVW-t	MT20	5.0	6.0
R	BMV1+p	MT20	3.0	4.0

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REORD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
R	1314	0	1314	0	0	5-8	5-8	5-8	5-8
K	1314	0	1314	0	0	5-8	5-8	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
R	931	600 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0
K	931	600 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.36 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-O, H-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED UNBRACED LENGTH (LC)	MAX. FACTORED UNBRACED LENGTH (LC)
FR-TO		FROM TO		FR-TO			
A-B	0 / 17	-56.6 -56.6	0.07 (1)	10.00	Q-C	-82 / 54	0.03 (1)
B-C	-1864 / 0	-56.6 -56.6	0.57 (1)	4.36	C-O	-477 / 0	0.27 (1)
C-D	-1457 / 0	-56.6 -56.6	0.50 (1)	4.86	O-E	0 / 327	0.07 (1)
D-E	-1457 / 0	-56.6 -56.6	0.50 (1)	4.86	E-N	0 / 0	0.00 (1)
E-F	-1286 / 0	-56.6 -56.6	0.24 (1)	5.43	N-F	0 / 328	0.07 (1)
F-G	-1458 / 0	-56.6 -56.6	0.50 (1)	4.86	N-H	-476 / 0	0.26 (1)
G-H	-1458 / 0	-56.6 -56.6	0.50 (1)	4.86	H-I	-82 / 54	0.03 (1)
H-I	-1863 / 0	-56.6 -56.6	0.57 (1)	4.36	B-Q	0 / 1698	0.38 (1)
I-J	0 / 17	-56.6 -56.6	0.07 (1)	10.00	L-I	0 / 1698	0.38 (1)
R-B	-1275 / 0	0.0 0.0	0.13 (1)	7.13			
K-I	-1275 / 0	0.0 0.0	0.13 (1)	7.13			

R-Q	0 / 0	-12.3 -12.3	0.18 (4)	10.00
Q-P	0 / 1687	-12.3 -12.3	0.36 (1)	10.00
P-O	0 / 1687	-12.3 -12.3	0.36 (1)	10.00
O-N	0 / 1286	-12.3 -12.3	0.26 (1)	10.00
N-M	0 / 1687	-12.3 -12.3	0.36 (1)	10.00
M-L	0 / 1687	-12.3 -12.3	0.36 (1)	10.00
L-K	0 / 0	-12.3 -12.3	0.18 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.09")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.20")

CSI: TC=0.57/1.00 (B-C:1), BC=0.36/1.00 (O-Q:1),
WB=0.38/1.00 (B-Q:1), SSI=0.19/1.00 (H-I:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.87 (B) (INPUT = 0.90)
JSI METAL= 0.57 (P) (INPUT = 1.00)



Structural component only
DWG# T-2126490

JOB NAME 420376	TRUSS NAME T26	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 13:00:47 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-JTp?NKz4DgQLRtx3vJVCiJsN0HrSPpWJAnrLSyrEP



TOTAL WEIGHT = 164 lb
[M][F]

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
I - L	2x4	DRY	No.2
V - B	2x4	DRY	No.2
M - K	2x4	DRY	No.2
V - S	2x4	DRY	No.2
S - P	2x4	DRY	No.2
P - M	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0	2.00	2.75
C, E, H, J						
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TS-t	MT20	3.0	6.0		
F	TTWW-m	MT20	5.0	6.0	2.25	2.25
G	TTW-m	MT20	4.0	4.0		
I	TS-t	MT20	3.0	6.0		
K	TMVW-t	MT20	5.0	6.0	2.00	2.75
M	BMV1+p	MT20	3.0	4.0		
N	BMVW-t	MT20	5.0	6.0	2.50	2.50
O, R, T						
O	BMVW-t	MT20	4.0	4.0		
P	BS-t	MT20	3.0	6.0		
Q	BMVW-t	MT20	4.0	6.0	2.00	1.50
S	BS-t	MT20	3.0	6.0		
U	BMVW-t	MT20	5.0	6.0	2.50	2.50
V	BMV1+p	MT20	3.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	UP	BRG
V	1971	0	1971	0	5-8
M	1971	0	1971	0	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
V	1397	900 / 0	0 / 0	0 / 0	498 / 0	0 / 0
M	1397	900 / 0	0 / 0	0 / 0	498 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) V, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.77 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-R, H-Q.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS			WEBS				
MEMB.	MAX. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1	MAX. UNBRAC CS1 (LC)	MEMB.	MAX. FORCE (LBS)	FACTORED MAX CS1 (LC)
FR-TO		FROM TO		LENGTH	FR-TO		
A-B	0 / 26	-84.9	-84.9	0.11 (1)	10.00	U-C	-251 / 0
B-C	-2755 / 0	-84.9	-84.9	0.50 (1)	3.77	C-T	-291 / 0
C-D	-2505 / 0	-84.9	-84.9	0.40 (1)	4.03	T-E	0 / 275
D-E	-2505 / 0	-84.9	-84.9	0.40 (1)	4.03	E-R	-743 / 0
E-F	-1981 / 0	-84.9	-84.9	0.39 (1)	4.44	R-F	0 / 588
F-G	-1784 / 0	-84.9	-84.9	0.06 (1)	5.00	F-Q	0 / 33
G-H	-1988 / 0	-84.9	-84.9	0.39 (1)	4.43	Q-G	0 / 623
H-I	-2503 / 0	-84.9	-84.9	0.40 (1)	4.03	Q-H	-734 / 0
I-J	-2503 / 0	-84.9	-84.9	0.40 (1)	4.03	O-H	0 / 265
J-K	-2756 / 0	-84.9	-84.9	0.50 (1)	3.77	O-J	-294 / 0
K-L	0 / 26	-84.9	-84.9	0.11 (1)	10.00	N-J	-249 / 1
V-B	-1923 / 0	0.0	0.0	0.19 (1)	6.07	B-U	0 / 2509
M-K	-1924 / 0	0.0	0.0	0.19 (1)	6.06	N-K	0 / 2509
V-U	0 / 0	-18.5	-18.5	0.13 (4)	10.00		
U-T	0 / 2482	-18.5	-18.5	0.46 (1)	10.00		
T-S	0 / 2240	-18.5	-18.5	0.43 (1)	10.00		
S-R	0 / 2240	-18.5	-18.5	0.43 (1)	10.00		
R-Q	0 / 1759	-18.5	-18.5	0.37 (1)	10.00		
Q-P	0 / 2239	-18.5	-18.5	0.45 (1)	10.00		
P-O	0 / 2239	-18.5	-18.5	0.45 (1)	10.00		
O-N	0 / 2483	-18.5	-18.5	0.45 (1)	10.00		
N-M	0 / 0	-18.5	-18.5	0.13 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.28")

CSI: TC=0.50/1.00 (J-K:1), BC=0.46/1.00 (T-U:1),
WB=0.56/1.00 (K-N:1), SS=0.21/1.00 (J-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.89 (K) (INPUT = 0.90)
JSI METAL= 0.73 (S) (INPUT = 1.00)



Structural component only
DWG# T-2126491

JOB NAME 420376	TRUSS NAME T27	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 13:00:48 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1I60ZyxmN3-BfOCdJKbrWoGzaS8cdqkIWf0aQlftqyx3YqXOtuyrEOz



Scale = 1:13.1

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
A - C	2x4 DRY	No.2	SPF
C - D	2x4 DRY	No.2	SPF
E - B	2x4 DRY	No.2	SPF
G - B	2x4 DRY	No.2	SPF
G - E	2x4 DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2			
EXCEPT			
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	4.0	4.0	2.00 1.25
C	TTWW-m	MT20	5.0	6.0	1.75 1.75
D	TMVW-p	MT20	3.0	4.0	
E	BMVW1-t	MT20	4.0	6.0	
F	BMVW1-t	MT20	4.0	4.0	
G	BMVW1-p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQRD
JT	GROSS REACTION	GROSS REACTION	DOWN	BRG	BRG
E	483 0	483 0	0	5-8	5-8
G	661 0	661 0	0	5-8	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	338	243 / 0	0 / 0	0 / 0	0 / 0	95 / 0	0 / 0
G	460	344 / 0	0 / 0	0 / 0	0 / 0	116 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 17	-56.6 -56.6	0.08 (1)	10.00	F-C	-249 / 0	0.04 (1)
B-C	-529 / 0	-56.6 -56.6	0.08 (1)	6.25	C-E	-466 / 0	0.16 (1)
C-H	0 / 0	-140.6 -140.6	0.53 (1)	10.00	B-F	0 / 528	0.13 (1)
H-I	0 / 0	-140.6 -140.6	0.53 (1)	10.00			
I-D	0 / 0	-140.6 -140.6	0.53 (1)	10.00			
E-D	-316 / 0	0.0 0.0	0.04 (1)	7.81			
G-B	-650 / 0	0.0 0.0	0.07 (1)	7.81			
G-F	0 / 0	-12.3 -12.3	0.05 (4)	10.00			
F-J	0 / 440	-12.3 -12.3	0.11 (1)	10.00			
J-K	0 / 440	-12.3 -12.3	0.11 (1)	10.00			
K-E	0 / 440	-12.3 -12.3	0.11 (1)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	1-4-8	-30	-30	---	FRONT	VERT	DEAD	---	C1
C	1-4-8	-52	-52	53	FRONT	VERT	TOTAL	---	C1
C	1-4-8	-134	-134	---	FRONT	VERT	SNOW	---	C1
F	1-5-4	7	1	9	FRONT	VERT	TOTAL	---	C1
H	3-5-4	1	1	53	FRONT	VERT	TOTAL	---	C1
I	5-5-4	1	1	45	FRONT	VERT	TOTAL	---	C1
J	3-5-4	7	1	9	FRONT	VERT	TOTAL	---	C1
K	5-5-4	6	1	8	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.53/1.00 (C-D:1), BC=0.11/1.00 (E-F:1), WB=0.16/1.00 (C-E:1), SSI=0.27/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.75 (B) (INPUT = 0.90)
JSI METAL = 0.20 (B) (INPUT = 1.00)




Structural component only
DWG# T-2126492

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Wed Aug 4 14:46:59 2021 Page 1
ID:rhtOOT9Mf?GOVQD_N1l60ZyxmN3-8KsILBRuSOTlog?bK8dS1DnLct1z3D3pYXK0_7yrCrC

1-3-8 0-0 1-9-8 1-9-8 3-7-12 5-5-4 5-10-8 5-2-12 11-1-4 5-0-4 16-1-8 16-5-4 17-11-8 20-9-9 4-6-13 25-4-7 30-0-8 35-11-0 37-2-8 1-3-8

Scale = 1/61.0



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

UNFACTORED REACTIONS

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M, X

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

X- W	0 / 906	-18.5	-18.5	0.04 (1)	10.00
W- V	0 / 592	0.0	0.0	0.44 (1)	10.00
V- C	0 / 1327	0.0	0.0	0.48 (1)	10.00
V-AJ	0 / 10490	-18.5	-18.5	0.45 (1)	10.00
AJ-AK	0 / 10490	-18.5	-18.5	0.45 (1)	10.00
AK- U	0 / 10490	-18.5	-18.5	0.45 (1)	10.00
U-AL	0 / 7339	-18.5	-18.5	0.34 (1)	10.00
AL-AM	0 / 7339	-18.5	-18.5	0.34 (1)	10.00
AM- T	0 / 7339	-18.5	-18.5	0.34 (1)	10.00
T-AN	0 / 11078	-18.5	-18.5	0.50 (1)	10.00
AN-AO	0 / 11078	-18.5	-18.5	0.50 (1)	10.00
AO-AP	0 / 11078	-18.5	-18.5	0.50 (1)	10.00
AP- S	0 / 11078	-18.5	-18.5	0.50 (1)	10.00
R- S	0 / 75	0.0	0.0	0.17 (1)	10.00
S- F	-787 / 0	0.0	0.0	0.17 (1)	7.81
R-AQ	0 / 365	-18.5	-18.5	0.04 (4)	10.00
AQ-AR	0 / 365	-18.5	-18.5	0.04 (4)	10.00
AR- Q	0 / 365	-18.5	-18.5	0.04 (4)	10.00

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY
USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 2.00/12 MINIMUM

*** NON STANDARD GIRDER ***
ADD'L USER-DEFINED LOADS APPLIED TO ALL
LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018 , ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 086-14
 - TPIC 2014

DESIGN ASSUMPTIONS
-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.31")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/ 725 (0.59")

CSI: TC=0.50/1.00 (E-F:1), BC=0.50/1.00 (S-T:1),
WB=0.68/1.00 (B-V:1), SSI=0.39/1.00 (C-V:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00


AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES					
PLATE	GRIP(DRY)		SHEAR		SECTION
	(PSI)		(PLI)		(PLI)
	MAX	MIN	MAX	MIN	MAX MIN
MT20	650	371	1747	798	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.



JOB NAME 420377	TRUSS NAME T28S	QUANTITY 1	PLY 3	JOB DESC. ROYAL PINE HOMES	DRWG NO.
---------------------------	---------------------------	----------------------	-----------------	--------------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:46:59 2021 Page 2
ID:rhOOT9Mf?GOVQD N1160ZyxmN3-8KslBRuS0Tlog?bK8dlS1DnLc1z3D3pYXK0 7yrCrC

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	8.0		
C	TMVW+p	MT20	4.0	4.0	1.50	2.00
D	TTWW-m	MT20	5.0	8.0	2.00	3.00
E	TMVW-t	MT20	4.0	4.0		
F	TMV+p	MT20	3.0	4.0		
G	TS-t	MT20	3.0	6.0		
H	TMVW-t	MT20	4.0	6.0		
I	TMVW-t	MT20	4.0	4.0		
J	TTWW-m	MT20	5.0	8.0	2.25	3.25
K	TMVW-p	MT20	5.0	6.0	2.00	3.00
M	BMV1+p	MT20	3.0	6.0		
N, P, T, U						
N	BMVW-t	MT20	5.0	6.0		
O	BS-t	MT20	5.0	6.0		
Q	BMVWW-t	MT20	8.0	9.0		
R	BMV+p	MT20	3.0	6.0		
S	BMVWW-t	MT20	8.0	12.0	5.00	4.75
V	BMVWW-t	MT20	5.0	12.0		
W	BMV+p	MT20	3.0	6.0		
X	BMVW1-t	MT20	5.0	6.0		

NOTES: (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO			FR-TO		
Q-AS	0 / 7860	-18.5	-18.5	0.34 (1)	10.00		
AS-AT	0 / 7860	-18.5	-18.5	0.34 (1)	10.00		
AT-P	0 / 7860	-18.5	-18.5	0.34 (1)	10.00		
P-AU	0 / 5262	-18.5	-18.5	0.24 (1)	10.00		
AU-O	0 / 5262	-18.5	-18.5	0.24 (1)	10.00		
O-N	0 / 5262	-18.5	-18.5	0.24 (1)	10.00		
N-AV	0 / 0	-18.5	-18.5	0.05 (4)	10.00		
AV-AW	0 / 0	-18.5	-18.5	0.05 (4)	10.00		
AW-M	0 / 0	-18.5	-18.5	0.05 (4)	10.00		


SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
D	5-10-8	-30	-30	---	FRONT	VERT	DEAD	---	C1
D	5-10-8	-133	-133	---	FRONT	VERT	SNOW	---	C1
F	16-5-4	-113	-113	---	FRONT	VERT	TOTAL	---	C1
G	17-11-8	-113	-113	---	FRONT	VERT	TOTAL	---	C1
J	30-0-8	-374	-374	---	FRONT	VERT	TOTAL	---	C1
N	29-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
O	27-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
S	16-3-4	-35	-35	---	FRONT	VERT	TOTAL	---	C1
W	1-7-12	-402	-402	---	FRONT	VERT	TOTAL	---	C1
Y	5-5-4	-90	-90	---	FRONT	VERT	TOTAL	---	C1
Z	7-5-4	-73	-73	---	FRONT	VERT	TOTAL	---	C1
AA	9-5-4	-73	-73	---	FRONT	VERT	TOTAL	---	C1
AB	11-5-4	-73	-73	---	FRONT	VERT	TOTAL	---	C1
AC	13-5-4	-73	-73	---	FRONT	VERT	TOTAL	---	C1
AD	15-5-4	-73	-73	---	FRONT	VERT	TOTAL	---	C1
AE	19-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AF	21-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AG	23-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AH	25-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AI	27-11-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AJ	3-5-4	-60	-60	---	FRONT	VERT	TOTAL	---	C1
AK	5-5-4	-60	-60	---	FRONT	VERT	TOTAL	---	C1
AL	7-5-4	-60	-60	---	FRONT	VERT	TOTAL	---	C1
AM	9-5-4	-60	-60	---	FRONT	VERT	TOTAL	---	C1
AN	11-5-4	-60	-60	---	FRONT	VERT	TOTAL	---	C1
AO	13-5-4	-60	-60	---	FRONT	VERT	TOTAL	---	C1
AP	15-5-4	-61	-61	---	FRONT	VERT	TOTAL	---	C1
AQ	17-11-8	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AR	19-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AS	21-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AT	23-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AU	25-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AV	31-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
AW	33-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

JSI GRIP= 0.86 (D) (INPUT = 0.90)
JSI METAL= 0.62 (D) (INPUT = 1.00)





Structural component only
DWG# T-2126494 *ML*

JOB NAME 420377	TRUSS NAME T29S	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Thu Aug 5 07:30:54 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3_Z_0MPC1DSfVLHT4n5ENTUki9DjdcuZP1ueJyr_8F



LUMBER				DESCR.	
N. L. G. A. RULES	SIZE	LUMBER			
CHORDS					
A - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
G - H	2x4	DRY	No.2	SPF	
H - K	2x4	DRY	No.2	SPF	
V - B	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
V - U	2x4	DRY	No.2	SPF	
U - C	2x4	DRY	No.2	SPF	
T - Q	2x4	DRY	No.2	SPF	
P - F	2x4	DRY	No.2	SPF	
P - N	2x4	DRY	No.2	SPF	
N - L	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
Q - O	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	9.0	2.00	4.00
C	TMVW-p	MT20	4.0	4.0	1.50	2.00
D	TTWW-m	MT20	5.0	8.0	2.25	3.50
E	TMVW-t	MT20	4.0	4.0		
F	TMV-p	MT20	3.0	4.0		
G	TSWW-h	MT20	5.0	6.0		
H	TTWW-m	MT20	5.0	6.0	2.25	1.75
I	TMVW-t	MT20	4.0	6.0		
J	TMV-p	MT20	3.0	4.0		
L	BMVW1-t	MT20	5.0	6.0		
M	BMVW-t	MT20	4.0	4.0		
N	BS-t	MT20	3.0	6.0		
O	BMVW-t	MT20	6.0	10.0	3.00	2.50
P	BMV-p	MT20	3.0	4.0		
Q	BMVW-t	MT20	7.0	12.0	3.25	4.50
R	BMVW-t	MT20	4.0	6.0		
S	BMVW-t	MT20	4.0	6.0		
T	BMVW-t	MT20	5.0	12.0	Edge	6.75
U	BMV-p	MT20	3.0	4.0		
V	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	BRG	BRG
L	1313	0	1313	0	0	5-8	5-8		
V	1316	0	1316	0	0	5-8	5-8		

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN	COMPONENT REACTIONS						
L	930	599 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0		
V	932	601 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, V

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.57 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MAX. FACTORED		FACTORED		MAX. FACTORED				
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM	TO		FR-TO			
A-B	0 / 17	-56.6	-56.6	0.07 (1)	10.00	C-S	-1234 / 0	0.70 (1)
B-C	-3134 / 0	-56.6	-56.6	0.17 (1)	3.83	S-D	0 / 166	0.04 (4)
C-D	-2293 / 0	-56.6	-56.6	0.45 (1)	4.11	Q-O	0 / 2270	0.36 (1)
D-E	-2829 / 0	-56.6	-56.6	0.28 (1)	3.93	Q-G	0 / 946	0.21 (1)
E-F	-3204 / 0	-56.6	-56.6	0.40 (1)	3.59	O-G	-795 / 0	0.27 (1)
F-G	-3172 / 0	-56.6	-56.6	0.51 (1)	3.57	O-H	0 / 878	0.20 (1)
G-H	-2317 / 0	-56.6	-56.6	0.59 (1)	3.94	M-H	0 / 58	0.02 (4)
H-I	-1804 / 0	-56.6	-56.6	0.13 (1)	4.87	M-I	0 / 116	0.03 (4)
I-J	0 / 8	-56.6	-56.6	0.09 (1)	10.00	I-L	-1877 / 0	0.82 (1)
J-K	0 / 17	-56.6	-56.6	0.07 (1)	10.00	V-T	-306 / 0	0.05 (1)
V-B	-1135 / 0	0.0	0.0	0.11 (1)	7.45	B-T	0 / 2821	0.83 (1)
L-J	-161 / 0	0.0	0.0	0.02 (1)	7.81	E-Q	0 / 474	0.11 (1)
						D-R	0 / 973	0.22 (1)
						R-E	-543 / 0	0.12 (1)
V-U	0 / 254	-12.3	-12.3	0.05 (1)	10.00			
U-T	0 / 11	0.0	0.0	0.38 (1)	10.00			
T-C	0 / 344	0.0	0.0	0.44 (1)	10.00			
T-S	0 / 3275	-12.3	-12.3	0.28 (1)	10.00			
S-R	0 / 2055	-12.3	-12.3	0.19 (1)	10.00			
R-Q	0 / 2829	-12.3	-12.3	0.24 (1)	10.00			
P-Q	0 / 36	0.0	0.0	0.16 (1)	10.00			
Q-F	-342 / 0	0.0	0.0	0.16 (1)	7.81			
P-O	0 / 110	-12.3	-12.3	0.11 (4)	10.00			
O-N	0 / 1605	-12.3	-12.3	0.33 (1)	10.00			
N-M	0 / 1605	-12.3	-12.3	0.33 (1)	10.00			
M-L	0 / 1511	-12.3	-12.3	0.32 (1)	10.00			

TOTAL WEIGHT = 148 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL)= L/999 (0.23")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL)= L/982 (0.44")

CSI: TC=0.59/1.00 (G-H:1), BC=0.44/1.00 (C-T:1), WB=0.70/1.00 (C-S:1), SSI=0.38/1.00 (C-T:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.90 (B) (INPUT = 0.90)
JSI METAL= 0.55 (T) (INPUT = 1.00)




Structural component only
DWG# T-2126495

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ROYAL PINE HOMES	DRWG NO.
420377	T30S	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MitTek Industries, Inc. Wed Aug 4 14:47:01 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxnN3-5j_SmtT9_dj02_9_SZgDXSi85QiEX4o60rp730yrCrC



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - E	2x4	DRY	No.2
E - H	2x4	DRY	No.2
H - J	2x4	DRY	No.2
J - M	2x4	DRY	No.2
Y - B	2x4	DRY	No.2
N - L	2x4	DRY	No.2
Y - X	2x4	DRY	No.2
X - C	2x4	DRY	No.2
W - S	2x4	DRY	No.2
R - G	2x4	DRY	No.2
R - P	2x4	DRY	No.2
P - N	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
S - Q	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0		
C	TMVW-t	MT20	4.0	4.0	2.00	1.25
D	TMVW-t	MT20	4.0	4.0	2.00	1.75
E	TTWW-m	MT20	5.0	6.0	2.25	2.00
F	TMVW-t	MT20	4.0	4.0		
G	TMV-p	MT20	3.0	4.0		
H	TS-t	MT20	3.0	6.0		
I	TMVW-t	MT20	4.0	4.0		
J	TTWW-m	MT20	5.0	6.0	2.25	2.00
K	TMVW-t	MT20	4.0	6.0		
L	TMV-p	MT20	3.0	4.0		
N	BMVW1-t	MT20	5.0	6.0		
O, T, U, V						
P	BMVW-t	MT20	4.0	4.0		
Q	BS-t	MT20	3.0	6.0		
R	BMVW-t	MT20	6.0	10.0	3.00	2.75
S	BMV-p	MT20	3.0	4.0		
W	BVMW-t	MT20	6.0	12.0	3.00	4.50
X	BVMW-t	MT20	5.0	12.0	Edge	6.75
Y	BMV-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
N	1313	0	1313	0
Y	1316	0	1316	0

UNFACTORED REACTIONS

	1ST LCASE	MAX / MIN	COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
N	930	599 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0
Y	932	601 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, Y

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.79 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LC1 (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 17	-56.6	-56.6 0.07 (1)	U-E	0 / 284	0.06 (1)	
B-C	-2930 / 0	-56.6	-56.6 0.29 (1)	S-Q	0 / 2063	0.33 (1)	
C-D	-2498 / 0	-56.6	-56.6 0.30 (1)	S-I	0 / 684	0.15 (1)	
D-E	-2179 / 0	-56.6	-56.6 0.20 (1)	Q-I	-778 / 0	0.34 (1)	
E-F	-2437 / 0	-56.6	-56.6 0.19 (1)	Q-J	0 / 697	0.16 (1)	
F-G	-2668 / 0	-56.6	-56.6 0.20 (1)	O-J	0 / 94	0.03 (4)	
G-H	-2650 / 0	-56.6	-56.6 0.42 (1)	O-K	0 / 53	0.02 (4)	
H-I	-2650 / 0	-56.6	-56.6 0.42 (1)	K-N	-1908 / 0	0.86 (1)	
I-J	-2093 / 0	-56.6	-56.6 0.37 (1)	Y-W	-284 / 0	0.04 (1)	
J-K	-1778 / 0	-56.6	-56.6 0.20 (1)	B-W	0 / 2601	0.59 (1)	
K-L	0 / 11	-56.6	-56.6 0.14 (1)	F-S	0 / 340	0.08 (1)	
L-M	0 / 17	-56.6	-56.6 0.07 (1)	E-T	0 / 722	0.16 (1)	
Y-B	-1147 / 0	0.0	0.0 0.12 (1)	T-F	-479 / 0	0.14 (1)	
N-L	-174 / 0	0.0	0.0 0.02 (1)	D-U	-400 / 0	0.12 (1)	
Y-X	0 / 236	-12.3	-12.3 0.04 (1)	V-D	0 / 93	0.02 (4)	
X-W	0 / 11	0.0	0.0 0.36 (1)	C-V	-775 / 0	0.18 (1)	
W-C	0 / 347	0.0	0.0 0.41 (1)				
W-V	0 / 3025	-12.3	-12.3 0.52 (1)				
V-U	0 / 2263	-12.3	-12.3 0.39 (1)				
U-T	0 / 1942	-12.3	-12.3 0.33 (1)				
T-S	0 / 2437	-12.3	-12.3 0.42 (1)				
R-S	0 / 33	0.0	0.0 0.11 (1)				
S-G	-245 / 0	0.0	0.0 0.11 (1)				
R-Q	0 / 74	-12.3	-12.3 0.09 (4)				
Q-P	0 / 1581	-12.3	-12.3 0.36 (1)				
P-O	0 / 1581	-12.3	-12.3 0.36 (1)				
O-N	0 / 1563	-12.3	-12.3 0.36 (1)				

TOTAL WEIGHT = 155 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF	

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.19")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.36")

CSI: TC=0.42/1.00 (G-I:1), BC=0.52/1.00 (V-W:1),
WB=0.86/1.00 (K-N:1), SS=0.35/1.00 (C-W:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.88 (B) (INPUT = 0.90)
JSI METAL = 0.68 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126496

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Wed Aug 4 14:47:02 2021 Page 1

ID:rhtOOT9Mf?GOVQD_N1I60ZyxmN3-ZvYq_CtNlxtf8kA0HBS4frKOp1HGbCGEVZgbSyrCrN

-1-3-8 0-0 1-9-8 1-9-8 4-0-8 5-10-0 4-0-8 9-10-8 6-3-0 16-1-8 4-11-8 21-1-0 4-11-8 26-0-8 4-10-0 30-10-8 5-0-8 35-11-0 37-2-8

1-3-8 1-9-8 4-0-8 5-10-0 4-0-8 9-10-8 6-3-0 16-1-8 4-11-8 21-1-0 4-11-8 26-0-8 4-10-0 30-10-8 5-0-8 35-11-0 37-2-8

Scale = 1/61.0



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
<u>BEARINGS</u>									
	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQ'D BRG			
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
M	1313	0	1313	0	0	5-8	5-8		
X	1316	0	1316	0	0	5-8	5-8		

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 2.00/12 MINIMUM

THIS DESIGN COMPLIES WITH:
 - PART 9 OF BCBC 2018 , ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 086-14
 - TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= $L/360$ (1.20")
 CALCULATED VERT. DEFL.(LL) = $L/999$ (0.16")
 ALLOWABLE DEFL.(TL)= $L/360$ (1.20")
 CALCULATED VERT. DEFL.(TL) = $L/999$ (0.32")

CSI: TC=0.38/1.00 (E-F:1), BC=0.53/1.00 (U-V:1),
WB=0.59/1.00 (B-V:1), SSI=0.35/1.00 (C-V:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES					
PLATE	GRIP (DRY)		SHEAR		SECTION
	(PSI)		(PLI)		(PLI)
	MAX	MIN	MAX	MIN	MAX MIN
MT20	650	371	1747	788	1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg


JSI GRIP= 0.89 (B) (INPUT = 0.90)

JSI METAL= 0.68 (B) (INPUT = 1.00)

TOTAL LOAD CASES: (4)									
C H O R D S					W E B S				
MAX. FACTORED		FACTORED			MAX. FACTORED				
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 CS1 (LC)	MAX CS1 (LC)	MAX. UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX CS1 (LC)	
FR-TO		FROM	TO			FR-TO			
A-B	0 / 17	-56.6	-56.6	0.07 (1)	10.00	T-E	0 / 331	0.07 (1)	
B-C	-2952 / 0	-56.6	-56.6	0.23 (1)	3.88	E-S	0 / 596	0.13 (1)	
C-D	-2444 / 0	-56.6	-56.6	0.28 (1)	4.16	S-Q	0 / 1863	0.30 (1)	
D-E	-2073 / 0	-56.6	-56.6	0.20 (1)	4.55	S-H	0 / 614	0.14 (1)	
E-F	-2323 / 0	-56.6	-56.6	0.38 (1)	4.17	Q-H	-713 / 0	0.42 (1)	
F-G	-2312 / 0	-56.6	-56.6	0.28 (1)	4.27	Q-I	0 / 529	0.12 (1)	
G-H	-2312 / 0	-56.6	-56.6	0.28 (1)	4.27	P-I	0 / 136	0.03 (4)	
H-I	-1869 / 0	-56.6	-56.6	0.21 (1)	4.74	P-J	-131 / 0	0.08 (1)	
I-J	-1722 / 0	-56.6	-56.6	0.21 (1)	4.90	N-J	-216 / 0	0.05 (1)	
J-K	-1814 / 0	-56.6	-56.6	0.22 (1)	4.79	N-K	0 / 1658	0.37 (1)	
K-L	0 / 17	-56.6	-56.6	0.07 (1)	10.00	X-V	-287 / 0	0.04 (1)	
X-B	-1146 / 0	0.0	0.0	0.12 (1)	7.43	B-V	0 / 2625	0.59 (1)	
M-K	-1284 / 0	0.0	0.0	0.13 (1)	7.11	D-T	-448 / 0	0.18 (1)	
						U-D	0 / 101	0.03 (4)	
						C-U	-851 / 0	0.26 (1)	
X-W	0 / 238	-12.3	-12.3	0.04 (1)	10.00				
W-V	0 / 11	0.0	0.0	0.36 (1)	10.00				
V-C	0 / 339	0.0	0.0	0.41 (1)	10.00				
V-U	0 / 3052	-12.3	-12.3	0.53 (1)	10.00				
U-T	0 / 2211	-12.3	-12.3	0.41 (1)	10.00				
T-S	0 / 1846	-12.3	-12.3	0.35 (1)	10.00				
R-S	0 / 27	0.0	0.0	0.08 (1)	10.00				
S-F	-361 / 0	0.0	0.0	0.10 (1)	7.81				
R-Q	0 / 53	-12.3	-12.3	0.07 (4)	10.00				
Q-P	0 / 1529	-12.3	-12.3	0.28 (1)	10.00				
P-O	0 / 1634	-12.3	-12.3	0.29 (1)	10.00				
O-N	0 / 1634	-12.3	-12.3	0.29 (1)	10.00				
N-M	0 / 0	-12.3	-12.3	0.06 (4)	10.00				



JOB NAME 420377	TRUSS NAME T33S	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:47:04 2021 Page 1 ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-V1fbPuV1HY6bvRuY7iDw94wg9djSkVyZlp2ngKyrCrL			



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - E	2x4 DRY	No.2	SPF
E - H	2x4 DRY	No.2	SPF
H - K	2x4 DRY	No.2	SPF
W - B	2x4 DRY	No.2	SPF
L - J	2x4 DRY	No.2	SPF
W - V	2x4 DRY	No.2	SPF
V - C	2x4 DRY	No.2	SPF
U - R	2x4 DRY	No.2	SPF
Q - F	2x4 DRY	No.2	SPF
Q - N	2x4 DRY	No.2	SPF
N - L	2x4 DRY	No.2	SPF
ALL WEBS EXCEPT R - P	2x3 DRY	No.2	SPF
DRY: SEASONED LUMBER.			

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMVW-t	MT20	4.0	9.0	2.00 4.00
C TMVW+p	MT20	4.0	4.0	1.50 2.00
D TMVW-t	MT20	4.0	4.0	2.00 1.75
E TTVW-m	MT20	5.0	6.0	2.25 2.00
F TMV+p	MT20	3.0	4.0	
G TMVW-t	MT20	4.0	4.0	
H TTVW-m	MT20	5.0	6.0	2.25 2.00
I TMVW-t	MT20	4.0	4.0	2.00 1.75
J TMVW-t	MT20	4.0	6.0	
L BMV+p	MT20	3.0	4.0	
M BMVW-t	MT20	5.0	6.0	
N BS-t	MT20	3.0	6.0	
O BMVW-t	MT20	4.0	4.0	
P BMVW-t	MT20	6.0	10.0	
Q BMV+p	MT20	3.0	4.0	
R BVVWVW-t	MT20	6.0	12.0	Edge 4.25
S BMVW-t	MT20	4.0	4.0	
T BMVW-t	MT20	4.0	6.0	
U BVVWVW-t	MT20	5.0	12.0	Edge 6.75
V BMV+p	MT20	3.0	4.0	
W BMVW-t	MT20	4.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REORD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
L	1313	0	1313	0	5-8
W	1316	0	1316	0	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
L	930	599 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0
W	932	601 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, W

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.89 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LC1 MAX. UNBRACED LENGTH (LC)	
FR-TO				FR-TO			
A-B	0 / 17	-56.6	-56.6 0.07 (1)	10.00	C-T	-1003 / 0	0.53 (1)
B-C	-3007 / 0	-56.6	-56.6 0.19 (1)	3.89	T-D	0 / 138	0.04 (4)
C-D	-2347 / 0	-56.6	-56.6 0.35 (1)	4.18	D-S	-571 / 0	0.43 (1)
D-E	-1851 / 0	-56.6	-56.6 0.29 (1)	4.67	S-E	0 / 366	0.08 (1)
E-F	-1797 / 0	-56.6	-56.6 0.13 (1)	4.90	E-R	0 / 294	0.07 (1)
F-G	-1792 / 0	-56.6	-56.6 0.11 (1)	4.92	R-P	0 / 1580	0.25 (1)
G-H	-1546 / 0	-56.6	-56.6 0.10 (1)	5.21	P-G	0 / 490	0.11 (1)
H-I	-1600 / 0	-56.6	-56.6 0.33 (1)	4.90	P-H	-643 / 0	0.64 (1)
I-J	-1855 / 0	-56.6	-56.6 0.36 (1)	4.60	H-R	0 / 288	0.06 (1)
J-K	0 / 17	-56.6	-56.6 0.07 (1)	10.00	O-H	0 / 231	0.05 (1)
W-B	-1143 / 0	0.0	0.0 0.12 (1)	7.43	O-I	-312 / 0	0.35 (1)
L-J	-1279 / 0	0.0	0.0 0.13 (1)	7.13	M-I	-140 / 18	0.04 (1)
W-V	0 / 243	-12.3	-12.3 0.04 (1)	10.00	M-J	0 / 1690	0.38 (1)
V-U	0 / 11	0.0	0.0 0.37 (1)	10.00	W-U	-292 / 0	0.04 (1)
U-C	0 / 331	0.0	0.0 0.42 (1)	10.00	B-U	0 / 2684	0.60 (1)
U-T	0 / 3119	-12.3	-12.3 0.55 (1)	10.00			
T-S	0 / 2122	-12.3	-12.3 0.38 (1)	10.00			
S-R	0 / 1645	-12.3	-12.3 0.30 (1)	10.00			
Q-R	0 / 20	0.0	0.0 0.04 (1)	10.00			
R-F	-214 / 0	0.0	0.0 0.08 (1)	7.81			
Q-P	0 / 31	-12.3	-12.3 0.03 (4)	10.00			
P-O	0 / 1417	-12.3	-12.3 0.26 (1)	10.00			
O-N	0 / 1675	-12.3	-12.3 0.32 (1)	10.00			
N-M	0 / 1675	-12.3	-12.3 0.32 (1)	10.00			
M-L	0 / 0	-12.3	-12.3 0.12 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.27")

CSI: TC=0.36/1.00 (I-J:1), BC=0.55/1.00 (T-U:1), WB=0.64/1.00 (G-P:1), SSI=0.36/1.00 (C-U:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (J) (INPUT = 0.90)
JSI METAL= 0.54 (N) (INPUT = 1.00)




Structural component only
DWG# T-2126499

JOB NAME 420377	TRUSS NAME T34S	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:47:05 2021 Page 1

ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-zUDzcEWf2sESWbTlhPkAilTpP13STwKixTnKCnyrCrK



TOTAL WEIGHT = 162 lb
[M](F)

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - E	2x4	DRY	No.2
E - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - I	2x4	DRY	No.2
I - L	2x4	DRY	No.2
W - B	2x4	DRY	No.2
M - K	2x4	DRY	No.2
W - V	2x4	DRY	No.2
V - C	2x4	DRY	No.2
U - R	2x4	DRY	No.2
Q - G	2x4	DRY	No.2
Q - O	2x4	DRY	No.2
O - M	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
R - P	2x4	DRY	No.2
DRY: SEASONED LUMBER.			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
		GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	UPLIFT	IN-SX
M	1313	0	1313	0	5-8
W	1316	0	1316	0	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
M	930	599 / 0	0 / 0	0 / 0	0 / 0	332 / 0
W	932	601 / 0	0 / 0	0 / 0	0 / 0	332 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M, W

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.89 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-R, J-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)
FR-TO		FROM TO		FR-TO	
A-B	0 / 17	-56.6 -56.6	0.07 (1)	C-T	-1085 / 0
B-C	-3039 / 0	-56.6 -56.6	0.17 (1)	T-D	0 / 151
C-D	-2300 / 0	-56.6 -56.6	0.42 (1)	D-S	-631 / 0
D-E	-1745 / 0	-56.6 -56.6	0.35 (1)	S-F	0 / 391
E-F	-1745 / 0	-56.6 -56.6	0.35 (1)	F-R	0 / 266
F-G	-1636 / 0	-56.6 -56.6	0.20 (1)	R-P	0 / 1345
G-H	-1632 / 0	-56.6 -56.6	0.26 (1)	P-H	0 / 431
H-I	-1535 / 0	-56.6 -56.6	0.41 (1)	H-P	0 / 82
I-J	-1535 / 0	-56.6 -56.6	0.41 (1)	P-J	-390 / 0
J-K	-1860 / 0	-56.6 -56.6	0.46 (1)	N-J	-113 / 33
K-L	0 / 17	-56.6 -56.6	0.07 (1)	N-K	0 / 1695
W-B	-1141 / 0	0.0 0.0	0.12 (1)	W-U	-296 / 0
M-K	-1276 / 0	0.0 0.0	0.13 (1)	B-U	0 / 2718
W-V	0 / 246	-12.3 -12.3	0.05 (1)		
V-U	0 / 11	0.0 0.0	0.37 (1)		
U-C	0 / 331	0.0 0.0	0.42 (1)		
U-T	0 / 3158	-12.3 -12.3	0.56 (1)		
T-S	0 / 2079	-12.3 -12.3	0.39 (1)		
S-R	0 / 1548	-12.3 -12.3	0.28 (1)		
Q-R	0 / 31	0.0 0.0	0.04 (1)		
R-G	-319 / 0	0.0 0.0	0.04 (1)		
Q-P	0 / 28	-12.3 -12.3	0.11 (4)		
P-O	0 / 1682	-12.3 -12.3	0.34 (1)		
O-N	0 / 1682	-12.3 -12.3	0.34 (1)		
N-M	0 / 0	-12.3 -12.3	0.13 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 23.3 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 16.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.28")

CSI: TC=0.46/1.00 (J-K:1), BC=0.56/1.00 (T-U:1),
WB=0.76/1.00 (C-T:1), SS=0.37/1.00 (C-U:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (K) (INPUT = 0.90)


JSI METAL= 0.53 (O) (INPUT = 1.00)



Structural component only
DWG# T-2126500

JOB NAME 420377	TRUSS NAME T35S	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:47:07 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-vtLj1wXvaTUAmvd7oqmenjYJCqIMxpD?OnGRGfyrCr



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - E	2x4	DRY	No.2
E - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
I - K	2x4	DRY	No.2
K - N	2x4	DRY	No.2
Y - B	2x4	DRY	No.2
O - M	2x4	DRY	No.2
Y - X	2x4	DRY	No.2
X - C	2x4	DRY	No.2
W - T	2x4	DRY	No.2
S - H	2x4	DRY	No.2
S - P	2x4	DRY	No.2
P - O	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
T - R	2x4	DRY	No.2


DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	4.0	9.0	2.00 4.00
C	TMVW+p	MT20	4.0	4.0	1.50 2.00
D	TMVW-t	MT20	4.0	4.0	2.00 1.75
E	TS-t	MT20	3.0	6.0	
F	TMVW-t	MT20	4.0	4.0	2.00 1.75
G	TTW-m	MT20	4.0	4.0	
H	TMV+p	MT20	3.0	4.0	
I	TTW-m	MT20	5.0	6.0	2.25 2.00
J	TMVW-t	MT20	4.0	4.0	
K	TS-t	MT20	3.0	6.0	
L	TMVW-t	MT20	4.0	6.0	
M	TMV+p	MT20	3.0	4.0	
O	BMVW1-t	MT20	5.0	6.0	
P	BS-t	MT20	3.0	6.0	
Q, U, V					
Q	BMVW-t	MT20	4.0	4.0	
R	BMVW-t	MT20	6.0	10.0	
S	BMV+p	MT20	3.0	4.0	
T	BVMWVW-t	MT20	6.0	16.0	3.25 5.00
W	BVMWVW-t	MT20	5.0	12.0	Edge 6.75
X	BMV+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
BEARINGS									
JT	FACTORED GROSS REACTION	VERT	HORZ	MAXIMUM FACTORED GROSS REACTION	DOWN	UPLIFT	INPUT BRG	REQD BRG	
O	1313	0	0	1313	0	0	5-8	5-8	
Y	1316	0	0	1316	0	0	5-8	5-8	
UNFACTORED REACTIONS									
JT	1ST LCASE	COMBINED	SNOW	MAX./MIN. COMPONENT REACTIONS	LIVE	PERM. LIVE	WIND	DEAD	SOIL
O	930	599 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0
Y	932	601 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	332 / 0	0 / 0
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, Y									
BRACING									
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.88 FT.									
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.									
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.									
1 LATERAL BRACE(S) AT 1/2 LENGTH OF H-T.									
END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW									

LOADING									
TOTAL LOAD CASES: (4)									
CHORDS									
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC2)	MAX. FACTORED VERT. LOAD (LC3)	MAX. FACTORED VERT. LOAD (LC4)	MAX. FACTORED VERT. LOAD (LC5)	MAX. FACTORED VERT. LOAD (LC6)	MAX. FACTORED VERT. LOAD (LC7)
FR-TO									
A-B	0 / 17	-56.6	-56.6	0.07 (1)	10.00	T-R	0 / 1295	0.21 (1)	
B-C	-2980 / 0	-56.6	-56.6	0.21 (1)	3.88	T-I	0 / 378	0.09 (1)	
C-D	-2407 / 0	-56.6	-56.6	0.30 (1)	4.18	R-I	0 / 97	0.03 (4)	
D-E	-2015 / 0	-56.6	-56.6	0.20 (1)	4.61	R-J	-400 / 0	0.52 (1)	
E-F	-2015 / 0	-56.6	-56.6	0.20 (1)	4.61	J-Q	0 / 100	0.03 (4)	
F-G	-1566 / 0	-56.6	-56.6	0.17 (1)	5.13	Q-L	0 / 54	0.02 (4)	
G-H	-1478 / 0	-56.6	-56.6	0.10 (1)	5.31	L-O	-1922 / 0	0.80 (1)	
H-I	-1476 / 0	-56.6	-56.6	0.16 (1)	5.24	G-T	0 / 636	0.14 (1)	
I-J	-1450 / 0	-56.6	-56.6	0.22 (1)	5.21	Y-W	-290 / 0	0.04 (1)	
J-K	-1766 / 0	-56.6	-56.6	0.26 (1)	4.82	B-W	0 / 2654	0.60 (1)	
K-L	-1766 / 0	-56.6	-56.6	0.26 (1)	4.82	C-V	-920 / 0	0.33 (1)	
L-M	0 / 13	-56.6	-56.6	0.17 (1)	10.00	V-D	0 / 119	0.03 (4)	
M-N	0 / 17	-56.6	-56.6	0.07 (1)	10.00	D-U	-451 / 0	0.22 (1)	
Y-B	-1144 / 0	0.0	0.0	0.12 (1)	7.43	U-F	0 / 321	0.07 (1)	
O-M	-164 / 0	0.0	0.0	0.02 (1)	7.81	F-T	-560 / 0	0.61 (1)	
Y-X	0 / 240	-12.3	-12.3	0.04 (1)	10.00				
X-W	0 / 11	0.0	0.0	0.36 (1)	10.00				
W-C	0 / 336	0.0	0.0	0.41 (1)	10.00				
W-V	0 / 3085	-12.3	-12.3	0.54 (1)	10.00				
V-U	0 / 2174	-12.3	-12.3	0.39 (1)	10.00				
U-T	0 / 1799	-12.3	-12.3	0.34 (1)	10.00				
S-T	0 / 19	0.0	0.0	0.03 (1)	10.00				
T-H	-238 / 0	0.0	0.0	0.03 (1)	6.25				
S-R	0 / 19	-12.3	-12.3	0.10 (4)	10.00				
R-Q	0 / 1545	-12.3	-12.3	0.33 (1)	10.00				
Q-P	0 / 1569	-12.3	-12.3	0.34 (1)	10.00				
P-O	0 / 1569	-12.3	-12.3	0.34 (1)	10.00				

DESIGN CRITERIA	
SPECIFIED LOADS:	
TOP CH. LL	= 23.3 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 36.7 PSF
SPACING = 16.0 IN./C	
LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM	
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015	
THIS DESIGN COMPLIES WITH:	
- PART 9 OF BCBC 2018, ABC 2019	
- PART 9 OF OBC 2012 (2019 AMENDMENT)	
- CSA 086-14	
- TPIC 2014	
DESIGN ASSUMPTIONS	
- OVERHANG NOT TO BE ALTERED OR CUT OFF.	
(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD	
ALLOWABLE DEFL.(LL)= L/360 (1.20")	
CALCULATED VERT. DEFL.(LL) = L/999 (0.13")	
ALLOWABLE DEFL.(TL)= L/360 (1.20")	
CALCULATED VERT. DEFL.(TL) = L/999 (0.27")	
CSI: TC=0.30/1.00 (C-D:1), BC=0.54/1.00 (V-W:1), WB=0.80/1.00 (L-O:1), SSI=0.36/1.00 (C-W:1)	
DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10	
COMPANION LIVE LOAD FACTOR = 1.00	
AUTOSOLVE RIGHT HEEL ONLY	
TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.	
NAIL VALUES	
PLATE GRIP(DRY)	SHEAR SECTION
(PSI)	(PLI)
MAX MIN	MAX MIN
MT20	650 371 1747 788 1987 1873
PLATE PLACEMENT TOL = 0.250 inches	
PLATE ROTATION TOL = 5.0 Deg.	
JSI GRIP= 0.90 (V) (INPUT = 0.90)	
JSI METAL= 0.52 (W) (INPUT = 1.00)	



Structural component only
DWG# T-2126501

JOB NAME 420377	TRUSS NAME T35S	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:47:07 2021 Page 2
ID:rhOOT9Mf?GOVQD N1160ZyxmN3-vtLj1wXvaTUAmvd7oqmeniYCJqIMxpD?OnGRGfyrCrl

PLATES (table is in inches)
JT TYPE PLATES W LEN Y X
Y BMVW1-t MT20 4.0 4.0

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.

NOTES: (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.




Structural component only
DWG# T-2126501 *me*

JOB NAME 420377	TRUSS NAME T36S	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Wed Aug 4 14:47:08 2021 Page 1

ID: rhtOOT9Mf?GOVQD_N1I60ZyxmN3-N3v5EGYYLnc1N3BKMxiw5MnE4Ughv8dR0_p6yrCrH



TOTAL WEIGHT = 168 lb [M][F]

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - E	2x4 DRY	No.2	SPF
E - G	2x4 DRY	No.2	SPF
G - H	2x4 DRY	No.2	SPF
H - J	2x4 DRY	No.2	SPF
J - M	2x4 DRY	No.2	SPF
Z - B	2x4 DRY	No.2	SPF
N - L	2x4 DRY	No.2	SPF
Z - Y	2x4 DRY	No.2	SPF
Y - C	2x4 DRY	No.2	SPF
X - U	2x4 DRY	No.2	SPF
T - Q	2x4 DRY	No.2	SPF
Q - N	2x4 DRY	No.2	SPF
ALL WEBS EXCEPT	2x3 DRY	No.2	SPF
S - G	2x4 DRY	No.2	SPF
U - R	2x4 DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	9.0	2.00	4.00
C	TMVW-p	MT20	4.0	4.0	1.50	2.00
D, F, I, K						
D	TMVW-t	MT20	4.0	4.0	2.00	1.75
E	TS-t	MT20	3.0	6.0		
G	TTW-m	MT20	4.0	4.0		
H	TTW-m	MT20	5.0	8.0	2.25	2.00
J	TS-t	MT20	3.0	6.0		
L	TMVW-t	MT20	4.0	6.0		
N	BMV1-p	MT20	3.0	4.0		
O	BMVW-t	MT20	5.0	6.0		
P	BMVW-t	MT20	4.0	4.0		
Q	BS-t	MT20	3.0	6.0		
R	BMVW-t	MT20	6.0	10.0		
S	BMVW-t	MT20	2.0	4.0		
U	BMVW-t	MT20	6.0	12.0	Edge	4.50
V	BMVW-t	MT20	4.0	4.0		
W	BMVW-t	MT20	4.0	6.0		
X	BMVW-t	MT20	5.0	12.0	Edge	6.75
Y	BMV-p	MT20	3.0	4.0		
Z	BMVW-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	UP
N	1316	0	1316	0
Z	1320	0	1320	0

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX. MIN. SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
N	933	599 / 0	0 / 0	0 / 0	0 / 0	334 / 0	0 / 0
Z	936	601 / 0	0 / 0	0 / 0	0 / 0	335 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, Z

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.88 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

MAX. UNBRACED INTERIOR CHORD LENGTH = 10.00 FT

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF H-R, I-R.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC)	
FR-TO		FROM	TO	FR-TO		FROM	TO
A-B	0 / 17	-56.6	-56.6 0.07 (1)	C-W	-966 / 0	0.40 (1)	
B-C	-3006 / 0	-56.6	-56.6 0.20 (1)	W-D	0 / 127	0.03 (4)	
C-D	-2391 / 0	-56.6	-56.6 0.32 (1)	D-V	-469 / 0	0.26 (1)	
D-E	-1976 / 0	-56.6	-56.6 0.21 (1)	V-F	0 / 328	0.07 (1)	
E-F	-1976 / 0	-56.6	-56.6 0.21 (1)	F-H	-42 / 22	0.02 (1)	
F-G	-1524 / 0	-56.6	-56.6 0.21 (1)	H-I	-461 / 0	0.23 (1)	
G-H	-1360 / 0	-56.6	-56.6 0.08 (1)	I-J	0 / 160	0.04 (4)	
H-I	-1372 / 0	-56.6	-56.6 0.22 (1)	J-K	-168 / 0	0.13 (1)	
I-J	-1692 / 0	-56.6	-56.6 0.22 (1)	K-L	-178 / 0	0.04 (1)	
J-K	-1692 / 0	-56.6	-56.6 0.22 (1)	L-M	0 / 1671	0.38 (1)	
K-L	-1835 / 0	-56.6	-56.6 0.27 (1)	M-N	0 / 15	0.02 (1)	
L-M	0 / 17	-56.6	-56.6 0.07 (1)	N-O	0 / 477	0.10 (1)	
M-N	-1147 / 0	0.0	0.0 0.12 (1)	O-P	-596 / 0	0.70 (1)	
N-O	-1285 / 0	0.0	0.0 0.13 (1)	P-Q	-292 / 0	0.04 (1)	
O-P	0 / 243	-12.3	-12.3 0.04 (1)	Q-R	0 / 2681	0.60 (1)	
P-Q	0 / 11	0.0	0.0 0.37 (1)	R-S	0 / 1282	0.21 (1)	
Q-R	0 / 335	0.0	0.0 0.42 (1)	S-T	0 / 470	0.11 (1)	
R-S	0 / 3116	-12.3	-12.3 0.54 (1)	T-U			
S-T	0 / 2159	-12.3	-12.3 0.38 (1)	U-V			
T-U	0 / 1767	-12.3	-12.3 0.33 (1)	V-W			
U-V	0 / 0	-12.3	-12.3 0.00 (4)	W-X			
V-W	0 / 15	-12.3	-12.3 0.06 (4)	X-Y			
W-X	0 / 1514	-12.3	-12.3 0.29 (1)	Y-Z			
X-Y	0 / 1514	-12.3	-12.3 0.29 (1)	Z-A			
Y-Z	0 / 1652	-12.3	-12.3 0.30 (1)	A-B			
Z-A	0 / 0	-12.3	-12.3 0.08 (4)	B-C			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 16.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.27")

CSI: TC=0.32/1.00 (C-D:1), BC=0.54/1.00 (W-X:1), WB=0.70/1.00 (F-U:1), SSI=0.36/1.00 (C-X:1)

DOL LUMBER=1.00 NAIL=1.00 LS DEN=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (L) (INPUT = 0.90)
JSI METAL= 0.52 (X) (INPUT = 1.00)



Structural component only
DWG# T-2126502




Structural component only
DWG# T-2126508

JOB NAME 420378	TRUSS NAME T39	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
---------------------------	--------------------------	----------------------	-----------------	--------------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:17 2021 Page 1
ID:rhT0OT9Mf?GOVQD_N1160ZyxnN3-KbKH-HykeJaf9L_Um?8UTCOMIjAb?hRdiGhQBMkyrCka



Scale = 1:34.7

TOTAL WEIGHT = 2 X 34 = 69 lb

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
F - A	2x6 DRY	No.2	SPF
A - C	2x4 DRY	No.2	SPF
D - C	2x4 DRY	No.2	SPF
F - D	2x6 DRY	No.2	SPF
ALL WEBS	2x3 DRY	No.2	SPF
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F-A 2	12	TOP
A-C 1	12	TOP
C-D 1	12	SIDE(53.2)
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2	12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
B-E 1	6	SIDE(83.5)
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	5.0	6.0	2.00	2.25
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TMV+p	MT20	3.0	4.0		
D	BMVW1+p	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REORD	
JT	GROSS REACTION	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	BRG
F	1060	0	0	1060	0	0	5-8	5-8	
D	1441	0	0	1441	0	0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 4.0.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	746	512 / 0	0 / 0	0 / 0	0 / 0	0 / 0	234 / 0	0 / 0
D	1016	683 / 0	0 / 0	0 / 0	0 / 0	0 / 0	333 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
F-A	-886 / 0	0.0	0.0 0.03 (1)	A-E	0 / 680	0.08 (1)	
A-B	-793 / 0	-84.9	-84.9 0.05 (1)	E-B	0 / 1030	0.13 (1)	
B-C	-16 / 0	-84.9	-84.9 0.05 (1)	B-D	-1009 / 0	0.16 (1)	
D-C	-91 / 0	0.0	0.0 0.03 (1)				
F-G	0 / 0	-18.5	-18.5 0.06 (1)				
G-E	0 / 0	-18.5	-18.5 0.06 (1)				
E-H	0 / 621	-18.5	-18.5 0.15 (1)				
H-D	0 / 621	-18.5	-18.5 0.15 (1)				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	2-11-4	-720	-720	---	FRONT	VERT	TOTAL	---	C1
G	11-4	-166	-166	---	TOP	VERT	TOTAL	---	C1
H	4-11-4	-473	-473	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.05/1.00 (A-B:1), BC=0.15/1.00 (D-E:1),
WB=0.16/1.00 (B-D:1), SS=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.56 (B) (INPUT = 0.90)
JSI METAL= 0.14 (D) (INPUT = 1.00)



Structural component only
DWG# T-2126509

CONTINUED ON PAGE 2


JOB NAME 420378	TRUSS NAME T39	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:17 2021 Page 2
ID:rhT0OT9Mf?GOVQD N1160ZyxmN3-KbKHHykeJaf9L Um?8UTCOMIiAb?hRdlGhQBMkyrCka

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
E	BMWV-t	MT20	5.0	6.0		
F	BMV1+p	MT20	3.0	6.0		


NOTES: (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.



Structural component only
DWG# T-2126509 *me*

JOB NAME 420378	TRUSS NAME T39Z	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:18 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1I60ZymN3-ocufUIIG4un0z83zYr?ilcuwUav4QtoRVKAluAyrGkZ



TOTAL WEIGHT = 2 X 34 = 69 lb [M]

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
F - A	2x6 DRY	No.2	SPF
A - C	2x4 DRY	No.2	SPF
D - C	2x4 DRY	No.2	SPF
F - D	2x6 DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF			
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F-A 3	2	SIDE (242.8)
A-C 1	12	TOP
C-D 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2	12	SIDE (183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
B-E 1	6	SIDE (75.3)
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	5.0	6.0	2.00	2.25
B	TMVW-l	MT20	4.0	4.0	2.00	1.25
C	TMV+p	MT20	3.0	4.0		
D	BMVW1+p	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	UP	BRG
F	2372	0	2372	0	5-8
D	1809	0	1809	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 4-0.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
F	1675	1113 / 0	0 / 0	0 / 0	0 / 0	562 / 0	0 / 0	
D	1278	846 / 0	0 / 0	0 / 0	0 / 0	432 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6-25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO	FROM TO	FR-TO	FROM TO
F-A	-1231 / 0	A-E	0 / 974
A-B	-1143 / 0	E-B	0 / 1601
B-C	-15 / 0	B-D	-1445 / 0
D-C	-93 / 0		
F-G	0 / 0		
G-E	0 / 0		
E-H	0 / 890		
H-D	0 / 890		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	2-6-12	-699	-699	---	BACK	VERT	TOTAL	---	C1
G	8-4	-1152	-1152	---	BACK	VERT	TOTAL	---	C1
H	4-6-12	-700	-700	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
DL = 6.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.05/1.00 (A-B:1), BC=0.29/1.00 (E-F:1),
WB=0.23/1.00 (B-D:1), SSI=0.38/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (B) (INPUT = 0.90)
JSI METAL= 0.20 (D) (INPUT = 1.00)



Structural component only
DWG# T-2126510

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ROYAL PINE HOMES	DRWG NO.
420378	T39Z	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington


Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:18 2021 Page 2
ID:rhT0OT9Mf?GOVQD N1I60ZyxmN3-ooofUIIG4un0z83zYr?ilcuwUav4QtoRVKAiuAyrCKZ

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
E	BMW-t	MT20	5.0	6.0		
F	BMV1+p	MT20	3.0	6.0		

NOTES- (1)


1) Lateral braces to be a minimum of 2X4 SPF #2.



Structural component only
DWG# T-2126510 *me*

JOB NAME 420378	TRUSS NAME T40	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:19 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZymN3-G_R1iemurCvble96ZWxHpR2qzFz9F?ak_vIRdyrCkY



TOTAL WEIGHT = 89 lb [M/F]

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - H	2x4	DRY	No.2
M - B	2x4	DRY	No.2
I - G	2x4	DRY	No.2
M - K	2x4	DRY	No.2
K - I	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVW-t	MT20	4.0	6.0		
D	TTW-m	MT20	4.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMVW-t	MT20	4.0	6.0		
G	TMV+p	MT20	3.0	4.0		
I	BMVW1-t	MT20	4.0	4.0		
J	BMVW-t	MT20	4.0	4.0		
K	BS-t	MT20	3.0	8.0		
L	BMVWW-t	MT20	4.0	9.0	2.00	3.50
M	BMVW1-t	MT20	4.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	BRG	BRG
M	1009 0	1009 0	0 0	5-8	5-8
I	1009 0	1009 0	0 0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 3-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
M	714	466 / 0	0 / 0	0 / 0	248 / 0	0 / 0
I	714	466 / 0	0 / 0	0 / 0	248 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 / 38	C-L	-156 / 0
B-C	0 / 25	L-D	0 / 218
C-D	-677 / 0	D-E	0 / 5
D-E	-503 / 0	E-F	0 / 212
E-F	-676 / 0	F-G	-157 / 0
F-G	0 / 25	G-H	-931 / 0
G-H	0 / 38	H-I	-929 / 0
H-I	-242 / 0	I-G	0 / 0
I-G	-242 / 0		
M-L	0 / 604		
L-K	0 / 502		
K-J	0 / 502		
J-I	0 / 603		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
DL = 6.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD = 36.7 PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.57")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.57")
CALCULATED VERT. DEFL.(TL) = L/999 (0.11")

CSI: TC=0.21/1.00 (F-G:1), BC=0.31/1.00 (L-M:4),
WB=0.55/1.00 (C-M:1), SSI=0.12/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.71 (M) (INPUT = 0.90)
JSI METAL= 0.56 (K) (INPUT = 1.00)




Structural component only
DWG# T-2126511

JOB NAME 420378	TRUSS NAME T41	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:20 2021 Page 1
ID:rhT0OT9Mf?GOVQD_N160ZyxmN3-kA?Qv_nWbV1kCRDLgG2Aq1_BzNc0uookyefrz3yrCkX



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
K - B	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	
K - I	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TTW-m	MT20	4.0	4.0		
E	TMVW+p	MT20	4.0	4.0	1.00	2.00
G	BMV1+p	MT20	3.0	4.0		
H	BMVWW-t	MT20	4.0	9.0		
I	BS-t	MT20	3.0	6.0		
J	BMVW-t	MT20	4.0	4.0		
K	BMV1+p	MT20	3.0	4.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	GROSS REACTION	BRG	BRG	
JT VERT	HORZ	DOWN	HORZ	UPLIFT
K 1009	0	1009	0	0
G 1009	0	1009	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3'-8".

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
K 714	466 / 0	0 / 0	0 / 0	0 / 0	248 / 0	0 / 0	
G 714	466 / 0	0 / 0	0 / 0	0 / 0	248 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)	W E B S	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC)
FR-TO						FR-TO			
A-B	0 / 38	-84.9	-84.9	0.12 (1)	10.00	J-C	-13 / 81	0.03 (4)	
B-C	-742 / 0	-84.9	-84.9	0.37 (1)	6.25	C-H	0 / 2	0.00 (4)	
C-D	-569 / 0	-84.9	-84.9	0.36 (1)	6.25	H-D	-11 / 82	0.03 (4)	
D-E	-743 / 0	-84.9	-84.9	0.37 (1)	6.25	B-J	0 / 583	0.13 (1)	
E-F	0 / 38	-84.9	-84.9	0.12 (1)	10.00	H-E	0 / 583	0.13 (1)	
K-B	-964 / 0	0.0	0.0	0.10 (1)	7.81				
G-E	-964 / 0	0.0	0.0	0.10 (1)	7.81				
K-J	0 / 0	-18.5	-18.5	0.14 (4)	10.00				
J-I	0 / 568	-18.5	-18.5	0.19 (4)	10.00				
I-H	0 / 568	-18.5	-18.5	0.19 (4)	10.00				
H-G	0 / 0	-18.5	-18.5	0.14 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.57")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.57")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.37/1.00 (D-E:1), BC=0.19/1.00 (H-J:4),
WB=0.13/1.00 (E-H:1), SSI=0.19/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.88 (E) (INPUT = 0.90)
JSI METAL= 0.25 (E) (INPUT = 1.00)



Structural component only
DWG# T-2126512

JOB NAME 420378	TRUSS NAME T43	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:22 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxnM3-gZ7AKfon77HSSINKnh4evS3YFBJaMjH1Qy8y1yyrCkV



Scale = 1:40.7

TOTAL WEIGHT = 65 lb
[M/F]

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
J - B	2x4	DRY	No.2
G - E	2x4	DRY	No.2
J - G	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TTW-m	MT20	4.0	4.0		
E	TMVW+p	MT20	4.0	4.0	1.00	2.00
G	BMV1+p	MT20	3.0	4.0		
H	BMVWW-t	MT20	4.0	6.0	2.00	1.50
I	BMVW-t	MT20	4.0	4.0		
J	BMV1+p	MT20	3.0	4.0		

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	DOWN	HORIZ	UPLIFT
J	686	0	686	0
G	686	0	686	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	485	321 / 0	0 / 0	0 / 0	0 / 0	164 / 0	0 / 0
G	485	321 / 0	0 / 0	0 / 0	0 / 0	164 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 38	-84.9	-84.9 0.12 (1)	I-C	-66 / 19	0.06 (1)	
B-C	-295 / 0	-84.9	-84.9 0.26 (1)	C-H	-4 / 1	0.00 (1)	
C-D	-224 / 0	-84.9	-84.9 0.02 (1)	H-D	-71 / 21	0.07 (1)	
D-E	-294 / 0	-84.9	-84.9 0.26 (1)	B-I	0 / 263	0.06 (1)	
E-F	0 / 38	-84.9	-84.9 0.12 (1)	H-E	0 / 262	0.06 (1)	
J-B	-649 / 0	0.0	0.0 0.12 (1)				
G-E	-648 / 0	0.0	0.0 0.12 (1)				
J-I	0 / 0	-18.5	-18.5 0.10 (4)				
I-H	0 / 225	-18.5	-18.5 0.12 (4)				
H-G	0 / 0	-18.5	-18.5 0.10 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.37")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.37")
CALCULATED VERT. DEFL.(TL)= L/999 (0.02")

CSI: TC=0.26/1.00 (B-C:1), BC=0.12/1.00 (H-I:4), WB=0.07/1.00 (D-H:1), SI=0.12/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.47 (B) (INPUT = 0.90)
JSI METAL= 0.13 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126514

JOB NAME 420378	TRUSS NAME T44	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					



Scale = 1:31.2

TOTAL WEIGHT = 68 lb

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - H	2x4	DRY	No.2
O - B	2x4	DRY	No.2
I - G	2x4	DRY	No.2
O - N	2x4	DRY	No.2
N - C	2x4	DRY	No.2
M - K	2x4	DRY	No.2
J - F	2x4	DRY	No.2
J - I	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2
O - M	2x4	DRY	No.2
K - I	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00	2.00
C	TMV+p	MT20	3.0	4.0		
D	TTWW+m	MT20	5.0	6.0	Edge	
E	TTWW+m	MT20	5.0	6.0	Edge	
F	TMV+p	MT20	3.0	4.0		
G	TMVW+p	MT20	4.0	4.0	1.00	2.00
I	BMVW1-t	MT20	4.0	4.0		
J	BMV+p	MT20	3.0	4.0		
K	BMVWWW-I	MT20	6.0	10.0	3.00	4.00
L	BMVW-t	MT20	4.0	4.0		
M	BMVWWW-I	MT20	6.0	10.0	3.00	4.00
N	BMV+p	MT20	3.0	4.0		
O	BMVW1-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
O	925	0	925	0	5-8
I	925	0	925	0	5-8

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
O	653	434 / 0	0 / 0	0 / 0	0 / 0	219 / 0	0 / 0
I	653	434 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	FORCE (LBS)	MEMB.	FORCE (LBS)
FR-TO	FROM TO	FR-TO	FROM TO
A-B	0 / 38	C-M	-12 / 0
B-C	-565 / 0	K-I	-12 / 0
C-D	-530 / 0	B-M	0 / 519
D-P	-480 / 0	K-G	0 / 519
P-Q	-480 / 0	D-L	0 / 78
Q-R	-480 / 0	M-D	-97 / 0
R-S	-480 / 0	L-E	0 / 78
S-F	-480 / 0	E-K	-97 / 0
F-G	-530 / 0		
G-H	-565 / 0		
H-I	0 / 38		
O-B	-901 / 0		
I-G	-901 / 0		
O-N	0 / 8		
N-M	0 / 143		
M-C	-65 / 0		
M-T	0 / 441		
T-U	0 / 441		
U-L	0 / 441		
L-V	0 / 441		
V-W	0 / 441		
W-K	0 / 441		
J-K	0 / 17		
K-F	-65 / 0		
J-I	0 / 8		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
K	9-4-4	-90	-90	---	FRONT	VERT	TOTAL	---	C1
N	1-7-12	-90	-90	---	FRONT	VERT	TOTAL	---	C1
P	3-5-4	-40	-40	---	FRONT	VERT	TOTAL	---	C1
Q	5-0-0	-26	-26	---	FRONT	VERT	TOTAL	---	C1
R	6-0-0	-26	-26	---	FRONT	VERT	TOTAL	---	C1
S	7-6-12	-40	-40	---	FRONT	VERT	TOTAL	---	C1
T	3-5-4	-6	-6	---	FRONT	VERT	TOTAL	---	C1
U	5-0-0	-6	-6	---	FRONT	VERT	TOTAL	---	C1
V	6-0-0	-6	-6	---	FRONT	VERT	TOTAL	---	C1
W	7-6-12	-6	-6	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.37")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.37")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.60/1.00 (D-E:1), BC=0.15/1.00 (K-L:4), WB=0.13/1.00 (G-K:1), SS=0.27/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.62 (B) (INPUT = 0.90)
JSI METAL= 0.18 (G) (INPUT = 1.00)




Structural component only
DWG# T-2126515

CONTINUED ON PAGE 2

JOB NAME 420378	TRUSS NAME T45	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:24 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1l60ZyxmN3-cxFWLq1fkX9h3X7v666_t8ww_z2qerJtGd36qyrCkt



Scale = 1:27.3

TOTAL WEIGHT = 2 X 22 = 43 lb

LUMBER			
CHORDS	SIZE	LUMBER	DESCR.
D - A	2x4 DRY	No.2	SPF
A - B	2x4 DRY	No.2	SPF
C - B	2x4 DRY	No.2	SPF
D - C	2x6 DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF			
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
D-A 1	12	TOP
A-B 1	12	TOP
B-C 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D-C 2	12	SIDE (0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TMV+p	MT20	3.0	4.0		
C	BMVW1-t	MT20	5.0	6.0		
D	BMV1+p	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQD
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
D	534	0	534	0	0
C	534	0	534	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 2-0.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
D	377	251 / 0	0 / 0	0 / 0	0 / 0	0 / 0	127 / 0	0 / 0
C	377	251 / 0	0 / 0	0 / 0	0 / 0	0 / 0	127 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED UNBRACED LENGTH (FT)
FR-TO			
D-A	-164 / 0	0.0	0.01 (1)
A-B	0 / 0	-84.9	0.12 (1)
C-B	-164 / 0	0.0	0.03 (1)
D-E	0 / 0	-18.5	0.25 (1)
E-C	0 / 0	-18.5	0.25 (1)

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	1-11-4	-470	-470	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.12/1.00 (A-B:1), BC=0.25/1.00 (C-D:1),
WB=0.00/1.00 (A-C:1), SS=0.12/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.06 (A) (INPUT = 0.90)
JSI METAL= 0.03 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126516

JOB NAME 420378	TRUSS NAME T46	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:25 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N160ZyxmN3-58pJyhqfQ2g0JD6JTpLX4h44OM?Z5nT6wMceGyrCkS



Scale = 1:25.4

TOTAL WEIGHT = 2 X 26 = 52 lb [M]

LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	SPF	
A - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	
G - B	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	
ALL WEBS 2x3 DRY No.2 EXCEPT				SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TMV+p	MT20	3.0	4.0		
E	BMVW1-t	MT20	4.0	4.0		
F	BMVW1-t	MT20	4.0	4.0		
G	BMV1+p	MT20	3.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	VERT	HORZ	DOWN	HORZ
E	138	0	138	0	0
G	314	0	314	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	99	61 / -16	0 / 0	0 / 0	0 / 0	38 / 0	0 / 0
G	220	157 / 0	0 / 0	0 / 0	0 / 0	63 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (9)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 38	-84.9	-84.9 0.16 (5)	10.00	F-C	-37 / 28	0.01 (6)
B-C	-68 / 0	-84.9	-84.9 0.15 (5)	6.25	C-E	-64 / 8	0.02 (1)
C-D	0 / 0	-84.9	-84.9 0.04 (1)	10.00	B-F	-8 / 50	0.01 (1)
E-D	-64 / 0	0.0	0.0 0.02 (1)	7.81			
G-B	-299 / 0	0.0	0.0 0.06 (1)	7.81			
G-F	0 / 0	-18.5	-18.5 0.01 (4)	10.00			
F-E	-3 / 22	-18.5	-18.5 0.01 (1)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	1-4-8	-25	-25	---	BACK	VERT	TOTAL	---	C1
F	1-5-4	-2	-2	30	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.16/1.00 (A-B:5), BC=0.01/1.00 (E-F:1), WB=0.02/1.00 (C-E:1), SSI=0.09/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX MIN	MAX MIN	MAX MIN	
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.20 (B) (INPUT = 0.90)
JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126517

JOB NAME 420378	TRUSS NAME T47	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:26 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-ZKNhA1rHBLotwMgV0X9a4IEGSoiGIYLcLa6AAjyrCkR



TOTAL WEIGHT = 2 X 16 = 32 lb

LUMBER				DESCR.	
N. L. G. A. RULES	SIZE	LUMBER			
CHORDS					
A - C	2x4 DRY	No.2		SPF	
D - C	2x4 DRY	No.2		SPF	
E - B	2x4 DRY	No.2		SPF	
E - D	2x4 DRY	No.2		SPF	
ALL WEBS	2x3 DRY	No.2		SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
C	TMV+p	MT20	3.0	4.0	
D	BMVW1-t	MT20	4.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
		GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
D	12	0	14	0	-43
E	248	0	248	0	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
D	10	0/-32	0/0	0/0	0/0	10/0	0/0
E	172	129/0	0/0	0/0	0/0	43/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRACED LENGTH (FT)	MEMB. MAX. FACTORED FORCE (LBS)
FR-TO					
A-B	0/38	-84.9	-84.9 0.12 (1)	10.00	B-D 0/0
B-C	-38/0	-84.9	-84.9 0.11 (1)	6.25	
D-C	0/52	0.0	0.0 0.01 (5)	10.00	
E-B	-235/0	0.0	0.0 0.04 (1)	7.81	
E-D	0/0	-18.5	-18.5 0.01 (4)	10.00	

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (TL) = L/360 (0.19")
CALCULATED VERT. DEFL. (TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.01/1.00 (D-E:4),
WB=0.00/1.00 (B-D:1), SS=0.07/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.17 (B) (INPUT = 0.90)
JSI METAL = 0.04 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126518

JOB NAME 420378	TRUSS NAME T48	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:27 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-1Ww3NNsvyhwkYWFhaEgpcVmM2Cwq1rxmZErj9yrCkQ



TOTAL WEIGHT = 2 X 197 = 394 lb

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - C	2x4	DRY	No.2
C - F	2x6	DRY	No.2
F - H	2x6	DRY	No.2
H - J	2x4	DRY	No.2
T - B	2x6	DRY	No.2
K - I	2x6	DRY	No.2
T - Q	2x6	DRY	No.2
Q - N	2x6	DRY	No.2
N - K	2x6	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2
B - S	2x4	DRY	No.2
L - I	2x4	DRY	No.2

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
H - J	12	TOP
C - F	12	SIDE(0.0)
F - H	12	TOP
T - B	12	TOP
K - I	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
T - Q	12	SIDE(183.1)
Q - N	12	SIDE(183.1)
N - K	12	TOP
WEBS : (0.122"x3") SPIRAL NAILS		
R - D	6	SIDE(188.0)
E - O	6	SIDE(284.0)
2x3	6	
2x4	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS			
FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT HORZ	JT VERT HORZ	IN-SX	IN-SX
T 4136 0	4136 0	5-8	5-8
K 3574 0	3574 0	5-15	5-15

UNFACTORED REACTIONS

1ST LCASE	MAX. MIN. COMPONENT REACTIONS						
JT COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	
T 2924	1923 / 0	0 / 0	0 / 0	0 / 0	1001 / 0	0 / 0	
K 2528	1656 / 0	0 / 0	0 / 0	0 / 0	872 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.11 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED HORZ. LOAD (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORZ. LOAD (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 38	-84.9 -84.9 0.06 (1)	10.00	S-C	-671 / 0	0.19 (1)	
B-C	-4611 / 0	-84.9 -84.9 0.45 (1)	4.14	L-H	-572 / 0	0.16 (1)	
C-D	-6731 / 0	-84.9 -84.9 0.24 (1)	4.43	B-S	0 / 3639	0.32 (1)	
D-U	-7691 / 0	-84.9 -84.9 0.32 (1)	4.11	L-I	0 / 3079	0.27 (1)	
U-V	-7691 / 0	-84.9 -84.9 0.32 (1)	4.11	R-D	-1697 / 0	0.46 (1)	
V-W	-7691 / 0	-84.9 -84.9 0.32 (1)	4.11	M-G	-2499 / 0	0.68 (1)	
W-E	-7691 / 0	-84.9 -84.9 0.32 (1)	4.11	C-R	0 / 4532	0.56 (1)	
E-F	-7705 / 0	-84.9 -84.9 0.29 (1)	4.15	M-H	0 / 3707	0.46 (1)	
F-G	-7705 / 0	-84.9 -84.9 0.29 (1)	4.15	E-O	-304 / 0	0.08 (1)	
G-H	-5608 / 0	-84.9 -84.9 0.15 (1)	4.87	P-E	-562 / 0	0.16 (1)	
H-I	-3902 / 0	-84.9 -84.9 0.39 (1)	4.47	D-P	0 / 1306	0.16 (1)	
I-J	0 / 41	-84.9 -84.9 0.08 (1)	10.00	O-G	0 / 2857	0.35 (1)	
T-B	-4101 / 0	0.0 0.0 0.15 (1)	7.03				
K-I	-3534 / 0	0.0 0.0 0.13 (1)	7.45				

T-S	0 / 0	-18.5 -18.5 0.04 (4)	10.00
S-R	0 / 3561	-18.5 -18.5 0.26 (1)	10.00
R-Q	0 / 6731	-18.5 -18.5 0.49 (1)	10.00
Q-X	0 / 6731	-18.5 -18.5 0.49 (1)	10.00
X-Y	0 / 6731	-18.5 -18.5 0.49 (1)	10.00
Y-Z	0 / 6731	-18.5 -18.5 0.49 (1)	10.00
Z-P	0 / 6731	-18.5 -18.5 0.49 (1)	10.00
P-O	0 / 7742	-18.5 -18.5 0.57 (1)	10.00
O-N	0 / 5606	-18.5 -18.5 0.43 (1)	10.00
N-M	0 / 5606	-18.5 -18.5 0.43 (1)	10.00
M-L	0 / 3013	-18.5 -18.5 0.22 (1)	10.00
L-K	0 / 0	-18.5 -18.5 0.03 (4)	10.00

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
O	18-6-8	-1263	-1263	---	BACK	VERT	TOTAL	---	C1
R	11-1-8	-1001	-1001	---	BACK	VERT	TOTAL	---	C1
U	13-0-12	-102	-102	---	BACK	VERT	TOTAL	---	C1
V	15-0-12	-102	-102	---	BACK	VERT	TOTAL	---	C1
W	16-7-4	-102	-102	---	BACK	VERT	TOTAL	---	C1
X	13-0-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
Y	15-0-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
Z	16-7-4	-26	-26	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.28")

CSI: TC=0.45/1.00 (B-C:1), BC=0.57/1.00 (O-P:1),
WB=0.68/1.00 (G-M:1), SS=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (L) (INPUT = 0.90)
JSI METAL= 0.61 (Q) (INPUT = 1.00)



Structural component only
DWG# T-2126519

CONTINUED ON PAGE 2

JOB NAME 420378	TRUSS NAME T48	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:27 2021 Page 2
ID:rhT0OT9Mf?GOVQD N160ZyxmN3-1Ww3NNsvyfwkYWFhaEgpcVmM2Cwg1rxmZErij9yrCkQ

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	Edge	
C	TTWW+m	MT20	5.0	8.0	Edge	
D, E, G						
D	TMWW-t	MT20	5.0	6.0		
F	TS-t	MT20	5.0	6.0		
H	TTWW+m	MT20	5.0	8.0	Edge	
I	TMVW-p	MT20	5.0	8.0	Edge	
K	BMV1+p	MT20	3.0	6.0		
L, O, P, S						
L	BMWW-t	MT20	5.0	6.0		
M	BMWW+t	MT20	5.0	6.0	2.75	2.00
N	BS-t	MT20	5.0	6.0		
Q	BS-t	MT20	5.0	6.0		
R	BMWW+t	MT20	5.0	6.0	2.75	2.00
T	BMV1+p	MT20	3.0	6.0		


Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

NOTES- (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




Structural component only
DWG# T-2126519 *ML*

JOB NAME 420381	TRUSS NAME T49	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:31 2021 Page 1

ID:Z9U1O5i40r9N9gEXuxpSeqywcSD- _spe1e3JmmPL_fElh6fWZg3L8TGLQ668PEAJV_yrCMw



TOTAL WEIGHT = 2 X 172 = 344 lb [M/F]

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
G - H	2x4	DRY	No.2	SPF	
H - K	2x4	DRY	No.2	SPF	
T - B	2x4	DRY	No.2	SPF	
T - J	2x4	DRY	No.2	SPF	
T - O	2x4	DRY	No.2	SPF	
O - L	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT E - P	2x3	DRY	No.2	SPF	
P - G	2x4	DRY	No.2	SPF	
P - F	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0	2.50	2.75
C	TMVW-t	MT20	4.0	4.0	2.00	1.50
D	TS-t	MT20	3.0	6.0		
E	TTWW-m	MT20	5.0	6.0	2.25	2.00
F	TMVW-w	MT20	2.0	4.0		
G	TTWW-m	MT20	5.0	6.0	2.25	2.00
H	TS-t	MT20	3.0	6.0		
I	TMVW-t	MT20	4.0	4.0	2.00	1.50
J	TMVW-t	MT20	5.0	6.0	2.50	2.75
L	BMV1+p	MT20	3.0	4.0		
M	BMVW-t	MT20	5.0	6.0		
N	BMVW-t	MT20	4.0	4.0		
O	BS-t	MT20	3.0	6.0		
P	BMVW-t	MT20	4.0	9.0		
Q	BS-t	MT20	3.0	6.0		
R	BMVW-t	MT20	4.0	4.0		
S	BMVW-t	MT20	5.0	6.0		
T	BMV1+p	MT20	3.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	GROSS REACTION	GROSS REACTION	DOWN	HORZ	UPLIFT	BRG	IN-SX	BRG	IN-SX
T	1973	0	1973	0	0	5-8	5-8	5-8	5-8
L	1973	0	1973	0	0	5-8	5-8	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
T	1398	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0
L	1398	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.97 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-R, F-P, I-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM TO		FR-TO			
A-B	0 / 32	-84.9 -84.9	0.11 (1)	10.00	S-C	-189 / 35	0.09 (1)
B-C	-2266 / 0	-84.9 -84.9	0.60 (1)	3.97	C-R	-420 / 0	0.20 (1)
C-D	-1956 / 0	-84.9 -84.9	0.54 (1)	4.26	R-E	0 / 378	0.09 (1)
D-E	-1956 / 0	-84.9 -84.9	0.54 (1)	4.26	E-P	0 / 361	0.06 (1)
E-F	-1773 / 0	-84.9 -84.9	0.34 (1)	4.67	P-F	-543 / 0	0.36 (1)
F-G	-1773 / 0	-84.9 -84.9	0.34 (1)	4.67	P-G	0 / 361	0.06 (1)
G-H	-1956 / 0	-84.9 -84.9	0.54 (1)	4.26	N-G	0 / 378	0.09 (1)
H-I	-1956 / 0	-84.9 -84.9	0.54 (1)	4.26	N-I	-420 / 0	0.20 (1)
I-J	-2266 / 0	-84.9 -84.9	0.60 (1)	3.97	M-I	-189 / 35	0.09 (1)
J-K	0 / 32	-84.9 -84.9	0.11 (1)	10.00	B-S	0 / 1942	0.44 (1)
T-B	-1923 / 0	0.0 0.0	0.20 (1)	6.07	M-J	0 / 1942	0.44 (1)
L-J	-1923 / 0	0.0 0.0	0.20 (1)	6.07			
T-S	0 / 0	-18.5 -18.5	0.18 (4)	10.00			
S-R	0 / 1915	-18.5 -18.5	0.40 (1)	10.00			
R-Q	0 / 1599	-18.5 -18.5	0.32 (1)	10.00			
Q-P	0 / 1599	-18.5 -18.5	0.32 (1)	10.00			
P-O	0 / 1599	-18.5 -18.5	0.32 (1)	10.00			
O-N	0 / 1599	-18.5 -18.5	0.32 (1)	10.00			
N-M	0 / 1915	-18.5 -18.5	0.40 (1)	10.00			
M-L	0 / 0	-18.5 -18.5	0.18 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 36.7	PSF	

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.09")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.17")

CSI: TC=0.60/1.00 (I-J:1) , BC=0.40/1.00 (M-N:1) , WB=0.44/1.00 (J-M:1) , SSI=0.22/1.00 (I-J:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.89 (J) (INPUT = 0.90)
JSI METAL= 0.56 (J) (INPUT = 1.00)



Structural component only
DWG# T-2126524

JOB NAME 420381	TRUSS NAME T50	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:31 2021 Page 1
ID:Z9U1O5I40rN9gEXuxpSeqyWCSd_spe1e3JmmPL_fElh6fWZg3NWTGpQ3D8PEAJV_ycMw



LUMBER				DESCR.	
N. L. G. A. RULES	SIZE	LUMBER			
CHORDS					
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
F - G	2x4	DRY	No.2	SPF	
G - I	2x4	DRY	No.2	SPF	
I - L	2x4	DRY	No.2	SPF	
T - B	2x4	DRY	No.2	SPF	
M - K	2x4	DRY	No.2	SPF	
T - R	2x4	DRY	No.2	SPF	
R - O	2x4	DRY	No.2	SPF	
O - M	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x4	DRY	No.2	SPF	
C - S	2x3	DRY	No.2	SPF	
S - E	2x3	DRY	No.2	SPF	
E - Q	2x3	DRY	No.2	SPF	
P - H	2x3	DRY	No.2	SPF	
H - N	2x3	DRY	No.2	SPF	
N - J	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	3.0	4.0
C	TMVW-t	MT20	5.0	6.0
D	TS-t	MT20	3.0	6.0
E	TMVW-t	MT20	4.0	4.0
F	TTW-m	MT20	4.0	4.0
G	TTW-m	MT20	5.0	8.0
H	TMVW-t	MT20	4.0	4.0
I	TS-t	MT20	3.0	6.0
J	TMVW-t	MT20	5.0	6.0
K	TMV+p	MT20	3.0	4.0
M	BMVW1-t	MT20	5.0	6.0
N, P, S				
N	BMVW-t	MT20	4.0	4.0
O	BS-t	MT20	3.0	6.0
Q	BMVW-t	MT20	4.0	9.0
R	BS-t	MT20	3.0	6.0
T	BMVW1-t	MT20	5.0	6.0

NOTES (1)
1)

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	BRG	BRG
T	1973	0	1973	0	5-8
M	1973	0	1973	0	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	DEAD	SOIL
T	COMBINED	SNOW	LIVE	PERM. LIVE
T	1398	900 / 0	0 / 0	0 / 0
M	1398	900 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.21 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, H-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED	W E B S	FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1	MAX. MAX. UNBRAC	MEMB. FORCE (LBS)
FR-TO		FROM TO	CS1 (LC)	FR-TO
A-B	0 / 32	-84.9	-84.9 0.11 (1)	10.00
B-C	0 / 40	-84.9	-84.9 0.33 (1)	10.00
C-D	-2156 / 0	-84.9	-84.9 0.51 (1)	4.21
D-E	-2156 / 0	-84.9	-84.9 0.51 (1)	4.21
E-F	-1777 / 0	-84.9	-84.9 0.39 (1)	4.61
F-G	-1455 / 0	-84.9	-84.9 0.36 (1)	5.02
G-H	-1777 / 0	-84.9	-84.9 0.39 (1)	4.61
H-I	-2156 / 0	-84.9	-84.9 0.51 (1)	4.21
I-J	-2156 / 0	-84.9	-84.9 0.51 (1)	4.21
J-K	0 / 40	-84.9	-84.9 0.33 (1)	10.00
K-L	0 / 32	-84.9	-84.9 0.11 (1)	10.00
T-B	-186 / 0	0.0	0.0 0.02 (1)	7.81
M-K	-186 / 0	0.0	0.0 0.02 (1)	7.81
T-S	0 / 1746	-18.5	-18.5 0.43 (1)	10.00
S-R	0 / 1761	-18.5	-18.5 0.43 (4)	10.00
R-Q	0 / 1761	-18.5	-18.5 0.43 (4)	10.00
Q-P	0 / 1455	-18.5	-18.5 0.32 (1)	10.00
P-O	0 / 1761	-18.5	-18.5 0.43 (1)	10.00
O-N	0 / 1761	-18.5	-18.5 0.43 (1)	10.00
N-M	0 / 1746	-18.5	-18.5 0.43 (1)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 36.7	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.08")
ALLOWABLE DEFL.(TL) = L/360 (1.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.19")

CSI: TC=0.51/1.00 (H-J:1), BC=0.43/1.00 (N-P:1),
WB=0.62/1.00 (J-M:1), SSI=0.19/1.00 (H-J:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.84 (J) (INPUT = 0.90)

JSI METAL = 0.64 (O) (INPUT = 1.00)




Structural component only
DWG# T-2126525



NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (FLF)	LC1 MAX CSI (LC)	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO	LENGTH	FR-TO		
A-B	0 / 32	-84.9	-84.9	0.11 (1)	10.00	Q-C	-298 / 0
B-C	-2230 / 0	-84.9	-84.9	0.37 (1)	4.25	C-P	-208 / 0
C-D	-2102 / 0	-84.9	-84.9	0.35 (1)	4.37	P-D	0 / 261
D-E	-2197 / 0	-84.9	-84.9	0.81 (1)	3.56	D-N	0 / 672
E-F	-2197 / 0	-84.9	-84.9	0.81 (1)	3.56	N-E	-811 / 0
F-G	-2102 / 0	-84.9	-84.9	0.35 (1)	4.37	N-F	0 / 672
G-H	-2230 / 0	-84.9	-84.9	0.37 (1)	4.25	L-F	0 / 261
H-I	0 / 32	-84.9	-84.9	0.11 (1)	10.00	L-G	-208 / 0
R-B	-1929 / 0	0.0	0.0	0.20 (1)	6.06	K-G	-298 / 0
J-H	-1929 / 0	0.0	0.0	0.20 (1)	6.06	B-Q	0 / 1918
						K-H	0 / 1918
R-Q	0 / 0	-18.5	-18.5	0.11 (4)	10.00		
Q-P	0 / 1878	-18.5	-18.5	0.39 (1)	10.00		
P-O	0 / 1726	-18.5	-18.5	0.40 (1)	10.00		
O-N	0 / 1726	-18.5	-18.5	0.40 (1)	10.00		
N-M	0 / 1726	-18.5	-18.5	0.40 (1)	10.00		
M-L	0 / 1726	-18.5	-18.5	0.40 (1)	10.00		
L-K	0 / 1878	-18.5	-18.5	0.39 (1)	10.00		
K-J	0 / 0	-18.5	-18.5	0.11 (4)	10.00		

JSI GRIP= 0.89 (B) (INPUT = 0.90)
JSI METAL= 0.55 (H) (INPUT = 1.00)



Tamarack Roof Truss, Burlington


Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:33 2021 Page 1

ID:Z9U1O540r9N9gEXuxpSeqywwCSD-xFwOSK4aHNf2DyO8oWh_f58dlHwCuyWRTYfQZsyrCMu

-13-8 0-0 3-11-8 3-11-8 7-8-7 14-6-14 6-9-3 21-4-2 6-10-7 28-2-9 3-9-0 31-11-8 3-11-8 35-11-0 37-2-8

1-3-8 1-3-8 3-11-8 3-9-0 6-10-7 6-9-3 21-4-2 6-10-7 28-2-9 3-9-0 31-11-8 3-11-8 35-11-0 37-2-8

Scale = 1/60.2



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
<u>BEARINGS</u>									
JT	FACTORED		MAXIMUM FACTORED			INPUT	REQRD		
	VERT	HORZ	GROSS	REACTION	DOWN	UP	BRG	BRG	BRG
S	1973	0	1973	0	0	5-8	5-8	5-8	5-8
L	1973	0	1973	0	0	5-8	5-8	5-8	5-8

<u>UNFACTORED REACTIONS</u>									
JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS						
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL		
S	1398	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0		
L	1398	900 / 0	0 / 0	0 / 0	0 / 0	498 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S. I									
--	--	--	--	--	--	--	--	--	--

<u>DESIGN CRITERIA</u>		
SPECIFIED LOADS:		
TOP CH.	LL = 23.3	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 36.7	PSF
<u>SPACING = 24.0 IN. C/C</u>		
LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM		
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR		

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.43 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.
1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-O.
END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN
THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED		MAX. FACTORED		
MEMB.	FORCE (LBS)	VERT. LOAD	LC1	MAX. CSI (LC)	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO	LENGTH		FR-TO			
A-B	0 / 32	-84.9	-84.9	0.11 (1)	10.00	C-R	0 / 179	0.04 (4)	
B-C	0 / 30	-84.9	-84.9	0.22 (1)	10.00	R-D	0 / 112	0.04 (4)	
C-D	-2208 / 0	-84.9	-84.9	0.35 (1)	4.28	D-P	0 / 112	0.25 (1)	
D-E	-2644 / 0	-84.9	-84.9	0.85 (1)	3.43	P-E	-629 / 0	0.44 (1)	
E-F	-2643 / 0	-84.9	-84.9	0.83 (1)	3.43	E-O	-2 / 0	0.00 (1)	
F-G	-2643 / 0	-84.9	-84.9	0.83 (1)	3.43	O-G	-628 / 0	0.44 (1)	
G-H	-2643 / 0	-84.9	-84.9	0.84 (1)	3.44	C-H	0 / 1110	0.25 (1)	
H-I	-2209 / 0	-84.9	-84.9	0.35 (1)	4.28	M-H	0 / 112	0.04 (4)	
I-J	0 / 30	-84.9	-84.9	0.22 (1)	10.00	M-I	0 / 179	0.04 (4)	
J-K	0 / 32	-84.9	-84.9	0.11 (1)	10.00	S-C	-2400 / 0	0.70 (1)	
S-B	-187 / 0	0.0	0.0	0.02 (1)	7.81	I-L	-2401 / 0	0.70 (1)	
L-J	-187 / 0	0.0	0.0	0.02 (1)	7.81				
S-R	0 / 1667	-18.5	-18.5	0.41 (1)	10.00				
R-Q	0 / 1821	-18.5	-18.5	0.43 (1)	10.00				
Q-P	0 / 1821	-18.5	-18.5	0.43 (1)	10.00				
P-O	0 / 2645	-18.5	-18.5	0.50 (1)	10.00				
O-N	0 / 1821	-18.5	-18.5	0.44 (1)	10.00				
N-M	0 / 1821	-18.5	-18.5	0.44 (1)	10.00				
M-L	0 / 1668	-18.5	-18.5	0.41 (1)	10.00				

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.20")
CALCULATED DEF. DEFL.(LL)= L/999 (0.14")
ALLOWABLE DEFL.(TL)= L/360 (1.20")
CALCULATED DEF. DEFL.(TL)= L/999 (0.28")

CSI: TC=0.85/1.00 (D-E-1), BC=0.50/1.00 (O-P-1),
WB=0.70/1.00 (I-L-1), SSI=0.27/1.00 (D-E-1) .

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (L) (INPUT = 0.90)
JSI METAL= 0.59 (N) (INPUT = 1.00)



Structural component only
DWG# T-2126527


Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:35 2021 Page 1

ID:Z9U1O5I40r9N9gEXuxpSeqywCSD-te28t06qp_vmTGXWwxjSkWE5e4e?MvXjKr8WelyrCms

Diagram showing a roof truss structure with dimensions and member labels. The dimensions are: 1-3-8, 0-0, 5-2-7, 5-2-7, 10-4-7, 15-5-2, 5-0-12, 4-11-8, 20-4-10, 20-5-14, 5-0-12, 25-6-9, 5-2-0, 30-8-9, 5-2-7, 35-11-0, 37-2-8, 1-3-8. The member labels are: 1-3-8, 5-2-7, 5-2-0, 5-0-12, 4-11-8, 20-4-10, 20-5-14, 5-0-12, 25-6-9, 5-2-0, 30-8-9, 5-2-7, 35-11-0, 37-2-8, 1-3-8.

Scale = 1/80.2



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER A - C 2x4 DRY No.2 C - G 2x4 DRY No.2 G - J 2x4 DRY No.2 J - L 2x4 DRY No.2 V - B 2x6 DRY No.2 M - K 2x6 DRY No.2 V - S 2x6 DRY No.2 S - P 2x6 DRY No.2 P - M 2x6 DRY No.2 ALL WEBS 2x3 DRY No.2 EXCEPT			DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 36.7 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC2018, ABC 2019 - PART 9 OF CBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (1.20") CALCULATED VERT. DEFL.(LL) = L/999 (0.13") ALLOWABLE DEFL.(TL)= L/360 (1.20") CALCULATED VERT. DEFL.(TL) = L/999 (0.26") CSI: TC=0.37/1.00 (B-C:1), BC=0.35/1.00 (Q-R:1), WB=0.47/1.00 (B-U:1), SSI=0.11/1.00 (I-J:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00 COMPANION LIVE LOAD FACTOR = 1.00 AUTOSOLVE HEELS OFF TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT. NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.87 (N) (INPUT = 0.90) JSI METAL= 0.43 (N) (INPUT = 1.00)			DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 36.7 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC2018, ABC 2019 - PART 9 OF CBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (1.20") CALCULATED VERT. DEFL.(LL) = L/999 (0.13") ALLOWABLE DEFL.(TL)= L/360 (1.20") CALCULATED VERT. DEFL.(TL) = L/999 (0.26") CSI: TC=0.37/1.00 (B-C:1), BC=0.35/1.00 (Q-R:1), WB=0.47/1.00 (B-U:1), SSI=0.11/1.00 (I-J:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00 COMPANION LIVE LOAD FACTOR = 1.00 AUTOSOLVE HEELS OFF TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT. NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.87 (N) (INPUT = 0.90) JSI METAL= 0.43 (N) (INPUT = 1.00)			DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 36.7 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC2018, ABC 2019 - PART 9 OF CBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (1.20") CALCULATED VERT. DEFL.(LL) = L/999 (0.13") ALLOWABLE DEFL.(TL)= L/360 (1.20") CALCULATED VERT. DEFL.(TL) = L/999 (0.26") CSI: TC=0.37/1.00 (B-C:1), BC=0.35/1.00 (Q-R:1), WB=0.47/1.00 (B-U:1), SSI=0.11/1.00 (I-J:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00 COMPANION LIVE LOAD FACTOR = 1.00 AUTOSOLVE HEELS OFF TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT. NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.87 (N) (INPUT = 0.90) JSI METAL= 0.43 (N) (INPUT = 1.00)			DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 36.7 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC2018, ABC 2019 - PART 9 OF CBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (1.20") CALCULATED VERT. DEFL.(LL) = L/999 (0.13") ALLOWABLE DEFL.(TL)= L/360 (1.20") CALCULATED VERT. DEFL.(TL) = L/999 (0.26") CSI: TC=0.37/1.00 (B-C:1), BC=0.35/1.00 (Q-R:1), WB=0.47/1.00 (B-U:1), SSI=0.11/1.00 (I-J:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00 COMPANION LIVE LOAD FACTOR = 1.00 AUTOSOLVE HEELS OFF TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT. NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.87 (N) (INPUT = 0.90) JSI METAL= 0.43 (N) (INPUT = 1.00)			DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 36.7 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC2018, ABC 2019 - PART 9 OF CBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL)= L/360 (1.20") CALCULATED VERT. DEFL.(LL) = L/999 (0.13") ALLOWABLE DEFL.(TL)= L/360 (1.20") CALCULATED VERT. DEFL.(TL) = L/999 (0.26") CSI: TC=0.37/1.00 (B-C:1), BC=0.35/1.00 (Q-R:1), WB=0.47/1.00 (B-U:1), SSI=0.11/1.00 (I-J:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00 COMPANION LIVE LOAD FACTOR = 1.00 AUTOSOLVE HEELS OFF TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT. NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PS
---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

JOB NAME 420381	TRUSS NAME T53	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:35 2021 Page 2

ID:Z9U1O5I40r9N9gEXuxpSeqywCSD-te28t06qp vmTGXWwxjSkWE5e4e?MvXjKr8WelyrCMs

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	1.50	3.00
C	TTWW+m	MT20	5.0	6.0	2.75	2.25
D, F, I						
D	TMWW-t	MT20	4.0	4.0		
E	TMW+w	MT20	2.0	4.0		
G	TS-t	MT20	3.0	6.0		
H	TMW+w	MT20	2.0	4.0		
J	TTWW+m	MT20	5.0	6.0	2.75	2.25
K	TMVW-p	MT20	5.0	6.0	1.50	3.00
M	BMV1+p	MT20	3.0	6.0		
N, O, T, U						
N	BMWW-t	MT20	5.0	6.0		
P	BS-t	MT20	5.0	6.0		
Q	BMWWW-t	MT20	5.0	8.0		
R	BMWWW-t	MT20	5.0	3.0		
S	BS-t	MT20	5.0	6.0		
V	BMV1+p	MT20	3.0	6.0		

NOTES- (1)


1) Lateral braces to be a minimum of 2X4 SPF #2.



Structural component only
DWG# T-2126528 *ml*

JOB NAME 420381	TRUSS NAME T54	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:36 2021 Page 1
ID:Z9U1O5I40r9N9gEXxpSeqywCSD-LqcX4L7Sal1d4Q6jUfEhGjmCMU?_5QutZVu4AByrCMr



Scale = 1:12.7

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	DRY
F - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F-A 1	12	TOP
A-C 1	12	TOP
C-D 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2	12	SIDE (0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y
A	TMVW-t	MT20	4.0	4.0
B	TMW-w	MT20	2.0	4.0
C	TMVW-t	MT20	4.0	4.0
D	BMV1-p	MT20	3.0	6.0
E	BMVWW-t	MT20	5.0	8.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
F	1904	0	1904	0	0
D	1916	0	1916	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 4'-0".

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	1351	861 / 0	0 / 0	0 / 0	0 / 0	490 / 0	0 / 0
D	1357	877 / 0	0 / 0	0 / 0	0 / 0	480 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.18 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC1)
FR-TO		FROM	TO	FR-TO		FROM	TO
F-A	-1878 / 0	0.0	0.0	0.11 (1)	A-E	0 / 1694	0.21 (1)
A-G	-1298 / 0	-84.9	-84.9	0.57 (1)	E-B	-1352 / 0	0.11 (1)
G-B	-1298 / 0	-84.9	-84.9	0.57 (1)	B-C	0 / 1694	0.21 (1)
B-C	-1298 / 0	-84.9	-84.9	0.21 (1)	C-D	0.0	0.0
D-C	-1030 / 0	0.0	0.0	0.06 (1)			
F-E	0 / 0	-18.5	-18.5	0.01 (1)			
E-H	0 / 0	-18.5	-18.5	0.30 (1)			
H-D	0 / 0	-18.5	-18.5	0.30 (1)			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-0-0	-1245	-1245	---	TOP	VERT	TOTAL	---	C1
H	2-11-4	-1179	-1179	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:		
TOP CH.	LL	= 23.3 PSF
	DL	= 6.0 PSF
BOT CH.	LL	= 0.0 PSF
	DL	= 7.4 PSF
TOTAL LOAD		= 36.7 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.57/1.00 (A-B:1), BC=0.30/1.00 (D-E:1), WB=0.21/1.00 (A-E:1), SS=0.48/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00

COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES		
PLATE	GRIP (DRY) (PSI)	SHEAR SECTION (PLI)
MT20	650	371
	788	1987
	1873	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.82 (A) (INPUT = 0.90)
JSI METAL= 0.23 (A) (INPUT = 1.00)



Structural component only
DWG# T-2126529

CONTINUED ON PAGE 2

JOB NAME 420381	TRUSS NAME T54	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:36 2021 Page 2
ID:Z9U1O5l40r9N9qEXuxpSeqywCSD-LqcX4L7Sal1d4Q6jUfEhGimCMU? 5QutZVu4AByrCMr

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
F	BMV1+p	MT20	3.0	6.0		

NOTES- (1)


1) Lateral braces to be a minimum of 2X4 SPF #2.



Structural component only
DWG# T-2126529 *HL*

JOB NAME 420381	TRUSS NAME T55	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:37 2021 Page 1
ID:Z9U1O5I40r9N9gEXuPSeqwCSD-p0Avh74Lc9Uiahv1MlwpXJLMuK2qp10o9ddieyrCMq



LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
G - I	2x4	DRY	No.2	SPF
Q - B	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
Q - O	2x4	DRY	No.2	SPF
O - L	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				
DRY: SEASONED LUMBER.				

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMVW-t	MT20	5.0	6.0
C	TTWW-m	MT20	5.0	6.0 2.00 1.50
D	TMW-w	MT20	2.0	4.0
E	TS-t	MT20	3.0	6.0
F	TMVW-t	MT20	4.0	4.0
G	TTWW-m	MT20	5.0	6.0 2.00 1.50
H	TMVW-t	MT20	5.0	6.0
J	BMV1-p	MT20	3.0	4.0
K, M, P				
K	BMVW-t	MT20	4.0	6.0
L	BS-t	MT20	3.0	6.0
N	BMVWW-t	MT20	4.0	9.0
O	BS-t	MT20	3.0	6.0
Q	BMV1-p	MT20	3.0	4.0

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
	GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
Q	1684	0	1684	0	0	5-8	5-8	
J	1684	0	1684	0	0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT J. MINIMUM BEARING LENGTH AT JOINT J = 3-8.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
Q	1193	770 / 0	0 / 0	0 / 0	0 / 0	423 / 0	0 / 0
J	1193	770 / 0	0 / 0	0 / 0	0 / 0	423 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.15 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 32	-84.9 -84.9	0.11 (1)	10.00	P-C	-465 / 0	0.35 (1)
B-C	-1294 / 0	-84.9 -84.9	0.46 (1)	5.08	C-N	0 / 1060	0.24 (1)
C-D	-1838 / 0	-84.9 -84.9	0.67 (1)	4.16	N-D	-620 / 0	0.46 (1)
D-E	-1838 / 0	-84.9 -84.9	0.67 (1)	4.15	N-F	0 / 17	0.00 (1)
E-F	-1838 / 0	-84.9 -84.9	0.67 (1)	4.15	M-F	-633 / 0	0.47 (1)
F-G	-1826 / 0	-84.9 -84.9	0.68 (1)	4.16	M-G	0 / 1100	0.25 (1)
G-H	-1246 / 0	-84.9 -84.9	0.41 (1)	5.23	K-G	-509 / 0	0.38 (1)
H-I	0 / 32	-84.9 -84.9	0.11 (1)	10.00	B-P	0 / 1227	0.28 (1)
Q-B	-1648 / 0	0.0 0.0	0.30 (1)	6.45	K-H	0 / 1212	0.27 (1)
J-H	-1650 / 0	0.0 0.0	0.32 (1)	6.45			
Q-P	0 / 0	-18.5 -18.5	0.16 (4)	10.00			
P-O	0 / 1068	-18.5 -18.5	0.26 (1)	10.00			
O-N	0 / 1068	-18.5 -18.5	0.26 (1)	10.00			
N-M	0 / 1826	-18.5 -18.5	0.38 (1)	10.00			
M-L	0 / 1027	-18.5 -18.5	0.25 (1)	10.00			
L-K	0 / 1027	-18.5 -18.5	0.25 (1)	10.00			
K-J	0 / 0	-18.5 -18.5	0.15 (4)	10.00			

TOTAL WEIGHT = 133 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.01")
CALCULATED VERT. DEFL.(LL) = L/999 (0.08")
ALLOWABLE DEFL.(TL)= L/360 (1.01")
CALCULATED VERT. DEFL.(TL) = L/999 (0.16")

CSI: TC=0.68/1.00 (F-G:1), BC=0.38/1.00 (M-N:1), WB=0.47/1.00 (F-M:1), SS=0.27/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (G) (INPUT = 0.90)
JSI METAL= 0.37 (O) (INPUT = 1.00)




Structural component only
DWG# T-2126530

JOB NAME 420381	TRUSS NAME T56S	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:38 2021 Page 1
ID:Z9U1O5I40R9NgEXuPSeqyWCD-HDKHV18I6vHLKkG5b4H9M8rczhYZIVA0pNBE4yrCmp

1-3-8 0-0 2-8-7 2-8-7 5-2-5 7-10-12 5-1-1 12-11-13 5-3-15 18-3-12 19-11-4 2-0-0 21-11-4 22-10-13 23-11-4 25-6-4 2-0-0 27-6-4 27-10-9 2-8-7 30-7-0
1-3-8 2-8-7 2-8-7 5-2-5 7-10-12 5-1-1 12-11-13 5-3-15 18-3-12 19-11-4 2-0-0 21-11-4 22-10-13 23-11-4 25-6-4 2-0-0 27-6-4 27-10-9 2-8-7 30-7-0

Scale = 1:52.2



TOTAL WEIGHT = 2 X 156 = 311 lb

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - C	2x4 DRY	No.2	SPF
C - F	2x4 DRY	No.2	SPF
F - I	2x4 DRY	No.2	SPF
I - J	2x4 DRY	No.2	SPF
T - B	2x4 DRY	No.2	SPF
K - J	2x6 DRY	No.2	SPF
T - Q	2x6 DRY	No.2	SPF
Q - O	2x6 DRY	No.2	SPF
O - G	2x4 DRY	No.2	SPF
N - K	2x6 DRY	No.2	SPF
ALL WEBS	2x3 DRY	No.2	SPF
EXCEPT			
P - N	2x6 DRY	No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
A-C	12	TOP
C-F	12	TOP
F-I	12	TOP
I-J	12	TOP
T-B	12	TOP
K-J	12	TOP
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
T-Q	12	TOP
Q-O	12	TOP
N-K	12	TOP
O-G	12	TOP
WEBS: (0.122"x3") SPIRAL NAILS		
2x3	6	TOP
2x6	6	TOP

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
T	1892	0	1892	0	5-8
K	1838	0	1838	0	3-0

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
T	1340	869 / 0	0 / 0	0 / 0	0 / 0	471 / 0
K	1303	834 / 0	0 / 0	0 / 0	0 / 0	469 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.98 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS		FACTORED		WEBS	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)
FR-TO		FROM TO		FR-TO	
A-B	0 / 32	-84.9 -84.9 0.06 (1)	10.00	S-C	-901 / 0
B-C	-1150 / 0	-84.9 -84.9 0.06 (1)	6.25	P-E	-1699 / 0
C-D	-2277 / 0	-84.9 -84.9 0.20 (1)	5.70	P-N	0 / 3213
D-E	-3019 / 0	-84.9 -84.9 0.23 (1)	5.10	E-N	0 / 2569
E-F	-5281 / 0	-84.9 -84.9 0.28 (1)	4.02	L-I	-459 / 0
F-G	-5281 / 0	-84.9 -84.9 0.28 (1)	4.02	B-S	0 / 1396
G-U	-5321 / 0	-84.9 -84.9 0.30 (1)	3.98	L-J	0 / 1786
U-V	-5321 / 0	-84.9 -84.9 0.30 (1)	3.98	M-I	0 / 2630
V-W	-5321 / 0	-84.9 -84.9 0.30 (1)	3.98	N-H	0 / 1575
W-H	-5321 / 0	-84.9 -84.9 0.30 (1)	3.98	M-H	-1256 / 0
H-X	-3956 / 0	-84.9 -84.9 0.24 (1)	4.57	D-P	0 / 1030
X-Y	-3956 / 0	-84.9 -84.9 0.24 (1)	4.57	C-R	0 / 1831
Y-Z	-3956 / 0	-84.9 -84.9 0.24 (1)	4.57	R-D	-1198 / 0
Z-I	-3956 / 0	-84.9 -84.9 0.24 (1)	4.57		
I-J	-2028 / 0	-84.9 -84.9 0.07 (1)	6.12		
T-B	-1891 / 0	0.0 0.0 0.18 (1)	7.81		
K-J	-1843 / 0	0.0 0.0 0.07 (1)	7.81		

T-S	0 / 0	-18.5 -18.5 0.03 (4)	10.00
S-R	0 / 935	-18.5 -18.5 0.09 (1)	10.00
R-Q	0 / 2277	-18.5 -18.5 0.19 (1)	10.00
Q-P	0 / 2277	-18.5 -18.5 0.19 (1)	10.00
P-AA	0 / 57	-18.5 -18.5 0.10 (1)	10.00
AA-O	0 / 57	-18.5 -18.5 0.10 (1)	10.00
O-N	0 / 422	0.0 0.0 0.12 (1)	10.00
N-G	-383 / 0	0.0 0.0 0.09 (1)	7.81
N-AB	0 / 3956	-18.5 -18.5 0.30 (1)	10.00
AB-AC	0 / 3956	-18.5 -18.5 0.30 (1)	10.00
AC-AD	0 / 3956	-18.5 -18.5 0.30 (1)	10.00
AD-M	0 / 3956	-18.5 -18.5 0.30 (1)	10.00
M-AE	0 / 1666	-18.5 -18.5 0.14 (1)	10.00
AE-AF	0 / 1666	-18.5 -18.5 0.14 (1)	10.00
AF-L	0 / 1666	-18.5 -18.5 0.14 (1)	10.00
L-AG	0 / 0	-18.5 -18.5 0.03 (1)	10.00
AG-K	0 / 0	-18.5 -18.5 0.03 (1)	10.00

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
L	27-6-4	1	1	70	FRONT	VERT	TOTAL	---	C1
U	18-3-12	1	1	70	FRONT	VERT	TOTAL	---	C1
V	19-11-4	1	1	70	FRONT	VERT	TOTAL	---	C1
W	21-11-4	1	1	70	FRONT	VERT	TOTAL	---	C1
X	23-11-4	1	1	70	FRONT	VERT	TOTAL	---	C1

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.02")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL) = L/360 (1.02")
CALCULATED VERT. DEFL.(TL) = L/999 (0.26")

CSI: TC=0.30/1.00 (G-H:1), BC=0.30/1.00 (M-N:1), WB=0.33/1.00 (E-P:1), SSI=0.14/1.00 (O-P:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788 1987 1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.89 (C) (INPUT = 0.90)
JSI METAL = 0.28 (E) (INPUT = 1.00)



Structural component only
DWG# T-2126531

CONTINUED ON PAGE 2

JOB NAME 420381	TRUSS NAME T56S	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:38 2021 Page 2

ID:Z9U1O5I40r9N9gEXuxpSeqywCSD-HDKHV18i6vHLKkG5b4H9M8rczlhYZIVA0pNBE4yrCMp

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVV+p	MT20	4.0	4.0	1.25	2.00
C	TTWW-m	MT20	5.0	6.0	2.25	1.50
D	TMWW-t	MT20	4.0	4.0		
E	TMWW-t	MT20	4.0	6.0		
F	TS-t	MT20	3.0	6.0		
G	TMV+p	MT20	3.0	4.0		
H	TMWW-t	MT20	4.0	4.0		
I	TTWW-m	MT20	5.0	8.0	2.00	3.00
J	TMVV-t	MT20	5.0	6.0	2.50	1.75
K	BMV1+p	MT20	4.0	6.0		
L, M, R, S						
L	BMWW-t	MT20	5.0	6.0		
N	BVMWWW-I	MT20	8.0	12.0	4.50	4.50
O	BMV+p	MT20	3.0	8.0		
P	BMWWW-t	MT20	7.0	8.0		
Q	BS-t	MT20	5.0	6.0		
T	BMV1+p	MT20	3.0	6.0		

NOTES: (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
Y	25-6-4	1	1	70	FRONT	VERT	TOTAL	---	C1
Z	27-6-4	1	1	55	FRONT	VERT	TOTAL	---	C1
AA	17-4-8	-316	-316	---	FRONT	VERT	TOTAL	---	C1
AB	18-3-12	-3	-3	---	FRONT	VERT	TOTAL	---	C1
AC	19-11-4	1	1	---	FRONT	VERT	TOTAL	---	C1
AD	21-11-4	1	1	---	FRONT	VERT	TOTAL	---	C1
AE	23-11-4	1	1	---	FRONT	VERT	TOTAL	---	C1
AF	25-6-4	1	1	---	FRONT	VERT	TOTAL	---	C1
AG	29-6-4	1	1	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS


1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2126531 *ML*

JOB NAME 420381	TRUSS NAME T57	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:39 2021 Page 1
ID:Z9U1O5I40r9N9gEXuxpSeqywcSD-IPHfIN9KiDPCxtrH9noOuMOr0i2ulquJFT6knWyrCMc



Scale = 1:29.4

TOTAL WEIGHT = 2 X 18 = 35 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
D - A	2x4	DRY	No.2	SPF
A - B	2x4	DRY	No.2	SPF
C - B	2x4	DRY	No.2	SPF
D - C	2x6	DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF				
DRY: SEASONED LUMBER.				

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
D-A 1	12	TOP
A-B 1	12	TOP
B-C 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D-C 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00 2.00
B	TMV+p	MT20	3.0	4.0	
C	BMVW1+p	MT20	4.0	6.0	
D	BMV1+p	MT20	3.0	6.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	GROSS REACTION	VERT	HORZ	GROSS REACTION	DOWN	HORZ	UPLIFT	BRG	IN-SX
D	726	0	0	726	0	0	5-8	5-8	
C	461	0	0	461	0	0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 2-0.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
D	513	339 / 0	0 / 0	0 / 0	0 / 0	174 / 0	0 / 0	
C	326	214 / 0	0 / 0	0 / 0	0 / 0	111 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE	VERT. LOAD	LC1 MAX	MEMB.	FORCE	MAX	LC1 (C)
FR-TO		FROM	TO	FR-TO			
D-A	-80 / 0	0.0	0.0 0.01 (1)	7.81	A-C	0 / 0	0.00 (1)
A-B	0 / 0	-84.9	-84.9 0.03 (1)	10.00			
C-B	-80 / 0	0.0	0.0 0.02 (1)	7.81			
D-E	0 / 0	-18.5	-18.5 0.16 (1)	10.00			
E-C	0 / 0	-18.5	-18.5 0.16 (1)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	8-4	-701	-701		BACK	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 36.7	PSF	

SPACING = 24.0 IN./C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.03/1.00 (A-B:1), BC=0.16/1.00 (C-D:1), WB=0.00/1.00 (A-C:1), SSI=0.21/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PS)	(PL)	(PL)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.03 (A) (INPUT = 0.90)
JSI METAL= 0.01 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126532

JOB NAME 420381	TRUSS NAME T58	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:40 2021 Page 1
ID:Z9U1O5I40r9N9gEXxpSeqywCSD-Ebr1wjAzeXX3Z1QUjVJdRZxx95Ox1EYTU7sHJzrCMr



LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
M - B	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	
M - J	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.25	2.00
C	TTWW+m	MT20	5.0	6.0	2.00	1.50
D	TMW+w	MT20	2.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.00	1.50
F	TMVW+p	MT20	4.0	4.0	1.25	2.00
H	BMV1+p	MT20	3.0	4.0		
I	BMVW-t	MT20	4.0	4.0		
J	BS-t	MT20	3.0	6.0	1.50	2.75
K	BMVW-t	MT20	4.0	9.0		
L	BMVW-t	MT20	4.0	4.0		
M	BMV1+p	MT20	3.0	4.0		

NOTES: (1)

1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQRD
JT	GROSS REACTION	GROSS REACTION	DOWN	HORZ	UPLIFT
M	1008	0	1008	0	0
H	1008	0	1008	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 3-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
M	713	466 / 0	0 / 0	0 / 0	0 / 0	248 / 0	0 / 0
H	713	466 / 0	0 / 0	0 / 0	0 / 0	248 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX LC1 (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 32	-84.9 -84.9	0.11 (1)	L-C	-118 / 35	0.07 (1)	
B-C	-713 / 0	-84.9 -84.9	0.32 (1)	C-K	0 / 188	0.04 (1)	
C-D	-699 / 0	-84.9 -84.9	0.17 (1)	K-D	-413 / 0	0.23 (1)	
D-E	-699 / 0	-84.9 -84.9	0.17 (1)	E-K	0 / 383	0.09 (1)	
E-F	-582 / 0	-84.9 -84.9	0.17 (1)	F-E	-286 / 0	0.16 (1)	
F-G	0 / 32	-84.9 -84.9	0.11 (1)	G-L	0 / 634	0.14 (1)	
M-B	-966 / 0	0.0 0.0	0.12 (1)	B-L	0 / 612	0.14 (1)	
H-F	-979 / 0	0.0 0.0	0.19 (1)				
M-L	0 / 0	-18.5 -18.5	0.12 (4)				
L-K	0 / 591	-18.5 -18.5	0.17 (4)				
K-J	0 / 478	-18.5 -18.5	0.12 (1)				
J-I	0 / 478	-18.5 -18.5	0.12 (1)				
I-H	0 / 0	-18.5 -18.5	0.07 (4)				

TOTAL WEIGHT = 83 lb

(M/F)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.57")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.02")
ALLOWABLE DEFL.(TL) = $L/360$ (0.57")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.03")

CSI: TC=0.32/1.00 (B-C:1), BC=0.17/1.00 (K-L:4), WB=0.23/1.00 (D-K:1), SS=0.16/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PS)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788
	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.71 (L) (INPUT = 0.90)
JSI METAL = 0.20 (B) (INPUT = 1.00)




Structural component only
DWG# T-2126533

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ROYAL PINE HOMES	DRWG NO.
420381	T59S	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:41 2021 Page 1
ID:Z9U1O5I40rN9gEXuxpSeqwCSD-ioPQ73BbPqgwBB?gGCqsznT6bVj3medcjbrrPyrCmm



CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4 DRY	No.2	SPF
C - F	2x4 DRY	No.2	SPF
F - H	2x4 DRY	No.2	SPF
O - B	2x4 DRY	No.2	SPF
I - G	2x4 DRY	No.2	SPF
O - L	2x6 DRY	No.2	SPF
L - E	2x4 DRY	No.2	SPF
K - I	2x6 DRY	No.2	SPF
ALL WEBS EXCEPT M - K	2x3 DRY	No.2	SPF

DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
O	1131	0	1131	0	0	5-8	5-8	5-8	5-8
I	1290	0	1290	0	0	5-8	5-8	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS		DEAD		SOIL	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
O	800	525 / 0	0 / 0	0 / 0	0 / 0	275 / 0	0 / 0
I	911	605 / 0	0 / 0	0 / 0	0 / 0	306 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.85 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FORCE (LBS)	MAX. CSI (LC)	MAX. CSI (LC)
FR-TO		FROM TO		FR-TO			
A-B	0 / 32	-84.9 -84.9	0.13 (1)	10.00	N-C	-399 / 0	0.19 (1)
B-C	-668 / 0	-84.9 -84.9	0.19 (1)	6.25	C-M	0 / 594	0.15 (1)
C-D	-875 / 0	-84.9 -84.9	0.17 (5)	6.25	M-K	-930 / 0	0.43 (1)
D-E	-1556 / 0	-84.9 -84.9	0.29 (1)	4.92	M-K	0 / 1003	0.13 (1)
E-P	-1565 / 0	-84.9 -84.9	0.34 (1)	4.85	D-K	0 / 925	0.23 (1)
P-Q	-1565 / 0	-84.9 -84.9	0.34 (1)	4.85	K-F	0 / 1108	0.27 (1)
Q-F	-1565 / 0	-84.9 -84.9	0.34 (1)	4.85	J-F	-452 / 0	0.10 (1)
F-G	-811 / 0	-84.9 -84.9	0.13 (1)	6.25	B-N	0 / 730	0.18 (1)
G-H	0 / 32	-84.9 -84.9	0.13 (1)	10.00	J-G	0 / 927	0.23 (1)
O-B	-1107 / 0	0.0 0.0	0.21 (1)	7.49			
I-G	-1337 / 0	0.0 0.0	0.17 (1)	6.97			
O-N	0 / 0	-18.5 -18.5	0.03 (4)	10.00			
N-M	0 / 545	-18.5 -18.5	0.09 (1)	10.00			
M-L	0 / 15	-18.5 -18.5	0.03 (4)	10.00			
L-K	0 / 30	0.0 0.0	0.05 (1)	10.00			
K-E	-410 / 0	0.0 0.0	0.06 (1)	7.81			
K-R	0 / 638	-18.5 -18.5	0.24 (1)	10.00			
R-S	0 / 638	-18.5 -18.5	0.24 (1)	10.00			
S-T	0 / 638	-18.5 -18.5	0.24 (1)	10.00			
T-J	0 / 638	-18.5 -18.5	0.24 (1)	10.00			
J-I	0 / 0	-18.5 -18.5	0.10 (1)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	15-4-8	-45	-45	70	FRONT	VERT	TOTAL	---	C1
J	15-3-12	1	1	---	FRONT	VERT	TOTAL	---	C1
P	12-2-4	1	1	70	FRONT	VERT	TOTAL	---	C1
Q	13-3-12	1	1	70	FRONT	VERT	TOTAL	---	C1
R	11-1-8	-240	-240	---	FRONT	VERT	TOTAL	---	C1
S	12-2-4	1	1	---	FRONT	VERT	TOTAL	---	C1
T	13-3-12	1	1	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 36.7	PSF	

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.58")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL) = L/360 (0.58")
CALCULATED VERT. DEFL.(TL) = L/999 (0.08")

CSI: TC=0.34/1.00 (E-F:1), BC=0.24/1.00 (J-K:1),
WB=0.43/1.00 (D-M:1), SS=0.21/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747	788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (G) (INPUT = 0.90)
JSI METAL= 0.27 (G) (INPUT = 1.00)



Structural component only
DWG# T-2126534

Tamarack Roof Truss, Burlington



TOTAL WEIGHT = 63 lb

DESCR

DESCR.	BEARINGS

DESCR

DESCR

DESCR

DESCR

DESCR

DESCR

DESCR

DESCR

DESCR

DESCR

DESCR

SPECIFIED LOADS:

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

- | | | | | | |
|------------|-----|----|---|------|----------|
| TOP | CH. | LL | = | 23.3 | PSF |
| | | DL | = | 6.0 | PSF |
| BOT | CH. | LL | = | 0.0 | PSF |
| | | DL | = | 7.4 | PSF |
| TOTAL LOAD | | | | = | 36.7 PSF |

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF


TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF


TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF

TOP	CH.	LL	=	23.3	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	36.7 PSF



JOB NAME 420381	TRUSS NAME T61	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			



LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				DESIGN CRITERIA			
---------------	--	--	--	--	--	--	--	------------------------	--	--	--

N. L. G. A. RULES				BEARINGS				SPECIFIED LOADS:			
CHORDS	SIZE	LUMBER	DESCR.	FACTORED	MAXIMUM FACTORED	INPUT	REORD	TOP CH.	LL	=	23.3 PSF
A - C	2x4	DRY	No.2	GROSS REACTION	GROSS REACTION	BRG	BRG	DL	=	6.0 PSF	
C - E	2x4	DRY	No.2	VERT	HORZ	DOWN	HORZ	BOT CH.	LL	=	0.0 PSF
E - G	2x4	DRY	No.2	JT	790	0	790	DL	=	7.4 PSF	
L - B	2x4	DRY	No.2	H	761	0	761	TOTAL LOAD	=	36.7 PSF	
H - F	2x4	DRY	No.2								
L - H	2x4	DRY	No.2								

ALL WEBS 2x3 DRY No.2				UNFACTORED REACTIONS				SPACING = 24.0 IN. C/C			
EXCEPT				1ST CASE				LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM			
DRY: SEASONED LUMBER.				MAX./MIN. COMPONENT REACTIONS				THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015			

				JT COMBINED				THIS DESIGN COMPLIES WITH:			
				L				- PART 9 OF BCBC 2018, ABC 2019			
				H				- PART 9 OF OBC 2012 (2019 AMENDMENT)			

				L				- CSA 086-14			
				H				- TPIC 2014			

				L				(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD			
--	--	--	--	---	--	--	--	---	--	--	--

				L				ALLOWABLE DEFL.(LL) = L/360 (0.37")			
				H				CALCULATED VERT. DEFL.(LL) = L/999 (0.01")			

				L				ALLOWABLE DEFL.(TL) = L/360 (0.37")			
				H				CALCULATED VERT. DEFL.(TL) = L/999 (0.02")			

				L				CSI: TC=0.13/1.00 (A-B:1), BC=0.11/1.00 (J-K:1), WB=0.13/1.00 (B-K:1), SS=0.12/1.00 (C-D:1)			
--	--	--	--	---	--	--	--	---	--	--	--

				L				DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00			
--	--	--	--	---	--	--	--	---	--	--	--

				L				COMPANION LIVE LOAD FACTOR = 1.00			
--	--	--	--	---	--	--	--	-----------------------------------	--	--	--

				L				TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.			
--	--	--	--	---	--	--	--	---	--	--	--

				L				NAIL VALUES			
--	--	--	--	---	--	--	--	-------------	--	--	--

				L				PLATE GRIP(DRY) SHEAR SECTION			
				H				(PSI) (PLI) (PLI)			

				L				MAX MIN MAX MIN MAX MIN			
				H				MT20 650 371 1747 788 1987 1873			

				L				PLATE PLACEMENT TOL. = 0.250 inches			
--	--	--	--	---	--	--	--	-------------------------------------	--	--	--

				L				PLATE ROTATION TOL. = 5.0 Deg.			
--	--	--	--	---	--	--	--	--------------------------------	--	--	--

				L				JSI GRIP= 0.60 (K) (INPUT = 0.90)			
				H				JSI METAL= 0.17 (K) (INPUT = 1.00)			

				L				SPECIFIED CONCENTRATED LOADS (LBS)			
--	--	--	--	---	--	--	--	------------------------------------	--	--	--

				H				LOC. LC1 MAX- MAX+			
				L				FACE DIR. TYPE HEEL CONN.			

				H				C 2-8-7 -79 -79 49 FRONT VERT TOTAL --- C1			
				L				E 8-3-9 -42 70 FRONT VERT TOTAL --- C1			

				H				I 8-2-13 1 1 --- FRONT VERT TOTAL --- C1			
				L				K 2-9-3 1 1 --- FRONT VERT TOTAL --- C1			

				H				M 4-9-3 1 1 70 FRONT VERT TOTAL --- C1			
				L				N 6-2-13 1 1 70 FRONT VERT TOTAL --- C1			

				H				O 1-11-4 1 1 --- FRONT VERT TOTAL --- C1			
				L				P 4-9-3 1 1 --- FRONT VERT TOTAL --- C1			


				H				Q 6-2-13 1 1 --- FRONT VERT TOTAL --- C1			
				L				R 9-0-12 1 1 --- FRONT VERT TOTAL --- C1			

				L				CONNECTION REQUIREMENTS			
--	--	--	--	---	--	--	--	-------------------------	--	--	--

				H				1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.			
--	--	--	--	---	--	--	--	---	--	--	--

				L				TOTAL WEIGHT = 49 lb			
--	--	--	--	---	--	--	--	----------------------	--	--	--

				H							
--	--	--	--	---	--	--	--	--	--	--	--




Structural component only
DWG# T-2126536

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ROYAL PINE HOMES	DRWG NO.
420381	T62	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:44 2021 Page 1
ID:Z9U1O5I40r9N9gEXuxpSeqywCSD-6N5Ym4DTi2U2fkFyKNZbP5imjn8z582PlqVSkYrCM



Scale = 1:21.4

TOTAL WEIGHT = 2 X 13 = 26 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
D - A	2x4	DRY	No.2	SPF	
A - B	2x4	DRY	No.2	SPF	
C - B	2x4	DRY	No.2	SPF	
D - C	2x6	DRY	No.2	SPF	
ALL WEBS 2x3 DRY No.2					SPF
DRY: SEASONED LUMBER.					

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
D-A 1 12		TOP
A-B 1 12		TOP
B-C 1 12		TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D-C 2 12		SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.25	2.00
B	TMV+p	MT20	3.0	4.0		
C	BMVW1+p	MT20	4.0	6.0		
D	BMV1+p	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
D	353	0	353	0	5-8	5-8
C	353	0	353	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 2-0.

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
D	250	163 / 0	0 / 0	0 / 0	0 / 0	87 / 0	0 / 0
C	250	163 / 0	0 / 0	0 / 0	0 / 0	87 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO			FR-TO			
D-A	-80 / 0	0.0	0.0	0.01 (1)	7.81	A-C	0 / 0	0.00 (1)	
A-B	0 / 0	-84.9	-84.9	0.03 (1)	10.00				
C-B	-80 / 0	0.0	0.0	0.01 (1)	7.81				
D-E	0 / 0	-18.5	-18.5	0.09 (1)	10.00				
E-C	0 / 0	-18.5	-18.5	0.09 (1)	10.00				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	11-4	-362	-362		BACK	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.03/1.00 (A-B:1), BC=0.09/1.00 (C-D:1), WB=0.00/1.00 (A-C:1), SS=0.09/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.03 (A) (INPUT = 0.90)

JSI METAL= 0.01 (B) (INPUT = 1.00)




Structural component only
DWG# T-2126537

JOB NAME 420375	TRUSS NAME J1	QUANTITY 13	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:40 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1I60ZyxmN3-oo1CHARUBo99E9VMXEXDQlrpfuqmG5ZEReaRyrEgv



Scale = 1:23.1

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
F - B	2x4 DRY	No.2	SPF
A - C	2x4 DRY	No.2	SPF
F - D	2x4 DRY	No.2	SPF
ALL WEBS	2x3 DRY	No.2	SPF
DRY: SEASONED LUMBER.			

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMW-t	MT20	4.0	4.0	2.00	1.25
E	BMW+w	MT20	3.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
F	419	0	419	0	5-8	5-8
C	249	0	249	0	1-8	1-8
D	54	0	61	0	1-8	1-8

SEE MITEK STANDARD DETAIL 897791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	295	200 / 0	0 / 0	0 / 0	0 / 0	95 / 0	0 / 0
C	172	137 / 0	0 / 0	0 / 0	0 / 0	35 / 0	0 / 0
D	43	0 / 0	0 / 0	0 / 0	0 / 0	43 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)	UNBRACED LENGTH
FR-TO				FR-TO			
F-B	-364 / 0	0.0	0.0 0.04 (1)	B-E	0 / 0	0.00 (1)	7.81
A-B	0 / 26	-84.9	-84.9 0.11 (1)				10.00
B-C	0 / 0	-84.9	-84.9 0.50 (1)				10.00
F-E	0 / 0	-18.5	-18.5 0.14 (4)				10.00
E-D	0 / 0	-18.5	-18.5 0.19 (4)				10.00

TOTAL WEIGHT = 13 X 18 = 234 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.05")

CSI: TC=0.50/1.00 (B-C:1), BC=0.19/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.17/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.21 (B) (INPUT = 0.90)
JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126452

JOB NAME 420376	TRUSS NAME J1S	QUANTITY 8	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 13:00:35 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1I60ZyxmN3-396HUGARuX97vbeMO5hjmpsyABCH499YJtCw9yrEPA



TOTAL WEIGHT = 8 X 21 = 166 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
I - B	2x4	DRY	No.2
A - D	2x4	DRY	No.2
I - H	2x4	DRY	No.2
H - C	2x4	DRY	No.2
G - E	2x4	DRY	No.2

ALL WEBS 2x3 DRY
DRY: SEASONED LUMBER.

DESCR.

SPF
SPF
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	DOWN	IN-SX	IN-SX
I	432	0	0	5-8
D	184	0	0	1-8
E	107	0	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) D, E

UNFACTORED REACTIONS

JT	1ST LOASE COMBINED	MAX./MIN. SNOW	MAX./MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
I	304	207 / 0	0 / 0	0 / 0	0 / 0	97 / 0	0 / 0
D	128	96 / 0	0 / 0	0 / 0	0 / 0	32 / 0	0 / 0
E	79	33 / 0	0 / 0	0 / 0	0 / 0	45 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LO)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LO)	
FR-TO		FROM TO		FR-TO			
I-B	-417 / 0	0.0	0.04 (1)	B-H	0 / 192	0.04 (1)	
A-B	0 / 26	-84.9	-84.9 0.11 (1)	C-F	-481 / 0	0.07 (1)	
B-C	-216 / 0	-84.9	-84.9 0.11 (1)				
C-D	0 / 4	-84.9	-84.9 0.27 (1)				
I-H	0 / 0	-18.5	-18.5 0.01 (4)				
H-G	-73 / 0	0.0	0.0 0.23 (1)				
G-C	0 / 134	0.0	0.0 0.25 (1)				
G-F	0 / 419	-18.5	-18.5 0.39 (1)				
F-E	0 / 0	-18.5	-18.5 0.32 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 23.3 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.06")
ALLOWABLE DEFL. (TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (TL) = $L/587$ (0.12")

CSI: TC=0.27/1.00 (C-D:1), BC=0.39/1.00 (F-G:1),
WB=0.07/1.00 (C-F:1), SS=0.19/1.00 (C-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY) SHEAR	SECTION (PLI)	MAX MIN	MAX MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.36 (C) (INPUT = 0.90)
JSI METAL = 0.15 (G) (INPUT = 1.00)

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TMVW-t	MT20	4.0	4.0	2.00	1.25
F	BMVW-w	MT20	3.0	6.0		
G	BMVW-t	MT20	3.0	4.0		
H	BMVW-t	MT20	4.0	4.0		
I	BMV1+p	MT20	3.0	4.0		

NOTES-


- (1) Lateral braces to be a minimum of 2X4 SPF #2.



Structural component only
DWG# T-2126481

JOB NAME 420375	TRUSS NAME J1C	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:41 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1I60ZymN3-G?baUWS7y6H0sJGhwElmler473D3aDWEouBC6tyrEgu



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
F - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-1	MT20	4.0	4.0	2.00 1.25
E	BMV+w	MT20	3.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
JT	330	0	330	0	5-8	5-8
F	161	0	161	0	1-8	1-8
D	54	0	61	0	1-8	1-8

SEE MITK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	234	151 / 0	0 / 0	0 / 0	0 / 0	82 / 0	0 / 0
C	111	88 / 0	0 / 0	0 / 0	0 / 0	23 / 0	0 / 0
D	43	0 / 0	0 / 0	0 / 0	0 / 0	43 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED				WEBS		FACTORED	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	CS1 (LC)	UNBRAC LENGTH	MEMB.	MAX. FORCE (LBS)	MAX	CS1 (LC)
FR-TO						FR-TO			
F-B	-276 / 0	0.0	0.0	0.03 (1)	7.81	B-E	0 / 0	0.00 (1)	
A-B	0 / 26	-84.9	-84.9	0.11 (1)	10.00				
B-C	0 / 0	-84.9	-84.9	0.21 (1)	10.00				
F-E	0 / 0	-18.5	-18.5	0.14 (4)	10.00				
E-D	0 / 0	-18.5	-18.5	0.19 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.21/1.00 (B-C:1), BC=0.19/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)




Structural component only
DWG# T-2126453

JOB NAME 420375	TRUSS NAME J1C3	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:43 2021 Page 1
ID:rhT00T9Mf?GOVQD_N1160ZyxmN3-DNjLvCUNUjXk5dQ42fnEr3wS7sx270XFBglBmyrEgs

Scale = 1:13.2



TOTAL WEIGHT = 2 X 8 = 17 lb

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	250	0	250	0	5-8	5-8
C	32	0	32	0	1-8	1-8
D	15	0	17	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX./MIN. COMPONENT REACTIONS		PERM. LIVE	WIND	DEAD	SOIL
	SNOW	LIVE	SNOW	LIVE				
E	174	129 / 0	0 / 0	0 / 0	0 / 0	45 / 0	0 / 0	0 / 0
C	22	18 / -24	0 / 0	0 / 0	0 / 0	5 / 0	0 / 0	0 / 0
D	12	0 / 0	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. VERT. (LC1)	MAX. HORZ. (LC)	MEMB.	MAX. FORCE (LBS)	MAX. VERT. (LC)	MAX. HORZ. (LC)
FR-TO		FROM TO			FR-TO			
E-B	-235 / 0	0.0	0.0	0.02 (1)	B-D	0 / 0	0.00 (1)	
A-B	0 / 26	-84.9	-84.9	0.11 (1)				
B-C	-20 / 0	-84.9	-84.9	0.11 (1)				
E-D	0 / 0	-18.5	-18.5	0.01 (4)				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(TL) = L/360 (0.19")

CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.11/1.00 (A-B:1), BC=0.01/1.00 (D-E:4), WB=0.00/1.00 (B-D:1), SS=0.08/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.14 (B) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126455

JOB NAME 420375	TRUSS NAME J1C4	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:44 2021 Page 1
ID:rh1OOT9Mf?GOVQD_N1l60ZyxmN3-haGj6YU?F1fbjn?GbMJTNGTbNGHTnaGgUrPsjCyrEgr



TOTAL WEIGHT = 2 X 11 = 22 lb

LUMBER				DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF
ALL WEBS 2x3 DRY				SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	4.0	4.0	2.00 1.25
D	BMV1+w	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
E	291	0	291	0	5-8	5-8		
C	161	0	161	0	1-8	1-8		
D	15	0	17	0	1-8	1-8		

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
E	203	151 / 0	0 / 0	0 / 0	0 / 0	51 / 0	0 / 0
C	111	88 / 0	0 / 0	0 / 0	0 / 0	23 / 0	0 / 0
D	12	0 / 0	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		W E B S		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (LBS)	LC1 (PLF)	MAX. CSI (LC)	MAX. UNBRACED LENGTH	MEMB. FR-TO	MAX. FORCE (LBS)	MAX. CSI (LC)
E-B	-276 / 0	0.0	0.0	0.03 (1)	7.81	B-D	0 / 0	0.00 (1)
A-B	0 / 26	-84.9	-84.9	0.12 (5)	10.00			
B-C	0 / 0	-84.9	-84.9	0.21 (1)	10.00			
E-D	0 / 0	-18.5	-18.5	0.01 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.21/1.00 (B-C:1), BC=0.01/1.00 (D-E:4),
WB=0.00/1.00 (B-D:1), SSI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.16 (B) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126456

JOB NAME 420375	TRUSS NAME J2	QUANTITY 3	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:45 2021 Page 1
ID:rhTOOT9Mf?GOVQD_N160ZyxnN3-9mq5KuVd0KnSLxaT94qiwU0jagbOW1WqiV9PFeyrEgq



Scale = 1:33.8

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
F - B	2x4 DRY	No.2	SPF
A - C	2x4 DRY	No.2	SPF
F - D	2x4 DRY	No.2	SPF
ALL WEBS	2x3 DRY	No.2	SPF
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
E	BMV+w	MT20	2.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

NOTES: (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
F	401	0	401	0	5-8	5-8	5-8	5-8
C	232	0	232	0	1-8	1-8	1-8	1-8
D	51	0	57	0	1-8	1-8	1-8	1-8

SEE MITTEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LOASE COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	282	192 / 0	0 / 0	0 / 0	0 / 0	90 / 0	0 / 0
C	160	128 / 0	0 / 0	0 / 0	0 / 0	33 / 0	0 / 0
D	41	0 / 0	0 / 0	0 / 0	0 / 0	41 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED UNBRAC LENGTH	FR-TO
F-B	-350 / 0	0.0	0.0 0.04 (1)	7.81	B-E	0 / 0	0.00 (1)
A-B	0 / 38	-84.9	-84.9 0.12 (1)	10.00			
B-C	0 / 0	-84.9	-84.9 0.43 (1)	10.00			
F-E	0 / 0	-18.5	-18.5 0.13 (4)	10.00			
E-D	0 / 0	-18.5	-18.5 0.16 (4)	10.00			

TOTAL WEIGHT = 3 X 19 = 58 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.43/1.00 (B-C:1), BC=0.16/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SSI=0.14/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX MIN	MAX MIN	MAX MIN	
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.26 (B) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126457

JOB NAME 420375	TRUSS NAME J3	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:46 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxmN3-dyOTXEWfnewJy49fjnLxShYz74zTFUlx9uyo5yrEgg



Scale = 1:23.2

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				TOTAL WEIGHT = 2 X 13 = 25 lb			
N. L. G. A. RULES				BEARINGS				DESIGN CRITERIA			
CHORDS	SIZE	LUMBER	DESCR.	FACTORED	MAXIMUM FACTORED	INPUT	REQD	SPECIFIED LOADS:			
F - B	2x4	DRY	No.2	GROSS REACTION	GROSS REACTION	BRG	BRG	TOP CH. LL = 23.3 PSF			
A - C	2x4	DRY	No.2	VERT	DOWN	UPLIFT	IN-SX	DL = 6.0 PSF			
F - D	2x4	DRY	No.2	HORZ	HORZ	0	5-8	BOT CH. LL = 0.0 PSF			
ALL WEBS 2x3 DRY				JT	0	0	1-8	DL = 7.4 PSF			
DRY: SEASONED LUMBER.				F	266	0	1-8	TOTAL LOAD = 36.7 PSF			
				C	122	0	1-8				
				D	27	0	1-8				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
E	BMV+w	MT20	2.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS							
1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	
JT	187	131 / 0	0 / 0	0 / 0	55 / 0	0 / 0	
F	84	67 / 0	0 / 0	0 / 0	17 / 0	0 / 0	
C	21	0 / 0	0 / 0	0 / 0	21 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED (LC)	
FR-TO		FROM	TO	FR-TO			
F-B	-240 / 0	0.0	0.0 0.03 (1)	B-E	0 / 0	0.00 (1)	
A-B	0 / 38	-84.9	-84.9 0.13 (5)				
B-C	0 / 0	-84.9	-84.9 0.12 (1)				
F-E	0 / 0	-18.5	-18.5 0.04 (4)				
E-D	0 / 0	-18.5	-18.5 0.04 (4)				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TO=0.13/1.00 (A-B:5), BC=0.04/1.00 (E-F:4), WB=0.00/1.00 (B-E:1), SS=0.08/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)




Structural component only
DWG# T-2126458

JOB NAME 420375	TRUSS NAME J3C	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 12:41:47 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1l60ZyxmN3-59ysIZXtYy2AaEkrGVsA?v57mTli_x?77ApeWKXyrEgo



Scale = 1:19.2

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
F - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
E	BMVW+w	MT20	2.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
F	268	0	268	0	5-8	5-8
C	39	0	39	0	1-8	1-8
D	27	0	30	0	1-8	1-8

SEE MITK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LOASE COMBINED		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM. LIVE	WIND			
F	188	132 / 0	0 / 0	0 / 0	55 / 0	0 / 0	0 / 0
C	27	21 / -23	0 / 0	0 / 0	5 / 0	0 / 0	0 / 0
D	21	0 / 0	0 / 0	0 / 0	21 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MEMB. FORCE (LBS)	MAX. CSI (LC)	MAX. FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO			FR-TO			
F-B	-241 / 0	0.0	0.0	0.03 (1)	7.81	0.00 (1)	0 / 0	0.00 (1)
A-B	0 / 38	-84.9	-84.9	0.13 (5)	10.00			
B-C	-27 / 0	-84.9	-84.9	0.13 (5)	6.25			
F-E	0 / 0	-18.5	-18.5	0.04 (4)	10.00			
E-G	0 / 0	-18.5	-18.5	0.04 (4)	10.00			
G-D	0 / 0	-18.5	-18.5	0.04 (4)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	2-0-12	-0	-0	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 11 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.13/1.00 (A-B:5), BC=0.04/1.00 (E-F:4), WB=0.00/1.00 (B-E:1), SSI=0.08/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)




Structural component only
DWG# T-2126459

Structural component only
DWG# T-2126460

JOB NAME 420376	TRUSS NAME J4	QUANTITY 3	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 13:00:36 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxnN3-XLglicB3fqHzXKv6cwF_L4Cad30YVInzdmTbyrEP9



Scale = 1:12.2

LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

NOTES: (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	243	0	243	0	5-8	5-8
C	15	0	15	0	1-8	1-8
D	0	0	11	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LOASE COMBINED		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM. LIVE	WIND			
E	189	126 / 0	0 / 0	0 / 0	43 / 0	0 / 0	0 / 0
C	10	8 / -22	0 / 0	0 / 0	3 / 0	0 / 0	0 / 0
D	0	0 / -9	0 / 0	0 / 0	8 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		MAX. FACTORED	MEMB.	WEBS		MAX. FACTORED
	FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX			FORCE (LBS)	MAX	
FR-TO									
E-B	-217 / 0	0.0	0.0	0.03 (5)	7.81				
A-B	0 / 26	-84.9	-84.9	0.11 (1)	10.00				
B-C	-20 / 0	-84.9	-84.9	0.08 (1)	6.25				
E-D	0 / 0	-18.5	-18.5	0.03 (5)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 3 X 6 = 18 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	36.7	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.11/1.00 (A-B:1), BC=0.03/1.00 (D-E:5), WB=0.00/1.00 (n/a:0), SSI=0.08/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.09 (E) (INPUT = 0.90)
JSI METAL = 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126482

JOB NAME 420378	TRUSS NAME J5	QUANTITY 5	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:10 2021 Page 1
ID: rhtOOT9Mf?GOVQD_N1160ZyxnN3-1FPepZfFyRn8?vSQ4AsqQwZVxLDQYJNGf5EKceyrCkh



Scale = 1:27.3

TOTAL WEIGHT = 5 X 15 = 75 lb [M]

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS	2x4	DRY	SPF
F - B	2x4	DRY	SPF
A - C	2x4	DRY	SPF
F - D	2x4	DRY	SPF
ALL WEBS	2x3	DRY	SPF
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
E	BMV+w	MT20	2.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
F	318	0	318	0	0	5-8	5-8	
C	164	0	164	0	0	1-8	1-8	
D	36	0	40	0	0	1-8	1-8	

SEE MITK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE		MAX / MIN COMPONENT REACTIONS		PERM. LIVE	WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE				
F	223	155 / 0	0 / 0	0 / 0	0 / 0	69 / 0	0 / 0	
C	113	90 / 0	0 / 0	0 / 0	0 / 0	23 / 0	0 / 0	
D	29	0 / 0	0 / 0	0 / 0	0 / 0	29 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO				
F-B	-282 / 0	0.0	0.0	0.0
A-B	0 / 38	-84.9	-84.9	0.0
B-C	0 / 0	-84.9	-84.9	0.0
F-E	0 / 0	-18.5	-18.5	0.0
E-D	0 / 0	-18.5	-18.5	0.0

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.22/1.00 (B-C:1), BC=0.08/1.00 (D-E:4),
WB=0.00/1.00 (B-E:1), SSI=0.10/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.21 (B) (INPUT = 0.90)
JSI METAL= 0.06 (B) (INPUT = 1.00)




Structural component only
DWG# T-2126503



JOB NAME 420378	TRUSS NAME J6	QUANTITY 4	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 14:54:13 2021 Page 1
ID:rhtOOT9Mf?GOVQD_N1l60ZyxmN3-Rq4mRah7FM9jsNB?mIQX2YB2aZGlg7lL3S_DzyrCke



Scale = 1:23.2

TOTAL WEIGHT = 4 X 13 = 50 lb [M]

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
F - B	2x4 DRY	No.2	SPF
A - C	2x4 DRY	No.2	SPF
F - D	2x4 DRY	No.2	SPF
ALL WEBS	2x3 DRY	No.2	SPF
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
E	BMV+w	MT20	2.0	4.0	
F	BMV1+p	MT20	3.0	4.0	

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED		MAXIMUM FACTORED		INPUT		REQD	
	GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
F	266	0	266	0	0	5-8	5-8	
C	122	0	122	0	0	1-8	1-8	
D	27	0	30	0	0	1-8	1-8	

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	COMBINED	MAX./MIN. COMPONENT REACTIONS				DEAD	SOIL
		1ST LCASE	SNOW	LIVE	PERM. LIVE		
F	187	131 / 0	0 / 0	0 / 0	0 / 0	55 / 0	0 / 0
C	84	67 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	21	0 / 0	0 / 0	0 / 0	0 / 0	21 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		WEBS		MEMB.	MAX. FACTORED	
	MAX. FACTORED	FACTORED	VERT. LOAD LC1	MAX. FACTORED		FORCE	MAX
	FORCE (LBS)	(PLF)	CSI (LC)	UNBRAC		(LBS)	CSI (LC)
FR-TO		FROM TO		LENGTH	FR-TO		
F-B	-240 / 0	0.0 0.0 0.03 (1)	7.81	B-E	0 / 0	0.00 (1)	
A-B	0 / 38	-84.9 -84.9 0.13 (5)	10.00				
B-C	0 / 0	-84.9 -84.9 0.12 (1)	10.00				
F-E	0 / 0	-18.5 -18.5 0.04 (4)	10.00				
E-D	0 / 0	-18.5 -18.5 0.04 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.13/1.00 (A-B:5), BC=0.04/1.00 (E-F:4), WB=0.00/1.00 (B-E:1), SSI=0.08/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX MIN	MAX MIN	MAX MIN	
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.18 (B) (INPUT = 0.90)
JSI METAL = 0.05 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126506




Structural component only
DWG# T-2126507

JOB NAME 420381	TRUSS NAME J8	QUANTITY 3	PLY 1	JOB DESC. ROYAL PINE HOMES	TRUSS DESC.	DRWG NO.
---------------------------	-------------------------	----------------------	-----------------	--------------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:27 2021 Page 1
ID:Z9U1O5I40r9N9gEXuxpSeqywCSD-65Z7BG0piXvV1w_SGaaPqul5s_vUPIYVcC5NDyrCN



Scale = 1:27.3

TOTAL WEIGHT = 3 X 15 = 46 lb

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
F - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00	2.00
E	BMV+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

NOTES- (1)
1) Lateral braces to be a minimum of 2X4 SPF #2.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	GROSS REACTION	DOWN	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	IN-SX
F	367	0	367	0	0	5-8	5-8		
G(C)	123	0	123	0	0	1-8	1-8		
D	27	0	30	0	0	1-8	1-8		

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	258	177 / 0	0 / 0	0 / 0	0 / 0	82 / 0	0 / 0
G(C)	85	68 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	22	0 / 0	0 / 0	0 / 0	0 / 0	21 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, G(C)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT.	LOAD LC1 MAX (PLF)	CS1 (LC)	UNBRAC LENGTH FR-TO	MEMB.	FORCE (LBS)
F-B	-344 / 0	0.0	0.0	0.08 (4)	7.81	B-E	0 / 42
A-B	0 / 38	-84.9	-84.9	0.14 (5)	10.00		
B-C	-26 / 0	-84.9	-84.9	0.22 (1)	6.25		
F-E	-32 / 0	-18.5	-18.5	0.03 (4)	6.25		
E-D	0 / 0	-18.5	-18.5	0.04 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL(LL)= L/360 (0.19")
CALCULATED VERT. DEFL(LL) = L/999 (0.00")
ALLOWABLE DEFL(TL)= L/360 (0.19")
CALCULATED VERT. DEFL(TL) = L/999 (0.01")

CSI: TC=0.22/1.00 (B-C:1), BC=0.04/1.00 (D-E:4),
WB=0.01/1.00 (B-E:4), SS=0.12/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
	MAX	MIN	MAX MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.24 (B) (INPUT = 0.90)
JSI METAL = 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126520

JOB NAME 420381	TRUSS NAME J9	QUANTITY 11	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:28 2021 Page 1
ID:Z9U1O5I40r9N9gEXuxpSeqywCSD-ai7VPc1RT1m7BVA0z5py1RyPGKbDsAhjGyfufyrcMz



Scale = 1:19.1

TOTAL WEIGHT = 11 X 10 = 111 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ
E	256	0	256	0
C	36	0	36	0
D	16	0	18	0

SEE MITK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	179	132 / 0	0 / 0	0 / 0	0 / 0	0 / 0	47 / 0	0 / 0
C	25	20 / -24	0 / 0	0 / 0	0 / 0	0 / 0	5 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
E-B	-241 / 0	0.0	0.0 (1)	B-D	0 / 0	0.00 (1)	
A-B	0 / 38	-84.9	-84.9 (1)				
B-C	-28 / 0	-84.9	-84.9 (1)				
E-D	0 / 0	-18.5	-18.5 (4)				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (B-D:1), SS=0.07/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
	MAX	MIN	MAX MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.18 (B) (INPUT = 0.90)
JSI METAL = 0.05 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126521

JOB NAME 420381	TRUSS NAME J9C	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:29 2021 Page 1
ID:Z9U1O5I40r9N9gEXxpSeqywCSD-2Uhtcy13E89dIL4MZhc2UF_79ggqyJQrywhCQ5yrCMY



Scale: 3/4"=1'

TOTAL WEIGHT = 2 X 9 = 18 lb

LUMBER			
N.L.G.A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2
ALL WEBS 2x3 DRY No.2			
DRY: SEASONED LUMBER.			

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	DOWN	IN-SX	IN-SX
E	253	0	5-8	5-8
C	-24	0	-66	1-8
D	16	0	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE	
E	177	130 / 0	0 / 0	0 / 0	46 / 0
C	-16	0 / -39	0 / 0	0 / 0	0 / -3
D	13	0 / 0	0 / 0	0 / 0	13 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX (LC)	
FR-TO		FROM	TO	FR-TO			
E-B	-237 / 0	0.0	0.0	0.03 (1)	7.81	B-D	0 / 0
A-B	0 / 38	-84.9	-84.9	0.12 (1)	10.00		
B-C	-46 / 0	-84.9	-84.9	0.11 (1)	6.25		
E-D	0 / 0	-18.5	-18.5	0.02 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	PSF
	DL	6.0
BOT CH.	LL	PSF
	DL	7.4
TOTAL LOAD		36.7

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL(TL)= L/360 (0.19")
CALCULATED VERT. DEFL(TL)= L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (B-D:1), SSI=0.07/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX	MIN	MAX
650	371	1747
788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.18 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126522

JOB NAME 420381	TRUSS NAME J10	QUANTITY 3	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Wed Aug 4 15:19:30 2021 Page 1
ID:Z9U1O5I40r9N9gEXuPSeqyWCSD-WgFqI2h?SHUMVfZ7O7H1SWly302hmg_BaRmyYyrCMx



Scale = 1:21.4

TOTAL WEIGHT = 3 X 11 = 33 lb [M]

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	
CHORDS			
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
E	255	0	255	0	0	5-8	5-8	
C	37	0	37	0	-33	1-8	1-8	
D	16	0	18	0	0	1-8	1-8	

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	COMBINED	MAX./MIN. COMPONENT REACTIONS					
		1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD
E	178	131 / 0	0 / 0	0 / 0	0 / 0	0 / 0	47 / 0
C	25	20 / -23	0 / 0	0 / 0	0 / 0	0 / 0	5 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (LBS)	MAX. FORCE (LBS)	VERT. LOAD (LBS)	MAX. FORCE (LBS)	VERT. LOAD (LBS)	MAX. FORCE (LBS)	VERT. LOAD (LBS)
FR-TO								
E-B	-239 / 0	0.0	0.0	0.03 (1)	7.81	0 / 0	0.00 (1)	
A-B	0 / 32	-84.9	-84.9	0.11 (1)	10.00			
B-C	-24 / 0	-84.9	-84.9	0.11 (1)	6.25			
E-D	0 / 0	-18.5	-18.5	0.02 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3 PSF
DL = 6.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD	= 36.7 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.11/1.00 (A-B:1), BC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (B-D:1), SSI=0.08/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.15 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)



Structural component only
DWG# T-2126523



Alves Engineering Services Inc.

5208 Easton road
Burlington, Ontario L7L 6N6
(289) 259 5455

RESPONSABILITIES

- 1-Alves Engineering Services Inc. is responsible for the design of trusses as individual components
- 2-It is the responsibility of others to ascertain that the design loads utilized on this drawing meet or exceed the actual dead load imposed by the structure and the live load imposed by the local building code or the authorities having jurisdictions.
- 3- All dimensions are to be verified by owner, contractor, architect or other authority before manufacture.
- 4- Alves Engineering Services Inc. bears no responsibility for the erection of the trusses. Persons erecting trusses are cautioned to seek professional advice regarding temporary and permanent bracing system. Bracing shown on Alves Engineering Services Inc. drawings is specified for the truss as a single component and forms an integral part of the truss design, but is not meant to represent the only required bracing for that truss when trusses are installed in a series of trusses forming a roof truss system.
- 5- It is the manufactures responsibility to ensure that the trusses are manufactured in conformance with Alves Engineering Services Inc. specifications outlined below.

SPECIFICATIONS

- 1-Truss components sealed by Alves Engineering Services Inc. conform to the relevant sections of the current Building Code of Ontario and Canada (part 4 or part 9) or the current Canadian code for Farm Buildings in accordance with the application specified on the sealed truss component drawing. All truss component design procedures must conform to the current design standard issued by the truss plate institute of Canada (TPIC). All lumber and nailing stresses to conform to the current CSA wood design standard identified on the current Building Code and TPIC.
- 2- Lumber is to be the sizes and grade specified on the truss drawing.
- 3- Moist content of lumber is not to exceed 19% in service unless otherwise specified.
- 4- Plates shall be applied to both faces of the each truss joint and shall be positioned as shown on the truss drawings
- 5- Lumber used on manufacture of trusses is not to be treated with chemicals unless otherwise specified on the truss drawings.
- 6- The top chord is assumed to be continuously laterally braced by the roof sheathing or purlins at intervals specified on the truss drawing but not exceeding 24" c/c for (part 9) and not exceeding 48" for (part 4 or farm design)
- 7- When rigid ceiling is not attached directly to the bottom chord, lateral bracing is required and it should not exceed more than 3m or 10' intervals.
- 8-Refer to Mitek sheet MII7473C REV.10-08 attached for information on symbols, numbering *em and General Safety notes.

T-1900218

Feb 09, 2018

TOE-NAIL CAPACITY DETAILS

LATERAL AND WITHDRAWAL RESISTANCE OF BEARING ANCHORAGE BY TOE-NAILS

			SPF	D. FIR	SPF	D. FIR
COMMON WIRE	3.00	0.144	122	139	30	42
	3.25	0.144	127	144	32	45
	3.50	0.160	152	173	38	52
COMMON SPIRAL	3.00	0.122	96	108	26	36
	3.25	0.122	97	108	28	40
	3.50	0.152	142	161	36	50
3.25" Gun nail	3.25	0.120	94	105	28	39

Note: If using truss with D. Fir lumber and SPF bearing plate, use tabulated SPF values in table.

Nail type:	Common wire	Common spiral	Common wire	Common spiral	Gun Nail
Diameter (in.)	0.160	0.152	0.144	0.122	0.120
Length (in.)	3.50	3.50	3.00	3.00	3.25
MAXIMUM NUMBER OF TOE NAILS					
2x4 SPF	2	2	3	3	3
2x6 SPF	4	4	4	5	5
2x4 D. FIR	2	2	2	2	2
2x6 D. FIR	3	3	3	4	4




Figure 1: Toe-Nailing Rafter / Ceiling Member to Girder Truss


PEO
Certificate No. 10889485



December 21, 2020

TOE-NAIL CAPACITY DETAILS

Figure 2: Toe-Nail Anchorage to Bearing Plate for Uplift



NOTES:

1. Rafter and ceiling members may be connected to top and bottom chords of girder truss by toe-nailing the members into the girder chords (see fig. 1), provided the factored vertical reactions of the supported members do not exceed the lateral resistance of the toe-nails. Mechanical connectors (hangers) are required if factored vertical reactions exceed the toe-nail capacity, or if the connection must resist horizontal loads (loads perpendicular to the face of girder or rafter).
2. Trusses, rafters or ceiling members may be anchored to the bearing plate with toe-nails (see fig. 2), provided that the factored uplift reactions due to **wind or earthquake loads** do not exceed the **withdrawal resistance of the toe-nails**. Mechanical anchors (tie-downs) are required for reactions that exceed the toe-nail withdrawal capacity. Toe-nail anchorage to bearing plates is **NOT** permitted if uplift reactions are generated from gravity loads (snow, floor live, dead).
3. Tabulated toe-nail resistances on page 1 are for **one** toe-nail. Multiply unit values by the number of nails used in the connection. Maximum number of nails in a connection shall not exceed the tabulated limits shown on page 1 for a given lumber size /species.
4. Nail values are based on specific gravity of $G = 0.42$ (SPF) and $G = 0.49$ (D. Fir).
5. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member.
6. For wind / earthquake loads, tabulated lateral resistances may be multiplied by 1.15 (K_D factor). No increases are permitted for tabulated withdrawal resistances.
7. Lumber must be dry ($< 19\%$ moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-19, Clause 12.9.

PEO
Certificate No. 10889485



LUL/LUS/LJS/HUS/HHUS/HGUS

SIMPSON
Strong-Tie

Standard and Double-Shear Joist Hangers



This product is preferable to similar connectors because of
 a) easier installation, b) higher capacities, c) lower installed
 cost, or a combination of these features.

Most hangers in this series have double-shear nailing — an innovation that distributes the load through two points on each joist nail for greater strength. This allows for fewer nails, faster installation, and the use of all common nails for the same connection. (Do not bend or remove tabs)

Double-shear hangers range from the light capacity LUS hangers to the highest capacity HGUS hangers. For medium load truss applications, the HUS offers a lower cost alternative and easier installation than the HGUS hangers, while providing greater load capacity and bearing than the LUS.

Material: See table on pp. 217–218.


Finish: Galvanized. Some products available in stainless steel or ZMAX® coating; see Corrosion Information, pp. 18–20.

Installation:


- Use all specified fasteners; see General Notes.
- Nails must be driven at an angle through the joist or truss into the header to achieve the tabulated resistances (except LUL).
- Where 16d commons are specified, 10d commons may be used at 0.83 of the tabulated factored resistance.
- Not designed for welded or nailer applications.
- With single ply 2x carrying members, use 10d x 1 1/2" nails into the header and 10d commons into the joist, and reduce the resistance to 0.64 of the table value where 16d nails are specified and 0.77 where 10d nails are specified.

Options:


- LUS, LJS, LUL and HUS hangers cannot be modified.
- Other sizes available; consult your Simpson Strong-Tie representative.
- See Hanger Options information on pp. 105–107.



Double-Shear
Nailing
Top View






Double-Shear
Nailing
Side View;
Do not
bend tab




Dome Double-Shear
Nailing
Side View
(available on
some models)


**Typical HUS26
Installation
with Reduced
Heel Height**
 (Truss Designer
to provide
fastener quantity
for connecting
multiple members
together)




LUS28




LU26L




HUS210
(HUS26, HUS28,
and HHUS similar)



HGUS28-2



HHUS210-2



LJS26DS

LUS – Double Shear Joist Hangers

SIMPSON
Strong-Tie

All LUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections.

Material: 18 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners.
- Nails: 16d = 0.162" dia. x 3½" long common wire,
10d = 0.148" x 3" long common wire.
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads.
- Not designed for welded or nailer applications.

Options:

- These hangers cannot be modified




Typical LUS
Installation




Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _e ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _p =1.15)	Normal (K _p =1.00)	Uplift (K _p =1.15)	Normal (K _p =1.00)
LUS24	18	1⅞	3⅞	1¼	1⅞	(4) 10d	(2) 10d	710	1630	645	1155
LUS24-2	18	3⅞	3⅞	2	1⅞	(4) 16d	(2) 16d	835	2020	590	1435
LUS26	18	1⅞	4¾	1¼	3⅞	(4) 10d	(4) 10d	1420	2170	1290	1630
LUS26-2	18	3⅞	4¾	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920
LUS26-3	18	4¾	4¾	2	3¼	(4) 16d	(4) 16d	1720	2595	1545	2340
LUS28	18	1⅞	6⅞	1¼	3¾	(6) 10d	(6) 10d	1420	2520	1290	1790
LUS28-2	18	3⅞	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575
LUS28-3	18	4¾	6¼	2	3¼	(6) 16d	(4) 16d	1720	3325	1545	2375
LUS210	18	1⅞	7⅞	1¼	3⅞	(8) 10d	(4) 10d	1420	2785	1290	2210
LUS210-2	18	3⅞	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195
LUS210-3	18	4¾	8¾	2	5¼	(8) 16d	(6) 16d	2580	3345	2320	2375


1. d_e is the distance from the seat of the hanger to the highest joist nail.



Dome Double
Shear Nailing
prevents tabs
breaking off
(available on
some models).
U.S. Patent
5,603,580



Double
Shear
Nailing
Top View.



**LIMIT
STATES
DESIGN**

This technical bulletin is effective until June 30, 2022, and reflects information available as of April 1, 2020. This information is updated periodically and should not be relied upon after June 30, 2022. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2020 Simpson Strong-Tie Company Inc.

T-SPEC LUS20 3/20 exp. 6/22

(800) 999-5099
strongtie.com

TECHNICAL BULLETIN

HUS/LJS – Double Shear Joist Hangers

SIMPSON
Strong-Tie

All hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: See table

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86 -14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia. x 3½" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:


- See current catalogue for options




LJS26DS




HUS210
(HUS26, HUS28, similar)



Typical LJS26DS
Installation




Typical HUS
Installation




Typical HUS Installation
(Truss Designer to provide fastener
quantity for connecting multiple
members together)

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _e ¹	Face	Joist	D-Fir-L		S-P-F	
								Uplift (K _p =1.15) lb.	Normal (K _p =1.00) lb.	Uplift (K _p =1.15) lb.	Normal (K _p =1.00) lb.
LJS26DS	18	1⅞	5	3½	4⅞	(16) 16d	(6) 16d	2055	4265	1460	4115
HUS26	16	1⅞	5⅞	3	3⅞	(14) 16d	(6) 16d	2705	4940	2065	3875
HUS28	16	1⅞	7⅞	3	6⅞	(22) 16d	(8) 16d	3605	5365	2675	4345
HUS210	16	1⅞	9⅞	3	7⅞	(30) 16d	(10) 16d	4505	5795	4010	4740
HUS1.81/10	16	1⅞	9	3	8	(30) 16d	(10) 16d	4505	6450	4010	5200


1. d_e is the distance from the seat of the hanger to the highest joist nail.



Dome Double
Shear Nailing
prevents tabs
breaking off
(available on
some models).
U.S. Patent
5,603,580



Double
Shear
Nailing
Side View.
Do not
bend tab
back.



Double
Shear
Nailing
Top View.



**LIMIT
STATES
DESIGN**

This technical bulletin is effective until June 30, 2022, and reflects information available as of April 1, 2020. This information is updated periodically and should not be relied upon after June 30, 2022. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2020 Simpson Strong-Tie Company Inc.

T-SPECHUS20 3/20 exp. 6/22

(800) 999-5099
strongtie.com

TECHNICAL BULLETIN

HGUS – Double Shear Joist Hangers

SIMPSON
Strong-Tie

All HGUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: 12 gauge

Finish: G90 galvanized

Design:



- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia x 3½" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:

- See current catalogue for options




Typical HGUS Installation



Typical HGUS Installation
(Truss Designer to provide fastener quantity for connecting multiple members together)


Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _o ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K _o =1.15)	(K _o =1.00)	(K _o =1.15)	(K _o =1.00)
HGUS26	12	1½	5½	5	4½	(20) 16d	(8) 16d	2685	6625	2685	5700
HGUS26-2	12	3½	5½	4	4½	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-3	12	4½	5½	4	4½	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-4	12	6½	5½	4	4½	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS28	12	1½	7½	5	6½	(36) 16d	(12) 16d	3310	7675	3100	6900
HGUS28-2	12	3½	7½	4	6½	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-3	12	4½	7½	4	6½	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-4	12	6½	7½	4	6½	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS210	12	1½	9½	5	7½	(46) 16d	(16) 16d	3535	11070	2510	8090
HGUS210-2	12	3½	9½	4	8½	(46) 16d	(16) 16d	6840	14015	4855	10270
HGUS210-3	12	4½	9½	4	8½	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS210-4	12	6½	9½	4	8½	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS212-4	12	6½	10½	4	10½	(56) 16d	(20) 16d	7640	14995	5425	10645
HGUS214-4	12	6½	12½	4	11½	(66) 16d	(22) 16d	10130	16400	7195	11645

1. d_o is the distance from the seat of the hanger to the highest joist nail.




Dome Double Shear Nailing prevents tabs breaking off (available on some models).


U.S. Patent 5,603,580



Double Shear Nailing Side View. Do not bend tab back.



Double Shear Nailing Top View.



LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2022, and reflects information available as of April 1, 2020. This information is updated periodically and should not be relied upon after June 30, 2022. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2020 Simpson Strong-Tie Company Inc.


T-SPECHGUS20 3/20 exp. 6/22

(800) 999-5099
strongtie.com

Symbols

PLATE LOCATION AND ORIENTATION

Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths or mm. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0-1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.



* Plate location details available in Mitek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.

Industry Standards:

TPIC: Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths or mm (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

CCMC Reports:

11996-L, 10319-L, 13270-L, 12691-R

© 2007 Mitek® All Rights Reserved

Mitek
POWER TO PERFORM.™

Mitek Engineering Reference Sheet: MII-7473C rev. 10-08

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

- Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
- Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
- Never exceed the design loading shown and never stack materials on inadequately braced trusses.
- Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
- Cut members to bear lightly against each other.
- Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by TPIC.
- Design assumes trusses will be suitably protected from the environment in accord with TPIC.
- Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
- Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
- Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
- Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
- Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
- Top chords must be sheathed or purlins provided at spacing indicated on design.
- Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
- Connections not shown are the responsibility of others.
- Do not cut or alter truss member or plate without prior approval of an engineer.
- Install and load vertically unless indicated otherwise.
- Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
- Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
- Design assumes manufacture in accordance with TPIC Quality Criteria.