


		Products		
PlotID	Length	Product	Plies	Net Qty
J1	20-00-00	11 7/8" NI-40x	1	5
J1DJ	20-00-00	11 7/8" NI-40x	2	2
J2	18-00-00	11 7/8" NI-40x	1	6
J2DJ	18-00-00	11 7/8" NI-40x	2	2
J3	16-00-00	11 7/8" NI-40x	1	5
J4	14-00-00	11 7/8" NI-40x	1	21
J4DJ	14-00-00	11 7/8" NI-40x	2	4
J5	12-00-00	11 7/8" NI-40x	1	8
J6	8-00-00	11 7/8" NI-40x	1	4
J7	6-00-00	11 7/8" NI-40x	1	5
J8	4-00-00	11 7/8" NI-40x	1	2
B1	18-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	2	2
B5	16-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	1	1
B2	14-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	2	2
B3	8-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	1	1
B4	8-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	1	1
B6	8-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	1	1
R1	128-00-00	1 1/8" x 11 7/8" APA Rim Board	1	1
Bk1	36-00-00	11 7/8" NI-40x	1	1
Col	nnector Sumn	nary		

Connector Summary										
Qty Manuf Product										
10	H1	IUS2.56/11.88								
4	H1	IUS2.56/11.88								
5	H1	IUS2.56/11.88								
3	H3	HUS1.81/10								
2	H3	HUS1.81/10								



# THIS IS A FLOOR COMPONENT PLACEMENT PLAN ONLY.

The wood beams and joists outlined on this plan are designed as individual building components to be incorporated into the design of the building at the specification of the building designer. Please see the individual beam reports, joist reports, and/or joist span tables for each component identified on this placement plan.

joist span tables for each component identified on this placement plan.

The supporting structure is to be specified by the building designer prior to the installation of joist(s) and/or beam(s). The building designer is responsible for the bracing of the floor system and its integration into the bracing of the overall structure. All components labelled "by others" or "as per plan", and all steel beams, and all steel beams, and the structure is the scan of work of this scale.

are not within the scope of work of this seal.

The building designer must review and approve this plan to acertain conformity to the overall structural plan of the building. All dimensions to be verified on site.

**DATE:** 3/05/24

1st FLOOR FRAMING



FROM PLAN DATED: SEPT 2021
BUILDER: ROYAL PINE HOMES
SITE: SUMMER RIDGE ESTATES

MODEL: 2505 ELEVATION: A,B

LOT:

**CITY:** BRAMPTON

**SALESMAN**: WILLIAM GARCIA

DESIGNER: EEO REVISION:

REFER TO THE NORDIC INSTALLATION GUIDE FOR PROPER STORAGE AND INSTALLATION. SQUASH BLOCKS OF 2x4, 2x6, 2x8 SPF #2 REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. MULTIPLE SQUASH BLOCKS REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. CANTILEVERED JOISTS INCLUDING CANT' OVER

BRICK REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4/5 FOR REINFORCEMENT REQUIREMENTS. FOR HOLES INCLUDING DUCT CHASE AND FIELD CUT OPENINGS SEE FIGURE 6 AND TABLES 6.1/6.2. CERAMIC TILE APPLICATION AS PER OBC 9.30.6.

ALL CONNECTORS MUST BE INSTALLED AS PER THE MANUFACTURER'S SPECIFICATIONS USING THE MANUFACTURER SPECIFIED FASTENERS.


ALL BEAM HANGER FASTENERS INSTALLED INTO THE SUPPORTING MEMBER MUST BE A MINIMUM OF 3.5" IN LENGTH UNLESS OTHERWISE SPECIFIED BY THE SUPPORTING MEMBER ENGINEER OF RECORD.

#### LOADING:

LIVE LOAD: 40.0 lb/ft<sup>2</sup>
DEAD LOAD: 15.0 lb/ft<sup>2</sup>
TILE LOAD: +5.0 lb/ft<sup>2</sup>


JOIST LL DEFLECTION LIMIT: L/480

SUBFLOOR: 3/4" GLUED AND NAILED



Products											
PlotID	Length	Product	Plies	Net Qty							
J1	20-00-00	11 7/8" NI-40x	1	8							
J2	18-00-00	11 7/8" NI-40x	1	3							
J3	16-00-00	11 7/8" NI-40x	1	8							
J4	14-00-00	11 7/8" NI-40x	1	28							
J5	12-00-00	11 7/8" NI-40x	1	10							
J6	10-00-00	11 7/8" NI-40x	1	21							
J7	8-00-00	11 7/8" NI-40x	1	6							
B9	18-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	1	1							
B8	14-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	1	1							
B7 DR	14-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	3	3							
B10	8-00-00	1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL	1	1							
R1	150-00-00	1 1/8" x 11 7/8" APA Rim Board	1	1							
Bk1	30-00-00	11 7/8" NI-40x	1	1							

Connector Summary										
	Qty	Manuf	Product							
	7	H1	IUS2.56/11.88							
	2	H3	HUS1.81/10							



# THIS IS A FLOOR COMPONENT PLACEMENT PLAN ONLY.

The wood beams and joists outlined on this plan are designed as individual building components to be incorporated into the design of the building at the specification of the building designer. Please see the individual beam reports, joist reports, and/or joist span tables for each component identified on this placement plan. The supporting structure is to be specified by the building designer prior to the installation of joist(s) and/or beam(s). The building designer is responsible for the

The supporting structure is to be specified by the building designer prior to the installation of joist(s) and/or beam(s). The building designer is responsible for the bracing of the floor system and its integration into the bracing of the overall structure. All components labelled "by others" or "as per plan", and all steel beams, are not within the scope of work of this seal.

are not within the scope of work of this seal.

The building designer must review and approve this plan to acertain conformity to the overall structural plan of the building. All dimensions to be verified on site.

**DATE:** 3/05/24

2nd FLOOR FRAMING ALL OPT



FROM PLAN DATED: SEPT 2021
BUILDER: ROYAL PINE HOMES
SITE: SUMMER RIDGE ESTATES

MODEL: 2505 ELEVATION: A,B

LOT:

CITY: BRAMPTON

SALESMAN: WILLIAM GARCIA

DESIGNER: EEO REVISION:

REFER TO THE NORDIC INSTALLATION GUIDE FOR PROPER STORAGE AND INSTALLATION.

SQUASH BLOCKS OF 2x4, 2x6, 2x8 SPF #2 REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS.

MULTIPLE SQUASH BLOCKS REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1.

CANTILEVERED JOISTS INCLUDING CANT' OVER BRICK REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4/5 FOR REINFORCEMENT REQUIREMENTS.

FOR HOLES INCLUDING DUCT CHASE AND FIELD CUT OPENINGS SEE FIGURE 6 AND TABLES 6.1/6.2. CERAMIC TILE APPLICATION AS PER OBC 9.30.6.

ALL CONNECTORS MUST BE INSTALLED AS PER THE MANUFACTURER'S SPECIFICATIONS USING THE MANUFACTURER SPECIFIED FASTENERS.

ALL BEAM HANGER FASTENERS INSTALLED INTO THE SUPPORTING MEMBER MUST BE A MINIMUM OF 3.5" IN LENGTH UNLESS OTHERWISE SPECIFIED BY THE SUPPORTING MEMBER ENGINEER OF RECORD.

#### LOADING:

LIVE LOAD: 40.0 lb/ft²
DEAD LOAD: 15.0 lb/ft²
TILE LOAD: +5.0 lb/ft²

JOIST LL DEFLECTION LIMIT: L/480

SUBFLOOR: 5/8" GLUED AND NAILED

# NORDIC

INSTALLATION GUIDE NORDIC JOIST NS-GI33 **■**◆■

**Engineered Wood Products** 

BASIC INSTALLATION **GUIDE FOR RESIDENTIAL FLOORS** 

NORDIC **U**JOIST

NORDIC **STRUCTURES** 

WEB STIFFENERS

NAIL SPACING

nordic.ca

1 x 2-5/16 Minimum width 1-1/2 x 2-5/16 Minimum width

1g

1h

#### INSTALLING NORDIC I-JOISTS

- Except for cutting to length, I-joist flanges should never be cut, drilled or notched
- Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment
- Concentrated loads should only be applied to the top surface of the top flange. Concentrated loads should not be suspended from the bottom flange with the exception of light loads, such as ceiling fans or light fixtures.
- I-joists must be protected from the weather prior to installation.
- I-joists must not be used in applications where they will be permanently exposed to weather, or will reach a moisture content of 15 percent or greater, such as in swimming pool or hot tub areas. They must not be installed where they will remain in direct contact with
- End bearing length must be at least 1-3/4 inch. For multiple-span joists, intermediate bearing length must be at least 3-1/2 inches.
- I-joists installed beneath bearing walls perpendicular to the joists shall have full-depth blocking panels, rim board, or squash blocks (cripple blocks) to transfer gravity loads from above the floor system to the wall or foundation below.
- For I-inists installed directly beneath bearing walls parallel to the joists or used as rim board or blocking panels, the using a single I-joist is 3.300 plf, and 6.600 plf if double I-joists are used.
- . Continuous lateral support of the I-joist's compression flange is required to prevent rotation and buckling. In simple span uses, lateral support of the top flange is normally supplied by the floor sheathing. In multiple-span or cantilever applications, bracing of the I-joist's bottom flange is also required at interior supports of multiple-span joists, and at the end support next to the cantilever extension. The ends of all cantilever extensions must be laterally braced as shown in details 3, 4, or 5.
- . Nails installed in flange face or edge shall be spaced in accordance with the applicable building code requirements or approved building plans, but should not be closer than those specified on page 3.3 of the Nordic Joist Technical Guide (NS-GT3).
- B. Details 1 show only I-joist-specific fastener requirements. For other fastener requirements, see the applicable building code.
- 4. For proper temporary bracing of wood I-joists and placement of temporary construction loads, see APA Technical Note: Temporary Construction Loads over I-Joist Roofs and Floors, Form J735.

All nails shown in the details are assumed to be common nails unless otherwise noted. Nails shall have a diameter not less than 0.128 inch for 2-1/2-inch nails, or 0.144 inch for 3-inch nails. Individual components not shown to scale for clarity.

1b

1


2×3 S-P-F No. 2

NORDIC I-JOIST SERIES RESIDENTIAL SERIES

2x3 1950f MSR 3/8 in. web 33 pieces per unit



1k



2x plate flush with inside face of wall or beam. 1/8" overhang allowed past inside face of wall or beam.

SAFETY AND CONSTRUCTION PRECAUTIONS

Avoid Accidents by Following these Important Guidelines

of I-ioists at the end of the bay.

rim board, or cross-bridging.

5. Never install a damaged I-joist

-joists are not stable until completely installed, and will not carry any load until fully brace

I. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and

or cross-bridging at joist ends. When I-joists are applied continuous over interior supports

and a load-bearing wall is planned at that location, blocking will be required at the interior

2. When the building is completed, the floor sheathing will provide lateral support for the top

or temporary sheathing must be applied to prevent I-joist rollover or buckling. Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced

system. Then, stack building materials over beams or walls only.

flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts,

no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2-inch nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.

Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet

3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels

Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure

to use web stiffeners when required can result in serious accidents. Follow these installation

NI-90 2x4 2400f MSR 7/16 in. web

Width Length 1-1/8 in. 16 ft APA Rim Board Plus

RIM BOARDS

Do not walk on I-joist

Never stack building

braced or serious


until fully fastened an

#### WEB HOLES AND OPENINGS

#### WEB HOLES IN I-JOISTS

- Rules for Cutting Holes in I-Joists The distance between the inside edge of the support and the centreline of any hole shall be in compliance with the requirement of Table 6.1.

- A 1-1/2 inch hole or smaller can be placed anywhere in the web provide
- materials over unsheathed I-joists Once sheathed, do no overstress I-joist with



#### DUCT CHASE OPENINGS


6b

Rules for Cutting Duct Chase Openings in I-joists

- he distance between the inside edge of the support and the cu uct chase opening shall be in compliance with the requiremen
- I-joist top and bottom flanges must never be cut, notched or otherwise mo
- The maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the opening and the adjacent I-joist flange. Holes cut into the blocking panels are subject to the following limitations The top and bottom flanges of an I-joist blocking panel must never be cut,
- All openings shall be cut in accordance with the restrictions listed above and as illustrated in detail 6h


Allowable Hole Size in Lateral-restraint-only Blocking Panels

HOLES IN BLOCKING PANELS



I-joist or rim board blocking depth (in.)	Maximum allowable hole diameter (in.) <sup>(a)</sup>
9-1/2	6-1/4
11-7/8	7-3/4
14	9-1/4

# TABLE 6.1 - LOCATION OF WEB HOLES



I-joist depth (in.)	Maximum depth of the opening (in.)
9-1/2	6-1/4
11-7/8	8-5/8
14	10-3/4
16	12-3/4

# Minimum 1/8" space between top or bottom flange and openin

	imple or multiple span linimum distance from inside face of any support to centre of hole (ft-in.)															Simple spa Minimum di	
Joist Joist Round hole diameter (in.)													Joist				
depth	series						6-1/4			8-5/8		10	10-3/4		12	12-3/4	depth :
	NI-20	0'-7"	1'-6"	2'-10"	4'-3"	5'-8"	6'-0"	-	-	-	-	-	-	-	-	-	
9-1/2"	NI-40x	0'-7"	1'-6"	3'-0"	4'-4"	6'-0"	6'-4"	-	-	-	-	-	-	-	-	-	9-1/2"
9-1/2	NI-60	1'-3"	2'-6"	4'-0"	5'-4"	7'-0"	7'-5"	-	-	-	-	-	-	-	-	-	9-1/2
	NI-80	2'-3"	3'-6"	5'-0"	6'-6"	8'-2"	8'-8"	-	-	-	-	-	-	-	-	-	
	NI-20	0'-7"	0'-8"	1'-0"	2'-4"	3'-8"	4'-0"	5'-0"	6'-6"	7'-9"	-	-	-	-	-	-	
	NI-40x	0'-7"	0'-8"	1'-3"	2'-8"	4'-0"	4'-4"	5'-5"	7'-0"	8'-4"	-	-	-	-	-	-	
11-7/8"	NI-60	0'-7"	1'-8"	3'-0"	4'-3"	5'-9"	6'-0"	7'-3"	8'-10"	10'-0"	-	-	-	-	-	-	11-7/8"
	NI-80	1'-6"	2'-10"	4'-2"	5'-6"	7'-0"	7'-5"	8'-6"	10'-3"	11'-4"	-	-	-	-	-	-	
	NI-90	0'-7"	0'-8"	1'-5"	3'-2"	4"-10"	5'-4"	6'-9"	8'-9"	10'-2"	-	-	-	-	-	-	
	NI-40x	0'-7"	0"-8"	0'-8"	1'-0"	2'-4"	2'-9"	3'-9"	5'-2"	6'-0"	6'-6"	8'-3"	10'-2"	-	-	-	
	NI-60	0'-7"	0'-8"	1'-8"	3'-0"	4'-3"	4'-8"	5'-8"	7'-2"	8'-0"	8'-8"	10'-4"	11'-9"	-	-	-	

Design Criteria		
Joist spacing	Up to 24 inches	
Loads	Live load = 40 psf and dead load = 15 psf	
Deflection limits	L/480 under live load and L/240 under total load	


# TABLE 6.2 - LOCATION OF DUCT CHASE OPENINGS


aeptn	series	8	10	12	14	16	18	20	22	24
	NI-20	4'-1"	4'-5"	4'-10"	-	-	-	-	-	-
0.4/01	NI-40x	5'-3"	5'-8"	6'-0"	6'-5"	6'-10"	7'-3"	7'-8"	-	-
9-1/2"	NI-60	5'-4"	5'-9"	6'-2"	6'-7"	7'-1"	7'-5"	8'-0"	-	-
	NI-80	5'-3"	5'-8"	6'-0"	6'-5"	6'-10"	7'-3"	7'-8"	8'-2"	8'-6"
	NI-20	5'-9"	6'-2"	6'-6"	-	-	-	-	-	-
	NI-40x	6'-8"	7'-2"	7'-6"	8'-1"	8'-6"	9'-1"	9'-6"	-	-
11-7/8"	NI-60	7'-3"	7'-8"	8'-0"	8'-6"	9'-0"	9'-3"	9'-9"	-	-
	NI-80	7'-2"	7'-7"	8'-0"	8'-5"	8'-10"	9'-3"	9'-8"	10'-2"	10'-8
	NI-90	7'-6"	7'-11"	8'-4"	8'-9"	9'-2"	9'-7"	10'-1"	10'-7"	10'-1
	NI-40x	8'-1"	8'-7"	9'-0"	9'-6"	10'-1"	10'-7"	11'-2"	-	-
	NI-60	8'-9"	9'-3"	9'-8"	10'-11"	10'-6"	11'-1"	11'-6"	-	-
14"	NI-80	9'-0"	9'-3"	9'-9"	10'-1"	10'-7"	11'-1"	11'-6"	12'-1"	12'-€
	NI-90	9'-2"	9'-8"	10'-0"	10'-6"	10'-11"	11'-5"	11'-9"	12'-4"	12'-1
	NI-60	10'-3"	10'-8"	11'-2"	11'-6"	12'-1"	12'-6"	13'-2"	-	-
16"	NI-80	10'-4"	10'-9"	11'-3"	11'-9"	12'-1"	12'-7"	13'-1"	13'-8"	14'-4
	NI-90	10'-9"	11'-2"	11'-8"	12'-0"	12'-6"	13'-0"	13'-6"	14'-2"	14'-1
		D! 0								
		Design C	riteria							


#### RIM BOARDS 8a


8f

















#### -JOIST MARKING




For the latest version, consult nordic.ca or contact Nordic Structures.	

FOR ALL construction details  $\rightarrow$ DC3








connection. Leave a 1/8-inch to 1/4-inch gap between top of filler block and bottom of top

2 x 2x12

1s-1

use net joist depth minus 3-1/4 inches for joists with



1.) Filler block size (in.) Example

2-1/8 to 2-1/4 x 6 2x6 + 5/8" or 3/4" she

2-1/8 to 2-1/4 x 8 2x8 + 5/8" or 3/4" she

2-1/8 to 2-1/4 x 10 2x10 + 5/8" or 3/4" she 2-1/8 to 2-1/4 x 12 2x12 + 5/8" or 3/4" she 2 x 2x10



CITY:

**ROYAL PINE HOMES** 

2505

**SUMMER RIDGE ESTATES** 

**BRAMPTON** 

Job Name: 2505

**1ST FLR FRAMING** Level:

Label: B1 - i26463 Type: **Beam** 

2 Ply Member 1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL

Status: Design Passed

Designed by Single Member Design Engine in MiTek® Structure Version Illustration Not to Scale. Pitch: 0/12 Report Version: 2021.03.26 03/05/2024 14:40 8.6.3.353.Update16.11 16-01-08 16-09-06

#### **DESIGN INFORMATION**

NBCC 2015, Part9, BCBC 2018, **Building Code:** ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD Service Condition: Dry LL Deflection Limit: L/360 TL Deflection Limit: L/240,

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Bottom: 9'- 8"

#### Factored Resistance of Support Material:

- 615 psi Wall @ 0'- 2 1/2"
- 615 psi Wall @ 16'- 6"

PLY TO PLY CONNECTION: 4 ROWS OF 3.25" PNEUMATIC GUN NAILS (0.120"x3.25") @ 12" O/C

PLY TO PLY CONNECTION ASSUMES ANY SUPPORTED BEAM HANGERS ARE FASTENED TO THIS BEAM WITH MIN. 3.5" FASTENERS.



ANALYSIS RESULTS						
Design Criteria	Location	<b>Load Combination</b>	LDF	Design	Limit	Result
Factored Pos. Moment:	10'- 3/8"	1.25D + 1.5L + S	1.00	11531 lb ft	35345 lb ft	Passed - 33%
Factored Shear:	1'- 3 3/8"	1.25D + 1.5L	1.00	2838 lb	13815 lb	Passed - 21%
Live Load (LL) Pos. Defl.:	8'- 3 3/4"	L + 0.5S		0.242"	L/360	Passed - L/800
Total Load (TL) Pos. Defl.:	8'- 3 5/16"	D + L + 0.5S		0.405"	L/240	Passed - L/477

SUPPORT AND REACTION INFORMATION												
	ID	Input Bearing Length	Controlling Load Combination	LDF	Factored Downward Reaction	Factored Uplift Reaction	Factored Resistance of Member	Factored Resistance of Support	Result			
l	1	3-08	1.25D + 1.5L + S	1.00	3753 lb		12740 lb	7536 lb	Passed - 50%			
l	2	4-06	1.25D + 1.5L + S	1.00	2040 lb		15926 lb	9421 lb	Passed - 22%			

Ш	SPECIF	IED LOAL	08						
Ш	Туре	Start Loc	End Loc	Source	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)
	Self Weight	0'	16'- 9 3/8"	Self Weight	Тор	12 lb/ft	-	-	-
	Uniform	-0'	9'- 11 1/2"	FC1 Floor Decking (Plan View Fill)	Тор	5 lb/ft	11 lb/ft	-	-
Ш	Uniform	0'- 5 1/2"	4'- 10 1/2"	User Load	Top	60 lb/ft	-	-	-
Ш	Uniform	0'- 5 1/2"	4'- 1 1/2"	User Load	Top	80 lb/ft	160 lb/ft	-	-
	Uniform	9'- 11 1/2"	16'- 9 3/8"	FC1 Floor Decking (Plan View Fill)	Тор	13 lb/ft	27 lb/ft	-	-
Ш	Point	10'- 3/8"	10'- 3/8"	B3(i26458)	Back	443 lb	831 lb	-	-
Ш	Point	0'- 2 3/4"	0'- 2 3/4"	E29(i22520)	Тор	245 lb	141 lb	8 lb	-
Ш	Point	3'- 11 1/2"	3'- 11 1/2"	User Load	Тор	240 lb	480 lb	=	-

UNFAC	CTORED R	EACTIONS					
ID	Start Loc	End Loc	Source	Dead (D)	Live (L)	Snow (S)	Wind (W)
1	0'	0'- 3 1/2"	W36(i22497)	1251 lb	1476 lb	8 lb	-
2	16'- 5"	16'- 9 3/8"	W19(i20629)	580 lb	855 lb	-	-

#### **DESIGN NOTES**

- The dead loads used in the design of this member were applied to the structure as projected dead loads.
- · Lateral stability factor (KL) was based on user preference to use the width of all plies. (Consult with manufacturer for guideline pertaining to this design option.)
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.
- Bearing length at support 2 was calculated based on the actual bearing area divided by the supported member width and may not match expected value when bearing is not rectangular or when the supported member is not supported by its full

#### PLY TO PLY CONNECTION

Member design assumed proper ply to ply connection by others. Fastener spacing along length of member must not exceed 4 times depth of member. Verify connection between plies according to code specification and follow the manufacturer's installation instruction. Loads assumed to be distributed equally to each ply.



CITY:

ROYAL PINE HOMES
SUMMER RIDGE ESTATES

2505 BRAMPTON Job Name: **2505** 

Level: 1ST FLR FRAMING

Label: **B2 - i26464**Type: **Beam** 

2 Ply Member 1 3/4" x 11 7/8" (2.0E 3100)

WestFraser LVL


Status:

Design
Passed

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.6.3.353.Update16.11

Report Version: 2021.03.26 03/05/2024 14:40



#### DESIGN INFORMATION

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD
Service Condition: Dry
LL Deflection Limit: L/360,
TL Deflection Limit: L/240,

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Гор: 0' Bottom: 11'- 2"

#### Factored Resistance of Support Material:

- 615 psi Wall @ 0'- 2 1/2"
  615 psi Beam @ 12'- 2 3/4"
- PLY TO PLY CONNECTION:

4 ROWS OF 3.25" PNEUMATIC GUN NAILS (0.120"x3.25") @ 12" O/C

PLY TO PLY CONNECTION ASSUMES ANY SUPPORTED BEAM HANGERS ARE FASTENED TO THIS BEAM WITH MIN. 3.5" FASTENERS.

ROFESSIONAL CARE SIONAL CARE S
(3/05/24)
의 C. M. HEYENS 및
100505065
TOUNCE OF ONTARIO
NCE OF ON
STRUCTURAL COMPONENT ONLY

DWG # TF24030127

ANALYSIS RESULTS						
Design Criteria	Location	Load Combination	LDF	Design	Limit	Result
Factored Pos. Moment:	5'- 5 1/2"	1.25D + 1.5L	1.00	8093 lb ft	35262 lb ft	Passed - 23%
Factored Neg. Moment:	12'- 2 3/4"	1.25D + 1.5L + S	1.00	182 lb ft	28951 lb ft	Passed - 1%
Factored Shear:	11'- 1 7/8"	1.25D + 1.5L	1.00	3157 lb	13783 lb	Passed - 23%
Live Load (LL) Pos. Defl.:	6'	L + 0.5S		0.075"	L/360	Passed - L/999
Total Load (TL) Pos. Defl.:	6'- 5/8"	D + L + 0.5S		0.149"	L/240	Passed - L/956

	SUP	JPPORT AND REACTION INFORMATION										
	ID	Input Bearing Length	Controlling Load Combination	LDF	Factored Downward Reaction	Factored Uplift Reaction	Factored Resistance of Member	Factored Resistance of Support	Result			
	1	3-08	1.25D + 1.5L + S	1.00	2918 lb		12738 lb	7535 lb	Passed - 39%			
L	2	5-08	1.25D + 1.5L	1.00	4549 lb		19973 lb	11811 lb	Passed - 39%			

П	SPECIF	IED LOAD	S						
ı	Туре	Start Loc	End Loc	Source	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)
I	Self Weight	0'	12'- 7 1/4"	Self Weight	Тор	12 lb/ft	-	-	-
	Uniform	-0'	11'- 5 1/2"	FC1 Floor Decking (Plan View Fill)	Тор	6 lb/ft	12 lb/ft	-	-
ı	Uniform	0'- 3 1/2"	12'- 1 3/4"	User Load	Top	60 lb/ft	-	-	-
I	Uniform	1'- 11 1/2"	5'- 7 1/2"	User Load	Top	80 lb/ft	160 lb/ft	-	-
	Uniform	11'- 5 1/2"	12'- 4 1/2"	FC1 Floor Decking (Plan View Fill)	Тор	13 lb/ft	27 lb/ft	-	-
I	Point	11'- 6 3/8"	11'- 6 3/8"	B3(i26458)	Front	464 lb	852 lb	-	-
П	Point	0'- 2 3/4"	0'- 2 3/4"	E31(i22526)	Top	370 lb	107 lb	51 lb	-
	Point	5'- 5 1/2"	5'- 5 1/2"	User Load	Top	240 lb	480 lb	-	-
l	Point	12'- 4 1/2"	12'- 4 1/2"	6(i22535)	Тор	401 lb	490 lb	3 lb	-

Point	12'- 4 1/2"	12'- 4 1/2"	6(i22535)	Тор	401 lb	490 lb	3 lb	-
UNFAC	CTORED RI	EACTIONS						
ID	Start Loc	End Loc	Source		Dead (D)	Live (L)	Snow (S)	Wind (W)
1	0'	0'- 3 1/2"	W41(i22502)		1218 lb	928 lb	52 lb	-
2	12'- 1 3/4"	12'- 7 1/4"	STLBM(i22545	)	1495 lb	1755 lb	2 lb	-

#### **DESIGN NOTES**

- The dead loads used in the design of this member were applied to the structure as projected dead loads.
- Lateral stability factor (KL) was based on user preference to use the width of all plies. (Consult with manufacturer for guideline pertaining to this design option.)
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already
  specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if
  required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load
  transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.

#### PLY TO PLY CONNECTION

Member design assumed proper ply to ply connection by others. Fastener spacing along length of member must not exceed
4 times depth of member. Verify connection between plies according to code specification and follow the manufacturer's
installation instruction. Loads assumed to be distributed equally to each ply.



CITY:

**ROYAL PINE HOMES SUMMER RIDGE ESTATES** 

2505

**BRAMPTON** 

Job Name: 2505

**1ST FLR FRAMING** Level: Label: B3 - i26458

Type: **Beam** 

1 Ply Member 1 3/4" x 11 7/8" (2.0E 3100)


WestFraser LVL

Status: Design Passed

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.6.3.353.Update16.11

Report Version: 2021.03.26 03/05/2024 14:40



#### **DESIGN INFORMATION**

NBCC 2015, Part9, BCBC 2018, **Building Code:** ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD Service Condition: Dry LL Deflection Limit: L/360 TL Deflection Limit: L/240,

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Bottom: 1'- 1 1/2"

#### Factored Resistance of Support Material:

- 615 psi Beam @ 0'
- 615 psi Beam @ 6'- 10"

ANALYSIS RESULTS						
Design Criteria	Location	Load Combination	LDF	Design	Limit	Result
Factored Pos. Moment:	3'- 5 1/2"	1.25D + 1.5L + S	1.00	3285 lb ft	17672 lb ft	Passed - 19%
Factored Shear:	5'- 10 1/8"	1.25D + 1.5L + S	1.00	1281 lb	6908 lb	Passed - 19%
Live Load (LL) Pos. Defl.:	3'- 5 1/8"	L		0.026"	L/360	Passed - L/999
Total Load (TL) Pos. Defl.:	3'- 5 1/8"	D + L		0.041"	L/240	Passed - L/999

П	SUP	SUPPORT AND REACTION INFORMATION											
	ID	Input Bearing Length	Controlling Load Combination	LDF	Factored Downward Reaction	Factored Uplift Reaction	Factored Resistance of Member	Factored Resistance of Support	Result				
Ш	1	1-08	1.25D + 1.5L + S	1.00	1798 lb		2730 lb	-	Passed - 66%				
Ш	2	1-08	1.25D + 1.5L + S	1.00	1859 lb		2730 lb	-	Passed - 68%				

CONIN	COTOD	INICODI	MATION
CONN	ECIUR	INFOR	MATION

ID	Part No.	Manufacturer	Nailing Requirements			Other Information or Requirement for
טו	Fait No.	Manufacturer	Тор	Face	Member	Reinforcement Accessories
1	HUS1.81/10		-	-	-	Connector manually specified by the user.
2	HUS1.81/10		-	-	-	Connector manually specified by the user.

\* Connectors: Refer to manufacturer's specifications, fasteners requirements and installation instruction. Where header fasteners are longer than the width of the supporting member, install backer block or clinch header nails.

SPECIFIED LOADS												
Type	Start Loc	End Loc	Source	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)				
Self Weight	0'	6'- 10"	Self Weight	Тор	6 lb/ft	-	-	-				
Uniform	0'	3'- 4"	User Load	Top	60 lb/ft	120 lb/ft	-	-				
Uniform	3'- 4"	6'- 10"	User Load	Back	60 lb/ft	120 lb/ft	-	-				
Point	0'- 9 1/2"	0'- 9 1/2"	J6(i26481)	Front	76 lb	152 lb	-	-				
Point	2'- 1 1/2"	2'- 1 1/2"	J6(i26468)	Front	89 lb	178 lb	-	-				
Point	3'- 5 1/2"	3'- 5 1/2"	J6(i26462)	Front	86 lb	171 lb	-	-				
Point	4'- 8 1/4"	4'- 8 1/4"	J6(i26459)	Front	48 lb	95 lb	-	-				
Point	4'- 10 5/8"	4'- 10 5/8"	B4(i26471)	Front	82 lb	117 lb	-	-				
Point	6'- 1 1/2"	6'- 1 1/2"	J7(i26503)	Front	75 lb	150 lb	-	-				

UNFAC	CTORED RI	EACTIONS					
ID	Start Loc	End Loc	Source	Dead (D)	Live (L)	Snow (S)	Wind (W)
1	0'	0'	B1(i26463)	443 lb	831 lb	-	-
2	6'- 10"	6'- 10"	B2(i26464)	464 lb	852 lb	-	-

#### **DESIGN NOTES**

- The dead loads used in the design of this member were applied to the structure as projected dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.



DWG # TF24030128



CITY:

R: ROYAL PINE HOMES
SUMMER RIDGE ESTATES

L: 2505 BRAMPTON Job Name: **2505** 

Level: 1ST FLR FRAMING

Label: **B4 - i26471**Type: **Beam** 

1 Ply Member 1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL

Report Version: 2021.03.26

Status:

Design
Passed

03/05/2024 14:40

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.6.3.353.Update16.11

6-03-12

DESIGN INFORMATION
--------------------

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD
Service Condition: Dry
LL Deflection Limit: L/360,
TL Deflection Limit: L/240,

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Top: 0' Bottom: 5'- 10 1/2"

#### Factored Resistance of Support Material:

- 615 psi Beam @ 0'
- 615 psi Wall @ 6'- 4 3/4"

ANALTSIS RESULTS								
Design Criteria	Location	Load Combination	LDF	Design	Limit	Result		
Factored Pos. Moment:	4'- 1 1/16"	1.25D + 1.5L	1.00	572 lb ft	17672 lb ft	Passed - 3%		
Factored Shear:	5'- 3 7/8"	1.25D + 1.5L	1.00	963 lb	6908 lb	Passed - 14%		
SUDDODT AND DEACTION INFORMATION								

l	SUP	PORT AND	REACTION INFORM	NOITAN					
	ID	Input Bearing Length	Controlling Load Combination	LDF	Factored Downward Reaction	Factored Uplift Reaction	Factored Resistance of Member	Factored Resistance of Support	Result
l	1	1-08	1.25D + 1.5L	1.00	289 lb		2730 lb	-	Passed - 11%
l	2	4-06	1.25D + 1.5L	1.00	1027 lb		7963 lb	4710 lb	Passed - 22%

#### **CONNECTOR INFORMATION**

ID	Part No.	Manufacturer	Nalling Requirements			Other Information or Requirement for
טו	Fait No.		Тор	Face	Member	Reinforcement Accessories
1	HUS1.81/10		-	-	-	Connector manually specified by the user.

\* Connectors: Refer to manufacturer's specifications, fasteners requirements and installation instruction. Where header fasteners are longer than the width of the supporting member, install backer block or clinch header nails.

SPECIF	IED LOAD	S						
Туре	Start Loc	End Loc	Source	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)
Self Weight	0'	6'- 8 1/8"	Self Weight	Тор	6 lb/ft	-	-	-
Uniform	0'	6'- 8 1/8"	FC1 Floor Decking (Plan View Fill)	Тор	2 lb/ft	4 lb/ft	-	-
Uniform	0'	6'- 1/4"	FC1 Floor Decking (Plan View Fill)	Тор	12 lb/ft	25 lb/ft	-	-
Uniform	6'- 1/4"	6'- 8 1/8"	FC1 Floor Decking (Plan View Fill)	Тор	2 lb/ft	3 lb/ft	-	-
Point	5'- 11 3/8"	5'- 11 3/8"	B6(i26515)	Back	265 lb	365 lb	0 lb	-
UNFAC	TORED RE	EACTIONS	3					
ID	Start Loc	End Loc	Source		Dead (D)	Live (L)	Snow (S)	Wind (W)
1	0'	0'	B3(i26458)		82 lb	117 lb	-	-
2	6'- 3 3/4"	6'- 8 1/8"	W19(i20629)	1	313 lb	430 lb	-	-

#### DESIGN NOTES

- The dead loads used in the design of this member were applied to the structure as projected dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the
  default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already
  specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if
  required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.
- Bearing length at support 2 was calculated based on the actual bearing area divided by the supported member width and may not match expected value when bearing is not rectangular or when the supported member is not supported by its full width.





**ROYAL PINE HOMES SUMMER RIDGE ESTATES** 


> 2505 **BRAMPTON**

Job Name: 2505

Level: **1ST FLR FRAMING** Label: B5 - i26514

1 Ply Member 1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL

Status: Design Passed



#### **DESIGN INFORMATION**

NBCC 2015, Part9, BCBC 2018, **Building Code:** ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD Service Condition: Dry LL Deflection Limit: L/360 TL Deflection Limit: L/240,

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Bottom: 8'- 4"

#### Factored Resistance of Support Material:

- 615 psi Beam @ 0'- 4 1/2"
- 615 psi Wall @ 13'- 10 3/4"

ANALYSIS RESULTS						
Design Criteria	ign Criteria Location		LDF	Design	Limit	Result
Factored Pos. Moment:	5'- 4 7/8"	1.25D + 1.5L	0.93	5882 lb ft	16397 lb ft	Passed - 36%
Factored Neg. Moment:	0'- 4 1/2"	1.25D + 1.5L + S	0.93	29 lb ft	5386 lb ft	Passed - 1%
Factored Shear:	1'- 5 3/8"	1.25D + 1.5L	0.93	1349 lb	6409 lb	Passed - 21%
Live Load (LL) Pos. Defl.:	6'- 9 1/2"	L + 0.5S		0.113"	L/360	Passed - L/999
Total Load (TL) Pos. Defl.:	6'- 11 5/16"	D + L + 0.5S		0.279"	L/240	Passed - L/574
Permanent Deflection:	7'- 1/2"			-	L/360	Passed - L/996

Permane	int Dellection	. /-	- 1/2				-	L/360	Passeu - L/996
SUPPO	ORT AND R	EACTION	INFORM	ATION					
	Input Bearing Length	Controlling Combina	,	LDF	Factored Downward Reaction	d Uplift	Factored Resistance of Member	Factored Resistance of Support	Result
1	5-08	1.25D +	1.5L	0.93	1683 lb		9287 lb	5492 lb	Passed - 31%
2	3-08	1.25D + 1.	5S + L	0.80	1292 lb		5082 lb	3006 lb	Passed - 43%
SPECI	FIED LOAD	)S							
Type	Start Loc	End Loc	Sourc	e	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)
Self Weight	0'	14'- 1 1/4"	Self We	eight	Тор	6 lb/ft	-	-	-
Uniform	0'- 2 3/4"	5'- 5 3/4"	FC1 Floor (Plan Vie		Тор	27 lb/ft	53 lb/ft	-	-
Uniform	5'- 5 3/4"	14'- 1 1/4"	FC1 Floor (Plan Vie		Тор	13 lb/ft	26 lb/ft	-	-
Uniform	5'- 5 3/4"	13'- 9 3/4"	User L	oad	Тор	60 lb/ft	-	-	-
Point	5'- 4 7/8"	5'- 4 7/8"	B6(i26	515)	Front	373 lb	344 lb	-	-
Point	0'- 2 3/4"	0'- 2 3/4"	5(i225	34)	Тор	52 lb	80 lb	-	-
Point	13'- 10 1/2"	13'- 10 1/2"	E35(i22	517)	Тор	66 lb	24 lb	47 lb	-

ı	Point	13'- 10 1/2"	13'- 10 1/2"	E35(i22517)	Top 66 lb	24 lb	47 lb	-
l	UNFAC	CTORED RE	EACTIONS					
l	ID	Start Loc	End Loc	Source	Dead (D)	Live (L)	Snow (S)	Wind (W)
l	1	0'	0'- 5 1/2"	STLBM(i2254	5) 631 lb	591 lb	-	-
l	2	13'- 9 3/4"	14'- 1 1/4"	W7(i20617)	695 lb	360 lb	47 lb	-
ı	D=010							

- The dead loads used in the design of this member were applied to the structure as projected dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.



STRUCTURAL COMPONENT ONLY DWG # TF24030130



CITY:

**ROYAL PINE HOMES SUMMER RIDGE ESTATES** 

**BRAMPTON** 

2505

Job Name: 2505

**1ST FLR FRAMING** Level:

Label: B6 - i26515 Type: **Beam** 

1 Ply Member 1 3/4" x 11 7/8" (2.0E 3100)


WestFraser LVL

Status: Design Passed

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.6.3.353.Update16.11

Report Version: 2021.03.26 03/05/2024 14:40



#### **DESIGN INFORMATION**

NBCC 2015, Part9, BCBC 2018, **Building Code:** ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD Service Condition: Dry LL Deflection Limit: L/360. TL Deflection Limit: L/240,

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Bottom: 1'- 3 1/4"

#### Factored Resistance of Support Material:

- 615 psi Beam @ 0'
- 615 psi Beam @ 7'- 10 1/2"

ANALYSIS RESULTS						
Design Criteria	Location	Load Combination	LDF	Design	Limit	Result
Factored Pos. Moment:	3'- 10"	1.25D + 1.5L	1.00	2066 lb ft	17672 lb ft	Passed - 12%
Factored Shear:	6'- 10 5/8"	1.25D + 1.5L	1.00	899 lb	6908 lb	Passed - 13%
Live Load (LL) Pos. Defl.:	3'- 11 3/16"	L		0.019"	L/360	Passed - L/999
Total Load (TL) Pos. Defl.:	3'- 11 13/16"	D + L		0.035"	L/240	Passed - L/999

l	SUP	PORT AND	REACTION INFORM	IATION					
	ID	Input Bearing Length	Controlling Load Combination	LDF	Factored Downward Reaction	Factored Uplift Reaction	Factored Resistance of Member	Factored Resistance of Support	Result
l	1	1-08	1.25D + 1.5L	1.00	880 lb		2730 lb	-	Passed - 32%
l	2	1-08	1.25D + 1.5L	1.00	980 lb		2730 lb	-	Passed - 36%

CONIN	IECTOE	INIEO	RMATIO	м

ID	ID Part No. Manufacturer		Na	ailing Requireme	nts	Other Information or Requirement for
טו	Fait No.	Manuacturei	Тор	Face	Member	Reinforcement Accessories
1	HUS1.81/10		-	-	-	Connector manually specified by the user.
2	HUS1.81/10		-	-	-	Connector manually specified by the user.

\* Connectors: Refer to manufacturer's specifications, fasteners requirements and installation instruction. Where header fasteners are longer than the width of the supporting member, install backer block or clinch header nails.

Туре	Start Loc	End Loc	Source	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)
Self Weight	0'	7'- 10 1/2"	Self Weight	Тор	6 lb/ft	-	-	-
Uniform	3'- 10 1/2"	7'- 10 1/2"	User Load	Top	60 lb/ft	-	-	-
Tapered	3'- 2"	7'- 2"	Smoothed Load	Back	50 To 56 lb/ft	101 To 111 lb/ft	-	-
Point	1'- 2"	1'- 2"	J7(i26503)	Back	79 lb	158 lb	-	-
Point	2'- 6"	2'- 6"	J7(i26502)	Back	61 lb	128 lb	0 lb	-
UNFAC	TORED RI	EACTIONS						
ID	Start Loc	End Loc	Source		Dead (D)	Live (L)	Snow (S)	Wind (W)
1	0'	0'	B4(i26471)		265 lb	365 lb	-	-
2	7'- 10 1/2"	7'- 10 1/2"	B5(i26514)		373 lb	344 lb	-	-

#### **DESIGN NOTES**

**SPECIFIED LOADS** 

- The dead loads used in the design of this member were applied to the structure as projected dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.



DWG # TF24030131



CITY:

ROYAL PINE HOMES
SUMMER RIDGE ESTATES

2505 BRAMPTON Job Name: **2505** 

Level: 2ND FLR FRAMING
Label: B7 DR - i26444

Type: Beam

3 Ply Member 1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL Status:

Design
Passed

Illustration Not to Scale. Pitch: 0/12 Designed by Single Member Design Engine in MiTek® Structure Version Report Version: 2021.03.26 03/05/2024 14:40 8.6.3.353.Update 16.11

#### DESIGN INFORMATION

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD
Service Condition: Dry
LL Deflection Limit: L/360,
TL Deflection Limit: L/240,

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Top: 0'- 10 3/4" Bottom: 13'

#### Factored Resistance of Support Material:

- 812 psi Wall @ 0'- 2"
- 812 psi Wall @ 12'- 10"

#### PLY TO PLY CONNECTION:

4 ROWS OF 3.25" PNEUMATIC GUN NAILS (0.120"x3.25") @ 12" O/C

NAIL FROM BOTH FACES (STAGGER 1/2 SPACE)

PLY TO PLY CONNECTION ASSUMES ANY SUPPORTED BEAM HANGERS ARE FASTENED TO THIS BEAM WITH MIN. 3.5" FASTENERS.



ANALYSIS RESULT	ΓS							
Design Criteria	Location	Load Combination	LDF	Design	Limit	Result		
Factored Pos. Moment:	6'- 4 1/2"	1.25D + 1.5L	1.00	23154 lb ft	53017 lb ft	Passed - 44%		
Factored Shear:	1'- 2 7/8"	1.25D + 1.5L	1.00	6716 lb	20723 lb	Passed - 32%		
Live Load (LL) Pos. Def	i.: 6'- 5 13/16"	L		0.202"	L/360	Passed - L/741		
Total Load (TL) Pos. De	fl.: 6'- 5 13/16"	D + L		0.335"	L/240	Passed - L/447		
SUPPORT AND REACTION INFORMATION								

	Input Bearing Length	Controlling Combina	11)⊢	Factored Downwar Reaction	d Uplift	Factored Resistance of Member	Factored Resistance of Support	Result
1	3-00	1.25D + 1	1.5L 1.00	7388 lb		16380 lb	12789 lb	Passed - 58%
2	3-00	1.25D + 1	1.5L 1.00	7572 lb		16380 lb	12789 lb	Passed - 59%
SPECI	FIED LOAD	os						
Туре	Start Loc	End Loc	Source	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)
Self Weight	0'	13'	Self Weight	Тор	18 lb/ft	-	-	-
Uniform	0'	13'	User Load	Тор	60 lb/ft	-	-	-
Uniform	0'- 4 1/2"	5'- 8 1/2"	Smoothed Load	Тор	258 lb/ft	515 lb/ft	-	-
Uniform	6'- 10 1/2"	12'- 10 1/2"	Smoothed Load	Тор	258 lb/ft	515 lb/ft	-	-
Point	6'- 1/2"	6'- 1/2"	J4(i26353)	Тор	182 lb	363 lb	-	-
Point	6'- 4 1/2"	6'- 4 1/2"	J5(i26075)	Тор	123 lb	248 lb	-	-
UNFAC	CTORED R	EACTIONS						
ID	Start Loc	End Loc	Source		Dead (D)	Live (L)	Snow (S)	Wind (W)
1	0'	0'- 3"	5(i22534)		2096 lb	3174 lb	-	-

2142 lb

3268 lb

#### **DESIGN NOTES**

12'- 9"

· The dead loads used in the design of this member were applied to the structure as projected dead loads.

4(i22533)

- Lateral stability factor (KL) was based on user preference to use the width of all plies. (Consult with manufacturer for guideline pertaining to this design option.)
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the
  default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already
  specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if
  required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load
  transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.

#### PLY TO PLY CONNECTION

 Member design assumed proper ply to ply connection by others. Fastener spacing along length of member must not exceed 4 times depth of member. Verify connection between plies according to code specification and follow the manufacturer's installation instruction. Loads assumed to be distributed equally to each ply.



**ROYAL PINE HOMES SUMMER RIDGE ESTATES** 

2505 **BRAMPTON**  Job Name: 2505

Level: 2ND FLR FRAMING B8 - i26175

Label: Type: **Beam** 

1 Ply Member 1 3/4" x 11 7/8" (2.0E 3100)

WestFraser LVL

Design Passed

Status:

CITY: Designed by Single Member Design Engine in MiTek® Structure Version Illustration Not to Scale. Pitch: 0/12 Report Version: 2021.03.26 03/05/2024 14:40 8.6.3.353.Update16.11 2

> 11-08-04 12-06-02

#### **DESIGN INFORMATION**

NBCC 2015, Part9, BCBC 2018, **Building Code:** ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD Service Condition: Dry L/360 LL Deflection Limit: TL Deflection Limit: L/240,

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Bottom: 10'- 2"

#### Factored Resistance of Support Material:

- 615 psi Wall @ 0'- 3 3/8"
- 615 psi Wall @ 12'- 1 5/8"

ANALYSIS RESULTS							
Design Criteria	Location	Load Combination	LDF	Design	Limit	Result	
Factored Pos. Moment:	8'- 3 3/8"	1.25D + 1.5L	0.95	4253 lb ft	16787 lb ft	Passed - 25%	
Factored Shear:	11'- 3/4"	1.25D + 1.5L	0.95	2532 lb	6562 lb	Passed - 39%	
Live Load (LL) Pos. Defl.:	6'- 9 9/16"	L + 0.5S		0.071"	L/360	Passed - L/999	
Total Load (TL) Pos. Defl.:	6'- 6 3/8"	D + L + 0.5S		0.171"	L/240	Passed - L/819	
CLIDDODT AND DEAC	TION INFORM	IATION					

SUPF	SUPPORT AND REACTION INFORMATION									
ID	Input Bearing Length	Controlling Combina		Factored Downwar Reaction	rd Uplift	Factored Resistance of Member	Factored Resistance of Support	Result		
1 2	4-06 5-08	1.25D + 1.25D +		1178 lb 2629 lb		5176 lb 9509 lb	3062 lb 5625 lb	Passed - 38% Passed - 47%		
SPEC	IFIED LOAD	S								
Туре	Start Loc	End Loc	Source	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)		
Self Weight	0'	12'- 6 1/8"	Self Weight	Тор	6 lb/ft	-	-	-		
Uniform	n 0'	12'- 3 3/8"	FC2 Floor Decking (Plan View Fill)	Тор	9 lb/ft	18 lb/ft	-	-		
Uniform	n 0'	10'- 6 3/8"	FC2 Floor Decking (Plan View Fill)	Тор	2 lb/ft	3 lb/ft	-	-		
Uniform	n 0'	1'- 10 3/8"	E47(i22540)	Тор	145 lb/ft	-	70 lb/ft	-		
Uniform	0'- 4 3/8"	10'- 6 3/8"	User Load	Тор	60 lb/ft	-	-	-		
Uniform	10'- 6 3/8"	12'- 3 3/8"	FC2 Floor Decking (Plan View Fill)	Тор	8 lb/ft	16 lb/ft	-	-		
Point	10'- 7 1/4"	10'- 7 1/4"	B10(i26363)	Front	534 lb	1026 lb	-	-		
Point	0'- 1/4"	0'- 1/4"	E47(i22540)	Тор	14 lb	-	7 lb	-		
UNFA	CTORED R	EACTIONS	3							
ID	Start Loc	End Loc	Source		Dead (D)	Live (L)	Snow (S)	Wind (W)		
1	0'	0'- 4 3/8"	E31(i22526)	)	790 lb	271 lb	130 lb	-		
2	12'- 5/8"	12'- 6 1/8"	6(i22535)		852 lb	1033 lb	7 lb	-		

#### **DESIGN NOTES**

- The dead loads used in the design of this member were applied to the structure as projected dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.



STRUCTURAL COMPONENT ONLY DWG # TF24030133



CITY:

ROYAL PINE HOMES
SUMMER RIDGE ESTATES

2505 BRAMPTON Job Name: **2505** 

Level: 2ND FLR FRAMING

Label: **B9 - i26148** Type: **Beam** 

1 Ply Member 1 3/4" x 11 7/8" (2.0E 3100) WestFraser LVL Status:

Design
Passed

Illustration Not to Scale. Pitch: 0/12 Designed by Single Member Design Engine in MiTek® Structure Version 8.6.3.353.Update16.11

Peport Version: 2021.03.26 03/05/2024 14:40

11 2

15-11-08 15-08

#### DESIGN INFORMATION

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD
Service Condition: Dry
LL Deflection Limit: L/360,
TL Deflection Limit: L/240,

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Top: 0' Bottom: 8'- 8"

#### Factored Resistance of Support Material:

- 615 psi Wall @ 0'- 3 3/8"
- 615 psi Wall @ 16'- 4 7/8"

[	Design Criteria	Lo	cation	Load	Combinatio	n LDF	Design	Limit	Result
Factore	ed Pos. Momen	t: 9'-	1 1/4"	1.2	25D + 1.5L	0.98	8478 lb ft	17277 lb ft	Passed - 49%
Factore	ed Shear:	1'-	4 1/4"	1.2	25D + 1.5L	0.98	1369 lb	6753 lb	Passed - 20%
Live Lo	ad (LL) Pos. De	efl.: 8'- 6	6 7/16"		L		0.273"	L/360	Passed - L/701
Total Lo	oad (TL) Pos. D	efl.: 8'- 4	11/16"		D + L		0.532"	L/240	Passed - L/360
Permar	nent Deflection:	8'- 2	2 11/16"				-	L/360	Passed - L/762
SUPF	PORT AND R	EACTION	INFORMA	NOITA					
ID	Input Bearing Length	Controlling Combin		LDF	Factored Downward Reaction	Factored Uplift Reaction	Resistance		Result
1 2	4-06 5-08	1.25D + 1.25D +		0.98 0.98	1496 lb 1352 lb		7784 lb 9786 lb	4605 lb 5789 lb	Passed - 32% Passed - 23%
SPEC	IFIED LOAD	S							
Туре	Start Loc	End Loc	Source	)	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)
Self Weight	0'	16'- 9 3/8"	Self We	ight	Тор	6 lb/ft	-	-	-
Uniform	n 0'	9'- 3/8"	FC2 Floor D (Plan Viev		Тор	2 lb/ft	3 lb/ft	-	-

Weight	0'	16'- 9 3/8"	Self Weight	Тор	6 lb/ft	-	-	-
Jniform	0'	9'- 3/8"	FC2 Floor Decking (Plan View Fill)	Тор	2 lb/ft	3 lb/ft	-	-
Jniform	0'	1'- 4 7/8"	FC2 Floor Decking (Plan View Fill)	Тор	6 lb/ft	11 lb/ft	-	-
Jniform	0'- 4 3/8"	8'- 4 3/8"	User Load	Тор	60 lb/ft	-	-	-
Jniform	1'- 4 7/8"	16'- 6 5/8"	FC2 Floor Decking (Plan View Fill)	Тор	8 lb/ft	16 lb/ft	-	-
Jniform	9'- 3/8"	16'- 6 5/8"	FC2 Floor Decking (Plan View Fill)	Тор	2 lb/ft	4 lb/ft	-	-
Point	9'- 1 1/4"	9'- 1 1/4"	B10(i26363)	Back	357 lb	671 lb	-	-
JNFACT	ORED RE	ACTIONS						
ID	Start Loc	End Loc	Source		Dead (D)	Live (L)	Snow (S)	Wind (W)
1	0'	0'- 4 3/8"	E29(i22520)		649 lb	462 lb	-	-
	Jniform Jniform Jniform Jniform Jniform Point JNFACT	Weight  Jniform  0'  Jniform  0'- 4 3/8"  Jniform  1'- 4 7/8"  Jniform  9'- 3/8"  Point  9'- 1 1/4"  JNFACTORED RE  ID Start Loc	Weight 0' 16-9 3/8"  Jniform 0' 9'- 3/8"  Jniform 0' 1'- 4 7/8"  Jniform 0'- 4 3/8" 8'- 4 3/8"  Jniform 1'- 4 7/8" 16'- 6 5/8"  Jniform 9'- 3/8" 16'- 6 5/8"  Point 9'- 1 1/4" 9'- 1 1/4"  JNFACTORED REACTIONS  ID Start Loc End Loc	Weight         0"         16-9 3/8"         Self Weight           Jniform         0'         9'-3/8"         FC2 Floor Decking (Plan View Fill)           Jniform         0'         1'-47/8"         FC2 Floor Decking (Plan View Fill)           Jniform         0'-43/8"         8'-43/8"         User Load           Jniform         1'-47/8"         16'-65/8"         FC2 Floor Decking (Plan View Fill)           Jniform         9'-3/8"         16'-65/8"         FC2 Floor Decking (Plan View Fill)           Point         9'-11/4"         9'-11/4"         B10(i26363)           JNFACTORED REACTIONS           ID         Start Loc         End Loc         Source	Weight   U	Weight   O'   16'-9 3/8"   Self Weight   Iop   6 Ib/ft	Weight   O	Weight   U

#### **DESIGN NOTES**

**ANALYSIS RESULTS** 

- The dead loads used in the design of this member were applied to the structure as projected dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the
  default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already
  specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if
  required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.





CITY:

ROYAL PINE HOMES SUMMER RIDGE ESTATES

2505 BRAMPTON Job Name: **2505** 

Level: **2ND FLR FRAMING**Label: **B10 - i26363** 

Type: Beam

1 Ply Member 1 3/4" x 11 7/8" (2.0E 3100)

WestFraser LVL


Status:

Design
Passed

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.6.3.353.Update16.11

Report Version: 2021.03.26 03/05/2024 14:40



#### DESIGN INFORMATION

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)
Design Methodology: LSD

 $\begin{array}{lll} \mbox{Service Condition:} & \mbox{Dry} \\ \mbox{LL Deflection Limit:} & \mbox{L/360,} \\ \mbox{TL Deflection Limit:} & \mbox{L/240,} \\ \end{array}$ 

#### Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Top: 0' Bottom: 1'- 1 1/2"

#### Factored Resistance of Support Material:

- 615 psi Beam @ 0'
- 615 psi Beam @ 7'- 2"

ANALYSIS RESULTS						
Design Criteria	Location	Load Combination	LDF	Design	Limit	Result
Factored Pos. Moment:	4'- 1 1/2"	1.25D + 1.5L	1.00	3191 lb ft	17672 lb ft	Passed - 18%
Factored Shear:	0'- 11 7/8"	1.25D + 1.5L	1.00	1251 lb	6908 lb	Passed - 18%
Live Load (LL) Pos. Defl.:	3'- 8 5/16"	L		0.028"	L/360	Passed - L/999
Total Load (TL) Pos. Defl.:	3'- 8 5/16"	D + L		0.043"	L/240	Passed - L/999

l	SUP	SUPPORT AND REACTION INFORMATION										
	ID	Input Bearing Length	Controlling Load Combination	LDF	Factored Downward Reaction	Factored Uplift Reaction	Factored Resistance of Member	Factored Resistance of Support	Result			
П	1	1-08	1.25D + 1.5L	1.00	1450 lb		2730 lb	-	Passed - 53%			
П	2	1-08	1.25D + 1.5L	1.00	2210 lb		2730 lb	-	Passed - 81%			

CONIN	COTOD	INICODI	MATION
CONN	ECIUR	INFOR	MATION

ID	ID Part No. Manufacturer		Na	ailing Requireme	nts	Other Information or Requirement for
טו	Fait No.	Manuacturei	Тор	Face	Member	Reinforcement Accessories
1	HUS1.81/10		-	-	-	Connector manually specified by the user.
2	HUS1.81/10		-	-	-	Connector manually specified by the user.


\* Connectors: Refer to manufacturer's specifications, fasteners requirements and installation instruction. Where header fasteners are longer than the width of the supporting member, install backer block or clinch header nails.

SPECIF	IED LOAD	S						
Type	Start Loc	End Loc	Source	Face	Dead (D)	Live (L)	Snow (S)	Wind (W)
Self Weight	0'	7'- 2"	Self Weight	Тор	6 lb/ft	-	-	-
Uniform	0'- 7 1/2"	4'- 7 1/2"	Smoothed Load	Front	75 lb/ft	150 lb/ft	-	-
Uniform	3'- 6"	7'- 2"	User Load	Back	60 lb/ft	120 lb/ft	-	-
Point	0'- 1 1/2"	0'- 1 1/2"	J7(i25941)	Front	45 lb	90 lb	-	-
Point	5'- 1 1/2"	5'- 1 1/2"	J7(i26196)	Front	88 lb	175 lb	-	-
Point	6'- 5 1/2"	6'- 5 1/2"	J3(i26376)	Front	196 lb	392 lb	-	-
UNFAC	TORED R	EACTIONS						
ID	Start Loc	End Loc	Source		Dead (D)	Live (L)	Snow (S)	Wind (W)
1	0'	0'	B9(i26148)		357 lb	671 lb	-	-
2	7'- 2"	7'- 2"	B8(i26175)		534 lb	1026 lb	-	-

#### **DESIGN NOTES**

- The dead loads used in the design of this member were applied to the structure as projected dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the
  default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already
  specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if
  required) as per manufacturer's instruction.
- Beam Stability Factor used in the calculation for Allowable Max Pos Moment (KL) = 1.00
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load
  transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.





#### Notes:


- 1. To prevent interference with plumbing, a joist may be shifted up to 3 inches if the edge of the floor panel is supported and the span rating is not exceeded.
- 2. In all other cases, an additional joist is required.


All nails shown in the details are assumed to be common nails unless otherwise noted. Nails shall have a diameter not less than 0.128 inch for 2-1/2-inch nails, or 0.144 inch for 3-inch nails. Individual components not shown to scale for clarity.





Allowance for Piping		7c	
CATEGORY  Openings for Vertical Elements	SCALE	DATE 2020-10-01	PAGE 3.10
Openings for Vertical Elements	-	2020-10-01	3.10





#### Notes:

- 1. Blocking required at bearing for lateral support, not shown for clarity.
- 2. The maximum dimensions for a notch on the side of the top flange are 4-inch length by 1/2-inch depth for flange width of 2-1/2 inches, and 4-inch length by 1-inch depth for flange width of 3-1/2 inches.
- 3. This detail applies to simple-span joists and multiple-span joists where the notch is located at the end half-span.
- 4. For other applications, contact Nordic Structures.

All nails shown in the details are assumed to be common nails unless otherwise noted. Nails shall have a diameter not less than 0.128 inch for 2-1/2-inch nails, or 0.144 inch for 3-inch nails. Individual components not shown to scale for clarity.





TITLE		DRAWING		
Notch in I-joist for Heat Register		7d		
			_	
CATEGORY	SCALE	DATE	PAGE	
Openings for Vertical Elements	-	2020-10-01	3.11	



# Maximum Floor Spans - S2.1

#### Design Criteria

Spans: Simple span

Live load = 40 psf and dead load = 15 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 5/8 in. nailed-glued oriented strand board (OSB) sheathing

#### **Maximum Floor Spans**

			В	are			1/2 in. gyp	sum ceiling		
Joist depth	Joist series	On centre spacing				On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	15'-1"	14'-3"	13'-10"	-	15'-7"	14'-9"	14'-3"	-	
9-1/2"	NI-40x	16'-2"	15'-3"	14'-8"	-	16'-7"	15'-8"	15'-1"	-	
9-1/2	NI-60	16'-4"	15'-4"	14'-10"	-	16'-9"	15'-9"	15'-3"	-	
	NI-80	17'-3"	16'-3"	15'-8"	-	17'-8"	16'-7"	16'-0"	-	
	NI-20	17'-0"	16'-0"	15'-6"	-	17'-6"	16'-7"	16'-0"	-	
11-7/8"	NI-40x	18'-2"	17'-1"	16'-6"	-	18'-9"	17'-6"	16'-11"	-	
	NI-60	18'-5"	17'-3"	16'-8"	-	19'-0"	17'-8"	17'-1"	-	
	NI-80	19'-9"	18'-3"	17'-7"	-	20'-4"	18'-10"	18'-0"	-	
	NI-90	20'-2"	18'-8"	17'-10"	-	20'-9"	19'-2"	18'-4"	-	
	NI-40x	20'-1"	18'-8"	17'-10"	-	20'-10"	19'-4"	18'-6"	-	
14"	NI-60	20'-6"	18'-11"	18'-2"	-	21'-2"	19'-8"	18'-9"	-	
14	NI-80	21'-11"	20'-3"	19'-4"	-	22'-7"	20'-11"	20'-0"	-	
	NI-90	22'-5"	20'-8"	19'-9"	-	23'-0"	21'-4"	20'-4"	-	
	NI-60	22'-4"	20'-8"	19'-9"	-	23'-1"	21'-5"	20'-6"	-	
16"	NI-80	23'-11"	22'-1"	21'-1"	-	24'-8"	22'-10"	21'-9"	-	
	NI-90	24'-5"	22'-6"	21'-6"	-	25'-1"	23'-2"	22'-2"	-	

		Mi	d-span blocking	g with 1x4 inch s	trap	Mid-sp	an blocking an	d 1/2 in. gypsum	ceiling
Joist depth	Joist series		On cent	re spacing		On centre spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	16'-8"	15'-3"	14'-5"	-	16'-8"	15'-3"	14'-5"	-
0.4/0"	NI-40x	17'-11"	17'-0"	16'-1"	-	18'-5"	17'-1"	16'-1"	-
9-1/2"	NI-60	18'-2"	17'-1"	16'-4"	-	18'-8"	17'-4"	16'-4"	-
	NI-80	19'-5"	18'-0"	17'-5"	-	19'-10"	18'-5"	17'-8"	-
	NI-20	19'-7"	18'-2"	17'-3"	-	19'-11"	18'-3"	17'-3"	-
	NI-40x	21'-1"	19'-7"	18'-8"	-	21'-8"	20'-2"	19'-2"	-
11-7/8"	NI-60	21'-4"	19'-9"	18'-11"	-	21'-11"	20'-5"	19'-6"	-
	NI-80	22'-9"	21'-1"	20'-2"	-	23'-3"	21'-8"	20'-8"	-
	NI-90	23'-3"	21'-6"	20'-6"	-	23'-9"	22'-0"	21'-0"	-
	NI-40x	23'-8"	21'-11"	20'-11"	-	24'-4"	22'-8"	21'-8"	-
14"	NI-60	24'-0"	22'-3"	21'-3"	-	24'-8"	22'-11"	21'-11"	-
14	NI-80	25'-7"	23'-9"	22'-7"	-	26'-2"	24'-4"	23'-3"	-
	NI-90	26'-1"	24'-2"	23'-0"	-	26'-8"	24'-9"	23'-7"	-
	NI-60	26'-5"	24'-6"	23'-5"	-	27'-2"	25'-3"	24'-2"	-
16"	NI-80	28'-2"	26'-1"	24'-10"	-	28'-10"	26'-9"	25'-6"	-
	NI-90	28'-8"	26'-6"	25'-3"	-	29'-3"	27'-2"	25'-11"	-

- 1. The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



# Maximum Floor Spans - S4.1

#### Design Criteria

Spans: Simple span

Live load = 40 psf and dead load = 15 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 3/4 in. nailed-glued oriented strand board (OSB) sheathing

#### **Maximum Floor Spans**

			В	are			1/2 in. gy	osum ceiling	
Joist depth	Joist series		On cent	re spacing	On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	15'-11"	15'-0"	14'-6"	13'-5"	16'-5"	15'-5"	14'-6"	13'-5"
0.4/0"	NI-40x	17'-0"	16'-0"	15'-5"	14'-10"	17'-5"	16'-5"	15'-10"	15'-2"
9-1/2"	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-7"	16'-7"	16'-0"	15'-4"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
	NI-20	17'-11"	16'-11"	16'-3"	15'-8"	18'-7"	17'-5"	16'-10"	16'-2"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-7"	19'-11"	18'-6"	17'-9"	17'-0"
11-7/8"	NI-60	19'-7"	18'-2"	17'-6"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
	NI-80	21'-1"	19'-6"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
	NI-90	21'-6"	19'-10"	18'-11"	17'-11"	22'-0"	20'-4"	19'-5"	18'-4"
	NI-40x	21'-5"	19'-11"	18'-11"	18'-0"	22'-1"	20'-7"	19'-7"	18'-7"
14"	NI-60	21'-10"	20'-2"	19'-3"	18'-3"	22'-6"	20'-10"	19'-11"	18'-10
14	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
	NI-90	23'-10"	22'-1"	21'-0"	19'-10"	24'-5"	22'-7"	21'-6"	20'-4"
	NI-60	23'-9"	22'-0"	21'-0"	19'-10"	24'-6"	22'-9"	21'-8"	20'-7"
16"	NI-80	25'-6"	23'-7"	22'-5"	21'-2"	26'-2"	24'-3"	23'-1"	21'-10
	NI-90	26'-0"	24'-0"	22'-10"	21'-6"	26'-7"	24'-8"	23'-5"	22'-2"

		Mi	d-span blocking	with 1x4 inch	strap	Mid-sp	oan blocking an	d 1/2 in. gypsui	m ceiling
Joist depth	Joist series		On cent	re spacing		On centre spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"
9-1/2"	NI-40x	18'-8"	17'-2"	16'-3"	15'-2"	18'-10"	17'-2"	16'-3"	15'-2"
9-1/2	NI-60	18'-11"	17'-6"	16'-6"	15'-5"	19'-2"	17'-6"	16'-6"	15'-5"
	NI-80	20'-3"	18'-10"	17'-11"	16'-10"	20'-8"	19'-3"	18'-2"	16'-10'
	NI-20	20'-1"	18'-5"	17'-5"	16'-2"	20'-1"	18'-5"	17'-5"	16'-2"
	NI-40x	21'-10"	20'-4"	19'-4"	17'-8"	22'-5"	20'-6"	19'-4"	17'-8"
11-7/8"	NI-60	22'-1"	20'-7"	19'-8"	18'-4"	22'-8"	20'-10"	19'-8"	18'-4"
	NI-80	23'-8"	22'-0"	20'-11"	19'-10"	24'-1"	22'-6"	21'-6"	20'-0"
	NI-90	24'-1"	22'-5"	21'-4"	20'-2"	24'-7"	22'-11"	21'-10"	20'-7"
	NI-40x	24'-5"	22'-9"	21'-9"	19'-5"	25'-1"	23'-2"	21'-9"	19'-5"
14"	NI-60	24'-10"	23'-2"	22'-1"	20'-10"	25'-6"	23'-8"	22'-4"	20'-10'
14	NI-80	26'-6"	24'-8"	23'-6"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"
	NI-90	27'-0"	25'-1"	23'-11"	22'-7"	27'-6"	25'-8"	24'-6"	23'-2"
	NI-60	27'-3"	25'-5"	24'-3"	22'-11"	28'-0"	26'-2"	24'-9"	23'-1"
16"	NI-80	29'-1"	27'-1"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
	NI-90	29'-7"	27'-6"	26'-2"	24'-9"	30'-2"	28'-2"	26'-10"	25'-5"

- 1. The tabulated clear spans are based on CSA 086-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



# Maximum Floor Spans - S6.1

#### Design Criteria

Spans: Simple span

Loads: Live load = 40 psf and dead load = 15 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 5/8 in. nailed-glued Canadian softwood plywood

#### **Maximum Floor Spans**

			В	are			1/2 in. gyp	sum ceiling		
Joist depth	Joist series		On cent	re spacing		On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	14'-11"	14'-1"	13'-7"	-	15'-4"	14'-6"	14'-1"	-	
0.4/0"	NI-40x	15'-11"	15'-0"	14'-6"	-	16'-4"	15'-5"	14'-11"	-	
9-1/2"	NI-60	16'-1"	15'-2"	14'-8"	-	16'-6"	15'-7"	15'-1"	-	
	NI-80	17'-1"	16'-1"	15'-6"	-	17'-5"	16'-5"	15'-10"	-	
	NI-20	16'-9"	15'-10"	15'-4"	-	17'-4"	16'-4"	15'-10"	-	
	NI-40x	17'-10"	16'-10"	16'-3"	-	18'-6"	17'-4"	16'-9"	-	
11-7/8"	NI-60	18'-1"	17'-0"	16'-5"	-	18'-9"	17'-6"	16'-11"	-	
	NI-80	19'-6"	18'-0"	17'-4"	-	20'-1"	18'-7"	17'-9"	-	
	NI-90	19'-11"	18'-4"	17'-8"	-	20'-5"	18'-11"	18'-1"	-	
	NI-40x	19'-10"	18'-4"	17'-8"	-	20'-6"	19'-1"	18'-3"	-	
14"	NI-60	20'-2"	18'-8"	17'-11"	-	20'-10"	19'-4"	18'-6"	-	
14	NI-80	21'-8"	20'-0"	19'-1"	-	22'-4"	20'-8"	19'-9"	-	
	NI-90	22'-1"	20'-5"	19'-6"	-	22'-9"	21'-0"	20'-1"	-	
	NI-60	22'-0"	20'-4"	19'-6"	-	22'-9"	21'-1"	20'-2"	-	
16"	NI-80	23'-7"	21'-10"	20'-10"	-	24'-4"	22'-6"	21'-6"	-	
	NI-90	24'-1"	22'-2"	21'-2"	-	24'-9"	22'-11"	21'-10"	-	

	·	Mi	d-span blocking	with 1x4 inch st	trap	Mid-sp	an blocking an	d 1/2 in. gypsum	ceiling
Joist depth	Joist series		On cent	re spacing			On cent	re spacing	24"
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
	NI-20	16'-6"	15'-1"	14'-3"	-	16'-6"	15'-1"	14'-3"	-
0.4/0"	NI-40x	17'-9"	16'-10"	15'-11"	-	18'-2"	16'-11"	15'-11"	-
9-1/2"	NI-60	17'-11"	16'-11"	16'-2"	-	18'-5"	17'-2"	16'-2"	-
	NI-80	19'-3"	17'-10"	17'-3"	-	19'-8"	18'-3"	17'-7"	-
	NI-20	19'-4"	18'-0"	17'-1"	-	19'-9"	18'-1"	17'-1"	-
	NI-40x	20'-10"	19'-4"	18'-6"	-	21'-5"	19'-11"	19'-0"	-
11-7/8"	NI-60	21'-1"	19'-7"	18'-8"	-	21'-8"	20'-2"	19'-3"	-
	NI-80	22'-6"	20'-10"	19'-11"	-	23'-1"	21'-5"	20'-5"	-
	NI-90	23'-0"	21'-3"	20'-4"	-	23'-6"	21'-10"	20'-10"	-
	NI-40x	23'-5"	21'-8"	20'-9"	-	24'-0"	22'-5"	21'-5"	-
14"	NI-60	23'-9"	22'-0"	21'-0"	-	24'-5"	22'-8"	21'-8"	-
14	NI-80	25'-4"	23'-6"	22'-5"	-	25'-11"	24'-1"	23'-0"	-
	NI-90	25'-10"	23'-11"	22'-9"	-	26'-5"	24'-6"	23'-4"	-
	NI-60	26'-2"	24'-3"	23'-2"	-	26'-11"	25'-0"	23'-11"	-
16"	NI-80	27'-11"	25'-10"	24'-7"	-	28'-7"	26'-6"	25'-3"	-
	NI-90	28'-5"	26'-3"	25'-0"	-	29'-0"	26'-11"	25'-8"	-

- 1. The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



# Maximum Floor Spans - S7.1

#### Design Criteria

Spans: Simple span

 Loads:
 Live load = 40 psf and dead load = 15 psf

 Deflection limits:
 L/480 under live load and L/240 under total load

 Sheathing:
 3/4 in. nailed-glued Canadian softwood plywood

#### **Maximum Floor Spans**

			В	are			1/2 in. gy	sum ceiling		
Joist depth	Joist series		On cent	re spacing		On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"	
0.4/0"	NI-40x	16'-11"	15'-11"	15'-4"	14'-9"	17'-4"	16'-4"	15'-9"	15'-1"	
9-1/2"	NI-60	17'-1"	16'-1"	15'-6"	14'-10"	17'-6"	16'-6"	15'-11"	15'-3"	
	NI-80	18'-1"	17'-0"	16'-4"	15'-8"	18'-7"	17'-4"	16'-8"	16'-0"	
	NI-20	17'-10"	16'-10"	16'-2"	15'-7"	18'-5"	17'-4"	16'-9"	16'-1"	
	NI-40x	19'-3"	17'-10"	17'-2"	16'-6"	19'-10"	18'-5"	17'-8"	16'-11	
11-7/8"	NI-60	19'-6"	18'-1"	17'-4"	16'-8"	20'-1"	18'-8"	17'-10"	17'-1"	
	NI-80	20'-11"	19'-4"	18'-5"	17'-7"	21'-5"	19'-10"	18'-11"	17'-11	
	NI-90	21'-4"	19'-9"	18'-9"	17'-10"	21'-10"	20'-3"	19'-3"	18'-3"	
	NI-40x	21'-4"	19'-9"	18'-10"	17'-11"	22'-0"	20'-5"	19'-6"	18'-6"	
14"	NI-60	21'-8"	20'-1"	19'-2"	18'-2"	22'-4"	20'-9"	19'-9"	18'-9"	
14	NI-80	23'-3"	21'-6"	20'-5"	19'-4"	23'-10"	22'-1"	21'-0"	19'-11	
	NI-90	23'-9"	21'-11"	20'-10"	19'-8"	24'-3"	22'-6"	21'-5"	20'-3"	
	NI-60	23'-7"	21'-10"	20'-10"	19'-9"	24'-4"	22'-7"	21'-7"	20'-5"	
16"	NI-80	25'-4"	23'-5"	22'-3"	21'-1"	26'-0"	24'-1"	22'-11"	21'-8"	
	NI-90	25'-10"	23'-10"	22'-8"	21'-5"	26'-5"	24'-6"	23'-4"	22'-0"	

		Mi	d-span blocking	with 1x4 inch	strap	Mid-sp	an blocking an	d 1/2 in. gypsu	ım ceiling	
Joist depth	Joist series		On cent	re spacing		On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"	
9-1/2"	NI-40x	18'-7"	17'-2"	16'-3"	15'-2"	18'-10"	17'-2"	16'-3"	15'-2"	
9-1/2	NI-60	18'-10"	17'-6"	16'-6"	15'-5"	19'-1"	17'-6"	16'-6"	15'-5"	
	NI-80	20'-2"	18'-9"	17'-11"	16'-10"	20'-7"	19'-2"	18'-2"	16'-10'	
	NI-20	20'-1"	18'-5"	17'-5"	16'-2"	20'-1"	18'-5"	17'-5"	16'-2"	
	NI-40x	21'-9"	20'-3"	19'-4"	17'-8"	22'-4"	20'-5"	19'-4"	17'-8"	
11-7/8"	NI-60	22'-0"	20'-6"	19'-7"	18'-4"	22'-7"	20'-10"	19'-8"	18'-4"	
	NI-80	23'-6"	21'-10"	20'-10"	19'-9"	24'-0"	22'-5"	21'-4"	20'-0"	
	NI-90	24'-0"	22'-4"	21'-3"	20'-1"	24'-6"	22'-10"	21'-9"	20'-7"	
	NI-40x	24'-4"	22'-8"	21'-8"	19'-5"	25'-0"	23'-2"	21'-9"	19'-5"	
14"	NI-60	24'-9"	23'-0"	22'-0"	20'-9"	25'-5"	23'-8"	22'-4"	20'-10'	
14	NI-80	26'-5"	24'-6"	23'-4"	22'-1"	27'-0"	25'-2"	24'-0"	22'-8"	
	NI-90	26'-11"	25'-0"	23'-10"	22'-6"	27'-5"	25'-7"	24'-5"	23'-1"	
	NI-60	27'-2"	25'-4"	24'-2"	22'-10"	27'-11"	26'-1"	24'-9"	23'-1"	
16"	NI-80	29'-0"	26'-11"	25'-8"	24'-3"	29'-7"	27'-7"	26'-4"	24'-11'	
	NI-90	29'-6"	27'-5"	26'-1"	24'-8"	30'-1"	28'-1"	26'-9"	25'-4"	

- 1. The tabulated clear spans are based on CSA 086-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



# Maximum Floor Spans - M2.1

#### Design Criteria

Spans: Simple span

Live load = 40 psf and dead load = 20 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 5/8 in. nailed-glued oriented strand board (OSB) sheathing

#### **Maximum Floor Spans**

			В	are			1/2 in. gyp	sum ceiling		
Joist depth	Joist series		On cent	re spacing		On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	15'-1"	14'-3"	13'-10"	-	15'-7"	14'-9"	14'-3"	-	
0.4/0"	NI-40x	16'-2"	15'-3"	14'-8"	-	16'-7"	15'-8"	15'-1"	-	
9-1/2"	NI-60	16'-4"	15'-4"	14'-10"	-	16'-9"	15'-9"	15'-3"	-	
	NI-80	17'-3"	16'-3"	15'-8"	-	17'-8"	16'-7"	16'-0"	-	
	NI-20	17'-0"	16'-0"	15'-6"	-	17'-6"	16'-7"	16'-0"	-	
	NI-40x	18'-2"	17'-1"	16'-6"	-	18'-9"	17'-6"	16'-11"	-	
11-7/8"	NI-60	18'-5"	17'-3"	16'-8"	-	19'-0"	17'-8"	17'-1"	-	
	NI-80	19'-9"	18'-3"	17'-7"	-	20'-4"	18'-10"	18'-0"	-	
	NI-90	20'-2"	18'-8"	17'-10"	-	20'-9"	19'-2"	18'-4"	-	
	NI-40x	20'-1"	18'-8"	17'-10"	-	20'-10"	19'-4"	18'-6"	-	
14"	NI-60	20'-6"	18'-11"	18'-2"	-	21'-2"	19'-8"	18'-9"	-	
14	NI-80	21'-11"	20'-3"	19'-4"	-	22'-7"	20'-11"	20'-0"	-	
	NI-90	22'-5"	20'-8"	19'-9"	-	23'-0"	21'-4"	20'-4"	-	
	NI-60	22'-4"	20'-8"	19'-9"	-	23'-1"	21'-5"	20'-6"	-	
16"	NI-80	23'-11"	22'-1"	21'-1"	-	24'-8"	22'-10"	21'-9"	-	
	NI-90	24'-5"	22'-6"	21'-6"	-	25'-1"	23'-2"	22'-2"	-	

Joist depth		Mid-span blocking with 1x4 inch strap On centre spacing				Mid-span blocking and 1/2 in. gypsum ceiling On centre spacing				
	Joist series									
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	16'-8"	15'-3"	14'-5"	-	16'-8"	15'-3"	14'-5"	-	
0.4/0"	NI-40x	17'-11"	17'-0"	16'-1"	-	18'-5"	17'-1"	16'-1"	-	
9-1/2"	NI-60	18'-2"	17'-1"	16'-4"	-	18'-8"	17'-4"	16'-4"	-	
	NI-80	19'-5"	18'-0"	17'-5"	-	19'-10"	18'-5"	17'-8"	-	
	NI-20	19'-7"	18'-2"	17'-3"	-	19'-11"	18'-3"	17'-3"	-	
	NI-40x	21'-1"	19'-7"	18'-8"	-	21'-8"	20'-2"	19'-0"	-	
11-7/8"	NI-60	21'-4"	19'-9"	18'-11"	-	21'-11"	20'-5"	19'-6"	-	
	NI-80	22'-9"	21'-1"	20'-2"	-	23'-3"	21'-8"	20'-8"	-	
	NI-90	23'-3"	21'-6"	20'-6"	-	23'-9"	22'-0"	21'-0"	-	
	NI-40x	23'-8"	21'-11"	20'-11"	-	24'-4"	22'-8"	20'-11"	-	
14"	NI-60	24'-0"	22'-3"	21'-3"	-	24'-8"	22'-11"	21'-11"	-	
14	NI-80	25'-7"	23'-9"	22'-7"	-	26'-2"	24'-4"	23'-3"	-	
	NI-90	26'-1"	24'-2"	23'-0"	-	26'-8"	24'-9"	23'-7"	-	
16"	NI-60	26'-5"	24'-6"	23'-5"	-	27'-2"	25'-3"	24'-2"	-	
	NI-80	28'-2"	26'-1"	24'-10"	-	28'-10"	26'-9"	25'-6"	-	
	NI-90	28'-8"	26'-6"	25'-3"	-	29'-3"	27'-2"	25'-11"	_	

- 1. The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



# Maximum Floor Spans - M4.1

#### Design Criteria

Spans: Simple span

Live load = 40 psf and dead load = 20 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 3/4 in. nailed-glued oriented strand board (OSB) sheathing

#### **Maximum Floor Spans**

			В	are		1/2 in. gypsum ceiling					
Joist depth	Joist series	On centre spacing				On centre spacing					
		12"	16"	19.2"	24"	12"	16"	19.2"	24"		
	NI-20	15'-11"	15'-0"	14'-6"	13'-5"	16'-5"	15'-5"	14'-6"	13'-5"		
0.4/0"	NI-40x	17'-0"	16'-0"	15'-5"	14'-10"	17'-5"	16'-5"	15'-10"	14'-11'		
9-1/2"	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-7"	16'-7"	16'-0"	15'-4"		
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"		
	NI-20	17'-11"	16'-11"	16'-3"	15'-8"	18'-7"	17'-5"	16'-10"	16'-1"		
	NI-40x	19'-4"	17'-11"	17'-3"	16'-7"	19'-11"	18'-6"	17'-9"	17'-0"		
11-7/8"	NI-60	19'-7"	18'-2"	17'-6"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"		
	NI-80	21'-1"	19'-6"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"		
	NI-90	21'-6"	19'-10"	18'-11"	17'-11"	22'-0"	20'-4"	19'-5"	18'-4"		
	NI-40x	21'-5"	19'-11"	18'-11"	18'-0"	22'-1"	20'-7"	19'-7"	18'-7"		
4.4"	NI-60	21'-10"	20'-2"	19'-3"	18'-3"	22'-6"	20'-10"	19'-11"	18'-10'		
14"	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"		
	NI-90	23'-10"	22'-1"	21'-0"	19'-10"	24'-5"	22'-7"	21'-6"	20'-4"		
16"	NI-60	23'-9"	22'-0"	21'-0"	19'-10"	24'-6"	22'-9"	21'-8"	20'-7"		
	NI-80	25'-6"	23'-7"	22'-5"	21'-2"	26'-2"	24'-3"	23'-1"	21'-10'		
	NI-90	26'-0"	24'-0"	22'-10"	21'-6"	26'-7"	24'-8"	23'-5"	22'-2"		

		Mi	d-span blocking	with 1x4 inch	strap	Mid-span blocking and 1/2 in. gypsum ceiling				
Joist depth	Joist series	On centre spacing				On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"	
0.4/0!!	NI-40x	18'-8"	17'-2"	16'-3"	14'-11"	18'-10"	17'-2"	16'-3"	14'-11'	
9-1/2"	NI-60	18'-11"	17'-6"	16'-6"	15'-5"	19'-2"	17'-6"	16'-6"	15'-5"	
	NI-80	20'-3"	18'-10"	17'-11"	16'-10"	20'-8"	19'-3"	18'-2"	16'-10'	
	NI-20	20'-1"	18'-5"	17'-5"	16'-1"	20'-1"	18'-5"	17'-5"	16'-1"	
	NI-40x	21'-10"	20'-4"	19'-0"	17'-0"	22'-5"	20'-6"	19'-0"	17'-0"	
11-7/8"	NI-60	22'-1"	20'-7"	19'-8"	18'-4"	22'-8"	20'-10"	19'-8"	18'-4"	
	NI-80	23'-8"	22'-0"	20'-11"	19'-10"	24'-1"	22'-6"	21'-6"	20'-0"	
	NI-90	24'-1"	22'-5"	21'-4"	20'-2"	24'-7"	22'-11"	21'-10"	20'-7"	
	NI-40x	24'-5"	22'-9"	20'-11"	18'-8"	25'-1"	22'-11"	20'-11"	18'-8"	
1.4"	NI-60	24'-10"	23'-2"	22'-1"	20'-10"	25'-6"	23'-8"	22'-4"	20'-10'	
14"	NI-80	26'-6"	24'-8"	23'-6"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"	
	NI-90	27'-0"	25'-1"	23'-11"	22'-7"	27'-6"	25'-8"	24'-6"	23'-2"	
16"	NI-60	27'-3"	25'-5"	24'-3"	22'-11"	28'-0"	26'-2"	24'-9"	23'-1"	
	NI-80	29'-1"	27'-1"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"	
	NI-90	29'-7"	27'-6"	26'-2"	24'-9"	30'-2"	28'-2"	26'-10"	25'-5"	

- 1. The tabulated clear spans are based on CSA 086-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



# Maximum Floor Spans - M6.1

#### Design Criteria

Spans: Simple span

Loads: Live load = 40 psf and dead load = 20 psf
Deflection limits: L/480 under live load and L/240 under total load
Sheathing: 5/8 in. nailed-glued Canadian softwood plywood

#### **Maximum Floor Spans**

			В	are		1/2 in. gypsum ceiling				
Joist depth	Joist series	On centre spacing				On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	14'-11"	14'-1"	13'-7"	-	15'-4"	14'-6"	14'-1"	-	
9-1/2"	NI-40x	15'-11"	15'-0"	14'-6"	-	16'-4"	15'-5"	14'-11"	-	
9-1/2	NI-60	16'-1"	15'-2"	14'-8"	-	16'-6"	15'-7"	15'-1"	-	
	NI-80	17'-1"	16'-1"	15'-6"	-	17'-5"	16'-5"	15'-10"	-	
	NI-20	16'-9"	15'-10"	15'-4"	-	17'-4"	16'-4"	15'-10"	-	
	NI-40x	17'-10"	16'-10"	16'-3"	-	18'-6"	17'-4"	16'-9"	-	
11-7/8"	NI-60	18'-1"	17'-0"	16'-5"	-	18'-9"	17'-6"	16'-11"	-	
	NI-80	19'-6"	18'-0"	17'-4"	-	20'-1"	18'-7"	17'-9"	-	
	NI-90	19'-11"	18'-4"	17'-8"	-	20'-5"	18'-11"	18'-1"	-	
	NI-40x	19'-10"	18'-4"	17'-8"	-	20'-6"	19'-1"	18'-3"	-	
14"	NI-60	20'-2"	18'-8"	17'-11"	-	20'-10"	19'-4"	18'-6"	-	
14"	NI-80	21'-8"	20'-0"	19'-1"	-	22'-4"	20'-8"	19'-9"	-	
	NI-90	22'-1"	20'-5"	19'-6"	-	22'-9"	21'-0"	20'-1"	-	
16"	NI-60	22'-0"	20'-4"	19'-6"	-	22'-9"	21'-1"	20'-2"	-	
	NI-80	23'-7"	21'-10"	20'-10"	-	24'-4"	22'-6"	21'-6"	-	
	NI-90	24'-1"	22'-2"	21'-2"	-	24'-9"	22'-11"	21'-10"	-	

Joist depth		Mid-span blocking with 1x4 inch strap On centre spacing				Mid-span blocking and 1/2 in. gypsum ceiling On centre spacing				
	Joist series									
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	16'-6"	15'-1"	14'-3"	-	16'-6"	15'-1"	14'-3"	-	
0.4/0"	NI-40x	17'-9"	16'-10"	15'-11"	-	18'-2"	16'-11"	15'-11"	-	
9-1/2"	NI-60	17'-11"	16'-11"	16'-2"	-	18'-5"	17'-2"	16'-2"	-	
	NI-80	19'-3"	17'-10"	17'-3"	-	19'-8"	18'-3"	17'-7"	-	
	NI-20	19'-4"	18'-0"	17'-1"	-	19'-9"	18'-1"	17'-1"	-	
	NI-40x	20'-10"	19'-4"	18'-6"	-	21'-5"	19'-11"	19'-0"	-	
11-7/8"	NI-60	21'-1"	19'-7"	18'-8"	-	21'-8"	20'-2"	19'-3"	-	
	NI-80	22'-6"	20'-10"	19'-11"	-	23'-1"	21'-5"	20'-5"	-	
	NI-90	23'-0"	21'-3"	20'-4"	-	23'-6"	21'-10"	20'-10"	-	
	NI-40x	23'-5"	21'-8"	20'-9"	-	24'-0"	22'-5"	20'-11"	-	
14"	NI-60	23'-9"	22'-0"	21'-0"	-	24'-5"	22'-8"	21'-8"	-	
14"	NI-80	25'-4"	23'-6"	22'-5"	-	25'-11"	24'-1"	23'-0"	-	
	NI-90	25'-10"	23'-11"	22'-9"	-	26'-5"	24'-6"	23'-4"	-	
16"	NI-60	26'-2"	24'-3"	23'-2"	-	26'-11"	25'-0"	23'-11"	-	
	NI-80	27'-11"	25'-10"	24'-7"	-	28'-7"	26'-6"	25'-3"	-	
	NI-90	28'-5"	26'-3"	25'-0"	_	29'-0"	26'-11"	25'-8"	_	

- 1. The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



# Maximum Floor Spans - M7.1

#### Design Criteria

Spans: Simple span

Loads: Live load = 40 psf and dead load = 20 psf
Deflection limits: L/480 under live load and L/240 under total load
Sheathing: 3/4 in. nailed-glued Canadian softwood plywood

#### **Maximum Floor Spans**

			В	are		1/2 in. gypsum ceiling				
Joist depth	Joist series	On centre spacing				On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"	
0.4/0"	NI-40x	16'-11"	15'-11"	15'-4"	14'-9"	17'-4"	16'-4"	15'-9"	14'-11'	
9-1/2"	NI-60	17'-1"	16'-1"	15'-6"	14'-10"	17'-6"	16'-6"	15'-11"	15'-3"	
	NI-80	18'-1"	17'-0"	16'-4"	15'-8"	18'-7"	17'-4"	16'-8"	16'-0"	
	NI-20	17'-10"	16'-10"	16'-2"	15'-7"	18'-5"	17'-4"	16'-9"	16'-1"	
	NI-40x	19'-3"	17'-10"	17'-2"	16'-6"	19'-10"	18'-5"	17'-8"	16'-11'	
11-7/8"	NI-60	19'-6"	18'-1"	17'-4"	16'-8"	20'-1"	18'-8"	17'-10"	17'-1"	
	NI-80	20'-11"	19'-4"	18'-5"	17'-7"	21'-5"	19'-10"	18'-11"	17'-11'	
	NI-90	21'-4"	19'-9"	18'-9"	17'-10"	21'-10"	20'-3"	19'-3"	18'-3"	
	NI-40x	21'-4"	19'-9"	18'-10"	17'-11"	22'-0"	20'-5"	19'-6"	18'-6"	
14"	NI-60	21'-8"	20'-1"	19'-2"	18'-2"	22'-4"	20'-9"	19'-9"	18'-9"	
14"	NI-80	23'-3"	21'-6"	20'-5"	19'-4"	23'-10"	22'-1"	21'-0"	19'-11'	
	NI-90	23'-9"	21'-11"	20'-10"	19'-8"	24'-3"	22'-6"	21'-5"	20'-3"	
16"	NI-60	23'-7"	21'-10"	20'-10"	19'-9"	24'-4"	22'-7"	21'-7"	20'-5"	
	NI-80	25'-4"	23'-5"	22'-3"	21'-1"	26'-0"	24'-1"	22'-11"	21'-8"	
	NI-90	25'-10"	23'-10"	22'-8"	21'-5"	26'-5"	24'-6"	23'-4"	22'-0"	

		Mi	d-span blocking	with 1x4 inch	strap	Mid-span blocking and 1/2 in. gypsum ceiling				
Joist depth	Joist series	On centre spacing				On centre spacing				
		12"	16"	19.2"	24"	12"	16"	19.2"	24"	
	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"	
9-1/2"	NI-40x	18'-7"	17'-2"	16'-3"	14'-11"	18'-10"	17'-2"	16'-3"	14'-11'	
9-1/2	NI-60	18'-10"	17'-6"	16'-6"	15'-5"	19'-1"	17'-6"	16'-6"	15'-5"	
	NI-80	20'-2"	18'-9"	17'-11"	16'-10"	20'-7"	19'-2"	18'-2"	16'-10'	
	NI-20	20'-1"	18'-5"	17'-5"	16'-1"	20'-1"	18'-5"	17'-5"	16'-1"	
	NI-40x	21'-9"	20'-3"	19'-0"	17'-0"	22'-4"	20'-5"	19'-0"	17'-0"	
11-7/8"	NI-60	22'-0"	20'-6"	19'-7"	18'-4"	22'-7"	20'-10"	19'-8"	18'-4"	
	NI-80	23'-6"	21'-10"	20'-10"	19'-9"	24'-0"	22'-5"	21'-4"	20'-0"	
	NI-90	24'-0"	22'-4"	21'-3"	20'-1"	24'-6"	22'-10"	21'-9"	20'-7"	
	NI-40x	24'-4"	22'-8"	20'-11"	18'-8"	25'-0"	22'-11"	20'-11"	18'-8"	
4.4"	NI-60	24'-9"	23'-0"	22'-0"	20'-9"	25'-5"	23'-8"	22'-4"	20'-10'	
14"	NI-80	26'-5"	24'-6"	23'-4"	22'-1"	27'-0"	25'-2"	24'-0"	22'-8"	
	NI-90	26'-11"	25'-0"	23'-10"	22'-6"	27'-5"	25'-7"	24'-5"	23'-1"	
16"	NI-60	27'-2"	25'-4"	24'-2"	22'-10"	27'-11"	26'-1"	24'-9"	23'-1"	
	NI-80	29'-0"	26'-11"	25'-8"	24'-3"	29'-7"	27'-7"	26'-4"	24'-11'	
	NI-90	29'-6"	27'-5"	26'-1"	24'-8"	30'-1"	28'-1"	26'-9"	25'-4"	

- 1. The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.