


Schedule 1: Designer Information

Use one form for each individual who reviews and takes responsibility for design activities with respect to the project.

A. Project Information			
Building number, street name		Unit no.	Lot/con.
Municipality BRAMPTON	Postal code	Plan number/ other description	
B. Individual who reviews and takes responsibility for design activities			
Name MICHAEL O'ROURKE		Firm HVAC DESIGNS LTD.	
Street address 375 FINLEY AVE		Unit no. 202	Lot/con. N/A
Municipality AJAX	Postal code L1S 2E2	Province ONTARIO	E-mail info@hvacdesigns.ca
Telephone number (905) 619-2300	Fax number (905) 619-2375	Cell number ()	
C. Design activities undertaken by individual identified in Section B. [Building Code Table 3.5.2.1 OF Division C]			
<input type="checkbox"/> House <input type="checkbox"/> Small Buildings <input type="checkbox"/> Large Buildings <input type="checkbox"/> Complex Buildings <input checked="" type="checkbox"/> HVAC – House <input type="checkbox"/> Building Services <input type="checkbox"/> Detection, Lighting and Power <input type="checkbox"/> Fire Protection <input type="checkbox"/> Building Structural <input type="checkbox"/> Plumbing – House <input type="checkbox"/> Plumbing – All Buildings <input type="checkbox"/> On-site Sewage Systems			
Description of designer's work HEAT LOSS / GAIN CALCULATIONS DUCT SIZING RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY RESIDENTIAL SYSTEM DESIGN per CSA-F280-12		Model: 2503 Project: SUMMER RIDGE ESTATES INC.	
D. Declaration of Designer			
I, <u>MICHAEL O'ROURKE</u> declare that (choose one as appropriate): (print name)			
<input type="checkbox"/> I review and take responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Division C, of the Building Code. I am qualified, and the firm is registered, in the appropriate classes/categories. Individual BCIN: _____ Firm BCIN: _____			
<input checked="" type="checkbox"/> I review and take responsibility for the design and am qualified in the appropriate category as an "other designer" under subsection 3.2.5. of Division C, of the Building Code. Individual BCIN: <u>19669</u> Basis for exemption from registration and qualification: <u>O.B.C SENTENCE 3.2.4.1 (4)</u>			
<input type="checkbox"/> The design work is exempt from the registration and qualification requirements of the Building Code. Basis for exemption from registration and qualification: _____			
I certify that:			
1. The information contained in this schedule is true to the best of my knowledge. 2. I have submitted this application with the knowledge and consent of the firm.			
April 25, 2022		 Signature of Designer	
Date			

NOTE:

- For the purposes of this form, "individual" means the "person" referred to in Clause 3.2.4.7(1) d) of Division C, Article 3.2.5.1. of Division C, and all other persons who are exempt from qualification under Subsections 3.2.4. and 3.2.5. of Division C.
- Schedule 1 is not required to be completed by a holder of a license, temporary license, or a certificate of authorization, issued by the Ontario Association of Architects. Schedule 1 is also not required to be completed by a holder of a license to practise, a limited license to practise, or a certificate of authorization, issued by the Association of Professional Engineers of Ontario.

Application for a Permit Construct or Demolish – Effective January 1, 2015

SITE NAME: SUMMER RIDGE ESTATES INC.

BUILDER: ROYAL PINE HOMES

TYPE: 2503

GFA: 2049

DATE: Apr-22

LO# 95319

WINTER NATURAL AIR CHANGE RATE 0.282

SUMMER NATURAL AIR CHANGE RATE 0.088

HEAT LOSS ΔT °F. 74

HEAT GAIN ΔT °F. 11

CSA-F280-12

SB-12 PERFORMANCE

ROOM USE	EXP. WALL	CLG. HT.	FACTORS	LOSS	GAIN	MBR	ENS	BED-2	BED-3	BATH				
						39	7	25	14	9				
						9	9	9	9	9				
GRS.WALL AREA	GLAZING					351	63	225	126	81				
						LOSS	GAIN	LOSS	GAIN	LOSS	GAIN			
NORTH	20.8	15.5	0	0	0	0	0	0	0	0	0			
EAST	20.8	41.0	0	0	0	0	0	26	540	1067	46	956	1888	
SOUTH	20.8	24.4	0	0	0	0	0	0	0	0	0			
WEST	20.8	41.0	34	706	1396	17	353	0	0	0	0			
SKYLT.	34.1	100.3	0	0	0	0	0	0	0	0	0			
DOORS	19.6	2.9	0	0	0	0	0	0	0	0	0			
NET EXPOSED WALL	3.5	0.5	317	1099	163	46	159	199	690	102	80	277	41	
NET EXPOSED BSMT WALL ABOVE GR	3.5	0.5	0	0	0	0	0	0	0	0	0	0	0	
EXPOSED CLG	1.3	0.6	378	474	211	130	163	155	194	86	140	175	78	
NO ATTIC EXPOSED CLG	2.7	1.2	0	0	0	0	0	25	67	30	50	134	60	
EXPOSED FLOOR	2.5	0.4	0	0	0	0	0	150	373	55	0	0	0	
BASEMENT/CRAWL HEAT LOSS			0			0	0	0	0	0	0	0	0	
SLAB ON GRADE HEAT LOSS			0			0	0	0	0	0	0	0	0	
SUBTOTAL HT LOSS			2279			676		1865		1543		711		
SUB TOTAL HT GAIN				1769			794		1341		2067		148	
LEVEL FACTOR / MULTIPLIER			0.20	0.29		0.20	0.29	0.20	0.29			0.20	0.29	
AIR CHANGE HEAT LOSS			659			195		540		446		206		
AIR CHANGE HEAT GAIN				103			46		78		120		9	
DUCT LOSS			0			0		240		0		92		
DUCT GAIN				0		0			220		0		16	
HEAT GAIN PEOPLE	240		2		480	0		1		240	1		240	
HEAT GAIN APPLIANCES/LIGHTS					538	0			538		538		0	
TOTAL HT LOSS BTU/H					2938		871		2645		1989		1009	
TOTAL HT GAIN x 1.3 BTU/H						3756	1092		3141		3854		224	

ROOM USE	EXP. WALL	CLG. HT.	FACTORS	LOSS	GAIN	LV/DN	K/B/F	LAUN	FOY	MUD				
						29	45	0	10	12				
						10	10	9	11	10				
GRS.WALL AREA	GLAZING					290	450	0	110	120				
						LOSS	GAIN	LOSS	GAIN	LOSS	GAIN			
NORTH	20.8	15.5	0	0	0	0	0	0	0	0	0			
EAST	20.8	41.0	34	706	1396	0	0	0	0	0	0			
SOUTH	20.8	24.4	0	0	0	0	0	0	0	0	0			
WEST	20.8	41.0	0	0	0	73	1517	0	0	0	0			
SKYLT.	34.1	100.3	0	0	0	0	0	0	0	0	0			
DOORS	19.6	2.9	0	0	0	0	0	0	20	392	58	20	392	58
NET EXPOSED WALL	3.5	0.5	256	888	132	377	1307	0	90	312	46	100	347	51
NET EXPOSED BSMT WALL ABOVE GR	3.5	0.5	0	0	0	0	0	0	0	0	0	0	0	0
EXPOSED CLG	1.3	0.6	0	0	0	0	0	60	75	33		0	0	0
NO ATTIC EXPOSED CLG	2.7	1.2	0	0	0	0	0	0	0	0	0	0	0	0
EXPOSED FLOOR	2.5	0.4	0	0	0	0	0	0	0	0	0	0	0	0
BASEMENT/CRAWL HEAT LOSS			0			0	0	0	0	0	0	0	0	0
SLAB ON GRADE HEAT LOSS			0			0	0	0	0	0	0	0	0	0
SUBTOTAL HT LOSS						1594	2824		704		738			
SUB TOTAL HT GAIN							1527			104		109		
LEVEL FACTOR / MULTIPLIER			0.30	0.53		0.30	0.53	0.20	0.29			0.30	0.53	
AIR CHANGE HEAT LOSS						844			373		391			
AIR CHANGE HEAT GAIN							89			6		6		
DUCT LOSS			0			0		10		0		0		
DUCT GAIN						0		57		0		0		
HEAT GAIN PEOPLE	240		0		0	0		0		0		0		
HEAT GAIN APPLIANCES/LIGHTS					538		538		538		538		0	
TOTAL HT LOSS BTU/H					2438		4319		1076		1129		10002	
TOTAL HT GAIN x 1.3 BTU/H						2799	5087			143		151		1328

TOTAL HEAT GAIN BTU/H:

22583

TONS: 1.88

LOSS DUE TO VENTILATION LOAD BTU/H: 1274

STRUCTURAL HEAT LOSS: 28523

TOTAL COMBINED HEAT LOSS BTU/H: 29797

SITE NAME: SUMMER RIDGE ESTATES INC.
BUILDER: ROYAL PINE HOMES

TYPE: 2503

DATE: Apr-22

GFA: 2049

LO# 95319

HEATING CFM 710 COOLING CFM 710
TOTAL HEAT LOSS 28,523 TOTAL HEAT GAIN 22,394
AIR FLOW RATE CFM 24.89 AIR FLOW RATE CFM 31.7

furnace pressure 0.6
furnace filter 0.05
a/c coil pressure 0.2
available pressure
for s/a & r/a 0.35

#CARRIER

AFUE = 97 %

59SP5A-40-10

40

INPUT (BTU/H) = 40,000

OUTPUT (BTU/H) = 39,000

FAN SPEED

LOW 0

MEDLOW 0

MEDIUM 0

MEDIUM HIGH 710

HIGH 875

DESIGN CFM = 710

CFM @ .6" E.S.P.

TEMPERATURE RISE 51 °F

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	9	5	3
R/A	0	0	4	2	1

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5"Ø unless noted otherwise on layout.

RUN #	1	2	3	4	5	6	7	10	13	14	15	17	19	20	21	22	23
ROOM NAME	MBR	ENS	BED-2	BED-2	BED-3	BED-3	BATH	MBR	LV/DN	K/B/F	K/B/F	LAUN	FOY	MUD	BAS	BAS	BAS
RM LOSS MBH.	1.47	0.87	1.32	1.32	0.99	0.99	1.01	1.47	2.44	2.16	2.16	0.11	1.08	1.13	3.33	3.33	3.33
CFM PER RUN HEAT	37	22	33	33	25	25	25	37	61	54	54	3	27	28	83	83	83
RM GAIN MBH.	1.88	1.09	1.57	1.57	1.93	1.93	0.22	1.88	2.80	2.54	2.54	0.82	0.14	0.15	0.44	0.44	0.44
CFM PER RUN COOLING	60	35	50	50	61	61	7	60	89	81	81	26	5	5	14	14	14
ADJUSTED PRESSURE	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.16	0.16	0.16	0.17	0.17	0.17	0.16	0.16	0.16
ACTUAL DUCT LGH.	44	49	53	57	63	70	36	35	49	26	18	46	40	17	17	15	45
EQUIVALENT LENGTH	160	180	120	130	150	170	150	140	120	110	100	130	120	150	120	130	140
TOTAL EFFECTIVE LENGTH	204	229	173	187	213	240	186	175	169	136	118	176	160	167	137	145	185
ADJUSTED PRESSURE	0.08	0.08	0.1	0.09	0.08	0.07	0.09	0.1	0.1	0.12	0.14	0.1	0.11	0.1	0.12	0.11	0.09
ROUND DUCT SIZE	5	4	5	5	5	5	4	5	6	5	5	4	4	4	6	6	6
HEATING VELOCITY (ft/min)	272	252	242	242	184	184	287	272	311	396	396	34	310	321	423	423	423
COOLING VELOCITY (ft/min)	441	402	367	367	448	448	80	441	454	595	595	298	57	57	71	71	71
OUTLET GRILL SIZE	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	4X10	3X10	3X10	3X10	3X10	3X10	4X10	4X10	4X10
TRUNK	A	C	C	C	B	B	C	A	B	A	A	C	B	C	A	A	B

RUN #	ROOM NAME	RM LOSS MBH.	CFM PER RUN HEAT	RM GAIN MBH.	CFM PER RUN COOLING	ADJUSTED PRESSURE	ACTUAL DUCT LGH.	EQUIVALENT LENGTH	TOTAL EFFECTIVE LENGTH	ADJUSTED PRESSURE	ROUND DUCT SIZE	HEATING VELOCITY (ft/min)	COOLING VELOCITY (ft/min)	OUTLET GRILL SIZE	TRUNK
1	MBR	1.47	37	1.88	60	0.17	44	160	204	0.08	5	272	441	3X10	A
2	ENS	0.87	22	1.09	35	0.17	49	180	229	0.08	4	252	402	3X10	C
3	BED-2	1.32	33	1.57	50	0.17	53	120	173	0.1	5	242	367	3X10	C
4	BED-2	1.32	33	1.57	50	0.17	57	130	187	0.09	5	242	367	3X10	C
5	BED-3	0.99	25	1.93	61	0.17	63	150	213	0.08	5	184	448	3X10	B
6	BED-3	0.99	25	1.93	61	0.17	70	170	240	0.07	5	184	448	3X10	B
7	BATH	1.01	25	0.22	7	0.17	36	150	186	0.09	4	287	80	3X10	C
10	MBR	1.47	37	1.88	60	0.17	44	160	204	0.08	5	272	441	3X10	A
13	LV/DN	2.44	61	2.80	89	0.16	49	120	169	0.1	6	311	454	4X10	B
14	K/B/F	2.16	54	2.54	81	0.16	26	110	136	0.12	5	396	595	3X10	A
15	K/B/F	2.16	54	2.54	81	0.16	18	100	118	0.14	5	396	595	3X10	A
17	LAUN	0.11	3	0.82	26	0.17	46	130	176	0.1	4	34	298	3X10	C
19	FOY	1.08	27	0.14	5	0.17	40	120	160	0.11	4	310	57	3X10	B
20	MUD	1.13	28	0.15	5	0.17	17	150	167	0.1	4	321	57	3X10	C
21	BAS	3.33	83	0.44	14	0.16	17	120	137	0.12	6	423	71	4X10	A
22	BAS	3.33	83	0.44	14	0.16	15	130	145	0.11	6	423	71	4X10	A
23	BAS	3.33	83	0.44	14	0.16	45	140	185	0.09	6	423	71	4X10	B

SUPPLY AIR TRUNK SIZE															RETURN AIR TRUNK SIZE														
TRUNK		STATIC	ROUND	RECT	VELOCITY			TRUNK		STATIC	ROUND	RECT	VELOCITY			TRUNK		STATIC	ROUND	RECT	VELOCITY								
	CFM	PRESS.	DUCT	DUCT			(ft/min)		CFM	PRESS.	DUCT	DUCT			(ft/min)		CFM	PRESS.	DUCT	DUCT			(ft/min)						
TRUNK A	348	0.08	9.4	10	x	8	626	TRUNK G	0	0.00	0	0	x	8	0	TRUNK O	0	0.05	0	0	x	8	0						
TRUNK B	221	0.07	8.2	8	x	8	497	TRUNK H	0	0.00	0	0	x	8	0	TRUNK P	0	0.05	0	0	x	8	0						
TRUNK C	365	0.07	9.9	12	x	8	548	TRUNK I	0	0.00	0	0	x	8	0	TRUNK Q	0	0.05	0	0	x	8	0						
TRUNK D	0	0.00	0	0	x	8	0	TRUNK J	0	0.00	0	0	x	8	0	TRUNK R	0	0.05	0	0	x	8	0						
TRUNK E	0	0.00	0	0	x	8	0	TRUNK K	0	0.00	0	0	x	8	0	TRUNK S	0	0.05	0	0	x	8	0						
TRUNK F	0	0.00	0	0	x	8	0	TRUNK L	0	0.00	0	0	x	8	0	TRUNK T	0	0.05	0	0	x	8	0						

RETURN AIR #	1	2	3	4	5	6	0	0	0	0	0	0	0	0	0	0	BR
AIR VOLUME	85	65	65	65	180	135	0	0	0	0	0	0	0	0	0	0	115
PLENUM PRESSURE	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15
ACTUAL DUCT LGH.	44	57	63	54	15	39	1	1	1	1	1	1	1	1	1	1	14
EQUIVALENT LENGTH	155	270	245	205	175	270	0	0	0	0	0	0	0	0	0	0	135
TOTAL EFFECTIVE LH	199	327	308	259	190	309	1	1	1	1	1	1	1	1	1	1	149
ADJUSTED PRESSURE	0.07	0.05	0.05	0.06	0.08	0.05	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	0.10
ROUND DUCT SIZE	5.8	5.7	5.7	5.4	7.4	7.5	0	0	0	0	0	0	0	0	0	0	5.9
INLET GRILL SIZE	8	8	8	8	8	8	0	0	0	0	0	0	0	0	0	0	8
	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
INLET GRILL SIZE	14	14	14	14	14	14	0	0	0	0	0	0	0	0	0	0	14

TYPE: 2503
SITE NAME: SUMMER RIDGE ESTATES INC.

LO # 95319

RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY

COMBUSTION APPLIANCES		9.32.3.1(1)
a)	<input checked="" type="checkbox"/> Direct vent (sealed combustion) only	
b)	<input type="checkbox"/> Positive venting induced draft (except fireplaces)	
c)	<input type="checkbox"/> Natural draft, B-vent or induced draft gas fireplace	
d)	<input type="checkbox"/> Solid Fuel (including fireplaces)	
e)	<input type="checkbox"/> No Combustion Appliances	

HEATING SYSTEM	
<input checked="" type="checkbox"/> Forced Air	<input type="checkbox"/> Non Forced Air
<input type="checkbox"/> Electric Space Heat	

HOUSE TYPE		9.32.1(2)
<input checked="" type="checkbox"/> I	Type a) or b) appliance only, no solid fuel	
<input type="checkbox"/> II	Type I except with solid fuel (including fireplaces)	
<input type="checkbox"/> III	Any Type c) appliance	
<input type="checkbox"/> IV	Type I, or II with electric space heat	
<input type="checkbox"/>	Other: Type I, II or IV no forced air	

SYSTEM DESIGN OPTIONS		O.N.H.W.P.
<input type="checkbox"/> 1	Exhaust only/Forced Air System	
<input type="checkbox"/> 2	HRV with Ducting/Forced Air System	
<input checked="" type="checkbox"/> 3	HRV Simplified/connected to forced air system	
<input type="checkbox"/> 4	HRV with Ducting/non forced air system	
<input type="checkbox"/>	Part 6 Design	

TOTAL VENTILATION CAPACITY		9.32.3.3(1)
Basement + Master Bedroom	<u>2</u> @ 21.2 cfm	<u>42.4</u> cfm
Other Bedrooms	<u>2</u> @ 10.6 cfm	<u>21.2</u> cfm
Kitchen & Bathrooms	<u>4</u> @ 10.6 cfm	<u>42.4</u> cfm
Other Rooms	<u>5</u> @ 10.6 cfm	<u>53.0</u> cfm
Table 9.32.3.A.	TOTAL	<u>159.0</u> cfm

PRINCIPAL VENTILATION CAPACITY REQUIRED		9.32.3.4.(1)
1 Bedroom	31.8	cfm
2 Bedroom	47.7	cfm
3 Bedroom	63.6	cfm
4 Bedroom	79.5	cfm
5 Bedroom	95.4	cfm
TOTAL		<u>63.6</u> cfm

SUPPLEMENTAL VENTILATION CAPACITY		9.32.3.5.
Total Ventilation Capacity	<u>159</u>	cfm
Less Principal Ventil. Capacity	<u>63.6</u>	cfm
Required Supplemental Capacity	<u>95.4</u>	cfm

PRINCIPAL EXHAUST FAN CAPACITY	
Model:	VANEE V150H
Location:	BSMT
<u>63.6</u> cfm	<input checked="" type="checkbox"/> HVI Approved

PRINCIPAL EXHAUST HEAT LOSS CALCULATION				
CFM	ΔT °F	FACTOR	% LOSS	
63.6 CFM	X 74 F	X 1.08	X	0.25

SUPPLEMENTAL FANS		BY INSTALLING CONTRACTOR		
Location	Model	cfm	HVI	Sones
ENS	BY INSTALLING CONTRACTOR	50	<input checked="" type="checkbox"/>	3.5
BATH	BY INSTALLING CONTRACTOR	50	<input checked="" type="checkbox"/>	3.5

HEAT RECOVERY VENTILATOR		9.32.3.11.
Model:	VANEE V150H	
<u>150</u> cfm high	<u>35</u> cfm low	
<u>75</u> % Sensible Efficiency @ 32 deg F (0 deg C)	<input checked="" type="checkbox"/> HVI Approved	

LOCATION OF INSTALLATION	
Lot:	Concession
Township	Plan:
Address	
Roll #	Building Permit #

BUILDER:	
ROYAL PINE HOMES	
Name:	
Address:	
City:	
Telephone #:	Fax #:

INSTALLING CONTRACTOR	
Name:	
Address:	
City:	
Telephone #:	Fax #:

DESIGNER CERTIFICATION	
I hereby certify that this ventilation system has been designed in accordance with the Ontario Building Code.	
Name:	HVAC Designs Ltd.
Signature:	<i>Michael O'Rourke</i>
HRAI #	001820
Date:	April-22

I REVIEW AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED IN THE APPROPRIATE CATEGORY AS AN "OTHER DESIGNER" UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.

INDIVIDUAL BCIN: 19669

MICHAEL O'ROURKE

CSA F280-12 Residential Heat Loss and Heat Gain Calculations																																																																			
Formula Sheet (For Air Leakage / Ventilation Calculation)																																																																			
LO#: 95319		Model: 2503		Builder: ROYAL PINE HOMES SUMMER RIDGE ESTATES INC.				Date: 2022-04-25																																																											
Volume Calculation					Air Change & Delta T Data																																																														
House Volume <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Level</th> <th>Floor Area (ft²)</th> <th>Floor Height (ft)</th> <th>Volume (ft³)</th> </tr> </thead> <tbody> <tr> <td>Bsmt</td> <td>914</td> <td>9</td> <td>8226</td> </tr> <tr> <td>First</td> <td>914</td> <td>10</td> <td>9140</td> </tr> <tr> <td>Second</td> <td>1135</td> <td>9</td> <td>10215</td> </tr> <tr> <td>Third</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td>Fourth</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td colspan="3" style="text-align: right;">Total:</td> <td>27,581.0 ft³</td> </tr> <tr> <td colspan="3" style="text-align: right;">Total:</td> <td>781.0 m³</td> </tr> </tbody> </table>					Level	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)	Bsmt	914	9	8226	First	914	10	9140	Second	1135	9	10215	Third	0	9	0	Fourth	0	9	0	Total:			27,581.0 ft³	Total:			781.0 m³	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2">WINTER NATURAL AIR CHANGE RATE</td> <td>0.282</td> </tr> <tr> <td colspan="2">SUMMER NATURAL AIR CHANGE RATE</td> <td>0.088</td> </tr> </table> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="5">Design Temperature Difference</th> </tr> <tr> <th></th> <th>Tin °C</th> <th>Tout °C</th> <th>ΔT °C</th> <th>ΔT °F</th> </tr> <tr> <td>Winter DTDh</td> <td>22</td> <td>-19</td> <td>41</td> <td>74</td> </tr> <tr> <td>Summer DTDc</td> <td>24</td> <td>30</td> <td>6</td> <td>11</td> </tr> </table>					WINTER NATURAL AIR CHANGE RATE		0.282	SUMMER NATURAL AIR CHANGE RATE		0.088	Design Temperature Difference						Tin °C	Tout °C	ΔT °C	ΔT °F	Winter DTDh	22	-19	41	74	Summer DTDc	24	30	6	11
Level	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)																																																																
Bsmt	914	9	8226																																																																
First	914	10	9140																																																																
Second	1135	9	10215																																																																
Third	0	9	0																																																																
Fourth	0	9	0																																																																
Total:			27,581.0 ft³																																																																
Total:			781.0 m³																																																																
WINTER NATURAL AIR CHANGE RATE		0.282																																																																	
SUMMER NATURAL AIR CHANGE RATE		0.088																																																																	
Design Temperature Difference																																																																			
	Tin °C	Tout °C	ΔT °C	ΔT °F																																																															
Winter DTDh	22	-19	41	74																																																															
Summer DTDc	24	30	6	11																																																															
5.2.3.1 Heat Loss due to Air Leakage					6.2.6 Sensible Gain due to Air Leakage																																																														
$HL_{airb} = LR_{airh} \times \frac{V_b}{3.6} \times DTD_h \times 1.2$ <p>0.282 x 216.95 x 41 °C x 1.2 = 3031 W</p> <p>= 10341 Btu/h</p>					$HG_{salb} = LR_{airc} \times \frac{V_b}{3.6} \times DTD_c \times 1.2$ <p>= 0.088 x 216.95 x 6 °C x 1.2 = 141 W</p> <p>= 480 Btu/h</p>																																																														
5.2.3.2 Heat Loss due to Mechanical Ventilation					6.2.7 Sensible heat Gain due to Ventilation																																																														
$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E)$ <p>64 CFM x 74 °F x 1.08 x 0.25 = 1274 Btu/h</p>					$HL_{vairb} = PVC \times DTD_h \times 1.08 \times (1 - E)$ <p>64 CFM x 11 °F x 1.08 x 0.25 = 189 Btu/h</p>																																																														
5.2.3.3 Calculation of Air Change Heat Loss for Each Room (Floor Multiplier Section)																																																																			
$HL_{airr} = Level\ Factor \times HL_{airbv} \times \{(HL_{agcr} + HL_{bgcr}) \div (HL_{agclevel} + HL_{bgclevel})\}$ <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Level</th> <th>Level Factor (LF)</th> <th>HLairve Air Leakage + Ventilation Heat Loss (Btu/h)</th> <th>Level Conductive Heat Loss: (HL_{clevel})</th> <th>Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>0.5</td> <td rowspan="5" style="text-align: center; vertical-align: middle;">10,341</td> <td>4,831</td> <td>1.070</td> </tr> <tr> <td>2</td> <td>0.3</td> <td>5,860</td> <td>0.529</td> </tr> <tr> <td>3</td> <td>0.2</td> <td>7,149</td> <td>0.289</td> </tr> <tr> <td>4</td> <td>0</td> <td>0</td> <td>0.000</td> </tr> <tr> <td>5</td> <td>0</td> <td>0</td> <td>0.000</td> </tr> </tbody> </table>										Level	Level Factor (LF)	HLairve Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{clevel})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)	1	0.5	10,341	4,831	1.070	2	0.3	5,860	0.529	3	0.2	7,149	0.289	4	0	0	0.000	5	0	0	0.000																																
Level	Level Factor (LF)	HLairve Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{clevel})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)																																																															
1	0.5	10,341	4,831	1.070																																																															
2	0.3		5,860	0.529																																																															
3	0.2		7,149	0.289																																																															
4	0		0	0.000																																																															
5	0		0	0.000																																																															
<p>*HLairbv = Air leakage heat loss + ventilation heat loss</p> <p>*For a balanced or supply only ventilation system HLairve = 0</p>					<p>Michael O'Rourke BCIN# 19669</p>																																																														

HEAT LOSS AND GAIN SUMMARY SHEET

MODEL: 2503	BUILDER: ROYAL PINE HOMES
SFQT: 2049	LO# 95319
	SITE: SUMMER RIDGE ESTATES INC.

DESIGN ASSUMPTIONS

HEATING	°F	COOLING	°F
OUTDOOR DESIGN TEMP.	-2	OUTDOOR DESIGN TEMP.	86
INDOOR DESIGN TEMP.	72	INDOOR DESIGN TEMP. (MAX 75°F)	75
		WINDOW SHGC	0.50

BUILDING DATA

ATTACHMENT:	ATTACHED	# OF STORIES (+BASEMENT):	3
FRONT FACES:	EAST	ASSUMED (Y/N):	Y
AIR CHANGES PER HOUR:	3.00	ASSUMED (Y/N):	Y
AIR TIGHTNESS CATEGORY:	TIGHT	ASSUMED (Y/N):	Y
WIND EXPOSURE:	SHELTERED	ASSUMED (Y/N):	Y
HOUSE VOLUME (ft ³):	27581.0	ASSUMED (Y/N):	Y
INTERNAL SHADING:	BLINDS/CURTAINS	ASSUMED OCCUPANTS:	4
INTERIOR LIGHTING LOAD (Btu/h/ft ²):	1.27	DC BRUSHLESS MOTOR (Y/N):	Y
FOUNDATION CONFIGURATION	BCIN_1	DEPTH BELOW GRADE:	6.0 ft
LENGTH: 51.0 ft	WIDTH: 23.0 ft	EXPOSED PERIMETER:	98.0 ft


2012 OBC - COMPLIANCE PACKAGE	Compliance Package	
	SB-12 PERFORMANCE	
	Nominal	Min. Eff.
Ceiling with Attic Space Minimum RSI (R)-Value	60	59.22
Ceiling Without Attic Space Minimum RSI (R)-Value	31	27.65
Exposed Floor Minimum RSI (R)-Value	31	29.80
Walls Above Grade Minimum RSI (R)-Value	22+1.5	21.40
Basement Walls Minimum RSI (R)-Value	20	21.12
Below Grade Slab Entire surface > 600 mm below grade Minimum RSI (R)-Value	-	-
Edge of Below Grade Slab ≤ 600 mm Below Grade Minimum RSI (R)-Value	10	10
Heated Slab or Slab ≤ 600 mm below grade Minimum RSI (R)-Value	10	11.13
Windows and Sliding Glass Doors Maximum U-Value	1.6	-
Skylights Maximum U-Value	2.6	-
Space Heating Equipment Minimum AFUE	96%	-
HRV/ERV Minimum Efficiency	75%	-
Domestic Hot Water Heater Minimum EF	0.9	-

INDIVIDUAL BCIN: 19669
MICHAEL O'ROURKE



Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description		
Province:	Ontario	
Region:	Brampton	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Floor Length (m):	15.5	 Insulation Configuration
Floor Width (m):	7.0	
Exposed Perimeter (m):	29.9	
Wall Height (m):	2.7	
Depth Below Grade (m):	1.83	
Window Area (m ²):	0.6	
Door Area (m ²):	1.9	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Foundation Loads		
Heating Load (Watts):		962


TYPE: 2503
LO# 95319

Air Infiltration Residential Load Calculator


Supplemental tool for CAN/CSA-F280

Weather Station Description				
Province:	Ontario			
Region:	Brampton			
Weather Station Location:	Open flat terrain, grass			
Anemometer height (m):	10			
Local Shielding				
Building Site:	Suburban, forest			
Walls:	Heavy			
Flue:	Heavy			
Highest Ceiling Height (m):	6.71			
Building Configuration				
Type:	Semi			
Number of Stories:	Two			
Foundation:	Full			
House Volume (m ³):	781.0			
Air Leakage/Ventilation				
Air Tightness Type:	Energy Star Attached (3.0 ACH)			
Custom BDT Data:	ELA @ 10 Pa.	874.9 cm ²		
	3.00	ACH @ 50 Pa		
Mechanical Ventilation (L/s):	Total Supply	Total Exhaust		
	30.0	30.0		
Flue Size				
Flue #:	#1	#2	#3	#4
Diameter (mm):	0	0	0	0
Natural Infiltration Rates				
Heating Air Leakage Rate (ACH/H):	0.282			
Cooling Air Leakage Rate (ACH/H):	0.088			


TYPE: 2503
LO# 95319



GROUND FLOOR PLAN ELEV 'A1' (REV)



PART. GROUND FLOOR PLAN ELEV 'A2'



PART. GROUND FLOOR PLAN ELEV 'B2'

I MICHAEL O'ROURKE HAVE REVIEWED AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.
Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.


PARTIAL GROUND FLOOR PLAN ELEV 'B1' (REV)

CSA-F280-12
SB-12 PERFORMANCE


HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.		
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	REVISED TO PERFORMANCE PATH	APR/2022
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.


Client		<div></div> <div>375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services</div>	Sheet Title	
ROYAL PINE HOMES			FIRST FLOOR HEATING LAYOUT	
Project Name SUMMER RIDGE ESTATES INC. BRAMPTON, ONTARIO			Date	MAR/2022
25032049 sqft			Scale	3/16" = 1'-0"
		BCIN# 19669		
		LO#	95319	
		Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.		




SECOND FLR PLAN ELEV 'A1' (REV)




PARTIAL SECOND FLR PLAN,
ELEV 'A1' (REV)
(W/ OPT. ENSUITE LAYOUT)
(ELEV. 'B1' REV. & 'B2' SIMILAR)



PARTIAL SECOND FLR PLAN ELEV 'A2'



PARTIAL SECOND FLR PLAN, ELEV
'B1' (REV)



PARTIAL SECOND FLR PLAN, ELEV 'B2'

I MICHAEL O'ROURKE HAVE REVIEWED AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.

Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

CSA-F280-12

SB-12 PERFORMANCE

HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.		
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	REVISED TO PERFORMANCE PATH	APR/2022
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client		<div></div> <div>375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services</div> <div>Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.</div>	Sheet Title	
ROYAL PINE HOMES			SECOND FLOOR HEATING LAYOUT	
Project Name SUMMER RIDGE ESTATES INC. BRAMPTON, ONTARIO			Date	MAR/2022
25032049 sqft			Scale	3/16" = 1'-0"
			BCIN# 19669	
			LO#	95319