



ELEVATION 'A'



ELEVATION 'B'

UNIT 2005

SB-12 ENERGY EFFICIENCY DESIGN MATRIX

PERFORMANCE COMPLIANCE

SPACE HEATING FUEL	
☒ GAS	☐ OIL
☐ ELECTRIC	☐ PROPANE
☐ EARTH	☐ SOLID FUEL

BUILDING COMPONENT	PROPOSED
INSULATION RSI (R) VALUE	
CEILING W/ ATTIC SPACE	10.56 (R60)
CEILING W/O ATTIC SPACE	5.46 (R31)
EXPOSED FLOOR	5.46 (R31)
WALLS ABOVE GRADE	3.87 (R22) + 1.5ci
BASEMENT WALLS	R20 Blanket or R12+R10ci
BELOW GRADE SLAB ENTIRE SURFACE > 600mm BELOW GRADE	-
EDGE OF BELOW GRADE SLAB ≤ 600mm BELOW GRADE	1.76 (R10)
HEATED SLAB ≤ 600mm BELOW GRADE	1.76 (R10)
CONC. SLAB ≤ 600mm BELOW GRADE	1.76 (R10)
WINDOWS & DOORS	
WINDOWS/SLIDING GLASS DOORS (MAX U-VALUE or MIN. ER)	1.6
SKYLIGHTS (MAX. U-VALUE)	2.8
APPLIANCE EFFICIENCY	
SPACE HEATING EQUIP. (AFUE%)	Combo 95% AFUE GLOW C140
HRV EFFICIENCY (%)	75%
DOMESTIC HOT WATER HEATER (EF)	0.84
DWHR UNIT (%)	53.3% ON 1 SHOWERS MIN.

AREA CALCULATIONS		EL. 'A'	EL. 'B'
	STD. PLAN	STD. PLAN	
GROUND FLOOR AREA	993 sq. ft.	993 sq. ft.	
SECOND FLOOR AREA	997 sq. ft.	997 sq. ft.	
SUBTOTAL	1990 sq. ft.	1990 sq. ft.	
DEDUCT ALL OPEN AREAS	19 sq. ft.	19 sq. ft.	
TOTAL NET AREA	1971 sq. ft. (183.11 sq. m.)	1971 sq. ft. (183.11 sq. m.)	
FINISHED BASEMENT AREA	724 sq. ft.	724 sq. ft.	
COVERARGE W/OUT PORCH	1407 sq. ft. (130.71 sq. m.)	1407 sq. ft. (130.71 sq. m.)	
COVERARGE W/ PORCH	1548 sq. ft. (143.81 sq. m.)	1452 sq. ft. (134.90 sq. m.)	
WINDOW / WALL AREA CALCULATIONS			
	EL. 'A'	EL. 'A'	EL. 'B'
	STD. PLAN	OPT. PLAN	STD. PLAN
GROSS WALL AREA	3164.38 sq. ft. (293.98 sq. m.)	3164.38 sq. ft. (293.98 sq. m.)	3177 sq. ft. (295.15 sq. m.)
GROSS WINDOW AREA (INCL. GLASS DOORS & SKYLIGHTS)	381.19 sq. ft. (35.41 sq. m.)	391.52 sq. ft. (36.37 sq. m.)	450.17 sq. ft. (41.82 sq. m.)
TOTAL WINDOW %	12.05 %	12.37 %	14.17 %
			14.49 %

- 1 - TITLE PAGE
- 2 - BASEMENT PLAN, ELEV. 'A'
- 3 - GROUND FLOOR & SECOND FLOOR PLAN, ELEV. 'A'
- 4 - BASEMENT PLAN, ELEV. 'B'
- 5 - GROUND FLOOR PLAN, ELEV. 'B'
- 6 - FRONT & REAR ELEVATION 'A'
- 7 - FLANKAGE, CROSS SECTION 'B-B', 'C-C' & 'E-E' FOR ELEV. 'A'
- 8 - FRONT & REAR ELEVATION 'B'
- 9 - FLANKAGE, CROSS SECTION 'B-B' & 'C-C' FOR ELEV. 'B'
- 10 - CROSS SECTION 'A-A'
- 11 - CONSTRUCTION NOTES

8. REVISED PLAN W/ SERVICE STAIR & CLIENTS' COMMENTS	2023/12/01	TT
7. ISSUED FOR PERMIT	-	-
6. ISSUED FOR FINAL APPROVAL	2023/01/13	MM
5. REVISED AS PER ARCHITECTURAL CONTROL COMMENTS	-	-
4. REVISED AS PER ENGINEER COMMENTS	2023/01/05	MM
3. REVISED AS PER FLOOR & ROOF MANUFACTURE PLANS	2022/06/15	MM
2. REVISED AS PER CLIENT'S COMMENTS	2021/09/28	DSI
1. ISSUED FOR CLIENT REVIEW	2021/07/07	BB
REVISIONS		DATE (YYYYMMDD) BY




THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN AND HAS THE QUALIFICATIONS AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE TO BE A DESIGNER.

QUALIFICATION INFORMATION
Derek R. Santos 37308
NAME
REGISTRATION INFORMATION BCIN
HUNT DESIGN ASSOCIATES INC. 19695

HUNT
DESIGN ASSOCIATES INC.
www.huntdesign.ca

Royal Pine Homes/Summer Ridge Estates Inc.-216051 UNIT 2005
"MAYFIELD VILLAGE", BRAMPTON, ON. REV.2024.03.15
Drawn By MA/TT Checked By DS Scale 3/16"=1'-0" File Number 216051WT2005 Page Number 1 of 11
8966 Woodbine Ave., Markham, ON L3R 0J7 T 905.737.5133 F 905.737.7326

All drawings specifications related documents and design are the copyright property of Hunt Design Associates (H.D.A.). Reproduction of this property in whole or in part is strictly prohibited without H.D.A.'s written permission (H.D.A. assumes no responsibility or liability for this property unless it bears the appropriate BCIN number and original signature.)



BASEMENT PLAN, EL. 'A'



PROVIDE SOLID WOOD BLOCKING @
24" O.C. FOR FIRST JOIST SPAN
WHEN PARALLEL W/ EXTERIOR WALL

APROX. LOCATION OF
FURNACE AND HOT
WATER TANK

PROVIDE SOLID WOOD BLOCKING @
24" O.C. FOR FIRST JOIST SPAN
WHEN PARALLEL W/ EXTERIOR WALL

EGRESS WINDOW - BELOW GRADE
 PROVIDE PREMANUF. EGRESS
 COMPLIANT WINDOW WHERE INDICATED.
 WINDOW SILL MUST BE 150mm (4'-11")
 MAX. ABOVE ADJACENT GROUND
 LEVEL AS PER O.B.C. 9.9.10.1. WINDOW
 MUST HAVE A MIN. OF 0.35m² OPENING
 AREA REQUIRED FOR BEDROOM SPACE
 WITH NO DIMENSION LESS THAN 0.30m.
 WINDOW WELL SHALL MEET O.B.C.
 9.9.10.1(5) REQUIREMENTS.

APROX. LOCATION OF
FURNACE AND HOT
WATER TANK


[illegible]

REFER TO FLOOR JOIST MANUFACTURER'S DRAWINGS FOR LAYOUT, SPACING, BLOCKING & STRAPPING REQUIREMENTS, INSTALLATION DETAILS AND HANGER SIZES, & SUBFLOOR THICKNESS	ALL DOORS ON PLAN ARE 7'-10" HIGH TOP OF FRAME. UNLESS LABELED OTHERWISE.
---	--

PROVIDE SOLID WOOD BLOCKING @
24" O.C. FOR FIRST JOIST SPAN
WHEN PARALLEL W/ EXTERIOR WALL

NOTE: STEP TRUSSES @ RAISED / TRAY CEILINGS		
REFER TO ROOF TRUSS MANUFACTURER'S DRAWINGS FOR LAYOUT, SPACING, INSTALLATION DETAILS AND HANGER SIZES.		

SB: MIN. 2/ 2"x6" SPF OR 3/ 2"x4" SPF
SBI: MIN. 3/ 2"x6" SPF OR 4/ 2"x4" SPF
SB2: MIN. 4/ 2"x6" SPF OR 5/ 2"x4" SPF





BASEMENT PLAN, ELEV. 'B'

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THE DESIGN AND CONSTRUCTION OF THE BASEMENT PLAN. THE DESIGN AND CONSTRUCTION OF THE BASEMENT PLAN IS THE RESPONSIBILITY OF THE UNDERSIGNED. THE UNDERSIGNED IS NOT RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THE BASEMENT PLAN. THE UNDERSIGNED IS NOT RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THE BASEMENT PLAN.

DESIGNED BY: **HUNT DESIGN ASSOCIATES INC.**
DRAWN BY: **MA/TT**
CHECKED BY: **DS**
DATE: **3/16/2024**
PROJECT: **216051WT2005**
SHEET: **4** OF **11**

ROYAL PINE HOMES/SUMMER RIDGE ESTATES INC.-216051 UNIT 2005
"MAYFIELD VILLAGE", BRAMPTON, ON.
REV. 2024.03.15




NOTE:
STEP TRUSSES @ RAISED /
TRAY CEILINGS



REFER TO ROOF TRUSS
MANUFACTURER'S DRAWINGS
FOR LAYOUT, SPACING,
INSTALLATION DETAILS AND
HANGER SIZES.

SECOND FLOOR PLAN, EL. 'B


MMELILLO | WED MAR 20/24 01:47 PM | K:\PROJECTS\2016\216051.BOY\WORKING\TOWNS\20' REARLANE\216051WT2005.DWG



PART. REAR GARAGE ELEVATION 'D-D'



ROOF PLAN
EL. 'A'
N.T.S.




REAR ELEVATION 'A'

FRONT ELEVATION 'A'



FLANKAGE ELEVATION 'A'



PART. REAR EL. 'C-C'
FOR ELEVATION 'A'

PART. REAR GARAGE EL. 'B-B'
FOR ELEVATION 'A'

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN AND HAS THE QUALIFICATIONS AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE TO BE A DESIGNER.

Derek R. Santos
NAME
REGISTRATION INFORMATION
HUNT DESIGN ASSOCIATES INC.
19695

37308

BCN




19695

HUNT
DESIGN ASSOCIATES INC.
www.hunt-design.ca

FLANKAGE, CROSS SECTION 'B-B', 'C-C' & 'E-E' FOR ELEV. 'A'
Royal Pine Homes/Summer Ridge Estates Inc.-216051 UNIT 2005
"MAYFIELD VILLAGE", BRAMPTON, ON.
REV.2024.03.15

Drawn By: MA/TT
Checked By: DS
Scale: 3/16"=1'-0"
File Number: 216051WT2005
Page Number: 7 of 11

All drawings specifications related documents and design are the copyright property of Hunt Design Associates (H.D.A.). Reproduction of this property in whole or in part is strictly prohibited without H.D.A.'s written permission (H.D.A. assumes no responsibility or liability for this property unless it bears the appropriate BCN number and original signature).




ROOF PLAN
EL. 'B'
N.T.S.

REFER TO FRONT
ELEVATION FOR TYPICAL
NOTES & INFORMATION


ROOF OVERHANGS TO BE 18"
UNLESS NOTED OTHERWISE

PART. REAR GARAGE ELEVATION 'D-D'




REAR ELEVATION 'B'

FRONT ELEVATION 'B'



PART. REAR EL. 'C-C'
FOR ELEVATION 'B'

PART. REAR GARAGE EL. 'B-B'
FOR ELEVATION 'B'



SECTION 1.0. CONSTRUCTION NOTES

- 1 ROOF CONSTRUCTION** (9.19, 9.23.1.3, 9.23.1.5)
NO. 210 (10.25 KG/M2) ASPHALT SHINGLES. 3/8" (9.5) PLYWOOD SHEATHING WITH 1" CLIPS. APPROVED WOOD TRUSSES @ 24" (610) O.C. MAX. APPROVED EAVES PROTECTION TO EXTEND 2'-11" (660) TO EAVE OF ROOF AND 1'-2" (30) MIN. 12" (305) BEYOND INNER FACE OF EXTERIOR WALL. 2"x4" (38x89) TRUSS BRACING @ 6'-0" (1830) O.C. AT BOTTOM CHORD. PREFIN. ALUM. EAVESTROUGH, FASCIA, RVL, & VENTED SOFFIT. ATTIC VENTILATION 1:300 OF INSULATED CEILING AREA WITH MIN. 25% OF REQUIRED OPENINGS LOCATED AT TOP OF SPACE & MIN. 25% OF REQUIRED OPENINGS LOCATED AT BOTTOM OF SPACE. EAVESTROUGH TO BE 4" MIN. WITH RVL. DISCHARGING ONTO CONCRETE SPLASH POUNDING AREA WITH MIN. 25% OF REQUIRED OPENINGS TO HAVE 5" MIN. EAVESTROUGH WITH ELEC. TRACED HEATER CABLE ALONG EAVESTROUGH AND DOWN RVL.
- 1A ICE AND WATER SHIELD**
PROVIDE ICE AND WATER SHIELD IN THE AREAS INDICATED. THE ICE AND WATER SHIELD SHALL BE A SELF-ADHERING AND SELF-SEALING MEMBRANE. SIPS LAPS MUST BE A MINIMUM 3 1/2" (90) AND END LAPS A MINIMUM 6" (152), AND TO EXTEND UP DORMER WALLS A MINIMUM 12" (305).
- 1B PROFILED ROOF TRUSSES**
ROOF TRUSSES SHALL BE PROFILED AND/OR STEPPED AT RAISED COFFER/TRAY CELINGS, ANGLED TRAY CELINGS WILL BE SHEATHED W/ 3/8" (9.5) PLYWOOD.
- 2 SIDING WALL CONSTRUCTION (2"x6")**
SIDING MATERIAL AS PER ELEVATION ATTACHED TO FRAMING MEMBERS. FURRING MEMBERS OR BLOCKING BETWEEN THE FRAMING MEMBERS ON APPROVED SHEATHING PAPER ON 3/8" (9.5) EXT. GRADE SHEATHING ON STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION, APPROVED 6 MIL. POLYETHYLENE AIR/VAPOUR BARRIER, ON 1/2" (12.7) GYPSUM WALLBOARD INT. FIN. GYPSUM SHEATHING, RIGID INSULATION, AND FIBERBOARD SHALL NOT BE USED FOR THE ATTACHMENT OF SIDING (9.23.16.3.1.1) (REFER TO 35 NOTE AS REQ.)
- 2A SIDING WALL CONSTRUCTION (2"x6") W/ CONTIN. INSULATION**
SIDING MATERIAL AS PER ELEVATION ATTACHED TO FURRING MEMBERS ON APPROVED AIR/VAPOUR BARRIER AS PER O.B.C. 9.27.3. ON EXTERIOR TYPE RIGID INSULATION (JOINTS UNTAPED), MECHANICALLY FASTENED AS PER MANUFACTURERS SPECIFICATIONS, ON 3/8" (9.5) EXT. GRADE SHEATHING ON STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION, APPROVED 6 MIL. POLYETHYLENE AIR/VAPOUR BARRIER, ON 1/2" (12.7) GYPSUM WALLBOARD INT. FIN. GYPSUM SHEATHING, RIGID INSULATION, AND FIBERBOARD SHALL NOT BE USED FOR THE ATTACHMENT OF SIDING (9.23.16.3.1.1) (REFER TO 35 NOTE AS REQ.)
- 2B SIDING WALL @ GARAGE CONSTRUCTION**
SIDING MATERIAL AS PER ELEVATION ATTACHED TO FRAMING MEMBERS. FURRING MEMBERS OR BLOCKING BETWEEN THE FRAMING MEMBERS ON APPROVED SHEATHING PAPER ON 3/8" (9.5) EXTERIOR TYPE SHEATHING ON STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION, APPROVED 6 MIL. POLYETHYLENE AIR/VAPOUR BARRIER, ON 1/2" (12.7) GYPSUM WALLBOARD INTERIOR FINISH. PROVIDE WEEP HOLES @ 32" (800) O.C. BOTTOM COURSE AND OVER OPENINGS. PROVIDE BASE FLASHING UP MIN. 8" (150) BEHIND BUILDING PAPER (9.20.13.6) (REFER TO 35 NOTE AS REQ.)
- 3 BRICK VENEER WALL CONSTRUCTION (2"x6")**
3 1/2" (90) BRICK VENEER 1" (25) AIR SPACE, 7/8"x7/8"x3" (22x180x76) GALV. METAL TIES @ 16" (406) O.C. HORIZ. 2"x4" (600) O.C. VERT. BONDING AND FASTENING FOR TIES TO CONFORM WITH 9.23.9. ON APPROVED SHEATHING PAPER, 3/8" (9.5) EXTERIOR TYPE SHEATHING, STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION, AND 6 MIL. POLYETHYLENE AIR/VAPOUR BARRIER WITH APPROVED CONTIN. AIR BARRIER, 1/2" (12.7) GYPSUM WALLBOARD INTERIOR FINISH. PROVIDE WEEP HOLES @ 32" (800) O.C. BOTTOM COURSE AND OVER OPENINGS. PROVIDE BASE FLASHING UP MIN. 8" (150) BEHIND BUILDING PAPER (9.20.13.6) (REFER TO 35 NOTE AS REQ.)
- 3A BRICK VENEER WALL CONSTRUCTION (2"x6") W/ CONTIN. INSULATION**
3 1/2" (90) BRICK VENEER 1" (25) AIR SPACE, 7/8"x7/8"x3" (22x180x76) GALV. METAL TIES @ 16" (406) O.C. HORIZ. 2"x4" (600) O.C. VERT. BONDING AND FASTENING FOR TIES TO CONFORM WITH 9.23.9. ON APPROVED SHEATHING PAPER, 3/8" (9.5) EXTERIOR TYPE SHEATHING, STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION, AND 6 MIL. POLYETHYLENE AIR/VAPOUR BARRIER WITH APPROVED CONTIN. AIR BARRIER, 1/2" (12.7) GYPSUM WALLBOARD INTERIOR FINISH. PROVIDE WEEP HOLES @ 32" (800) O.C. BOTTOM COURSE AND OVER OPENINGS. PROVIDE BASE FLASHING UP MIN. 8" (150) OVER RIGID INSULATION (9.20.13.6) (REFER TO 35 NOTE AS REQ.)
- 3B BRICK VENEER WALL @ GARAGE CONSTRUCTION**
3 1/2" (90) BRICK VENEER, MIN. 1" (25) AIR SPACE, 7/8"x7/8"x3" (22x180x76) GALV. METAL TIES @ 16" (406) O.C. HORIZ. 2"x4" (600) O.C. VERT. BONDING AND FASTENING FOR TIES TO CONFORM WITH 9.23.9. ON APPROVED SHEATHING PAPER, 3/8" (9.5) EXTERIOR TYPE SHEATHING ON STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION, APPROVED 6 MIL. POLYETHYLENE AIR/VAPOUR BARRIER WITH APPROVED CONTIN. AIR BARRIER, 1/2" (12.7) GYPSUM WALLBOARD INTERIOR FINISH. PROVIDE WEEP HOLES @ 32" (800) O.C. AT BOTTOM COURSE AND OVER OPENINGS. PROVIDE BASE FLASHING UP 6" (150) MIN. BEHIND BUILDING PAPER (9.20.13.6) (REFER TO 35 NOTE AS REQ.)
- 4 INTERIOR STUD PARTITIONS** (9.23.9.8, 9.23.10)
BEARING PARTITIONS SHALL BE A MINIMUM 2"x4" (38x89) @ 16" (406) O.C. FOR 2 STORY AND 1/2" (305) O.C. FOR 3 STORY. NON-BEARING PARTITIONS 2"x4" (38x89) @ 16" (406) O.C. FOR 2 STORY AND 1/2" (305) O.C. FOR 3 STORY. TOP OF PARTITION SHALL BE 1/2" (12.7) MIN. DRYWALL, BOTH SIDES OF STUDS. PROVIDE 2"x6" (38x140) STUDS WHERE NOTED. PROVIDE 2"x4" (38x89) @ 24" (610) O.C. LADDER FRAMING WHERE WALLS INTERSECT PERPENDICULAR TO ONE ANOTHER. PROVIDE 2"x4" (38x89) WOOD BLOCKING ON FLAT @ 3'-11" (1194) O.C. MAX. BETWEEN FLOOR JOISTS WHEN NON-LOADBEARING WALLS ARE ADJACENT TO FLOOR JOISTS.
- 4A EXT. LOFT WALL CONSTRUCTION (2"x6") - NO CLADDING**
3/8" (9.5) EXTERIOR TYPE SHEATHING, STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION AND 6 MIL. POLYETHYLENE AIR/VAPOUR BARRIER WITH APPROVED CONT. AIR BARRIER, 1/2" (12.7) GYPSUM WALLBOARD INT. FINISH. (9.23.1)
- 4B EXT. LOFT WALL CONSTRUCTION (2"x6") WITH CLADDING**
APPROVED AIR/VAPOUR BARRIER AS PER O.B.C. 9.27.3. ON EXTERIOR TYPE RIGID INSULATION (JOINTS UNTAPED), MECHANICALLY FASTENED AS PER MANUFACTURERS SPECIFICATIONS, ON 3/8" (9.5) EXTERIOR TYPE SHEATHING, STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION AND 6 MIL. POLYETHYLENE AIR/VAPOUR BARRIER WITH APPROVED CONT. AIR BARRIER, 1/2" (12.7) GYPSUM WALLBOARD INT. FINISH. (9.23.1)
- 5 FOUNDATION WALL/FOOTINGS**
POURED CONC. FOUNDATION WALL AS PER CHART BELOW ON CONTINUOUS REINFORCED CONCRETE FOOTING. FOUNDATION WALLS SHALL EXTEND NOT LESS THAN 8" (150) ABOVE FINISHED GRADE. THE OUTSIDE OF THE FOUNDATION SHALL BE DAMPROOFED FROM THE TOP OF THE FOOTING TO FINISHED GRADE AND BRUSH COAT FROM THE TOP 2" BELOW GRADE. PROVIDE A DRAINAGE LAYER ON THE OUTSIDE OF THE FOUNDATION WALL. SEAL THE DRAINAGE LAYER AT THE TOP OF THE CONC. FOOTING SHALL BE DAMPROOFED. CONCRETE FOOTINGS SUPPORTING JOIST SPANS GREATER THAN 16'-4" (4900) SHALL BE SIZED IN ACCORDANCE WITH 9.15.3.4 (1) (2) OF THE O.B.C. (REFER TO CHART BELOW FOR RESPECTIVE SIZE). BRACE FOUNDATION WALL PRIOR TO BACKFILLING. ALL FOOTINGS SHALL REST ON NATURAL UNDISTURBED SOIL OF 75kPa OR COMPACTED ENGINEERED FILL WITH MIN. BEARING CAPACITY OF 150kPa. IF SOIL BEARING DOES NOT MEET MINIMUM CAPACITY, ENGINEERED FOOTINGS ARE REQUIRED. ACTUAL SOIL BEARING CAPACITY TO BE VERIFIED WITH SOIL ENGINEERING REPORT. REFER TO CONSTRUCTION DRAWINGS AND DETAILS FOR FOUNDATION WALL STRENGTH AND THICKNESS AND 9.15.4. FOUNDATION WALLS SHALL NOT EXCEED 9'-10" (3.0m) IN UNSUPPORTED HEIGHT UNLESS OTHERWISE NOTED. (9.15.4.2.1.1)
- UNREINFORCED SOLID CONCRETE FOUNDATION WALLS (9.15.4.2.1)
- | HEIGHT
THICKNESS | MAX. HEIGHT FROM FIN. SLAB TO GRADE | |
|---------------------|-------------------------------------|---------------------|
| | UNSUPPORTED
AT TOP | SUPPORTED
AT TOP |
| 10" 15 MPa | 3'-11" (1.20m) | 7'-0" (2.15m) |
| 12" 15 MPa | 4'-7" (1.40m) | 7'-6" (2.30m) |
| 14" 15 MPa | 4'-11" (1.50m) | 7'-6" (2.30m) |
| 16" 20 MPa | 3'-11" (1.20m) | 7'-6" (2.30m) |
| 18" 20 MPa | 4'-7" (1.40m) | 7'-6" (2.30m) |
| 20" 20 MPa | 4'-11" (1.50m) | 7'-6" (2.30m) |
- *9 MIN. THICK FOUNDATION WALL IS REQUIRED FOR MASONRY VENEER FINISHED EXTERIOR WALLS WITH CONTINUOUS INSULATION CONFINED TO PROVIDE MIN. BEARING FOR SILL PLATES, BEAMS AND FLOOR JOIST AS PER 9.23.2.7, 9.23.8.1, & 9.23.9.1. OF THE O.B.C.
- MINIMUM STRIP FOOTING SIZES (9.15.3)
- | NUMBER FLOORS SUPPORTED | SUPPORTING INT. LOAD BEARING | SUPPORTING EXTERIOR | SUPPORTING PARTIALLY |
|-------------------------|------------------------------|---------------------|----------------------|
| 1 | 16" WIDE x 8" THICK | 16" WIDE x 6" THICK | 16" WIDE x 6" THICK |
| 2 | 24" WIDE x 8" THICK | 20" WIDE x 6" THICK | 24" WIDE x 8" THICK |
| 3 | 36" WIDE x 14" THICK | 26" WIDE x 9" THICK | 36" WIDE x 14" THICK |

REFER TO SB-12 ENERGY EFFICIENCY DESIGN MATRIX ON THE TITLE PAGE FOR ALL VALUES AS REQUIRED PER 3.1.1., 3.1.2., 3.1.3. OF THE OBC.

- 5A FOUNDATION REDUCTION IN THICKNESS FOR MASONRY**
WHERE THE TOP OF THE FOUNDATION WALL IS REDUCED IN THICKNESS TO PERMIT THE INSTALLATION OF MASONRY EXTERIOR FINISHING. THE REDUCED SECTION SHALL BE NOT LESS THAN 3 1/2" (90) THICK. THE BRICK VENEER SHALL BE TIED TO THE FOUNDATION WALL WITH CORROSION RESISTANT METAL TIES @ 7/8" (200) VERTICAL AND 2'-11" (889) HORIZONTAL. FILL VOID WITH MORTAR BETWEEN WALL AND BRICK VENEER. (9.15.4.7)(2)(3) & 9.20.3.4(3)
- 5B FOUNDATION REDUCTION IN THICKNESS FOR JOISTS**
WHERE THE TOP OF THE FOUNDATION WALL IS REDUCED IN THICKNESS TO PERMIT THE INSTALLATION OF JOIST OR JOISTS. THE REDUCED SECTION SHALL BE NOT MORE THAN 13/34" (305) HIGH & NOT LESS THAN 3 1/2" (90) THICK (9.15.4.7)(1)
- 6 WEEPING TIE** (9.14.3.3)
4" (100) @ WEEPING TIE W/ FILTER CLOTH W/RAE @ 6" (152) CRUSHED STONE COVER
- 7 BASEMENT SLAB OR SLAB ON GRADE** (9.16.4.3)
3" (80) MIN. 25MPa (3600psi) CONC. SLAB ON 4" (100) COARSE GRANULAR FILL OR 20MPa (2900psi) CONC. WITH DAMPROOFING BELOW SLAB. PROVIDE 1/2" (12.7) IMPERVIOUS BOARD FOR DOND BREAK AT EDGE. WHERE A BASEMENT SLAB IS WITHIN 24" (610) OF THE EXTERIOR GRADE PROVIDE RIGID INSUL. AROUND THE PERMETER EXTENDING MIN. 24" (610) BELOW GRADE. FOR SLAB ON GRADE CONDITIONS RIGID INSULATION SHALL BE APPLIED TO THE UNDERSIDE OF THE ENTIRE SLAB. (SB-12) 3.1.1.7.6 (a) 6)
- 8 EXPOSED FLOOR TO EXTERIOR** (9.10.17.10, & CANULC-S705.2)
PROVIDE SPRAY FOAM INSULATION BETWEEN CONT. JOIST AND INSTALL OBS. CONFORMING TO 9.29.9. FIN. SOFT OR CLADDING AS PER ELEVATION TO VIS OF EXPOSED CONT. JOIST.
- 9 EXPOSED CEILING TO EXTERIOR W/ ATTIC** (9.25.2.4)
INSULATION, 6 MIL. POLYETHYLENE VAPOUR BARRIER, 1/2" (12.7) GYPSUM BOARD INTERIOR FINISH OR APPROVED EQ.
- 9 EXPOSED CEILING TO EXTERIOR w/o ATTIC**
JOIST/TRUSSES AS PER PLANS W/ 2"x2" (38x38) PURLINS @ 16" (406) O.C. PERPENDICULAR TO JOISTS. PURLINS NOT REQ. W/ SPRAY FOAM OR TRUSS TRUSSES. W/ INSULATION BETWEEN JOIST & RAMPING. POLYETHYLENE VAPOUR BARRIER, 1/2" (12.7) GYPSUM BOARD INT. FINISH OR APPROVED EQ. (CANULC-S705.2, 9.19.1, 9.10.17.10)
- 10 ALL STAIRS/EXTERIOR STAIRS** (9.8.1.2, 9.8.2, 9.8.4.3)
MAX. RISE MIN. RISE MAX. RUN MIN. RUN ALL STAIRS
PRIVATE 7/8" (200) 9" (125) 14" (355) 10" (250)
PUBLIC 7" (180) 9" (125) NO LIMIT 11" (280)
MAX. NOSING 1" (25)
MIN. STAIR WIDTH TAPERED TREADS
PRIVATE 2'-10" (600) MIN. RUN 5'7" (150) MIN. AVG. RUN 10" (250)
PUBLIC 2'-11" (600) MIN. RUN 5'7" (150) MIN. AVG. RUN 11" (280)
- AVERAGE RUN OF TAPERED TREAD MEASURED AT A POINT 300mm FROM THE CENTERLINE OF INSIDE OF STAIRS (9.8.4.3.3)
** HEIGHT OVER STAIRS (HEADROOM) IS MEASURED VERTICALLY ACROSS WIDTH OF STAIRS FROM A STRAIGHT LINE TO THE TREAD & LANDING NOSING TO LOWEST POINT ABOVE AND NOT LESS THAN 6'-8" (190) FOR SINGLE DWELLING UNIT & 6'-4" (194) (200) FOR EVERYTHING ELSE. (9.8.2.2.2)
REQUIRED LANDING IN GARAGE - O.B.C. 9.8.2.6.2(3)
FOR AN EXTERIOR STAIR SERVING A GARAGE - W/ MORE THAN 3 RISERS, GUARDS, HANDRAILS & STEPS AS PER CONSTRUCTION HEX NOTE 10 & 11.
- 11 GUARDS/HANDRAILS** (9.8.7, 9.8.8)
GUARDS TO BE DESIGNED NOT TO FACILITATE CLIMBING AND PROVIDING MAX. OPENING CONFORMING TO O.B.C. 9.8.8.5, & 9.8.8.6. AND BE ABLE TO RESIST LOADS AS PER TABLE 9.8.8.2
GUARD HEIGHTS - O.B.C. 9.8.8.
INTERIOR GUARDS: 2'-11" (600) MIN. (LESS THAN 5'-11" (1800) TO GRADE) EXTERIOR GUARDS: 3'-0" (914) MIN. (LESS THAN 5'-11" (1800) TO GRADE) GUARDS FOR EXITS: 3'-6" (1070) MIN.
GUARDS FOR LANDING @ EXIT STAIRS: 3'-6" (1070) MIN.
GUARDS FOR FLOORS & RAMPS IN GARAGES (SERVICE STAIRS): FLOOR OR RAMP W/ EXTERIOR WALLS THAT IS 23 5/8" (600) OR MORE ABOVE ADJACENT SURFACE REQUIRES CONT. CURB MIN. 5 1/2" (140) HIGH, AND GUARD MIN. 3'-0" (914) HIGH.
REQUIRED GUARDS: BETWEEN WALKING SURFACE & ADJACENT SURFACE WITH A DIFFERENCE IN ELEVATION MORE THAN 23 5/8" (600) OR ADJACENT SURFACE WITHIN 3'-11" (1200) S WALKING SURFACE W/ A DIFFERENCE NOT MORE THAN 1 IN 12 SHALL BE PROTECTED HANDRAIL HEIGHTS - O.B.C. 9.8.7 - REQUIRED AS PER 9.8.7.1.3
MIN. HEIGHT AT STAIRS, RAMPS AND LANDINGS: 2'-10" (605) MAX. HEIGHT AT STAIRS, RAMPS AND LANDINGS: 3'-0" (1070)
- 12 SILL PLATES**
2"x4" (38x89) SILL PLATE WITH 1/2" (12.7) ANCHOR BOLTS 8" (200) LONG EMBEDDED MIN. 4" (100) INTO CONC. @ 7'-10" (2389) O.C. CALKING OR GASKET BETWEEN PLATE AND TOP OF FOUNDATION WALL. USE NON-SHRINK GROUT TO FILL SILL PLATE WHEN REQUIRED (9.23.7)
- 13 BASEMENT INSULATION** (9.12-311.7)
PROVIDE CONTINUOUS BLANKET INSULATION W/ BUILT IN 6 MIL. POLYETHYLENE VAPOUR BARRIER. INSULATION TO EXTEND NO MORE THAN 8" (200) ABOVE FINISHED BASEMENT FLOOR. DAMPROOFED WITH BUILDING PAPER BETWEEN THE FOUNDATION WALL AND INSULATION UP TO GRADE LEVEL.
- 14 BEARING STUD PARTITION IN BASEMENT** (9.15.3.6, 9.23.10.1)
2"x4" (38x89) STUDS @ 16" (406) O.C. 2"x4" (38x89) SILL PLATE 2"x6" (38x140) AS REQUIRED ON DAMPROOFING PAPER OR 2 MIL. POLYETHYLENE FILM, 1/2" (12.7) 2" ANCHOR BOLTS 8" (200) LONG. EMBEDDED 4" (100) MIN. INTO CONC. @ 7'-10" (2389) O.C. 4" (100) HIGH CONC. CURB ON CONC. FOOTING. FOR SIZE REFER TO HEX NOTE 5. ADD HORIZ. BLOCKING AT MID-HEIGHT IF WALL IS UNFINISHED.
- 15 ADJUSTABLE STEEL BASEMENT COLUMN** (9.15.3.4)
9'-10" (3000) MAX. SPAN BETWEEN COLUMNS, 3 1/2" (90) SINGLE TUBE ADJUSTABLE STEEL COLUMN CONFORMING TO CAN/CSA-S7.2M, AND WITH 6"x6"x3/8" (152x152x9.5) STEEL PLATE TOP & BOTTOM, FIELD WELD BASEMENT COLUMN CONNECTION. POURED CONCRETE FOOTING ON NATURAL UNDISTURBED SOIL OF 75kPa OR COMPACTED ENGINEERED FILL WITH MIN. BEARING CAPACITY OF 150kPa AS PER SOIL REPORT.
(SUPPORTING 3 STOREY FLR. LOAD PROVIDE 34"x34"x16" (870x870x410) CONC. FOOTING SUPPORTING 3 STOREY FLR. LOAD PROVIDE 40"x40"x19" (1060x1060x480) CONC. FOOTING)
- 15A NON-ADJUSTABLE STEEL BASEMENT COLUMN**
3 1/2" (90) x 10" (188) (4.78) NON-ADJUSTABLE STEEL COLUMN WITH 6"x6"x3/8" (152x152x9.5) STEEL PLATE TOP & BOTTOM, FIELD WELD BASEMENT COLUMN CONNECTION. POURED CONCRETE FOOTING ON NATURAL UNDISTURBED SOIL OF 75kPa OR COMPACTED ENGINEERED FILL WITH MIN. BEARING CAPACITY OF 150kPa AS PER SOIL REPORT.
(SUPPORTING 3 STOREY FLR. LOAD PROVIDE 42"x42"x18" (1070x1070x460) CONC. FOOTING SUPPORTING 3 STOREY FLR. LOAD PROVIDE 46"x46"x24" (1220x1220x610) CONC. FOOTING)
- 15B NON-ADJUSTABLE STL. COLUMN AT FOUNDATION WALL**
3 1/2" (90) x 10" (188) (4.78) NON-ADJUSTABLE STEEL COLUMN WITH 6"x6"x3/8" (152x152x9.5) STEEL PLATE TOP & BOTTOM, FIELD WELD BASEMENT COLUMN CONNECTION. POURED CONCRETE FOOTING ON NATURAL UNDISTURBED SOIL OF 75kPa OR COMPACTED ENGINEERED FILL WITH MIN. BEARING CAPACITY OF 150kPa AS PER SOIL REPORT.
(SUPPORTING 3 STOREY FLR. LOAD PROVIDE 42"x42"x18" (1070x1070x460) CONC. FOOTING SUPPORTING 3 STOREY FLR. LOAD PROVIDE 46"x46"x24" (1220x1220x610) CONC. FOOTING)
- 16 STEEL BEAM BEARING AT FOUNDATION WALL** (9.23.8.1)
BEAM POCKET OR 8"x8" (200x200) POURED CONC. NIB WALLS, MIN. BEARING 3 1/2" (90), CONC. NIB WALLS TO HAVE EXTENDED FOOTINGS
- 17 WOOD STRAPPING AT STEEL BEAMS** (9.23.4.3, 9.23.9.3)
1"x3" (19x49) CONTIN. WOOD STRAPPING BOTH SIDES OF STEEL BEAM.
- 18 GARAGE SLAB** (9.16, 9.35)
4" (100) 32MPa (4600psi) CONC. SLAB WITH 5-8% AIR ENTRAINMENT ON OPT. 4" (100) COARSE GRANULAR FILL WITH COMPACTED SUB-BASE OR COMPACTED NATIVE FILL. SLOPE TO FRONT @ 1% MIN.
- 19 GARAGE TO HOUSE WALLS/CEILING** (9.10.9.16)
1/2" (12.7) GYPSUM BOARD ON WALL AND CEILING BETWEEN HOUSE AND GARAGE. PLUS REQUIRED INSULATION ON WALLS AND SPRAY FOAM FOR CEILINGS. TAPE AND SEAL ALL JOINTS GAS TIGHT. (9.10.17.10, CANULC-S705.2)

- 19A GARAGE TO HOUSE WALLS/CEILING W/ CONTIN. INSULATION**
1/2" (12.7) GYPSUM BOARD ON WALL AND CEILING WITH INSULATION OVER EXTERIOR TYPE RIGID INSULATION (JOINTS UNTAPED), MECHANICALLY FASTENED AS PER MANUFACTURERS SPECIFICATIONS ON 3/8" EXTERIOR GRADE SHEATHING ON STUDS BETWEEN HOUSE AND GARAGE. PLUS REQUIRED INSULATION IN WALLS & SPRAY FOAM FOR CEILINGS. TAPE AND SEAL ALL JOINTS GAS TIGHT. (9.10.9.16, 9.10.17.10, CANULC-S705.2)
- 20 GARAGE DOOR TO HOUSE** (9.10.9.16, 9.10.13.10, 9.10.13.15)
GAS-PROOF DOOR AND FRAME, DOOR EQUIPPED WITH SELF-CLOSING DEVICE AND WEATHER STRIPPING.
- 21 EXTERIOR AND GARAGE STEPS**
PRECAST CONC. STEP OR WOOD STEP WHERE NOT EXPOSED TO WEATHER. MAX. RISE 7/8" (200), MIN. TREAD 10" (255). FOR THE REQUIRED NUMBER OF STEPS REFER TO SITING AND GRADING DRAWINGS. EXTERIOR CONCRETE STAIRS WITH MORE THAN 2 RISERS AND 2 TREADS SHALL BE PROVIDED WITH FOUNDATION AS REQUIRED BY ARTICLE 9.8.9.2, OR SHALL BE CANTILEVERED AS PER SUBSECTION 9.8.10.
- 22 DRYER EXHAUST**
CAPPED DRYER EXHAUST VENTED TO EXT. CONFORMING TO PART 6, OBC 9.32.
- 23 ATTIC ACCESS** (9.19.2.1)
ATTIC ACCESS HATCH WITH MIN. AREA OF 0.3m² AND NO DIM. LESS THAN 21 1/2" (545) WITH WEATHER STRIPPING. HATCHWAYS TO THE ATTIC OR ROOF SPACE WILL BE FITTED WITH DOORS OR COVERS AND WILL CONFORM WITH MIN. REQ. (9.3.5.5) (SB-12) 3.1.1.1.6(1)
- 24 FIREPLACE CHIMNEYS** (9.21)
TOP OF FIREPLACE CHIMNEY SHALL BE 2'-11" (889) ABOVE THE HIGHEST POINT AT WHICH IT COMES IN CONTACT WITH THE ROOF AND 2'-0" (610) ABOVE THE ROOF SURFACE WITHIN A HORIZ. DISTANCE OF 10'-0" (3048) FROM THE CHIMNEY.
- 25 LINEN CLOSET**
PROVIDE 4 SHELVES MIN. 14" (356) DEEP.
- 26 MECHANICAL VENTILATION** (9.32.1.3)
MECHANICAL EXHAUST FAN, VENTED TO EXTERIOR, TO PROVIDE AT LEAST ONE AIR CHANGE PER HOUR. SEE GENERAL NOTE 2.3.
- 27 PARTY WALL BEARING** (9.23.8)
1/2" (12.7) GYPSUM SHEATHING ON EACH SIDE ON 2"x2" (38x38) VERTICAL WOOD STRAPPING @ 24" (610) O.C. ON 2"x2" (38x38) BLOCK 75% SOLID. FILL STRAPPING EACH SIDE WITH AT LEAST 90% OF ABSORPTIVE MATERIAL PROCESSED FROM ROCK, SLAG OR GLASS. TAPE FILL & SAND ALL GYPSUM JOINTS. EXPOSED BLOCK MUST BE SEALED W/ 2 COATS OF PAINT OR FURRED WITH 2"x2" (38x38) WOOD STRAPPING @ 1/2" (12.7) GYPSUM SHEATHING.
- 28 WOOD FRAMING IN CONTACT TO CONCRETE**
WOOD BEARING WALLS, THE UNDERSIDE OF BUILT-UP WOOD POSTS AND SILLS SHALL BE WRAPPED WITH 2 MIL POLY. STRIP FOOTINGS SUPPORTING THE FOUNDATION WALL SHALL BE WIDENED 6" (152) BELOW THE BEARING WALL AND WOOD POST, (9.17.4.3.3)
- 29 BUILT-UP WOOD POST AND FOOTING** (9.17.4.1, 9.15.3.7.2)
3-2"x6" (3-38x140) BUILT-UP WOOD POST (UNLESS OTHERWISE NOTED) ON METAL BASE SHOE ANCHORED TO CONC. WITH 1/2" (12.7) @ BOLT. 2"x4"x24" (610x610x605) CONC. FOOTING OR AS PROVIDED ON PLAN. REFER TO NOTE 28
- 30 STEP FOOTINGS** (9.15.3.9)
MIN. HORIZ. STEP = 23 5/8" (600), MAX. VERT. STEP = 23 5/8" (600).
- 31 CONC. PORCH SLAB** (9.16.4)
4" (100) CONCRETE SLAB ON GRADE ON 4" (100) COARSE GRANULAR FILL, REINFORCED WITH 6mmx250mmx2 MESH PLACED NEAR MID-DEPTH OF SLAB, CONC. STRENGTH 32MPa (4600psi) WITH 5-8% AIR ENTRAINMENT ON COMPACTED SUB-GRADE.
- 32 FURNACE VENTING** (9.32)
DIRECT VENT FURNACE TERMINAL MIN. 3'-0" (915) FROM A GAS REGULATOR, MIN. 1/2" (305) ABOVE FIN. GRADE. FROM ALL OPENINGS, EXHAUST AND INTAKE VENTS, HRV INDOOR VENTS, AND EXHAUST VENTS @ 1/330) FROM ALL EXHAUST TERMINALS. REFER TO GAS UTILIZATION CODE.
- 33 FIREPLACE VENTING** (9.23.2)
DIRECT VENT GAS FIREPLACE VENT TO BE A MIN. 1/2" (305) FROM ANY OPENING AND ABOVE FIN. GRADE. REFER TO GAS UTILIZATION CODE.
- 34 FLOOR FRAMING** (9.23.3.5, 9.23.3.4, 9.23.14)
T&G SUBFLOOR ON WOOD FLOOR JOISTS. FOR CERAMIC TILE APPLICATION SEE O.B.C. 9.30.6. ALL JOISTS WHERE REQUIRED TO BE BRIDGED WITH 2"x2" (38x38) CROSS BRACING OR SILD BLOCKING @ 6'-11" (2108) O.C. MAX. ALL JOISTS TO BE STRAPPED WITH 1"x3" (19x49) @ 6'-11" (2108) O.C. UNLESS A PANEL TYPE CEILING FINISH IS APPLIED.
- 34A HEADER CONSTRUCTION**
PROVIDE CONTINUOUS APPROVED AIR/VAPOUR BARRIER (HEADER WRAP) UNDER THE SILL PLATE. AROUND THE RIM BOARD AND UNDER THE BOTTOM PLATE. THE HEADER WRAP SHALL EXTEND 6" (152) BELOW THE TOP OF FOUNDATION WALL AND WILL BE SEALED TO THE CONCRETE FOUNDATION WALL. EXTEND HEADER WRAP 6" (152) UP THE INTERIOR SIDE OF THE STUD WALL AND OVERLAP WITH THE VAPOUR BARRIER AND SEAL THE JOINT. ALL EDGES/JOINTS MUST BE MECHANICALLY CLAMPED.
- 35 EXPOSED BUILDING FACE W/ LIMITING DISTANCE < 3 1/2" (1.20m)**
WALL ASSEMBLY CONTAINS INSULATION CONFORMING TO CANULC-S7.2M & HAVING A MASS OF NOT LESS THAN 1.22 KG/M² OF WALL SURFACE AND 1/2" (12.7) TYPE X GYPSUM WALLBOARD INTERIOR FINISH. EXTERIOR CLADDING MUST BE NON-COMBUSTIBLE WHEN LIMITING DISTANCE IS 23 5/8" (600) OR LESS. WALL ASSEMBLY REQUIRES TO HAVE A FIRE RESISTANCE RATING OF NOT LESS THAN 45 MINUTES & CONFORMING TO O.B.C. (9.10.4, 9.10.15). REFER TO DETAILS FOR TYPE & SPECS. ** AN OPENING IN AN EXPOSING BUILDING FACE NOT MORE THAN 21' (6400) MIN. SHALL NOT BE CONSIDERED AN UNPROTECTED OPENING AS PER 9.10.14.6
- 36 COLD CELLAR PORCH SLAB** (9.39)
FOR MAX. 8'-2" (2500) POOR DEPTH, 5" (127) 32 MPa (4600psi) CONC. SLAB W/ 5-8% AIR ENTRAINMENT. REIN. WITH 10M BARS @ 7' (210) O.C. EACH DIRECTION. W/ 1 1/4" (32) CLEAR COVER FROM BOTTOM OF SLAB TO FIRST LAYER OF BARS & SECOND LAYER OF BARS Laid DIRECTLY ON TOP OF LOWER LAYER OR OPPOSITE DIR. 2"x4"x24" (610x610x100) DOWELS @ 23 5/8" (600) O.C. ANCHORED IN PERIMETER FND. WALLS - 3% CRP. SLAB 1.0% FROM ROOM.
- 37 RANGE HOODS AND RANGE-TOP FANS**
COOKING APPLIANCE EXHAUST FANS VENTED TO EXTERIOR MUST CONFORM TO OBC 9.10.22, 9.23.9.3, & 9.23.10.1
- 38 CONVENTIONAL ROOF FRAMING** (9.23.13, 9.23.15)
2"x2" (38x140) RAFTERS @ 16" (406) O.C. 2"x8" (38x184) RIDGE BOARD. 2"x4" (38x89) COLLAR TIES AT MID-SPAN, CEILING JOISTS TO BE 2"x4" (38x89) @ 16" (406) O.C. FOR MAX. SPAN 14'-0" (4260). RAFTERS FOR BUILT UP ROOF OVER PRE-ENGINEERED ROOF TRUSSES AND OR CONVENTIONAL FRAMING TO BE 2"x4" (38x89) @ 24" (610) O.C. UNLESS OTHERWISE SPECIFIED.
- 39 TWO STOREY VOLUME SPACES** (9.23.10.1, 9.23.11, 9.23.16)
WALL ASSEMBLY WIND LOADS > 0.5 kPa (G50)
EXTERIOR STUDS SPACING MAX HEIGHT SPACING MAX HEIGHT
BRICK 2'-2"x6" (12" (305) O.C. 18'-4" (5588) 8" (200) O.C. 18'-4" (5588)
SIDING 2'-2"x6" (12" (305) O.C. 18'-4" (5588) 8" (200) O.C. 18'-4" (5588)
BRICK 2'-2"x6" (12" (305) O.C. 21'-0" (6400) 12" (305) O.C. 21'-0" (6400)
SIDING 2'-2"x6" (12" (305) O.C. 21'-0" (6400) 12" (305) O.C. 21'-0" (6400)
** STUD SIZE & SPACING TO BE VERIFIED BY STRUCTURAL ENGINEER **
STUDS ARE TO BE CONTINUOUS, CW 3/8" (9.5) THICK EXTERIOR PLYWOOD SHEATHING. PROVIDE SOLID WOOD BLOCKING BETWEEN WOOD STUDS @ 4'-0" (1220) O.C. VERTICALLY.
- FOR HORIZ. DISTANCES LESS THAN 9'-0" (2696) PROVIDE 2"x6" (38x140) STUDS @ 16" (406) O.C. WITH CONTIN. 2"x6" (38x140) TOP PLATE @ 1'-2"x6" (1-38x140) BOTTOM PLATE & MIN. OF 2'-0" (610) (3-38x184) CONT. HEADER AT GROUND FLOOR CEILING LEVEL TO EAVE & GUED AT TOP. BOTTOM PLATES & HEADERS.
- 40 1 HR. PARTY WALL (CONC. BLOCK)** (SB-3) WALL TYPE 966 & 916)
1/2" (12.7) GYPSUM SHEATHING ON EACH SIDE ON 2"x2" (38x38) VERTICAL WOOD STRAPPING @ 24" (610) O.C. ON 2"x2" (38x38) BLOCK 75% SOLID. FILL STRAPPING EACH SIDE WITH AT LEAST 90% OF ABSORPTIVE MATERIAL PROCESSED FROM ROCK, SLAG OR GLASS. TAPE FILL & SAND ALL GYPSUM JOINTS. EXPOSED BLOCK MUST BE SEALED W/ 2 COATS OF PAINT OR FURRED WITH 2"x2" (38x38) WOOD STRAPPING @ 1/2" (12.7) GYPSUM SHEATHING.
- 40 1 HR. PARTY WALL (DOUBLE STUD)** (SB-3) WALL TYPE 7103)
5/8" (15.9) STEEL W/ GYPSUM SHEATHING ON EXTERIOR SIDE OF 2" WINDS @ 2"x2" (38x38) STUDS @ 16" (406) O.C. 1" (25) APART ON SEPARATE 2"x4" (38x89) SILL PLATES. (2"x6" (38x140) AS REQUIRED) FILL ONE SIDE OF STUD CAVITY WITH AT LEAST 90% OF ABSORPTIVE MATERIAL PROCESSED FROM ROCK, SLAG OR GLASS. TAPE FILL AND SAND ALL GYPSUM JOINTS.
- 40A 2 HR. FIREWALL** (SB-3) WALL TYPE 966 & 916)
1/2" (12.7) GYPSUM SHEATHING ON EACH SIDE ON 2"x2" (38x38) VERTICAL WOOD STRAPPING @ 24" (610) O.C. ON 2"x2" (38x38) BLOCK 75% SOLID. FILL STRAPPING EACH SIDE WITH AT LEAST 90% OF ABSORPTIVE MATERIAL PROCESSED FROM ROCK, SLAG OR GLASS. TAPE FILL & SAND ALL GYPSUM JOINTS. EXPOSED BLOCK MUST BE SEALED W/ 2 COATS OF PAINT, GYPSUM SHEATHING TO BE ATTACHED TO CONC. BLOCK. (REFER TO DETAILS)
- 41 STUCCO WALL CONSTRUCTION (2"x6")**
STUCCO FINISH CONFORMING TO O.B.C. SECTION 9.28. AND APPLIED PER MANUFACTURERS SPECIFICATIONS OVER 1 1/2" (38) E.F.S. (MINIMUM) ON APPROVED DRAINAGE MAT ON 1/2" (12.7) DENGLASS GOLD GYPSUM BOARD ON STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION, APPROVED 6 MIL. POLYETHYLENE VAPOUR BARRIER, 1/2" (12.7) GYPSUM WALLBOARD INT. FINISH. (REFER TO 35 NOTE AS REQ.)
- 41A STUCCO WALL CONSTRUCTION (2"x6") W/ CONTIN. INSUL.**
STUCCO FINISH CONFORMING TO O.B.C. SECTION 9.28. AND APPLIED PER MANUFACTURERS SPECIFICATIONS OVER 1 1/2" (38) E.F.S. (MINIMUM) ON APPROVED DRAINAGE MAT ON APPROVED AIR/VAPOUR BARRIER AS PER O.B.C. 9.27.3. ON EXTERIOR TYPE RIGID INSULATION (JOINTS UNTAPED), MECHANICALLY FASTENED AS PER MANUFACTURERS SPECIFICATIONS, ON 3/8" (9.5) EXTERIOR TYPE SHEATHING ON STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, INSULATION, APPROVED 6 MIL. POLYETHYLENE AIR/VAPOUR BARRIER, 1/2" (12.7) GYPSUM WALLBOARD INT. FINISH. (REFER TO 35 NOTE AS REQ.)
- 41B STUCCO WALL @ GARAGE CONST.**
STUCCO FINISH CONFORMING TO O.B.C. SECTION 9.28. AND APPLIED PER MANUFACTURERS SPECIFICATIONS OVER 1 1/2" (38) E.F.S. (MINIMUM) ON APPROVED DRAINAGE MAT ON 1/2" (12.7) DENGLASS GOLD GYPSUM BRD. ON STUDS CONFORMING TO O.B.C. (9.23.10.1, 1) & SECTION 1.1, 1/2" (12.7) GYPSUM WALLBOARD INT. FINISH. (REFER TO 35 NOTE AS REQ.)